

Operational Report

Wisconsin State Highway 2007 Maintenance, Traffic, and Operations Conditions

Compass Advisory Team

Adam Boardman, WisDOT State Highway Program Development & Analysis Section Chief Scott Bush, WisDOT Compass Program Manager John Corbin, WisDOT Traffic Engineering Section Chief Bob Hanifl, WisDOT SW Region Maintenance Project Engineer Todd Hogan, WisDOT SW Region Engineering Technician John Kinar, WisDOT Highway Maintenance & Roadside Mngmt. Section Chief Dennis Newton, WisDOT SE Region Signing and Marking Supervisor Mike Ostrenga, WisDOT NW Region Area Supervisor Doug Passineau, Wood County Patrol Superintendent Ken Pesch, Washington County Highway Commissioner Brett Wallace, WisDOT NE Region SPO Manager Tom Walther, Eau Claire County Highway Commissioner Jim Wendels, WisDOT NC Region Roadway Maintenance Engineer Mark Woltmann, WisDOT Highway Operations Program Mngmt. Section Chief Jack Yates, Marquette County Patrol Superintendent



Table of Contents

Existing State Highway Conditions and Maintenance Strategies	
Executive Summary	
About this report	
Background	
Process	
Results	
Wisconsin 2007 Targets: Targets for Paved Traveled Way Maintenance Conditions	
Wisconsin 2007: Targets for Highway Maintenance Conditions	
Wisconsin 2007: Compass Report on Paved Traveled Way Conditions	
Wisconsin 2007: Compass Report on Highway Maintenance Conditions	
Regions 2007: Compass Report on Highway Maintenance Conditions	
2007 Winter: Compass Report on Winter Maintenance	
Wisconsin and Regions 2007: Compass Report on Bridges	
Wisconsin and Regions 2007: Compass Report on Signs	
Wisconsin and Regions 2007: Sign Face Material Distribution	
Wisconsin and Regions 2007: Sign Face Material Trends	23
Operational Reports	
2007 Signs: Compass Report on Routine Replacement and Age Distribution	25
Wisconsin 2007: Routine Replacement of Signs	26
Regions 2007: Routine Replacement of Signs	26
Counties 2007: Routine Replacement of Signs	27
Wisconsin and Regions 2007: Age Distribution of Signs	30
2007 Traveled Way: Compass Report on Maintenance Condition	
Wisconsin 2007: Traveled Way Maintenance Condition	33
Regional Trends: Traveled Way	
Wisconsin 2007: Traveled Way Condition Distribution	
Regions 2007: Traveled Way Condition Distribution	
Counties 2007: Traveled Way	40
2007 Winter: Compass Report on Winter Maintenance	
Executive summary	43
2006-2007 winter season snowfall for Wisconsin	45
2006-2007 Winter Severity Index by County	46
Winter by the numbers	
Compass winter maintenance measures	
2007 Highway Maintenance Conditions: Compass Report on Traffic, Shoulders, Drainage, Roadsides	52
Counties 2007: Traffic and Shoulders	
Counties 2007: Drainage and Roadsides	
2007 Bridges: Compass Report on Condition, Maintenance, and Inspection Backlog	
Wisconsin 2007: Bridge Condition Distribution	
Region 2007: Bridge Condition Distribution	
Wisconsin 2007: Bridge Maintenance Needs	
Counties 2007: Bridge Maintenance Needs	
Wisconsin and Regions 2007: Bridge Special Inspection Backlog	
Counties 2007: Bridge Special Inspection Backlog	
Appendices	
A. Program Contributors	
B. Compass Feature Thresholds and Grade Ranges	
C. Feature Contribution Categories	
D. 2006 and 2007 Highway Operations Targets	
E. 2007 Compass Rating Sheet	
1 ···· 0 ··	

Existing State Highway Conditions and Maintenance Strategies

The "Compass" program collects rating data each year to help the department understand current infrastructure conditions and trends. The data also helps WisDOT managers set reasonable maintenance targets that reflect department priorities and respond to limited resources. To ensure that maintenance targets are consistently reflected in work programs around the state, these priorities are shared with the WisDOT regions to help structure the Routine Maintenance Agreements with counties. And to evaluate the maintenance target setting process, existing conditions are compared to their target levels to see if the annual goals were met or exceeded.

The <u>2007 Compass Annual Report</u> has been completed based on the field review process from last year and data from the "Sign Inventory Management System". Below are the significant messages on the current condition of the state highway system and specific examples of how the Bureau of Highway Operations uses the information to manage the system:

- Pavement conditions are declining based on limited funding: The amount of asphalt pavements with rutting and cracking has dramatically increased over the last two years. Fewer roadways are being improved with full-depth reconstruction projects because of rising costs and limited funding. Pavement conditions are deteriorating because more low cost "band aid" improvements, such as thin overlays, are being programmed instead of optimal, higher-cost improvement designs. The maintenance community has tried to reduce rutting by setting more ambitious maintenance targets and working more closely with managers of the WisDOT Improvement Program. Unfortunately, rutting has increased because of limited maintenance dollars to wedge roads and fewer reconstruction projects that improve the structural integrity of roadway sub-bases. Pavement cracking has also increased because limited funding has forced the department to make the tough choice to spend fewer resources to rout and seal cracks.
- *Focus on reducing shoulder drop-off*: There has been an added emphasis on fixing shoulder drop off so that drivers who veer off the traveled way can safety get back onto the paved surface. More aggressive maintenance targets have been set over the last four years to deal with this problem. The actual amount of drop-off has remained steady over the last two years and there will be a continued focus on improving safety by reducing shoulder drop-off. The emphasis on fixing shoulder drop-off is also reflected in the department adding this feature to the "critical safety" category in 2008, creating a tougher" A" through "F" grading curve to illustrate existing conditions. The increasing sensitivity to shoulder drop-off was also addressed in 2003 when the *Compass* program reduced the deficiency threshold for drop-off from over 2" to over 1-1/2".
- *Removing hazardous debris on shoulders*: For several years the department has emphasized the safety benefits of removing hazardous debris from roadways. Last year 9% of roadways had hazardous debris, the lowest level recorded during the previous four-year period.
- *More visible, longer lasting traffic signs*: Over 20,000 new high-intensity signs were installed along the state highway system between 2006 and 2007. More than half of the 286,000 signs on the state system now have a high-intensity face material, providing better illumination to drivers during low light conditions and evenings. An added benefit is that the new signs last 72% longer than the older generation "engineering" grade signs.

• *Targeted replacement of regulatory and warning signs*: Over 110,000 signs around the state are older than their suggested useful life. With limited sign replacement funds, the routine replacement of regulatory and warning signs (such as stop signs and speed limit signs) has been prioritized over the replacement of other types of signs. Based on this policy, one-quarter of the regulatory and warning signs are beyond their recommended service life while 56% of other signs are older than their suggested useful life.

Executive Summary

About this report

The Compass *Operational Report* is issued annually to communicate the condition of Wisconsin's state highway network and to demonstrate accountability for maintenance expenditures. The primary audience for this report includes Maintenance Supervisors and Operations Managers at the Wisconsin Department of Transportation (WisDOT) and partner organizations including the 72 counties. Compass reports are used to understand trends and conditions, prioritize resources, and set future target condition levels for the state highway system. As more information is gathered, data will also be used to illustrate and communicate the consequences of funding and policy shifts within WisDOT and to the State Legislature.

This report *includes* data on bridges, traveled ways, shoulders, drainage, roadsides, selected traffic devices, and specific aspects of winter maintenance activities. It *does not include* measures of preventive maintenance, operational services (like traveler information and incident management), or electrified traffic assets (like signals and lighting). It is important to consider these exclusions when using this report to make investment decisions.

The first section of this report is an executive overview, a condensed version of the full report for executive managers in WisDOT. Both documents are available on the Compass website (<u>http://dotnet/dtid_bho/extranet/compass/reports/index.shtm</u> from within WisDOT or <u>https://trust.dot.state.wi.us/extntgtwy/dtid_bho/extranet/compass/reports/index.shtm</u> from outside WisDOT).

Feedback on format, content, and other aspects of the report is welcome and should be sent to Scott Bush, Compass Program Manager, at <u>scott.bush@dot.state.wi.us</u> or (608) 266-8666.

Background

Compass was implemented statewide in 2002 as WisDOT's maintenance quality assurance and asset management program for highway operations. The Compass report is intended to provide a comprehensive overview of highway operations by integrating information from field reviews with inventory data and other data sources.

Process

The Compass report is issued annually in cooperation with the research team from the Wisconsin Transportation Center (WTC) at University of Wisconsin – Madison. Starting in September of each year, WTC and the Compass Program Manager work on the analysis of each element. The project team presents the draft report at the Compass Advisory Team meeting and the WisDOT Operations Managers meeting in May and June respectively. The report is revised based on feedback from these meetings. The report is finalized and officially published in July.

This report uses inventory data for bridges, pavement, routine maintenance of signs, and winter storms. It uses sample data for highway maintenance features. The project team collected data from the WisDOT business areas between October 2007 and April 2008.

The highway maintenance data includes data sampled from the field. Two hundred and forty 1/10-mile segments are randomly selected in each of the five WisDOT regions. A WisDOT Maintenance Coordinator and a County Patrol Superintendent collect the field data in each county between August 15 and October 15 every year. The field survey includes a condition analysis of shoulders, drainage features, roadside attributes, pavement markings and signs.

Winter maintenance data is gathered from the winter season 2006-07 and includes Time to Bare Wet, Winter Severity Index, Winter VMT, and crash data. Also included are figures and tables directly taken from the 2006-07 WisDOT *Annual Winter Maintenance Report* prepared by WisDOT's Winter Operations unit, including the "Winter by the Numbers" table and the statewide snowfalls and Winter Severity Index figures.

Pavement data was obtained from the Pavement Information File (PIF) and contains the complete highway pavement inventory data in Wisconsin. Inspections of state-maintained highway pavements in Wisconsin are done regularly in two-year cycles, with half of the state's pavements inspected in one year and the other half in the next year. In past Compass reports, a two-year rolling average of all pavement segments condition was used to calculate statewide conditions. In 2006 it was determined that the rolling average method didn't accurately represent the actual condition at any one year and could dilute the condition of one or both halves of the state. Therefore, starting in 2006 the pavement condition is calculated for the current year of the report, which means that at any one year, statewide numbers of pavement condition will represent half of the state. This also means that a trend of pavement condition can only be shown as two separate trends, which shows the condition of pavements evaluated in years 2003, 2005, 2007 and those pavements reviewed in years 2002, 2004, and 2006.

Sign data comes from the Sign Inventory Management System (SIMS), and the bridge data comes from the Highway Structure Information System (HSIS).

Compass identifies backlog percentages for each feature at the county, region and statewide level. Backlog percentages indicate what percent of that feature is in a condition where maintenance work is required, if adequate budget was available. Therefore, an increasing backlog percentage reflects fiscal constraints rather than inadequate work.

Appendix B identifies when assets are considered backlogged for highway maintenance features. For pavement features, the backlog is determined based on the Pavement Maintenance Management System (PMMS) ratings. In the PMMS, each segment of road receives a rating for each distress type. The ratings include "excellent", "fair", "moderate", or "bad", depending on the extent and severity of distress. For the Compass report, a pavement segment that receives a rating other than "excellent" needs routine maintenance and is considered backlogged. Traffic signs are considered backlogged for maintenance if it is in use past its expected service life.

Compass uses predefined thresholds for the percent of features backlogged to assign a letter grade to the overall maintenance condition of each feature (from "A" to "F"). The feature grade declines as more of a feature is backlogged. These grading scales are curved to account for the importance of the feature to the roadway system. Thus a feature that contributes to critical safety, for example, would decline more rapidly than a feature that is primarily aesthetic in nature. A

feature grade of "A" means that all basic routine maintenance needs have been met within the maintenance season and there is not a significant backlog. Appendix B lists the grading scale for each Compass feature.

WisDOT Maintenance Supervisors and Operations Managers annually set the targets for backlog percentage levels for each feature. These targets are intended to reflect priorities and goals for the year in light of fiscal constraints. Appendix D provides the maintenance targets for 2007.

Results

The maintenance condition of most pavement features declined from 2005 to 2007. One pavement feature improved during the biennium, the condition of 11 pavement features declined and conditions remained constant for five pavement features. That said, most pavement features met or exceeded the maintenance target for the year. Seven of the 17 pavement features met their 2007 target condition, the condition of six pavement features exceeded their target condition and four pavement features were below their target condition.

The maintenance condition of most non-pavement features improved or stayed the same from 2006 to 2007. The condition of 13 features improved from the previous year, conditions remained constant for six features and conditions declined for nine features. All but one non-pavement feature met or exceeded their target condition in 2007. Twenty-one features met the target condition, six features exceeded the target and drop-off/build-up of unpaved shoulders was the only non-pavement feature with a condition below the target.

Each Compass feature is assigned to a category based on the primary type of contribution to the roadway system. The categories include Critical Safety, Safety, Ride/Comfort, Stewardship, and Aesthetics. The following tables show the trend of Compass feature grades for the past four years in each of the contribution categories, followed by some key observations for the features in each category.

Critical Safety

Critical Safety features are roadway attributes that provide secure operating conditions for the traveling public when in good condition and are priority maintenance items when their condition degrades. Two features were reassigned to the Critical Safety category in 2007. The features added to the Critical Safety category include Flushing and Unpaved Drop-off/build-up.

Feature	2007	2006	2005	2004	Element
Hazardous debris	С	D	D	D	Shoulders
Rutting	F		С		Traveled way, asphalt
Centerline markings	В	В	В	В	Traffic and safety devices
Regulatory/warning signs (emergency)	А	А	А	А	Traffic and safety devices
Flushing	А		А		Traveled way, asphalt
Drop-off/build-up (unpaved)	F	F	F	F	Shoulders

• Rutting declined from a C grade in 2005 to an F grade in 2007. The maintenance backlog for Rutting increased during the period from 6% in 2005 to 19% of road segments in 2007.

- Removal of Hazardous Debris on shoulders improved from a D grade in 2006 to a feature grade of C in 2007. The number of road segments with Hazardous Debris declined from 13% in 2006 to 9% in 2007.
- Centerline Markings and the emergency repair of Regulatory/Warning Signs consistently received grades of B and A, respectively.

Safety

Safety features are highway attributes and characteristics that protect users against – and provide them with a clear sense of freedom from – danger, injury or damage.

Feature	2007	2006	2005	2004	Element
Delineators	С	С	D	С	Traffic and safety devices
Regulatory/warning signs (routine)	D	D	F	D	Traffic and safety devices
Mowing	С	С	С	С	Roadsides
Edgeline markings	Α	В	В	В	Traffic and safety devices
Special pavement markings	В	А	А	С	Traffic and safety devices
Protective barriers	В	А	А	А	Traffic and safety devices
Fences	Α	А	А	А	Roadsides
Mowing for vision	Α	А		D	Roadsides
Woody vegetation control	Α	А	А	А	Roadsides
Woody vegetation control for vision	Α	А	А	А	Roadsides

- Edgeline Markings improved to an A grade level from the B it received the previous three years.
- The grades for both Special Pavement Markings and Protective Barriers declined to a B grade level after receiving A grades in the previous three years.
- All other Safety features maintained their grade level from the previous year.

Ride/Comfort

Ride/Comfort features provide a state of ease and quiet enjoyment for highway users and include a number of roadway characteristics such as ride quality and proper signing.

Feature	2007	2006	2005	2004	Element
Transverse faulting	F		F		Traveled way, concrete
Other signs (routine)	D	D	D	D	Traffic and safety devices
Distressed joints/cracks	С		С		Traveled way, concrete
Patch deterioration	C		С		Traveled way, concrete
Slab breakup	D		D		Traveled way, concrete
Cross-slope (unpaved)	В	С	В	В	Shoulders
Patch deterioration	В		В		Traveled way, asphalt
Longitudinal distortion	Α		А		Traveled way, asphalt
Longitudinal joint distress	Α		А		Traveled way, concrete
Surface raveling	Α		А		Traveled way, asphalt
Transverse distortion	Α		А		Traveled way, asphalt
Potholes/raveling (paved)	Α	А	В	А	Shoulders
Other signs (emergency repair)	А	А	А	А	Traffic and safety devices

- Cross-slope of unpaved shoulders improved to a feature grade of B, from a C in 2006.
- All other Ride/Comfort features maintained their grade level from the previous year.

Stewardship

Stewardship features help preserve the roadway system and obtain its full potential service life.

Feature	2007	2006	2005	2004	Element
Cracking (paved)	D	D	D	D	Shoulders
Culverts	С	В	В	В	Drainage
Flumes	С	С	С	С	Drainage
Noxious weeds	С	С	С	С	Roadsides
Edge raveling	В		В		Traveled way, asphalt
Longitudinal cracking	F		F		Traveled way, asphalt
Surface distress	В		А		Traveled way, concrete
Transverse cracking	F		D		Traveled way, asphalt
Storm sewer system	В	В	В	В	Drainage
Under-drains/edge-drains	В	В	В	В	Drainage
Alligator cracking	Α		А		Traveled way, asphalt
Block cracking	А		А		Traveled way, asphalt
Erosion (unpaved)	А	А	А	А	Shoulders
Curb & gutter	А	А	А	А	Drainage
Ditches	А	А	Α	Α	Drainage
Walls & barriers					Roadsides

- The Surface Distress of concrete pavements declined from an A grade in 2005 to a B in 2007. The maintenance backlog for Surface Distress increased during the period from 2% in 2005 to 11% of road segments in 2007.
- Culverts received a feature grade of C, down from a consistent B over the previous three years, but still within the target condition for the feature.
- Transverse Cracking received a feature grade of F, down from the D it received in 2005. The maintenance backlog for Transverse Cracking increased during the period from 54% in 2005 to 61% of road segments in 2007. The condition is much worse than the target level of 30%.
- For the fourth straight year, the sample size for Walls and Barriers was inadequate to establish a reliable condition level. The feature will be dropped from the Compass field review process in 2008 and a more targeted approach will be discussed with the WisDOT regions to monitor the condition of these assets.

Aesthetics

Aesthetics ensure the display of natural or fabricated beauty items located along a highway corridor and include aspects such as landscaping and decorative structures. Aesthetic features also include the absence of litter, which detracts from roadway sightlines.

Feature	2007	2006	2005	2004	Element
Litter	D	D	D	D	Roadsides

• Litter has consistently received a D throughout the four-year period, though the percent of road segments with litter declined slightly from 64% in 2006 to 60% in 2007.

The Compass report also includes measures for winter maintenance and bridges. Currently target levels and grade curves have not been established for winter maintenance and bridges. Some key observations on winter maintenance and bridges include:

Winter maintenance:

- In keeping with WisDOT guidelines, during similar storm events, drivers on major urban freeways and highways had less time to wait until they saw bare/wet pavement than did drivers on secondary roads. From storm to storm, however, variability in this time was due to specific local weather effects (type, duration and severity of storms throughout the winter season).
- The average time to bare/wet pavement during winter 2006-07 was 1 hour and 28 minutes, which is twenty seven minutes less than the previous winter. The average Winter Severity Index (WSI) in 2006-07 was 28.4 versus 31.8 in the previous year.

Bridges:

- Thirty-three percent of bridge decks are in "Fair" condition and in need of reactive maintenance, based on their NBI ratings of 5 or 6. The percentage of bridge decks in "Fair" condition stayed the same between 2006 and 2007.
- Twenty-eight percent of bridge superstructures are in "Fair" condition and in need of reactive maintenance, based on their NBI ratings of 5 or 6. The percentage of bridge superstructures in "Fair" condition in 2007 was a slight change from 2006, when 28% were in the "Fair" category.
- Twenty-nine percent of bridge substructures are in "Fair" condition and in need of reactive maintenance, based on their NBI ratings of 5 or 6. The percentage of bridge substructures in "Fair" condition stayed the same between 2006 and 2007.

Wisconsin 2007 Targets: Targets for Paved Traveled Way Maintenance Conditions

Targets are set annually, and are intended to reflect priorities for that year, given fiscal constraints. They are a measure of effective management, not system condition.

					S	tatewi				Regions ¹						
Contributio n Category			1	-			C	Gap if	f targ	get n	nisseo	1				
Date			Actual % backlog	Target % backlog	On	Wo	rse co	onditi	on	Be	etter c	condi	tion	Worse		Better
n C	Feature	Element	2007	2007	target ²	30	20	10			10	20	30	condition	On Target	condition
Critical Safety	Rutting	Traveled way, asphalt	19%	10%					9					NW, SW		
	Longitudinal distortion	Traveled way, asphalt	0%	1%	0										NW, SW	
Ride/	Patch deterioration	Traveled way, asphalt	9%	10%	0										NW, SW	
Comfort	Surface raveling	Traveled way, asphalt	0%	2%	0										NW, SW	
	Transverse distortion	Traveled way, asphalt	0%	5%	0										NW, SW	
	Distressed joints/cracks	Traveled way, concrete	27%	43%							16					NW, SW
	Longitudinal joint distress	Traveled way, concrete	0%	27%								27				NW, SW
	Patch deterioration	Traveled way, concrete	21%	30%						9						NW, SW
	Slab breakup	Traveled way, concrete	36%	45%						9						NW, SW
	Transverse faulting	Traveled way, concrete	81%	75%					6					NW	SW	
G. 1	Alligator cracking	Traveled way, asphalt	2%	5%	0										NW, SW	
Steward- ship	Block cracking	Traveled way, asphalt	4%	5%	0										NW, SW	
~ F	Edge raveling	Traveled way, asphalt	14%	20%						6					SW	NW
	Flushing	Traveled way, asphalt	1%	1%	0										NW, SW	
	Longitudinal cracking	Traveled way, asphalt	63%	30%		33						NW, SW				
	Transverse cracking	Traveled way, asphalt	61%	30%		31							NW, SW			
	Surface distress	Traveled way, concrete	11%	25%		51			14					NW, SW		

¹ The biennial inspection schedule for pavement conditions resulted in roads in the Northwest (NW) and Southwest (SW) regions being reviewed in 2007.

² This symbol indicates that the percent backlogged for that feature is the same as the target, or within 5 percentage points.

Wisconsin 2007: Targets for Highway Maintenance Conditions

Targets are set annually, and are intended to reflect priorities for that year, given fiscal constraints. They are a measure of effective management, not system condition.

					Stat	tewide							Regions	
									get mi			-		
Contribution			Actual % backlog	Target % backlog	On	Worse condition				Better onditio		Worse	On	Better
Category	Feature	Element	2007	2007	target ³	20	10	0	0	10	20	condition	Target	condition
	Centerline markings	Traffic and safety devices	3%	6%	0							-	All	
Critical	Regulatory/warning signs (emergency)	Traffic and safety devices	1%	0%	0								All	
Safety	Hazardous debris	Shoulders	9%	6%	0							SW	NC, NE, NW, SE	
	Drop-off/build-up (unpaved)	Shoulders	40%	25%			15					All		
	Delineators	Traffic and safety devices	21%	25%	0								NW, SW	NC, NE, SE
	Edgeline markings	Traffic and safety devices	4%	7%	0								NC, NW, SE, SW	NE
	Protective barriers	Traffic and safety devices	5%	3%	0							NE	NC, NW, SE, SW	
	Regulatory/warning signs (routine)	Traffic and safety devices	25%	30%	0							NW	NC, SE,	NE, SW
Safety	Special pavement markings	Traffic and safety devices	10%	25%						15			NC	NE, NW, SE, SW
	Fences	Roadsides	2%	14%						12				All
	Mowing	Roadsides	36%	40%	0							NE, SE		NC, NW, SW
	Mowing for vision	Roadsides	2%	5%	0								All	
	Woody vegetation control	Roadsides	3%	5%	0								All	
	Woody vegetation control for vision	Roadsides	2%	3%	0								All	

³ This symbol indicates that the percent backlogged for that feature is the same as the target, or within 5 percentage points.

					Stat	tewide							Regions	
							Gap	if tar	get mi	issed				
Contribution			Actual % backlog	Target % backlog	On		Worse onditio			Better onditio		Worse	On	Better
Category	Feature	Element	2007	2007	target ³	20	10	0	0	10	20	condition	Target	condition
	Other signs (routine)	Traffic and safety devices	56%	70%						14		-		All
Ride/Comfort	Potholes/raveling (paved)	Shoulders	6%	10%	0								NW, SE, NE	NC, SW
	Cross-slope (unpaved)	Shoulders	18%	20%	0								NC, NE, NW, SW	SE
	Other signs (emergency repair)	Traffic and safety devices	0%	1%	0								All	
	Cracking (paved)	Shoulders	53%	60%					7				NE, SE	NC, NW, SW
	Erosion (unpaved)	Shoulders	1%	5%	0								All	
	Culverts	Drainage	20%	15%	0							NE, NW, SW	NC, SE	
	Curb & gutter	Drainage	8%	10%	0								NC, NE, NW, SW	SE
	Ditches	Drainage	2%	2%	0								All	
Stewardship	Flumes	Drainage	25%	30%	0							NW		NC, NE, SE, SW
	Storm sewer system	Drainage	11%	10%	0							NW	NC, NE, SE, SW	
	Under-drains/edge- drains	Drainage	20%	25%	0							SW	NW	NC, NE, SE
	Walls and Barriers	Roadsides		5%	N/A									
	Noxious weeds	Roadsides	29%	50%							21		SW	NC, NW, NE, SE
Aesthetics	Litter	Roadsides	60%	75%						15			SW	NC, NW, NE, SE

nt	What a	re we spe	nding?		How much o the end o		n still needs tenance seas		Ho			intai tem?	
Element	D	ollars spent	4	Feature	Condition	% of s	system backlog	gged	2	2007 F	eature	grade	s
Ele		in millions) FY		_	change: 2005 to				A	В	С	D	F
	03	05	07		2007	2003	2005	2007					
				Alligator cracking	↑	1	3	2	х				
				Block cracking	\checkmark	2	3	4	х				
				Edge raveling	\checkmark	11	10	14		x			
nalt				Flushing	\checkmark	0	0	1	х				
y, aspl		16.8	21.2	Longitudinal cracking	\checkmark	26	61	63					х
Traveled way, asphalt		17.8 0.53 0.56	21.2 0.67 0.67	Longitudinal distortion		0	0	0	x				
vel		0.50	0.07	Patch deterioration		7	9	9		х			
Tra				Rutting	$\downarrow \downarrow$	12	6	19					х
				Surface raveling		1	0	0	х				
				Transverse cracking	\checkmark	23	54	61					х
				Transverse distortion		0	0	0	х				
				Distressed joints/cracks	\checkmark	20	24	27			x		
ay,		3.2 3.4	4.6 4.6	Longitudinal joint distress		1	0	0	x				
Traveled way, concrete		0.10	0.15	Patch deterioration	↓	18	20	21			х		
Traveled concrete		0.11	0.15	Slab breakup	↓	35	35	36				х	
rave				Surface distress	$\downarrow \downarrow$	9	2	11		х			
τy				Transverse faulting	↓	73	79	81					х

Wisconsin 2007: Compass Report on Paved Traveled Way Conditions

⁴ The dollar values listed in each column provide four figures: nominal dollars, real dollars (in 2007 constant dollars), nominal dollars per one thousand lane miles, and real dollars (in 2007 constant dollars) per one thousand lane miles, respectively.

Arrows indicate a condition change from 2005 to 2007 (\uparrow = improved condition/lower backlog percentage, Ψ = worse condition/higher backlog percentage). Double arrows indicate a change of 8 or more percentage points.

It	What	are we	e speno	ding?			How muc er		system e mainte			at the	m	aint	low v taine yster	d is tl	he
Element			ollars sp			Feature	Condition		% of sy	stem bac	klogged		20)07 H	Featur	e grad	es
E			n million		1	_	change:										
	FY 03	FY 04	FY 05	FY 06	FY 07		2006 to 2007 ⁶	2003	2004	2005	2006	2007	A	В	С	D	F
						Centerline markings	1	6	5	5	4	3		x			
						Delineators		19	21	24	21	21			х		
cted							1	11	7	5	6	4	x				
(selee	17.8	16.9	15.8 16.8	16.4	17.2		Υ	2	0	1	1	0	x				
fety	20.1	18.6		16.9	17.2	Other signs (routine)	\checkmark	n/a	46	59	55	56				х	
: sat	0.57	0.54 0.59	0.50 0.53	0.52 0.54	0.54 0.54	Protective barriers	\checkmark	18	3	4	4	5		х			
Traffic & safety (selected)	0.64	0.59	0.55	0.54	0.54	Reg./warning signs (emergency)		6	1	1	1	1	x				
Tra						Reg./warning signs (routine)	↑	n/a	36	41	31	25				Х	
						Special pavement markings	¥	15	13	5	3	10		x			
						Hazardous debris	1	9	13	12	13	9			х		
Shoulders	9.3 10.5	8.2 9.0	7.5 8.0	8.2 8.4	9.8 9.8	Cracking (paved)	¥	46	51	52	50	53				х	
Shou	0.30 0.34	0.26 0.29	0.24 0.26	0.26 0.27	0.31 0.31	Potholes/raveling (paved)	¥	7	5	7	5	6	x				
						Cross-slope (unpaved)	•	14	15	14	25	18		х			

Wisconsin 2007: Compass Report on Highway Maintenance Conditions

⁵ The dollar values listed in each column show the nominal dollars, real dollars (in 2007 constant dollars), nominal dollars per one thousand lane miles, and real dollars (in 2007 constant dollars) per one thousand lane miles, respectively.


⁶ Arrows indicate a condition change from 2006 to 2007 (\uparrow = improved condition/lower backlog percentage, Ψ = worse condition/higher backlog percentage). Double arrows indicate a change of 8 or more percentage points.

It	What	are we	e speno	ding?			How muc er		e system : e mainte			at the	m	ain	low w taine systen	d is th	ıe	
Element			ollars spo			Feature	Condition		% of sy	stem bac	klogged		20)07 I	Featur	e grad	es	
E	FY 03	(11) FY 04	FY 05	FY 06	FY 07		change: 2006 to 2007 ⁶	2003	2004	2005	2006	2007	A	В	С	D	F	
						Drop-off/build-up (unpaved)		45	37	36	40	40					х	
						Erosion (unpaved)	1	3	3	3	3	1	x					
						Culverts	↓	14	17	18	15	20			х			
					7.2	Curb & gutter		8	6	7	8	8	x					
Drainage	6.5 7.3	6.5 7.1	5.7 6.1	5.1 5.3	7.2	Ditches	^	2	2	2	3	2	x					
aina	0.21	0.21		0.16	0.23	Flumes	↑	20	32	19	27	25			х			
Dr	0.21	0.21			0.23	Storm sewer system	↓	8	9	9	9	11		х				
			0.18 0.19	0.18 0.19	0.16 0.17		Under-drains/edge- drains	¥	15	14	20	13	20		x			
						Walls and Barriers	n/a	2	n/a ⁷	n/a	n/a	n/a						
						Fences	↑	14	4	2	3	2	x					
	02.4	10.4	20.2	21.0	24.0	Litter	↑	67	70	62	64	60				Х		
ides	23.4 26.4	19.4 21.3	20.2 21.5	21.9 22.5	24.0 24.0	Mowing	^	n/a ⁸	40	35	39	36			х			
Roadsides	0.75	0.62	0.64	0.69	0.76	Mowing for vision		n/a ⁹	26	n/a	2	2	x					
Roi	0.85	0.62	0.68	0.05	0.76	Noxious weeds	<u>↑</u>	19	30	29	34	29			х			
						Woody vegetation		4	4	3	3	3	x					
						Woody veg. control for vision	\mathbf{V}	0	1	1	1	2	x					

⁷ There were not enough field observations of noise barriers and retaining walls to draw a valid conclusion about their condition in years 2004, 2005, 2006 and 2007.

 ⁸ There were not enough field observations of mowing to draw a valid conclusion about condition in the year 2003.
 ⁹ There were not enough field observations of mowing for vision to draw a valid conclusion about condition in the years 2003 and 2005.

WisDOT Regional Boundaries



				the se	eason?		the end of		
		What did it cost to achieve this condition? Region ¹⁰							
Element	Feature		Damaan			1-1	1		
		NO	1	t of Syst	1				
T 1 1	A 11' / 1 '	NC	NE	NW	SE	SW	Statewide		
Traveled way,	Alligator cracking			1%		4%	2		
asphalt	Block cracking			2%		6%	4		
	Edge raveling			8%		19%	14		
	Flushing			2%		0%	1		
	Longitudinal cracking			62%		65%	63		
	Longitudinal distortion			0%		0%	0		
	Patch deterioration			6%		13%	9		
	Rutting			20%		18%	19		
	Surface raveling			0%		0%	0		
	Transverse cracking			67%		55%	61		
	Transverse distortion			0%		0%	0		
	Dollars spent on traveled way, asphalt (in millions)	5.8	4.4	2.4	4.5	4.1	21.2		
Traveled way,	Distressed joints/cracks			28%		26%	27		
concrete	Longitudinal joint distress			0%		0%	0		
	Patch deterioration			20%		21%	21		
	Slab breakup			32%		38%	36		
	Surface distress			15%		9%	11		
	Transverse faulting			88%		78%	81		
	Dollars spent on traveled way, concrete (in millions)	1.7	1.2	0.6	0.3	0.8	4.6		
Traffic and	Centerline markings	1%	2%	5%	3%	3%	3		
safety (selected	Delineators	6%	10%	22%	14%	20%	21		
devices)	Edgeline markings	6%	1%	6%	5%	4%	4		
	Other signs (emergency repair)	0%	0%	0%	0%	1%	0		
	Other signs (routine)	60%	64%	54%	49%	56%	56		
	Protective barriers	1%	12%	2%	3%	8%	5		
	Regulatory/warning signs (emergency)	0%	1%	1%	2%	1%	1		
	Regulatory/warning signs (routine)	25%	39%	19%	28%	21%	25		
	Special pavement markings	23%	4%	11%	6%	5%	10		
	Dollars spent on traffic and								
	selected safety devices (in millions)	4.5	3.7	1.9	3.2	4.0	17.2		
Shoulders	Hazardous debris	8%	8%	5%	5%	18%	9		
	Cracking (paved)	47%	56%	44%	63%	53%	53		
	Potholes/raveling (paved)	4%	5%	6%	11%	4%	6		
	Cross-slope (unpaved)	19%	17%	24%	14%	15%	18		
	Drop-off/build-up (unpaved)	30%	45%	47%	39%	36%	40		

Regions 2007: Compass Report on Highway Maintenance Conditions

¹⁰ The biennial inspection schedule for pavement conditions resulted in roads in the Northwest (NW) and Southwest (SW) regions being reviewed in 2007.

				the se	eason?		the end of		
		What did it cost to achieve this condition?							
Element	Feature		P		ion ¹⁰				
			1	t of Syst			1		
		NC	NE	NW	SE	SW	Statewide		
	Erosion (unpaved)	1%	1%	3%	2%	0%	1		
	Dollars spent on shoulders (in millions)	2.7	1.4	1.5	1.9	2.4	9.8		
Drainage	Culverts	14%	24%	25%	15%	24%	20		
	Curb & gutter	11%	5%	12%	3%	10%	8		
	Ditches	1%	1%	1%	6%	2%	2		
	Flumes	10%	21%	50%	24%	19%	25		
	Storm sewer system	9%	7%	23%	9%	7%	11		
	Under-drains/edge-drains	7%	11%	21%	16%	45%	20		
	Dollars spent on drainage (in millions)	2.2	1.9	0.8	0.9	1.5	7.2		
Roadsides	Barriers								
	Fences	2%	0%	5%	1%	0%	2		
	Litter	49%	69%	57%	57%	71%	60		
	Mowing	24%	52%	34%	46%	23%	36		
	Mowing for vision	3%	1%	0%	2%	7%	2		
	Noxious weeds	19%	39%	5%	38%	48%	29		
	Woody vegetation control	8%	2%	2%	2%	3%	3		
	Woody vegetation control for vision	3%	2%	0%	3%	2%	2		
	Dollars spent on roadsides (in millions)	7.0	5.9	3.0	3.2	5.0	24.0		

2007 Winter: Compass Report on Winter Maintenance

The WisDOT Bureau of Highway Operations (BHO) reports winter performance measures in the Annual Winter Maintenance Report. The department is in the process of reviewing performance measures and grading curves for winter maintenance activities. As additional standards are put in place, this Compass Report on Winter Maintenance will measure how the department is meeting these expectations.

The BHO 2006-2007 Annual Winter Maintenance Report – with more operational detail – can be found on the winter reports home page (<u>http://dotnet/dtid_bho/extranet/winter/reports/index.htm</u> from inside WisDOT or

<u>https://trust.dot.state.wi.us/extntgtwy/dtid_bho/extranet/winter/reports/index.htm</u> from outside WisDOT).

	2003-04	2004-05	2005-06	2006-07
Time to bare/wet	2 hours 38	2 hours 4	1 hour 55	1 hour 28
pavement	minutes after	minutes after	minutes after	minutes after
	the storm ended	the storm ended	the storm ended	the storm ended
Cost per lane mile	\$1,279	\$1,374	\$1,386	\$1,549
Winter severity	31.2	31.9	31.8	28.4
index				
Winter related	26 per 100	25 per 100	24 per 100	23 per 100
	million vehicle	million vehicle	million vehicle	million vehicle
crash	miles traveled	miles traveled	miles traveled	miles traveled

Statewide measures for winter

Key findings

- In keeping with WisDOT guidelines, during similar storm events, drivers on major urban freeways and highways had less time to wait until they saw bare/wet pavement than did drivers on secondary roads. From storm to storm, however, most of the variability in this time was due to weather effects (type, duration and severity of storms throughout the winter season).
- The average time to bare/wet pavement during winter 2006-07 was 1 hour and 28 minutes, which is twenty seven minutes less than the previous winter. The average Winter Severity Index (WSI) in 2006-07 was 28.4 versus 31.8 in the previous year.

Wisconsin and Regions 2007: Compass Report on Bridges

Bridge Condition

	Region Percent of Bridges											
	N	C	N	Е	N	W	S	E	S	W	statev	wide
Feature	2006	2007	2006	2007	2006	2007	2006	2007	2006	2007	2006	2007
Decks in Fair ¹¹ condition	19%	21%	23%	21%	44%	47%	51%	48%	24%	24%	33%	33%
Superstructures in Fair condition	14%	15%	15%	17%	35%	32%	52%	50%	20%	22%	29%	28%
Substructures in Fair condition	17%	17%	27%	25%	34%	31%	51%	50%	16%	18%	29%	29%
Number of state-maintained bridges	604	620	771	837	1040	1067	1034	1023	1451	1462	4900	5007
Dollar spent on bridges (in millions)) \$10.5 \$11.4								\$11.4			

Bridge Maintenance Needs

		Region Percent of Bridges needing maintenance # of Bridges needing maintenance										
	N	С	N	Е	N	W SE			S	W	statewide	
Maintenance Action	2006	2007	2006	2007	2006	2007	2006	2007	2006	2007	2006	2007
Deals Seal Surface Create	24%	39%	13%	18%	8%	7%	12%	14%	8%	13%	11%	16%
Deck – Seal Surface Cracks	144	241	102	150	78	77	122	140	114	188	560	796
Europeion Jointa Saal	8%	11%	22%	25%	1%	2%	15%	18%	3%	4%	8%	11%
Expansion Joints – Seal	48	66	167	209	11	24	150	181	39	51	415	531
Migo Cut Pruch	2%	4%	2%	4%	8%	5%	13%	17%	5%	12%	7%	9%
Misc. – Cut Brush	12	24	18	32	85	57	138	174	68	174	321	461
Approach – Seal Approach	1%	1%	2%	4%	17%	16%	6%	9%	5%	10%	7%	9%
to Paving Block	4	5	15	37	175	174	63	89	74	146	331	451
Deck – Patching	10%	12%	6%	9%	4%	4%	8%	9%	2%	4%	5%	7%
Deck – Fatching	61	75	48	78	37	37	87	96	33	65	266	351
Drainage - Repair	1%	2%	7%	9%	5%	4%	11%	12%	3%	6%	6%	7%
Washouts / Erosion	8	11	56	78	50	45	112	121	46	83	272	338
Approach - Wedge	2%	3%	1%	1%	3%	2%	11%	12%	4%	7%	5%	5%
Approach	14	17	5	11	31	25	109	126	65	95	224	274

¹¹ Bridge decks, superstructures, and substructures that receive NBI ratings of 5 or 6 are regarded to be in fair condition and warrant reactive maintenance treatments

Wisconsin and Regions 2007: Compass Report on Signs

		Regulatory/Wari	-		Other Signs						
	Total Signs	%Backlog	Deficient Signs	Average Years Beyond Service Life ¹²	Total Signs	%Backlog	Deficient Signs	Average Years Beyond Service Life ¹²			
2005	160,185	41%	65,092	5.7	113,693	59%	67,449	6			
2006	157,742	31%	49,457	5	126,362	55%	69,051	5.9			
2007	160,206	25%	40,548	4.8	125,891	56%	70,099	6.3			

Wisconsin 2007: Routine Replacement of Signs

¹² When comparing the 'Average years beyond service life column', please note that starting with the 2006 data the useful life standard for signs with high intensity face material changes from 10 years to 12 years. The useful life standard for engineer-grade signs remained at 7 years.

			Regulatory/W	arning/School Signs	T			other Signs	Γ
Region	Total	Signs	%Backlog	Deficient Signs	Average Years Beyond Service Life ¹²	Total Signs	%Backlog	Deficient Signs	Average Years Beyond Service Life ¹²
	2005	26,164	45%	11,746	6.1	18,480	66%	12,177	6.6
NC	2006	26,117	35%	9,097	5.4	20,152	61%	12,342	6.5
	2007	26,663	25%	6,660	4.5	19,226	60%	11,494	6.5
	2005	22,246	47%	10,346	5.4	20,367	62%	12,647	5.5
NE	2006	21,520	39%	8,463	5	21,517	60%	12,953	5.5
	2007	21,887	39%	8,459	5.3	21,776	64%	13,831	6.1
	2005	36,737	37%	13,606	5.4	29,848	59%	17,541	5.2
NW	2006	34,087	26%	8,883	4.7	31,874	52%	16,544	5.1
	2007	33,786	19%	6,372	4.4	31,566	54%	16,962	5.3
	2005	32,872	32%	10,533	4.9	21,077	50%	10,439	5.7
SE	2006	35,226	30%	10,426	4.7	26,987	48%	12,835	5.7
	2007	36,390	28%	10,234	5	27,341	49%	13,386	6.2
	2005	42,166	45%	18,861	6.3	23,921	61%	14,645	7.0
SW	2006	40,792	31%	12,588	5.1	25,832	56%	14,377	6.9
	2007	41,480	21%	8,823	4.7	25,982	56%	14,426	7.4

Regions 2007: Routine Replacement of Signs – Region Detail

	Face			Region			Stat	ewide
Grade	Туре	NC	NE	NW	SE	SW	Total	Percentage
	Non-Reflective	4	90	465	147	125	831	0.3%
Engineering Grade (7 years service life)	Other or Varies	14	8	428	23	924	1,397	0.5%
(Reflective - Engineering Grade	20,094	25,127	31,502	31,757	28,913	137,393	48.0%
	Type D - Diamond Grade	32	15	5	7	156	215	0.1%
High Intensity	Type F - Fluorescent	479	178	353	740	724	2,474	0.9%
(12 years service life)	Type H - High Intensity	19,702	16,758	24,593	22,987	28,316	112,356	39.3%
Type HP - Prismatic High Intensity		5,564	1,487	8,006	8,070	8,304	31,431	11.0%
	Total			65,352	63,731	67,462	286,097	100%

Wisconsin and Regions 2007: Sign Face Material Distribution

Wisconsin and Regions 2007: Sign Face Material Trends

	2006		2007			
Region	Engineering Grade	High Intensity	Engineering Grade	High Intensity		
NC	24,877	21,392	20,112	25,777		
NE	25,942	17,095	25,225	18,438		
NW	38,240	27,721	32,395	32,957		
SE	34,430	27,783	31,927	31,804		
SW	34,528	32,096	29,962	37,500		
Statewide	158,017	126,087	139,621	146,476		
	56%	44%	49%	51%		

Operational Reports

2007 Signs: Compass Report on Routine Replacement and Age Distribution

Data in this section comes from the Sign Inventory Management System (SIMS). This section covers routine, not emergency replacement of knocked-down signs and related work.

Key Observations:

- The expected service life of signs is calculated based on the manufactured date of the signs, not the installation date. It is possible for a sign to be installed one or more years after it is manufactured.
- Signs that are in service beyond their expected service life are considered backlogged for replacement.
- Statewide and in each region a large number and percentage of signs are backlogged for replacement.
- WisDOT places a higher priority on routine replacement of regulatory and warning signs than on other signs, and this is reflected in a dip in the number and percent of regulatory signs that are backlogged for replacement.
- The NW region has the lowest percentages of signs backlogged for routine maintenance at 19% for regulatory/warning signs, while the SE region has the lowest backlog percentage for other signs at 49%.
- The backlog for routine maintenance in the counties ranges from 4% to 52% for regulatory/warning signs and from 27% to 83% for other signs. Buffalo County has the lowest percentages of backlog for regulatory/warning signs and Rusk County has the lowest percentages of backlog for other signs.

]	Regulatory/Wari	ning/School Signs	5	Other Signs						
	Total Signs	%Backlog	Deficient Signs	Average Years Beyond Service Life ¹³	Total Signs	%Backlog	Deficient Signs	Average Years Beyond Service Life ¹³			
2005	160185	41%	65092	5.7	113693	59%	67449	6.0			
2006	157742	31%	49457	5.0	126362	55%	69051	5.9			
2007	160206	25%	40548	4.8	125891	56%	70099	6.3			

Wisconsin 2007: Routine Replacement of Signs

Regions 2007: Routine Replacement of Signs

		Regulator	y/Warning/School Sign	s	Other Signs						
Region	Total Signs	%Backlog	Deficient Signs	Average Years Beyond Service Life ¹³	Total Signs	%Backlog	Deficient Signs	Average Years Beyond Service Life ¹³			
NC	26663	25%	6660	4.5	19226	60%	11494	6.5			
NE	21887	39%	8459	5.3	21776	64%	13831	6.1			
NW	33786	19%	6372	4.4	31566	54%	16962	5.3			
SE	36390	28%	10234	5.0	27341	49%	13386	6.2			
SW	41480	21%	8823	4.7	25982	56%	14426	7.4			

¹³ Years beyond service life depends upon the face material of the individual signs. When comparing the average years beyond service life for multiple years, please note that starting in 2006 the expected useful life of signs with high intensity face material increased from 10 to 12 years. The expected useful life for engineer-grade signs remains at 7 years.

		I	Regulatory/Wa	arning/School S	Signs		Other	r Signs	
Region	County	Total Signs	%Backlog	Deficient Signs	Average Years Beyond Service Life	Total Signs	%Backlog	Deficient Signs	Average Years Beyond Service Life
Kegion	ADAMS	922	14%	130	2.35	657	61%	399	5.0
	FLORENCE	922 485	34%	165	5.45	432	60%	261	3.0 7.2
	FOREST	1273	23%	105 296	6.13	985	39%	384	8.2
	GREEN LAKE	867	23% 13%	290 109	3.19	647	59% 66%	428	7.2
	IRON	1061	41%	431	6.88	730	54%	428 392	9.3
	LANGLADE	1231	39%	481	5.11	1201	83%	995	10.6
	LINCOLN	1231	21%	312	4.70	996	52%	518	8.4
	MARATHON	4107	21%	863	4.13	2521	57%	1434	4.8
	MARQUETTE	955	24%	232	4.19	948	73%	692	5.1
NC	MENOMINEE	427	27%	117	4.61	164	42%	69	5.9
	ONEIDA	1835	52%	951	5.81	1346	66%	884	7.7
	PORTAGE	2216	26%	567	4.19	1956	55%	1074	4.6
	PRICE	1022	44%	447	4.55	1051	66%	695	6.8
	SHAWANO	282	45%	127	4.65	363	56%	205	4.5
	VILAS	1552	29%	444	4.12	958	70%	203 667	8.1
	WAUPACA	2844	14%	397	2.91	1753	52%	916	4.6
	WAUSHARA	1855	15%	285	2.29	1280	69%	886	6.0
	WOOD	2258	14%	306	2.37	1238	48%	595	5.4
	BROWN	3125	40%	1258	4.74	3999	72%	2862	6.3
	CALUMET	1006	33%	330	5.14	1133	64%	726	5.9
	DOOR	1654	49%	807	4.83	997	74%	739	5.2
NE	FOND DU LAC	2460	29%	723	5.60	2345	50%	1178	6.8
INE	KEWAUNEE	570	43%	243	5.32	528	70%	372	5.9
	MANITOWOC	1733	50%	864	5.11	1975	81%	1598	6.2
	MARINETTE	1517	38%	584	5.39	1309	50%	648	5.9
	OCONTO	1756	16%	280	4.42	1265	43%	548	4.7

Counties 2007: Routine Replacement of Signs

	Γ	I	Regulatory/Wa	arning/School S	Signs		Other	r Signs	
				-	Average Years				Average Years
	~	Total		Deficient	Beyond			Deficient	Beyond
Region	County	Signs	%Backlog	Signs	Service Life	Total Signs	%Backlog	Signs	Service Life
	OUTAGAMIE	3110	39%	1202	6.33	2687	67%	1807	6.1
	SHEBOYGAN	2574	47%	1204	5.16	2989	69%	2053	5.9
	WINNEBAGO	2382	40%	964	5.32	2549	51%	1300	6.3
	ASHLAND	1208	20%	237	3.50	881	53%	468	4.5
	BARRON	1763	20%	349	3.90	1644	51%	839	6.1
	BAYFIELD	1483	21%	309	2.66	1188	46%	552	4.6
	BUFFALO	1564	4%	69	7.10	1305	55%	722	8.6
	BURNETT	1212	25%	305	3.96	868	59%	514	5.3
	CHIPPEWA	2218	12%	271	4.57	2341	47%	1102	5.0
	CLARK	1697	8%	137	4.66	1396	53%	742	4.4
	DOUGLAS	1909	31%	595	2.95	1667	54%	903	4.2
	DUNN	2047	14%	286	4.56	2419	51%	1234	4.3
NW	EAU CLAIRE	2557	32%	825	5.89	2426	55%	1329	5.2
IN W	JACKSON	1630	14%	232	6.61	1658	54%	888	8.6
	PEPIN	610	13%	79	6.20	654	50%	330	5.6
	PIERCE	1662	14%	232	3.66	2210	71%	1570	4.9
	POLK	2236	16%	358	3.52	1576	54%	858	5.3
	RUSK	1204	22%	267	4.29	847	27%	230	4.8
	SAWYER	1412	12%	173	3.09	1209	45%	546	4.7
	ST. CROIX	2525	18%	467	4.62	3011	61%	1826	4.5
	TAYLOR	972	11%	107	4.78	1009	44%	443	4.7
	TREMPEALEAU	1917	28%	537	6.47	1779	54%	957	7.4
	WASHBURN	1960	27%	537	3.28	1478	62%	909	4.4
	KENOSHA	3820	32%	1238	4.81	3301	44%	1443	6.2
	MILWAUKEE	10650	31%	3276	5.32	8641	53%	4563	7.1
	OZAUKEE	1812	19%	350	4.32	1384	57%	792	6.6
SE	RACINE	4544	32%	1450	4.04	3389	53%	1792	5.4
	WALWORTH	3616	20%	718	5.28	2641	49%	1304	5.4
	WASHINGTON	3668	22%	798	4.77	2853	45%	1275	5.2
	WAUKESHA	8280	29%	2404	5.48	5132	43%	2217	5.5

		I	Regulatory/Wa	arning/School S	Signs		Othe	r Signs	
					Average Years				Average Years
. .	a	Total		Deficient	Beyond			Deficient	Beyond
Region	County	Signs	%Backlog	Signs	Service Life	Total Signs	%Backlog	Signs	Service Life
	COLUMBIA	3169	15%	463	4.45	1511	52%	790	7.2
	CRAWFORD	2159	16%	356	3.19	1534	56%	855	7.2
	DANE	6238	32%	1991	5.71	2899	54%	1564	7.2
	DODGE	2972	26%	758	4.44	1751	56%	984	6.6
	GRANT	2978	21%	623	5.59	1739	58%	1005	7.4
	GREEN	1489	15%	229	4.29	705	52%	369	7.0
	IOWA	1920	34%	645	5.96	1166	58%	676	7.6
	JEFFERSON	2097	18%	368	3.74	1106	57%	635	7.7
SW	JUNEAU	1799	12%	219	3.00	1596	64%	1027	6.8
	LA CROSSE	2699	16%	420	2.85	2365	55%	1292	7.9
	LAFAYETTE	1191	12%	143	4.29	820	70%	575	9.5
	MONROE	2519	13%	317	3.05	2290	51%	1167	8.2
	RICHLAND	1912	13%	240	2.48	1529	48%	728	6.6
	ROCK	2320	32%	731	5.22	1548	55%	857	7.4
	SAUK	3288	19%	611	5.80	1274	54%	693	7.4
	VERNON	2730	26%	709	3.67	2149	56%	1209	6.8

Regulatory /								of signs						
warning	% of total of each age group													
/ school		Years prior to the end of service life								ars beyo	nd servic	e life		Total
Signs	6-10	5	4	3	2	1	0	1	2	3	4	5-10	>10	Total
Statewide	85433	4830	5711	4068	5652	6590	7374	5946	6313	6633	4608	13539	3509	160206
Statewide	53%	3%	4%	3%	4%	4%	5%	4%	4%	4%	3%	8%	2%	100%
NC	14687	871	1042	718	942	1014	729	1013	1218	1025	886	2072	446	26663
NC	55%	3%	4%	3%	4%	4%	3%	4%	5%	4%	3%	8%	2%	100%
NIE	8311	691	663	514	980	1000	1269	1166	838	1152	926	3617	760	21887
NE	38%	3%	3%	2%	4%	5%	6%	5%	4%	5%	4%	17%	3%	100%
NTXX/	20149	1119	1350	1055	1404	909	1428	1156	971	1307	770	1588	580	33786
NW	60%	3%	4%	3%	4%	3%	4%	3%	3%	4%	2%	5%	2%	100%
CE	18087	998	911	634	1024	2086	2416	1464	1629	1421	1075	3726	919	36390
SE	50%	3%	3%	2%	3%	6%	7%	4%	4%	4%	3%	10%	3%	100%
CW	24199	1151	1745	1147	1302	1581	1532	1147	1657	1728	951	2536	804	41480
SW	58%	3%	4%	3%	3%	4%	4%	3%	4%	4%	2%	6%	2%	100%

Wisconsin and Regions 2007: Age Distribution of Signs

								er of sign							
Other		% of total of each age group													
Signs	Years prior to the end of service life								Y	ears beyo	ond servi	ce life		Total	
	6-10	5	4	3	2	1	0	1	2	3	4	5-10	>10	10141	
Statewide	26525	5042	1818	2536	4294	7460	8117	6397	7884	8694	6118	29260	11746	125891	
Statewide	21%	4%	1%	2%	3%	6%	6%	5%	6%	7%	5%	23%	9%	100%	
NC	4084	886	235	234	544	913	836	1031	1604	1112	1235	4070	2442	19226	
NC	21%	5%	1%	1%	3%	5%	4%	5%	8%	6%	6%	21%	13%	100%	
NE	3456	602	181	481	766	1348	1111	910	1014	1723	1315	7259	1610	21776	
NE	16%	3%	1%	2%	4%	6%	5%	4%	5%	8%	6%	33%	7%	100%	
NW	6749	1349	502	628	956	1640	2780	2126	1863	3027	1516	6502	1928	31566	
IN VV	21%	4%	2%	2%	3%	5%	9%	7%	6%	10%	5%	21%	6%	100%	
SE	6776	1237	343	608	987	2220	1784	1294	1922	1442	1036	5427	2265	27341	
SE	25%	5%	1%	2%	4%	8%	7%	5%	7%	5%	4%	20%	8%	100%	
SW	5460	968	557	585	1041	1339	1606	1036	1481	1390	1016	6002	3501	25982	
3W	21%	4%	2%	2%	4%	5%	6%	4%	6%	5%	4%	23%	13%	100%	


2007 Traveled Way: Compass Report on Maintenance Condition

Data for this section comes from the Pavement Inventory File (PIF) dated March 2008 received from Mike Malaney.

Pavement Inspection Schedule Map

Note: The map below has two colors. If you are not viewing a color copy, please contact the Compass Program Manager at the Bureau of Highway Operations for a color version to be mailed or emailed to you

The map below shows the pavement evaluation schedule in Wisconsin. Pavement inventory data is collected every two years with the data from half the state collected in one year and the other half of the state in the other year. The yellow (lightly shaded) counties show the NW and SW regions with segments evaluated in 2003, 2005, and 2007 (odd years), while the green (darker shaded) counties show the NC, NE, and SE regions with segments evaluated in 2002, 2004, and 2006 (even years).



Wisconsin 2007: Traveled Way Maintenance Condition

Asphalt Traveled Way

	% of miles backlogged for year										
		NW, SW		NC, NE, SE							
Distress	2003	2005	2007	2002	2004	2006					
Alligator Cracking	1%	3%	2%	1%	1%	2%					
Block Cracking	2%	3%	4%	2%	4%	2%					
Edge Raveling	11%	10%	14%	15%	15%	17%					
Flushing	0%	0%	1%	0%	0%	0%					
Longitudinal Cracking	26%	61%	63%	17%	49%	62%					
Longitudinal Distortion	0%	0%	0%	0%	0%	0%					
Patch Deterioration	7%	9%	9%	10%	6%	7%					
Rutting	12%	6%	19%	6%	3%	7%					
Surface Raveling	1%	0%	0%	0%	0%	0%					
Transverse Cracking	23%	54%	61%	18%	49%	62%					
Transverse Distortion	0%	0%	0%	0%	0%	0%					

Concrete Traveled Way

		% of miles backlogged for year								
		NW, SW	NC, NE, SE							
Distress	2003	2005	2007	2002	2004	2006				
Distressed Joint/Cracks	20%	24%	27%	16%	16%	18%				
Longitudinal Joint Distress	1%	0%	0%	2%	1%	0%				
Patch Deterioration	18%	20%	21%	19%	18%	18%				
Slab Breakup	35%	35%	36%	33%	28%	29%				
Surface Distress	9%	2%	11%	16%	9%	8%				
Transverse Faulting	73%	79%	81%	77%	69%	61%				

Regional Trends: Traveled Way

	• - 4	% of Miles Backlogged in Region ¹⁴ Year NC NW SE SW								
Asphalt traveled way d	Asphalt traveled way distress			NE	NW	SE	SW			
	NW	2003			0%		1%			
	SW	2005			3%		3%			
Alligator Creaking	5 11	2007			1%		4%			
Alligator Cracking	NC	2002	1%	2%		2%				
	NE	2004	0%	1%		2%				
	SE	2006	1%	2%		3%				
	NUV	2003			2%		2%			
	NW SW	2005			2%		4%			
Die als Creation a	2 10	2007			2%		6%			
Block Cracking	NC	2002	2%	2%		3%				
	NE	2004	4%	3%		4%				
	SE	2006	2%	2%		2%				
		2003			8%		15%			
	NW	2005			7%		14%			
	SW	2007			8%		19%			
Edge Raveling	NC	2002	12%	15%		20%				
	NE	2004	11%	17%		23%				
	SE	2006	14%	15%		26%				
		2003			1%		0%			
	NW	2005			0%		0%			
	SW	2007			2%		0%			
Flushing	NC	2002	0%	0%		0%				
	NE	2004	0%	0%		0%				
	SE	2006	0%	0%		0%				
		2003			28%		26%			
	NW	2005			63%		62%			
	SW	2007			62%		65%			
Longitudinal Cracking	NC	2002	18%	16%		20%				
	NE	2002	50%	47%		66%				
	SE	2006	58%	64%		74%				
		2003			0%		0%			
	NW	2005			0%		0%			
	SW	2003			0%		0%			
Longitudinal Distortion	NC	2007	0%	0%		0%				
	NE	2002	0%	0%		0%				
	SE	2004	0%	0%		0%				
		2000			6%		10%			
	NW	2005			7%		13%			
	SW	2003			6%		13%			
Patch Deterioration	NC	2007	8%			14%				
	NC NE	2002	8% 5%							
	NE SE	2004	5%	4% 6%		13% 14%				

¹⁴ Due to the biennial inspection schedule for traveled way, there are not enough data taken to represent regions NW and SW in 2002, 2004 and 2006 and NC, NE, and SE in 2001, 2003, and 2005.

			% of Mi	iles Backlo	gged in R	egion ¹⁴	
Asphalt traveled way dis	Asphalt traveled way distress			NE	NW	SE	SW
	NW	2003			14%		11%
	SW	2005			0%		13%
Dutting	2.0	2007			20%		18%
Rutting	NC	2002	8%	5%		5%	
	NE	2004	6%	0%		0%	
	SE	2006	12%	5%		4%	
	NINI	2003			0%		1%
	NW	2005			0%		0%
Secure and December of	SW	2007			0%		0%
Surface Raveling	NC	2002	0%	0%		0%	
	NE	2004	0%	0%		0%	
	SE	2006	0%	0%		0%	
		2003			30%		17%
	NW	2005			63%		48%
T C L	SW	2007			67%		55%
Transverse Cracking	NC	2002	20%	18%		19%	
	NE	2004	52%	46%		64%	
	SE	2006	62%	62%		72%	
	N 11 1 <i>1</i>	2003			0%		0%
	NW	2005			0%		0%
П Р: (/:	SW	2007			0%		0%
Transverse Distortion	NC	2002	0%	0%		0%	
	NE	2004	0%	0%		0%	
	SE	2006	0%	0%		0%	

Commente translad mar dia	tragg		% M	iles Backlog	gged in Reg	gion	
Concrete traveled way dis	ress	Year	NC	NE	NW	SE	SW
	NW	2003			22%		20%
	SW	2005			25%		24%
Distressed Joint/Cracks	3 W	2007			28%		26%
Distressed Joint/Cracks	NC	2002	15%	16%		22%	
	NE	2004	16%	13%		25%	
	SE	2006	19%	21%		21%	
	NIX	2003			0%		0%
	NW SW	2005			0%		0%
Longitudinal Joint Distance	310	2007			0%		0%
Longitudinal Joint Distress	NC NE	2002	1%	4%		0%	
		2004	0%	0%		0%	
	SE	2006	0%	0%		0%	
	NW	2003			17%		20%
	SW	2005			20%		21%
Patch Deterioration	3 W	2007			20%		21%
Fatch Deterioration	NC	2002	17%	25%		23%	
	NE	2004	17%	20%		22%	
	SE	2006	16%	22%		22%	

Commente translad mar dia	1		% M	iles Backlo	gged in Reg	gion	
Concrete traveled way dis	tress	Year	NC	NE	NW	SE	SW
	NW	2003			35%		38%
	SW	2005			35%		38%
Slah Dreakur	3 W	2007			32%		38%
Slab Breakup	NC	2002	31%	40%		45%	
	NE	2004	28%	28%		37%	
	SE	2006	28%	29%		38%	
	NIXI	2003			5%		10%
	NW SW	2005			1%		3%
Surface Distance		2007			15%		9%
Surface Distress	NC	2002	7%	14%		7%	
	NE	2004	4%	5%		4%	
	SE	2006	2%	4%		4%	
	NIXI	2003			81%		75%
	NW SW	2005			78%		82%
Transverse Foulting	21	2007			88%		78%
Transverse Faulting	NC	2002	80%	88%		91%	
	NE	2004	80%	62%		91%	
	SE	2006	76%	40%		91%	

A anhalt though demons distances		% of miles ¹⁵ in	n condition ¹⁶	
Asphalt traveled way distress	Excellent Fair		Moderate	Poor
Alligator Cracking ¹⁷	98%	2%	0%	0%
Block Cracking ¹⁷	96%	1%	1%	1%
Edge Raveling	86%	12%	1%	2%
Flushing	99%	0%	0%	0%
Longitudinal Cracking ¹⁷	53%	44%	16%	3%
Longitudinal Distortion	100%	0%	0%	0%
Patch Deterioration	91%	2%	2%	6%
Rutting	81%	18%	0%	1%
Surface Raveling	100%	0%	0%	0%
Transverse Cracking ¹⁷	39%	42%	17%	2%
Transverse Distortion	100%	0%	0%	0%

Wisconsin 2007: Traveled Way Condition Distribution

Concrete traveled way	% of miles in condition						
distress	Excellent	Fair	Moderate	Poor			
Distressed Joint/Cracks	73%	17%	10%	1%			
Longitudinal Joint Distress	100%	0%	0%	0%			
Patch Deterioration	79%	14%	5%	1%			
Slab Breakup	64%	30%	5%	0%			
Surface Distress	89%	6%	5%	0%			
Transverse Faulting	19%	81%	0%	0%			

 ¹⁵ Rows may not sum to 100% due to rounding.
 ¹⁶ Condition comes from WisDOT's Pavement Maintenance Management System and reflects extent and severity of distress.

¹⁷ Cracks in asphalt pavement may be sealed or unsealed. Only miles with unsealed cracks are included in the % backlogged. Cracks in asphalt pavement may be sealed or unsealed.

Asphalt traveled way		% of miles						
distress	Condition		•	Region ¹⁸				
uisti CSS		NC	NE	NW	SE	SW		
	Excellent			99%		96%		
Alligator Cracking	Fair			1%		2%		
Anigator Clacking	Moderate			0%		1%		
	Poor			0%		0%		
	Excellent			98%		94%		
Block Cracking	Fair			1%		2%		
DIOCK CLACKING	Moderate			1%		2%		
	Poor			0%		2%		
	Excellent			92%		81%		
Edge Raveling	Fair			7%		16%		
Euge Ravening	Moderate			0%		1%		
	Poor			1%		2%		
	Excellent			98%		100%		
Flushing	Fair			1%		0%		
	Poor			1%		0%		
	Excellent			38%		35%		
Longitudinal Cracking	Fair			47%		40%		
	Moderate			12%		21%		
	Poor			3%		4%		
	Excellent			100%		100%		
Longitudinal Distortion	Fair			0%		0%		
Longitudinal Distortion	Moderate			0%		0%		
	Poor			0%		0%		
	Excellent			94%		87%		
Datah Datamianatian	Fair			1%		2%		
Patch Deterioration	Moderate			1%		3%		
	Poor			3%		8%		
	Excellent			80%		82%		
Rutting	Fair			19%		17%		
C C	Poor			1%		1%		
	Excellent			100%		100%		
	Fair			0%		0%		
Surface Raveling	Moderate			0%		0%		
	Poor			0%		0%		
	Excellent			33%		45%		
	Fair			51%		33%		
Transverse Cracking	Moderate			14%		19%		
	Poor			2%		3%		
	Excellent			100%		100%		
	Fair			0%		0%		
Transverse Distortion	Moderate			0%		0%		
	Poor			0%		0%		

Regions 2007: Traveled Way Condition Distribution

¹⁸ Due to the biennial inspection schedule for traveled way, only the NW and SW regions are reported in 2007.

		% of miles						
Concrete traveled way distress	Condition			Region ¹⁸				
		NC	NE	NW	SE	SW		
	Excellent			72%		74%		
Distressed Joint/Cracks	Fair			17%		16%		
Distressed John Clacks	Moderate			10%		9%		
	Poor			1%		1%		
	Excellent			100%		100%		
Longitudinal Joint Distross	Fair			0%		0%		
Longitudinal Joint Distress	Moderate			0%		0%		
	Poor			0%		0%		
	Excellent			80%		79%		
Patch Deterioration	Fair			15%		14%		
Patch Detenoration	Moderate			4%		6%		
	Poor			1%		1%		
	Excellent			68%		62%		
Slab Proslaup	Fair			28%		31%		
Slab Breakup	Moderate			3%		6%		
	Poor			0%		0%		
	Excellent			85%		91%		
Surface Distress	Fair			4%		7%		
	Moderate			11%		2%		
	Excellent			12%		22%		
Tropovorce Foulting	Fair			88%		78%		
Transverse Faulting	Moderate			0%		0%		
	Poor			0%		0%		

Counties 2007: Traveled Way

Asphalt traveled way

_			% of miles backlogged									
Region	County	Alligator Cracking	Block Cracking	Edge Raveling	Flushing	Longitudinal Cracking	Longitudinal Distortion	Patch Deterioration	Rutting	Surface Raveling	Transverse Cracking	Transverse Distortion
	ASHLAND	3%	2%	25%	0%	91%	0%	6%	32%	0%	94%	0%
	BARRON	0%	3%	3%	1%	56%	0%	1%	15%	0%	70%	0%
	BAYFIELD	4%	2%	7%	2%	51%	0%	5%	25%	0%	64%	0%
	BUFFALO	2%	1%	8%	0%	48%	0%	16%	21%	1%	37%	0%
	BURNETT	1%	2%	10%	6%	84%	0%	8%	29%	0%	93%	0%
	CHIPPEWA	0%	1%	5%	1%	68%	0%	1%	20%	0%	58%	0%
	CLARK	0%	2%	1%	1%	57%	0%	1%	11%	0%	70%	0%
	DOUGLAS	0%	3%	6%	2%	72%	0%	5%	5%	1%	69%	0%
	DUNN	2%	3%	10%	0%	61%	0%	2%	20%	0%	63%	0%
NW	EAU CLAIRE	0%	0%	3%	0%	59%	0%	1%	13%	0%	89%	0%
14 44	JACKSON	0%	2%	16%	0%	56%	0%	4%	25%	0%	64%	0%
	PEPIN	0%	0%	9%	0%	44%	0%	0%	28%	0%	53%	0%
	PIERCE	5%	5%	25%	2%	83%	0%	19%	11%	0%	81%	0%
	POLK	0%	0%	5%	5%	68%	0%	6%	26%	0%	71%	0%
	RUSK	0%	2%	2%	1%	51%	0%	3%	41%	0%	57%	0%
	SAWYER	0%	0%	2%	2%	41%	0%	1%	21%	0%	44%	0%
	ST. CROIX	1%	2%	7%	0%	74%	0%	8%	17%	0%	90%	0%
	TAYLOR	1%	2%	12%	14%	51%	0%	6%	8%	0%	64%	0%
	TREMPEALEAU	0%	1%	13%	0%	61%	0%	13%	21%	0%	57%	0%
	WASHBURN	0%	0%	2%	0%	61%	0%	4%	17%	0%	63%	0%
	COLUMBIA	7%	9%	22%	0%	69%	0%	8%	28%	0%	67%	0%
SW	CRAWFORD	7%	6%	25%	0%	75%	0%	24%	16%	0%	62%	0%
	DANE	1%	6%	30%	0%	76%	0%	17%	19%	0%	71%	0%

						% of 1	miles back	logged				
Region	County	Alligator Cracking	Block Cracking	Edge Raveling	Flushing	Longitudinal Cracking	Longitudinal Distortion	Patch Deterioration	Rutting	Surface Raveling	Transverse Cracking	Transverse Distortion
	DODGE	1%	1%	11%	0%	41%	0%	4%	10%	1%	38%	0%
	GRANT	2%	4%	11%	0%	62%	0%	7%	13%	0%	52%	0%
	GREEN	2%	16%	25%	0%	75%	0%	4%	8%	0%	53%	0%
	IOWA	7%	1%	23%	0%	70%	0%	9%	11%	0%	49%	0%
	JEFFERSON	6%	5%	24%	0%	82%	0%	6%	12%	0%	74%	0%
	JUNEAU	1%	15%	15%	0%	52%	0%	18%	31%	1%	46%	0%
	LA CROSSE	2%	6%	30%	0%	70%	0%	24%	17%	0%	59%	0%
	LAFAYETTE	3%	5%	11%	0%	64%	0%	18%	22%	0%	50%	0%
	MONROE	1%	1%	14%	0%	63%	0%	6%	15%	0%	59%	0%
	RICHLAND	2%	4%	22%	0%	60%	0%	24%	18%	0%	41%	0%
	ROCK	7%	11%	19%	0%	69%	0%	9%	18%	0%	59%	0%
	SAUK	2%	9%	12%	0%	48%	0%	18%	21%	0%	37%	0%
	VERNON	6%	0%	17%	0%	71%	0%	13%	17%	0%	54%	0%

Concrete traveled way

				% of miles	backlogged	-	
Region	County	Distressed Joint/Cracks	Longitudinal/ Joint Distress	Patch Deterioration	Slab Breakup	Surface Distress	Transverse Faulting
0	ASHLAND	75%	0%	50%	75%	25%	75%
	BARRON	38%	0%	25%	44%	13%	100%
	BAYFIELD	50%	0%	0%	50%	0%	100%
	BUFFALO	0%	0%	0%	75%	0%	100%
	BURNETT ¹⁹						
	CHIPPEWA	24%	0%	9%	29%	0%	99%
	CLARK	25%	0%	6%	27%	20%	92%
	DOUGLAS	27%	0%	37%	39%	49%	75%
	DUNN	38%	0%	14%	22%	0%	97%
N TXX 7	EAU CLAIRE	21%	0%	19%	24%	2%	97%
NW	JACKSON	20%	0%	20%	20%	67%	33%
	PEPIN	0%	0%	0%	0%	0%	100%
	PIERCE	74%	0%	9%	74%	0%	100%
	POLK	60%	0%	60%	70%	0%	100%
	RUSK ¹⁹						
	SAWYER	25%	0%	88%	25%	13%	100%
	ST. CROIX	16%	0%	4%	12%	4%	82%
	TAYLOR	0%	0%	0%	0%	0%	0%
	TREMPEALEAU	50%	0%	13%	63%	0%	100%
	WASHBURN	23%	0%	53%	38%	13%	89%
	COLUMBIA	21%	0%	16%	28%	36%	56%
	CRAWFORD	50%	0%	50%	83%	0%	100%
	DANE	25%	0%	19%	44%	7%	79%
	DODGE	25%	0%	7%	42%	6%	87%
	GRANT	12%	0%	6%	19%	0%	56%
	GREEN	39%	0%	14%	32%	4%	93%
	IOWA	15%	0%	38%	38%	0%	85%
SW	JEFFERSON	17%	0%	6%	37%	2%	65%
5 VV	JUNEAU	64%	0%	56%	65%	7%	93%
	LA CROSSE	42%	0%	34%	46%	1%	95%
	LAFAYETTE	10%	0%	3%	7%	3%	53%
	MONROE	22%	0%	13%	26%	39%	57%
	RICHLAND	25%	0%	38%	38%	0%	100%
	ROCK	15%	0%	9%	29%	0%	85%
	SAUK	38%	0%	50%	36%	7%	100%
	VERNON	33%	0%	0%	33%	0%	100%

¹⁹ There are no concrete traveled ways in Burnett and Rusk counties

2007 Winter: Compass Report on Winter Maintenance

Executive summary

	2003-04	2004-05	2005-06	2006-07
Average time to bare/wet pavement after a storm ends	2 hours 38 minutes	2 hours 4 minutes	1 hour 55 minutes	1 hour 28 minutes
Cost per lane mile	\$1,279	\$1,374	\$1,386	\$1,549
Winter severity index	31.2	31.9	31.8	28.4
Winter related crashes per 100 million vehicle miles traveled	26	25	24	23

Statewide measures for winter

Key findings

- In keeping with WisDOT guidelines, during similar storm events, drivers on major urban freeways and highways have less time to wait until they see bare/wet pavement than do drivers on secondary roads. From storm to storm, however, most of the variability in this time is due to weather effects (type, duration and severity of storms throughout the winter season).
- The average time to bare/wet pavement during winter 2006-07 was 1 hour and 28 minutes which is twenty seven minutes less than the previous winter. The average Winter Severity Index (WSI) in 2006-07 was 28.4 versus 31.8 in the previous year.

About this report

The measures in this section of the report focus on key winter operations outcomes critical to drivers and citizens. The primary audience for these measures is expected to be WisDOT and county highway managers with a general interest in winter maintenance, e.g., region directors and county commissioners. This section of the report looks at winter operations on state highways from November 1, 2006 to April 30, 2007.

The Bureau of Highway Operations issues two reports on winter. This Compass report on winter focuses on measures critical to drivers and citizens, and is directed toward a general audience. The Annual Winter Maintenance Report focuses on operational measures and analysis, and is directed toward front-line operations managers.

Unless otherwise noted, all material and labor figures come from the winter storm reports that are submitted by each county for every event or anti-icing procedure throughout the winter season. The data quality is unknown. Weather, road conditions, and materials usages are based upon the observations of county patrol superintendents and sometimes on their expert judgment and, as such, contain more variability than direct measurements.

Actual cost data incorporates all winter activities, including putting up snow fence, transporting salt, filling salt sheds, thawing out frozen culverts, calibrating salt spreaders, producing and storing salt brine, and anti-icing applications, as well as plowing and salting. Costs from storm reports, however, cover only plowing, sanding, salting, and anti-icing.

Several categories and groupings are used to present the winter maintenance measures.

Winter service group

Winter Service Group	County Name
А	Brown, Dane, Eau Claire, Kenosha, La Crosse, Marathon, Milwaukee, Ozaukee, Portage, Racine, Waukesha, Winnebago
В	Chippewa, Columbia, Dodge, Dunn, Jefferson, Manitowoc, Marquette, Oneida, Outagamie, Rock, Sauk, Shawano, Sheboygan, St. Croix, Walworth, Washington, Waushara
С	Calumet, Clark, Crawford, Door, Douglas, Fond du Lac, Grant, Iowa, Jackson, Juneau, Kewaunee, Lafayette, Lincoln, Monroe, Oconto, Trempealeau, Vernon, Vilas, Washburn, Waupaca, Wood
D	Adams, Ashland, Barron, Bayfield, Buffalo, Burnett, Florence, Forest, Green, Green Lake, Iron, Langlade, Marinette, Menominee, Pepin, Pierce, Polk, Price, Richland, Rusk, Sawyer, Taylor

Passable roadway expectation categories

Category	Definition	Lane miles	% of total
	Major urban freeways and most highways with six lanes and		
1	greater	2,839	8%
	High volume four-lane highways (Average Daily Traffic >		
	25,000) and some four-lane highways (ADT < 25,000), and some		
2	6-lane highways.	3,191	10%
3	All other four-lane highways (ADT < 25,000)	8,206	25%
	Most high volume two-lane highways (ADT $>$ 5,000) and some 2-		
4	lanes (ADT <5000)	4,895	15%
5	All other two-lane highways	14,090	42%


Winter service availability and coverage groups

Group	Definition	Number of Counties	% of Counties
А	Counties where all or most of the highways receive 24-hour coverage	12	17%
В	Counties with 18-hour and 24-hour coverage. More than 50% of highways receive 24-hour coverage.	17	24%
С	Counties with 18-hour and 24-hour coverage. Less than 50% of highways receive 24-hour coverage.	21	29%
D	Counties where no highways receive 24-hour coverage.	22	31%

2006-2007 winter season snowfall for Wisconsin

Note: The below map is in color. If you are not viewing a color copy, please contact the Compass Program Manager at the Bureau of Highway Operations for a color version to be mailed or emailed to you.


The National Weather Service (NWS) map below shows the snowfall for Wisconsin during the period July 1, 2006 to June 30, 2007. Comparison of the 2006-07 snowfall map to the average snowfall map (also from NWS) indicates that the northern regions had more snowfall than average and the southern regions had less.



2006-2007 Winter Severity Index by County

Note: The below map is in color. If you are not viewing a color copy, please contact the Compass Program Manager at the Bureau of Highway Operations for a color version to be mailed or emailed to you.

Wisconsin's Winter Severity Index (WSI) is highly correlated with snowfall. Looking at the statewide winter severity numbers, the statewide average for winter 2006-2007 was 28.4 which is slightly lower than the previous ten-year average of 30.7



Winter by the numbers

		2004-05	2005-06	2006-07
	Lane miles	31,810 miles	33,022 miles	33,221 miles
Infrastructure	Road Weather			
mirastructure	Information System	59	59	58
	(RWIS) stations			
		407,924 tons	426,723 tons	405,793 tons
		12.8 tons per	12.9 tons per	12.2 tons per
	Salt	lane mile	lane mile	lane mile
Material	Average cost of salt	\$31.42 per ton	\$35.25 per ton	\$39.04 per ton
usage ⁴	Pre-wetting liquid			
usage	used	638,685 gal.	803,131 gal.	745,919 gal.
	Anti-icing agent	272,856 gal.	435,277 gal.	485, 485 gal.
	Sand	15,843 cubic	15,997 cubic	13,636 cubic
		yd.	yd.	yd.
	Regular county hours			
	on winter ²⁰	110,390 hrs.	110,354 hrs.	112,087 hrs.
	Overtime county hours			
	on winter	123,300 hrs.	112,522 hrs.	120,603 hrs.
Services		6,382 total	6,989 total	5,545 total
	Public service	5,735 radio;	6,353 radio;	4,966 radio;
	announcements aired	647 TV	636 TV	579 TV
	Cost of public service			
	announcements	\$31,500	\$31,500	\$35,000
	Patrol sections	719	733	768
	Average patrol section			
	length	44.24 miles	45.05 miles	43.00 miles
	Salt spreaders			
	equipped with on-			
Management	board pre-wetting	639 of 2647	639 of 2647	658 of 2586
and	unit ²¹	(24%)	(24%)	(25%)
Technology	Counties with salt			
recimology	spreaders equipped			
	with on-board pre-			
	wetting unit	59 of 72 (82%)	59 of 72 (82%)	56 of 72 (78%)
	Salt spreaders			
	equipped with ground-	1316 of 2647	1316 of 2647	1332of 2586
	speed controller unit	(50%)	(50%)	(52%)

²⁰ Costs and hours come from county storm reports, and reflect sanding, salting, plowing and anti-icing efforts. ²¹ County equipment may be used on either state or county roads.

⁴ All material usage quantities are from the county storm reports except for salt. The salt quantities are from the Salt Inventory Reporting System.

	2004-05	2005-06	2006-07
Counties with salt			
spreaders equipped			
with ground-speed			
controller unit	69 of 72 (96%)	69 of 72 (96%)	65 of 72 (90%)
Underbody plows	508	508	507
Counties with			
underbody plows	51 of 72 (71%)	51 of 72 (71%)	51 of 72 (71%)
Counties equipped to			
use anti-icing agents	65 of 72 (90%)	65 of 72 (90%)	65 of 72 (90%)
Counties that used			
anti-icing agents			
during 2004-05 winter			
season	56 of 72 (78%)	50 of 72 (69%)	56 of 72 (78%)

Compass winter maintenance measures

Time to bare/wet pavement

The counties, under contract to WisDOT, provide different levels of effort during and after a storm depending on how busy and how critical a given category of highway is. State highways fall into five such categories, with category 1 being the highest priority. It would be expected that an urban freeway (category 1) would receive more materials, labor and equipment – and would show a quicker time to bare/wet pavement – than would a rural two-lane highway (category 5). For more information on these categories, see page 49.

The table below shows that the trend for average time to bare/wet pavement is as expected: The more critical the highway, the shorter the average time to bare/wet pavement. Time to bare/wet pavement is measured from the reported end time of a storm. 'Bare/wet never achieved' means that it took more than 24 hours to achieve bare/wet condition, or the next storm began before bare/wet condition was achieved. Less critical highways are more likely to have snow on them 24 hours after a storm has ended than are more critical highways. This suggests that major urban freeways and highways are receiving a higher level of effort for winter operations than secondary roads.

Further analysis suggests that variability, within a category, is due more to weather effects (type, duration and severity of storms throughout the winter season) than to differences in the level of effort or relative resources.

		Avera	age time to b	are/wet pav	ement		2006 - 07 St	torms
		(1	nours after e	nd of storm)*			%
Highway catego	Highway category More critical	2003 - 04 Average	2004 - 05 Average	2005 - 06 Average	2006 - 07 Average	Total	Bare/wet never achieved	Bare/wet never achieved
More critical	1	1.07	0.45	-1.21	-2.50	160	9	5.6
highways	2	1.31	0.64	0.2	-0.55	307	27	8.8
\checkmark	3	1.52	1.82	1.32	1.57	413	19	4.6
Less critical	4	2.45	3.06	2.47	2.70	450	62	13.8
highways	5	3.63	2.89	3.4	2.73	603	106	17.6

* Only includes storms where bare/wet pavement was achieved

Winter maintenance costs

As severity of the winter increases, so does the cost per lane mile. The statewide average cost per lane mile was \$1,549 with average severity index of 28.42. Regions that incurred higher cost per lane mile had more severe weather than the statewide average, with the exception of SE region. The following table lists the total actual cost per lane mile for winter operations in each region, along with region winter severity index. The costs were obtained from the WisDOT's FOS (Financial Operating System). Total costs include material, labor, equipment, and administrative costs.

Region		Avera	ge WSI		A	Actual cos	st (\$/LM))		-	per WSI LM / W	-
Region	2003- 04	2004- 05	2005- 06	2006- 07	2003- 04	2004- 05	2005- 06	2006- 07	2003- 04	2004- 05	2005- 06	2006- 07
NC	38.21	36.04	40.16	32.41	\$1,500	\$1,481	\$1,612	1,509	\$39	\$41	\$40	46.56
NE	30.26	31.04	32.48	26.67	\$1,394	\$1,389	\$1,396	1,492	\$46	\$45	\$43	55.94
NW	36.69	34.43	32.61	28.69	\$1,264	\$1,244	\$1,309	1,288	\$34	\$36	\$40	44.89
SE	20.45	25.29	20.32	24.19	\$1,734	\$1,733	\$1,431	2,138	\$85	\$69	\$70	88.38
SW	21.78	27.89	25.93	26.66	\$1,224	\$1,201	\$1,199	1,467	\$56	\$43	\$46	55.03
Statewide	31.20	31.91	31.80	28.42	\$1,391	\$1,374	\$1,386	1,549	\$45	\$43	\$44	54.50

Winter weather crashes per vehicle miles traveled (VMT)

The following table shows that counties with higher winter coverage tend to have fewer crashes per 100 million VMT. (Group A has higher coverage than Group B, etc.). For more information on county groupings A-D, see page 56 at the end of this section. Winter weather crashes are those crashes that occurred on snow-, slush-, or ice-covered pavements.


	Winter	VMT*		Crash	es per 10	0 million	VMT	Averag	ge Winter	· Severity	v Index
	Service Group	(100 million)	Crashes	2003 - 04	2004 - 05	2005 - 06	2006 - 07	2003 - 04	2004 - 05	2005 - 06	2006 - 07
Counties with more	А	13.74	2807	21	21	20	20	26.02	28.95	26.43	25.82
coverage	В	7.34	1820	29	26	25	25	25.32	27.16	27.39	24.17
Counties	С	4.55	1278	35	32	32	28	31.2	32.21	33.23	29.85
with less coverage	D	2.28	497	34	28	27	22	37.98	36.71	36.77	31.76

*100 million vehicle miles traveled (VMT) for November 1, 2006 though April 30, 2007 determined from annual average daily traffic (AADT) counts, gallons of gas sold, fuel tax collected, and average vehicle miles per gallon.

The following table shows the crashes per 100 million VMT statewide and in each Region. The state average is 23 winter crashes per 100 million VMT.

	VMT		Cras	hes per 10() million	VMT	Averag	e Winter	Severity	Index
Scope	(100 million)	Crashes	2003 - 04	2004 - 05	2005 - 06	2006 - 07	2003 - 04	2004 - 05	2005 - 06	2006 - 07
Statewide	279.11	6402	26	25	24	23	31.20	31.91	31.80	28.42
NC	34.11	866	34	31	31	25	38.21	36.04	40.16	32.41
NE	50.39	1061	26	25	24	21	30.26	31.04	32.48	26.67
NW	38.99	790	37	31	28	20	36.69	34.43	32.61	28.69
SE	85.61	1818	21	17	17	21	20.45	25.29	20.32	24.19
SW	70.01	1867	29	26	27	27	21.78	27.89	25.93	26.66

The following figure shows us that, as severity of the winter increases, so does the winter crash rate. As expected, the number of winter crashes increases as VMT increases. Regions with more rural roads tend to have higher winter crash rates (crashes per VMT) which are consistent with trends for non-winter crash rates.



2007 Highway Maintenance Conditions: Compass Report on Traffic, Shoulders, Drainage, Roadsides

Data in this section comes from the field review performed by WisDOT region Area Maintenance Coordinators and county Patrol Superintendents. Reporting was done by WisDOT staff. No statistical analysis has been done on this data at the county level. Readers should take the number of observations into account when reviewing the information. Extreme caution should be exercised when analyzing data that has less than 30 observations.

Traffic:

• Delineators received a feature grade of C for the second straight year.

Shoulders:

- Unpaved shoulders drop-off /buildup received a feature grade of F for the fourth consecutive year. Unpaved drop-off is the worst in the SE regions, but has increased in the NE and NW regions. Repair of shoulder drop-off contributes to safety by keeping cars from dropping down dramatically on one side and possibly over-correcting if one or two wheels leave the pavement.
- Hazardous debris received a feature grade of C, an improvement over the previous three years. Hazardous debris is significantly worse in the NE and SW regions than in other regions. Keeping hazardous debris off the shoulders prevents it from being somehow moved back into live traffic, and protects drivers of cars that may swerve or pull over onto the shoulder.
- Cracking on paved shoulders received a feature grade of D for the fourth year in a row. However, this score is better than targeted. Cracking on paved shoulders is worse in the SE and NE regions.
- Unpaved cross-slope regained a feature grade of B after falling to a C in 2006.

Roadsides and drainage:

- Flumes and culverts received a feature grade of C; all other drainage features received grades of A or B.
- Noxious weeds once again received a feature grade of C with a maintenance backlog much lower than targeted. Noxious weeds appear to be a statewide problem. There is a current policy to not spray Noxious Weeds due to budget limitations.

Counties 2007: Traffic and Shoulders

							C	Condition						
								backlogge						
							# of	observatio	ons					
					Traffic		· · · · · · ·				Shou	lders	1	
Region	County	Centerline	Delineators	Edgeline Markings	Other Signs (emergency)	Protective Barriers	Reg./Warn. Signs (emergencv)	Special Pavement Markings	Hazardous Debris	Cracking (paved)	Potholes (paved)	Cross Slope (unpaved)	Drop-off (unpaved)	Erosion (unpaved)
		0%		0%	0%		0%	0%	0%	27%	9%	9%	18%	0%
	ADAMS	11		11	3		3	2	11	11	11	11	11	11
		0%		0%	0%		0%		0%	60%	0%	0%	20%	0%
	FLORENCE	5		5	1		1		5	5	5	5	5	5
	FOREST	0% 11		0% 9	0% 4		0% 5		0% 11	43% 7	0% 7	44% 9	22% 9	11% 9
		0%		0%	0%		0%		0%	20%	0%	0%	60%	0%
	GREEN LAKE	5		5	3		2		5	5	5	5	5	5
		5%		42%	0%		0%		11%	29%	0%	26%	11%	0%
	IRON	19		19	4		5		19	7	7	19	19	19
		0%		0%	0%		0%	0%	0%	29%	0%	5%	25%	0%
NC	LANGLADE	20		20	5		7	2	20	14	14	20	20	20
		0%	13%	0%	0%	9%	0%		13%	71%	21%	36%	36%	0%
	LINCOLN	15	5	15	4	1	4		15	14	14	14	14	14
		0%	3%	0%	0%	0%	0%	60%	5%	71%	18%	20%	55%	0%
	MARATHON	21	8	21	8	1	7	5	21	17	17	20	20	20
		0%	0%	0%	0%	0%	0%		0%	50%	0%	0%	20%	0%
	MARQUETTE	10	1	10	3	1	2		10	10	10	10	10	10
		0%		67%	0%	0%	0%	0%	0%	0%	0%	0%	67%	0%
	MENOMINEE	4		3	4	1	1	1	4	1	1	3	3	3
		0%	43%	0%	0%	0%	0%	0%	0%	50%	0%	5%	18%	0%
	ONEIDA	23	2	23	9	1	11	1	23	22	22	22	22	22
		0%	0%	0%	0%		0%	0%	21%	67%	0%	14%	14%	0%
	PORTAGE	14	5	14	6		6	2	14	12	12	14	14	14

								condition						
								observatio						
					Traffic						Shou	Iders		
Region	County	Centerline	Delineators	Edgeline Markings	Other Signs (emergency)	Protective Barriers	Reg./Warn. Signs (emergencv)	Special Pavement Markings	Hazardous Debris	Cracking (paved)	Potholes (paved)	Cross Slope (unpaved)	Drop-off (unpaved)	Erosion (unpaved)
	55105	0%	7%	0%	0%		0%	100%	6%	36%	9%	19%	38%	0%
	PRICE	16	1	16	6		7	1	16	11	11	16	16	16
		0% 18	<u>5%</u> 8	0% 17	0% 8	<u>0%</u> 1	0% 5	17% 2	<u>22%</u> 18	81% 16	0% 16	59% 17	47% 17	0% 17
	SHAWANO	0%	8	8%	8 0%		5 0%	 0%	23%	67%	0%	23%	23%	0%
	VILAS	13		13	5		6	0%	13	9	9	13	13	13
	VILAS	0%	0%	21%	0%		0%	100%	14%	13%	0%	21%	50%	7%
	WAUPACA	14	3	14	2		7	100 /8	14 /0	8	8	14	14	14
		0%	0%	0%	0%	0%	0%	0%	0%	0%	0%	9%	18%	0%
	WAUSHARA	11	3	11	2	1	4	1	11	9	9	11	11	11
		10%		10%	0%		0%	0%	0%	0%	0%	13%	38%	0%
	WOOD	10		10	4		6	3	10	4	4	8	8	8
		4%	5%	4%	0%	17%	0%	0%	8%	76%	4%	13%	75%	4%
	BROWN	25	17	25	9	6	11	4	25	25	25	24	24	24
		0%		0%	0%		0%	0%	22%	56%	11%	0%	25%	0%
	CALUMET	9		9	6		5	3	9	9	9	8	8	8
		0%	33%	0%	0%		3%	0%	5%	58%	5%	21%	68%	0%
	DOOR	20	1	20	9		12	2	20	19	19	19	19	19
		3%	13%	0%	0%	2%	0%	0%	3%	83%	7%	31%	55%	0%
NE	FOND DU LAC	30	7	29	7	3	13	5	30	29	29	29	29	29
		0%	50%	0%	0%	3%	0%	0%	0%	56%	0%	56%	56%	0%
	KEWAUNEE	9	2	9	3	2	5	1	9	9	9	9	9	9
		0%	0%	0%	0%	0%	0%	0%	0%	92%	23%			
	MANITOWOC	13	2	13	5	2	6	1	13	13	13			
		3%	14%	0%	0%	100%	0%		3%	68%	4%	13%	29%	3%
	MARINETTE	31	4	31	11	1	11		31	28	28	31	31	31
		0%	4%	0%	0%	0%	0%	0%	0%	44%	0%	0%	19%	0%
		27	6	27	11	2	10	70/	27	25	25	27	27	27
	OUTAGAMIE	0%	22%	0%	0%	0%	2%	7%	25%	35%	5%	13%	35%	0%

								Condition						
							# of	observatio	ons					
					Traffic						Shou	lders	_	
Region	County	Centerline	Delineators	Edgeline Markings	Other Signs (emergency)	Protective Barriers	Reg./Warn. Signs (emergencv)		Hazardous Debris	Cracking (paved)	Potholes (paved)	Cross Slope (unpaved)	Drop-off (unpaved)	Erosion (unpaved)
		24	3	24	12	3	15	6	24	20	20	23	23	23
		4%	18%	4%	0%	1%	0%	0%	19%	38%	4%	20%	44%	0%
-	SHEBOYGAN	26	6	25	11	3	14	5	26	26	26	25	25	25
		0%	0%	0%	0%	0%	4%	6%	5%	18%	0%	0%	100%	0%
	WINNEBAGO	22	5	21	10	1	8	4	22	22	22	3	3	3
		30%		20%	0%		0%	100%	0%	33%	11%	20%	40%	0%
-	ASHLAND	10		10	2		5	1	10	9	9	10	10	10
	BARRON	17% 6	0%	0%	0% 3		0% 2	100%	<u>17%</u> 6	67%	0%	33% 6	83% 6	0% 6
-	BARRON	6 0%	2	6 10%			20%		0%	6 50%	6 17%	30%	40%	6 0%
	BAYFIELD	10		10%	1		7		10	6	6	10	10	10
-	DATFIELD	9%	43%	36%	0%	0%	0%		0%	71%	29%	82%	73%	0%
	BUFFALO	11	2	11	4	2	3		11	7	7	11	11	11
-	BOITALO	0%		0%			0%		0%	25%	0%	0%	100%	0%
	BURNETT	6		6			2		6	4	4	6	6	6
NW	DOTATETT	4%	7%	4%	0%	0%	0%	4%	0%	14%	0%	0%	43%	0%
	CHIPPEWA	23	7	23	5	3	6	6	23	21	21	23	23	23
		0%	0%	0%	0%		0%		0%	38%	0%	0%	54%	0%
	CLARK	13	3	13	2		5		13	13	13	13	13	13
-		0%	0%	0%	0%		0%		0%	50%	0%	0%	44%	22%
	DOUGLAS	9	4	9	4		3		9	8	8	9	9	9
		0%	29%	0%	0%	3%	0%		7%	57%	14%	27%	20%	20%
	DUNN	15	6	15	3	6	3		15	14	14	15	15	15
		0%	8%	0%	0%	8%	0%	10%	21%	85%	8%	0%	17%	8%
	EAU CLAIRE	14	5	13	7	4	11	5	14	13	13	12	12	12
		8%	57%	8%	0%	0%	0%	0%	0%	50%	10%	23%	15%	0%
	JACKSON	13	4	13	1	2	4	1	13	10	10	13	13	13
	DED	0%	80%	0%		0%	0%		0%	80%	0%	60%	60%	20%
	PEPIN	5	3	5		3	2		5	5	5	5	5	5

								condition						
								observati						
					Traffic						Shou	lders		
Region	County	Centerline	Delineators	Edgeline Markings	Other Signs (emergency)	Protective Barriers	Reg./Warn. Signs (emergencv)	Special Pavement Markings	Hazardous Debris	Cracking (paved)	Potholes (paved)	Cross Slope (unpaved)	Drop-off (unpaved)	Erosion (unpaved)
		0%	20%	0%	0%	0%	0%	0%	14%	80%	0%	0%	43%	0%
	PIERCE	7	1	7	4	1	5	1	7	5	5	7	7	7
		5%	0%	0%	0%		0%	0%	9%	33%	10%	50%	68%	0%
	POLK	22	1	22	9		13	3	22	21	21	22	22	22
		0%	0%	0%	0%		8%	100%	0%	11%	11%	56%	56%	0%
	RUSK	9	1	9	1		6	2	9	9	9	9	9	9
		6%		0%	0%		0%		0%	7%	0%	6%	29%	0%
	SAWYER	17		17	6		4		17	14	14	17	17	17
		5%	16%	5%	0%	0%	0%		11%	68%	5%	26%	37%	5%
	ST. CROIX	19	7	19	6	2	4		19	19	19	19	19	19
	TN/ 00	0%	0%	0%	0%		0%		0%	44%	0%	0%	0%	0%
	TAYLOR	9	1	9	1		3		9	9	9	9	9	9
	TREMPEALEAU	18% 11		27%	0%		9% 6		0% 11	56%	0%	73% 11	82% 11	0% 11
	TREIMPEALEAU	0%	 0%	11 9%	3 0%		0%		9%	9 27%	9 9%	18%	91%	0%
	WASHBURN	11	0% 1	9% 11	3		4		<u>9%</u> 11	11	9% 11	10%	11	11
	WASHDURN	3%	6%	3%		0%	4	0%	7%	24%	8%	22%	70%	0%
	KENOSHA	29	11	29	15	4	21	13	29	24 %	25	22 /0	23	23
	RENOONA	5%	0%	19%	0%	3%	5%	15%	 5%	64%	18%	50%	67%	17%
	MILWAUKEE	39	6	27	35	15	31	22	39	22	22	12	12	12
		0%	16%	0%	0%	7%	0%	0%	0%	63%	0%	6%	44%	0%
	OZAUKEE	19	8	19	8	5	8	7	19	16	16	16	16	16
SE		0%	13%	3%	0%	0%	2%	8%	0%	54%	18%	40%	48%	0%
	RACINE	31	6	31	10	2	21	10	31	28	28	25	25	25
		5%	24%	5%	2%	18%	0%	0%	5%	71%	13%	0%	11%	0%
	WALWORTH	38	10	38	19	3	15	3	38	38	38	38	38	38
		3%	17%	0%	0%	0%	0%	0%	3%	87%	3%	6%	19%	0%
	WASHINGTON	32	11	32	12	5	13	8	32	31	31	32	32	32
	WAUKESHA	4%	0%	4%	0%	0%	1%	0%	10%	65%	13%	3%	49%	3%

							%	Condition backlogge observation	ed					
·					Traffic						Shou	lders		
Region	County	Centerline	Delineators	Edgeline Markings	Other Signs (emergency)	Protective Barriers	Reg./Warn. Signs (emergencv)	L L L	Hazardous Debris	Cracking (paved)	Potholes (paved)	Cross Slope (unpaved)	Drop-off (unpaved)	Erosion (unpaved)
		51	12	51	31	9	30	18	51	40	40	37	37	37
		0%	50%	0%	0%	0%	0%		50%	73%	0%	69%	81%	0%
	COLUMBIA	16	2	16 11%	7	1 0%	2 0%		<u>16</u> 0%	11 0%	11 0%	16	16 0%	16 0%
	CRAWFORD	0% 9	25% 2	9	0% 2	<u>0%</u> 3	0% 7	0% 2	9	0% 8	0% 8	13% 8	0% 8	8
	CRAWFURD	9 7%	29%	9 7%	 0%		0%	 10%	<u> </u>	。 74%	0 13%	0 4%	。 54%	0%
	DANE	28	3	27	12	5	13	5	28	23	23	28	28	28
•	DANL	0%	21%	0%	0%		0%	0%	38%	69%	15%	15%	62%	0%
	DODGE	13	4	13	7		6	3	13	13	13	13	13	13
	DODOL	0%	0%	0%	0%	77%	0%		0%	25%	0%	11%	22%	0%
SW	GRANT	9	1	9	1	1	3		9	8	8	9	9	9
		0%	0%	11%	0%		0%		0%	40%	0%	0%	0%	0%
	GREEN	9	1	9	3		3		9	5	5	9	9	9
		0%	5%	0%	0%	0%	0%	0%	0%	73%	0%	0%	42%	0%
	IOWA	12	4	12	6	1	4	1	12	11	11	12	12	12
		0%		5%	10%	0%	0%	0%	16%	50%	0%	32%	11%	5%
	JEFFERSON	19		19	8	1	9	3	19	18	18	19	19	19
		6%	0%	6%	0%			0%	13%	54%	0%	0%	25%	0%
	JUNEAU	16	3	16	5			1	16	13	13	16	16	16
		0%	38%	0%	0%	5%	0%	100%	33%	63%	0%	11%	67%	0%
	LA CROSSE	9	5	9	4	3	5	1	9	8	8	9	9	9
		9%	38%	9%	0%	0%	0%		0%	11%	0%	0%	0%	0%
	LAFAYETTE	11 7%	3 2%	11 7%	2 0%	3 0%	5 0%	 0%	11 30%	9 70%	9 0%	11 0%	11 22%	11 0%
	MONROE	27	2% 11	27	9	3	3	0%	<u> </u>	10%	10%	27	22%	27
	WONTOL	0%	0%	7%	9 0%	0%	10%	0%	0%	29%	0%	7%	0%	0%
	RICHLAND	14	4	14	6	4	7	1	15	14	14	14	14	14
		0%	0%	0%	0%	0%	0%	0%	0%	82%	9%	0%	8%	0%
	ROCK	13	3	13	4	1	4	1	13	11	11	13	13	13

					Traffic		%	Condition backlogge observation	ed		Shou	Idoro		
	I		Traffic Shoulders											
Region	County	Centerline	Centerline Centerline Edgeline Markings Other Signs (emergency) Protective Barriers Barriers Reg./Warn. Signs (emergency) Special Pavement Markings Cracking (paved) Potholes (paved) Cross Slope (unpaved) Drop-off (unpaved)											Erosion (unpaved)
		0%	44%	0%	0%	100%	0%	0%	44%	56%	0%	64%	71%	0%
	SAUK	16												
		6%												
	VERNON	18		17	6		8		18	9	9	16	16	16

Counties 2007: Drainage and Roadsides

							#	Conc % back of obse	logged	S					
			-	Drai	nage				-	-	Road	sides	-		
Region	County	Culverts	Curb & Gutter	Ditches	Drains	Flumes	Storm Sewer	Barriers	Fences	Litter	Mowing	Mowing for Vision	Noxious Weeds	Woody Vegetation Control	Woody Vegetation Control for Vision
	10110	0%	5%	0%		0%				27%	0%	0%	0%	9%	0%
	ADAMS	4	2	10		2				11	11	2	11	11	11
		0%		0%						0%	0%		40%	0%	0%
	FLORENCE	2 50%	 42%	5 0%			 11%			5 27%	5 27%	 0%	5 36%	5 9%	5 0%
	FOREST	4	42%	8			2			11	11	1	11	9%	11
		0%	3%	0%		0%				40%	40%	0%	20%	0%	0%
	GREEN LAKE	1	1	5		1				5	5	1	5	5	5
		18%		1%	0%					21%	11%	10%	11%	26%	5%
	IRON	10		19	1					19	19	10	19	19	19
NC		0%	0%	0%		0%				30%	5%	0%	35%	0%	5%
	LANGLADE	5	1	20		1				20	20	6	20	20	20
		0%		2%	5%		0%		5%	80%	53%	0%	53%	7%	0%
	LINCOLN	6		15	5		1		4	15	15	3	15	15	15
		11%	1%	0%	3%	0%	0%		2%	71%	48%	0%	29%	0%	5%
	MARATHON	5	3	20	9	1	2		4	21	21	8	21	21	21
		0%	0%	0%		0%			0%	30%	40%	0%	0%	0%	0%
	MARQUETTE	1	1	10		1			1	10	10	1	10	10	10
			3%	0%		0%	0%			100%	25%	0%	0%	50%	0%
	MENOMINEE		1	3		1	1			4	4	1	4	4	4
		0%	11%	0%						57%	13%	11%	13%	9%	13%
	ONEIDA	4	1	22						23	23	9	23	23	23
		38%	1%	1%	0%		100%		0%	57%	14%	0%	50%	0%	0%
	PORTAGE	8	1	14	1		2		5	14	14	2	14	14	14

Region Cour PRIC SHAWA VILA	Inty 17%	b & Gutter	Drai	nage		#	% back f of obse		S	Road	sides			
PRIC SHAW		∞ŏ	Drai	nage		<u>*</u>			>	Road	sides			
PRIC SHAW		∞ŏ												
PRIC SHAW		∞ŏ				/er					r Vision	eeds	Vegetation	getation Vision
SHAW	17%	Curb	Ditches	Drains	Flumes	Storm Sewer	Barriers	Fences	Litter	Mowing	Mowing for	Noxious Weeds	Woody Control	Woody Vegetation Control for Vision
SHAW			1%		50%			13%	63%	44%	0%	6%	38%	0%
VILA	-	2	16		1			1	16	16	13	16	16	16
VILA	10%		0%	11%	17%	0%			44%	22%	0%	0%	6%	0%
		3	17	8	2	3			18	18	1	18	18	18
	0%	18%	5%						77%	23%	0%	8%	8%	0%
		2	13						13	13	10	13	13	13
	33%		0%	0%	0%				57%	14%	0%	0%	0%	0%
WAUP		1	13	2	1				14	14	1	14	14	14
	0%	0%	0%			0%		0%	36%	0%	0%	9%	0%	0%
WAUSH		1	11			1		1	11	11	1	11	11	11
	20%		0%	0%		6%			50%	50%	0%	20%	0%	0%
WOO	-	3	8	1		3			10	10	3	10	10	10
	0%	6%	0%	0%	0%	0%	0%	0%	80%	16%	0%	60%	0%	4%
BROV		1	25	9	2	4	2	12	25	25	2	25	25	25
CALLI	67%		3%	0%	0%	40%			100%	56%	0%	56%	11%	0%
CALU	IMET 4 33%	4	9 2%		2 100%	2 11%		 0%	9 70%	9 50%	8 0%	9 20%	9 0%	9 0%
DOC		3	18		100%	4		0%	20	20	0% 4	20%	20	20
NE DOC	<u>30%</u>	-	18	 9%	10%	13%		0%		20 80%	4	77%	20 7%	20 3%
FOND D		4	29	9%	10%	4		0% 5	30	30%	0% 5	30	30	3%
	0%	0%	1%	9	2 0%	4			78%	30 56%		89%	0%	30 11%
KEWAL		2	9		2				9	9	3	9	9	9
INE VAL	25%		0%			0%		0%	9 77%	9 31%	0%	9 15%	9 0%	9 0%
ΜΔΝΙΤΟ	ZO //	1	13			1		2	13	13	11	13 //	13	13
		•	2%			-								
MARIN	OWOC 6				1	0%	0%	0%	45%	48%	0%	3%	0%	0%
OCON	OWOC 6 30%		31			0%	0% 1	0% 3	45% 31	48% 31	0% 14	3% 31	0% 31	0% 31

									dition dogged						
							#	f of obse		S					
				Drai	nage						Road	sides			
Region	County	Culverts	Curb & Gutter	Ditches	Drains	Flumes	Storm Sewer	Barriers	Fences	Litter	Mowing	Mowing for Vision	Noxious Weeds	Woody Vegetation Control	Woody Vegetation Control for Vision
		16	4	26	2	2	4		5	27	27	14	27	27	27
		20%	0%	5%	50%	40%	8%		0%	63%	54%	0%	21%	4%	0%
	OUTAGAMIE	5 0%	6 4%	23 1%	2 0%	3 20%	5 0%		2 0%	24 58%	24 77%	13 0%	24 88%	24 0%	24 0%
	SHEBOYGAN	5	4%	25	3	20%	6		3	26	26	4	26	26	26
	SHEDOTGAN	0%	0%	0%	36%		0%		0%	73%	41%	0%	5%	0%	0%
	WINNEBAGO	6	3	21	2		2		2	22	22	14	22	22	22
		0%		1%						30%	10%	0%	0%	10%	0%
	ASHLAND	1		7						10	10	1	10	10	10
		67%		0%			0%		0%	67%	50%	0%	0%	0%	17%
	BARRON	2		6			1		2	6	6	1	6	6	6
		50%		5%	100%					60%	30%	0%	0%	0%	0%
	BAYFIELD	4		9	1					10	10	4	10	10	10
		18%		1%						55%	64%	0%	9%	0%	0%
N 13 A /	BUFFALO	8		11						11	11	3	11	11	11
NW	BURNETT		17% 1	<u>0%</u> 6		0%				67% 6	67% 6	0%	0% 6	0% 6	0% 6
	DURINETT	20%	6%	0%	40%	75%			 0%	70%	57%		0%	0%	0%
	CHIPPEWA	9	4	23	40 %	3			4	23	23		23	23	23
		0%	17%	0%	- 	0%	0%			69%	46%		0%	0%	0%
	CLARK	2	3	13	3	1	1			13	13		13	13	13
		0%		1%						78%	22%	0%	0%	0%	0%
	DOUGLAS	2		9						9	9	2	9	9	9
		13%		0%		0%			22%	53%	13%		20%	0%	0%
	DUNN	6		14		1			2	15	15		15	15	15
		70%	2%	0%	0%	100%	10%	2%	0%	93%	7%		21%	21%	0%
	EAU CLAIRE	7	6	12	2	2	2	2	4	14	14		14	14	14

									dition						
								% back of obset	logged	-					
				Drai	nage		Ŧ	F OT ODSE	ervation	5	Poad	sides			
				Dial	naye				1		Ruau	1		_	_
Region	County	Culverts	Curb & Gutter	Ditches	Drains	Flumes	Storm Sewer	Barriers	Fences	Litter	Mowing	Mowing for Vision	Noxious Weeds	Woody Vegetation Control	Woody Vegetation Control for Vision
		0%		0%	0%				29%	54%	0%		0%	0%	0%
	JACKSON	6		10	3				2	13	13		13	13	13
		0%		0%						60%	20%		20%	0%	0%
	PEPIN	2		4						5	5 71%		5 0%	5 0%	5
	PIERCE	100%	2% 2	0% 6			100%			43%	71%		0%	0%	0% 7
	PIERCE	43%	2 42%	0%		0%	•			27%	36%	0%	0%	0%	0%
	POLK	43% 5	42%	20		1				21%	22	18	22	22	22
	FULK	25%	 100%	0%						44%	33%	0%	0%	11%	0%
	RUSK	4	10070	8						9	9	6	9	9	9
	ROOK	0%	92%	0%			100%			41%	41%	0%	0%	0%	0%
	SAWYER	3	2	14			1			17	17	3	17	17	17
	•••••	20%	44%	0%		50%	0%		0%	74%	32%		5%	0%	0%
	ST. CROIX	5	2	19		2	2		4	19	19		19	19	19
		0%		8%						67%	56%		0%	0%	0%
	TAYLOR	2		8						9	9		9	9	9
		25%		1%						36%	45%	0%	36%	0%	0%
	TREMPEALEAU	4		8						11	11	2	11	11	11
		20%	14%	0%			0%		4%	64%	0%	0%	0%	0%	0%
	WASHBURN	5	1	9			1		1	11	11	2	11	11	11
		50%	0%	6%	34%	0%	18%		0%	93%	66%	0%	3%	0%	0%
	KENOSHA	2	12	23	6	3	13		2	29	29	12	29	29	29
		50%	4%	15%	0%	33%	11%	0%	0%	82%	18%	5%	46%	10%	10%
SE	MILWAUKEE	4	28	18	1	5	28	3	10	39	39	19	39	39	39
		0%	0%	0%	27%	0%	4%	0%	0%	26%	37%	0%	68%	0%	0%
	OZAUKEE	3	8	16	6	1	8	1	6	19	19	2	19	19	19
	RACINE	29%	0%	15%	13%		10%		0%	71%	65%	0%	16%	0%	0%

								Conc % back # of obse	logged	s					
				Drai	nage					•	Road	sides			
Region	County	Culverts	Curb & Gutter	Ditches	Drains	Flumes	Storm Sewer	Barriers	Fences	Litter	Mowing	Mowing for Vision	Noxious Weeds	Woody Vegetation Control	Woody Vegetation Control for Vision
		6	7	27	7		16		2	31	31	18	31	31	31
		7% 11	51%	3% 35	0% 7	50%	0% 4		4% 12	47% 38	45%	0% 4	71% 38	0% 38	0% 38
	WALWORTH	20%	5 24%	35 2%	0%	1 0%	4	 0%	0%	13%	38 47%	4	38 75%	38 0%	38
	WASHINGTON	5	5	31	4	3	4	2	9	32	32	7	32	32	378
	WAGHINGTON	0%	0%	0%	0%	33%	0%	0%	0%	55%	51%		4%	2%	2%
	WAUKESHA	8	21	31	7	5	20	2	13	51	51		51	51	51
		33%	78%	0%	67%				0%	94%	25%	0%	81%	0%	6%
	COLUMBIA	3	1	15	2				2	16	16	1	16	16	16
		0%	5%	0%			0%			33%	0%	0%	0%	0%	0%
	CRAWFORD	3	4	6			2			9	9	1	9	9	9
		9%	1%	1%	7%	0%	0%		0%	82%	18%	0%	57%	4%	0%
	DANE	10	4	26	3	2	4		5	28	28	5	28	28	28
	DODOF	33%	20%	5%	33%	100%			0%	100%	46%		85%	0%	0%
SW	DODGE	6 0%	1	12 0%	3	1			4	13 22%	13 33%		13 0%	13 0%	13 0%
500	GRANT	<u> </u>		9						9	33%		9	9	9
	GIANT	50%		0%						56%	22%		100%	0%	0%
	GREEN	2		9						9	9		9	9	9
		0%	0%	0%			0%		0%	58%	17%		92%	0%	0%
	IOWA	1	1	11			1		2	12	12		12	12	12
		0%	9%	2%		50%	0%		0%	68%	32%	0%	74%	0%	0%
	JEFFERSON	5	5	15		2	1		2	19	19	6	19	19	19
		60%		1%					0%	69%	6%		0%	0%	0%
	JUNEAU	8		14					3	16	16		16	16	16
		33%	2%	6%	25%	0%	25%		1%	78%	44%	0%	22%	0%	11%
	LA CROSSE	6	2	9	1	2	1		3	9	9	9	9	9	9

							#	% back	lition logged ervation	S					
				Drai	nage					r	Road	sides			
Region	County	Culverts	Curb & Gutter	Ditches	Drains	Flumes	Storm Sewer	Barriers	Fences	Litter	Mowing	Mowing for Vision	Noxious Weeds	Woody Vegetation Control	Woody Vegetation Control for Vision
		0%	0%	0%	0%	0%	0%		0%	91%	27%		100%	0%	0%
	LAFAYETTE	5	2	11	2	1	1		1	11	11		11	11	11
		23%	0%	1%	100%	0%	0%		0%	85%	7%		0%	0%	0%
	MONROE	12	1	22	2	2	2		7	27	27		27	27	27
		0%	12%	0%		0%	0%			33%	27%	0%	0%	7%	0%
	RICHLAND	3	2	13		1	1			15	15	5	15	15	15
		100%		4%	0%		0%		0%	69%	15%	100%	100%	0%	0%
	ROCK	1		13	1		1		2	13	13	1	13	13	13
		33%	16%	0%	67%		40%		0%	81%	44%	0%	63%	0%	0%
	SAUK	3	4	14	2		3		2	16	16	1	16	16	16
		27%	6%	6%		50%	100%			67%	17%	12%	22%	28%	11%
	VERNON	11	3	17		2	1			18	18	17	18	18	18

Mowing

The following table shows the number of segments with deficient Mowing and the distribution of the deficiencies' 'how' (shown as columns) and 'why' (shown as rows) at the statewide level. For the overall report, all of the segments shown are considered a backlog and contributed to the backlog percentage reported for Mowing. Note that multiple reasons for mowing deficiency are allowed; therefore the sum of percentages for each deficiency type can be more than 100%.

			How is it	deficient?				
		# of se	gments with	observed def	iciency			
			% of se	egment				
		Too Wide	Too Short	Too High	In the No Mow Zone			
0.	Sofoty/Equipment	9	0	3	3			
nt,	Safety/Equipment	4%	0%	1%	75%			
cie	Mowed by Property Owner	205	380	72	1			
deficient?	Mowed by Property Owner	86%	99%	21%	25%			
÷	Mander Magnetation Constral	5	0	1	0			
is'	Woody Vegetation Control	2%	0%	0%	0%			
Why	Maintananaa Dagigian	59	69	319	0			
>	Maintenance Decision	25%	18%	91%	0%			
	Total 237 385 349 4							

2007 Bridges: Compass Report on Condition, Maintenance, and Inspection Backlog

The compass bridge report uses data from the Highway Structures Information System (HSI) online report. Data was taken during the period of three weeks from April 7th to May 2nd, 2008.

Key observations

Bridge Deck Condition Distribution

- 33% of decks statewide are in Fair condition and need reactive maintenance, based on their NBI ratings of 5 or 6. These include 28% of concrete bridges and 42% of steel bridges.
- The SE region has the lowest percent of decks in good condition, only 48% of decks in good condition and 5% of decks in poor condition. However, this is a 5% improvement from last year, and SE region does have the largest deck area to maintain (13,897,617 ft2).
- The NE region (837 bridges) has the best bridge ratings in the state with 79% of decks in Good condition and an impressive 0% in Poor condition.

Bridge Maintenance Needs

- Maintenance actions are those recommended by bridge inspectors for each bridge at the time of inspection.
- The following maintenance actions are recommended as needed. As approaches settle, brush continually grows, decks eventually crack and drainage issues arise at wings, these actions become necessary:
 - Deck Seal Surface Cracks
 - Expansion Joints Seal
 - Misc Cut Brush
 - Approach Seal Approach to Paving Block
 - Deck Patching
 - Drainage Repair Washouts / Erosion
 - Approach Wedge Approach

Bridge Special Inspection Backlog

- Backlog for bridge inspection is calculated based on the mandatory inspection frequency for each inspection type. Bridges without a 'Last Inspection Date' are reported in HSI as 'Unknown' and are regarded as non-compliant (backlogged) for this report. All bridges require initial and biennial routine inspections. Initial inspections are the most up to date with 0% of backlogs statewide, while routine inspections and Underwater Diving inspections as the next lowest with only 2% backlog.
- Fracture critical and in-depth inspections have the highest percent backlogs with 52% and 44%, respectively, but this represents only 8 and 35 bridges, respectively. These compliance estimates for fracture critical and in-depth inspections are preliminary as the state is still populating the HIS database. The HSI database becomes current for all inspection types in 2008.

2007 Bridges: Compass Report on Condition

	Dridaaa	Deck Area	Component	%	of bridges	in condi	tion
	Bridges	(ft^2)	Component	Good ¹	Fair ²	Poor ³	Critical ³
			Decks	64%	33%	3%	0%
All	5007	48,232,589	Superstructures	70%	28%	1%	0%
			Substructures	70%	29%	1%	0%
			Decks	70%	28%	2%	0%
Concrete	3423	25,833,160	Superstructures	78%	21%	1%	0%
			Substructures	79%	21%	0%	0%
			Decks	53%	42%	5%	0%
Steel	1584	22,399,429	Superstructures	55%	43%	2%	0%
			Substructures	54%	44%	3%	0%

Wisconsin 2007: Bridge Condition Distribution

Region 2007: Bridge Condition Distribution

		-						
Region	Bridges	Deck Area	Component		% of bridges	in condition		
Region	Dilages	(ft^2)	Component	Good ¹	Fair ²	Poor ³	Critical ³	
			Decks	77%	21%	2%	0%	
NC	620	4,323,989	Superstructures	84%	15%	1%	0%	
			Substructures	82%	17%	1%	0%	
			Decks	79%	21%	0%	0%	
NE	837	8,656,480	Superstructures	82%	17%	1%	0%	
			Substructures	73%	25%	1%	0%	
			Decks	50%	47%	4%	0%	
NW	1067	9,461,499	Superstructures	65%	32%	2%	0%	
			Substructures	67%	31%	2%	0%	
			Decks	48%	48%	5%	0%	
SE	1023	13,897,617	Superstructures	49%	50%	1%	0%	
			Substructures	50%	50%	0%	0%	
			Decks	73%	24%	3%	0%	
SW	1462	1462 11,894,594			76%	22%	2%	0%
	· · · ·		11,894,594	Substructures	81%	18%	1%	0%

¹Good: Bridges with NBI rating 7-9 should receive Preventive Maintenance

²Fair: Bridges with NBI 5-6 should receive Reactive Maintenance. These bridges are considered backlogged for maintenance

³Poor and Critical: Bridges with NBI 0-4 should receive Rehabilitation or Replacement.

Bridge Maintenance Needs

Bridges recommended for maintenance are shown as percent of total bridges in the county/region/state. The recommended maintenance activities listed on this table are the 20 most recommended maintenance activities statewide.

		recom	% of br mended fo		ance	
				Region		
Maintenance	Statewide	NC	NE	NW	SE	SW
Deck - Seal Surface Cracks	16%	39%	18%	7%	14%	13%
Expansion Joints – Seal	11%	11%	25%	2%	18%	4%
Misc - Cut Brush	9%	4%	4%	5%	17%	12%
Approach - Seal Approach to Paving Block	9%	1%	4%	16%	9%	10%
Deck – Patching	7%	12%	9%	4%	9%	4%
Drainage - Repair Washouts / Erosion	7%	2%	9%	4%	12%	6%
Approach - Wedge Approach	5%	3%	1%	2%	12%	7%
Misc - Remove/Monitor Loose Concrete	5%	0%	0%	0%	23%	1%
Approach - Other Work	3%	1%	1%	1%	9%	3%
Approach - Seal Cracks	3%	0%	0%	1%	11%	2%
Deck - Other Work	3%	1%	3%	1%	6%	3%
Channel - Remove Debris	2%	1%	1%	1%	2%	5%
Drainage - Clean Downspouts	2%	0%	2%	0%	8%	1%
Substructure - Repair Abutment / Wings	2%	2%	4%	1%	4%	1%
Deck - Surface Repair Spalls	2%	2%	2%	4%	2%	2%
Approach - Repair Approaches	2%	2%	1%	1%	4%	2%
IMP-Concrete Overlay	2%	0%	0%	0%	3%	0%
Slope Protection - Other Work	2%	2%	2%	1%	1%	1%
Slope Protection - Reseal Slope Paving	2%	1%	0%	3%	1%	0%
Drainage - Repair/Construct Drainage Flumes	2%	1%	1%	0%	1%	2%
Misc - Other Work*	11%	9%	6%	2%	37%	4%

Wisconsin 2007: Bridge Maintenance Needs

'* All maintenance activities that are not listed.

Counties 2007: Bridge Maintenance Needs

The recommended maintenance activities listed on this table are the twelve most recommended maintenance activities statewide

				%	of bridges	recommend	ed for main	tenance		
Region	County	Number of state bridges	Deck - Seal Surface Cracks	Expansion Joints - Seal	Misc - Cut Brush	Approach - Seal Approach to Paving Block	Deck - Patching	Drainage - Repair Washouts / Erosion	Approach - Wedge Approach	Misc - Other Work*
	ADAMS	7	43%	29%	0%	0%	0%	0%	14%	0%
	FLORENCE	8	0%	0%	0%	0%	0%	0%	0%	0%
	FOREST	11	0%	0%	9%	0%	0%	9%	0%	0%
	GREEN LAKE	10	50%	20%	10%	0%	0%	0%	20%	0%
	IRON	18	0%	0%	17%	0%	0%	0%	0%	0%
	LANGLADE	11	0%	0%	0%	9%	0%	0%	0%	0%
	LINCOLN	52	15%	2%	2%	0%	0%	0%	4%	6%
	MARATHON	151	53%	18%	7%	0%	20%	3%	3%	15%
	MARQUETTE	36	42%	25%	0%	0%	8%	0%	6%	6%
NC	MENOMINEE	3	33%	0%	33%	33%	0%	0%	0%	0%
	ONEIDA	14	14%	0%	0%	0%	0%	0%	0%	0%
	PORTAGE	79	57%	9%	1%	1%	29%	1%	0%	11%
	PRICE	21	10%	0%	0%	0%	0%	0%	0%	0%
	SHAWANO	53	36%	2%	8%	2%	0%	4%	4%	2%
	VILAS	11	55%	0%	0%	0%	9%	0%	0%	0%
	WAUPACA	63	25%	8%	0%	0%	5%	2%	0%	13%
	WAUSHARA	21	33%	19 %	0%	0%	29%	0%	0%	10%
	WOOD	51	61%	16%	4%	2%	18%	4%	6%	14%
	BROWN	246	17%	21%	4%	0%	8%	9%	0%	7%
	CALUMET	13	8%	38%	8%	0%	15%	31%	8%	8%
	DOOR	13	23%	15%	8%	0%	0%	0%	0%	31%
NE	FOND DU LAC	72	36%	17%	0%	3%	4%	7%	6%	7%
	KEWAUNEE	18	0%	11%	0%	0%	6%	6%	0%	0%
	MANITOWOC	89	6%	22%	3%	6%	7%	4%	0%	3%

				%	of bridges	recommend	ed for main	tenance		
Region	County	Number of state bridges	Deck - Seal Surface Cracks	Expansion Joints - Seal	Misc - Cut Brush	Approach - Seal Approach to Paving Block	Deck - Patching	Drainage - Repair Washouts / Erosion	Approach - Wedge Approach	Misc - Other Work*
	MARINETTE	34	21%	24%	12%	18%	9%	0%	0%	3%
	OCONTO	37	35%	16%	0%	0%	3%	14%	0%	0%
	OUTAGAMIE	80	13%	44%	4%	15%	10%	15%	4%	9%
	SHEBOYGAN	85	21%	24%	7%	4%	25%	13%	1%	0%
	WINNEBAGO	146	18%	33%	2%	6%	10%	10%	0%	10%
	ASHLAND	19	0%	0%	0%	0%	0%	0%	5%	0%
	BARRON	65	2%	0%	9%	6%	6%	2%	0%	0%
	BAYFIELD	34	0%	0%	0%	0%	0%	0%	0%	0%
	BUFFALO	71	1%	0%	0%	3%	0%	0%	1%	0%
	BURNETT	15	0%	0%	0%	13%	0%	0%	7%	0%
	CHIPPEWA	135	15%	11%	2%	21%	5%	4%	1%	5%
	CLARK	43	9%	2%	19%	37%	2%	0%	0%	5%
	DOUGLAS	61	0%	0%	0%	0%	0%	0%	0%	0%
	DUNN	91	9%	1%	10%	24%	3%	5%	4%	4%
	EAU CLAIRE	111	14%	0%	5%	41%	5%	5%	0%	1%
NW	JACKSON	74	5%	4%	4%	12%	3%	9%	1%	3%
	PEPIN	16	0%	13%	13%	0%	0%	0%	0%	6%
	PIERCE	57	5%	2%	9%	7%	2%	12%	5%	2%
	POLK	13	8%	0%	0%	0%	15%	8%	0%	0%
	RUSK	30	3%	0%	0%	0%	0%	0%	0%	0%
	SAWYER	19	0%	0%	5%	11%	11%	0%	5%	0%
	ST. CROIX	99	15%	1%	11%	30%	3%	10%	9%	2%
	TAYLOR	21	5%	0%	0%	0%	10%	0%	0%	10%
	TREMPEALEAU	73	0%	0%	5%	11%	4%	4%	3%	0%
	WASHBURN	20	5%	0%	0%	0%	5%	0%	0%	0%
	KENOSHA	56	27%	34%	5%	5%	4%	7%	2%	27%
SE	MILWAUKEE	503	10%	23%	22%	6%	12%	5%	5%	32%
SE	OZAUKEE	50	16%	6%	22%	14%	10%	16%	22%	58%

				%	of bridges	recommend	ed for main	tenance		
Region	County	Number of state bridges	Deck - Seal Surface Cracks	Expansion Joints - Seal	Misc - Cut Brush	Approach - Seal Approach to Paving Block	Deck - Patching	Drainage - Repair Washouts / Erosion	Approach - Wedge Approach	Misc - Other Work*
	RACINE	53	6%	13%	11%	17%	2%	0%	8%	30%
	WALWORTH	115	17%	16%	11%	8%	4%	15%	16%	62%
	WASHINGTON	74	1%	7%	4%	15%	0%	4%	5%	27%
	WAUKESHA	172	25%	9%	15%	11%	15%	37%	37%	37%
	COLUMBIA	97	4%	0%	23%	5%	4%	5%	2%	1%
	CRAWFORD	66	52%	2%	14%	15%	6%	3%	24%	11%
	DANE	283	1%	6%	19%	13%	2%	7%	4%	4%
	DODGE	64	2%	3%	9%	3%	2%	3%	5%	5%
	GRANT	67	22%	0%	10%	12%	4%	7%	9%	7%
	GREEN	28	7%	0%	4%	0%	7%	0%	0%	7%
	IOWA	56	4%	0%	9%	2%	4%	5%	2%	0%
	JEFFERSON	72	0%	3%	8%	6%	3%	0%	0%	0%
SW	JUNEAU	80	33%	16%	0%	8%	11%	5%	0%	1%
	LA CROSSE	107	36%	5%	10%	33%	7%	11%	10%	9%
	LAFAYETTE	40	3%	0%	10%	3%	8%	10%	5%	0%
	MONROE	154	0%	3%	7%	9%	6%	3%	10%	10%
	RICHLAND	78	17%	3%	22%	10%	6%	3%	10%	6%
	ROCK	120	4%	2%	7%	4%	3%	1%	2%	3%
	SAUK	77	0%	1%	4%	9%	0%	4%	1%	0%
	VERNON	73	7%	4%	12%	5%	4%	22%	23%	0%

'* All maintenance activities that are not listed.

Wisconsin and Regions 2007: Bridge Special Inspection Backlog

Inspection backlogs are shown as 'percent of bridges in the county/region/state requiring this type of inspection'. Shown under the percentages are the numbers of bridges backlogged for that inspection type in the county/region/state. Data was extracted from WisDOT's HSI (Highway Structures Information System) on-line reports.

The special inspection types have a mandatory inspection frequency. The inspection frequencies for each special inspection are as follows:

- Initial: After construction & Major Rehab, or 48 months
- Routine: 24 months
- Load Posted: 12 months
- In-depth: 72 months
- Fracture Critical: 24 months
- Underwater Diving: 60 months
- Underwater Probe/Visual: 24 months

	Special Inspection Type % of bridges backlogged for inspection type # of bridges backlogged for inspection						
Region	Initial	Routine	Load Posted	In-depth	Fracture Critical	Underwater Diving	Underwater Probe/Visual
NC	0%	0%	0%	100%	0%	0%	24%
	0	0	0	5	0	0	63
NE	0%	0%	100%	67%	17%	3%	16%
	0	0	5	4	5	2	36
NW	0%	3%	100%	83%	9%	1%	27%
	1	30	3	10	2	1	147
SE	0%	2%	0%	18%	0%	11%	35%
	1	21	0	7		1	92
SW	0%	3.22%	100%	53%	3%	2%	12%
3 W	2	47	3	9	1	2	37
Statewide	0%	2%	8%	44%	52%	2%	23%
	4	98	11	35	8	6	375

				% bridges ba	ial Inspection T cklogged for ins backlogged for	pection type		
Region	County	Initial	Routine	Load Posted	In-depth	Fracture Critical	Underwater Diving	Underwater Probe/Visual
		0%	0%				0%	0%
	ADAMS	0	0				0	0
		0%	0%			0%	0%	0%
	FLORENCE	0	0			0	0	0
		0%	0%					100%
	FOREST	0	0					3
		0%	0%					20%
	GREEN LAKE	0	0					2
		0%	0%				0%	0%
	IRON	0	0				0	0
		0%	0%			0%		50%
	LANGLADE	0	0			0		1
		0%	0%			0%	0%	100%
	LINCOLN	0	0			0	0	6
NC		0%	0%			100%	0%	20%
	MARATHON	0	0			4	0	16
		0%	0%				0%	29%
	MARQUETTE	0	0				0	4
		0%	0%					100%
	MENOMINEE	0	0					1
		0%	0%				0%	100%
	ONEIDA	0	0				0	3
		0%	0%				0%	0%
	PORTAGE	0	0				0	0
		0%	0%				0%	0%
	PRICE	0	0				0	0
		0%	0%			0%	0%	43%
	SHAWANO	0	0			0	0	3
	VILAS	0%	0%				0%	75%

Counties 2007: Bridge Special Inspection Backlog

				% bridges ba	ial Inspection T cklogged for ins backlogged for	pection type		
Region	County	Initial	Routine	Load Posted	In-depth	Fracture Critical	Underwater Diving	Underwater Probe/Visual
		0	0				0	3
		0%	0%			0%	0%	36%
	WAUPACA	0	0			0	0	14
		0%	0%					75%
	WAUSHARA	0	0					6
		0%	0%		100%	0%	0%	2%
	WOOD	0	0		1	0	0	1
		0%	0%		100%	50%	0%	38%
	BROWN	0	0		1	4	0	16
		0%	0%					0%
	CALUMET	0	0					0
		0%	0%	100%		0%	0%	0%
	DOOR	0	0	4		0	0	0
		0%	0%					0%
	FOND DU LAC	0	0					0
		0%	0%				0%	100%
	KEWAUNEE	0	0				0	14
NE		0%	0%			0%		10%
T L	MANITOWOC	0	0			0		3
		0%	0%			0%	25%	0%
	MARINETTE	0	0			0	2	0
		0%	0%			0%		0%
	OCONTO	0	0			0		0
		0%	0%	100%	50%	0%	0%	0%
	OUTAGAMIE	0	0	1	1	0	0	0
		0%	0%					10%
	SHEBOYGAN	0	0					3
		0%	0%		67%	13%	0%	0%
	WINNEBAGO	0	0		2	1	0	0
		0%	0%				0%	56%
NW	ASHLAND	0	0				0	5
	BARRON	0%	0%				0%	17%

	1	Special Inspection Type % bridges backlogged for inspection type # of bridges backlogged for inspection								
Region	County	Initial	Routine	Load Posted	In-depth	Fracture Critical	Underwater Diving	Underwater Probe/Visual		
		0	0				0	4		
		0%	0%				0%	8%		
	BAYFIELD	0	0				0	2		
		0%	0%			0%	7%	15%		
	BUFFALO	0	0			0	1	6		
		0%	0%			0%	0%	29%		
	BURNETT	0	0			0	0	2		
		0%	0%			0%	0%	41%		
	CHIPPEWA	0	0			0	0	21		
		0%	0%					100%		
	CLARK	0	0					23		
		0%	0%	100%		0%	0%	25%		
	DOUGLAS	0	0	1		0	0	8		
		0%	0%		100%	0%	0%	5%		
	DUNN	0	0		2	0	0	3		
		1%	1%		100%	0%	0%	38%		
	EAU CLAIRE	1	1		4	0	0	13		
		0%	0%				0%	16%		
	JACKSON	0	0				0	5		
		0%	0%				0%	0%		
	PEPIN	0	0				0	0		
		0%	49%		100%	0%	0%	77%		
	PIERCE	0	28		1	0	0	33		
		0%	0%		0%	0%	0%	0%		
	POLK	0	0		0	0	0	0		
		0%	0%		0%		0%	10%		
	RUSK	0	0		0		0	2		
		0%	0%				0%	0%		
	SAWYER	0	0				0	0		
		0%	1%	100%	0%		0%	17%		
	ST. CROIX	0	1	1	0		0	11		
	TAYLOR	0%	0%		100%	67%		33%		

			I	% bridges ba	ial Inspection T cklogged for ins backlogged for	pection type		
Region	County	Initial	Routine	Load Posted	In-depth	Fracture Critical	Underwater Diving	Underwater Probe/Visual
		0	0		1	2		3
		0%	0%	100%	100%	0%	0%	20%
	TREMPEALEAU	0	0	1	1	0	0	4
		0%	0%					14%
	WASHBURN	0	0					2
		0%	4%			0%		17%
	KENOSHA	0	2			0		4
		0%	2%	0%	18%	0%	0%	53%
	MILWAUKEE	1	9	0	6	0	0	40
		0%	0%	0%			100%	27%
	OZAUKEE	0	0	0			1	4
SE		0%	4%					4%
SL	RACINE	0	2					1
		0%	0%	0%	50%			22%
	WALWORTH	0	0	0	1			8
		0%	0%		0%		0%	25%
	WASHINGTON	0	0		0		0	6
		0%	5%		0%			46%
	WAUKESHA	0	8		0			29
		0%	1%	100%	0%	0%	7%	12%
	COLUMBIA	0	1	1	0	0	1	2
		0%	0%	100%	0%	0%	0%	9%
	CRAWFORD	0	0	1	0	0	0	2
		0%	3%		100%	0%	0%	18%
~~~	DANE	0	9		1	0	0	5
SW	DODGE	0%	0%				0%	10%
	DODGE	0	0				0	1
	ODANT	0%	0%			0%	0%	0%
	GRANT	0	0			0	0	0
	ODEEN	0%	0%				0%	0%
	GREEN	0	0				0	0
	IOWA	4%	2%		100%	0%	0%	0%

		Special Inspection Type % bridges backlogged for inspection type # of bridges backlogged for inspection								
Region	County	Initial	Routine	Load Posted	In-depth	Fracture Critical	Underwater Diving	Underwater Probe/Visual		
		2	1		1	0	0	0		
		0%	0%				0%	6%		
	JEFFERSON	0	0				0	1		
		0%	0%			0%	0%	6%		
	JUNEAU	0	0			0	0	1		
		0%	0%		100%	17%	0%	69%		
	LA CROSSE	0	0		3	1	0	11		
		0%	0%			0%	0%	8%		
	LAFAYETTE	0	0			0	0	1		
		0%	0%		100%	0%		0%		
	MONROE	0	0		1	0		0		
		0%	41%			0%	25%	29%		
	RICHLAND	0	32			0	1	6		
		0%	3%		50%	0%	0%	0%		
	ROCK	0	4		2	0	0	0		
		0%	0%		100%	0%	0%	3%		
	SAUK	0	0		1	0	0	1		
		0%	0%	100%	0%	0%		22%		
	VERNON	0	0	1	0	0		6		

# Appendices

- A. Program Contributors
  B. Feature Thresholds and Grade Ranges
  C. Feature Contribution Categories
  D. 2006-2007 Maintenance Targets

# **A. Program Contributors**

The Wisconsin Department of Transportation appreciates the significant contributions to the Compass program that were made by the following people:

## 2007 Compass Advisory Team

Scott Bush, WisDOT Compass Program Manager John Corbin, WisDOT Traffic Engineering Section Chief Bob Hanifl, WisDOT SW Region Maintenance Project Engineer Todd Hogan, WisDOT SW Region Engineering Technician John Kinar, WisDOT Highway Maintenance & Roadside Mngmt. Section Chief Mike Ostrenga, WisDOT NW Region Area Supervisor Doug Passineau, Wood County Patrol Superintendent Ken Pesch, Washington County Highway Commissioner Brett Wallace, WisDOT NE Region SPO Manager Tom Walther, Eau Claire County Highway Commissioner Jim Wendels, WisDOT NC Region Roadway Maintenance Engineer Mark Woltmann, WisDOT Highway Operations Program Mngmt, Section Chief Jack Yates, Marquette County Patrol Superintendent

### 2007 Compass Training Team

Scott Bush, WisDOT Compass Program Manager Leif Hubbard, WisDOT Central Office Jerry Jagmin, Lincoln County Ed Kazik, Brown County Tim Nachreiner, WisDOT Central Office Dennis Newton, WisDOT SE Region

### 2007 Compass Quality Assurance Team

Lance Burger, WisDOT NW Region Scott Bush, WisDOT Compass Program Manager (all regions) Bob Hanifl, WisDOT SW Region Jerry Jagmin, Lincoln County (NC Region) Ed Kazik, Brown County (NE Region) Dennis Newton, WisDOT SE Region

### 2007 Certified Compass Raters

Dawonn Averhart, Milwaukee County Kris Baguhn, Marathon County Mike Baker, Washburn County Gary Bauer, Pepin County Dave Beaster, Fond du Lac County Jerry Boettcher, Eau Claire County Dennis Bonnell, Waupaca County

Lance Burger, WisDOT NW Region Michael Burke, WisDOT NW Region Chuck Buss, Green Lake County Grant Bystol, Shawano County Terry Cilley, Juneau County Russell Cooper, Jefferson County John Czarnecki, Sawyer County Dan Davis, WisDOT NE Region Marc Davison, Oneida County John Delaney, WisDOT SW Region William Demler, Winnebago County Darwin Derge, WisDOT SE Region Jeff Fish. Vernon County Paul Gingras, WisDOT NW Region Gregory Gordinier, WisDOT SW Region Don Grande, Ashland County Susan Greeno-Eichinger, WisDOT NC Region Robert Hanifl, WisDOT SW Region Gus Hanold, WisDOT NE Region Leo Hanson, Iron County Jim Harer, St. Croix County Ron Hintz, WisDOT NC Region Todd Hogan, WisDOT SW Region Wenzel Husnick, Langlade County Brandon Hytinen, WisDOT NE Region Jason Jackman, Douglas County Jerry Jagmin, Lincoln County Paul Johanik, Bayfield County Gerald Kast, Monroe County Ed Kazik, Brown County Kevin Kent, Milwaukee County Brad Kimball, WisDOT NC Region Jon Knautz, Grant County Patrick Kotlowski, Adams County Don Kreft, Walworth County Michael Larson, WisDOT NW Region Kevin Leffler, Florence County Mark Leibham, Sheboygan County Wayne Lien, Trempealeau County Jarred Maney, Vilas County Dick Marti, Green County Andrea Maxwell, WisDOT SE Region Hal Mayer, Rock County Jeff McLaughlin, Waukesha County Brenda McNallan, WisDOT NW Region Carl Meverden, Marinette County Randy Miller, Washington County Michael Mischnick, Calumet County George Molnar, Price County Phil Montwill, Rusk County

Mark Mullikin, Walworth County Todd Myers, Crawford County John Nelson, Columbia County Gordy Nesseth, Barron County Bill Niederer, Kenosha County Pat Nolan, Racine County Emil "Moe" Norby, Polk County Clair "Jeep" Norris, WisDOT SW Region Charles Oleinik, WisDOT NC Region Donnie Olsen, Jackson County Shaun Olson, Dane County Al Olson, Oconto County Doug Passineau, Wood County Bill Patterson, Waushara County Tim Pawelski, WisDOT NW Region Kevin Peiffer, WisDOT SE Region Lance Penney, Waupaca County Dale Petersen, Portage County Gregg Petersen, Manitowoc County Carl "Buzz" Peterson, Lafayette County Patricia Pollock, WisDOT NW Region Rick Potter, Juneau County Dennis Premo, Adams County Larry Price, Walworth County Bill Prue, WisDOT NE Region Dan Raczkowski, Marathon County Perry Raivala, WisDOT NW Region Gale Reinecke, Dunn County Louis Revoir, Chippewa County Randal Richardson, Richland County Jeff Rischette, Monroe County Michael Roberts, WisDOT SW Region Dave Rogers, WisDOT NC Region Randy Roloff, Outagamie County Jess Sackmann, Taylor County Chuck Saldivar, WisDOT SE Region Jeff Scanlon, Burnett County Diane Scherrman, WisDOT NW Region Brenda Schoenfeld, WisDOT NC Region Joel Seaman, WisDOT NC Region

Stacey Shampo, Forest County Ken Stock, Dodge County Pete Strachan, WisDOT SW Region William Tackes, Ozaukee County Raymond Thomas, Florence County Michael Thompson, Buffalo County John Thompson, Kewaunee County Alan Thoner, Pierce County Paul Van Beek, Marinette County Roger Venden, Iowa County Paul Vetter, Dane County Don Walker, Clark County Allen Washinawatok, Menominee County Jim Weiglein, WisDOT SE Region Jack Yates, Marquette County John Ziech, Sauk County

#### **Additional Compass Resources**

Mike Adams, WisDOT Central Office (winter) Dr. Teresa Adams, University of Wisconsin - Madison (data analysis, report) Dave Babler, WisDOT Central Office (bridge) Scott Erdman, WisDOT Central Office (segment data) Chuck Failing, WisDOT Central Office (mapping) Preston Judkins, University of Wisconsin - Madison (data analysis, report) Emil Juni, University of Wisconsin - Madison (data analysis, report) Mary Kirkpatrick, WisDOT Central Office (desktop publishing) Mike Malaney, WisDOT Central Office (pavement) Tim Nachreiner, WisDOT Central Office (database, Rating Sheets) Matt Rauch, WisDOT Central Office (signs) Kanisa Rungjang, University of Wisconsin - Madison (data analysis, report) Mike Sproul, WisDOT Central Office (winter)

<b>B.</b> Compass Feature Thresholds and Grade Ranges
-------------------------------------------------------

Element	Feature	Threshold	<b>Ranges for System Grades</b> <i>Grade determined by percent backlogged</i> shown: top of range					
			A	В	С	D	F	
Traveled way, asphalt	Alligator cracking	10% or more of the surface has unsealed alligator cracking (by mile)	0-7%	8-18%	19-35%	36- 60%	>60%	
	Block cracking	10% or more of the surface has unsealed block cracking (by mile)	7%	18%	35%	60%	>60%	
	Edge raveling	Visible cracking is present for 10% or more of the mile	7%	18%	35%	60%	>60%	
	Flushing	Flushing is present in more than small, isolated areas (by mile)	7%	18%	35%	60%	>60%	
	Longitudinal cracking	Any unsealed longitudinal cracking (by mile)	7%	18%	35%	60%	>60%	
	Longitudinal distortion					50%	>50%	
	Patch deterioration	Any patch is deteriorated enough to affect ride quality (by mile)	6%	15%	29%	50%	>50%	
	Rutting	Ruts are ¹ / ₄ inch or deeper (by mile)	2%	5%	9%	15%	>15%	
	Surface raveling	The aggregate and/or asphalt binder has worn away and the surface texture is rough or pitted (by mile)	6%	15%	29%	50%	>50%	
	Transverse cracking	Any unsealed transverse cracks at least 6' in length (by mile)	7%	18%	35%	60%	>60%	
	Transverse distortion	Significant distortion affects 1% or more of roadway (by mile)	6%	15%	29%	50%	>50%	
Traveled way, concrete	Distressed joints/cracks	Distress in wheel path greater than 2 inches wide (by mile)	6%	15%	29%	50%	>50%	
	Longitudinal joint distress	Faulting or signs of distress are present (by mile)	6%	15%	29%	50%	>50%	
	Patch deterioration	Any patch is deteriorated enough to affect ride quality (by mile)	6%	15%	29%	50%	>50%	
	Slab breakup	Slab is divided into at least 2-3 large blocks, affecting 10% or more of the slab (by mile)	6%	15%	29%	50%	>50%	
	Surface distress	Any measurable surface distress is present (by mile)	7%	18%	35%	60%	>60%	
	Transverse faulting	Any measurable faulting (by mile)	6%	15%	29%	50%	>50%	
Traffic control	Centerline markings	Line with > 20% paint missing (by mile)	2%	5%	9%	15%	>15%	

Element	Feature	Threshold	<b>Ranges for System Grades</b> <i>Grade determined by percent backlogged</i> shown: top of range					
			A	В	C	D	F	
& safety	Edgeline markings	Line with > 20% paint missing (by mile)	4%	9%	18%	30%	>30%	
devices (selected)	Delineators	Missing OR not visible at posted speed OR damaged (by delineator)	5%	12%	23%	40%	>40%	
	Other signs (emergency repair)	Missing OR not visible at posted speed (by sign)	4%	9%	18%	30%	>30%	
	Other signs (routine)		7%	18%	35%	60%	>60%	
	Protective barriers	Not functioning as intended (linear feet of barrier)	4%	9%	18%	30%	>30%	
	Raised pavement markers	Missing OR damaged (by RPM)	4%	9%	18%	30%	>30%	
	Regulatory/warning signs (emergency repair)	Missing OR not visible at posted speed (by sign)	2%	5%	9%	15%	>15%	
	Regulatory/warning signs (routine)	Beyond recommended service life (by sign)	5%	12%	23%	40%	>40%	
	Special pavement markings	Missing OR not functioning as intended (by marking)	5%	12%	23%	40%	>40%	
Shoulders	Hazardous debris	Any items large enough to cause a safety hazard (by mile)	2%	5%	9%	15%	>15%	
	Cracking on paved shoulder	200 linear feet or more of unsealed cracks > 1/4 inch (by mile)	7%	18%	35%	60%	>60%	
	Potholes/raveling on paved shoulder	Any potholes OR raveling > 1 square foot by 1 inch deep (by mile)	6%	15%	29%	50%	>50%	
	Cross-slope on unpaved shoulder	200 linear feet or more of cross-slope at least 2x planned slope with the maximum cross slope of 8% (by mile)	7%	18%	35%	60%	>60%	
	Drop-off/build-up on unpaved shoulder	200 linear feet or more with drop-off or build-up > 1.5 inches (by mile)	4%	9%	18%	30%	>30%	
	Erosion on unpaved shoulder	200 linear feet or more with erosion >2 inches deep (by mile)	7%	18%	35%	60%	>60%	
Drainage	Culverts	Culverts that are >25% obstructed OR where a sharp object - e.g., a shovel-can be pushed through the bottom of the pipe OR pipe is collapsed or separated (by culvert)	7%	18%	35%	60%	>60%	
	Curb & gutter	Curb & gutter with severe structural distress OR >1 inch structural misalignment OR >1 inch of debris build-up in the curb line (by linear feet of curb & gutter)	9%	22%	41%	70%	>70%	

Element	Feature	Threshold	<b>Ranges for System Grades</b> Grade determined by percent backlogged shown: top of range					
			A	В	C	D	F	
	Ditches	Ditch with greater than minimal erosion of ditch line OR obstructions to flow of water requiring action (by linear feet of ditch)	7%	18%	35%	60%	>60%	
	Flumes	Not functioning as intended OR deteriorated to the point that they are causing erosion (by flume)	7%	18%	35%	60%	>60%	
	Storm sewer system	Inlets, catch basins, and outlet pipes with >=50% capacity obstructed OR <80% structurally sound OR >1 inch vertical displacement or heaving OR not functioning as intended (by inlet, catch basin & outlet pipes)	7%	18%	35%	60%	>60%	
	Under-drains/edge-drains	9%	22%	41%	70%	>70%		
Roadsides	Barriers	Noise barrier or retaining wall not functioning as intended (by LF of barrier)	4%	9%	18%	30%	>30%	
	Fences	Fence missing OR not functioning as intended (by LF of fence)	4%	9%	18%	30%	>30%	
	Litter	Any pieces of litter on shoulders and roadside visible at posted speed, but not causing a safety threat. (by mile)	10%	25%	47%	80%	>80%	
	Mowing	Any roadside has mowed grass that is too short, too wide or is mowed in a no-mow zone (by mile)	10%	25%	47%	80%	>80%	
	Mowing for vision	Any instances in which grass is too high or blocks a vision triangle (by mile)	4%	9%	18%	30%	>30%	
	Noxious weeds	Any visible clumps (by mile)	7%	18%	35%	60%	>60%	
	Woody vegetation control	Any instances in which a tree is present in the clear zone OR trees and/or branches overhang the roadway or shoulder creating a clearance problem (by mile)	4%	9%	18%	30%	>30%	
	Woody vegetation control for vision	Any instances in which woody vegetation blocks a vision triangle (by mile)	4%	9%	18%	30%	>30%	

# C. Feature Contribution Categories

			This Feat	ure Contribute	es Primarily To:	
Element	Feature	Critical Safety	Safety/ Mobility	Ride/ Comfort	Stewardship	Aesthetics
Asphalt Traveled Way	Alligator Cracking Block Cracking Edge Raveling Flushing Longitudinal Cracking Longitudinal Distortion Patch Deterioration Rutting Surface Raveling Transverse Cracking Transverse Distortion	✓		✓ ✓ ✓ ✓		
Concrete Traveled Way	Distressed Joints/Cracks Longitudinal Joint Distress Patch Deterioration Slab Breakup Surface Distress Transverse Faulting			✓ ✓ ✓ ✓ ✓ ✓	✓	

					es Primarily To:	
Element	Feature	Critical Safety	Safety/ Mobility	Ride/ Comfort	Stewardship	Aesthetics
	Centerline Markings	$\checkmark$				
	Delineators		✓			
	Edgeline Markings		~			
	Other Signs (emerg. repair)		✓			
	Other Signs (routine repair)			~		
Traffic and Safety	Protective Barriers		✓			
anu Salety	Raised Pavement Markers		~			
	Reg./Warning Signs (emerg.)	$\checkmark$				
	Reg./Warning Signs (routine)		~			
	Special Pavement Markings		~			
	Hazardous Debris	~				
	Cracking (paved)				~	
Should	Potholes/Ravel- ing (paved)			~		
Shoulders	Cross-Slope (unpaved)			~		
	Drop-off/Build- up (unpaved)		~			
	Erosion (unpaved)				~	

			This Feat	ure Contribut	tes Primarily To:	
Element	Feature	Critical Safety	Safety/ Mobility	Ride/ Comfort	Stewardship	Aesthetics
	Culverts				$\checkmark$	
	Curb & Gutter				$\checkmark$	
	Ditches				$\checkmark$	
_	Flumes				$\checkmark$	
Drainage	Storm Sewer System				~	
	Under- drains/Edge- drains				~	
	Barriers				✓	
	Fences		✓			
	Litter					✓
	Mowing		✓			
Roadside	Mowing for Vision		~			
Roauside	Noxious Weeds				✓	
	Woody Vegetation		~			
	Woody Veg. Control for Vision		$\checkmark$			

## **Category Definitions:**

<u>Critical safety:</u> Critical safety features that would necessitate immediate action – with overtime pay if necessary - to remedy if not properly functioning.

<u>Safety:</u> Highway features and characteristics that protect users against - and provide them with a clear sense of freedom from - danger, injury or damage.

<u>Ride/comfort:</u> Highway features and characteristics, such as ride quality, proper signing, or lack of obstructions, that provide a state of ease and quiet enjoyment for highway users.

<u>Stewardship:</u> Actions taken to help a highway element obtain its full potential service life.

<u>Aesthetics:</u> The display of natural or fabricated beauty items, such as landscaping or decorative structures, located along a highway corridor. Also, the absence of things like litter and graffiti, that detract from the sightlines of the road.

# WisDOT Highway Operations 2006 and 2007 Target Service Levels

October 16, 2006

Issued by David Vieth, Director of the Bureau of Highway Operations

Attached are the 2006 and 2007 target service levels for highway operations. Highway operations managers expect these targets to provide guidance to central and regional highway operations staff in selecting activities and expending resources. The 2007 targets will help structure the process for developing 2007 Routine Maintenance Agreements.

Targets are the conditions expected on state highways at the end of the summer maintenance season. They were selected by highway operations managers in the regions and BHO to set priorities within the budget, and to increase consistency across region and county lines.

The condition measure used is the percent of inventory with backlogged maintenance work. A measure greater than 0% backlogged reflects work left undone at the end of the summer season. Under full funding of operations needs, we would expect to see features at or close to 0%. The following chart provides historical service levels statewide and by region for 2005. Please remember that targets have not yet been set for a portion of highway operations expenditures including winter operations, certain traffic devices and electrical operations.

Targets do not necessarily reflect an optimal maintenance condition for the highways, but instead reflect organizational priorities, existing highway conditions, and dollars available. It is assumed that all highway operations staff is doing the best job possible, given constrained resources. These organizational priorities include:

- Focusing our resources on keeping the system safe and operating from day to day. Highway operations will:
  - Decrease the amount of hazardous debris on shoulders.
  - Decrease drop-off on unpaved shoulders.
  - Increase the routine replacement of regulatory and warning signs.
- Expending far fewer resources based on limited funding.
  - Activities that address pavement cracking, noxious weeds and fence maintenance will be done infrequently, if at all. Litter removal and mowing will be reduced over time.
  - No maintenance of raised pavement markers and other wet reflective markings. Special pavement markings will only be addressed for the most critical safety needs. Some edgeline markings will be deferred due to reduced funding.
- Leveraging improvements that can decrease the maintenance workload.
  - Now and going forward, operations managers will step up their work with the improvement program to decrease pavement rutting and to improve culverts.

Thank you to Scott Bush and the Compass program for coordinating this effort and preparing this report.

D. 2006 and 2007 Hig	ghway Operations Targets	•
----------------------	--------------------------	---

Element	Feature	2003 Actual Percent Backlogged and Feature Grade - Statewide	2004 Actual Percent Backlogged and Feature Grade - Statewide	2005 Actual Percent Backlogged and Feature Grade - Statewide	2004 Target Percent Backlogged and Feature Grade - Statewide	2005 Target Percent Backlogged and Feature Grade - Statewide	2006 Target Percent Backlogged and Feature Grade - Statewide	2007 Target Percent Backlogged and Feature Grade - Statewide
Asphalt Traveled Way	Alligator Cracking	1=A	1=A	1=A	3=A	5=A	5=A	5=A
	Block Cracking	3=A	3=A	3=A	5=A	5=A	5=A	5=A
	Edge Raveling	14=B	15=B	15=B	15=B	15=B	18=B	20=C
	Flushing	1=A	0=A	0=A	1=A	1=A	1=A	1=A
	Longitudinal Cracking	24=C	26=C	26=C	21=C	25=C	28=C	30=C
	Longitudinal Distortion	0=A	0=A	0=A	0=A	1=A	1=A	1=A
	Patch Deterioration	10=B	9=B	9=B	10=B	10=B	10=B	10=B
	Rutting	11=D	9=C	9=C	17=F	15=D	13=D	10=D
	Surface Raveling	2=A	1=A	1=A	2=A	2=A	2=A	2=A
	Transverse Cracking	22=C	24=C	24=C	24=C	25=C	28=C	30=C
	Transverse Distortion	1=A	1=A	1=A	5=A	5=A	5=A	5=A
Concrete Traveled Way	Distressed Joints/Cracks	34=D	34=D	33=D	43=D	43=D	43=D	43=D

Element	Feature	2003 Actual Percent Backlogged and Feature Grade - Statewide	2004 Actual Percent Backlogged and Feature Grade - Statewide	2005 Actual Percent Backlogged and Feature Grade - Statewide	2004 Target Percent Backlogged and Feature Grade - Statewide	2005 Target Percent Backlogged and Feature Grade - Statewide	2006 Target Percent Backlogged and Feature Grade - Statewide	2007 Target Percent Backlogged and Feature Grade - Statewide
	Longitudinal Joint Distress	22=C	21=C	21=C	27=C	27=C	27=C	27=C
	Patch Deterioration	28=C	28=C	28=C	30=D	30=D	30=D	30=D
	Slab Breakup	46=D	45=D	44=D	44=D	45=D	45=D	45=D
	Surface Distress	21=C	20=C	20=C	25=C	25=C	25=C	25=C
	Transverse Faulting	76=F	74=F	74=F	80=F	75=F	75=F	75=F
Traffic and Safety	Centerline Markings	6=C	5=B	5=B	6=C	5=B	5=B	6=C
-	Delineators	19=C	21=C	24=D	15=C	15=C	25=D	25=D
	Edgeline Markings	11=C	7=B	5=B	6=B	6=B	6=B	7=B
	Other Signs (emerg. repair)	2=A	0=A	1=A	15=C	1=A	1=A	1=A
	Other Signs (routine repair)		46=D	59=D		50=D	65=F	70=F
	Protective Barriers	18=C	3=A	4=A	9=B	3=A	3=A	3=A
	Raised Pavement Markers	11=C	15=C	15=C	14=C	25=D	25=D	25=D

Element	Feature	2003 Actual Percent Backlogged and Feature Grade - Statewide	2004 Actual Percent Backlogged and Feature Grade - Statewide	2005 Actual Percent Backlogged and Feature Grade - Statewide	2004 Target Percent Backlogged and Feature Grade - Statewide	2005 Target Percent Backlogged and Feature Grade - Statewide	2006 Target Percent Backlogged and Feature Grade - Statewide	2007 Target Percent Backlogged and Feature Grade - Statewide
	Reg./Warning Signs (emerg.)	6=C	1=A	1=A	6=C	0=A	0=A	0=A
	Reg./Warning Signs (routine)		36=D	41=F		40=D	35=D	30=D
	Special Pavement Markings	15=C	13=C	5=A	21=C	25=D	25=D	25=D
Shoulders	Hazardous Debris	9=C	13=D	12=D	6=C	6=C	6=C	6=C
	Cracking (paved)	46=D	51=D	52=D	50=D	60=D	60=D	60=D
	Potholes/Raveling (paved)	7=B	5=A	7=B	12=B	10=B	10=B	10=B
	Cross-Slope (unpaved)	14=B	15=B	14=B	9=B	20=C	20=C	20=C
	Drop-off/Build- up (unpaved)	45=F	37=F	36=F	34=F	35=F	30=D	25=D
	Erosion (unpaved)	3=A	3=A	3=A	8=B	5=A	5=A	5=A
Drainage	Culverts	14=B	17=B	18=B	13=B	15=B	15=B	15=B
	Curb & Gutter	8=A	6=A	7=A	8=A	8=A	10=B	10=B
	Ditches	2=A	2=A	2=A	2=A	2=A	2=A	2=A
	Flumes	20=C	32=C	19=C	14=B	30=C	30=C	30=C
	Storm Sewer System	8=B	9=B	9=B	8=B	10=B	10=B	10=B

Element	Feature	2003 Actual Percent Backlogged and Feature Grade - Statewide	2004 Actual Percent Backlogged and Feature Grade - Statewide	2005 Actual Percent Backlogged and Feature Grade - Statewide	2004 Target Percent Backlogged and Feature Grade - Statewide	2005 Target Percent Backlogged and Feature Grade - Statewide	2006 Target Percent Backlogged and Feature Grade - Statewide	2007 Target Percent Backlogged and Feature Grade - Statewide
	Under- drains/Edge- drains	15=B	14=B	20=B	11=B	20=B	25=C	25=C
Roadside	Barriers	2=A			5=B	5=B	5=B	5=B
	Fences	14=C	4=A	2=A	16=C	14=C	14=C	14=C
	Litter	67=D	70=D	62=D	71=D	75=D	75=D	75=D
	Mowing		40=C	35=C	58=D	40=C	40=C	40=C
	Mowing for Vision		26=D		5=B	5=B	5=B	5=B
	Noxious Weeds	19=C	30=C	29=C	48=D	50=D	50=D	50=D
	Woody Vegetation	4=A	4=A	3=A	7=B	5=B	5=B	5=B
	Woody Veg. Control for Vision	0=A	1=A	1=A	5=B	5=B	3=A	3=A

# E. 2007 Compass Rating Sheet



🖋 🍒 2007 Compass Rating Sheet Wisconsin Department of Transportation

#### «MySegment», «MyRoute», «MyCounty», «MyDistrict» Directions: «PrimaryDir» Alternate Directions: «AltDir»

Date	Survey	Taken:
Duio	JUI V C Y	Tukon.

Start Time:

Stop Time:

Reviewed by:

Segments can only be discarded for the following reasons. If this segment meets one of these criteria, please check the appropriate box and add the next highest numbered "spare" segment to your list of segments to be rated. Please enter the reject reason in the database.  $\Box$  A piece or all of the segment falls on a bridge. A piece or all of the segment is currently under construction.  $\square$  We believe it would be unsafe to rate this segment.  $\square$  We cannot locate this segment.

□ An organization other than WisDOT is responsible for the maintenance of ANY of the four elements within this section.

Shoulders	Standard	Value	Comments
Hazardous Debris (S-1)	Number of items large enough to cause a safety hazard		
Paved Shoulde	r □None (If none, skip to Unpaved Shoulder)		
<b>Cracking</b> (S-2)	Linear ft. of unsealed cracks greater than ¼" (up to 150' on undivided or 300' on divided hwy).		
Potholes/ Raveling (S-3)	Total sq. ft. of BOTH potholes AND raveling greater than 1 ft ² x 1" deep		
<b>Unpaved Shou</b>	lder 🛛 None (If none, skip to Drainage)		
Drop off/ build-up (S-4)	Linear ft. of <u>paved-to-unpaved</u> drop-off/build-up greater than 1.5"		
Cross Slope (S-5)	Linear ft. with unpaved cross slope greater than 2x planned angle		
Erosion (S-6)	Linear ft. with ruts deeper than 2 inches.		

Drainage			Value	Comments
Ditches (D-1)	□ None	Total linear ft. of ditch. Linear ft. with more than minimal erosion of ditch line OR obstructions to the flow of water requiring action.		
Culverts (D-2)	□ None	Total number of culverts. Number more than 25% obstructed OR where a sharp object (a shovel) can be pushed thru bottom of pipe OR pipe is collapsing.		
Under/ Edge Drain (D-3)	□ None	Total number of drains. Number with outlets, endwalls or end protection closed or crushed OR where water flow or end protection is obstructed.		
Flumes (D-4)	□ None	Total number of flumes. Number not functioning as intended OR deteriorated to the point that they are causing erosion.		
Curb & Gutter (D-5)	□ None	Total linear ft. of curb and gutter. Linear ft. with severe structural distress OR more than 1" structural misalignment OR more than 1" of debris build up in the curb line		
Storm Sewer (D-6)	□ None	Total number of inlets, catch basins and outlet pipes. Number with more than 50% capacity obstructed OR less than 80% structurally sound OR more than 1" vertical displacement OR not functioning as intended.		

Roadsides			Value	Comments
<b>⊟ Litter</b> (R-1)		er of pieces (up to 15) of litter & non-natural encroachments on ers & roadside visible at posted speed, but not causing a safety		
Mowing (R-2)	If NC	g meets standard ), grass is mowed:  too wide too short too high in a no mow zone ), why:  safety/equipment mowed by property owner woody vegetation control maintenance decision	□yes □no	
⊜Mowing Vision (R-2)	□ None	Grass blocks a vision triangle or sightlines	□yes □no	
Noxious Weeds (R-3)	Visible	clumps of noxious weeds are present	□yes □no	
Woody Vegetation (R-4)	zone O	er of instances in which a tree > 4" in diameter is present in the clear DR trees and/or branches overhang the roadway or shoulder creating rance problem.		
⇔Woody Vegetation Vision (R-4)	Woody	v vegetation causes a vision problem	□yes □no	
Fences (R-5)	□ None	Total linear ft. of right-of-way fence. Linear ft. missing OR not functioning as intended		
Walls & Barriers (R-6)	□ None	Total linear ft. of retaining walls and noise barriers. Linear ft. not functioning as intended.		

Traffic Control	and Safe	ety	Value	Comments
Centerline Markings (T-1)	□ None	Over total segment, > 20% centerline paint missing	□yes □no	
Edgeline Markings (T-1)	□ None	Over total segment, > 20% edgeline paint missing	□yes □no	
Special Pavement Markings (T-2)	□ None	Total number Number missing OR not functioning as intended		
Regulatory/ Warning Signs (T-3)	□ None	Total number Number missing OR not visible at posted speed		
<b>⇔ Other Signs</b> (T-4)	□ None	Total number Number missing OR not visible at posted speed		
<b>⇔ Delineators</b> (T-5)	□ None	Total number. Number missing OR not visible at posted speed OR damaged		
Protective Barriers (T-6)	□ None	Total linear ft. of beam guard, concrete barrier, & cable guard Linear ft. of protective barriers not functioning as intended		

Indicates some or all of feature rating must be completed while driving at posted speed OR rated through the eyes of a driver traveling at posted speed.

528 ft
1056 ft
1584 ft
2112 ft

Rating sheets should be entered into your laptop database and emailed or given to your LAN administrator by October 16, 2007

Questions? Please call Scott Bush, Compass Program Manager, at 608-266-8666