US 141 IMPROVEMENTS
VILLAGE OF CRIVITZ

PROJECT ID 1490-46-00
MARINETTE COUNTY

DECEMBER 2023

DESIGN SUMMARY

- Roadway Diet: Converting the existing 4-lane roadway to a 3-lane two-way left turn lane (TWLTL) with new pavement markings. Dedicated left turn lanes for US 141 will be provided at intersections with Oak Street and Pine Avenue.
- Resurfacing: Remove the top 2" of asphalt and resurface with 2" of brand new asphalt.
- Intersection Improvements at County W - The existing traffic signals at the US 141 and County W intersection will be upgraded to include left turn arrows for the new left turn lane and phases for northbound and southbound US 141 traffic. Curbs will be reconstructed with concrete truck aprons behind to allow for trucks to make turning movements.
- Intersection Improvements at Oak Street - Improvements at the intersection to include a 200' dedicated right turn lane for northbound US 141 traffic.
- Railroad Crossing Rehabilitation - Install raised medians at the southern and northern approaches to the railroad crossing. Rehabilitate the existing railroad track and replace the existing concrete approaches with asphalt.
- Flume Installation - Remove the existing inlets and replace them with asphalt flumes that will reduce maintenance needs and costs.

SUMMARY OF IMPACTS

Temporary Right of Way Acquisition	0.022 acres (3 total properties)
Permanent Right of Way Acquisition	0.026 acres (3 total properties)
Driveway Access Changes	1 - reduced to right-in/right-out
Utility Relocations	1 - power pole
Current Estimated Construction Cost	$1,250,000