

ENGINEER'S ESTIMATE

PROJECT ID: 1177-11-22, Parcels 42, 55, 58, USH 51, Town of Cassian & Hazelhurst (Rocky Run Road - CTH Y), USH 51, Oneida County

ID/Parcel# /Address/Description	Estimated Razing Costs	Estimated Asbestos Removal Costs	Total Estimated Removal Costs
ID: 1177-11-22, Parcel 42: Hwy 51, Hazelhurst, WI. One-story (600 sq. ft.) residential structure with no basement. Exterior walls consist of concrete block. Interior finishes include poured concrete floor, raised wood flooring and wood partitioned walls with paneling, particleboard, peg-board and drywall. Septic system is on east side of structure with drain field to north of building. Well is located near southwest corner of structure.	\$6,000	\$1,000	\$7,000
ID: 1177-11-22, Parcel 55: 5899 Hwy 51, Hazelhurst, WI. One-story (1,000 sq. ft.) wood framed single family residence with a crawl space, large detached wood-framed garage (480 sq. ft.) with Masonite siding and gravel driveway. Exterior walls consist of vinyl siding over cedar lap siding and asphalt shingles. Interior finishes include wood paneling and car siding, wood, carpet and tile and linoleum floorings. Well is located in southwest corner of home and septic system is located east of driveway and west of highway right of way line.	\$11,900	\$1,000	\$12,900
ID: 1177-11-22, Parcel 58: 5977 Hwy 51, Hazelhurst, WI. Two-story (1,100 sq. ft.) wood framed single family residence with concrete slab foundation and no basement, 2-car attached wood-framed garage (850 sq. ft.) with asphalt shingles and metal roof, poured concrete and wood block foundation, and gravel driveway. Exterior walls consist of wood siding and asphalt shingles. Interior finishes include wood, drywall or melamine walls, wood, carpet, ceramic and tile floorings. Well is in garage and septic is located at south end of house.	\$14,400	\$1,000	\$15,400
Total:	\$32,300	\$3,000	\$35,300

The estimates are based on the current rates for demolition of these types and sizes of structures.