



### **35.6.1 Testing**

#### **35.6.1.1 Controllers and Detectors**

Reference Standard Specifications 675.3(14) through 675.3(20) for testing procedures. In 675.3(15), traffic flow information includes volume and speed data.

#### **35.6.1.2 Field System Integrator**

Refer to Standard Specification 670.3.2.1 for field system integrator duties.

Contractor-furnished equipment and materials, refer to Standard Specification 670.3.3.1.

Department-furnished equipment and materials, refer to Standard Specification 670.3.3.2

### **35.6.2 Acceptance**

Notify the State Traffic Operations Center after testing is complete. The State Traffic Operations Center Maintenance Representative will do the final concurrence of acceptance before the State Traffic Operations Center accepts ownership and maintenance of the PCMS.