

**ADDENDUM
CONFIRMATION REQUIRED**

For the letting of October 30, 2014

Date: Tuesday, September 30, 2014

For Proposal Number: 01

Attached is addendum number : 01

Number of pages attached: 3

Sender: Wisconsin Department of Transportation
Division of Transportation System Development
Northeast Region – Green Bay State Office Building
944 Vanderperren Way
Green Bay, WI 54304

Attention: Ruth Johnson, Property Management

Phone: (920) 492-2386

Fax: (920) 492-0144

Email: Ruth.Johnson@dot.wi.gov


**Please acknowledge receipt of this transmittal,
whether bidding on the project or not,
by filling out the information below and return
via email, fax, or by mail
prior to 4:00 PM, Friday, October 24, 2014**

Reminder: This addenda must be attached to the bidding documents when submitting your bid.

Individual responding: _____

On behalf of: _____

We acknowledge receipt of the above mentioned addendum.



Wisconsin Department of Transportation

September 30, 2014

Division of Transportation Systems Development

Bureau of Project Development
4802 Sheboygan Avenue, Rm 601
P O Box 7916
Madison, WI 53707-7916

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #01: 9180-28-21, Parcel 1
Oconto Falls - Oconto
Cream City Rd Intersection
STH 22
Oconto County

4075-28-21, Parcel 27
Village of Wrightstown
Fox River Bridge & Approaches
STH 96
Brown County

1146-75-21, Parcel 10
STH 76 – New London
Lilly Valley Rd/CTH T/Givens Rd
STH 15
Outagamie County

9202-12-21, Parcel 9
STH 29 Corridor Plan
WCL – CTH J
STH 29
Brown County

Letting of October 30, 2014

This is Addendum No. 1, which provides for the following:

Special Provisions

Revised Special Provisions	
Article No.	Description
20	Removal and Razing Operations

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 1

9180-28-21, 1146-75-21, 4075-28-21, & 9202-12-21

September 30, 2014

Special Provisions

20. Removal and Razing Operations.

Remove entire language and replace with the following:

Projects 9180-28-21, Parcel 1; 1146-75-21, Parcel 10; 9202-12-21, Parcel 9

This work shall be in accordance with section 204 of the standard specifications and as hereinafter provided.

Furnish all labor, equipment, tools, transportation, and incidentals necessary for the performance of the work.

Remove all concrete steps, concrete sidewalks, and concrete slabs from the premises.

In compliance with the ordinances and permit requirements of the municipality in which the buildings are situated, and in the presence of the local governing unit, a certified/licensed well driller, pump installer or water system operator shall seal or abandon all sewer and water lines and/or wells pursuant to Wisconsin Statute 280.30 and the Natural Resources portion of the Wisconsin Administrative Code covered under NR 811 and 812..

Until standing walls have been razed, the walls shall be reasonably and safely braced at all times to ensure complete safety during the wrecking operations.

Break, roll, and remove all basement walls, floors, and footings in their entirety from the site.

Dispose of all non-hazardous demolition waste in a landfill licensed or approved in writing by the Department of Natural Resources and in accordance with NR500, Wisconsin Administrative Code. Failure to properly dispose of solid waste is a violation of State Solid Waste Statutes and Administrative code and is subject to issuance of a citation under Wisconsin Statute 287.81(2)(a).

Remove all hazardous materials from the site, **only** after proper notification and compliance with the department requirements of the Wisconsin Department of Natural Resources and local government regulations.

Remove all material from the premises in a safe manner and in compliance with all applicable laws and ordinances. Do not disturb adjacent property.

Project 4075-28-21, Parcel 27

This work shall be in accordance with section 204 of the standard specifications and as hereinafter provided.

Furnish all labor, equipment, tools, transportation, and incidentals necessary for the performance of the work.

Remove all concrete steps and concrete sidewalks from the premises.

In compliance with the ordinances and permit requirements of the municipality in which the buildings are situated, and in the presence of the local governing unit, a certified/licensed well driller, pump

installer or water system operator shall seal or abandon all sewer and water lines and/or wells pursuant to Wisconsin Statute 280.30 and the Natural Resources portion of the Wisconsin Administrative Code covered under NR 811 and 812..

Until standing walls have been razed, the walls shall be reasonably and safely braced at all times to ensure complete safety during the wrecking operations.

The floor, foundation, and footings shall remain in place. There are 3 monitoring wells located around the building. They are flush mounted and shall not be disturbed.

Dispose of all non-hazardous demolition waste in a landfill licensed or approved in writing by the Department of Natural Resources and in accordance with NR500, Wisconsin Administrative Code. Failure to properly dispose of solid waste is a violation of State Solid Waste Statutes and Administrative code and is subject to issuance of a citation under Wisconsin Statute 287.81(2)(a).

Remove all hazardous materials from the site, **only** after proper notification and compliance with the department requirements of the Wisconsin Department of Natural Resources and local government regulations.

Remove all material from the premises in a safe manner and in compliance with all applicable laws and ordinances. Do not disturb adjacent property.

END OF ADDENDUM