



Wisconsin Department of Transportation

January 6, 2015

Division of Transportation Systems Development

Bureau of Project Development
4802 Sheboygan Avenue, Rm 601
P O Box 7916
Madison, WI 53707-7916

NOTICE TO ALL CONTRACTORS:

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

**Proposal #05: 5255-01-61, WISC 2015 004
Mineral Point – Spring Green
Lower Wyoming Road to N County Line
STH 23
Iowa County**

Letting of January 13, 2015

This is Addendum No. 1, which provides for the following:

Special Provisions

Added Special Provisions	
Article No.	Description
23	Beam Guard

Schedule of Items

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
204.0115	Removing Asphaltic Surface Butt Joints	SY	4260	4340	4340

Plan Sheets

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
34	Miscellaneous Quantities

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01

5255-01-61

January 6, 2015

Special Provisions

23. Beam Guard

Supplement standard spec 614 as follows:

All beam guard posts, including thrie beam and energy absorbing terminal sections, shall be timber posts.

Schedule of Items

Attached, dated January 6, 2015, are the revised Schedule of Items Page 1.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:
Revised: 34

END OF ADDENDUM

**204.0115
REMOVING ASPHALTIC SURFACE BUTT JOINTS**

STATION	LOCATION	(SY)
582+00	MAINLINE	473
583+00	LOWER WYOMING RD	80
589+68.80	MAINLINE	472
590+23.20	MAINLINE	472
582+00	RUSH CREEK R & G CLUB	53
589+68.80	MAINLINE	62
609+65	HILLSIDE SCHOOL ROAD	62
706+17.20	MAINLINE	472
706+62.70	CTH T	472
719+50	MAINLINE	76
723+62.00	MAINLINE	472
723+99.30	MAINLINE	472
748+25	CTH C, WEST	71
756+40	CTH C, EAST	76
758+73.00	UNDISTRIBUTED DRIVEWAYS	473
		80
	TOTAL	4340

**204.0157
REMOVING CONCRETE BARRIER**

STATION	LOCATION	(LF)
589+61.7	MAINLINE RT	91
589+50	MAINLINE LT	90
590+21.8	MAINLINE RT	86
590+41.3	MAINLINE LT	87
709+23.0	MAINLINE LT & RT	171
709+63.0	MAINLINE RT	109
722+63.0	MAINLINE LT	112
723+47.0	MAINLINE RT	86
724+75.0	MAINLINE LT	94
724+07.0	MAINLINE RT	86
724+12.0	MAINLINE LT	86
	TOTAL	1100

**614.0920
SALVAGED RAIL**

CATEGORY	STATION	LOCATION	(L.F.)
	619+39.40	833+79.00	1463
	622+94.90	823+85.00	92
	629+16.40	830+69.50	156
	756+57.00	758+66.00	313
	756+92.00	758+66.00	176
		TOTAL	2200

**204.0180
REMOVING DELINEATORS AND MARKERS**

STATION	LOCATION	(EACH)
588+60	MAINLINE RT	1
591+65	MAINLINE LT	1
708+23	MAINLINE RT	1
710+73	MAINLINE LT	1
722+63	MAINLINE RT	1
723+53	MAINLINE LT	1
	TOTAL	6

**204.0245
REMOVING STORM SEWER (SIZE)**

STATION	LOCATION	SIZE (IN)	LF
590+25	MAINLINE, RT	15	10
709+65	MAINLINE, LT	15	10
709+65	MAINLINE, RT	15	10
724+15	MAINLINE, LT	15	10
	TOTAL		40

**305.0500
SHAPING SHOULDERS**

STATION	LOCATION	(STA)
525+00	MAINLINE, LT	232
525+00	MAINLINE, RT	232
	TOTAL	464

**204.0190
REMOVING SURFACE DRAINS**

STATION	LOCATION	(EACH)
588+60	MAINLINE, RT	1
	TOTAL	1

**204.0220
REMOVING INLETS**

STATION	LOCATION	(EACH)
590+25	MAINLINE, RT	1
709+65	MAINLINE, RT	1
724+15	MAINLINE, LT	1
	TOTAL	4

**416.1010
CONCRETE SURFACE DRAINS**

STATION	LOCATION	(CY)
590+40	MAINLINE, RT	7
709+75	MAINLINE, RT	2
709+75	MAINLINE, RT	3
	TOTAL	12

ASPHALTIC ITEMS 455.0105 455.0605 460.1101

STATION	LOCATION	ASPHALTIC MATERIAL PG58-28 (TON)	TACK COAT (GAL)	HMA PAVEMENT TYPE E-1 (TON)
582+00.00	MAINLINE, LT & RT	27	150	489
583+00.00	LOWER WYOMING ROAD	12	16	218
599+25.20	RUSH CREEK R & G CLUB	46	256	940
603+45.00	MAINLINE, LT & RT	2	14	31
619+68.00	MAINLINE, LT	56	308	1010
622+68.00	MAINLINE, RT	27	150	493
624+68.00	MAINLINE, LT	9	50	135
624+15.00	MAINLINE, RT	3	20	65
629+00.00	MAINLINE, RT	8	48	154
639+65.00	MAINLINE, RT	4	24	66
634+00.00	MAINLINE, RT	5	32	100
634+00.00	MAINLINE, LT & RT	215	1174	3870
	HILLTOP ROAD	2	14	32
	HILLSIDE SCHOOL ROAD	2	16	38
694+95.00	MAINLINE, LT & RT	32	178	596
707+00.00	MAINLINE, LT & RT	7	40	130
709+52.70	MAINLINE, LT & RT	5	38	118
711+55.00	MAINLINE, LT & RT	21	116	378
718+25.00	MAINLINE, LT & RT	1	64	200
	CTH T	2	16	31
721+00.00	MAINLINE, LT & RT	3	20	66
722+00.00	MAINLINE, LT & RT	5	36	109
723+98.30	MAINLINE, LT & RT	8	50	152
724+25.00	MAINLINE, LT & RT	13	70	245
747+00.00	MAINLINE, LT & RT	13	70	245
	CTH C, WEST	3	20	67
759+75.00	MAINLINE, LT & RT	5	36	109
753+00.00	MAINLINE, LT & RT	18	104	337
753+00.00	MAINLINE, LT & RT	3	20	63
757+50.00	MAINLINE, LT & RT	18	104	337
757+50.00	MAINLINE, LT & RT	3	20	63
757+50.00	MAINLINE, LT & RT	4	26	76
	TOTALS	890	3,200	10,510

**490.0200
SALVAGED ASPHALTIC PAVEMENT MILLING**

STATION	LOCATION	(SY)
582+20.00	MAINLINE, LT & RT	2756
583+00.00	LOWER WYOMING RD	216
590+43.20	MAINLINE, LT & RT	38531
	RUSH CREEK R & G CLUB	134
	HILLTOP RD	126
	HILLSIDE SCHOOL RD	161
684+95.00	MAINLINE, LT & RT	3904
708+45.00	MAINLINE, LT & RT	174
709+72.70	MAINLINE, RT	2283
709+72.70	MAINLINE, LT	1420
	MAINLINE, LT	735
718+25.00	MAINLINE, LT	403
721+00.00	MAINLINE, LT & RT	419
725+45.00	MAINLINE, LT & RT	5536
725+45.00	CTH C, WEST	266
748+05.00	MAINLINE, LT & RT	3098
	CTH C, EAST	242
	TOTAL	62,500

**306.0110
BASE AGGREGATE DENSE 3/4-INCH**

STATION	LOCATION	(TON)
582+00.00	MAINLINE LT & RT	21
590+23.20	MAINLINE LT & RT	35
603+45.00	MAINLINE LT & RT	40
618+50.00	MAINLINE LT	83
618+50.00	MAINLINE RT	5
622+00.00	MAINLINE RT	15
629+00.00	MAINLINE RT	5
631+00.00	MAINLINE RT	15
631+00.00	MAINLINE RT	4
639+00.00	MAINLINE LT & RT	90
639+00.00	MAINLINE LT & RT	132
708+45.00	MAINLINE LT & RT	31
718+25.00	MAINLINE RT	10
723+99.30	MAINLINE LT & RT	101
724+45.00	MAINLINE LT & RT	224
748+05.00	MAINLINE LT & RT	8
	SIDEROADS	5
	DRIVEWAYS	5
	TOTAL	990

Addendum No. 1
ID 5255-01-60
Revised Sheet 34
January 6, 2015

NOTE: ALL ITEMS ARE CATEGORY 0010, UNLESS OTHERWISE NOTED.

SCHEDULE OF ITEMS

REVISED:

CONTRACT:
20150113005PROJECT(S):
5255-01-61FEDERAL ID(S):
WISC 2015004

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS

SECTION 0001 Contract Items

0010	204.0115 Removing Asphaltic Surface Butt Joints	4,340.000 SY
0020	204.0157 Removing Concrete Barrier	1,100.000 LF
0030	204.0180 Removing Delineators and Markers	6.000 EACH
0040	204.0190 Removing Surface Drains	1.000 EACH
0050	204.0220 Removing Inlets	4.000 EACH
0060	204.0245 Removing Storm Sewer (size) 01. 15-Inch	40.000 LF
0070	213.0100 Finishing Roadway (project) 01. 5255-01-61	1.000 EACH
0080	305.0110 Base Aggregate Dense 3/4-Inch	900.000 TON
0090	305.0500 Shaping Shoulders	464.000 STA
0100	416.1010 Concrete Surface Drains	12.000 CY