

December 16, 2015

#### Division of Transportation Systems Development Bureau of Project Development 4802 Sheboygan Avenue, Rm 601

4802 Sheboygan Avenue, Rm 60 P O Box 7916 Madison, WI 53707-7916

Telephone: (608) 266-1631 Facsimile (FAX): (608) 266-8459

# NOTICE TO ALL CONTRACTORS:

Proposal #26: 5105-16-60 Statewide Tree Clearing Various Locations Non Highway Statewide

# Letting of January 12, 2016

This is Addendum No. 01, which provides for the following:

# **Special Provisions**

|                | Revised Special Provisions |
|----------------|----------------------------|
| Article<br>No. | Description                |
| 4              | Prosecution and Progress   |
| 5              | Traffic                    |

|                | Added Special Provisions  |  |  |  |  |
|----------------|---|--|--|--|--|
| Article<br>No. | Description   |  |  |  |  |
| 25             | Mobilization and Traffic Control Site 5, Item SPV.0105.05; Site 6, Item SPV.0105.06; Site 7, Item SPV.0105.07; Site 8, Item SPV.0105.08 |  |  |  |  |

| Deleted Special Provisions |  |  |  |  |
|----------------------------|--|--|--|--|
| Article                    | Description  |  |  |  |
| No.                        | Description  |  |  |  |
| 6 – 9                      | Utilities (Sites 1 – 4)  |  |  |  |
|                            | Mobilization and Traffic Control Site 1, Item SPV.0105.01; Site 2, Item SPV.0105.02; Site 3, |  |  |  |
| 24                         | Item SPV.0105.03; Site 4, Item SPV.0105.04; Site 5, Item SPV.0105.05; Site 6, Item           |  |  |  |
|                            | SPV.0105.06; Site 7, SPV.0105.07; Site 8, Item SPV.0105.08.                                  |  |  |  |

## Schedule of Items

| Revised Bid Item Quantities |                  |      |                 |                     |                   |
|-----------------------------|------------------|------|-----------------|---------------------|-------------------|
| Bid Item                    | Item Description | Unit | Old<br>Quantity | Revised<br>Quantity | Proposal<br>Total |
| 201.0105                    | Clearing         | STA  | 618             | -64                 | 554               |

| Deleted Bid Item Quantities                         |   |      |          |          |          |  |
|---|---|------|----------|----------|----------|--|
| Bid Item  | Item Description                                    | Unit | Old      | Revised  | Proposal |  |
| Did item  | Refit Description                                   |      | Quantity | Quantity | Total    |  |
| SPV.0105.01   | Mobilization and Traffic Control Site 1             | LS   | 1        | -1       | 0        |  |
| SPV.0105.02   | SPV.0105.02 Mobilization and Traffic Control Site 2 |      | 1        | -1       | 0        |  |
| SPV.0105.03 Mobilization and Traffic Control Site 3 |   | LS   | 1        | -1       | 0        |  |
| SPV.0105.04   | Mobilization and Traffic Control Site 4             | LS   | 1        | -1       | 0        |  |

## **Plan Sheets**

|               | Revised Plan Sheets                                      |
|---------------|--|
| Plan<br>Sheet | Plan Sheet Title (brief description of changes to sheet) |
| 18            | Miscellaneous Quantities (removed Clearing Sites 1 – 4)  |
| 19            | Miscellaneous Quantities (removed Clearing Sites 1 – 4)  |

|               | Deleted Plan Sheets   |
|---------------|---|
| Plan<br>Sheet | Plan Sheet Title (brief description of why sheet was deleted) |
| 4 – 7         | Sites 1 – 4 Location Maps                                     |
| 12 – 14       | Sites 1 – 4 Overview  |
| 20 – 29       | Sites 1 – 4 Plans   |

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist Proposal Management Section

# ADDENDUM NO. 01 5105-16-60 December 16, 2015

#### **Special Provisions**

#### 4. Prosecution and Progress.

Replace entire article language with the following:

Begin work within five calendar days after the engineer issues a written notice to do so.

#### Northern Long-eared Bat (Myotis septentrionalis)

Northern Long-eared Bats (NLEB) have the potential to inhabit the project limits because they roost in trees and structures (bridges, culverts, buildings). Roosts may not have been observed on this project, but conditions to support the species exist. The species and all active roosts are protected by the Federal Endangered Species Act.

In order to avoid adverse impacts upon the NLEBs, no vegetation clearing and grubbing within the identified clearing and grubbing limits will be allowed from April 1 to September 30, both dates inclusive.

If the required clearing and removal is not completed by March 31, the department will assess the contractor \$2,000 in interim liquidated damages for each calendar day that clearing and removal remains incomplete beyond 12:01 AM, March 31. An entire calendar day will be charged for any period of time within a calendar day that the clearing and removal remains incomplete beyond 12:01 AM.

Submit a schedule and description of Clearing operations 5 days prior to any Clearing operations.

#### 5. Traffic.

#### Replace entire article language with the following:

Keep all lanes open to through traffic at all times when shoulders are available. Temporary shoulder closures conforming to the standard detail drawings 'Traffic Control, Shoulder Closure on Divided Roadway, Speeds Greater than 40 M.P.H.' and 'Traffic Control, Work on Shoulder or Parking Lane, Undivided Roadway' will be allowed.

In urban locations without shoulder or parking lanes, lane closures conforming to 'Traffic Control for Lane Closure (Suitable for Moving Operations)' will be allowed.

Do not park or store equipment, vehicles or construction materials on any roadway carrying traffic during non-working hours.

Do not implement a lane closure during inclement weather or poor visibility.

#### USH 51 (Site 7)

During working hours, traffic on USH 51 may be restricted to a single lane in either direction only between the hours of 8:00 AM and 2:00 PM Monday through Friday, and 7:00 AM to 3:00 PM Saturday and Sunday.

## Wisconsin Lane Closure System Advance Notification

Provide the following advance notification to the engineer for incorporation into the Wisconsin Lane Closure System (LCS).

## TABLE 108-1 CLOSURE TYPE AND REQUIRED MINIMUM ADVANCE NOTIFICATION

| Closure type without height, weight, or width restrictions (available width, all lanes in one direction >16') | MINIMUM<br>NOTIFICATION |
|---|-------------------------|
| Lane and shoulder closures  | 3 business days         |

Discuss LCS completion dates and provide changes in the schedule to the engineer at weekly project meetings in order to manage closures nearing their completion date.

- 6. DELETED
- 7. DELETED
- 8. DELETED
- 9. DELETED
- 24. DELETED

# 25. Mobilization and Traffic Control Site 5, Item SPV.0105.05; Site 6, Item SPV.0105.06; Site 7, SPV.0105.07; Site 8, Item SPV.0105.08.

#### A Description

Provide mobilization conforming to standard spec 619.

Provide traffic control conforming to standard spec 643. Provide all traffic control required to perform closures as shown in standard detail drawing (SDD) 'Traffic Control, Shoulder Closure on Divided Roadway, Speeds Greater than 40 M.P.H.,' SDD 'Traffic Control, Work on Shoulder or Parking Lane, Undivided Roadway' and SDD 'Traffic Control for Lane Closure (Suitable for Moving Operations),' or as directed by the engineer.

#### B (Vacant)

#### C (Vacant)

#### **D** Measurement

The department will measure Mobilization and Traffic Control (Location) as a single lump sum unit of work for each site, acceptably completed.

#### E Payment

The department will pay for measured quantities at the contract unit price under the following bid items:

| ITEM NUMBER | DESCRIPTION                             | UNIT |
|-------------|---|------|
| SPV.0105.05 | Mobilization and Traffic Control Site 5 | LS   |
| SPV.0105.06 | Mobilization and Traffic Control Site 6 | LS   |
| SPV.0105.07 | Mobilization and Traffic Control Site 7 | LS   |
| SPV.0105.08 | Mobilization and Traffic Control Site 8 | LS   |

Payment is full compensation for supplying and providing all materials, facilities, and services, and for performing all work necessary to complete this contract bid item.

Payment is also full compensation for providing, constructing, assembling, painting, hauling, erecting, re-erecting, maintaining, restoring, and removing traffic signs, drums, barricades, and similar control devices, including arrow boards; for partially or fully covering or uncovering signs; for providing, placing, and maintaining lights, including the fuel or power; and for providing, applying, and removing pavement markings.


#### Schedule of Items

Attached, dated December 16, 2015, are the revised Schedule of Items Page 1.

#### **Plan Sheets**

The following  $8\frac{1}{2} \times 11$ -inch sheets are attached and made part of the plans for this proposal: Revised: 18 and 19

END OF ADDENDUM



c

| 109+87 (AH) |
|-------------|
| 127+00 (AH) |
| 130+50 (AH) |
| 133+73      |
| 144+17      |
| 148+62      |
| 151+06      |
| 155+00      |
| 9T+79T      |
| 07+9/T      |
| 181+41      |
| 190+38      |
| 209+08      |
| 212+43      |
| 248+22      |
| 266+00      |
| 306+16      |
| 341+33      |
| 377+25      |
| 425+61      |
| 429+37      |
| 431+70      |
| 439+03      |
| 101+50      |
| 98+25       |
| 197+50      |
| 18+69       |
| TOTAL       |
|             |
|             |
|             |
|             |
|             |
|             |
|             |
|             |
|             |
|             |
|             |

|                          | Wisconsin Department c    | of Transportation    | PAGE:<br>DATE: | 1<br>12/16/15 |
|--------------------------|---------------------------|----------------------|----------------|---------------|
|                          | SCHEDULE OF               | ITEMS                | REVISED:       |               |
| CONTRACT:<br>20160112026 | PROJECT(S):<br>5105-16-60 | FEDERAL ID(S)<br>N/A | :              |               |

CONTRACTOR :\_\_\_\_\_

| LINE | ITEM        | APPROX.   | UNIT PRICE  | BID AMOUNT  |
|------|-------------|-----------|-------------|-------------|
| NO   | DESCRIPTION | QUANTITY  |             |             |
|      |             | AND UNITS | DOLLARS CTS | DOLLARS CTS |
|      |             |           |             |             |

SECTION 0001 Statewide Tree Clearing

| 0010 | 201.0105 Clearing  | <br> <br> STA       | 554.000 | <br> <br>  .       | <br> <br>  . |
|------|--|---------------------|---------|--------------------|--------------|
| 0060 | SPV.0105 Special 05.<br>Mobilization And Traffic<br>Control Site 5 | <br> <br>  LUMP<br> |         | <br> LUMP<br>      | <br> <br>  . |
| 0070 | SPV.0105 Special 06.<br>Mobilization And Traffic<br>Control Site 6 | <br> <br>  LUMP<br> |         | <br> LUMP<br>      | <br> <br>  . |
| 0080 | SPV.0105 Special 07.<br>Mobilization And Traffic<br>Control Site 7 | <br> LUMP<br>       |         | <br> LUMP<br>      | <br> <br>  . |
| 0090 | SPV.0105 Special 08.<br>Mobilization And Traffic<br>Control Site 8 | <br> LUMP<br>       |         | <br> <br> LUMP<br> | <br> <br>  . |
|      | SECTION 0001 TOTAL   |                     |         | <br> <br>          | ·            |
|      | TOTAL BID  |                     |         |                    |              |