



# Wisconsin Department of Transportation

May 3, 2018

## Division of Transportation Systems Development

Bureau of Project Development  
4802 Sheboygan Avenue, Rm 601  
P O Box 7916  
Madison, WI 53707-7916

Telephone: (608) 266-1631  
Facsimile (FAX): (608) 266-8459

### NOTICE TO ALL CONTRACTORS:

**Proposal #40: 7730-20-60**  
**Cream - Mondovi**  
**CTH U to STH 37**  
**STH 88**  
**Buffalo County**

### Letting of May 8, 2018

This is Addendum No. 02, which provides for the following:

#### Schedule of Items:

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
614.0200	Steel Thrie Beam Structure Approach	LF	0	83	83

Deleted Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
614.0230	Steel Thrie Beam	LF	83	-83	0

#### Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
14	Miscellaneous Quantities – Revised quantity table

**Schedule of Items**

Attached, dated May 3, 2018 are the revised Schedule of Items Pages 1 – 4.

**Plan Sheets**

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: Page 14

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

*Mike Coleman*

Proposal Development Specialist  
Proposal Management Section

END OF ADDENDUM

**CONCRETE SIDEWALK**

602.040		602.050	
PROJECT ID	STATION - LOCATION	CONCRETE SIDEWALK 5-INCH	CURB RAMP DETECTABLE WARNING FIELD YELLOW
7730-02-60	1355+76 - 1355+88	(SF) 18	(SF) 10
TOTAL		18	10

**BEAM GUARD**

614.2300		614.2610		614.0305		614.0370	
PROJECT ID	STATION - LOCATION	MGS GUARDRAIL	STEEL PLATE BEAM GUARDRAIL	STEEL PLATE BEAM GUARDRAIL CLASS	STEEL BEAM ABSORBING TERMINAL	STEEL PLATE BEAM GUARDRAIL CLASS	STEEL BEAM ABSORBING TERMINAL
7730-02-60	1331+90 - 1334+84	(LF) 188	(EA) 2	(LF) 188	(EA) 2	(LF) 188	(EA) 2
7730-02-60	1395+47 - 1398+78	(LF) 225	(EA) 2	(LF) 225	(EA) 2	(LF) 225	(EA) 2
7730-02-60	1569+46 - 1570+89	(LF) 43	(EA) 4	(LF) 43	(EA) 4	(LF) 43	(EA) 4
7730-02-60	1572+84 - 1573+89	(LF) 5	(EA) 1	(LF) 5	(EA) 1	(LF) 5	(EA) 1
7730-02-60	1572+84 - 1574+27	(LF) 43	(EA) 4	(LF) 43	(EA) 4	(LF) 43	(EA) 4
TOTAL		413	4	413	4	413	4

**EROSION CONTROL**

625.0500		628.2004		628.1504		628.0210		630.0330	
PROJECT ID	STATION - LOCATION	SALVAGED TOPSOIL CLASS I	EROSION MAT TYPE B	FERTILIZER TYPE B	SEEDING MIXTURE NO. 30	BORROW PIT	SEEDING	BORROW PIT	SEEDING
7730-02-60	1331+83 - 1334+93	(SY) 773	(SY) 300	(CWT) 0.49	(LB) 9	(LB) 9	(LB) 9	(LB) 9	(LB) 9
7730-02-60	1394+85 - 1399+97	(SY) 425	(SY) 52	(CWT) 0.28	(LB) 6	(LB) 6	(LB) 6	(LB) 6	(LB) 6
7730-02-60	1568+25 - 1570+87	(SY) 583	(SY) 262	(CWT) 0.43	(LB) 9	(LB) 9	(LB) 9	(LB) 9	(LB) 9
7730-02-60	1572+87 - 1575+66	(SY) 610	(SY) 279	(CWT) 0.39	(LB) 8	(LB) 8	(LB) 8	(LB) 8	(LB) 8
7730-02-60	1572+89 - 1575+68	(SY) 696	(SY) 280	(CWT) 0.45	(LB) 9	(LB) 9	(LB) 9	(LB) 9	(LB) 9
7730-02-60	UNDISTRIBUTED	(SY) 38	(SY) 94	(CWT) 0.03	(LB) 1	(LB) 1	(LB) 1	(LB) 1	(LB) 1
TOTAL		3,785	3,785	2,000	2,45	50	50	50	50

**MAINTENANCE AND REPAIR OF HAUL ROADS**

618.0000		619.0000	
PROJECT ID	STATION - LOCATION	MAINTENANCE AND REPAIR OF HAUL ROADS	MOBILIZATION
7730-02-60	1	(EA) 1	(EA) 1
TOTAL		1	1

**WATER**

624.0000		624.0000	
PROJECT ID	STATION - LOCATION	WATER	WATER
7730-02-60	30	(MGAL) 30	(MGAL) 30
TOTAL		30	30

**MOBILIZATION EROSION CONTROL**

628.1905		628.1910	
PROJECT ID	STATION - LOCATION	MOBILIZATIONS EROSION CONTROL	MOBILIZATIONS EROSION CONTROL
7730-02-60	2	(EA) 2	(EA) 2
TOTAL		2	2

**TRAFFIC CONTROL**

643.0300		643.0310.5		643.0900		643.5000	
PROJECT ID	STATION - LOCATION	TRAFFIC CONTROL DRUMS	TEMPORARY PORTABLE RUMBLE STRIPS	TRAFFIC CONTROL SIGNS	TRAFFIC CONTROL SIGNS	TRAFFIC CONTROL	TRAFFIC CONTROL
7730-02-60	1080	(DAY) 1	(LS) 1	(DAY) 2196	(DAY) 2196	(EA) 1	(EA) 1
TOTAL		1	1	2196	2196	1	1

**LOCATING NO PASSING ZONES**

646.0000		646.0000	
PROJECT ID	STATION - LOCATION	LOCATING NO-PASSING ZONES	LOCATING NO-PASSING ZONES
7730-02-60	1027+00 - 1516+00	(WP) 10.4	(WP) 10.4
TOTAL		10.4	10.4

**PAVEMENT MARKING**

PROJECT ID	STATION	LOCATION	MARKING LINE SAME ON BOTH SIDES			MARKING LINE STOP 18-INCH	MARKING LINE STOP 18-INCH	TEMPORARY MARKING LINE PAINT YELLOW 4-INCH
			YELLOW (LF)	WHITE (LF)	STOP 18-INCH			
7730-02-60	1027+00	1176+75	CL NP : NP	29,350	---	---	---	59,300
7730-02-60	1027+00	1053+00	RT EDGE LINE	---	2,600	---	---	---
7730-02-60	1027+00	1084+50	RT EDGE LINE	---	3,100	---	---	---
7730-02-60	1027+00	1253+70	LT EDGE LINE	---	25,670	---	---	---
7730-02-60	1176+75	1186+00	CL NP : SD	1,156	---	---	---	2,312
7730-02-60	1186+00	1192+50	CL NP : SD	1,063	---	---	---	2,126
7730-02-60	1201+00	1214+50	CL NP : NP	2,700	---	---	---	5,400
7730-02-60	1085+10	1329+50	RT EDGE LINE	---	24,440	---	---	---
7730-02-60	1214+50	1222+10	CL NP : SD	950	---	---	---	1,900
7730-02-60	1222+10	1238+50	CL SD	410	---	---	---	820
7730-02-60	1238+50	1246+50	CL SD : NP	1,000	---	---	---	2,000
7730-02-60	1254+50	1299+00	CL NP : NP	10,500	---	---	---	21,000
7730-02-60	1299+00	1307+00	LT EDGE LINE	---	7,310	---	---	---
7730-02-60	1307+00	1321+00	CL NP : SD	4,000	---	---	---	8,000
7730-02-60	1321+00	1327+60	CL NP : NP	350	---	---	---	700
7730-02-60	1327+60	1327+60	STOP BAR	12	---	---	---	24
7730-02-60	1329+10	1329+10	STOP BAR	12	---	---	---	24
7730-02-60	1329+10	1329+50	CL NP : SD	50	---	---	---	100
7730-02-60	1329+10	1329+50	LT EDGE LINE	---	40	---	---	80
7730-02-60	1328+60	1347+00	CL NP : NP	3,680	---	---	---	7,360
7730-02-60	1329+10	1339+00	LT EDGE LINE	---	990	---	---	1,980
7730-02-60	1329+10	1350+50	RT EDGE LINE	---	2,140	---	---	4,280
7730-02-60	1347+00	1352+70	CL NP : SD	713	---	---	---	1,426
7730-02-60	1352+70	1352+70	STOP BAR	438	---	---	---	876
7730-02-60	1352+70	1423+40	RT EDGE LINE	---	7,220	---	---	14,440
7730-02-60	1359+80	1563+30	LT EDGE LINE	---	22,350	---	---	44,700
7730-02-60	1370+20	1378+00	CL SD : NP	975	---	---	---	1,950
7730-02-60	1378+00	1395+50	CL NP : NP	3,500	---	---	---	7,000
7730-02-60	1395+50	1403+00	CL NP : SD	938	---	---	---	1,876
7730-02-60	1403+00	1419+50	CL SD	413	---	---	---	826
7730-02-60	1419+50	1427+70	CL SD : NP	1,025	---	---	---	2,050
7730-02-60	1427+70	1557+30	CL NP : NP	25,320	---	---	---	50,640
7730-02-60	1424+00	1439+80	RT EDGE LINE	---	1,550	---	---	3,100
7730-02-60	1439+80	1498+60	RT EDGE LINE	---	5,740	---	---	11,480
7730-02-60	1498+60	1537+20	RT EDGE LINE	---	1,460	---	---	2,920
7730-02-60	1537+20	1555+50	RT EDGE LINE	---	4,170	---	---	8,340
7730-02-60	1556+50	1562+80	RT EDGE LINE	---	630	---	---	1,260
7730-02-60	1563+90	1575+70	RT EDGE LINE	---	1,180	---	---	2,360
7730-02-60	1564+10	1575+70	LT EDGE LINE	---	1,160	---	---	2,320
7730-02-60	1557+30	1566+60	CL NP : SD	1,163	---	---	---	2,326
7730-02-60	1566+60	1570+50	CL SD	98	---	---	---	196
7730-02-60	1570+50	1575+70	CL SD : NP	650	---	---	---	1,300
TOTAL				89,630	108,780	---	---	179,860

Addendum No. 02  
ID 7730-02-60  
Revised Sheet 14  
May 3, 2018

NOTE: THE STATION LIMITS ARE APPROXIMATE. THE ACTUAL PAVEMENT MARKING LIMITS WILL BE DETERMINED IN THE FIELD BY THE LOCATING NO PASSING ZONES ITEM FOR PERMANENT MARKINGS AND BY THE EXISTING LOCATIONS FOR THE TEMPORARY MARKINGS. ABBREVIATIONS USED IN THIS TABLE: NP = NO PASSING, SD = SKP DASH.



## Proposal Schedule of Items

Proposal ID: 20180508040 Project(s): 7730-02-60

Federal ID(s): N/A

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	201.0105 Clearing	3.000 STA	_____.	_____.
0004	201.0205 Grubbing	3.000 STA	_____.	_____.
0006	204.0120 Removing Asphaltic Surface Milling	148,666.000 SY	_____.	_____.
0008	204.0155 Removing Concrete Sidewalk	9.000 SY	_____.	_____.
0010	204.0165 Removing Guardrail	697.000 LF	_____.	_____.
0012	205.0100 Excavation Common	340.000 CY	_____.	_____.
0014	208.0100 Borrow	1,808.000 CY	_____.	_____.
0016	211.0100 Prepare Foundation for Asphaltic Paving (project) 01. 7730-02-60	LS	LUMP SUM	_____.
0018	213.0100 Finishing Roadway (project) 01. 7730- 02-60	1.000 EACH	_____.	_____.
0020	305.0110 Base Aggregate Dense 3/4-Inch	15,121.000 TON	_____.	_____.
0022	305.0500 Shaping Shoulders	1,074.000 STA	_____.	_____.
0024	440.4410 Incentive IRI Ride	20,800.000 DOL	1.00000	20,800.00
0026	455.0605 Tack Coat	3,717.000 GAL	_____.	_____.
0028	460.2005 Incentive Density PWL HMA Pavement	22,620.000 DOL	1.00000	22,620.00
0030	460.2010 Incentive Air Voids HMA Pavement	22,620.000 DOL	1.00000	22,620.00
0034	460.6444 HMA Pavement 4 MT 58-34 H	30,790.000 TON	_____.	_____.



## Proposal Schedule of Items

Proposal ID: 20180508040 Project(s): 7730-02-60

Federal ID(s): N/A

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0036	465.0110 Asphaltic Surface Patching	125.000 TON	_____.	_____.
0038	465.0120 Asphaltic Surface Driveways and Field Entrances	251.000 TON	_____.	_____.
0040	602.0410 Concrete Sidewalk 5-Inch	78.000 SF	_____.	_____.
0042	602.0505 Curb Ramp Detectable Warning Field Yellow	10.000 SF	_____.	_____.
0046	614.0305 Steel Plate Beam Guard Class A	214.000 LF	_____.	_____.
0048	614.0370 Steel Plate Beam Guard Energy Absorbing Terminal	4.000 EACH	_____.	_____.
0050	614.2300 MGS Guardrail 3	413.000 LF	_____.	_____.
0052	614.2610 MGS Guardrail Terminal EAT	4.000 EACH	_____.	_____.
0054	618.0100 Maintenance And Repair of Haul Roads (project) 01. 7730-02-60	1.000 EACH	_____.	_____.
0056	619.1000 Mobilization	1.000 EACH	_____.	_____.
0058	624.0100 Water	30.000 MGAL	_____.	_____.
0060	625.0500 Salvaged Topsoil	3,785.000 SY	_____.	_____.
0062	628.1504 Silt Fence	2,000.000 LF	_____.	_____.
0064	628.1905 Mobilizations Erosion Control	2.000 EACH	_____.	_____.
0066	628.1910 Mobilizations Emergency Erosion Control	1.000 EACH	_____.	_____.
0068	628.2004 Erosion Mat Class I Type B	3,785.000 SY	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20180508040 Project(s): 7730-02-60

Federal ID(s): N/A

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0070	629.0210 Fertilizer Type B	2.450 CWT	_____.	_____.
0072	630.0130 Seeding Mixture No. 30	50.000 LB	_____.	_____.
0074	630.0300 Seeding Borrow Pit	5.000 LB	_____.	_____.
0076	642.5001 Field Office Type B	1.000 EACH	_____.	_____.
0078	643.0300 Traffic Control Drums	1,080.000 DAY	_____.	_____.
0080	643.0310.S Temporary Portable Rumble Strips	1.000 LS	_____.	_____.
0082	643.0900 Traffic Control Signs	2,196.000 DAY	_____.	_____.
0084	643.5000 Traffic Control	1.000 EACH	_____.	_____.
0086	646.4520 Marking Line Same Day Epoxy 4-Inch	198,410.000 LF	_____.	_____.
0088	646.6120 Marking Stop Line Epoxy 18-Inch	36.000 LF	_____.	_____.
0090	648.0100 Locating No-Passing Zones	10.400 MI	_____.	_____.
0092	649.0105 Temporary Marking Line Paint 4-Inch	179,260.000 LF	_____.	_____.
0094	650.8000 Construction Staking Resurfacing Reference	54,900.000 LF	_____.	_____.
0096	650.9000 Construction Staking Curb Ramps	1.000 EACH	_____.	_____.
0098	650.9910 Construction Staking Supplemental Control (project) 01. 7730-02-60	LS	LUMP SUM	_____.
0100	690.0150 Sawing Asphalt	1,080.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20180508040 Project(s): 7730-02-60

Federal ID(s): N/A

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0102	690.0250 Sawing Concrete	5.000 LF	_____.	_____.
0104	SPV.0060 Special 01. HMA Percent Within Limits (PWL) Test Strip Volumetrics	1.000 EACH	_____.	_____.
0106	SPV.0060 Special 02. HMA Percent Within Limits (PWL) Test Strip Density	1.000 EACH	_____.	_____.
0108	460.2007 Incentive Density HMA Pavement Longitudinal Joints	21,820.000 DOL	1.00000	21,820.00
0110	614.0200 Steel Thrie Beam Structure Approach	83.000 LF	_____.	_____.
	Section: 0001		Total:	_____.
			Total Bid:	_____.

