



# Wisconsin Department of Transportation

May 6, 2024

## Division of Transportation Systems Development

Bureau of Project Development  
4822 Madison Yards Way, 4<sup>th</sup> Floor South  
Madison, WI 53705

Telephone: (608) 266-1631  
Facsimile (FAX): (608) 266-8459

### NOTICE TO ALL CONTRACTORS:

**Proposal #15: 1130-66-76**  
**Appleton – De Pere**  
**CTH N Intchg**  
**CTH N**  
**Outagamie County**

### Letting of May 14, 2024

This is Addendum No. 01, which provides for the following:

#### Special Provisions:

Revised Special Provisions	
Article No.	Description
2.1	Prosecution and Progress

Added Special Provisions	
Article No.	Description
1.13	Notice to Contractor – Airport Operating Restrictions

#### Schedule of Items:

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Quantity Added	Proposal Total After Addendum
646.2005	Marking Line Paint 6-Inch	LF	0	185	185
646.5305	Marking Railroad Crossing Paint	Each	0	6	6

**Plan Sheets:**

<b>Revised Plan Sheets</b>	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
141	Miscellaneous Quantities (updated tables, additional items)

<b>Added Plan Sheets</b>	
Plan Sheet	Plan Sheet Title (brief description of why sheet was added)
94A-94C	Pavement Markings (additional work at railroad crossings)

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

*Mike Coleman*

Proposal Development Specialist  
Proposal Management Section

**ADDENDUM NO. 01**

**1130-66-76**

**May 6, 2024**

**Special Provisions**

**1.13 Notice to Contractor – Airport Operating Restrictions.**

Fill out the Federal Aviation Administration (FAA) Notice Criteria Tool for all permanent structures (bridge, light pole, etc.) or equipment (crane, etc.) used during construction.

<https://oeaaa.faa.gov/oeaaa/external/portal.jsp>

If required by the Notice Criteria Tool, and for all crane or construction equipment higher than 200 feet above the ground, submit completed form 7460-1 (Notice of Proposed Construction or alteration) to the FAA at least 45 days before starting construction.

ner41-100 (20240401)

**2.1 Prosecution and Progress**

*Replace paragraph three under section titled **Construction Overview** with the following:*

Prior to closing and detouring CTH N, complete all railroad crossing pavement marking improvements along the detour route, as indicated in the plans.

**Schedule of Items**

Attached, dated May 6, 2024, are the revised Schedule of Items Pages

**Plan Sheets**

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 141

Added: 94A-C

END OF ADDENDUM

LONG LINE PAVEMENT MARKING ITEMS

CATEGORY	LOCATION	STATION	TO	STATION	ALIGNMENT	MARKING LINE EPOXY 4-INCH		MARKING LINE EPOXY 6-INCH		MARKING LINE EPOXY 8-INCH		MARKING LINE GROOVED WET REF EPOXY 6-INCH		MARKING LINE EPOXY 8-INCH		MARKING LINE GROOVED WET REF EPOXY 10-INCH	
						SOLID YELLOW	SOLID WHITE	SOLID YELLOW	SOLID WHITE	SOLID YELLOW	SOLID WHITE	SOLID YELLOW	SOLID WHITE	SOLID YELLOW	SOLID WHITE	SOLID YELLOW	SOLID WHITE
1000	CTH N	56+10.55	-	63+04.65	CTH N	51	-	-	-	-	-	-	-	-	-	-	-
	CTH N	65+23.75	-	70+34.30	CTH N	-	-	-	-	-	-	-	-	-	-	-	-
	RAMP NA	1016+40.97	-	1022+50	NA	-	587	-	590	-	162	-	151	-	-	-	-
	RAMP NB	1012+50	-	1016+14.52	NB	-	287	-	320	-	205	-	223	-	-	-	450
	RAMP NC	1010+60	-	1016+34.47	NC	-	534	-	536	-	122	-	113	-	-	-	-
	RAMP ND	1016+59.39	-	1022+25	ND	-	420	-	459	-	298	-	310	-	-	-	164
	SUBTOTAL					51	1,828	1,905	514	50	787	1,584	797	115	2,059	614	614
	PROJECT TOTAL					186	3,733		564					115	2,059	614	614

\*ADDITIONAL QUANTITIES SHOWN ELSEWHERE

MISCELLANEOUS PAVEMENT MARKING ITEMS

CATEGORY	LOCATION	STATION	TO	STATION	ALIGNMENT	MARKING		MARKING STOP LINE		MARKING CROSSWALK EPOXY		MARKING CURB		MARKING ISLAND	
						ARROW EPOXY	EPOXY	EPOXY	EPOXY	EPOXY	EPOXY	EPOXY	EPOXY	NOSE EPOXY	EACH
1000	CTH N	56+10.55	-	63+04.65	CTH N	8	3	91	440	311	4	4	4	4	4
	CTH N	65+23.75	-	70+34.30	CTH N	3	1	65	-	85	2	2	2	2	2
	RAMP NA	1016+40.97	-	1022+50	NA	-	-	-	106	-	-	-	-	-	-
	RAMP NB	1012+50	-	1016+14.52	NB	6	4	29	108	-	-	-	-	-	-
	RAMP NC	1010+60	-	1016+34.47	NC	-	-	-	110	-	-	-	-	-	-
	RAMP ND	1016+59.39	-	1022+25	ND	3	-	28	110	-	-	-	-	-	-
	PROJECT TOTAL					20	8	213	874	396	6	6	6	6	6

Addendum No. 01  
ID 1130-66-76  
Revised Sheet 141  
May 6, 2024

RAILROAD PAVEMENT MARKING ITEMS

CATEGORY	LOCATION	CROSSING PAINT
1000	DEPOT ST	2
	CTH OO	4
	PROJECT TOTAL	6

RAILROAD PAVEMENT MARKING ITEMS

CATEGORY	LOCATION	MARKING LINE PAINT
1000	BUCHANAN ST	185
	PROJECT TOTAL	185

PROJECT NO: 1130-66-76

HWY: CTH N

COUNTY: OUTAGAMIE

MISCELLANEOUS QUANTITIES

SHEET NO: 141



**RAILROAD CROSSING MARKING GENERAL NOTES**

- SEE THE FOLLOWING STANDARD DETAIL FOR LAYOUT: SIGNING AND PAVEMENT MARKING DETAILS FOR RAILROAD-HIGHWAY GRADE CROSSINGS.
- ALL MARKINGS ON THIS SHEET PAID FOR UNDER "MARKING RAILROAD CROSSING PAINT" ITEM.

Addendum No. 01  
 ID 1130-66-76  
 Added Sheet 94A  
 May 6, 2024

PROJECT NO: 1130-66-76	HWY: CTH N	COUNTY: OUTAGAMIE	PAVEMENT MARKING - DEPOT ST RR CROSSING	SHEET 94A
FILE NAME: C:\USERS\JL\CS\PROJECTS\1130-66-76\PROJECT FILES\505\GN\11306676\02502-PM\LDWG	LAYOUT NAME: Intergration 1	PLOT DATE: 5/2/2024 10:54 AM	PLOT BY: PETER UCHT	WISDOT\CADDS SHEET 42
			PLOT SCALE: 1 IN=40 FT	





Addendum No. 01  
 ID 1130-66-76  
 Added Sheet 94B  
 May 6, 2024

- RAILROAD CROSSING MARKING GENERAL NOTES
- SEE THE FOLLOWING STANDARD DETAIL FOR LAYOUT, SIGNING AND PAVEMENT MARKING DETAILS FOR RAILROAD-HIGHWAY GRADE CROSSINGS.
  - ALL MARKINGS ON THIS SHEET PAID FOR UNDER "MARKING RAILROAD CROSSING PAINT" ITEM.

PROJECT NO: 1130-66-76	HWY: CTH N	COUNTY: OUTAGAMIE	PAVEMENT MARKING - CTH OO RR CROSSING	SHEET 94B	E
FILE NAME: C:\USERS\JL\WORKSPACE\11306676\PROJECT FILES\5056\11306676\023002-P\MN.DWG	LAYOUT NAME: Intergration 3	PLOT DATE: 5/7/2024 10:04 AM	PLOT BY: PETER LUCHT	PLOT SCALE: 1 IN=40 FT	WISDOT/CADD/SHEET 42




Addendum No. 01  
ID 1130-66-76  
Added Sheet 94C  
May 6, 2024


**RAILROAD CROSSING DYNAMIC ENVELOPE NOTES**

1. ALL MARKINGS ARE 6" WIDE
  2. ALL MARKINGS PAID FOR UNDER "MARKING LINE PAINT 6-INCH" (WHITE) ITEM
  3. PLACE TWO 'X' MARKINGS IN EACH LANE
  4. BEGIN 'X' 4' MINIMUM FROM NEAR RAIL, MEASURED ON CENTERLINE\*
  5. MARK TRANSVERSE LINE 10' FROM NEAR RAIL ON CENTERLINE, OR FROM GATE IF PRESENT\*
  6. TERMINATE MARKINGS 9" LATERALLY FROM LANE LINES
- \*MAY ADJUST FOR HIGHLY SKEWED CROSSINGS


BUCHANAN ST




4'



9"



12'



10'



NEAREST RAIL, OR GATE IF PRESENT

PROJECT NO: 1130-66-76	HWY: CTH N	COUNTY: OUTAGAMIE	PAVEMENT MARKING - BUCHANAN ST RR CROSSING DYNAMIC ENVELOPE	SHEET 94C
FILE NAME: C:\Users\jacob\OneDrive\Documents\11306676\PROJECT FILES\94C\11306676\94C\94C.DWG	LAYOUT NAME: 11306676	PLOT DATE: 5/7/2024 10:53 AM	PLOT BY: PETER UCHT	PLOT SCALE: 1 IN=10 FT
WISDOT/CADD SHEET 42			WISDOT/CADD SHEET 42	



Proposal Schedule of Items

Proposal ID: 20240514015 Project(s): 1130-66-76

Federal ID(s): N/A

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	201.0205 Grubbing	5.000 STA	_____.	_____.
0004	203.0100 Removing Small Pipe Culverts	1.000 EACH	_____.	_____.
0006	203.0220 Removing Structure (structure) 0001. B-44-0179	1.000 EACH	_____.	_____.
0008	204.0100 Removing Concrete Pavement	17,470.000 SY	_____.	_____.
0010	204.0120 Removing Asphaltic Surface Milling	270.000 SY	_____.	_____.
0012	204.0150 Removing Curb & Gutter	331.000 LF	_____.	_____.
0014	204.0155 Removing Concrete Sidewalk	530.000 SY	_____.	_____.
0016	204.0165 Removing Guardrail	354.000 LF	_____.	_____.
0018	204.0170 Removing Fence	2,155.000 LF	_____.	_____.
0020	204.0180 Removing Delineators and Markers	10.000 EACH	_____.	_____.
0022	204.0195 Removing Concrete Bases	20.000 EACH	_____.	_____.
0024	204.0220 Removing Inlets	5.000 EACH	_____.	_____.
0026	204.0245 Removing Storm Sewer (size) 0001. 12-Inch	91.000 LF	_____.	_____.
0028	204.9060.S Removing (item description) 0301. Communications Vault	2.000 EACH	_____.	_____.
0030	204.9060.S Removing (item description) 0302. Removing Existing Pole	1.000 EACH	_____.	_____.





Proposal Schedule of Items

Proposal ID: 20240514015 Project(s): 1130-66-76

Federal ID(s): N/A

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0032	204.9090.S Removing (item description) 0001. Removing Pedestrian Railing	1,815.000 LF	_____.	_____.
0034	205.0100 Excavation Common	19,191.000 CY	_____.	_____.
0036	211.0500 Prepare Foundation for Base Aggregate	23.000 STA	_____.	_____.
0038	213.0100 Finishing Roadway (project) 0001. 1130-66-76	1.000 EACH	_____.	_____.
0040	305.0110 Base Aggregate Dense 3/4-Inch	620.000 TON	_____.	_____.
0042	305.0120 Base Aggregate Dense 1 1/4-Inch	11,553.000 TON	_____.	_____.
0044	310.0110 Base Aggregate Open-Graded	43.000 TON	_____.	_____.
0046	312.0110 Select Crushed Material	16,700.000 TON	_____.	_____.
0048	415.0090 Concrete Pavement 9-Inch	6,905.000 SY	_____.	_____.
0050	415.0100 Concrete Pavement 10-Inch	8,609.000 SY	_____.	_____.
0052	415.0410 Concrete Pavement Approach Slab	266.000 SY	_____.	_____.
0054	415.1100 Concrete Pavement HES 10-Inch	822.000 SY	_____.	_____.
0056	416.0610 Drilled Tie Bars	64.000 EACH	_____.	_____.
0058	416.0620 Drilled Dowel Bars	110.000 EACH	_____.	_____.
0060	455.0605 Tack Coat	459.000 GAL	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20240514015 Project(s): 1130-66-76

Federal ID(s): N/A

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0062	460.2000 Incentive Density HMA Pavement	320.000 DOL	1.00000	320.00
0064	460.5224 HMA Pavement 4 LT 58-28 S	497.000 TON	_____	_____
0066	460.6224 HMA Pavement 4 MT 58-28 S	31.000 TON	_____	_____
0068	465.0105 Asphaltic Surface	541.000 TON	_____	_____
0070	465.0120 Asphaltic Surface Driveways and Field Entrances	10.000 TON	_____	_____
0072	465.0125 Asphaltic Surface Temporary	21.000 TON	_____	_____
0074	502.0100 Concrete Masonry Bridges	163.000 CY	_____	_____
0076	502.3205 Pigmented Surface Sealer Reseal	179.000 SY	_____	_____
0078	502.4205 Adhesive Anchors No. 5 Bar	36.000 EACH	_____	_____
0080	505.0600 Bar Steel Reinforcement HS Coated Structures	44,700.000 LB	_____	_____
0082	509.1500 Concrete Surface Repair	6.000 SF	_____	_____
0084	520.8000 Concrete Collars for Pipe	5.000 EACH	_____	_____
0086	522.0142 Culvert Pipe Reinforced Concrete Class III 42-Inch	140.000 LF	_____	_____
0088	522.1042 Apron Endwalls for Culvert Pipe Reinforced Concrete 42-Inch	2.000 EACH	_____	_____
0090	531.2030 Drilling Shaft 30-Inch	52.000 LF	_____	_____



Proposal Schedule of Items

Proposal ID: 20240514015 Project(s): 1130-66-76

Federal ID(s): N/A

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0092	531.5220 Foundation Single-Shaft Type MF-II (structure) 0501. S-44-0383	2.000 EACH	_____.	_____.
0094	531.5220 Foundation Single-Shaft Type MF-II (structure) 0601. S-44-0384	2.000 EACH	_____.	_____.
0096	532.5220 Monotube Full Span Type II (structure) 0502. S-44-0383	1.000 EACH	_____.	_____.
0098	532.5220 Monotube Full Span Type II (structure) 0602. S-44-0384	1.000 EACH	_____.	_____.
0100	601.0405 Concrete Curb & Gutter 18-Inch Type A	2,256.000 LF	_____.	_____.
0102	601.0409 Concrete Curb & Gutter 30-Inch Type A	2,227.000 LF	_____.	_____.
0104	602.0405 Concrete Sidewalk 4-Inch	13,966.000 SF	_____.	_____.
0106	602.0505 Curb Ramp Detectable Warning Field Yellow	194.000 SF	_____.	_____.
0108	602.0605 Curb Ramp Detectable Warning Field Radial Yellow	45.000 SF	_____.	_____.
0110	602.0815 Concrete Driveway 7-Inch	222.000 SY	_____.	_____.
0112	602.3010 Concrete Surface Drains	16.000 CY	_____.	_____.
0114	606.0200 Riprap Medium	15.000 CY	_____.	_____.
0116	608.0312 Storm Sewer Pipe Reinforced Concrete Class III 12-Inch	108.000 LF	_____.	_____.
0118	611.0530 Manhole Covers Type J	2.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20240514015 Project(s): 1130-66-76

Federal ID(s): N/A

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0120	611.0624 Inlet Covers Type H	6.000 EACH	_____	_____
0122	611.2003 Manholes 3-FT Diameter	2.000 EACH	_____	_____
0124	611.3230 Inlets 2x3-FT	6.000 EACH	_____	_____
0126	611.8110 Adjusting Manhole Covers	1.000 EACH	_____	_____
0128	611.8115 Adjusting Inlet Covers	19.000 EACH	_____	_____
0130	612.0106 Pipe Underdrain 6-Inch	980.000 LF	_____	_____
0132	614.2300 MGS Guardrail 3	548.000 LF	_____	_____
0134	614.2610 MGS Guardrail Terminal EAT	4.000 EACH	_____	_____
0136	614.2620 MGS Guardrail Terminal Type 2	4.000 EACH	_____	_____
0138	616.0206 Fence Chain Link 6-FT	2,241.000 LF	_____	_____
0140	616.0700.S Fence Safety	270.000 LF	_____	_____
0142	618.0100 Maintenance and Repair of Haul Roads (project) 0001. 1130-66-76	1.000 EACH	_____	_____
0144	619.1000 Mobilization	1.000 EACH	_____	_____
0146	620.0100 Concrete Corrugated Median	246.000 SF	_____	_____
0148	620.0300 Concrete Median Sloped Nose	270.000 SF	_____	_____
0150	624.0100 Water	263.000 MGAL	_____	_____



Proposal Schedule of Items

Proposal ID: 20240514015 Project(s): 1130-66-76

Federal ID(s): N/A

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0152	625.0100 Topsoil	13,700.000 SY	_____.	_____.
0154	628.1504 Silt Fence	5,890.000 LF	_____.	_____.
0156	628.1520 Silt Fence Maintenance	5,890.000 LF	_____.	_____.
0158	628.1905 Mobilizations Erosion Control	3.000 EACH	_____.	_____.
0160	628.1910 Mobilizations Emergency Erosion Control	3.000 EACH	_____.	_____.
0162	628.2002 Erosion Mat Class I Type A	12,130.000 SY	_____.	_____.
0164	628.2008 Erosion Mat Urban Class I Type B	1,530.000 SY	_____.	_____.
0166	628.7005 Inlet Protection Type A	30.000 EACH	_____.	_____.
0168	628.7015 Inlet Protection Type C	40.000 EACH	_____.	_____.
0170	628.7504 Temporary Ditch Checks	450.000 LF	_____.	_____.
0172	628.7555 Culvert Pipe Checks	52.000 EACH	_____.	_____.
0174	628.7560 Tracking Pads	8.000 EACH	_____.	_____.
0176	628.7570 Rock Bags	20.000 EACH	_____.	_____.
0178	629.0210 Fertilizer Type B	10.300 CWT	_____.	_____.
0180	630.0130 Seeding Mixture No. 30	615.000 LB	_____.	_____.
0182	630.0200 Seeding Temporary	440.000 LB	_____.	_____.





Proposal Schedule of Items

Proposal ID: 20240514015 Project(s): 1130-66-76

Federal ID(s): N/A

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0184	630.0500 Seed Water	310.000 MGAL	_____.	_____.
0186	633.5200 Markers Culvert End	2.000 EACH	_____.	_____.
0188	634.0614 Posts Wood 4x6-Inch X 14-FT	12.000 EACH	_____.	_____.
0190	634.0616 Posts Wood 4x6-Inch X 16-FT	19.000 EACH	_____.	_____.
0192	634.0618 Posts Wood 4x6-Inch X 18-FT	13.000 EACH	_____.	_____.
0194	637.2210 Signs Type II Reflective H	597.750 SF	_____.	_____.
0196	637.2215 Signs Type II Reflective H Folding	125.040 SF	_____.	_____.
0198	638.2602 Removing Signs Type II	46.000 EACH	_____.	_____.
0200	638.3000 Removing Small Sign Supports	54.000 EACH	_____.	_____.
0202	643.0300 Traffic Control Drums	11,318.000 DAY	_____.	_____.
0204	643.0420 Traffic Control Barricades Type III	1,853.000 DAY	_____.	_____.
0206	643.0500 Traffic Control Flexible Tubular Marker Posts	21.000 EACH	_____.	_____.
0208	643.0600 Traffic Control Flexible Tubular Marker Bases	21.000 EACH	_____.	_____.
0210	643.0705 Traffic Control Warning Lights Type A	3,830.000 DAY	_____.	_____.
0212	643.0715 Traffic Control Warning Lights Type C	460.000 DAY	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20240514015 Project(s): 1130-66-76

Federal ID(s): N/A

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0214	643.0800 Traffic Control Arrow Boards	59.000 DAY	_____.	_____.
0216	643.0900 Traffic Control Signs	23,401.000 DAY	_____.	_____.
0218	643.0910 Traffic Control Covering Signs Type I	4.000 EACH	_____.	_____.
0220	643.0920 Traffic Control Covering Signs Type II	22.000 EACH	_____.	_____.
0222	643.1000 Traffic Control Signs Fixed Message	822.000 SF	_____.	_____.
0224	643.1050 Traffic Control Signs PCMS	307.000 DAY	_____.	_____.
0226	643.1070 Traffic Control Cones 42-Inch	1,781.000 DAY	_____.	_____.
0228	643.1205.S Basic Traffic Queue Warning System	8.000 DAY	_____.	_____.
0230	643.3150 Temporary Marking Line Removable Tape 4-Inch	1,350.000 LF	_____.	_____.
0232	643.3180 Temporary Marking Line Removable Tape 6-Inch	1,640.000 LF	_____.	_____.
0234	643.5000 Traffic Control	1.000 EACH	_____.	_____.
0236	644.1440 Temporary Pedestrian Surface Matting	238.000 SF	_____.	_____.
0238	644.1601 Temporary Pedestrian Curb Ramp	66.000 DAY	_____.	_____.
0240	644.1605 Temporary Pedestrian Detectable Warning Field	40.000 SF	_____.	_____.
0242	644.1810 Temporary Pedestrian Barricade	471.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20240514015 Project(s): 1130-66-76

Federal ID(s): N/A

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0244	645.0111 Geotextile Type DF Schedule A	436.000 SY	_____.	_____.
0246	645.0120 Geotextile Type HR	45.000 SY	_____.	_____.
0248	646.1020 Marking Line Epoxy 4-Inch	186.000 LF	_____.	_____.
0250	646.2020 Marking Line Epoxy 6-Inch	4,297.000 LF	_____.	_____.
0252	646.2040 Marking Line Grooved Wet Ref Epoxy 6-Inch	1,584.000 LF	_____.	_____.
0254	646.3020 Marking Line Epoxy 8-Inch	115.000 LF	_____.	_____.
0256	646.4020 Marking Line Epoxy 10-Inch	2,059.000 LF	_____.	_____.
0258	646.4040 Marking Line Grooved Wet Ref Epoxy 10-Inch	614.000 LF	_____.	_____.
0260	646.5020 Marking Arrow Epoxy	20.000 EACH	_____.	_____.
0262	646.5120 Marking Word Epoxy	8.000 EACH	_____.	_____.
0264	646.6020 Marking Stop Line Epoxy 12-Inch	213.000 LF	_____.	_____.
0266	646.7420 Marking Crosswalk Epoxy Transverse Line 6-Inch	874.000 LF	_____.	_____.
0268	646.8120 Marking Curb Epoxy	396.000 LF	_____.	_____.
0270	646.8220 Marking Island Nose Epoxy	6.000 EACH	_____.	_____.
0272	646.9010 Marking Removal Line Water Blasting 4-Inch	134.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20240514015 Project(s): 1130-66-76

Federal ID(s): N/A

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0274	646.9110 Marking Removal Line Water Blasting 8-Inch	65.000 LF	_____.	_____.
0276	646.9310 Marking Removal Special Marking Water Blasting	3.000 EACH	_____.	_____.
0278	652.0210 Conduit Rigid Nonmetallic Schedule 40 1-Inch	265.000 LF	_____.	_____.
0280	652.0225 Conduit Rigid Nonmetallic Schedule 40 2-Inch	4,903.000 LF	_____.	_____.
0282	652.0235 Conduit Rigid Nonmetallic Schedule 40 3-Inch	3,682.000 LF	_____.	_____.
0284	652.0335 Conduit Rigid Nonmetallic Schedule 80 3-Inch	1,015.000 LF	_____.	_____.
0286	652.0605 Conduit Special 2-Inch	355.000 LF	_____.	_____.
0288	652.0700.S Install Conduit into Existing Item	2.000 EACH	_____.	_____.
0290	652.0800 Conduit Loop Detector	801.000 LF	_____.	_____.
0292	653.0154 Pull Boxes Non-Conductive 24x36-Inch	12.000 EACH	_____.	_____.
0294	653.0164 Pull Boxes Non-Conductive 24x42-Inch	55.000 EACH	_____.	_____.
0296	653.0905 Removing Pull Boxes	31.000 EACH	_____.	_____.
0298	654.0101 Concrete Bases Type 1	8.000 EACH	_____.	_____.
0300	654.0105 Concrete Bases Type 5	17.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20240514015 Project(s): 1130-66-76

Federal ID(s): N/A

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0302	654.0110 Concrete Bases Type 10	4.000 EACH	_____.	_____.
0304	654.0113 Concrete Bases Type 13	1.000 EACH	_____.	_____.
0306	654.0120 Concrete Bases Type 10-Special	1.000 EACH	_____.	_____.
0308	654.0230 Concrete Control Cabinet Bases Type L30	2.000 EACH	_____.	_____.
0310	655.0230 Cable Traffic Signal 5-14 AWG	5,809.000 LF	_____.	_____.
0312	655.0240 Cable Traffic Signal 7-14 AWG	234.000 LF	_____.	_____.
0314	655.0260 Cable Traffic Signal 12-14 AWG	1,027.000 LF	_____.	_____.
0316	655.0305 Cable Type UF 2-12 AWG Grounded	1,458.000 LF	_____.	_____.
0318	655.0515 Electrical Wire Traffic Signals 10 AWG	2,179.000 LF	_____.	_____.
0320	655.0610 Electrical Wire Lighting 12 AWG	9,644.000 LF	_____.	_____.
0322	655.0615 Electrical Wire Lighting 10 AWG	18,494.000 LF	_____.	_____.
0324	655.0635 Electrical Wire Lighting 2 AWG	624.000 LF	_____.	_____.
0326	655.0700 Loop Detector Lead In Cable	1,937.000 LF	_____.	_____.
0328	655.0800 Loop Detector Wire	2,853.000 LF	_____.	_____.
0330	656.0201 Electrical Service Meter Breaker Pedestal (location) 0001. CB1100	1.000 EACH	_____.	_____.





Proposal Schedule of Items

Proposal ID: 20240514015 Project(s): 1130-66-76

Federal ID(s): N/A

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0332	656.0401 Electrical Service Main Lugs Only Meter Pedestal (location) 0001. CB1000	1.000 EACH	_____.	_____.
0334	657.0100 Pedestal Bases	8.000 EACH	_____.	_____.
0336	657.0255 Transformer Bases Breakaway 11 1/2-Inch Bolt Circle	17.000 EACH	_____.	_____.
0338	657.0322 Poles Type 5-Aluminum	16.000 EACH	_____.	_____.
0340	657.0350 Poles Type 10	4.000 EACH	_____.	_____.
0342	657.0352 Poles Type 10-Special	1.000 EACH	_____.	_____.
0344	657.0360 Poles Type 13	1.000 EACH	_____.	_____.
0346	657.0420 Traffic Signal Standards Aluminum 13-FT	6.000 EACH	_____.	_____.
0348	657.0430 Traffic Signal Standards Aluminum 10-FT	2.000 EACH	_____.	_____.
0350	657.0530 Monotube Arms 30-FT	4.000 EACH	_____.	_____.
0352	657.0541 Monotube Arms 40-FT-Special	1.000 EACH	_____.	_____.
0354	657.0550 Monotube Arms 50-FT	1.000 EACH	_____.	_____.
0356	657.0710 Luminaire Arms Truss Type 4 1/2-Inch Clamp 12-FT	20.000 EACH	_____.	_____.
0358	657.0812 Luminaire Arms Steel 12-FT	6.000 EACH	_____.	_____.
0360	658.0173 Traffic Signal Face 3S 12-Inch	20.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20240514015 Project(s): 1130-66-76

Federal ID(s): N/A

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0362	658.0174 Traffic Signal Face 4S 12-Inch	4.000 EACH	_____.	_____.
0364	658.0416 Pedestrian Signal Face 16-Inch	8.000 EACH	_____.	_____.
0366	658.0500 Pedestrian Push Buttons	8.000 EACH	_____.	_____.
0368	658.5070 Signal Mounting Hardware (location) 0201. IH 41 NB & CTH N (S44-2019)	1.000 EACH	_____.	_____.
0370	658.5070 Signal Mounting Hardware (location) 0202. IH 41 SB & CTH N (S44-0579)	1.000 EACH	_____.	_____.
0372	659.1120 Luminaires Utility LED B	26.000 EACH	_____.	_____.
0374	659.2130 Lighting Control Cabinets 120/240 30-Inch	1.000 EACH	_____.	_____.
0376	659.2230 Lighting Control Cabinets 240/480 30-Inch	1.000 EACH	_____.	_____.
0378	659.5000.S Lamp, Ballast, LED, Switch Disposal by Contractor	70.000 EACH	_____.	_____.
0380	670.0101 Field System Integrator	1.000 EACH	_____.	_____.
0382	670.0201 ITS Documentation	1.000 EACH	_____.	_____.
0384	671.0132 Conduit HDPE 3-Duct 2-Inch	962.000 LF	_____.	_____.
0386	671.0300 Fiber Optic Cable Marker	4.000 EACH	_____.	_____.
0388	673.0105 Communication Vault Type 1	2.000 EACH	_____.	_____.
0390	673.0110 Communication Vault Type Round	2.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20240514015 Project(s): 1130-66-76

Federal ID(s): N/A

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0392	673.0200 Tracer Wire Marker Posts	3.000 EACH	_____	_____
0394	678.0012 Install Fiber Optic Cable Outdoor Plant 12-CT	1,513.000 LF	_____	_____
0396	678.0024 Install Fiber Optic Cable Outdoor Plant 24-CT	2,078.000 LF	_____	_____
0398	678.0200 Fiber Optic Splice Enclosure	2.000 EACH	_____	_____
0400	678.0300 Fiber Optic Splice	50.000 EACH	_____	_____
0402	678.0400 Fiber Optic Termination	4.000 EACH	_____	_____
0404	678.0501 Communication System Testing	1.000 EACH	_____	_____
0406	690.0150 Sawing Asphalt	241.000 LF	_____	_____
0408	690.0250 Sawing Concrete	633.000 LF	_____	_____
0410	715.0502 Incentive Strength Concrete Structures	978.000 DOL	1.00000	978.00
0412	715.0720 Incentive Compressive Strength Concrete Pavement	4,900.800 DOL	1.00000	4,900.80
0414	SPV.0060 Special 0001. Construction Staking Survey Project 1130-66-76	1.000 EACH	_____	_____
0416	SPV.0060 Special 0201. Remove Traffic Signal IH 41 NB & CTH N (S44-2019)	1.000 EACH	_____	_____
0418	SPV.0060 Special 0202. Remove Traffic Signal IH 41 SB & CTH N (S44-0579)	1.000 EACH	_____	_____



Proposal Schedule of Items

Proposal ID: 20240514015 Project(s): 1130-66-76

Federal ID(s): N/A

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0420	SPV.0060 Special 0203. Temporary Traffic Signals IH 41 NB & CTH N (S44-2019)	1.000 EACH	_____.	_____.
0422	SPV.0060 Special 0204. Temporary Traffic Signals IH 41 SB & CTH N (S44-0579)	1.000 EACH	_____.	_____.
0424	SPV.0060 Special 0301. Salvage Microwave Detector Equipment	1.000 EACH	_____.	_____.
0426	SPV.0060 Special 0302. Remove and Reinstall Ramp Gate System	1.000 EACH	_____.	_____.
0428	SPV.0060 Special 0401. Temporary Support B-44- 0179	1.000 EACH	_____.	_____.
0430	SPV.0075 Special 0100. Street Sweeping	34.000 HRS	_____.	_____.
0432	SPV.0180 Special 0401. Methacrylate Flood Seal	2,459.000 SY	_____.	_____.
0434	646.2005 Marking Line Paint 6-Inch	185.000 LF	_____.	_____.
0436	646.5305 Marking Railroad Crossing Paint	6.000 EACH	_____.	_____.
<b>Section: 0001</b>			<b>Total:</b>	_____.
			<b>Total Bid:</b>	_____.