



Wisconsin Department of Transportation

May 6, 2024

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #18: 4075-41-71
Wcl - Appleton
Cleary Court – Tower View Drive
STH 96
Outagamie County

Letting of May 14, 2024

This is Addendum No. 01, which provides for the following:

Special Provisions:

Revised Special Provisions	
Article No.	Description
3	Prosecution and Progress

Added Special Provisions	
Article No.	Description
22	Electrical Meetings

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01

4075-41-71

May 6, 2024

Special Provisions

3. Prosecution and Progress.

*Replace entire paragraph under subheading **Milled Surface** with the following:*

For roadways open to thru traffic, pave milled surfaces within 96 hours of milling operations unless adverse weather prevents placement of the asphalt layer. Milling operations shall not begin if the weather forecast shows paving cannot be completed within 96 hours. Provide an even cross-sectional profile of the roadway at the end of each day's milling operations. Uneven lanes will not be allowed except during days of milling operations.

22. Electrical Meetings.

No later than 5 working days prior to starting any electrical installation construction activities, arrange and conduct an on-site electrical kickoff meeting between the contractor, engineer, region electrical unit, and electrical subcontractors to discuss the construction of the electrical elements of the project including traffic signals, roadway lighting systems, Intelligent Transportation Systems (ITS), and all other electrical facilities.

During the electrical kickoff meeting, the contractor may be requested to provide additional workplan information related to the electrical installation activities. Upon completion of the electrical kickoff meeting and acceptance of any additional requested workplan information, the contractor will be given authorization to proceed with electrical construction activities.

Arrange and conduct additional electrical progress meetings no later than 5 working days prior to energizing new systems, opening the roadway, and final inspection.

The contractor and electrical subcontractor are required to attend all electrical meetings. Electrical meetings are considered incidental to the electrical work.

END OF ADDENDUM