

March 2020 Solicitation Questions and Responses			
Solicitation	Project	Question	Response
BOS-01		Will only one contract be awarded, or will multiple contracts be considered for different inspection types?	Multiple master contracts awarded; one per firm.
BOS-02		How many master contracts will be awarded for this solicitation?	Several master contracts.
SE-01	1030-43-01, 1030-43-02	Are unusual geotechnical issues anticipated, or is this a standard soils investigation?	No; standard soils investigation required.
SE-02	1100-45-00	Who is developing the pre-60% plans, and what level will they be (e.g. 30%, 50%) when provided?	WisDOT; pre-60% plans include conceptual roadway alignments.
SE-02	1100-45-00	Can you confirm whether a plat is needed?	If the preferred alternative includes a noise wall a plat will be needed.
SE-02	1100-45-00	Can you confirm the geotechnical work and special skills are required?	Geotechnical investigation is needed primarily for sign structures. Pre-60% plans will be conceptual roadway alignment drawings.
SE-04	1360-12-00, 1360-13-00	Can you please clarify what scope of services are required for each of the 7 bridges listed on the NOI?	B-40-0253/0254/0255/0256: Deck overlays, concrete surface repair, paint girder bottom flange and bearings; repair bearings with sheared bolts (B-40-0253/0254 only) B-40-0297/0298: Repair superstructure/restore condition & capacity, repair/replace bearings B-40-0252: WisDOT design
SW-02	1067-02-07	Is BOS doing all the structures work on SW-02?	Yes - Preliminary and Final structure design, including hydraulics. Consultant will complete the structure survey reports.
SW-02	1067-02-07	Is R/W anticipated?	Yes - TPP: Due Date 11/1/2024.
SW-02	1067-02-07	Will WisDOT or the consultant be responsible for Geo-tech?	WisDOT
SW-04	3060-03-01	Will there be any improvements to Village of Marshall sanitary sewer or water main?	No
SW-04	3060-03-01	Is structure design other than curb and railing repairs anticipated?	Addition of structural approach slabs and other structure repairs.
SW-04	3060-03-01	Will the road be widened or is additional R/W anticipated for curb ramp improvements?	No road widening; R/W for curb ramps.

March 2020 Solicitation Questions and Responses			
SW-04	3060-03-01	Are unusual geotechnical issues anticipated, or is this a standard soils investigation?	No; standard soils investigation required.
SW-05	5606-03-00, 5926-05-30	Is WisDOT providing only the survey associated with the mapping?	Yes; consultant to provide survey work needed for TPP and ROW layout.
SW-08	5215-02-04	What are the limits of Project ID 5215-03-00s?	Approximately 300' on either side of the Hackett Branch Bridge (B-22-827); located on STH 81 just south of STH 35 and north of Short Cut Rd.
SW-08	5215-02-04	Is the Village of Beetown the urban area in the project description?	Yes
SW-09	1690-04-32, 5970-02-04	Will the department be performing all required real estate acquisition services?	No, R/W plat or real estate to be completed by consultant.
SW-10, SW-11	1009-20-97, 1009-20-98	Will eligible firms be limited on new plat work requests from the region to avoid conflict of interest of reviewing our own work?	No
SW-10, SW-11	1009-20-97, 1009-20-98	Can consultant staff work out of either office with multiple PLS staff or does it need to be one specified PLS out of each office?	Preference is consultant will need one point of contact/PLS for each office.