

This presentation is for the project on WIS 21 between 3rd Lane in the town of Coloma and Madison Street in the Village of Coloma, Waushara County.

An in-person meeting is not planned based on public health guidance to limit public gatherings.

All meeting materials, including the handout with a comment form, are posted on the design website for this project.

<https://wisconsindot.gov/Pages/projects/by-region/nc/wis21adams/default.aspx>

If you have any questions, please contact WisDOT Project Manager, Jeff Stewart, at 715-459-4525. Deaf or hard of hearing persons needing assistance should contact the Wisconsin Telecommunications Relay system (dial 711).

Public Involvement

WIS 21 3rd Lane to Madison Street

Public Comment Period:
July 6, 2020 to July 20, 2020



Project Team

- WisDOT North Central Region
 - Jeff Stewart, P.E. – Project Manager
- QUEST Civil Engineers, LLC
 - Jim Wendels, P.E. – Consultant Project Manager
 - Adam Osypowski, P.E. – Consultant Designer

Meeting objectives

- Project location
- Project purpose and need
- Proposed improvements
- Real estate needs
- Construction staging
- Current project schedule
- Questions and input

Project location



Purpose and need

- Deteriorating concrete pavement
- Deteriorating curb and gutter
- Existing curb ramps do not meet current ADA (Americans with Disabilities Act) standards
- Storm Sewer inlets and apron end walls are in poor condition

WIS 21 proposed improvements

- Roadway improvements recommended to keep WIS 21 traffic moving safely and efficiently
 - Replace sections of severely deteriorated concrete pavement and curb and gutter
 - Mill the concrete pavement surface and overlay with asphalt
 - New pavement marking (existing lane configuration to remain)
 - Installation of centerline rumble strips west of 4th Avenue
 - Bridge over I-39 and approaches constructed in 2014 are not included in this project

WIS 21 proposed improvements

- Intersection improvements
 - Replace concrete pavement and island at the end of the I-39 northbound off ramp to WIS 21
 - Replace County CH intersection approach pavement
 - Mill and overlay asphalt side road approaches west of I-39

WIS 21 proposed improvements

- Mobility improvements
 - Upgrade curb ramp at the in the southwest corner of the WIS 21/County CH intersection to ADA standards.
- Storm sewer system repairs
 - Repair inlets and end walls
 - Reconstruct flume at Church Lane
 - Replace pipe under Madison Street and relocate inlet
 - Clean and flush system

Real estate needs

- Minor permanent fee and temporary limited easement is needed
 - Grading for curb ramp improvement in southwest corner of WIS 21/ County CH intersection
- Acquisition process
 - WisDOT will acquire real estate
 - Begin real estate acquisitions in fall 2020
- Landowner rights brochure on the project website

Proposed construction staging

- Maintaining safety and mobility are important during construction
 - Through traffic will be maintained on WIS 21
- Proposed traffic impacts
 - Lane closures
 - Flaggers
 - Temporary signals
 - Short term ramp closures
 - County CH and Madison Street closures (phased)
 - Local and emergency access will be maintained

Current project schedule

- Local officials meeting June 30, 2020
- Public involvement July 6-July 20, 2020
- Preliminary plans August 2020
- Environmental document August 2020
- Final right of way plat September 2020
- Real estate negotiations Fall 2020 to Fall 2021
- Final plans November 2021
- Construction currently scheduled Spring/Summer 2022

