Project ID: 8510-01-00/70
Port Wing - Superior
County H to Engdahl Road
WIS 13
Douglas County

PROJECT INFORMATION

WisDOT is proposing to improve approximately 15.88 miles of WIS 13 from County H to Engdahl Road, which was last rehabilitated in 2000. See the attached project location map. The existing pavement exhibits signs of fatigue in the form of alligator cracking, block cracking, edge cracking, longitudinal and transverse cracking, patching and rutting.

Proposed improvements include:

1) Extending the service life of the asphaltic pavement by:
   a) Removing (milling) approximately 2 inches of the existing asphalt pavement
   b) Overlaying the road with 3.25 inches of asphalt pavement
2) Replacing substandard guardrail
3) Completing miscellaneous culvert pipe work (cleaning, replacing or placing liners in existing pipes)
4) Replacing curb and gutter in spot locations
5) Repairing flumes
6) Adding new pavement markings and centerline rumble strips

PROPOSED TRAFFIC IMPACTS

Construction currently is scheduled to begin in spring 2022 and expected to be completed within five months.

WIS 13 will remain open to through traffic during construction through the use of flagging operations. Temporary driveway closures may be necessary during parts of the construction process. Construction staff will contact homeowners, property owners and businesses in advance before closing a driveway. If you have special access needs during construction, please let us know so these can be considered as much as possible, and if needed, included in the bidding documents.

REAL ESTATE

No real estate acquisitions are anticipated for this project.

ANTICIPATED SCHEDULE

Environmental Review Complete:	September 2020
Preliminary Design Complete:	December 2020
Final Design Complete:	May 2021
Bid Date:	November 2021
Construction:	Spring 2022

PUBLIC INPUT/COMMENTS

We encourage you to talk to the project representatives and ask them questions. Your comments assist us in developing a project that will serve the needs of the traveling public as well as the needs of the local community. Your input is welcome and appreciated throughout the design process.

CONTACTS

Jeffrey Saxby, P.E.
WisDOT NW Region Consultant Project Manager
(920) 380-2805
jsaxby@sehinc.com

Ellery Schaffer, P.E.
Jewell Associates Engineers, Inc.
(608) 459-6027
ellery.schaffer@Jewellassoc.com

WisDOT Northwest Region – Superior
1701 N. Fourth St.
Superior, WI 54880

PROJECT WEBSITE

https://wisconsindot.gov/Pages/projects/by-region/nw/wis13douglas/default.aspx