ST CLOUD ST - LIVINGSTON ST: PREFERRED ALTERNATIVE

PREFERRED ALTERNATIVE TYPICAL SECTION
CAUSEWAY BLVD TO CLINTON ST

PREFERRED ALTERNATIVE TYPICAL SECTION
CLINTON ST TO LIVINGSTON ST

Scale: 1 IN:50 FT

ST CLOUD ST
ST JAMES ST
WALL ST
WINDSOR ST
CLINTON ST
GOLD ST
LOGAN ST
SILL ST
GILLETTE ST
RUBLEE ST
RIVERVIEW CT
COHRES ST
LIVINGSTON ST
ST PAUL ST

LA CROSSE CORRIDOR STUDIES

Project ID 1630-09-01
US 53 and US 14/61
WIS 35 - I-90
La Crosse County

PRELIMINARY 4/22/2026

Note: Aerial imagery may be out of date and shall be used for informational purposes only; may vary from present-day conditions.

Note: In addition to the spot improvements planned in the Clinton St to Livingston St section, other work includes pavement rehabilitation and curb ramp improvements as needed to comply with current ADA standards.

LEGEND

- Pavement
- Structure - Concrete Overlay
- Curb & Gutter/Median/Sidewalk
- Shared Use Path
- Sidewalk-Level Bike Lane
- Steet-Level Bike Lane or Cycle-Track
- Bike Crossing
- Pedestrian Crossing
- Terrace/Grass Median
- Paved Terrace
- Raised Median
- Existing Right of Way
- Existing Property Lines
- Proposed Right of Way
- Bus Stop
- Signalized Intersection

1. Signal Infrastructure Improvements
2. Signal Operation Improvements
3. Rectangular Rapid Flashing Beacon
4. Pedestrian Refuge
5. Speed Feedback Signs
6. New Driveway Access
7. Driveway Right In/Out Only
   *Full Access from Other Driveways
   **No other Full Access Driveway
   - XXX Driveway Closure
     Note: Existing driveways to remain unless otherwise noted.
   - XXX Potential Access Relocations or Consolidations.
8. Public Road Access Changes Due to Geometric Improvements