US 151
0.5 MI S CNW RR to WIS 49
DODGE COUNTY

PROJECT ID 1111-03-05
PUBLIC INVOLVEMENT MEETING
NOVEMBER 2025

WISCONSIN DEPARTMENT OF TRANSPORTATION

BEGIN PROJECT

B-14-058
CONCRETE SURFACE REPAIR AT ABUTMENTS AND PIERS AND DIAPHRAGM OVER PIER 2. REPLACE CRUSHED AGGREGATE SLOPE PAVING. RR FLAGGING NEEDED.

B-14-074
REPAIR AND RESEAL CRUSHED AGGREGATE SLOPE PAVING, CONCRETE SURFACE REPAIR ON SOUTH ABUTMENT SW CORNER .
RR FLAGGING WILL BE NEEDED.

B-14-150
NO WORK

B-14-047
REPAIR AND RESEAL CRUSHED AGGREGATE SLOPE PAVING, CONCRETE SURFACE REPAIR ON COLUMNS AND CAPS AT BOTH PIERS.

BOX CULVERT B-14-117
RIPRAP BOTH ENDS OF BOX CULVERT POTENTIAL CONCRETE SURFACE REPAIR INSIDE OF CULVERT.

B-14-137
MMA FLOOD SEAL. REPAIR AND RESEAL CRUSHED AGGREGATE SLOPE PAVING, TIE BACK NW AND SE WALL AND RESEAL JOINT.

CROSSOVER TRAFFIC TO ONE DIRECTION WITH TEMPORARY SIGNAL ON COUNTY G.

B-14-151
REPAIR AND RESEAL CRUSHED AGGREGATE SLOPE PAVING

LANE CLOSURE WITH FLAGGING ON COUNTY W

B-14-118
REPLACE CONCRETE APPROACH SLABS AND REPAIR AND RESEAL CRUSHED AGGREGATE SLOPE PAVING

LANE CLOSURE WITH FLAGGING ON COUNTY W

B-14-154
DECK PATCHING, CONCRETE SURFACE REPAIR AT ABUTMENTS AND REPAIR OF CONCRETE SLOPE PAVING

R-14-154
USH 151 SB OFF RAMP TIE BACK RETAINING WALL AND RESEAL JOINT.

B-14-152
DECK PATCHING, REPLACE BOTH APPROACH SLABS

B-14-155
NO WORK

B-14-153
NO WORK

LEGEND
- ▭ CULVERTS
- ┅ OVERNIGHT DETOUR FOR CULVERT WORK
- ┅ EXISTING RIGHT OF WAY
- ┅ PROPERTY LINE
- ┅ PROPOSED GUARDRAIL REHAB
- ● PROPOSED CULVERT PIPE REPLACEMENT
- 🟥 REPLACING CONCRETE APPROACH SLABS
- ▭ PROPOSED GUARDRAIL REPLACEMENT
- 🟩 STRUCTURE REHAB
- ● CULVERT REHAB

COORDINATING WITH RAILROAD FOR IMPROVEMENTS

B-14-119
REPLACE ASPHALT APPROACHES, CONCRETE SURFACE REPAIR AT SIDEWALKS & CONCRETE BARRIER, REPLACE PROTECTIVE SCREENING, REPAIR AND RESEAL CRUSHED AGGREGATE SLOPE PAVING

LANE CLOSURE WITH TEMPORARY SIGNAL ON COUNTY E.

B-14-056
REPLACE ASPHALT APPROACH SLABS, REPAIR CONCRETE SURFACE WITH FRP AT PIER 3, AND REPAIR AND RESEAL CRUSHED AGGREGATE SLOPE AGGREGATE.

LANE CLOSURE ON INDUSTRIAL DR.

B-14-122
REPLACE CONCRETE APPROACH SLABS, DECK PATCHING, AND REPAIR AND RESEAL CRUSHED AGGREGATE SLOPE PAVING

LANE CLOSURE WITH CROSSOVER: SIGNAL TIMING ADJUSTMENTS.

B-14-120
REPLACE CONCRETE APPROACH SLABS, REPLACE CRUSHED AGGREGATE SLOPE PAVING, AND REPAIR CONCRETE SURFACE AT ABUTMENTS, REPAIR VOID IN ABUTMENT FOOTINGS.

SHOULDER CLOSURE ON COUNTY A.

B-14-123
REPLACE CONCRETE APPROACH SLABS, REPLACE CRUSHED AGGREGATE SLOPE PAVING

SHOULDER CLOSURE ON COUNTY A.

LEGEND
- ▭ CULVERTS
- ┅ OVERNIGHT DETOUR FOR CULVERT WORK
- ┅ EXISTING RIGHT OF WAY
- ┅ PROPERTY LINE
- ┅ PROPOSED GUARDRAIL REHAB
- ● PROPOSED CULVERT PIPE REPLACEMENT
- 🟥 REPLACING CONCRETE APPROACH SLABS
- ▭ PROPOSED GUARDRAIL REPLACEMENT
- 🟩 STRUCTURE REHAB
- ● CULVERT REHAB