

WisDOT Structural Engineers Symposium

Program Agenda

May 22, 2018

8:00 a.m.	Registration	11:50 a.m.	Lunch
8:30 a.m.	Welcome & BOS Director's Perspective – <i>Scot Becker</i>	12:50 p.m.	Misc. Geotechnical/Structural Topics - <i>Jeff Horsfall (Bureau of Tech Services)</i>
8:45 a.m.	Contract Plans & Fabrication Shop Drawing Review Changes – <i>Najoua Ksontini, Kristin Revello</i>	1:20 p.m.	BOS Overlay Policy, Marquette Interchange PPC Overlays – <i>James Luebke, Jason Sadowski (Michael Baker)</i>
9:10 a.m.	Wind Loaded Structures Initiative – <i>Andrew Smith, Mark Maday (CH2M/Jacobs)</i>	1:50 p.m.	3D Design & Modeling, BIM for Structures – <i>Danielle DeTennis, Adam Swierczek</i>
9:30 a.m.	Removing Old Structure Over Waterways – <i>Bill Dreher</i>	2:05 p.m.	I94 N-S – <i>Frank Pritzlaff (SE Region PM), Aaron Bonk</i>
9:45 a.m.	Small Group (table) Discussion – <i>All</i>	2:35 p.m.	Break (Beverages and Snacks)
10:00 a.m.	Timeliness of Consultant Plan Submittals – <i>Najoua Ksontini</i>	2:55 p.m.	Strengthening Program for Local Load Posted Bridges – <i>Alex Pence, Josh Dietsche</i>
10:15 a.m.	Break (Beverages and Snacks)	3:20 p.m.	Small Group (table) Discussion – <i>All</i>
10:35 a.m.	Automation, Policy, and Standards – <i>Dave Kiekbusch, James Luebke</i>	3:35 p.m.	Interactive Survey & Q/A
11:15 a.m.	Complex Structures – <i>Andrew Smith</i>	4:00 p.m.	Adjourn
11:35 a.m.	SCC Prestressed Girders – <i>Steve Doocy</i>		

Conference Location: University of Wisconsin-Madison Union South
1308 West Dayton Street
Madison, WI 53715

For today's presentations, agenda, and proof of attendance, please visit:

<http://wisconsin.gov/Pages/doing-bus/eng-consultants/cnslt-rsrcs/strct/research.aspx>

Welcome - 2018 Symposium

Scot Becker

BOS Director, State Bridge Engineer

2018 WisDOT Structural Engineers Symposium
University of Wisconsin-Madison Union South, Madison, WI

May 22, 2018

Perspective Over View

- Welcome
- Agenda Highlight
 - What's new!
 - Continuing Progress

Today's Discussion - Focus Interactive

- Third Symposium – 2014,16,18
- Spend Time Today Discussing Issues, Clarifying Policies, Sharing Innovations, Questions or Concerns

What's New – Fabrication Library

- New Fabrication Improved SharePoint Library Includes Ancillary Structures


Version	Icon	Name	Type	ID	Date	Location	Description
1.0	Image	b7metals010.jpg	Meeting Minutes	B020066	9956-00-70	ZTest Fabricator - City...	01 Rolled B...
1.0	Image	US 41 Suamico Diaphragm Sho...	Shop Drawing	B050076	1130-32-71	Aura - Dalton, MN	20 Steel Di...
1.0	Image	US 41 Suamico Diaphragm Sho...	Shop Drawing	B050077	1130-32-71	Aura - Dalton, MN	20 Steel Di...
1.0	Image	B-05-78 Steel Diaphragms 02-1...	Shop Drawing	B050078	1130-32-71	Aura - Dalton, MN	20 Steel Di...
1.0	Image	B-05-78 Steel Diaphragms and...	Shop Drawing	B050078	1130-32-71	Aura - Dalton, MN	14 Steel Be...
1.0	Image	US 41 Suamico B-5-78 Expansio...	Shop Drawing	B050078	1130-32-71	Commercial Fabricator...	21 Expansio...
1.0	Image	US 41 Suamico Diaphragm Sho...	Shop Drawing	B050079	1130-32-71	Aura - Dalton, MN	20 Steel Di...
1.0	Image	US 41 Suamico B-5-79 Expansio...	Shop Drawing	B050079	1130-32-71	Commercial Fabricator...	21 Expansio...
1.0	Image	PQR 139.pdf	WPS-PQR	B050131	1130-32-71	Veritas Steel - Wausau...	
1.0	Image	PQR 138.pdf	WPS-PQR	B050131	1130-32-71	Veritas Steel - Wausau...	
1.0	Image	PQR 137.pdf	WPS-PQR	B050131	1130-32-71	Veritas Steel - Wausau...	
1.0	Image	PQR 131.pdf	WPS-PQR	B050131	1130-32-71	Veritas Steel - Wausau...	
1.0	Image	PQR 114.pdf	WPS-PQR	B050131	1130-32-71	Veritas Steel - Wausau...	
1.0	Image	PQR 105.pdf	WPS-PQR	B050131	1130-32-71	Veritas Steel - Wausau...	
1.0	Image	317090A WPS Submittal 02-12	WPS-PQR	B050131	1130-32-71	Veritas Steel - Wausau...	

What's New – SCC in Prestress Girders

- Self-Consolidating Concrete (SCC) for Prestressed Bridge Girders
- Moving Forward with SCC



What's New – Polyester Polymer Concrete (PPC) Overlay



What's New - LRFD Wind Loaded Structures





What's New – St. Croix Bridge



Highlight – Continued Progress

- Structures Asset Management

- Program Generated by Element Condition
- Emphasis on Preservation
- Emphasis on Extending Serviceable Life





What's New – Local Bridge Program Changes

- Local Bridge Program Changes
- Fed State Money Swap
- Replace in Kind Policy
- Minimum Standards Based on Engineering Evaluation



What's New - Local Bridge Strengthening Program



Closing Request

I will repeat myself from 2016 if you recall 😊

- We want your Feedback and Input
 - BOS - How are we doing?
 - 4th Symposium?
 - Innovations?
 - Issues?

Contract Plans- Review changes

Najoua Ksontini. P.E.

Consultant Review and Hydraulics Supervisor

2018 WisDOT Structural Engineers Symposium
University of Wisconsin-Madison Union South, Madison, WI

May 22, 2018



**BUREAU OF
STRUCTURES**

- Goals of presentation

- Discuss current plan submittal review process for various types of submittals and various types of structures
- Discuss changes to review processes for various types of submittals and various types of structures

Stream Crossing and Grade Separation Preliminary Structure Plans

- No review process changes
 - All preliminary plan submittals are reviewed with focus on providing concurrence on Type, Size, and Location
 - Reviewers may provide comments on details contained on the preliminary plans
 - Contact BOS if you need input regarding proposed unusual and non-standard details

Stream Crossing and Grade Separation Final Structure Plans

- No review process changes
 - BOS will perform a Quality Assurance review on a select number of final structure plan submittals
 - Focus of BOS QA review is on structural design adequacy and load capacity
 - Reviewers may provide comments on structural details, constructability and biddability.
 - Contact BOS if you need input regarding proposed unusual and non-standard details

Rehabilitation Preliminary Structure Plans

- Review Process changes:
 - BOS will continue to provide comments on preliminary plans for the more complex rehabilitation work such as superstructure replacement, re-decks and joint replacement
 - BOS may not provide comments on preliminary plans for certain types of rehabilitation work such as painting and Polymer overlays
 - Designers will be notified if comments will not be provided

Rehabilitation Final Structure Plans

- Review Process changes:
 - BOS will continue to perform Quality Assurance reviews on a select number of final structure plan submittals for rehabilitation work
 - Contact BOS early if you need input regarding unusual and non-standard rehabilitation structural details

Retaining Wall Preliminary and Final Structure Plans

- Review Process changes:
 - BOS will provide comments only on a select number of retaining wall preliminary and final structure plans
 - Focus will be on non-proprietary retaining walls, plans with unusual or non-standard details and complex geometry
 - Designers will be notified if comments on preliminary plans will not be provided

Sign Structure Preliminary and Final Plans

- Review Process changes:
 - BOS will provide comments only on a select number of sign structure preliminary and final plans
 - Contact BOS if you need input regarding non-standard sign structure details

Questions?

Fabrication Shop Drawing Review & Process Changes

Kristin Revello, P.E.

Structural Metals and Fabrication QA Inspection Unit Supervisor

2018 WisDOT Structural Engineers Symposium
University of Wisconsin-Madison Union South, Madison, WI

May 22, 2018



**BUREAU OF
STRUCTURES**

Presentation Goals

- To provide background on the Bureau of Structures Fabrication Initiatives
- Discuss the outcomes of each Fabrication Initiative, and highlight upcoming changes
- Address how these changes may affect you as designers of structures with fabricated items

Bureau of Structures Fabrication Initiatives

Overview

Tier 1

- Began Summer 2014
- Area of Focus
 - Steel Fabrication
- Creation of BOS Teams (Steering and Oversight)
- URS

Tier 2

- Began Winter 2017
- 4 Areas of Focus
 - Prestressed Concrete Girders
 - Retaining Walls
 - Sign Structures
 - Secondary Fabrication Items
- Creation of BOS Teams
- Michael Baker International

Bureau of Structures Fabrication Initiatives

Overview

- Interviews and Surveys were conducted regarding current processes, areas that worked well, and areas where improvements could be made
 - BOS staff
 - WisDOT region staff
 - Consultants
 - Fabricators
 - Steel Producers
 - Other state DOTs
- Other DOT specifications and processes were researched

Bureau of Structures Fabrication Initiatives

Overview

- For each area of focus, the current policy and practices were documented.
- Results of the interviews and surveys were documented, including current shop drawing review practices in other states
- A report for each initiative with findings and recommendations was created by the Consultant with input from the BOS Steering and Oversight Teams.
- Based on the report findings, BOS created an implementation plan for the outcomes that will be covered today.

Bureau of Structures Fabrication Initiatives

Tier 1 Outcomes

- The creation of the Contractor Certificate of Shop Drawing QC Form, DT 2333 for primary steel members.
 - Checklist based on Section 4 AASHTO/NSBA G1.1 Checklist Items
 - A P.E. is required to review the shop drawing and stamp the form, and a Contractor must sign certifying the review has occurred.
- The creation of the SharePoint Fabrication Library to receive steel shop drawings and fabrication documents
- The requirement of weekly Fabricator Progress Reports for primary steel members
- A reduction in the percentage of steel shop drawing reviews performed

Bureau of Structures Fabrication Initiative

Tier 2 Outcomes

WisDOT Fabrication Quality Assurance Program

Program Goal: To consistently enforce submittal of required documentation and enact Quality Assurance

- Provide electronic submittal requirements for fabrication documents
- Provide guidance for roles and responsibilities for all parties involved
- Ensure department quality assurance and contractor quality control roles
- Modify standard specifications and CMM for clarity and enforcement
- Clarify approved fabricator requirements

The WisDOT Fabrication Library Expansion

The Goal: A single comprehensive library for the submittal of all fabrication documents, accessible to all parties (as appropriate).

In March 2018, the new Fabrication Library went live for our users.

For December 2018 Let and beyond, this will be the mechanism to receive all structure shop drawings and fabrication documents.






Roles and Responsibilities - Reference Guide

Fabrication QA Program Reference Guide

- Definitions
- Roles & Responsibilities
- SFU Contact Information
- Required Documentation by Structure Type
- Standard Specification References

Is available on the fabrication and Quality Assurance website, and will be referenced in the CMM



FABRICATION QUALITY ASSURANCE PROGRAM REFERENCE GUIDE (DRAFT)

Section 3 Required Documentation

All Documentation shall be uploaded to the Fabrication Library. Visit this page to request access to library: <http://wisconsin.dot.gov/teams/doing-business-consultants/onsite-rates/structfab-sharepoint.aspx>

High Strength Structural Steel Members (Highway Bridge)

Document	Submitted by	WisDOT Specification	Note
DT230 – Fabrication Storage & Shipping Plan	Fabricator or Contractor		
Certified Mill Test Results (CMTR)	Fabricator or Contractor		
DT233 – Contractor's Certificate of Quality Control	Fabricator or Contractor		• For Highway Bridge, Structural Steel Member fabrication only • Submit one DT233 form for each revision
Shop Drawings	Fabricator or Contractor		• Submit Shop Drawings 14 days before start of fabrication
Welding Procedure Specifications (WPS)	Fabricator or Contractor		
DT172 – Weekly Fabrication Project Status Record	Fabricator		• For Highway Bridge, Structural Steel Member fabrication only
Non-Destructive Testing (NDT) Reports	Fabricator or Contractor		
High Strength Structural Bolt Test Results	Fabricator or Contractor		
Paint System Thickness Readings	Fabricator or Contractor		
Weekly Quality Assurance Inspection Reports	QA Inspector		

Prestressed Concrete Members (Highway Bridge)

Document	Submitted by	WisDOT Specification	Note
			• For Highway Bridge



Fabrication Shop Drawing Review & Process Changes

QA vs QC

- Although the Department intended to perform QA review of shop drawings, the reality was that we were performing QC in many areas.
 - We reviewed 100% of shop drawings
 - In some cases we were correcting errors, and essentially performing QC for the fabricator and contractor
- The decision was made to realign our processes with QA
 - Reducing the percentages of Department review
 - Look to place the responsibility of shop drawing QC on the contractor and fabricator

QA vs QC

- The Bureau of Structures has notified WTBA that we will no longer be reviewing all shop drawings.
- The percentages of review, and criteria of selection for each type of shop drawing will be determined by BOS.
- Project staff will be notified when a shop drawing has been selected for review.
- In the Fabrication Library, there is shop drawing status flag to indicate whether the shop drawing has been selected for review, if was reviewed and it needs to be resubmitted, or if it has been accepted.

Contractor Certificate of Shop Drawing QC Draft Forms

- Sign Structures and Overhead Sign Supports
- Retaining Walls
- Fabricated Bridge Components
- Prestressed Concrete Girders
 - Mesh substitutions are still being evaluated

Check lists are based on commonly found errors on shop drawings

Contractor's Certificate of Shop Drawing Quality Control
Sign Structures and Overhead Sign Supports
Wisconsin Department of Transportation
DT220a 2/2018

Project ID:	Structure Number:
Highway:	County:
Project Name:	
Region Contact:	Region:
Design Engineer:	
Contractor Shop Drawing Submittal Ref. No.:	

The Wisconsin Department of Transportation places all responsibility for quality review of shop drawings on the Contractor. With each shop drawing submittal the Contractor must include this certification that the following items have been checked on Shop Detail Drawings.

Shop drawings submitted with this certificate incomplete, or missing, will be rejected.	
Initials	Item
	1. Principal controlling dimensions
	2. Size and length of plates, shapes and pipes
	3. Splice details, if applicable
	4. Number, size and spacing of high strength bolts
	5. Weld size, location and type
	6. Weld Procedure Specification (WPS) number included on weld symbols
	7. All connection details
	8. Surface cleaning and profile specifications, coating notes, coating thickness and specifications
	9. Compliance with Wisconsin DOT standard specifications and project specific requirements
	10. List of materials designations and conformance to contract plans and standard drawings
	11. Incorporation of all necessary revisions into the shop detail drawings
	12. All Contractor Verify or "field verify" queries resolved
	13. If Wisconsin DOT approved material substitutions are used, verify the joint geometry and spacing
	14. Verify hatches and lighting details, if applicable
	15. Lendrain holes are detailed, if applicable
	16. Order sheet information (Wisconsin project and structure ID, fabricator job number)
	17. For contractor designed structures - Shop drawing and calculations sealed by a Professional Engineer licensed in the state of Wisconsin.

STATEMENT OF CERTIFICATION
I hereby certify that the attached shop drawings have been reviewed as indicated above.

(Contractor Company Name)	(Fabricator Company Name)
X (Authorized Contractor Signature)	X (Fabricator Reviewer Signature)
(Date)	(Date)
(Title)	(Title)
(Print Name)	(Print Name)

Original Revision Number

Contractor's Certificate of Shop Drawing Quality Control
Fabricated Bridge Components (Structural Steel Diaphragms, Expansion Devices, Railings and Bearing Assemblies)
Wisconsin Department of Transportation
DT220a 2/2018

Project ID:	Structure Number:
Highway:	County:
Project Name:	
Region Contact:	Region:
Design Engineer:	
Contractor Shop Drawing Submittal Ref. No.:	

The Wisconsin Department of Transportation places all responsibility for quality review of shop drawings on the Contractor. With each shop drawing submittal and resubmittal, the Contractor must include this certification that the following items have been checked on Shop Detail Drawings.

Shop drawings submitted with this certificate incomplete, or missing, will be rejected.	
Initials	Item
	1. Principal controlling dimensions
	2. Size and length of plates, shapes, pipes and tubes
	3. Splice details
	4. Number, size and spacing of bolts
	5. Weld sizes, locations and types
	6. Weld Procedure Specification (WPS) number included on weld symbols
	7. Surface cleaning and surface profile notes and specifications
	8. Coating system specifications, thickness and product name
	9. List of materials designations and conformance to contract plans and standard drawings
	10. Incorporation of all necessary revisions into the shop detail drawings
	11. All "contractor verify" or "field verify" queries resolved
	12. Compliance with Wisconsin DOT standard specifications and project specific requirements
	13. Constructability of curved sections
	14. Minimum number of posts
	15. Vent drain holes are detailed
	16. Order sheet information

STATEMENT OF CERTIFICATION
I hereby certify that the attached shop drawings have been reviewed as indicated above.

(Contractor Company Name)	(Fabricator Company Name)
X (Authorized Contractor Signature)	X (Fabricator Reviewer Signature)
(Date)	(Date)
(Title)	(Title)
(Print Name)	(Print Name)

Original Revision Number

Contractor's Certificate of Shop Drawing Quality Control
Fabricated Bridge Components (Structural Steel Diaphragms, Expansion Devices, Railings and Bearing Assemblies)
Wisconsin Department of Transportation
DT220a 2/2018

Project ID:	Structure Number:
Highway:	County:
Project Name:	
Region Contact:	Region:
Design Engineer:	
Contractor Shop Drawing Submittal Ref. No.:	

The Wisconsin Department of Transportation places all responsibility for quality review of shop drawings on the Contractor. With each shop drawing submittal and resubmittal, the Contractor must include this certification that the following items have been checked on Shop Detail Drawings.

Shop drawings submitted with this certificate incomplete, or missing, will be rejected.	
Initials	Item
	1. Principal controlling dimensions
	2. Size and length of plates, shapes, pipes and tubes
	3. Splice details
	4. Number, size and spacing of bolts
	5. Weld sizes, locations and types
	6. Weld Procedure Specification (WPS) number included on weld symbols
	7. Surface cleaning and surface profile notes and specifications
	8. Coating system specifications, thickness and product name
	9. List of materials designations and conformance to contract plans and standard drawings
	10. Incorporation of all necessary revisions into the shop detail drawings
	11. All "contractor verify" or "field verify" queries resolved
	12. Compliance with Wisconsin DOT standard specifications and project specific requirements
	13. Constructability of curved sections (railings)
	14. Minimum number of posts per rail sections (railings)
	15. Vent drain holes are detailed, if applicable (railings)
	16. Order sheet information (Wisconsin project and structure ID, fabricator job number)

STATEMENT OF CERTIFICATION
I hereby certify that the attached shop drawings have been reviewed as indicated above.

(Contractor Company Name)	(Fabricator Company Name)
X (Authorized Contractor Signature)	X (Fabricator Reviewer Signature)
(Date)	(Date)
(Title)	(Title)
(Print Name)	(Print Name)

Original Revision Number



Modified WisDOT Approved Fabricator List

2018 Standard Specification List: Bridge Metal Secondary Fabrication Item

Secondary fabrication items are defined as:

- | | |
|----------------------|--|
| Rail Posts | Curb and sidewalk cover plates |
| Sleeves | Floor drains |
| Shims | Guard rail anchors |
| Rail panels | Sheet Lead |
| Anchor Bolts | Non-Laminated Elastomeric pads |
| Protection Angles | <i>(see "Laminated Elastomeric Bearings" list for those items)</i> |
| Structural Fasteners | Bearing assemblies(steel) |
| Expansion Devices | Structural steel diaphragms |



Fabrication Shop Drawing Review & Process Changes

APPROVED FABRICATORS, BRIDGE METAL SECONDARY FABRICATION	
Date last edited: 12/21/2017	
Approved Fabricator	Location
Aura Fabricators ²⁷	14122 Norway Pine Dalton, MN 56324 218-583-7121
Camelot Metals Inc.	3100 82nd Ln NE, E (651) 636-3450
Commercial Fabricators	Bridgeview, IL
CON-SERV Inc.	2963 Interstate Pkwy Brunswick, OH 442
Badger Railing	Milwaukee, WI
D.S. Brown(Lewis Engineering Division)	Chaska, MN
ESPO Engineering	845 Midway Dr. Willowbrook , IL 60 630-789-2525
ESS Brothers	Minneapolis, MN
IronWorks (Synergies, LLC)	PO Box 620 13995 Industry Ave Becker, MN 55308 763-262-4760
Janke General Contractors, Inc.	1223 River View La Athens, WI 54411 Phone: 715.257.790
PACAL, LLC (Paper Calumansen)	St. Paul, MN
REMOVED FROM LIST 3/24/2015	
LienTec, Inc. ¹⁹	1000 East Street Stoughton, WI 5359 608-877-5887
REMOVED FROM LIST 3/24/2015	
Tobl Engineering, Inc.	3126 W. Lake Ave. Glenview, IL 60026 847-724-7880
Utility Sales and Supply, Inc.	23230 West Thome Loretto, MN 55357 612-385-7529
Van Lanen Mfg., Inc.	5335 8TH 29 Denmark, WI 5420 920-863-5705
Viking Steel Inc.	Oshkosh, WI

Modified WisDOT Approved Fabricator List

2019 Standard Specification List: Fabricated Bridge Components

- Railings
- Bearings
- Expansion Devices
- Structural Steel Diaphragms



Fabrication Shop Drawing Review & Process Changes

APPROVED FABRICATORS, RAIL ASSEMBLIES

Date last edited: XX/XX/2017

Approved Fabricator	Location	Phone Number	Approval Date	Status
Aura Fabricators	14122 Dieseth Rd Dalton, MN 56324	(218) 589-7121		S

APPROVED FABRICATORS, BEARINGS

Date last edited: XX/XX/2017

Approved Fabricator	Location	Phone Number	Approved Products	Approval Date	Status
Bridge Components Ind.	3476 Millikin Court Columbus, OH 43228	(614) 873-0777	1	11/28/2017	S

APPROVED FABRICATORS, EXPANSION DEVICES

Date last edited: XX/XX/2017

Approved Fabricator	Location	Phone Number	Approved Products	Approval Date	Status
Camelot Metals, Inc.	2501 County Road B West St. Paul, MN 55113	(651) 636-3450			S

APPROVED FABRICATORS, STRUCTURAL STEEL DIAPHRAGMS

Date last edited: XX/XX/2017

Approved Fabricator	Location	Phone Number	Approval Date	Status
Camelot Metals, Inc.	2501 County Road B West St. Paul, MN 55113	(651) 636-3450		S
Commercial Fabricators	7247 S 78th Ave Bridgeview, IL 60455	(708) 594-1199		S
D.S. Brown (Lewis Engineering Division)	4201 Nortex Dr Chaska, MN 55318	(952) 368-3000		S

Note:

1) For policy on acceptance/removal from the approved products list, please see:

[Status Options](#)

New WisDOT Approved Fabricator Lists

Effective with the 2019 Standard Specification

- WisDOT will be creating 2 new Approved Fabricator Lists
 - Primary Steel Members
 - Sign Structures and Overhead Sign Supports
- In order to fabricate these items, the fabricator will need to be on the appropriate APL prior to the Let.
- Fabricator requirements to be added to these lists and the application & renewal process will be clearly defined for all parties.

Fabrication Progress Reports

- The weekly requirement of Fabrication Progress Reports submitted to the Fabrication Library for prestressed girders, fabricated bridge components, sign structures, and overhead sign supports

This form shall be submitted to the Fabrication Library on a weekly basis. Create additional lines as needed.

Shop drawings, revisions to shop drawings, RFIs and NCRs must be submitted to the Fabrication Library
 If you don't have access to the Fabrication Library click here to apply for an account

I certify to the best of my knowledge that the information below is correct.

X _____ 5/12/2018
 (Fabricator's QC Manager – E-Signature) Today's Date

Week Ending	mm/dd/yyyy (Saturday)
Fabricator	Company Name
QC Manager	First Last Name

Shop drawings, revisions to shop drawings, RFIs and NCRs must be submitted to the Fabrication Library

PROJECT ID	STRUCTURE ID	JOB NUMBER	FABRICATED COMPONENT	MATERIAL AT SHOP FLOOR		CUTTING		WELDING		ASSEMBLY		SURFACE PREPARATION		@ GALVANIZER OR PAINTER		SHIPPED	
				Date Delivery Anticipated mm/dd/yy	Date Delivered mm/dd/yy	Date Started/ Anticipated mm/dd/yy	Date Completed mm/dd/yy	Date Started/ Anticipated mm/dd/yy	Date Completed mm/dd/yy	Date Started/ Anticipated mm/dd/yy	Date Completed mm/dd/yy	Date Started/ Anticipated mm/dd/yy	Date Completed mm/dd/yy	Date Shipped mm/dd/yy	Date Returned mm/dd/yy	Anticipated Date mm/dd/yy	Date Shipped mm/dd/yy
XXXX-XX-XX	X-XX-XXX	XXXXXXXX	Select from dropdown menu														

Upcoming Changes to Retaining Wall SPVs

For the August 1st 2018 PSE

- Changes will include updates to retaining wall system preapproval process information
- Added requirement of Contractor Certificate of Shop Drawing QC for retaining walls
- Adding requirement for Fabrication Library Submittal
- Updated SPVs to be available prior to June 1st for inclusion in August 2018 PSE projects

DELETE ALL DESIGNER NOTES FROM YOUR SPECIAL PROVISIONS
Recommended PPQ item. Please indicate PPQ in the project estimate.

Wall Concrete Panel Mechanically Stabilized Earth (structure), Item SPV.0165.XX

A Description

This special provision describes designing, furnishing materials and erecting a permanent earth retention system in accordance to the lines, dimension, elevations and details as shown on the plans and provided in the contract. The design life of the wall and all wall components shall be 75 years minimum.

This special provision describes the quality management program (QMP) for Mechanically Stabilized Earth (MSE) walls. A quality management program is defined as all activities, including process control, inspection, sampling and testing, and necessary adjustments in the process that are related to the construction of the MSE wall, which meets all the requirements of this provision.

This special provision describes contractor quality control (QC) sampling and testing for backfill density testing, documenting those results, and documenting related production and placement process changes. This special provision also describes department quality verification (QV), independent assurance (IA), and dispute resolution.

Chapter 8 of the department's construction and materials manual (CMM) provides additional detailed guidance for QMP work and describes sampling and testing procedures.

B Materials

B.1 Proprietary Wall Systems

The supplied wall system must be from the department's approved list of Concrete Panel Mechanically Stabilized Earth Wall systems. Proprietary wall systems must conform to the requirements of this specification and be pre-approved for use by the department's Bureau of Structures. The department maintains a list of pre-approved proprietary wall systems. The name of the pre-approved proprietary wall system selected shall be furnished to the engineer within 25 days after the award of contract.

To be eligible for use on this project, a system must have been pre-approved by the Bureau of Structures and added to that list prior to the bid opening date. To receive pre-approval, the retaining wall system must comply with all pertinent requirements of this provision and be prepared in accordance to the requirements of Chapter 14 of the department's LRFD Bridge Manual. Information and assistance with the pre-approval process can be obtained by contacting the Bureau of Structures, Structures Maintenance Section in Room 601 of the Hill Farms State Transportation Building in Madison or by calling (608) 266-8494.

B.2 Design Requirements

2019 Standard Specification

Upcoming Changes

- Working to remove cross-referencing across the structure sections, eliminating conflicts
 - Unique requirements (Such as DT2333 for primary steel members) will be included in the specific structure section
 - Under 105.2 Supplemental Plans and Drawings, adding guidance regarding Fabrication Library Submittal Requirements
- Added requirement of Contractor Certificate of Shop Drawing QC
- Requirement of weekly Fabrication Progress Reports

2019 Standard Specification

Upcoming Changes

- Added clarification in 506.3.1 regarding steel primary members
- Renamed secondary fabricated items “fabricated bridge components” and revised definition
- Requirements to use an approved fabricator from the Department’s APL for primary members, sign structures, and overhead sign supports

The Importance of Designer QA/QC

"The Big Picture"

- Consultant Review Unit
 - Performs QA reviews on a percentage of the design plans we receive
- Structural Metals and Fabrication QA Inspection Unit
 - Performs QA reviews on a percentage of the shop drawings we receive

There is a possibility that your design plan and the associated shop drawings may not be reviewed. Any plan errors may not be caught.

The Importance of Designer QA/QC

"The Big Picture"

- RFIs will be the mechanism for the Contractor and Fabricator to clarify possible issues with design plans
- There is a potential increased chance of Errors and Omissions
- Keeping this in mind when preparing design plans, and following your firm's QA/QC plan will help you avoid any potential issues

Questions?

Wind Loaded Structures Initiative

Andrew Smith/WisDOT
Mark Maday/Jacobs

WisDOT Structural
Engineers Symposium
May 22, 2018



JACOBS® **ch2m**®

Wind Loaded Structure Initiative

- Primary Purpose
 - Transition to LRFD
- While we are at it
 - Process improvement
- Current Challenges
 - Multiple processes but one design spec.
 - Getting plans in HSI



Wind Loaded Structure Initiative

- Wind Loaded Structures Include:
 - Sign Bridge, Cantilever and Butterfly Sign Structures
 - Overhead Sign Supports
 - High Mast Lighting
 - Associated Support Foundations and Anchorages
- Phase 1 - Evaluation:
 - Evaluating Process, Policy, Standards, and Specifications
 - Develop Recommendations for Improvements and Updates

Wind Loaded Structure Initiative

Phase 2 - Implementation

Goals and Anticipated Work Products:

- Clarified / Updated Process
- Increased Uniformity / Consistency
- Transition to LRFD Design
- Design Manual Updates (BM, FDM, CIM)
- Specification Updates (Standard Specifications and / or STSPs)

Team

WisDOT Work Group:

Andrew Smith – PM Andrew.Smith@dot.wi.gov

Alexander Crabtree – Design Alexander.Crabtree@dot.wi.gov

Steve Doocy – Design Steve.Doocy@dot.wi.gov

Jeff Horsfall – Geotechnical Jeffrey.Horsfall@dot.wi.gov

David Nelson – Development David1.Nelson@dot.wi.gov

William Oliva – Oversight William.Oliva@dot.wi.gov

Carla Principe – Fabrication Carla.Principe@dot.wi.gov

Matt Rauch – Traffic Ops Matt.Rauch@dot.wi.gov

Vu Thao – Design Vu.Thao@dot.wi.gov

Team

Jacobs:

Mark Maday Mark.Maday@Jacobs.com

Karl Schmid Karl.Schmid@jacobs.com

Schedule

Kick-Off: June 2017

Phase 1 Completion: August 2017

- Evaluation of Current Process
- Stakeholder Outreach
- Evaluation of Other DOT Processes
- Develop Recommendations:
 - Improving Uniformity
 - General Standards Updates
 - Transition to LRFD Design
 - Specification Updates
 - Design Software

Schedule

Phase 2 Completion: June 2019

- Design Manual Updates
- Revised Standard Detail Drawings and Insert Sheets
- Standard Specifications, STSP Updates
- Outreach and Training Presentations

Tasks & Progress to Date

Review of Current Process:

- Solicited Input from All WisDOT Regions and Central Office
- Identify What Works; Best Practices
- Identify Areas for Improvement

Tasks & Progress to Date

Stakeholder Outreach:

- Solicited Input From:
 - Sign Structures Suppliers / Fabricators
 - Contractors
 - DOT Designers (BOS)
 - Consultant Designers

Tasks & Progress to Date

Review of Other State DOT's:

Received Input from 10 State DOTs:

Florida, Indiana, Iowa, Michigan, Utah, Texas
North Dakota, Michigan, Virginia, Washington

Three States Using LRFD for Sign Structure Design:

Minnesota, Florida, Washington

Tasks & Progress to Date

Initial Recommendations:

Revised / Improved Process

- Clarify Process
- Emphasize Follow Through / Completing All Steps

Improving Uniformity

- Clarification / Concise Direction In BM
- Consistency Between Manuals, Standards and Specifications

General Standard Updates

- Standard for Each Structure Type
- Include Foundations

Current / Upcoming Activity

Recommendations:

- Transition to LRFD Design
- Specification Updates
- Design Software

Phase 1 Completion - Summary Report

It's Not Too Late!

We Welcome Your Input...

- Any Ideas, Comments or Suggestions?
- Contact Andrew or Any Member of the Work Group

Andrew Smith / WisDOT

Office: (608) 266-0989

Email: Andrew.Smith@dot.wi.gov

Mark Maday / Jacobs

Cell: (414) 975-6129

Email: Mark.Maday@Jacobs.com

Thank You

Questions?



JACOBS® **ch2m.**

Removing Old Structure Over Waterway

Bill Dreher, P.E.
Structures Design Chief

2018 WisDOT Structural Engineers Symposium
University of Wisconsin-Madison Union South, Madison, WI

May 22, 2018



**BUREAU OF
STRUCTURES**

- What are the options?
- What are the differences?
- What are the costs?
- How do I choose?



What are the options?

- Standard Specification
- + 3 choices with varying levels of restrictions

Wisconsin Department of Transportation
Standard Specifications



2018 Standard Specifications

Changes since the 2017 edition are highlighted in red and a brief explanation of each change is provided both in the table of contents and adjacent to each revised passage.

- Table of Contents
- Bid Items
- Index
- Help

Add Search Icon



Special Provisions		
Table of Contents		
Article	Description	Page #
1.	General.....	2
2.	Scope of Work.....	2
3.	Prosecution and Progress.....	2

Standard Specification

- Section 203 Removing Old Culverts and Bridges
 - 203.3.2.2 Removal Operations:
Minimize debris falling onto water surfaces and wetlands as the contract specifies in 107.18 or in the special provisions.

Standard Specification

- Section 107 Legal Relations and Responsibility to the Public
 - 107.18 Environmental Protection:
Take all necessary precautions to **prevent pollution** of streams...
Conduct work operations to avoid or **minimize siltation** of streams...
Remove existing structures in large pieces, minimizing the number of smaller pieces that drop into the water. Remove all steel and all concrete pieces or other debris larger than 5 inches.

Standardized Special Provisions (STSP's)

- Designer should coordinate with regional environmental coordinator and DNR to reach consensus on which special to use for the removal.

Standardized Special Provisions (STSP's)

- The lowest level of care is for situations where there is little choice but to drop the structure into the waterway.
- The highest level of care requires a debris capture system to prevent virtually all debris from falling into the waterway.

Standardized Special Provisions (STSP's)

- STSP 203-015: Removing Old Structure Over Waterway
 - Use this special provision where it is **not possible to remove the structure without dropping it**, or a portion of it, into a waterway or wetland; **and** that waterway or wetland is **not highly environmentally sensitive**.

Standardized Special Provisions (STSP's)

- STSP 203-015: Removing Old Structure Over Waterway
 - This special provision is typically appropriate for removing the following structure types:
 - Slab spans, voided slabs
 - Cast-in-place girder bridges
 - Earth-filled bridges
 - Some large trestle bridges

Standardized Special Provisions (STSP's)

- STSP 203-015: Removing Old Structure Over Waterway
 - Remove all reinforcing steel, all concrete, and all other debris that falls into the waterway or wetland.
 - Remove large pieces of the structure within 36 hours.
 - The contractor may leave limited amounts of small concrete pieces scattered over the waterway floor or wetland only if the engineer allows.

Standardized Special Provisions (STSP's)

- STSP 203-020: Removing Old Structure Over Waterway With Minimal Debris
 - Use this special provision where it is possible to remove the structure without dropping it, or a portion of it, into a waterway or wetland; and that waterway or wetland is not highly environmentally sensitive.

Standardized Special Provisions (STSP's)

- STSP 203-020: Removing Old Structure Over Waterway With Minimal Debris
 - This special provision is typically appropriate for removing **all structures types except** for the following:
 - Slab spans, voided slabs
 - Cast-in-place girder bridges
 - Earth-filled bridges
 - Some large trestle bridges

Standardized Special Provisions (STSP's)

- STSP 203-020: Removing Old Structure Over Waterway With Minimal Debris
 - This special provision will likely be used for most removals.

Standardized Special Provisions (STSP's)

- STSP 203-020: Removing Old Structure Over Waterway With Minimal Debris
 - Remove the existing structure in large sections.
 - Prevent all large pieces and minimize the number of small pieces from entering the waterway or wetland.

Standardized Special Provisions (STSP's)

- STSP 203-020: Removing Old Structure Over Waterway With Minimal Debris
 - Remove all reinforcing steel, all concrete, and all other debris that falls into the waterway or wetland.
 - The contractor may leave limited amounts of small concrete pieces scattered over the waterway floor or wetland only if the engineer allows.







Standardized Special Provisions (STSP's)


- STSP 203-025: Removing Old Structure Over Waterway With Debris Capture System
 - Consider using this special provision where a waterway or wetland is **highly environmentally sensitive**.
 - Consult with the department's regional environmental coordinator to determine if the affected waterway or wetland is highly environmentally sensitive and if this special provision is appropriate.

Standardized Special Provisions (STSP's)

- STSP 203-025: Removing Old Structure Over Waterway With Debris Capture System
 - Remove the existing structure in large sections.
 - Due to the very sensitive nature of the waterway name, provide a debris capture and containment system that prevents all large pieces and virtually all other debris, including fine particles and slurry, from entering the waterway or wetland.

	STSP 203-015 Removing Old Structure Over Waterway	STSP 203-020 Removing Old Structure Over Waterway With Minimal Debris	STSP 203-025 Removing Old Structure Over Waterway With Debris Capture System
Environmental Sensitivity of waterway	Not high	Not high	High
Allowable Debris		Prevent all large pieces and minimize the number of small pieces from entering the waterway or wetland	Prevent all large pieces and virtually all other debris, including fine particles and slurry, from entering the waterway or wetland.
	Remove all reinforcing steel, all concrete, and all other debris that falls into the waterway or wetland.	Remove all reinforcing steel, all concrete, and all other debris that falls into the waterway or wetland.	
	Remove large pieces of the structure within 36 hours.		
	May leave limited amounts of small concrete pieces scattered over the waterway floor or wetland only if the engineer allows	May leave limited amounts of small concrete pieces scattered over the waterway floor or wetland only if the engineer allows	
Removal Restrictions		Remove in large sections	Remove in large sections
Applicable Structure Type	Where it is not possible to remove the structure without dropping it	Where it is possible to remove the structure without dropping it, or a portion of it, into a waterway or wetland	
	For removing slab spans; voided slabs; cast-in-place girder bridges; earth-filled bridges; large trestle bridges.	For removing all structures types except for slab spans; voided slabs; cast-in-place girder bridges; earth-filled bridges; large trestle bridges.	

Average Bid Cost



How Do I Choose?

- Review all 3 specials and coordinate with regional environmental coordinator and DNR to reach consensus on which special to use for the removal.
- The special provision language is intended to be a reasonable starting point; however, it may need to be expanded to address additional DNR or other concerns.

How Do I Choose?

- For unique or difficult removals, consult with the contracting community to assess costs and the feasibility of a particular removal technique.
- Consult with the department's regional environmental coordinator to determine if the affected waterway or wetland is highly environmentally sensitive and which special provision is appropriate.
- Don't make the decision w/o good information!

Questions?

Timeliness of Consultant Plan Submittals

Najoua Ksontini, P.E.
Consultant Review and Hydraulics Supervisor

2018 WisDOT Structural Engineers Symposium
University of Wisconsin-Madison Union South, Madison, WI

May 22, 2018



**BUREAU OF
STRUCTURES**

BOS Plan Submittal Timeline Expectations

- Preliminary Structure Plans:
 - Project schedule should allow for a minimum of 60 days for BOS review. Adequate time for comment resolution, design, and final plan preparation prior to final plan submittal will determine the date that preliminary plans need to be submitted.
 - For the purpose of tracking, BOS considers preliminary plan submittals to be late if received less than 3 months prior to the PS&E date.

BOS Plan Submittal Timeline Expectations

- Final Structure Plans:
 - BOS requires that final structure plans, structural computations, and other pertinent documents are submitted 2 months prior to project PS&E date

Trends in Preliminary Plans Submittal Timeliness

Includes all types of structures: bridges, culverts, retaining walls, and sign structures

Preliminary Plan Submittals - On Time vs. Late*

*Late = received less than 3 months prior to PSE date




Trends in Final Structure Plans Submittal Timeliness

Includes all types of structures: bridges, culverts, retaining walls, and sign structures


Final Plan Submittals - On Time vs. Late*

*Late = received less than 2 months prior to PSE date



Late Final Plan Submittals by Structure Type

- In 2017, about 166 late final structure plan submittals.
- Evenly divided:
 - new bridges or culverts.
 - rehabilitation bridges or culverts.
 - retaining walls.
 - sign structures.




Why are past-deadline final plan submittals concerning to BOS

- We have a limited number of reviewers
- We have limited review time
- When plans are late, we have less time to work through issues with the designer
- We would like to provide input and QA reviews to as many submittals as possible
- Number of final structure plan submittals average about 120 per PS&E

On-Time Plan Submittal Improvement Form

- In March 2016, BOS implemented a new policy requiring designers to submit a form documenting the reasons for past-deadline final structure plan submittals.
- BOS categorized the reasons for past-deadline final structure plan submittals.

Reasons for Past-Deadline Final Structure Plan Submittals



Next Steps

- Designers- Please continue to communicate with BOS when project schedules are accelerated or advanced
- BOS- Will discuss with Regional offices impact of accelerated schedules on structure review timelines

Questions?

Automation, Policy & Standards

David Kiekbusch

Structures Development Supervisor

James Luebke

Structures Development Engineer

2018 WisDOT Structural Engineers Symposium
University of Wisconsin-Madison Union South, Madison, WI

May 22, 2018



**BUREAU OF
STRUCTURES**

New standards in past two years

- 9.01 – Structure Backfill Limits and Notes
- 9.02 – Structure Backfill Limits and Notes 2
- 9.03 – Wing Fill Sections at Wing Tips
- 13.08 – Pier Cap Reinforcement Details
- 14.11 – MSE Wall – Panel and Block Facing
- 14.12 – MSE Wall – Wire Faced 1
- 14.13 – MSE Wall – Wire Faced 2
- 17.03 – Edge of Deck Flashing
- 27.10 – Steel Expansion Bearing Details
- 30.22 – Conduit Details and Notes
- 40.40 & 40.41 – Moved A4 abutments to Bridge Rehabilitation

Notable Bridge Manual text changes

- Extensive rewrite of Chapter 45 – Bridge Rating (January 2017)
 - Entire chapter rewritten
 - More logical order
 - Better guidance for when and how to load rate bridges
 - Four new rating examples for LFR
 - Reinforced Concrete Slab
 - Single Span Prestressed Girder
 - Two Span Prestressed Girder
 - Two Span Steel Girder

Bridge Manual text changes (continued)

AASHTO 3.8 – Wind Load: WL and WS

- Extensive update to Chapter 13 – Piers, including examples (July 2017)
 - Wind speeds for various limit states
 - Wind pressure is a function of the wind speed, exposure condition and bridge elevation above the ground or water surface
 - WisDOT policy items to simplify wind loading for most bridges

MASH 2016



MASH 2016

Required for all lets after December 31, 2019

- 42SS parapet required for:
 - All Interstate structures
 - All STH and USH with a posted speed ≥ 45 mph
- Railings Type 'M' and Types 'NY 3' and 'NY 4' are TL-2
 - Good for most local and collector roads with design speeds ≤ 45 mph
- Trying to get Type 'M' and Types 'NY 3' and 'NY 4' to TL-3
 - If TL-3 can't be achieved, then a new railing (could be TL-4)

Bridge Maintenance and Bureau of Project Development Coordination

- Maintenance Items
- Erosion Issues
- Design Considerations



Bridge Maintenance Coordination

- Discuss Issues
 - Wing Wall Grading
 - Slope Paving Repairs
 - Approach Details
- Design Considerations



BPD Coordination

- Curb Usage
 - Recommended Increased Usage




BPD Coordination

- Drainage Features
 - Curb Details
 - Flumes (efficiencies, location, etc.)
 - Alternative drainage features




BPD Coordination

- Approach Details
 - Construction Details
 - Site Specific Requirements



Parapets

- Fillet Detail
 - Drainage
 - Damage



Updated Detail

Past Detail

Parapets

- Embankment Fills
 - Drainage
 - Damage



Wing Length

- Past Issues



- Insufficient Embankment Fills
- Beam Guard Embedment
- Erosion Wing Tips



Wing Length


- Updates

- 2:1 Slope + 2.0 ft (roundup)
- 2 ft berm (section detail)



Structural Approach Slabs

- Past Issues
 - Excessive Settlements
- Updates
 - Usage
 - Guidance



Structural Approach Slabs


- Current Usage

- Required: IH and USH Bridges
- Recommended: >3500 AADT
- Not Required: Buried Structures & Culverts
- Not Used: Rehabilitation Projects
- *Design exceptions considered on a project-by-project basis.*

Structural Approach Slabs

- Guidance:

- The geotechnical engineer should evaluate approaches for settlement susceptibility and provide recommendations for mitigating settlements prior to approach placement.
- Structural approach slabs are not intended to mitigate excessive approach settlements.



Structural Backfill


- Material Changes
- Payment of Quantities
- Past Maintenance Issues
 - Slope Stabilities
 - Erosion Issues



Structural Backfill

- Updates
 - Material
 - Geotextile
 - Pay Limits
 - Payment

Backfill placed beyond pay limits or exceeding plan quantities shall be incident



Structural Backfill

- Pay Limits

- Not Necessarily Representative of Actual Limits
- Payment Purposes Only

Backfill placed beyond pay limits or exceeding plan quantities shall be incident

- Excavation Limits – Contractor's Responsible

Precast Piers

- Past Usages


- Research Projects – Required
- Rawson Avenue - Required
- IH 39/90 – Contractor’s Option (noted allowance)
- Sign Structure Column – Contractor Requested



Precast Piers


- Current Policy

- Pier configurations shall be determined by providing the most efficient cast-in-place concrete pier design, unless approved otherwise. When the cast-in-place design can accommodate a precast option, include the noted allowance.



Conduit

- Updates
 - Standards (30.21 & 30.22)
- WBM Updates
 - Design Guidance



WisDOT Bridge Manual

Chapter 32 – Utilities and Lighting

- Structure mounted - Other: 1-inch PVC - schedule 80 (preferred), RTRC, RMC or LFMC may also be considered.
- The maximum allowable conduits that can be placed in concrete parapets is two 3-inch diameter conduits.
- Future conduit runs should not be placed unless future services are highly probable. Conduit systems are expensive and are routinely addressed by maintenance.
- All conduit runs shall have a limited number of bends. The sum of the individual conduit bends on a single run between boxes (pull or junction) shall not exceed 360 degrees, preferably not to exceed 270 degrees. No individual bend shall be greater than 90 degrees. Use two 45 degree bends in lieu of a 90 degree bend when space allows.
- Bends shall not be less than the minimum radius as specified by the National Electrical Code. For layout purposes, all bends shall have a minimum bend radius no less than 6 times the nominal diameter.
- Provide 3'-0" minimum RMC conduit on each side of semi-expansion joint fittings. For expansion joints, provide 3'-0" minimum RMC conduit on one side and extend the other side to a junction box. All semi-expansion and expansion joints with RMC conduit and fittings should be wrapped and bonded, as shown or noted in the Standards.
- For large movements or when joints exceed standard fitting allowances consider using a LFMC system. The specified LFMC conduit length should be at least 2 times the anticipated movements.
- Extend conduit a minimum of 2 inches above concrete surfaces and extend a minimum of 6 inches for buried applications. Provide temporary end caps, unless conduit terminates in a pull box.
- Provide 2'-0" minimum conduit cover when installed below roadways, 1'-6" minimum otherwise. Conduit cover should not exceed 3'-0". Provide 2-inch PVC - schedule 40 for buried applications, unless directed otherwise. Provide 2" minimum concrete cover when embedding in concrete.
- Conduit systems and light spacing requirements should be coordinated with the roadway engineer and the Regional electrical engineer.

Local Program bridges

- Railings and parapets to be MASH compliant:
 - Chapter 30 of Bridge Manual gives a MASH TL value for all railings and parapets
- Local road design speed versus posted speed (or no posted/statutory speed)
 - Will be working with Bureau of Project Development to provide guidance

Bridge drainage

- Desirable to maintain 0.50% profile for drainage, with solid parapets (WisDOT preference)
 - Investigating exceptions to the 0.50% criteria, especially for shorter bridges.

Future updates


- July Bridge Manual updates
 - Text with regards to AASHTO 8th Edition (Examples in January 2019)
 - Renumbering of Section 5 Concrete Structures (461 references in BM!)
 - New method for prestressed girder shear
 - New steel girder simplified field splice design procedure
 - 1/2" filler adjacent to 1/2" bearing pads
- Other
 - Insert sheets are being cleaned up – available as ready
 - Insert sheet(s) with available cells

Automation

- WiSAMS – Wisconsin Structures Asset Management System
 - Automated system to assist with determining the most appropriate course of action for structure maintenance, and eventual replacement, during its life cycle
 - Planners like it, bridge maintenance staff is a little more skeptical...
- Data Warehouse/Business Intelligence
 - Centralized location for all data related to WisDOT structures
 - Used to support important business activities
- BIM for Bridges and Structures

MSE Wall Specifications

- Updates
 - Pay Limits (Plan Values)
 - Shop Drawing Submittal



Shear Design – PS Girders

- Simplified Procedure removed from AASHTO LRFD 8th Edition for Prestressed Sections

V_c = the lesser of V_{ci} and V_{cw}

$$V_{ci} = 0.02\sqrt{f'_c}b_vd_v + V_d + \frac{V_iM_{cre}}{M_{max}} \geq 0.06\sqrt{f'_c}b_vd_v$$

$$V_{cw} = (0.06\sqrt{f'_c} + 0.30f_{pc})b_vd_v + V_p$$

Shear Design – PS Girders

- Update: Use General Procedure

$$V_c = 0.0316 \beta \sqrt{f'_c} b_v d_v$$

$$\beta = \frac{4.8}{(1 + 750 \epsilon_s)}$$

$$\epsilon_s = \frac{\left(\frac{|M_u|}{d_v} + 0.5 N_u + |V_u - V_p| - A_{ps} f_{po} \right)}{E_s A_s + E_p A_{ps}}$$

Shear Design – PS Girders


- Update: Use General Procedure
- Software Updates: In-House (in progress)

WisDOT policy item:

Web shear reinforcement shall be designed by **LRFD [5.7.3.4.2]** (General Procedure) using the Strength I limit state for WisDOT standard girders.


CIP Piles

- Additional Detail (Std. 11.01)
 - End Plate Detail For CIP Piling
- Specifications
 - Welds watertight (2019 spec)
 - Agg. size (2020 spec?)



Overlay Guidance

- Past Usages
- Overlay Systems
- Summary of Updates
- Polymer Overlays



Overlay Type	Advantages	Disadvantages	Notes
Thin Polymer Overlay	<ul style="list-style-type: none"> Minimal dead load Minimal traffic disruptions Seals the deck Provides traction 	<ul style="list-style-type: none"> Requires a concrete age of at least 21 days Requires decks with minimal defects and low chloride concentrations Sensitive to moisture, temperature, and humidity at placement Reflective Cracking (RCR) 	
Low Slump Concrete Overlay	<ul style="list-style-type: none"> Contractor familiar and department experience Long life span potential Durable Easy to accommodate grade differences and deficiencies 	<ul style="list-style-type: none"> Traffic disruptions Additional dead load High maintenance requirements Placing height concerns Sensitive to cracking Specialized finishing equipment 	<ul style="list-style-type: none"> May require crack sealing the following year and periodic seal treatments
Polymer Polymer Concrete Overlay	<ul style="list-style-type: none"> Minimal dead load Minimal traffic disruptions Seals the deck Provides traction Long life span potential Durable Low maintenance requirements 	<ul style="list-style-type: none"> High cost Deck slab equipment Limited usage in Wisconsin Sensitive to moisture, temperature, and humidity at placement Reflective Cracking (RCR) 	<ul style="list-style-type: none"> Requires BOS Pre-Approval
Polymer Modified Asphaltic Overlay	<ul style="list-style-type: none"> Minimal traffic disruptions Easy to construct Can be used on more flexible structures (e.g. timber decks or timber slabs) 	<ul style="list-style-type: none"> High cost Some restricts permeability Difficult to assess top of deck condition 	<ul style="list-style-type: none"> Conduct region for permeability Minimal research has been performed on the durability of this system in Wisconsin
Asphaltic Overlay	<ul style="list-style-type: none"> Low cost Easy to construct Easy to accommodate grade differences and deficiencies 	<ul style="list-style-type: none"> Short life span Hot engine for federal funds Overlay permeability Difficult to assess top of deck condition 	<ul style="list-style-type: none"> Deck or bridge replacement should be programmed within 4 years
Asphaltic Overlay with Membrane	<ul style="list-style-type: none"> Easy to construct Minimal traffic disruptions Long life span potential Can be used on more flexible structures (e.g. PG box girders) 	<ul style="list-style-type: none"> Some restricts permeability Requires a membrane Difficult to assess top of deck condition 	<ul style="list-style-type: none"> Currently under review Requires BOS Pre-Approval

Table 61.2-2
Overlay Advantages, Disadvantages, and Notes



Questions?

Answers??

My Favorite Complex Structures

Andrew Smith
Load Rating Engineer

2018 WisDOT Structural Engineers Symposium
University of Wisconsin-Madison Union South, Madison, WI

May 22, 2018

The “Home Sweet Home” Bridge

Category: Movable Bridge

- First Movable Bridge constructed with ABC techniques.
- Bridge operator lives on site



Bridge over Achievement Gap

Category: Box Girder Bridge

- Built by Red Neck and Sons
- Cost: 4 bottles of whiskey
- No children were hurt during construction



Load Rating

~~My Favorite~~ Complex Structures

Andrew Smith
Load Rating Engineer

2018 WisDOT Structural Engineers Symposium
University of Wisconsin-Madison Union South, Madison, WI

May 22, 2018




**BUREAU OF
STRUCTURES**

A Band of Complex Misfits



Approximate Break-down of WI Inventory by Bridge Type




What is Considered Complex?

WisDOT Bridge Manual 45.3.11


By Type (inherent):

- Steel Rigid Frames
- Bascule-type Movable
- Tied Aches
- Other Arches
- Cable Stayed (or suspension)
- Steel Box Girder





By Geometry:

- Curvature
- High Skew
- Misc...




By Type




By Geometry: *Curvature*

See LRFD 4.6.1.2.4 and Curved Steel Girder Guide Spec 4.2

- Girders are concentric;
- Bearing lines are not skewed more than 10 degrees from radial;
- The stiffnesses of the girders are similar;
- For all spans, the arc span divided by the girder radius in feet is less than 0.06 radians where the arc span, L_{as} , shall be taken as follows:



By Geometry: *High Skew* (2nd Tier)



Please contact Rating Unit if...



Girder Flare



Complex Framing

“Flexible” Supports



Complex Structures

What is required if a structure is categorized “complex”?

Generally... That these complexities are considered in a Load Rating Analysis

Specifically (45.3.11)...

1. Refined analysis is required
 - Design of new “complex” structures will be “refined” by default
2. Must consider certain load effects (e.g. from curvature and skew)
 - Already in national guidance
3. Submit Refined Analysis Rating Form (on website)
 - Flexible format – provide key information

What is required if a structure is categorized “complex”?

Generally... That these complexities are considered in a Load Rating Analysis


Specifically (45.3.11)...

1. Refined analysis is required
 - Design of new “complex” structures will be “refined” by default
2. Must consider certain load effects (e.g. from curvature and skew)
 - Already in national guidance
3. Submit Refined Analysis Rating Form (on website)
 - Flexible format – provide key information

What constitutes “refined” analysis?

- National resources: AASHTO, FHWA “Manual of Refined Analysis” (in-progress), NSBA G13.1
- Generally considered to be FEA (2D vertical/horizontal, PEB, 3D)
 - Chp 45 not dictating how to perform refined analysis
 - May depend on project requirements
- Refined \neq Complex
 - A 3D FE model can arguably be more efficient in some situations

e.g. stringer \rightarrow floorbeam \rightarrow girder



What is required if a structure is categorized “complex”?


Generally... That these complexities are considered in a Load Rating Analysis

Specifically (45.3.11)...

1. Refined analysis is required
 - Design of new “complex” structures will be “refined” by default
2. Must consider certain load effects (e.g. from curvature and skew)
 - Already in national guidance
3. Submit Refined Analysis Rating Form (on website)
 - Flexible format – provide key information


Torsion

- Caused by eccentric loading (i.e. structure on a horizontal curve)
- Torque is imparted to girders
- Results in additional normal and shear stresses (on top of those imparted from primary bending)
- Box girders and plate girders handle this differently




Load Shifting

- Global overturning resisted by force couples
- Additive effect to some girders, relieving effect to others
- Analogous to overturning (moment, eccentric load) in pile groups
 - If curve is slight enough, the effects of curvature on the gravity loads (i.e. “load shifting”) can be neglected – see LRFD 4.6.1.2.4



Flange Lateral Bending

- Flange Lateral Bending due to curvature effects must always be accounted for per LRFD
- Effects of Skew on f_l are more variable and difficult to predict
 - Investigate effects with discontinuous cross-frames with skews greater than 20°
- f_l due to skew determined by:
 1. Directly (3D FEM)
 2. Approximate eqns. and recommended values – see C6.10.1



What is required if a structure is categorized “complex”?

Generally... That these complexities are considered in a Load Rating Analysis

Specifically (45.3.11)...

1. Refined analysis is required
 - Design of new “complex” structures will be “refined” by default
2. Must consider certain load effects (e.g. from curvature and skew)
 - Already in national guidance
3. Submit Refined Analysis Rating Form (on website)
 - Flexible format – provide key information

REFINED ANALYSIS RATING FORM

In Addition to this form, submit electronic analysis files (eg. .MDX, .bdb)

ANALYSIS FILE SUMMARY (FILL OUT FOR EACH ANALYSIS FILE SUBMITTED)

Analysis Type: Grid/Grillage Plate & Ecc. Beam 3D FEM Other (describe below)

Analysis Program: MDX AASHTOWare CSI Bridge LARSA Other


Program Version: _____

File Name: _____

File Description: Describe the purpose of the file. Example: This file is used for the Wis-SPV rating using single lane distribution.

Analysis Assumptions: Highlight key assumptions in modeling. (This section may be omitted if submitting MDX or AASHTOWare analysis files. This section may also be omitted if submitting separate document containing analysis assumptions and results). Example of things to include: a description of the finite element model, simplifications made to model, exceptions to original design plans, loads applied, how loads are applied (e.g. equally distributed to all girders), support conditions, composite/non-composite sections.

Summary of Results: Summarize results. (This section may be omitted if submitting MDX or AASHTOWare analysis files. This section may also be omitted if submitting separate document containing analysis assumptions and results). Provide table of results for service load reactions, moment, shear, and/or stress output for members at 10th points (minimum) for the appropriate load cases. Provide a table of capacities at each 10th point, such that load ratings can be directly computed with appropriate load and/or resistance and impact factors. Provide example or typical calculations.



In Addition to this form, submit electronic analysis files (eg. .MDX, .bdb)

ANALYSIS FILE SUMMARY (FILL OUT FOR EACH ANALYSIS FILE SUBMITTED)

Analysis Type: Grid/Grillage Plate & Ecc. Beam 3D FEM Other (describe below)

Analysis Program: MDX AASHTOWare CSI Bridge LARSA Other

Program Version: _____

File Name: _____

File Description: Describe the purpose of the file. Example: This file is used for the Wis-SPV rating using single lane distribution.

Analysis Assumptions: Highlight key assumptions in modeling. (This section may be omitted if submitting MDX or AASHTOWare analysis files. This section may also be omitted if submitting separate document containing analysis assumptions and results). Example of things to include: a description of the finite element model, simplifications made to model, exceptions to original design plans, loads applied, how loads are applied (e.g. equally distributed to all girders), support conditions, composite/non-composite sections.

Summary of Results: Summarize results. (This section may be omitted if submitting MDX or AASHTOWare analysis files. This section may also be omitted if submitting separate document containing analysis assumptions and results). Provide table of results for service load reactions, moment, shear, and/or stress output for members at 10th points (minimum) for the appropriate load cases. Provide a table of capacities at each 10th point, such that load ratings can be directly computed with appropriate load and/or resistance and impact factors. Provide example or typical calculations.



OR...

Your own template is fine...

DOUGLAS COUNTY, WI
ST. LOUIS COUNTY, MN
 CITY OF SUPERIOR, WI
 &
 CITY OF DULUTH, MN
 USH 2 OVER ST. LOUIS RIVER (BONG BRIDGE)
 STRUCTURE B-13-38
 RATING COMPUTATIONS
 48-SPAN STEEL PLATE GIRDER BRIDGE
 1.5" MIN. OVERLAY
 HS-20 LOADING
 April 2013

 Ayres Associates Project Number: 42-0825.00
 Designed by: *** Date: 4-23-13
 Checked by: *** Date: 5-28-13

Bridge Evaluation
 WisDOT Project ID: 0656-22-11
 Bridge: B-12-27
 Hwy: 18/60 EW over Mississippi River
 Prairie du Chien, WI
 Submitted by: Teng & Associates, Inc.
 March 2012


ADJ 3/19/2014

Rating of Concrete Arch (B-37-568)


Eau Claire Dell's Bridge
Town of Plover
Marathon County

Summary of Rating
Controlling Location: Element 2 & 15
LFR: LFR
Rating Method: HS-28 (inventory)
Rating: HS-47 (operating)
Posting: No
Comment: Evaluation requested due to deterioration of and stone facing. The main structural component is in good condition and no section loss was assumed. In the model analysis, the controlling elements are Element 2 & 15. There is a degree of conservatism to the model analysis to dictate live load distribution and impact vary. The live load distribution factor was applied to the entire bridge.

Element	Controlling Thickness [in]	Controlling Reaction				RATING (HS-xx)	
		P _{DL} [kips]	M _{DL} [kip-ft]	P _{LL} [kips]	M _{LL} [kip-ft]	Inventory	operating
1	41.5	45.9	42.5	12.1	36.5	46	76
2	31.25	42.6	36.3	12.9	31.5	28	47
3	26.5	40.7	22.1	13.2	23.3	39	66
4	22.75	39.8	14.9	13.3	16.9	54	90
5	20.5	38.4	9.2	13.4	13.5	61	103
6	17.0	37.5	3.6	13.3	11.4	63	105
7	14.75	36.7	3.8	13.1	11.6	43	73
8	14.0	36.3	1.9	12.8	10.4	45	75


Rating Results Table

Analysis
Program/Method: CSI Bridge, P-M interaction diagrams
Assumptions: The arch was modeled as a 2-dimensional frame (see model diagram). The arch barrel was subdivided into smaller sections to capture the section properties. The remaining frame elements were modeled with moment-released end conditions, so as to transfer only axial forces through the arch. Nodes were connected at angles to mimic the original structure plans and assumed fixed to rotation at the spring. Supports were located at the construction of the bridge based on a 12" tributary width. Weight due to spandrel was assumed to be equally distributed to the 30-ft total arch width. Live load was calculated according to section 3.24 and 6.4 of the AASHTO Specification. Horizontal earth pressure was assumed to be zero. Per 6A.5.7 of the AASHTO Manual for Bridge Design, the arch members subjected to axial and flexural forces should be analyzed using interaction diagrams. Once the interaction diagram was obtained, the analysis were used to obtain a rating.



...But please fill it with meaningful information

Why is this “complex” distinction important?



What are the benefits?

- Consistency
 - In analysis assumptions
 - Among engineers
- Repeatability/Documentation
(Refined Analysis Rating Form)
 - For timely responses in permitting requests
 - Scoping, Posting, Damage



Performing a load rating on a complex structure?

Please contact rating unit:

Andrew Smith

Andrew.Smith@dot.wi.gov

608-266-0989

Josh Dietsche

Joshua.Dietsche@dot.wi.gov

608-266-8353

Self-Consolidating Concrete for Prestressed Girders

Steven Doocy, P.E.

2018 WisDOT Structural Engineers Symposium
University of Wisconsin-Madison Union South, Madison, WI

May 22, 2018



**BUREAU OF
STRUCTURES**

Introduction

- Research
- Test Girder
- Specification
- Implementation

Self-Consolidating Concrete for Prestressed Bridge Girders

Junwon Seo, PhD, PE (Assistant Professor)
Eduardo Torres, EIT (Graduate Student)
William Schaffer, EIT (Graduate Student)

Department of Civil and Environmental Engineering
South Dakota State University

SPV.0090 - Prestressed Girder Type I 54w Inch – Self-Consolidating Concrete.

This special provision describes requirements for self-consolidating concrete (SCC) mixture proportioning and test methods for fabrication of prestressed concrete bridge girders for structure B-17-223. Conform to standard specification Section 503 as modified in this special provision.

Replace 503.2.2 (5) with the following:

(5) The contractor may furnish prestressed concrete members cast from air-entrained concrete. Furnish concrete materials conforming to standard specification Section 501. Use Type I, IL, IS, IP, IT, II or III cement. The contractor may replace up to 30 percent of Type I, IL, II or III cement with an equal weight of fly ash or slag, or a combination of fly ash and slag. Use only one source and replacement rate for work under a single bid item. The gradation of the principal coarse



SCC for Prestressed Girders

Research Team

- Researchers
 - South Dakota State University
- Industry
 - County Materials
 - Spancrete
- WHRP Team
 - WisDOT
 - UW-Madison

Research

- Goals

- Develop mixture and testing requirements to supplement the Std. Spec.

(6) The contractor shall determine the proportions for the mix within the following limitations:

Water/cementitious material ratio (w/cm)	0.35 or less ⁽¹⁾
Cementitious materials content.....	750-800 pounds per cubic yard
Fine aggregate to total aggregate ratio.....	0.50 or less
Air content for prestressed I-type girders.....	6.0 percent maximum
Slump Flow (per ASTM C1611).....	25 to 28 inches ⁽²⁾
Visual Stability Index (VSI) (per ASTM C1611).....	0 to 1
Passing Ability by J-Ring (per ASTM C1621)	+/- 2.0 inches difference from slump flow
Column Segregation (per ASTM C1610).....	15 percent maximum



Research

- Results

- Strength
- Camber
- Transfer length
- Losses due to creep and shrinkage

Table 1 Compressive Strength Results

Time	CC (psi)	SCC (psi)
16 hr.	8157	7477
28 Days	11505	11270

Table 2 Camber Results

Time	CC (in)	SCC (in)
Day 1	0.62	0.5
28 days	1.0	1.25

Table 3 Transfer Length Results

Time	CC (in)	SCC (in)	AASHTO (in)
1 Day (Immediately after release)	24.0	19.0	36
28 Days	24.5	20.0	

Table 4 Prestress Losses

Time	CC (ksi)	SCC (ksi)	Type of Losses
1 Day (after release)	10.61	9.077	Elastic Shortening
1 st week	11.85	10.59	Time-Dependent Properties
2 nd week	12.83	11.70	
3 rd week	13.05	11.94	
4 th week (28 days)	14.07	12.92	

Test Girder


B-40-858



Test Girder

B-40-858

- 28 – 36W girders, 41'-9" long
- County Materials donated a girder (cast 29 total girders, 28 normal concrete, 1 SCC) for proof of concept
- If SCC girder met specifications, we would install it on the bridge



Test Girder

Conventional Pour



SCC for Prestressed Girders

Test Girder

SCC Pour



SCC for Prestressed Girders

Specification

- SPV for SCC
 - Concise SPV was developed with WisDOT Materials section
 - Specified testing, material and construction information for SCC.

SPV.0090 - Prestressed Girder Type I 54w Inch – Self-Consolidating Concrete.

This special provision describes requirements for self-consolidating concrete (SCC) mixture proportioning and test methods for fabrication of prestressed concrete bridge girders for structure B-17-223. Conform to standard specification Section 503 as modified in this special provision.

Replace 503.2.2 (5) with the following:

(5) The contractor may furnish prestressed concrete members cast from air-entrained concrete. Furnish concrete materials conforming to standard specification Section 501. Use Type I, IL, IS, IP, IT, II or III cement. The contractor may replace up to 30 percent of Type I, IL, II or III cement with an equal weight of fly ash or slag, or a combination of fly ash and slag. Use only one source and replacement rate for work under a single bid item. The gradation of the principal coarse aggregate source shall meet WisDOT size No. 1 requirements, but the contractor may replace up to 40 percent by weight of the total coarse aggregate with intermediate sized aggregate meeting ASTM C33 size #8 aggregate gradation requirements.

Replace 503.2.2 (6) with the following:

(6) The contractor shall determine the proportions for the mix within the following limitations:

Water/cementitious material ratio (w/cm)	0.35 or less ⁽¹⁾
Cementitious materials content.....	750-800 pounds per cubic yard
Fine aggregate to total aggregate ratio.....	0.50 or less
Air content for prestressed I-type girders.....	6.0 percent maximum
Slump Flow (per ASTM C1611).....	25 to 28 inches ⁽²⁾
Visual Stability Index (VSI) (per ASTM C1611).....	0 to 1
Passing Ability by J-Ring (per ASTM C1621)	+/- 2.0 inches difference from slump flow
Column Segregation (per ASTM C1610).....	15 percent maximum

For qualification of new mixes, demonstrate passing test results for all required properties. During concrete production using accepted mixes, test air content, slump flow and VSI for every load, and test J-ring and column segregation a minimum of once daily.


⁽¹⁾The water/cementitious materials ratio is the weight of the total added water plus the aggregate free water, divided by the total weight of the cement, fly ash and slag.

⁽²⁾Proportion the mix to provide a uniform quality and consistency with a slump flow no greater than necessary for proper placement and consolidation.

Implementation

B-17-223/224

- Looked for longer structure with deeper girders
- 10 – 54W girders @ 127' long (twin structures)
- 223 – mandatory SCC
- 224 – optional SCC



Implementation

- Cost??



Implementation

Current Data

Camber

- Actual = 4.00"
- Plan = 4.28"


Compressive Strength

- f'_{ci} (actual) = 7,900 psi
- f'_{ci} (plan) = 6,800 psi
- f'_c (actual) = 12,500 psi
- f'_c (plan) = 8,000 psi

Success!!

- Started with a little research
- Lead to a SPV
- Implemented on twin structures
- Future cases.....
 - Use for all girders
 - Complex concrete pours/tight rebar cages
 - Substructures
 - Other?

Questions



Miscellaneous Geotechnical/Structural Topics

Jeff Horsfall

BTS – Geotechnical Engineer

2018 WisDOT Structural Engineers Symposium
University of Wisconsin-Madison Union South, Madison, WI

May 22, 2018



**BUREAU OF
STRUCTURES**

Communications



“Well, I’ll be. ... I must’ve been holding the dang work order like *this!*”

Geotechnical/Structural Topics

- Geotechnical Manual
- Consultant Submittals
- Pre-boring in Consolidated Material (Intermediate GeoMaterial-IGM)

Geotechnical Manual

- Developed in April 2017 and published on the DOTNET

<http://wisconsindot.gov/Pages/doing-bus/eng-consultants/cnslt-rsrcs/default.aspx>

GEOTECHNICAL MANUAL



Wisconsin Department of Transportation
April 2017

Section 7-1 General

Section 7-2 Foundation Types

Section 7-3 Foundation Analyses and Design

Section 7-4 Subsurface Investigations – All Structures

Section 7-5 Bridges

Section 7-6 Retaining Walls

Section 7-7 Box Culvert, Rigid Frame and Plate Arches

Section 7-8 Ancillary Structures

Consultant Submittals

Special Provisions template gives:

I. SOILS AND SUBSURFACE INVESTIGATIONS

Add gINT soil boring logs and soils laboratory data to the following email addresses.

DOTDTSDGeotechnicalgINT@dot.wi.gov

DOTDTSDGeotechnicalSirLab@dot.wi.gov

Pre-boring in Consolidated Material (Intermediate GeoMaterial-IGM)

550.3.9 Pre-Boring

550.3.9.1 General

(1) Pre-bore holes to the depth the plans or special provisions require. Submit written requests for pre-boring not required under the contract to the engineer for review and approval. Do not impair the capacity of in-place piles or damage adjacent structures by pre-boring operations.

550.3.9.3 Pre-Boring in Rock or Consolidated Materials

- (1) For round piles, pre-bore holes at least one inch larger than the pile outside diameter. For other shapes, pre-bore holes at least one inch larger than the greatest diagonal pile section dimension.
- (2) Case holes as necessary to prevent introduction of unconsolidated material. Seat the casing firmly into the rock or consolidated material surface. Clear debris from the pre-bore hole before installing the pile.
- (3) Firmly seat piles after preboring and backfill within the rock or consolidated material with a cement grout. Remove the casing, backfill the piles with sand or other engineer-approved material, and dispose of excess material.
- (4) Do not blast without the engineer's approval.

Pre-boring in Consolidated Material (Intermediate GeoMaterial-IGM)

Intermediate GeoMaterial-IGM


- Cohesive IGMs exhibited unconfined compression strengths between 10 ksf to 100 ksf
- Cohesionless IGMs exhibited blow counts greater than 50 blows per foot (bpf) using a Standard Penetration Test


Project Illustration

B-13-831/832 USH18/USH 151 over CTH PD

Structure Consultant AECOM

Geotechnical Consultant SOILS & ENGINEERING SERVICES, INC.





STATE PROJECT NUMBER
1205-07-75

- LIST OF DRAWINGS**
1. GENERAL PLAN
 2. GENERAL NOTES & DESIGN DATA
 3. CROSS SECTION & DIMENSIONS
 4. PROFILE GRADE LINE
 5. SUBSURFACE EXPLORATION
 6. SURFACE ELEVATION
 7. SUBSURFACE EXPLORATION
 8. SUBSURFACE EXPLORATION

TABLE OF INTERSECTION POINTS

POINT	STA. 90+00	STA. 92+00	STA. 94+00	STA. 96+00	STA. 98+00	STA. 100+00
A	100+00	100+00	100+00	100+00	100+00	100+00
B	100+00	100+00	100+00	100+00	100+00	100+00
C	100+00	100+00	100+00	100+00	100+00	100+00
D	100+00	100+00	100+00	100+00	100+00	100+00
E	100+00	100+00	100+00	100+00	100+00	100+00
F	100+00	100+00	100+00	100+00	100+00	100+00
G	100+00	100+00	100+00	100+00	100+00	100+00
H	100+00	100+00	100+00	100+00	100+00	100+00
I	100+00	100+00	100+00	100+00	100+00	100+00
J	100+00	100+00	100+00	100+00	100+00	100+00
K	100+00	100+00	100+00	100+00	100+00	100+00
L	100+00	100+00	100+00	100+00	100+00	100+00
M	100+00	100+00	100+00	100+00	100+00	100+00



BENCH MARK TABLE

NO.	STATION	DESCRIPTION	ELEVATION
06	90+00	TOP MET HD	582.25
07	90+00	TOP MET HD	582.25

NO.	DATE	REVISION	BY

AECOM

STATE OF TEXAS
DEPARTMENT OF TRANSPORTATION

PROJECT: **NEW STRUCTURE OVER HIGHWAY**

STRUCTURE B-13-833

WE VERONA ROAD OVER CTH PD



CONTRACT: **1205-07-75**

DESIGN: **1205-07-75**

CONSTRUCTION: **1205-07-75**

GENERAL PLAN

PROJECT 2 OF 8





Project Team Foundation Discussion


Options

H-piles driven using modified Gates (resistance factor = 0.50)

H-piles driven using Pile Driving Analyzer (resistance factor = 0.65)

Pre-bored H-piles with a Static Load Test (resistance factor = 0.80)
































Questions



BOS Overlay Policy

James Luebke
Structural Development Engineer

2018 WisDOT Structural Engineers Symposium
University of Wisconsin-Madison Union South, Madison, WI

May 22, 2018



BUREAU OF
STRUCTURES

Current Bridge Manual

- Bridge Manual
 - Section 40.5 – Deck Overlays
 - Guidelines
 - Methods
 - Miscellaneous Item



3 pages

Overlay Methods

- Active
 - Thin Polymer
 - Low Slump Concrete
- Less Active
 - Polymer Modified Asphaltic
 - Polyester Polymer
 - Asphaltic
- Not Active
 - Asphaltic with Membrane



Thin Polymer Overlay
(Preservation)




Concrete Overlay
(Rehabilitation)


Overlay Methods

- Further Developments
 - Polyester Polymer
 - Asphaltic with Membrane
 - Latex Modified Concrete
- Further Guidance
 - WiSAMS (Wisconsin Structures Asset Management System)
 - Bridge Manual
 - Standard Details
 - Specifications


Past Overlay Usages




Past Overlay Usages




Past Overlay Usages




Past Overlay Usages




Past Overlay Usages



Past Overlay Usages



Past Overlay Usages



Updated Bridge Manual

- Bridge Manual
 - Section 40.5 – Deck Overlays
 - Methods
 - Selection Considerations
 - Background Information



20+ pages

Overlay Type	Advantages	Disadvantages	Notes
Thin Polymer Overlay	<ul style="list-style-type: none"> Minimal dead load Minimal traffic disruption Smooth deck Provides traction 	<ul style="list-style-type: none"> Requires a concrete age of at least 21 days Requires decks with minimal delamination and loose materials, and humidity at placement, if humidity affects curing Requires concrete with moisture content below 4% at placement Requires concrete with minimum compressive strength of 4,000 psi Requires concrete with minimum curing time of 7 days 	<ul style="list-style-type: none"> Requires BCI-III Prior Approval
Low Slump Concrete Overlay	<ul style="list-style-type: none"> Construction methods and equipment experience Long life span potential Durable Ease to accommodate grade differences and deficiencies 	<ul style="list-style-type: none"> Traffic disruptions Additional dead load High maintenance requirements Substantial curing time Specialized finishing equipment High cost Costly labor equipment Limited usage in Wisconsin Variable temperature, and humidity of placement Difficult to maintain 	<ul style="list-style-type: none"> Requires BCI-III Prior Approval
Preformed Polymer Concrete Overlay	<ul style="list-style-type: none"> Minimal dead load Minimal traffic disruption Provides traction Long life span potential Durable Low maintenance Substantial curing time 	<ul style="list-style-type: none"> High cost Costly labor equipment Limited usage in Wisconsin Variable temperature, and humidity of placement Difficult to maintain 	<ul style="list-style-type: none"> Requires BCI-III Prior Approval
Asphalt Overlay	<ul style="list-style-type: none"> Minimal traffic disruption Ease to construct Can be used on more flexible structures (e.g. bridge deck over bents) Low cost Easy to construct Ease to accommodate grade differences and deficiencies 	<ul style="list-style-type: none"> High cost Substantial curing time Difficult to access top of deck condition Costly labor equipment Not eligible for Federal funds Variable permeability Difficult to access top of deck condition 	<ul style="list-style-type: none"> Contract requires an inspection Material research has been performed on the durability of this system in Wisconsin Check or bridge replacement should be programmed within 4 years
Asphalt Overlay with Membrane	<ul style="list-style-type: none"> Minimal traffic disruption Long life span potential Can be used on more flexible structures (e.g. bridge deck over bents) Low cost Ease to construct Ease to accommodate grade differences and deficiencies 	<ul style="list-style-type: none"> High cost Substantial curing time Difficult to access top of deck condition Costly labor equipment Not eligible for Federal funds Variable permeability Difficult to access top of deck condition 	<ul style="list-style-type: none"> Contract requires an inspection Material research has been performed on the durability of this system in Wisconsin Check or bridge replacement should be programmed within 4 years

Table 40.5-2
Overlay Advantages, Disadvantages, and Notes

Overlay Advantages, Disadvantages, and Notes

40.5.3 Deck Assessment

The following are common deck assessment tools that can be used to survey existing deck conditions:

- Inspection reports
- Infrared thermography - Infrared Thermography (IR) is an alternative tool for locating and mapping delaminations in bridge decks and pavements. A technique using an infrared scanner and control video camera, infrared thermography senses temperature differences between delaminated and non-delaminated areas.

Polyester Polymer Overlay Usage

- Decks in Good Condition
 - NBI rating of 7 or greater
 - Distressed areas < 5%
 - Less than 15 years* old deck
- General Criteria
 - Traffic Restrictions
 - High Traffic (AADT > 20,000)
 - Remaining life > 20 years

New System
Restrictive Usage

Polyester Polymer Overlay Usage

Thin Polymer Overlays

- Decks in Good Condition

- NBI rating ≥ 7
- Distressed areas $< 5\%$
- Deck age < 15 years*

- General Criteria

- Traffic Restrictions
- High Traffic (AADT $> 20,000$)
- Remaining life > 20 years

- NBI rating > 7


- Distressed areas $< 2\%$

- Deck age < 10 years*

- No General Restrictions

Overlay Policy

- Overlay Selection
- Resources
 - Region
 - Bridge Manual
 - BOS
- Coordination



Marquette Interchange PPC Overlays

Presented by:

Jason Sadowski, PE, SE



**BUREAU OF
STRUCTURES**

**Michael Baker
INTERNATIONAL**

Agenda

- Project Overview
- Bridge Preservation
- What is PPC and why use it?
- Marquette Interchange Project
- Construction
- Conclusion

Project Overview


Michael Baker
INTERNATIONAL

Marquette Interchange Scope

- PPC overlay
- Lighting upgrade to LED
- ITS
- Splice plate painting

Valley Bridge Scope


- Concrete overlay




What is Bridge Preservation?

Michael Baker
INTERNATIONAL

- Extend service life
- Limit traffic impacts
- Optimize life cycle costs
- Cyclical activity



What is Bridge Preservation?




What is PPC and why use it?

Michael Baker
INTERNATIONAL

Polyester Polymer Concrete


- Binder
- Aggregate
- Sealing Primer



“Gamma-methacryloxypropyltrimethoxysilane”

What is PPC and why use it?

Michael Baker
INTERNATIONAL



Pros

- Impermeable seal
- Fast cure – all temps
- Durability
- Friction

What is PPC and why use it?

Michael Baker
INTERNATIONAL

Cons

- Cost (\$10-\$12 / sf)
- Few local contractors
- Fast cure



Identify the right projects!

What is PPC and why use it?

PPC

- Single course
- 3/4" minimum
- Impermeable
- 20-30 year life
- 2 – 4 hour cure
- Shotblast CSP 5
- \$10-12/sf

Thin Polymer

- Two course
- 3/8" typical
- Mostly impermeable
- 10-15 year life
- 4 – 14 hour cure
- Shotblast CSP 5
- \$3/sf

Marquette Interchange PPC Specification

Michael Baker
INTERNATIONAL

- Co-operative effort
- Experience requirements
- Bond critical performance
- $\frac{3}{4}$ " milling (optional)




Marquette Interchange Structural Design

Michael Baker
INTERNATIONAL

BOS Criteria

- ✓ Preservation project
- ✓ Age 10 years +/-
- ✓ Avg. NBI 6.7
- ✓ Deck distress < 1%
- ✓ Chloride profile
(5 lb limit at rebar)
- ✓ Traffic volume
- ✓ Key infrastructure




Marquette Interchange Traffic Control

Michael Baker
INTERNATIONAL


Staged vs. Full Closure

- 16' clear zone for PPC equipment
- Min roadway width = 36' for staged construction



Marquette Interchange Traffic Control

Michael Baker
INTERNATIONAL



PPC Construction Preparation

Michael Baker
INTERNATIONAL



Milling

- In advance of PPC
- Added PPC quantity
- Profile milling

Shot blasting

- 48" blaster – 6,000 sf/hr
- Spot cleaning



PPC Construction Placement

Michael Baker
INTERNATIONAL



- 2,000' per night
- Place uniform thickness
- Keep the paver moving
- Hardness testing

PPC Construction Spot Repairs

Michael Baker
INTERNATIONAL



- Sawcut and replace
- Methacrylate sealer to fill cracks

Driving Factors for Utilizing PPC


Michael Baker
INTERNATIONAL

- Traffic volume
- No joint replacement
- Limited impacts
- Difficulty to re-deck
- Complex structures
- Desire to delay major rehab



Conclusion

- Find the right projects!
- New WBM guidance
- On-going development



Potential Upcoming Southeast PPC Projects

WisDOT Structural Engineers Symposium

Michael Baker
INTERNATIONAL



Thank You!

3D Design & Modeling, BIM for Bridges and Structures

Danielle De Tennis & Adam Swierczek
BOS Structural Automation Engineer & Design Engineer



2018 WisDOT Structural Engineers Symposium
University of Wisconsin-Madison Union South, Madison, WI

May 22, 2018



**BUREAU OF
STRUCTURES**

What is BIM for Bridges and Structures?



What is our goal with BIM?

- Create an open data exchange between all involved parties for the lifecycle of the structure
 - Software-independent solutions
 - Streamline data exchanges
 - Eliminate data entry errors

BIM in BOS Design

- Preliminary Design
 - Create initial approximate structure geometry
 - Improve geometry coordination with roadway




BIM in BOS Design

- Hydrology & Hydraulics
 - Velocity vectors/flowpaths in X and Y direction – more accurate information leads to better bridge sizing, substructure placement and skew
 - Improved accuracy of scour prediction parameters
 - LiDAR and Bathymetry are easily integrated when developing a model
 - Identify conveyance patterns not readily identifiable in 1D models
 - Easier to model complex floodplains
 - Avoid many assumptions inherent to 1D models




BIM in BOS Design

- Final Design
 - Single source of truth throughout design
 - Improve process for design iterations and late design changes
 - Improve spatial awareness of structural components
 - Streamline quantity takeoffs



Baraboo Bypass Example Project




BIM in BOS Fabrication

- Move towards 3D model-based shop drawing submittal and review
 - Many fabricators already create 3D models to generate 2D shop drawings. Generating and fixing up these plans take up a lot of time.
 - They are looking into ways to eliminate the need for 2D plans, or move them closer to the end of the process so the plans don't need to be regenerated so many times.
- BOS is planning a 3D Fabrication pilot project with a steel structure


BIM in BOS Bridge Management

- Looking to add 3D models to HSI
 - Models are generated from data already entered in HSI
 - Inspectors can document defects directly on the model
 - Possibility to store design models & as-built models in the future




BIM in BOS Bridge Management

IFC Models Generated from AASHTOWare




BIM in BOS Bridge Management

IFC Models Generated from AASHTOWare



BIM in BOS Standards

- PDF plans with 3D Details by Iowa DOT
 - We are looking to adopt 3D details in some of our Standard Details
- BIM “Insert Sheets”
 - Standard models for WisDOT PS girder shapes, etc.



THIS IS A 3D FILE THAT CAN BE VIEWED ELECTRONICALLY. YOU WILL BE ABLE TO ZOOM IN OR OUT, PAN, ROTATE, ETC.

THIS STRUCTURE SHALL BE CONSTRUCTED FROM DIMENSIONS SHOWN ON THE PREVIOUS SHEETS. THIS SHEET IS INTENDED TO CLARIFY THE DESIGN DETAILS AS AN AID IN REPAIR OF THE STRUCTURE. CLICK ON THE DEFAULT VIEW ICON (THE HOUSE ICON) IN ADOBE ACROBAT READER TO RETURN TO THE ORIGINAL VIEW.

D.S. BROWN EXPANSION DEVICE SHOWN, SIMILAR FOR WATSON-BOWMAN & ACME CORP. EXPANSION DEVICE.

DESIGN TEAM DLB / JDC / RDM PROJECT DIRECTORY NAME 6803402012 9/30/2013 9:46:15 AM jcollie c:\pwwork\pwwork\jcollie\dms79784168034500.brg 680113a013 11x17.pdf.plt.cfg	MONROE COUNTY PROJECT NUMBER MD-034-S0500163--77-68	SHEET NUMBER 14
---	---	-----------------

DESIGN FOR REPAIRS TO A 37° 15' L.A. SKEW
190'-0" x 30'-0" CONTINUOUS I-BEAM BRIDGE
 58'-0" END SPANS 74'-0" INTERIOR SPAN
 STA. 583+37.00 (US 34) OCTOBER, 2013
MONROE COUNTY
 IOWA DEPARTMENT OF TRANSPORTATION - HIGHWAY DIVISION
 DESIGN SHEET NO. 13 OF 13 FILE NO. 30728 DESIGN NO. 113

IH 94 North South Project Overview

Frank Pritzlaff, P.E.

South/Central Segment Design Project Manager

2018 WisDOT Structural Engineers Symposium
University of Wisconsin-Madison Union South, Madison, WI


May 22, 2018



**BUREAU OF
STRUCTURES**


IH 94 North South Scope of Work - State

- Work Zone Prep Contract
 - February 2018 Let
- South/Central Packages (\$200M - \$250M expected)
 - May 22, 2018 Let
- North Package (\$175M - \$200M expected)
 - August 2018 Let




IH 94 North South Scope of Work – Local Rehab

- STH 20
 - February 2018 Let, June 2018 Completion
- CTH H
 - March 2018 Let, June 2018 Completion
- CTH A
 - March 2018 Let, June 2018 Completion



IH 94 North South Scope of Work – Development

- CTH KR
- CTH H
- Braun Road
- STH 11
- International Drive
- Wisconn Valley Way
 - All Construction Slated Between 2018 and 2021



IH 94 North South Quantity Highlights – South/Central Segments Only

- Common Excavation _____ ~ 844,000 CY
- Roadway Embankment _____ ~ 1,414,000 CY
- Base Aggregate Dense _____ ~ 302,000 CY
- Select Crushed Material _____ ~ 521,000 CY
- Concrete Pavement 12-Inch Special _____ ~ 980,000 SY
- Bridge Deck _____ ~ 76,500 SY
- Retaining Walls _____ ~ 130,000 SF

IH 94 North South Staging Concept (Accelerated)

- Two lanes in each direction (2/2 traffic)
 - 6 months 06/18 to 11/18
- Three lanes in each direction (3/3 traffic)
 - 6 months split bi-directional 12/18 to 05/19
 - 6 months bi-directional 06/19 to 11/19
- Reduces construction from 30 months to 18 months

IH 94 North South Staging Concept (Accelerated)

Stage 2: June – November 2018



Stage 3: December 2018 – May 2019



Stage 4: June – November 2019



IH 94 North South Unique Roadway Elements

- Compressed/Accelerated Construction Schedule
- Stage 3 Construction Through Winter
- Approximately 13' Profile Grade Change at CTH KR/Braun Road
- Multiple Adjacent Public and Private Projects
 - CTH K Crossroads, IH 94 Frontage Roads, Wis 45 Rehab, Wis 20/CTH C Roundabout, Foxconn Development, etc.
- Items Left in Place from Previous Prep Contract
- On Site Batch Plant/Crushing/Staging Locations

IH 94 North South Structures

Aaron Bonk, P.E.

Bureau of Structures Design Supervisor

IH 94 NS Structures Lead

2018 WisDOT Structural Engineers Symposium
University of Wisconsin-Madison Union South, Madison, WI

May 22, 2018




**BUREAU OF
STRUCTURES**

IH 94 NS Structures


Project Site Overview

- 27 Bridges
- 17 Retaining Walls
- 46 Sign Structures



IH 94 NS Structures Design Delivery Schedule

- Original designs and PS&E's in late 2000's/early 2010's
- Project restarted in 2017 with PS&E's set for early/mid 2018
 - Updates to LRFD for Racine/Kenosha County Structures
 - Standard Updates (Structural Approach Slabs, Parapet Size/Shape, etc.) for All Structures




IH 94 NS Structures

Unique Aspects of Design

- Typical prestress girder and slab span bridges...
 - Except for the condensed delivery schedule and “standards” updates required
- Typical vertical underclearance requirements...
 - Except for 6m requirement near Foxconn site
- Typical pier design...
 - Except for requirement not to preclude contractor precast option
- Partial depth precast prestressed deck panels required

IH 94 NS Structures Foxconn Area Impacts to Structures

- Full Redesign for 2 Interchanges and 2 Overpasses (14 State Structures and 10± Local Structures Impacted)
- Bridge Configurations In Flux Until Early 2018
- 6m Vertical Underclearance Requirement



IH 94 NS Structures Pier Design


- Construction Schedule Dictated ABC (Precast Pier) Option
- Multi-column Piers Designed as CIP, but not to Preclude Contractor Precast Option
- Chapter 7 Bridge Manual Standards



☆ THE CONTRACTOR MAY FURNISH PRECAST CONCRETE PIER IN LIEU OF THE CAST-IN-PLACE PIER WITH THE ACCEPTANCE OF THE SHOP DRAWINGS BY THE STRUCTURES DESIGN SECTION. THE PRECAST CONCRETE PIER SHALL CONFORM TO PRECAST DETAILS IN CHAPTER 7 STANDARDS OF THE CURRENT WISCONSIN DOT BRIDGE MANUAL AND SPECIAL PROVISIONS RELATED TO PRECAST ELEMENTS WITH THE EXCEPTION OF METHOD OF PAYMENT. PAYMENT FOR THE PRECAST PIER SHALL BE BASED ON THE QUANTITIES AND PRICES BID FOR THE ITEMS LISTED IN THE "TOTAL ESTIMATED QUANTITIES" FOR THE CAST-IN-PLACE PIER.

ELEVATION CHANGES DUE TO CAST-IN-PLACE BEARING BLOCKS SHALL REQUIRE SMALL DIMENSIONAL ADJUSTMENTS TO THE COLUMNS.

■ IF THE CONTRACTOR CHOOSES TO FURNISH PRECAST PIER MEMBERS, THE CAP HEIGHT SHALL BE 4'-0". THE REMAINING DIFFERENCE BETWEEN THE BEAM SEAT ELEVATIONS AND TOP OF 4'-0" CAP WILL BE THE "H" DIMENSION OF THE PRECAST BEARING BLOCKS. CONTRACTOR TO DETERMINE CAST-IN-PLACE BEARING BLOCK HEIGHTS. MINIMUM "H" VALUE TO BE GREATER THAN 5¹/₄", MAXIMUM "H" VALUE TO BE LESS THAN 2'-0". ADJUST SUBSTRUCTURE ELEVATIONS TO OBTAIN MINIMUM 5¹/₄" "H" VALUE AS NEEDED. PAYMENT FOR ANY ELEVATION ADJUSTMENT SHALL BE BASED ON THE QUANTITIES AND PRICES BID FOR THE ITEMS LISTED IN THE "TOTAL ESTIMATED QUANTITIES" FOR THE CAST-IN-PLACE PIER.



ELEVATION CHANGES DUE TO CAST-IN-PLACE BEARING BLOCKS SHALL REQUIRE SMALL DIMENSIONAL ADJUSTMENTS TO THE COLUMNS.

■ IF THE CONTRACTOR CHOOSES TO FURNISH PRECAST PIER MEMBERS, THE CAP HEIGHT SHALL BE 4'-0". THE REMAINING DIFFERENCE BETWEEN THE BEAM SEAT ELEVATIONS AND TOP OF 4'-0" CAP WILL BE THE "H" DIMENSION OF THE PRECAST BEARING BLOCKS. CONTRACTOR TO DETERMINE CAST-IN-PLACE BEARING BLOCK HEIGHTS. MINIMUM "H" VALUE TO BE GREATER THAN 5¹/₄". MAXIMUM "H" VALUE TO BE LESS THAN 2'-0". ADJUST SUBSTRUCTURE ELEVATIONS TO OBTAIN MINIMUM 5¹/₄" "H" VALUE AS NEEDED. PAYMENT FOR ANY ELEVATION ADJUSTMENT SHALL BE BASED ON THE QUANTITIES AND PRICES BID FOR THE ITEMS LISTED IN THE "TOTAL ESTIMATED QUANTITIES" FOR THE CAST-IN-PLACE PIER.

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION STRUCTURES DESIGN SECTION			
STRUCTURE B-30-113			
DRAWN BY		PLANS CHECKED	
		MJK	
PRECAST PIER ALTERNATIVE			SHEET 12


IH 94 NS Structures

Partial Depth Precast Prestressed Deck Panels


- Construction Schedule Dictated ABC (Partial Depth Precast Prestressed Deck Panels for Girder Bridges) Requirement
- Bridges Designed to Require Panel Use
- Refined/Updated Chapter 17.10 Bridge Manual Details




STATE PROJECT NUMBER
1035-03-72




DECK PANEL ELEVATION [P1]




TRANSVERSE SECTION THRU GIRDERS AND DECK PANELS



SECTION



DETAIL A - PANEL PLACEMENT




LIFTING/CONN. HOOK DETAILS


- NOTE: BARS IN WWF WHICH ARE PARALLEL TO THE STRANDS MUST BE A MINIMUM OF 1" CLEAR FROM THE STRANDS.
- * 3'-0" MAX SPACING BETWEEN ADJACENT ROWS
 - * * LONGITUDINAL REINFORCING AT PANELS ALONG SUBSTRUCTURES TO EXTEND 1'-0" BEYOND TRANSVERSE END OF PANELS INTO SUBSTRUCTURE DIAPHRAGMS.
 - ▲ HIGH-DENSITY EXPANDED POLYSTYRENE ADHERED TO TOP OF GIRDER FLUSH WITH EDGE OF FLANGE.

DESIGN DATA


INITIAL PRESTRESSED FORCE / STRAND = 14,37 KIPS
CONCRETE FOR DECK PANELS
f'c = 6,000 PSI
f'ci = 4,400 PSI



DECK PANEL PLAN [P1]



DECK PANEL PLAN [P2]




DECK PANEL PLAN [P3]

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION STRUCTURES DESIGN SECTION			
STRUCTURE B-30-113			
DRAWN BY		ABS	PLANS
CHECKED BY		MJK	CHK
PRECAST DECK PANEL DETAILS			SHEET 18

SCALE = 2:00

IH 94 North South

Questions?



Strengthening Program for Local Load Posted Bridges

Alex Pence

Rating Engineer – Local System

Josh Dietsche

Supervisor – Bridge Rating/Management Unit

WisDOT Structural Engineers Symposium
Madison, WI

May 22, 2018



**BUREAU OF
STRUCTURES**

Presentation Overview

- Load Postings on the Local System
 - Load Postings
 - SHV Load Posting Evaluation
- Strengthening Program
 - Program Concept
 - Overview of the Local Inventory
- BOS Efforts for Repair and Rehab
 - Assessing Candidate Bridges
 - Repair Methods





Load Postings on the Local System

Load Postings

- Bridges are load posted when analysis shows they can no longer safely carry legal-weight traffic.
- What is “legal weight?”

Load Postings: Federal Bridge Formula




- Federal Bridge Formula (FBF) provides a standard to control spacing of truck axles/weights...to make sure the bridge was designed to support what can legally cross it.





$$W = 500 * \left[\frac{LN}{N-1} + 12N + 36 \right]$$

Load Postings: Posting Vehicles

- Based on the FBF, AASHTO has an established suite of posting vehicles.



- Wisconsin has two state-specific posting vehicles.




- If/when a bridge can no longer carry legal-weight traffic...




SHV Load Posting Evaluation


- FHWA has mandated that states incorporate SHVs into their posting analysis by December 31, 2017
- Why are SHVs an issue?
 - Legal-weight...
 - ...but exceed intended limits of the FBF
- What are SHVs?




SHV Load Posting Evaluation: Load Models




Type SU5 Unit Weight = 62 Kips (31 tons)



Type SU6 Unit Weight = 69.5 Kips (34.75 tons)



Type SU4 Unit Weight = 54 Kips (27 tons)



Type SU7 Unit Weight = 77.5 Kips (38.75 tons)

SHV Load Posting Evaluation: Results

- So what was the outcome?
 - Some new postings
 - Some lower load postings

Posting Level	Local-Owned	
	Current	w/ SHV
40 ton or greater	372	281
35 ton	52	34
30 ton	11	44
25 ton	17	139
20 ton	100	146
15 ton	110	131
10 ton	71	73
5 ton	34	39
Less than 5 ton	6	6
TOTAL:	773	893



Strengthening Program for Local Load-Posted Structures



Mitigating Load Postings on the Local System

Strengthening Program: Overall Concepts

- The SHV evaluation effort highlighted load posting on the local system
- Load postings are implemented for safety purposes...
 - ...but they restrict the flow of freight
- With support of WisDOT upper management, BOS looks for methods to eliminate postings, when possible
- Strengthening Program For Local Load Posting Structures

Strengthening Program: Overall Concepts

- Work with local owners to implement cost-effective, stream-lined process to repair bridges and remove postings
- BOS to provide engineering and oversight for repairs
- Use local crews (with assistance from WisDOT) to perform repairs

Overview of the Local Bridge Inventory

- The local system is...different...than the state system.
 - Generally older
 - Generally much lower ADT
 - Much higher percentage of single-span
 - More variety of superstructure types
 - Timber
 - Concrete T-girder
 - PS Channel
 - Other...















BOS Efforts for Repair and Rehab




Mitigating Load Postings on the Local System

BOS Efforts for Repair and Rehab

- Want to target “high value” bridges – important for freight & commerce
- Consider life remaining condition
- Not every repair option is feasible for every bridge
- Need to review individually




Best Candidates screening group:

- Posting < 40 TON
- All NBI Conditions 5+
- ADT 100+ *or* ADT<100 w/ 10+ mi Detour






BOS Efforts for Repair and Rehab

- Timber Slab Bridges
 - Wheel Load Distribution




BOS Efforts for Repair and Rehab

- Timber Slab "Spreader Deck"



BOS Efforts for Repair and Rehab

- Timber Slab – Reduce overburden and add stiffener beams



BOS Efforts for Repair and Rehab


- Bolt additional steel section to existing members
 - Can often be done by state or local crews
 - Relatively inexpensive




P-16-47 | CTH B over Balsam Creek in Douglas County



Iowa DOT




BOS Efforts for Repair and Rehab



BOS Efforts for Repair and Rehab


- Make girder composite with slab
 - Several installation options available; would be site dependent
 - Girders assumed to be non-composite if plans are not available
 - First step- field verify if studs already exist




BOS Efforts for Repair and Rehab

- Concrete bridges

- Add rebar
- Add FRP



BOS Efforts for Repair and Rehab




- A. Surface Preparation
- B. Priming and Filling Voids
- C. Locate Strips/Check Surface
- D. Clean and Prepare FRP Strips
- E. Coat Strips with Epoxy
- F. Place Strips
- G. Roll Out to Ensure Total Contact

BOS Efforts for Repair and Rehab



Shear



Flexure

Mitigating Load Postings on the Local System

BOS Efforts for Repair and Rehab




Negative Moment



Positive Moment



BOS Efforts for Repair and Rehab

- RC slab retrofit




BOS Efforts for Repair and Rehab

- Refined analysis goes above and beyond the routine or traditional methods of analysis
- Often involves a 3D model of structure
- Takes advantage of a more true live load distribution (less simplifications)



BOS Efforts for Repair and Rehab

- Enormous amounts of data
- Processing data takes most of the time
- Processing required to obtain useful information for design or load rating purposes
- Requires more judgment, assumptions; less conservative



BOS Efforts for Repair and Rehab

- Other options (more case-specific):
 - **Removing overburden**
 - Install external post-tensioning
 - Add additional substructure units
 - New deck
 - Load testing
 - Enhanced inspection for better information (NDE methods)
 - Other...

Questions?

Alex Pence

alex.pence@dot.wi.gov | 608-267-6880

Josh Dietsche

joshua.dietsche@dot.wi.gov | 608-266-8353

WisDOT Structural Engineers Symposium
Madison, WI

May 22, 2018



**BUREAU OF
STRUCTURES**