



# Wisconsin Department of Transportation

October 28, 2015

**Division of Transportation Systems Development**

Bureau of Project Development  
 4802 Sheboygan Avenue, Rm 601  
 P O Box 7916  
 Madison, WI 53707-7916

Telephone: (608) 266-1631  
 Facsimile (FAX): (608) 266-8459

**NOTICE TO ALL CONTRACTORS:**

**Proposal #07: 5820-01-62**  
**Coon Valley - Bangor**  
**Dutch Creek Br to STH 16**  
**STH 162**  
**La Crosse County**

**Letting of November 10, 2015**

This is Addendum No. 02, which provides for the following:

**Special Provisions**

Added Special Provisions	
Article No.	Description
30	Pavement Marking Epoxy 4-Inch, Item 646.0106

Deleted Special Provisions	
Article No.	Description
26	Steel Thrie Beam Structure Approach Special, Item SPV.0090.01

**Schedule of Items**

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
614.2300	MGS Guardrail 3	LF	8,007	-126	7,881
614.2610	MGS Guardrail Terminal EAT	Each	60	-2	58
646.0106	Pavement Marking Epoxy 4-Inch	LF	88,819	73,237	194,188
649.0100	Temporary Pavement Marking 4-Inch	LF	65,176	129,012	194,188

Deleted Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
646.0406	Pavement Marking Same Day Epoxy 4-Inch	LF	73,237	0	0
SPV.0090.01	Steel Thrie Beam Structure Approach Special	LF	42	0	0

**Plan Sheets**

<b>Revised Plan Sheets</b>	
<b>Plan Sheet</b>	<b>Plan Sheet Title (brief description of changes to sheet)</b>
52-54, 56,60	Miscellaneous Quantity Sheets

**Special Provisions**

**26. DELETED**

**30. Pavement Marking Epoxy 4-Inch, Item 646.0106.**

Add the following to standard spec 646.3.1.2:

Apply permanent centerline markings to the upper layer of new asphaltic pavement or surfacing within 7 days after completing mainline paving, after rumble strips have been installed, and before scheduled work suspension, unless otherwise directed by the engineer.

**Schedule of Items**

Attached, dated October 28, 2015, are the revised Schedule of Items Pages 4, and 6 – 8.

**Plan Sheets**

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:  
Revised: 52 – 54, 56, and 60.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

*Mike Coleman*

Proposal Development Specialist  
Proposal Management Section

END OF ADDENDUM

STEEL PLATE BEAM GUARD

CATEGORY	STATION TO	STATION	LOCATION	LF	REMARKS
614.0200	50+85	51+35	RT		
614.0200	51+23	51+72	LT		
614.0200	51+35	51+85	RT	50	
614.0200	51+72	51+85	LT	13	
614.0200	51+85	52+06	LT		
614.0200	51+85	52+06	RT		
614.0200	52+06	53+06	RT		
614.0200	52+06	53+06	LT		
614.0200	53+06	53+26	RT		
614.0200	53+06	53+26	LT		
614.0200	53+26	53+51	LT		
614.0200	53+26	53+28	RT		
614.0200	53+28	53+29	RT		
614.0200	53+51	54+01	LT		
TOTAL	0010			84	
				200	
				88	
				25	
				3	
				1	

\* Posts are to remain in place on structure. Only Steel Thrie Beam itself is to be replaced.

SALVAGED RAIL

CATEGORY	STATION TO	STATION	LOCATION	LF	REMARKS
0010	419+00	419+58	LT	58	B-32-288 *
0010	419+00	419+58	RT	58	B-32-288 *
0010	422+00	422+58	LT	58	B-32-288 *
0010	422+00	422+58	RT	58	B-32-288 *
TOTAL	0010			232	

\* PROPERTY OF THE STATE. CONTACT TIM HAMMES, PATROL SUPERINTENDENT FOR LA CROSSE COUNTY HIGHWAY DEPARTMENT, (608) 792-1216

CATEGORY	STATION	LOCATION	MANHOLE_COVERS_TYPE	J-SPECIAL
0010	391+99	CL		1
TOTAL	0010			1

SALVAGED GUARDRAIL END TREATMENTS

CATEGORY	STATION	LOCATION	EACH	REMARKS
0010	419+00	LT	1	B-32-288 *
0010	419+00	RT	1	B-32-288 *
0010	422+00	LT	1	B-32-288 *
0010	422+00	RT	1	B-32-288 *
TOTAL	0010		4	

\* PROPERTY OF THE STATE. CONTACT TIM HAMMES, PATROL SUPERINTENDENT FOR LA CROSSE COUNTY HIGHWAY DEPARTMENT, (608) 792-1216

Addendum No. 01  
ID 5820-01-62  
Revised Sheet 52  
October 28, 2015

Addendum No. 01  
ID 5820-01-62  
Revised Sheet 53  
October 28, 2015

CATEGORY	STATION TO STATION		LT/RT	MGS GUARDRAIL			REMARKS
	LF	3K		LF	THRIE BEAM TRANSITION	EAT EACH	
0010	12+28 - 12+48		LT				B-32-160
0010	12+28 - 12+48		RT			21	B-32-160
0010	12+48 - 12+91		LT			43	B-32-160
0010	12+48 - 13+08		RT			60	B-32-160
0010	12+91 - 13+44		LT				B-32-160
0010	13+08 - 13+61		RT				B-32-160
0010	60+70 - 61+23		LT				18 FT TO FACE OF GUARD RAIL
0010	61+23 - 66+48		LT			525	18 FT TO FACE OF GUARD RAIL
0010	66+48 - 67+01		LT				18 FT TO FACE OF GUARD RAIL
0010	77+69 - 78+22		LT				18 FT TO FACE OF GUARD RAIL
0010	78+22 - 101+47		LT			2,325	18 FT TO FACE OF GUARD RAIL
0010	101+47 - 102+00		LT				18 FT TO FACE OF GUARD RAIL
0010	139+78 - 140+31		LT				18 FT TO FACE OF GUARD RAIL
0010	140+31 - 145+56		LT			525	18 FT TO FACE OF GUARD RAIL
0010	145+56 - 146+09		LT				18 FT TO FACE OF GUARD RAIL
0010	167+10 - 167+63		LT				18 FT TO FACE OF GUARD RAIL
0010	167+63 - 181+88		LT			1,425	18 FT TO FACE OF GUARD RAIL
0010	181+88 - 182+41		LT				18 FT TO FACE OF GUARD RAIL
0010	192+94 - 193+47		LT			963	18 FT TO FACE OF GUARD RAIL
0010	193+47 - 203+09.5		LT				18 FT TO FACE OF GUARD RAIL
0010	203+09.5 - 203+62.5		LT				18 FT TO FACE OF GUARD RAIL
0010	205+17 - 205+70		LT				18 FT TO FACE OF GUARD RAIL
0010	205+70 - 217+70		LT			1,200	18 FT TO FACE OF GUARD RAIL
0010	217+70 - 218+23		LT				18 FT TO FACE OF GUARD RAIL
0010	232+00 - 232+53		LT				18 FT TO FACE OF GUARD RAIL
0010	232+53 - 241+66		LT			913	18 FT TO FACE OF GUARD RAIL
0010	241+66 - 242+19		LT				18 FT TO FACE OF GUARD RAIL
0010	251+50 - 252+03		LT				18 FT TO FACE OF GUARD RAIL
0010	252+03 - 260+03		LT			800	18 FT TO FACE OF GUARD RAIL
0010	260+03 - 260+56		LT				18 FT TO FACE OF GUARD RAIL
0010	272+50 - 273+03		LT				18 FT TO FACE OF GUARD RAIL
0010	273+03 - 279+53		LT			650	18 FT TO FACE OF GUARD RAIL
0010	279+53 - 280+06		LT				18 FT TO FACE OF GUARD RAIL
0010	290+00 - 290+53		LT				18 FT TO FACE OF GUARD RAIL
0010	290+53 - 295+03		LT			450	18 FT TO FACE OF GUARD RAIL
0010	295+03 - 295+56		LT				18 FT TO FACE OF GUARD RAIL
	SUBTOTAL					3,966	
						5,913	
						42	
						22	

Addendum No. 01  
ID 5820-01-62  
Revised Sheet 54  
October 28, 2015

MGS GUARDRAIL CONTINUED

CATEGORY	STATION TO	STATION	LT/RT	614. 2300		614. 2500		614. 2610		REMARKS
				MGS GUARDRAIL 3 LF	MGS GUARDRAIL 3K LF	MGS THRIE BEAM TRANSITION LF	MGS GUARDRAIL EAT LF			
0010	316+64 -	317+17	LT					1	B-32-0015	
0010	317+17 -	317+42	LT	25					B-32-0015	
0010	317+42 -	317+63	LT			21			B-32-0015	
0010	316+85 -	317+58	RT					1	B-32-0015	
0010	317+58 -	317+63	RT	25					B-32-0015	
0010	317+63 -	317+84	RT			21			B-32-0015	
0010	318+72 -	318+93	LT			21			B-32-0015	
0010	318+93 -	319+56	LT	63					B-32-0015*	
0010	319+56 -	320+06	LT					1	B-32-0015	
0010	318+02 -	318+23	RT			21			B-32-0015	
0010	318+23 -	319+36	RT	113					B-32-0015*	
0010	319+36 -	319+89	RT					1	B-32-0015	
0010	400+50 -	401+03	LT					1		
0010	401+03 -	414+78	LT	1, 375						
0010	414+78 -	415+31	LT					1		
0010	401+57 -	402+10	RT					1		
0010	402+10 -	404+47.5	RT	238						
0010	404+47.5 -	405+00.5	RT					1		
0010	405+20.5 -	405+73.5	RT					1		
0010	405+73.5 -	414+48.5	RT	875						
0010	414+48.5 -	415+01.5	RT					1		
0010	415+32.5 -	415+85.5	RT					1		
0010	415+85.5 -	418+48	RT	263						
0010	418+48 -	419+00	RT			21			B-32-288	
0010	417+97 -	418+50	LT					1	B-32-288	
0010	418+50 -	418+75	LT	25					B-32-288	
0010	418+75 -	419+00	LT			21			B-32-288	
0010	421+43 -	421+64	LT			21			B-32-288	
0010	421+64 -	423+64	LT	200						
0010	423+64 -	424+17	LT					1		
0010	424+37 -	424+90	LT					1		
0010	424+90 -	428+76.5	LT	388						
0010	428+76.5 -	429+29.5	LT					1		
0010	421+43 -	421+64	RT			21			B-32-288	
0010	421+64 -	424+89	RT	325					B-32-288	
0010	424+89 -	425+42	RT					1	B-32-288	
0010	424+89 -	425+42	RT					16		
SUBTOTAL				3,915	0	168				
GRAND TOTAL 0010				7,881	5,913	210			58	

\* Posts are to remain in place on structure. Only Steel Thrie Beam itself is to be replaced.

TRAFFIC CONTROL WARNING LIGHTS TYPE C

CATEGORY	STATION	STATION	LOCATION	NO. LIGHTS	NO. DAY	REMARKS
0010	391+10 - 391+50		RT	5	25	TRAFFIC CONTROL: PEDESTRIAN ACCOMMODATION 1
0010	391' X' +09 - 391' X' +50		RT	5	25	TRAFFIC CONTROL: PEDESTRIAN ACCOMMODATION 2
0010	PEARL ST PARKING LANE		LT	5	25	TRAFFIC CONTROL: PEDESTRIAN ACCOMMODATION 3
0010	392+10 - 392+31		RT	5	25	TRAFFIC CONTROL: PEDESTRIAN ACCOMMODATION 4
0010	392+69 - 393+09		LT	5	25	TRAFFIC CONTROL: PEDESTRIAN ACCOMMODATION 3
0010	392+69 - 393+09		LT	5	25	TRAFFIC CONTROL: PEDESTRIAN ACCOMMODATION 4
0010	393+15 - 393+55		RT	5	25	TRAFFIC CONTROL: PEDESTRIAN ACCOMMODATION 5&6
0010	394+98 - 395+38		RT	5	25	TRAFFIC CONTROL: PEDESTRIAN ACCOMMODATION 7
0010	395+20 - 395+60		RT	5	25	TRAFFIC CONTROL: PEDESTRIAN ACCOMMODATION 8
0010	BADGER ST PARKING LANE		RT	5	25	TRAFFIC CONTROL: PEDESTRIAN ACCOMMODATION 8
0010	397+00 - 397+40		RT	5	25	TRAFFIC CONTROL: PEDESTRIAN ACCOMMODATION 9

TOTAL 0010 275  
 646.0106 PAVEMENT MARKING EPOXY 4-INCH

CATEGORY	STATION TO	STATION	C/L DASHED YELLOW LF	C/L DASHED YELLOW LT	C/L DASHED YELLOW RT	C/L SOLID NO PASSING YELLOW LF	C/L SOLID NO PASSING YELLOW LT	C/L SOLID NO PASSING YELLOW RT	EDGE LINE SOLID WHITE LT	EDGE LINE SOLID WHITE LF	EDGE LINE SOLID WHITE RT	REMARKS
0010	12+28 - 47+00					3,472		3,472	37,672		37,672	
0010	12+28 - 389+00				88							
0010	47+00 - 50+80											
0010	50+80 - 54+00		75									
0010	54+00 - 60+70			163								
0010	60+70 - 182+10				750							
0010	182+10 - 212+50											
0010	212+50 - 216+00		88									
0010	216+00 - 231+00											
0010	231+00 - 244+00			325								
0010	244+00 - 326+00											
0010	326+00 - 331+00											
0010	331+00 - 333+43											
0010	333+43 - 359+80											
0010	359+80 - 364+50											
0010	364+50 - 373+70			175								
0010	373+70 - 381+00											
0010	381+00 - 391+90											
0010	392+50 - 397+50				125							
0010	397+50 - 425+70		700									
0010	399+50 - 467+50											
0010	400+75 - 467+50											
0010	425+70 - 432+90			175								
0010	432+90 - 440+50		538		188							
0010	440+50 - 462+00											
0010	462+00 - 467+50			138								
	SUBTOTAL		1,401	976	1,756	35,432	33,672	44,347	44,347	44,347	44,347	
	GRAND TOTAL 0010											162,056

APPROACH TO IH 90 MEDIAN  
 MEDIAN  
 IH 90 AREA

Addendum No. 01  
 ID 5820-01-62  
 Revised Sheet 56  
 October 28, 2015

TEMPORARY PAVEMENT MARKING STOP LINE REMOVABLE TAPE 18-INCH

CATEGORY	STATION TO	STATION	LOCATION	REMARKS
0010	392+47 -	392+61	STH 162	SEE TRAFFIC CONTROL, PEDESTRIAN ACCOMMODATI ON 3 & 4
0010	392+00	392+100	PEARL ST	SEE TRAFFIC CONTROL, PEDESTRIAN ACCOMMODATI ON 3 & 4
TOTAL 0010				80

649,1200  
LF

80

3

3

TEMPORARY PAVEMENT MARKING 4-INCH

CATEGORY	STATION TO	STATION	LOCATION	REMARKS
0010	12+28 ##	466+00 ##	ML	CONSTRUCTION STAKING RESURFACING REFERENCE
TOTAL 0010				46,800

650,8000  
LF

46,800

46,800

TEMPORARY PAVEMENT MARKING STOP LINE REMOVABLE TAPE 18-INCH

CATEGORY	STATION TO	STATION	C/L	C/L	C/L	C/L	C/L	C/L	REMARKS
0010	12+28 -	47+00	C/L	SOLID	NO	PASSING	YELLOW	RT.	10,416
0010	47+00 -	50+80	93	1,140					670
0010	50+80 -	54+00	162	36,420	9,120				3,900
0010	54+00 -	60+70	732	4,500					24,600
0010	60+70 -	182+10	360	3,000	729				3,000
0010	182+10 -	212+50	84	1,410					729
0010	212+50 -	216+00	312	2,760	2,190				2,760
0010	216+00 -	231+00		2,190	3,270				2,190
0010	231+00 -	244+00		3,270	1,500				3,270
0010	244+00 -	326+00		3,000					3,000
0010	326+00 -	331+00		729					729
0010	331+00 -	333+43		1,410					1,410
0010	333+43 -	364+50		222					2,760
0010	364+50 -	373+70		177					2,190
0010	373+70 -	381+00		120					3,270
0010	381+00 -	391+90		174					2,160
0010	391+90 -	397+50		183					2,160
0010	397+50 -	425+70		132					1,650
0010	425+70 -	432+90		957					1,650
0010	432+90 -	440+50		1710					91,765
0010	440+50 -	462+00		98,385					91,765
0010	462+00 -	467+50							91,765
SUBTOTALS				1371	957	1710	98,385		
GRAND TOTAL 0010				194,188					

Addendum No. 01  
ID 5820-01-62  
Revised Sheet 60  
October 28, 2015

## SCHEDULE OF ITEMS

REVISED:

CONTRACT:  
20151110007PROJECT(S):  
5820-01-62FEDERAL ID(S):  
N/A

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	614.0345 Steel Plate Beam Guard Short Radius	25.000 LF	.		.	
0340	614.0370 Steel Plate Beam Guard Energy Absorbing Terminal	3.000 EACH	.		.	
0350	614.0390 Steel Plate Beam Guard Short Radius Terminal	1.000 EACH	.		.	
0360	614.0920 Salvaged Rail	232.000 LF	.		.	
0370	614.0925 Salvaged Guardrail End Treatments	4.000 EACH	.		.	
0380	614.2300 MGS Guardrail 3	7,881.000 LF	.		.	
0390	614.2330 MGS Guardrail 3 K	5,913.000 LF	.		.	
0400	614.2500 MGS Thrie Beam Transition	210.000 LF	.		.	
0410	614.2610 MGS Guardrail Terminal EAT	58.000 EACH	.		.	
0420	618.0100 Maintenance And Repair of Haul Roads (project) 01. 5820-01-62	1.000 EACH	.		.	
0430	619.1000 Mobilization	1.000 EACH	.		.	



## SCHEDULE OF ITEMS

REVISED:

CONTRACT:  
20151110007PROJECT(S):  
5820-01-62FEDERAL ID(S):  
N/A

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0550	642.5201 Field Office Type C	1.000 EACH	.		.	
0560	643.0100 Traffic Control (project) 01. 5820-01-62	1.000 EACH	.		.	
0570	643.0300 Traffic Control Drums	3,049.000 DAY	.		.	
0580	643.0410 Traffic Control Barricades Type II	135.000 DAY	.		.	
0590	643.0420 Traffic Control Barricades Type III	135.000 DAY	.		.	
0600	643.0705 Traffic Control Warning Lights Type A	225.000 DAY	.		.	
0610	643.0715 Traffic Control Warning Lights Type C	275.000 DAY	.		.	
0620	643.0900 Traffic Control Signs	4,556.000 DAY	.		.	
0630	646.0106 Pavement Marking Epoxy 4-Inch	162,056.000 LF	.		.	
0640	646.0126 Pavement Marking Epoxy 8-Inch	450.000 LF	.		.	
0660	647.0110 Pavement Marking Railroad Crossings Epoxy	2.000 EACH	.		.	

## SCHEDULE OF ITEMS

REVISED:

CONTRACT:  
20151110007PROJECT(S):  
5820-01-62FEDERAL ID(S):  
N/A

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0670	647.0156 Pavement Marking Arrows Epoxy Type 1	6.000 EACH	.		.	
0680	647.0166 Pavement Marking Arrows Epoxy Type 2	3.000 EACH	.		.	
0690	647.0456 Pavement Marking Curb Epoxy	402.000 LF	.		.	
0700	647.0566 Pavement Marking Stop Line Epoxy 18-Inch	122.000 LF	.		.	
0710	647.0726 Pavement Marking Diagonal Epoxy 12-Inch	30.000 LF	.		.	
0720	647.0776 Pavement Marking Crosswalk Epoxy 12-Inch	163.000 LF	.		.	
0730	648.0100 Locating No-Passing Zones	9.000 MI	.		.	
0740	649.0100 Temporary Pavement Marking 4-Inch	194,188.000 LF	.		.	
0750	649.1200 Temporary Pavement Marking Stop Line Removable Tape 18-Inch	80.000 LF	.		.	
0760	650.8000 Construction Staking Resurfacing Reference	46,800.000 LF	.		.	

## SCHEDULE OF ITEMS

REVISED:

CONTRACT:  
20151110007PROJECT(S):  
5820-01-62FEDERAL ID(S):  
N/A

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0770	650.9910 Construction Staking Supplemental Control (project) 01. 5820-01-62	LUMP	LUMP			.
0780	690.0150 Sawing Asphalt	1,170.000 LF	.			.
0790	690.0250 Sawing Concrete	103.000 LF	.			.
0800	SPV.0060 Special 01. Adjusting Water Valve Box	3.000 EACH	.			.
0810	SPV.0060 Special 02. Temporary Curb Ramp	7.000 EACH	.			.
0830	SPV.0090 Special 02. Temporary Pedestrian Safety Barrier	422.000 LF	.			.
0840	SPV.0090 Special 03. Removing HMA Pavement Notched Wedge Longitudinal Joint	45,047.000 LF	.			.
0850	SPV.0180 Special 01. Temporary Pedestrian Surface	4.000 SY	.			.
	SECTION 0001 TOTAL					.
	TOTAL BID					.