

Wisconsin Department of Transportation

November 5, 2015

Division of Transportation Systems Development

Bureau of Project Development 4802 Sheboygan Avenue, Rm 601 P O Box 7916 Madison, WI 53707-7916

Telephone: (608) 266-1631 Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #17: 3755-00-71, WISC 2015 577

CTH D (Washington Avenue)
Bridge over Fox River (B-51-0149)

CTH D

Racine County

Letting of November 10, 2015

This is Addendum No. 01, which provides for the following:

Special Provisions

Revised Special Provisions				
Article No.	Description			
3	Prosecution and Progress.			

Added Special Provisions					
Article No.		Description			
26	Temporary Causeways.				

Plan Sheets

Added Plan Sheets				
Plan	Plan Sheet Title (brief description of changes to sheet)			
Sheet	Flair Sileet Title (bilet description of changes to sileet)			
87A				
to	Standard Sign Plates			
87G				

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist Proposal Management Section

ADDENDUM NO. 01 3755-00-71

November 5, 2015

Special Provisions

3. Prosecution and Progress.

Replace entire article language with the following:

Begin work within ten calendar days after the engineer issues a written notice to do so.

Provide the start date to the engineer in writing within a month after executing the contract but at least 14 calendar days before the preconstruction conference. Upon approval, the engineer will issue the notice to proceed within ten calendar days before the approved start date.

To revise the start date, submit a written request to the engineer at least two weeks before the intended start date. The engineer will approve or deny that request based on the conditions cited in the request and its effect on the department's scheduled resources.

Fish Spawning

There shall be no instream disturbance of Fox River as a result of construction activity under or for this contract, from March 1 to May 15 both dates inclusive, in order to avoid adverse impacts upon the spawning of Walleye and River Redhorse.

Instream construction activity may be permitted between March 1 and May 15 with prior installation of Best Management Practices (BMPs) to enclose all instream construction operations. This may be achieved through the use of the special turbidity barrier as shown in the plans. Contractor may require extraordinary forces and equipment for installation prior to March 1. Installation of special turbidity barrier may require minor rock adjustments to achieve a proper seal to the bottom of the streambed.

Any change to this limitation will require submitting a written request by the contractor to the engineer, subsequent review and concurrence by the Department of Natural Resources in the request, and final approval by the engineer. The approval will include all conditions to the request as mutually agreed upon by WisDOT and DNR.

Migratory Birds

Swallow and other migratory birds' nests have been observed on or under the existing bridge. All active nests (when eggs or young are present) of migratory birds are protected under the federal Migratory Bird Treaty Act.

The nesting season for swallows and other birds is usually between May 1 and August 30. Either prevent active nests from becoming established, or apply for a depredation permit from the US Fish and Wildlife Service for work that may disturb or destroy active nests. The need for a permit may be avoided by removing the existing bridge structure prior to nest occupation by birds, or clearing nests from all structures before the nests become active in early spring. As a last resort, prevent birds from nesting by installing a suitable netting device on the remaining structure prior to nesting activity. Include the cost for preventing nesting in the cost of Removing Old Structure Over Waterway with Minimal Debris.

In-Stream Construction Options

The Rochester Dam currently has its gates fully open resulting in very low upstream water levels at the CTH D Bridge in Rochester. These levels are expected to remain until through the winter time

until February 15, 2016. The timing of the low water levels would likely be shortly after contract signing and would provide approximately a 6 week window for contractors to mobilize and complete in-stream activities viewed necessary for the demolition of the existing structure and the construction of the proposed pier. Causeway construction will be allowed. Other options or alternatives may exist.

A causeway to the new center pier must be made out of non-erodible material and submitted for approval with the ECIP. Furthermore, the contractor is expected to coordinate with the Racine County Board of Drainage Commissioners – Norway Dover to verify the approximately 6 week construction window and to see when the impoundment will start to be filled. The current WDNR permitting allows the drawdown until February 15, 2016. The Rochester drawdown permit can be provided upon request.

28. Temporary Causeways.

A Description

This special provision describes furnishing, placing and removing a temporary causeway into the Fox River as shown on the plans and as hereinafter provided. The purpose of the temporary causeway is to provide construction access between shoreline haul roads and the areas of the Fox River necessary to demolish the existing structure and construct the proposed pier. This special provision also includes restoring the sites after the temporary causeways are no longer needed.

B Materials

Obtain approval of the engineer for all materials and conform to the pertinent requirements of the standard specifications.

Provide timber mats or riprap material. The rip rap must be clean and relatively free of fine material, meeting the requirements of heavy riprap in standard spec 606.2, modified as follows: 100 percent of material utilized for the causeway construction shall pass a 6-inch sieve. Salvaged or recycled materials will not be permitted unless approved by the Department and WisDNR.

If using rip rap, provide a layer of geotextile fabric type HR under the riprap material. Place a layer of smaller rock over the heavy riprap for a driving surface. Screen the smaller rock to remove all fine materials.

C Construction

Operations and storage of equipment and materials shall occur only in permitted areas covered by the Section 404 permit. (If a causeway is utilized, the current Section 404 permit must be revised to include that operation.)

Submit a plan showing proposed dimensions, materials, construction method and timetable for construction and removal of the temporary causeways as part of the erosion control implementation plan (ECIP).

The causeway must be removed by February 16, 2016, 12:00AM.

Though not expected to be necessary, if dredging is desired to facilitate means and methods of construction, obtain all necessary regulatory agency approvals. Construction activities shall allow sufficient clearances for the navigation of boat traffic along the Fox River. Remove the temporary causeways as soon as practical after they are no longer needed for construction and as directed by the engineer. When removing the causeways, restore the Fox River as closely as possible to its natural state. Measure and record river bottom elevations before and after placement of causeway material. Remove causeway materials from the Fox River such that the river bottom elevation is the same as before the causeway was constructed. The cost of the pre-construction and post-

construction stream bed survey shall be included in the cost of **Construction Staking Supplemental Control (project) 01. 3755-00-71**.

D Measurement

The department will not measure Temporary Causeways.

E Payment


The department will not pay for measured quantities. The temporary causeway work, if utilized, will be considered incidental to Removing Old Structure Over Waterway with Minimal Debris (station) 01. 202+38.11.


Payment is full compensation for any additional agency coordination and/or permitting; for furnishing all materials; for construction and maintaining the temporary causeways; for removal of all causeway materials from the Fox River; and for installation and removal of erosion control.


Plan Sheets


The following $8\frac{1}{2}$ x 11-inch sheets are attached and made part of the plans for this proposal: Added: 87A - 87G.


END OF ADDENDUM











WISCONSIN DEPT OF TRANSPORTATI	the R Raw	PLATE NO. M6-4
DE	£ 200	4
WISCONSIN	APPROVED 7	DATE 7/03/14

3.06 6.25 6.25

SHEET NO: 87E

21

SIZE

НWY: СТН D PROJECT NO: 3755-00-71

COUNTY: RACINE

SIGN PLATES

1/2

%

1 1/8

3 34

7 1/2 4 1/4 3 3/4 7 1/2 4 1/4 3 3/4 7 1/2 4 1/4 3 3/4

7 ½ 8 ¾ 4 ¼ 10 ¾ 12 ½ 6 ¾ 10 ¾ 12 ½ 6 ¾ 10 ¾ 12 ½ 6 ¾

% % % %

1 3%

> 30 30 30

0 m 4

1/2 /2

WISDOT / CADDS SHEET 42

