



# Wisconsin Department of Transportation

December 3, 2015

## Division of Transportation Systems Development

Bureau of Project Development  
4802 Sheboygan Avenue, Rm 601  
P O Box 7916  
Madison, WI 53707-7916

Telephone: (608) 266-1631  
Facsimile (FAX): (608) 266-8459

### NOTICE TO ALL CONTRACTORS:

**Proposal #28: 8520-01-74, WISC 2015 658  
Hayward – Clam Lake  
CTH K / Mosquito Brook Road  
Intersection  
STH 77  
Sawyer County**

### Letting of December 8, 2015

This is Addendum No. 02, which provides for the following:

#### Schedule of Items

Deleted Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
208.0100	Borrow	CY	380	0	0

#### Schedule of Items

Attached, dated December 3, 2015, are the revised Schedule of Items Pages 1 – 6.

#### Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:  
Revised: 16, 63.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

*Mike Coleman*

Proposal Development Specialist  
Proposal Management Section

END OF ADDENDUM



Addendum No. 02  
 ID 8520-01-74  
 Revised Sheet 63  
 December 3, 2015

EARTHWORK DATA - CTH K														
STATION	AREA				VOLUME									
	(1)				(2)		(3)							
	UNCLASS.	EBS	MARSH	FILL	UNCLASS. CUT	EBS CUT	EXPANDED EBS FILL	MARSH CUT	EXPANDED MARSH FILL	EXPANDED FILL	USEABLE UNCLASSIFIED MATERIAL			
	SF	SF	SF	SF	CY	CY	CY	CY	CY	CY	CY	CY	CY	CY
10+59	60.47	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
11+00	53.62	0.00	0.00	0.23	86.62	0.00	0.00	0.00	0.00	0.22	0.00	0.00	86.62	0.00
11+50	35.53	0.00	0.00	14.10	82.55	0.00	0.00	0.00	0.00	16.59	0.00	0.00	51.48	0.00
12+00	28.13	0.00	0.00	48.24	58.94	0.00	0.00	0.00	0.00	72.15	0.00	0.00	27.88	0.00
12+50	8.92	3.54	0.00	63.69	34.31	4.10	0.00	0.00	0.00	129.55	0.00	0.00	34.31	0.00
13+00	0.00	2.27	0.00	114.62	8.26	5.38	0.00	0.00	0.00	206.38	0.00	0.00	8.26	0.00
13+50	0.00	0.00	0.00	119.07	0.00	2.10	0.00	0.00	0.00	270.47	0.00	0.00	0.00	0.00
14+00	43.61	0.00	0.00	55.71	40.38	0.00	0.00	0.00	0.00	202.29	0.00	0.00	40.38	0.00
14+50	136.09	0.00	0.00	23.01	166.39	0.00	0.00	0.00	0.00	91.11	0.00	0.00	141.31	0.00
15+00	97.59	0.00	0.00	10.87	216.37	0.00	0.00	0.00	0.00	39.21	0.00	0.00	144.24	0.00
15+50	177.13	0.00	0.00	2.39	254.37	0.00	0.00	0.00	0.00	15.35	0.00	0.00	139.97	0.00
16+00	177.37	0.00	0.00	1.27	328.24	0.00	0.00	0.00	0.00	4.24	0.00	0.00	160.35	0.00
16+50	150.08	0.00	95.17	303.19	0.00	0.00	0.00	88.12	132.18	111.62	0.00	0.00	95.50	0.00
17+00	84.30	0.00	30.70	128.90	217.02	0.00	0.00	116.55	174.82	259.34	0.00	0.00	64.22	0.00
17+34	195.5	0.00	0.00	62.67	176.17	0.00	0.00	19.33	28.99	150.77	0.00	0.00	50.02	0.00
TOTAL					1972.81	10.76	13.45	224.00	335.99	1569.29			1044.55	
					(PHASE 1&2)	(PHASE 2)	(PHASE 2)	(PHASE 1)	(PHASE 1)	(PHASE 1&2)			(PHASE 1)	

FILL QUANTITIES ARE EXPANDED, NATIVE & EBS FILL EXPANSION FACTOR = 1.25  
 MARSH EXPANSION FACTOR = 1.50, MARSH TO BE FILLED WITH SELECT BORROW  
 (1) EBS IS FOR PREPARING ROADWAY FOUNDATION (REMOVING PAVEMENT WITHIN 2' OF FG THAT ISN'T REMOVED UNDER UNCLASSIFIED)  
 (2) EXPANDED MARSH FILL IS AMOUNT OF SELECT GRANULAR REQUIRED TO FILL THE VOID LEFT IN THE MARSH AFTER EXCAVATION  
 (3) USEABLE UNCLASSIFIED MATERIAL REPRESENTS UNCLASSIFIED MATERIAL AVAILABLE FOR USE IN CONSTRUCTION OF THE ROADBED.

EARTHWORK DATA - MOSQUITO BROOK ROAD														
STATION	AREA				VOLUME									
	(1)				(2)		(3)							
	UNCLASS.	EBS	MARSH	FILL	UNCLASS.	EBS CUT	EBS FILL	MARSH CUT	MARSH FILL	EXPANDED FILL	USEABLE UNCLASSIFIED MATERIAL			
	SF	SF	SF	SF	CY	CY	CY	CY	CY	CY	CY	CY	CY	CY
10+35	46.37	1.02	0.00	68.53	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
10+50	15.52	5.89	0.00	46.74	17.19	1.92	2.40	0.00	0.00	40.02	0.00	0.00	17.19	0.00
11+00	86.82	3.76	0.00	1.08	94.76	8.94	11.17	0.00	0.00	55.35	0.00	0.00	94.76	0.00
11+50	85.43	0.00	0.00	10.59	159.49	3.48	4.35	0.00	0.00	13.51	0.00	0.00	159.49	0.00
12+00	47.15	0.00	0.00	1.03	122.76	0.00	0.00	0.00	0.00	13.45	0.00	0.00	122.76	0.00
12+28	53.15	0.00	0.00	0.00	52.01	0.00	0.00	0.00	0.00	0.67	0.00	0.00	52.01	0.00
TOTAL					446.21	14.34	17.92	0.00	0.00	123.00			446.21	
					(PHASE 2)	(PHASE 2)	(PHASE 2)	(PHASE 2)	(PHASE 2)	(PHASE 2)			(PHASE 2)	

FILL QUANTITIES ARE EXPANDED, NATIVE & EBS FILL EXPANSION FACTOR = 1.25  
 MARSH EXPANSION FACTOR = 1.50, MARSH TO BE FILLED WITH SELECT BORROW  
 (1) EBS IS FOR PREPARING ROADWAY FOUNDATION (REMOVING PAVEMENT WITHIN 2' OF FG THAT ISN'T REMOVED UNDER UNCLASSIFIED)  
 (2) USEABLE UNCLASSIFIED MATERIAL REPRESENTS UNCLASSIFIED MATERIAL AVAILABLE FOR USE IN CONSTRUCTION OF THE ROADBED.

SCHEDULE OF ITEMS

REVISED:

CONTRACT:  
20151208028

PROJECT(S):  
8520-01-74

FEDERAL ID(S):  
WISC 2015658

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS

SECTION 0001 Category Number 0010

0010	201.0105 Clearing	7.000 STA	.	.	.	.
0020	201.0205 Grubbing	7.000 STA	.	.	.	.
0030	203.0100 Removing Small Pipe Culverts	2.000 EACH	.	.	.	.
0040	204.0110 Removing Asphaltic Surface	270.000 SY	.	.	.	.
0050	204.0150 Removing Curb & Gutter	178.000 LF	.	.	.	.
0060	205.0100 Excavation Common	2,444.000 CY	.	.	.	.
0070	205.0400 Excavation Marsh	224.000 CY	.	.	.	.
0090	208.1100 Select Borrow	336.000 CY	.	.	.	.
0100	213.0100 Finishing Roadway (project) 01. 8520-01-74	1.000 EACH	.	.	.	.
0110	305.0110 Base Aggregate Dense 3/4-Inch	275.000 TON	.	.	.	.

## SCHEDULE OF ITEMS

REVISED:

CONTRACT:  
20151208028PROJECT(S):  
8520-01-74FEDERAL ID(S):  
WISC 2015658

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0120	305.0120 Base Aggregate Dense 1 1/4-Inch	2,398.000 TON	.	.	.	.
0130	455.0605 Tack Coat	172.000 GAL	.	.	.	.
0140	465.0120 Asphaltic Surface Driveways and Field Entrances	30.000 TON	.	.	.	.
0150	521.0118 Culvert Pipe Corrugated Steel 18-Inch	121.000 LF	.	.	.	.
0160	521.1018 Apron Endwalls for Culvert Pipe Steel 18-Inch	6.000 EACH	.	.	.	.
0170	522.0324 Culvert Pipe Reinforced Concrete Class IV 24-Inch	74.000 LF	.	.	.	.
0180	522.1024 Apron Endwalls for Culvert Pipe Reinforced Concrete 24-Inch	2.000 EACH	.	.	.	.
0190	601.0557 Concrete Curb & Gutter 6-Inch Sloped 36-Inch Type D	327.000 LF	.	.	.	.
0200	618.0100 Maintenance And Repair of Haul Roads (project) 01. 8520-01-74	1.000 EACH	.	.	.	.
0210	619.1000 Mobilization	1.000 EACH	.	.	.	.
0220	624.0100 Water	29.000 MGAL	.	.	.	.

## SCHEDULE OF ITEMS

REVISED:

CONTRACT:  
20151208028PROJECT(S):  
8520-01-74FEDERAL ID(S):  
WISC 2015658

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0230	625.0500 Salvaged Topsoil	5,875.000 SY	.	.	.	.
0240	627.0200 Mulching	5,875.000 SY	.	.	.	.
0250	628.1104 Erosion Bales	79.000 EACH	.	.	.	.
0260	628.1504 Silt Fence	711.000 LF	.	.	.	.
0270	628.1520 Silt Fence Maintenance	711.000 LF	.	.	.	.
0280	628.1905 Mobilizations Erosion Control	2.000 EACH	.	.	.	.
0290	628.1910 Mobilizations Emergency Erosion Control	1.000 EACH	.	.	.	.
0300	628.2027 Erosion Mat Class II Type C	648.000 SY	.	.	.	.
0310	628.7504 Temporary Ditch Checks	36.000 LF	.	.	.	.
0320	628.7555 Culvert Pipe Checks	4.000 EACH	.	.	.	.
0330	629.0210 Fertilizer Type B	4.000 CWT	.	.	.	.

## SCHEDULE OF ITEMS

REVISED:

CONTRACT:  
20151208028PROJECT(S):  
8520-01-74FEDERAL ID(S):  
WISC 2015658

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0340	629.1100 Agricultural Limestone Treatment	1.000 TON	.		.	
0350	630.0120 Seeding Mixture No. 20	159.000 LB	.		.	
0360	633.5200 Markers Culvert End	2.000 EACH	.		.	
0370	634.0616 Posts Wood 4x6-Inch X 16-FT	14.000 EACH	.		.	
0380	637.2210 Signs Type II Reflective H	57.000 SF	.		.	
0390	637.2230 Signs Type II Reflective F	21.000 SF	.		.	
0400	638.2102 Moving Signs Type II	3.000 EACH	.		.	
0410	638.2602 Removing Signs Type II	9.000 EACH	.		.	
0420	638.3000 Removing Small Sign Supports	11.000 EACH	.		.	
0430	642.5001 Field Office Type B	1.000 EACH	.		.	
0440	643.0100 Traffic Control (project) 01. 8520-01-74	1.000 EACH	.		.	

## SCHEDULE OF ITEMS

REVISED:

CONTRACT:  
20151208028PROJECT(S):  
8520-01-74FEDERAL ID(S):  
WISC 2015658

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0450	643.0300 Traffic Control Drums	3,094.000 DAY	.	.	.	.
0460	643.0715 Traffic Control Warning Lights Type C	625.000 DAY	.	.	.	.
0470	643.0900 Traffic Control Signs	892.000 DAY	.	.	.	.
0480	646.0106 Pavement Marking Epoxy 4-Inch	3,368.000 LF	.	.	.	.
0490	647.0566 Pavement Marking Stop Line Epoxy 18-Inch	24.000 LF	.	.	.	.
0500	648.0100 Locating No-Passing Zones	1.000 MI	.	.	.	.
0510	650.4500 Construction Staking Subgrade	711.000 LF	.	.	.	.
0520	650.5000 Construction Staking Base	711.000 LF	.	.	.	.
0530	650.5500 Construction Staking Curb Gutter and Curb & Gutter	327.000 LF	.	.	.	.
0540	650.6000 Construction Staking Pipe Culverts	4.000 EACH	.	.	.	.



SCHEDULE OF ITEMS

REVISED:

CONTRACT:  
20151208028

PROJECT(S):  
8520-01-74

FEDERAL ID(S):  
WISC 2015658

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0550	650.9910 Construction Staking Supplemental Control (project) 01. 8520-01-74	LUMP	LUMP			.
0560	690.0150 Sawing Asphalt	LF	675.000	.		.
0570	SPV.0035 Special 01. ABANDONING CULVERT PIPE SPECIAL	CY	7.000	.		.
0580	SPV.0090 Special 01. CONCRETE CURB AND GUTTER CURE AND SEAL TREATMENT	LF	327.000	.		.
0590	SPV.0195 Special 01. ASPHALTIC SURFACE SPECIAL	TON	1,124.000	.		.
0600	306.0110 Salvaged Asphaltic Pavement Base	TON	21.000	.		.
	SECTION 0001 TOTAL					.
	TOTAL BID					.