



Wisconsin Department of Transportation

April 27, 2017

Division of Transportation Systems Development

Bureau of Project Development
 4802 Sheboygan Avenue, Rm 601
 P O Box 7916
 Madison, WI 53707-7916

Telephone: (608) 266-1631
 Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

**Proposal #18: 4150-17-71, WISC 2017 274
 Baileys Harbor – Sister Bay
 CTH Q – STH 42
 STH 57
 Door County**

Letting of May 9, 2017

This is Addendum No. 01, which provides for the following:

Special Provisions:

Revised Special Provisions	
Article No.	Description
3	Prosecution and Progress
6	Holiday Work Restrictions

Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
204.0115	Removing Asphaltic Surface Butt Joints	SY	440	30	470
204.0120	Removing Asphaltic Surface Milling	SY	149,630	880	150,510
465.0105	Asphaltic Surface	Ton	110	135	245
643.0900	Traffic Control Signs	Day	2,482	1,216	3,698

Deleted Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
450.4000	HMA Cold Weather Paving	Ton	5,750	-5,750	0

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
44	Removing Asphaltic Surface Butt Joints miscellaneous quantity table updated
45	Removing Asphaltic Surface Milling miscellaneous quantity table updated
49	Asphalt Surface Summary miscellaneous quantity table updated with revised quantity for Asphaltic Surface
59	Traffic Control Summary miscellaneous quantity table updated with revised quantity for Traffic Control Signs

Other

Revise the contract time for completion from a completion date of October 31, 2017 to a completion date of June 20, 2018.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01

4150-17-71

April 27, 2017

Special Provisions

3. Prosecution and Progress

Replace entire article language with the following:

Begin work within ten calendar days after the engineer issues a written notice to do so.

Provide the start date to the engineer in writing within a month after executing the contract but at least 14 calendar days before the preconstruction conference. Upon approval, the engineer will issue the notice to proceed within ten calendar days before the approved start date.

To revise the start date, submit a written request to the engineer at least two weeks before the intended start date. The engineer will approve or deny that request based on the conditions cited in the request and its effect on the department's scheduled resources.

The contract time for completion is based on an expedited work schedule and may require extraordinary forces and equipment.

Work shall not begin until September 5, 2017.

Complete construction operations on STH 57 to the stage necessary to reopen it to through traffic prior to 12:01 AM October 12, 2017. Do not reopen until completing the following work: B-15-0026, culvert replacements, storm sewer installations, curb and gutter installations, and placement of asphaltic surface at storm sewer/culvert installation trenches.

If the contractor fails to complete the work necessary to reopen STH 57 to through traffic prior to 12:01 AM October 12, 2017, the department will assess the contractor \$7,200 in interim liquidated damages for each calendar day that the roadway remains closed after 12:01 AM, October 12, 2017. An entire calendar day will be charged for any period of time within a calendar day that the road remains closed beyond 12:01 AM.

If contract time expires prior to completing all work specified in the contract, additional liquidated damages will be affixed according to standard spec 108.11.

Complete the following construction operations during Detour 1:

- Removal of Structure C-15-0037 and associated items, and construction of Structure B-15-0026.
- Construction of the guardrail attached to Structure B-15-0026.
- Remove/abandon and replacement of the culvert pipes within the detoured section of STH 57.
- Storm sewer construction within the detoured section of STH 57.
- Grading within the detoured section of STH 57.
- Curb and gutter within the detoured section of STH 57.
- Construction of asphaltic surface and wedge adjacent to Structure B-15-0026 to match into existing pavement

Complete the following construction operations during Detour 2:

- Remove and replace the culvert pipes within the detoured section of STH 57.
- Grading within the detoured section of STH 57.

- Curb and gutter within the detoured section of STH 57.

The duration of Detour 2 shall be a maximum of five calendar days.

Winter Shutdown will commence at 12:01 AM November 1, 2017. Prior to Winter Shutdown, complete all contract work except milling, HMA pavement paving, aggregate shouldering, and pavement marking. Do not resume work until May 1, 2018 unless approved by the engineer. Provide a start date in writing at least 14 days prior to the planned start of construction in 2018. Upon approval the engineer will issue the notice to proceed within 10 days of the approved start date.

Complete all contract work prior to 12:01 AM June 21, 2018.

Fish Spawning

There shall be no instream disturbance of the unnamed tributary to Mud Lake as a result of construction activity under or for this contract, from March 1 to June 15 both dates inclusive, in order to avoid adverse impacts upon the spawning of fish.

Any change to this limitation will require submitting a written request by the contractor to the engineer, subsequent review and concurrence by the Department of Natural Resources in the request, and final approval by the engineer. The approval will include all conditions to the request as mutually agreed upon by WisDOT and DNR.

Northern Long-eared Bat (*Myotis septentrionalis*)

Northern Long-eared Bats (NLEB) have the potential to inhabit the project limits because they roost in trees. Roosts may not have been observed on this project, but conditions to support the species exist. The species and all active roosts are protected by the Federal Endangered Species Act. If an individual bat or active roost is encountered during construction operations, stop work and notify the engineer and the WisDOT Regional Environmental Coordinator (REC).

According to the final 4(d) rule issued for the NLEB, the department has determined that the proposed activity may affect, but will not result in prohibited take of the NLEB. The activity involves tree removal, but will not occur within 0.25 miles of a known hibernacula, nor will the activity remove a known maternity roost tree or any other tree within 150 feet of a known maternity roost tree.

If additional trees need to be removed, no Clearing shall occur without prior approval from the engineer, following coordination with the WisDOT REC. Additional tree removal beyond the area originally specified will require consultation with the United States Fish and Wildlife Service (USFWS) and may require a bat presence/absence survey. Notify the engineer if additional Clearing cannot be avoided to begin coordination with the WisDOT REC. The WisDOT REC will initiate consultation with the USFWS and determine if a survey is necessary.

Submit a schedule and description of Clearing operations with the ECIP 14 days prior to any Clearing operations. The department will determine, based on schedule and scope of work, what additional erosion control measures shall be implemented prior to the start of Clearing operations, and list those additional measures in the ECIP.

6. Holiday Work Restrictions.

Add the following to the end of the list of time periods for work restrictions:

- From noon Friday, May 25, 2018 to 6:00 AM Tuesday, May 29, 2018 for Memorial Day.

Schedule of Items

Attached, dated April 27, 2017, are the revised Schedule of Items Pages 1 – 9.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:
Revised: 44, 45, 49 and 59.

END OF ADDENDUM

Addendum No. 01
ID 4150-17-71
Revised Sheet 44
April 27, 2017

CLEARING AND GRUBBING

201. 0105 201. 0120 201. 0205 201. 0220

CATEGORY	STATION TO	STATION	LOCATION	STA	STA	STA	ID	STA	ID
0010	1520+66		LT		8				8
0010	1521+01		LT		10				10
0010	1560+00	-	1562+00	LT	2				2
0010	1563+00	-	1566+00	LT	3				3
0010	1761+00	-	1763+00	LT	2				2
TOTALS					7	18	7	18	18

REMOVING SMALL PIPE CULVERT

203. 0100

CATEGORY	STATION	LOCATION	REMARKS
0010	1435+68	STH 57	18" CMCP - 37 LF
0010	1475+66	STH 57	18" CMCP - 46 LF
0010	1510+37	STH 57	18" CMCP - 46 LF
0010	1519+04	STH 57	24" CMCP - 47 LF
0010	1536+62	STH 57	24" CMCP - 51 LF
0010	1543+13	STH 57	24" CMCP - 53 LF
0010	1603+91	STH 57	15" CMCP - 37 LF
0010	1675+98	STH 57	18" CMCP (WITH 15" LINER) - 67 LF
0010	1712+46	STH 57	24" CMCP - 39 LF
0010	1712+50	STH 57	24" CMCP - 40 LF
0010	1733+85	STH 57	24" CMCP - 42 LF
0010	1750+00	STH 57	24" CMCP - 49 LF
0010	1756+21	STH 57	24" CMCP - 59 LF
0010	1770+74	STH 57	24" CMCP - 46 LF
0010	1811+02	STH 57	24" CMCP - 62 LF
0010	10+59	SUN PLAZA	18" CMCP SOUTH AEW ONLY
TOTAL			16

REMOVING ASPHALTIC SURFACE

204. 0110

CATEGORY	STATION TO	STATION	LOCATION	SY	REMARKS
0010	1451+60	-	1452+65	RT	10 CURB & GUTTER REPLACEMENT
0010	1837+49	-	1838+00	RT	28 PARKING LOT REMOVAL
0010	1756+16	-	1756+37	LT & RT	2 CURB & GUTTER REPLACEMENT
TOTALS				40	

REMOVING ASPHALTIC SURFACE BUTT JOINTS

204. 0115

CATEGORY	STATION	LOCATION	REMARKS
0010	1423+24	STH 57	
0010	11+13	SUN PLAZA ROAD	
0010	8+86	AHRENS ROAD	
0010	1561+17	STH 57	FOR WEDGING TO B-15-26 IN 2017
0010	1563+57	STH 57	FOR WEDGING TO B-15-26 IN 2017
0010	1562+17	STH 57	AT B-15-26 IN 2018
0010	1562+57	STH 57	AT B-15-26 IN 2018
0010	10+39	E. MEADOW ROAD	
0010	9+00	W. MEADOW ROAD	
0010	11+04	GROVE ROAD (EAST)	
0010	8+75	GROVE ROAD (WEST)	
0010	10+84	OLD LIME KILN ROAD (EAST)	
0010	8+57	OLD LIME KILN ROAD (WEST)	
0010	10+53	PIONEER ROAD (EAST)	
0010	9+15	PIONEER ROAD (WEST)	
0010	11+00	GERMAN ROAD (EAST)	
0010	9+17	GERMAN ROAD (WEST)	
0010	11+02	CTH Q (EAST)	
0010	8+77	CTH Q (WEST)	
0010	9+32	SETTLEMENT ROAD	
0010	10+68	OLD STAGE ROAD	
0010	9+30	COUNTRY LANE	
0010	10+75	FLINT RIDGE ROAD	
0010	9+36	NORTHWOODS ROAD	
0010	11+19	ORCHARD ROAD	
0010	9+03	COUNTRY WALK DRIVE	
0010	1843+01	STH 57	
0010	DRIVEWAYS		
TOTAL			470

REMOVING ASPHALTIC SURFACE MILLING

CATEGORY	STATION TO	STATION	LOCATION	SY	REMARKS
0010	1423+24	-	1452+35	9875	
0010	1452+35	-	1518+25	22090	
0010	1518+25	-	1562+56	14620	
0010	1562+56	-	1596+87	11420	
0010	1596+87	-	1623+33	8880	
0010	1623+33	-	1649+99	8890	
0010	1649+99	-	1676+54	8850	
0010	1676+54	-	1703+24	8900	
0010	1703+24	-	1729+17	9050	
0010	1729+17	-	1755+65	9110	
0010	1755+65	-	1782+01	8790	
0010	1782+01	-	1804+16	7385	
0010	1804+16	-	1816+84	4295	
0010	1816+84	-	1833+77	5645	
0010	1833+77	-	1843+01	3520	
0010	11+13	-	STH 57	435	SUN PLAZA ROAD
0010	8+86	-	STH 57	450	AHRENS ROAD
0010	10+39	-	STH 57	80	E. MEADOW ROAD
0010	9+00	-	STH 57	405	W. MEADOW ROAD
0010	11+04	-	STH 57	390	GROVE ROAD (EAST)
0010	8+75	-	STH 57	490	GROVE ROAD (WEST)
0010	10+84	-	STH 57	245	OLD LIME KILN ROAD (EAST)
0010	8+57	-	STH 57	500	OLD LIME KILN ROAD (WEST)
0010	10+53	-	STH 57	140	PIONEER ROAD (EAST)
0010	9+15	-	STH 57	360	PIONEER ROAD (WEST)
0010	11+00	-	STH 57	290	GERMAN ROAD (EAST)
0010	9+17	-	STH 57	280	GERMAN ROAD (WEST)
0010	11+02	-	STH 57	520	CTH Q (EAST)
0010	8+77	-	STH 57	560	CTH Q (WEST)
0010	9+32	-	STH 57	380	SETTLEMENT ROAD
0010	10+68	-	STH 57	290	OLD STAGE ROAD
0010	9+30	-	STH 57	370	COUNTRY LANE
0010	10+75	-	STH 57	230	FLINT RIDGE ROAD
0010	9+36	-	STH 57	260	NORTHWOODS ROAD
0010	11+19	-	STH 57	510	ORCHARD ROAD
0010	9+03	-	STH 57	380	COUNTRY WALK DRIVE
0010	DRI VEWAYS	-		745	
0010	1561+16	-	1563+57	880	MILLING REQUIRED IN 2017 FOR B-15-26 TIE IN
TOTALS				150510	

REMOVING CURB & GUTTER

CATEGORY	STATION TO	STATION	LOCATION	LF	REMARKS
0010			SUN PLAZA ROAD	85	
0010			SETTLEMENT ROAD/OLD STAGE ROAD	25	
TOTALS				110	

REMOVING GUARDRAIL

CATEGORY	STATION TO	STATION	LOCATION	LF	REMARKS
0010	1560+54	-	1563+18	240	RAIL ATTACHED TO STRUCTURE C-15-37
0010	1561+54	-	1564+48	240	INCLUDED IN STRUCTURE REMOVAL
TOTALS				480	

REMOVING UTILITY POLES

CATEGORY	STATION	LOCATION	EACH	REMARKS
0010	1454+30	STH 57 LT	1	ABANDONED UTILITY POLE
TOTAL				1

REMOVING INLETS

CATEGORY	STATION	LOCATION	EACH	REMARKS
0010	1686+03	STH 57 RT	1	
TOTAL				1

REMOVING STORM SEWER 18-INCH

CATEGORY	STATION	LOCATION	LF	REMARKS
0010	1686+03	STH 57	45	204.0245.01
TOTAL				45

ABANDONING CULVERT PIPES

CATEGORY	STATION	LOCATION	EA	REMARKS
0010	1449+58	STH 57	1	30" CMCP
TOTAL				1

PREPARE FOUNDATION FOR ASPHALTIC PAVING

CATEGORY	STATION TO	STATION	LOCATION	LS	REMARKS
0010	1423+23.74	-	1562+15.75	STH 57	211.0100
0010	1562+56.25	-	1843+00.91	STH 57	1
TOTAL				1	

Addendum No. 01
 ID 4150-17-71
 Revised Sheet 49
 April 27, 2017

ASPHALT SURFACE SUMMARY

CATEGORY	LOCATION	465.0105 ASPHALTIC SURFACE TON	465.0110 ASPHALTIC SURFACE PATCHING TON	REMARKS
0010	STH 57	105		CULVERT/STORM REPLACEMENTS
0010	STH 57 STA. 1561+17-STA. 1562+17	32		1. 75" SURFACE LAYER TO B-15-26 OVER EXISTING PAVEMENT FOR STRUCTURE TIE IN
0010	STH 57 STA. 1562+57-STA. 1563+57	32		1. 75" SURFACE LAYER TO B-15-26 OVER EXISTING PAVEMENT FOR STRUCTURE TIE IN
0010	STH 57 STA. 1562+12-STA. 1562+17	2		2. 75" LOWER LAYER FROM EXISTING PAVEMENT TO B-15-26 FOR STRUCTURE TIE IN
0010	STH 57 STA. 1562+57-STA. 1562+62	2		2. 75" LOWER LAYER FROM EXISTING PAVEMENT TO B-15-26 FOR STRUCTURE TIE IN
0010	STH 57 STA. 1560+25-STA. 1564+47	43		4" THICKNESS FOR SHOULDERS BETWEEN EXISTING PAVEMENT AND PROPOSED GUARDRAIL FOR STRUCTURE TIE IN
0010	STH 57 STA. 1759+40-STA. 1762+60	24		4" THICKNESS ADJACENT TO PROPOSED CURB & GUTTER TIE IN UNTIL MAINLINE MILLING AND PAVING OPERATIONS
0010	SUN PLAZA ROAD	4		CURB & GUTTER REPLACEMENT
0010	SETTLEMENT ROAD/OLD STAGE ROAD	1		CURB & GUTTER REPLACEMENT
0010	STH 57		20	UNDISTRI BUTED
TOTALS		245	20	

ASPHALTIC FLUMES

CATEGORY	LOCATION	465.0315 SY	REMARKS
0010	SE QUADRANT STH 57/SUN PLAZA ROAD	4	
0010	NE QUADRANT STH 57/SUN PLAZA ROAD	3	
0010	NW QUADRANT STH 57/GROVE ROAD	3	
0010	SW QUADRANT STH 57/OLD LIME KI LN ROAD	3	
0010	NW QUADRANT STH 57/OLD LIME KI LN ROAD	3	
0010	SW QUADRANT STH 57/CTH 0	3	
0010	STA. 1759+50, STH 57 LT	4	
0010	STA. 1762+50, STH 57 LT	4	
0010	NE QUADRANT STH 57/ORCHARD ROAD	3	
TOTALS		30	

Addendum No. 01
 ID 4150-17-71
 Revised Sheet 59
 April 27, 2017

TRAFFIC CONTROL SUMMARY

CAT	LOCATION	643. 0300		*643. 0420		*643. 0705		643. 0900	
		APPROX. SERVICE DAYS	TRAFFIC CONTROL DRUMS NO IN SERVICE	TRAFFIC CONTROL BARRICADES TYPE III NO IN SERVICE	TRAFFIC CONTROL WARNING LIGHTS TYPE A NO IN SERVICE	TRAFFIC CONTROL SIGNS NO IN SERVICE			
0010	SUN PLAZA FOR CURB & GUTTER REPLACEMENT	10	10	100					
0010	NEAR SETTLEMENT ROAD FOR CURB & GUTTER REPLACEMENT	10	15	150					
0010	STH 57 DETOUR #1	38			26	988	42	1596	16
0010	STH 57 DETOUR #2	5			10	50	20	100	10
0010	STH 57 ADVANCE WARNING	95							10
0010	SIDEROAD ADVANCED WARNING	95							22
0010	UNDI STRIBUTED	10	10	100					2090
TOTALS				350		1,038		1,696	3,698

*ADDITIONAL QUANTITIES SHOWN ELSEWHERE



Proposal Schedule of Items

Proposal ID: 20170509018 Project(s): 4150-17-71

Federal ID(s): WISC 2017274

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0010	201.0105 Clearing	7.000 STA	_____.	_____.
0020	201.0120 Clearing	18.000 ID	_____.	_____.
0030	201.0205 Grubbing	7.000 STA	_____.	_____.
0040	201.0220 Grubbing	18.000 ID	_____.	_____.
0050	203.0100 Removing Small Pipe Culverts	16.000 EACH	_____.	_____.
0060	203.0600.S Removing Old Structure Over Waterway With Minimal Debris (station) 01. STA 1562+36	LS	LUMP SUM	_____.
0070	204.0110 Removing Asphaltic Surface	40.000 SY	_____.	_____.
0080	204.0115 Removing Asphaltic Surface Butt Joints	470.000 SY	_____.	_____.
0090	204.0120 Removing Asphaltic Surface Milling	150,510.000 SY	_____.	_____.
0100	204.0150 Removing Curb & Gutter	110.000 LF	_____.	_____.
0110	204.0165 Removing Guardrail	480.000 LF	_____.	_____.
0120	204.0205 Removing Utility Poles	1.000 EACH	_____.	_____.
0130	204.0220 Removing Inlets	1.000 EACH	_____.	_____.
0140	204.0245 Removing Storm Sewer (size) 01. 18-Inch	45.000 LF	_____.	_____.
0150	204.0270 Abandoning Culvert Pipes	1.000 EACH	_____.	_____.
0160	205.0100 Excavation Common	760.000 CY	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20170509018 Project(s): 4150-17-71

Federal ID(s): WISC 2017274

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0170	206.1000 Excavation for Structures Bridges (structure) 01. Structure B-15-26	LS	LUMP SUM	_____.
0180	206.5000 Cofferdams (structure) 01. Structure B-15-26	LS	LUMP SUM	_____.
0190	208.0100 Borrow	67.000 CY	_____.	_____.
0200	209.0300.S Backfill Coarse Aggregate (size) 01. No 1	40.000 CY	_____.	_____.
0210	210.1500 Backfill Structure Type A	330.000 TON	_____.	_____.
0220	211.0100 Prepare Foundation for Asphaltic Paving (project) 01. 4150-17-71	LS	LUMP SUM	_____.
0230	213.0100 Finishing Roadway (project) 01. 4150-17-71	1.000 EACH	_____.	_____.
0240	305.0110 Base Aggregate Dense 3/4-Inch	965.000 TON	_____.	_____.
0250	305.0120 Base Aggregate Dense 1 1/4-Inch	1,315.000 TON	_____.	_____.
0260	440.4410 Incentive IRI Ride	63,600.000 DOL	1.00000	63,600.00
0280	455.0605 Tack Coat	18,025.000 GAL	_____.	_____.
0290	460.2005 Incentive Density PWL HMA Pavement	22,590.000 DOL	1.00000	22,590.00
0300	460.2010 Incentive Air Voids HMA Pavement	33,020.000 DOL	1.00000	33,020.00
0310	460.4110.S Reheating HMA Pavement Longitudinal Joints	83,870.000 LF	_____.	_____.
0320	460.5223 HMA Pavement 3 LT 58-28 S	18,560.000 TON	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20170509018 Project(s): 4150-17-71

Federal ID(s): WISC 2017274

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0330	460.5224 HMA Pavement 4 LT 58-28 S	14,455.000 TON	_____.	_____.
0340	465.0105 Asphaltic Surface	245.000 TON	_____.	_____.
0350	465.0110 Asphaltic Surface Patching	20.000 TON	_____.	_____.
0360	465.0315 Asphaltic Flumes	30.000 SY	_____.	_____.
0370	502.0100 Concrete Masonry Bridges	122.000 CY	_____.	_____.
0380	502.3200 Protective Surface Treatment	193.000 SY	_____.	_____.
0390	505.0400 Bar Steel Reinforcement HS Structures	5,900.000 LB	_____.	_____.
0400	505.0600 Bar Steel Reinforcement HS Coated Structures	10,500.000 LB	_____.	_____.
0410	506.2605 Bearing Pads Elastomeric Non-Laminated	18.000 EACH	_____.	_____.
0420	513.7083 Railing Steel Type NY3 (structure) 01. Structure B-15-26	89.000 LF	_____.	_____.
0430	516.0500 Rubberized Membrane Waterproofing	20.000 SY	_____.	_____.
0440	521.0115 Culvert Pipe Corrugated Steel 15-Inch	34.000 LF	_____.	_____.
0450	521.0118 Culvert Pipe Corrugated Steel 18-Inch	152.000 LF	_____.	_____.
0460	521.0124 Culvert Pipe Corrugated Steel 24-Inch	430.000 LF	_____.	_____.
0470	521.1015 Apron Endwalls for Culvert Pipe Steel 15-Inch	2.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20170509018 Project(s): 4150-17-71

Federal ID(s): WISC 2017274

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0480	521.1018 Apron Endwalls for Culvert Pipe Steel 18-Inch	7.000 EACH	_____.	_____.
0490	521.1024 Apron Endwalls for Culvert Pipe Steel 24-Inch	20.000 EACH	_____.	_____.
0500	522.1018 Apron Endwalls for Culvert Pipe Reinforced Concrete 18-Inch	2.000 EACH	_____.	_____.
0510	522.1024 Apron Endwalls for Culvert Pipe Reinforced Concrete 24-Inch	1.000 EACH	_____.	_____.
0520	550.0020 Pre-Boring Rock or Consolidated Materials	210.000 LF	_____.	_____.
0530	550.1100 Piling Steel HP 10-Inch X 42 Lb	238.000 LF	_____.	_____.
0540	601.0557 Concrete Curb & Gutter 6-Inch Sloped 36-Inch Type D	410.000 LF	_____.	_____.
0550	606.0300 Riprap Heavy	90.000 CY	_____.	_____.
0560	608.0418 Storm Sewer Pipe Reinforced Concrete Class IV 18-Inch	130.000 LF	_____.	_____.
0570	608.0424 Storm Sewer Pipe Reinforced Concrete Class IV 24-Inch	48.000 LF	_____.	_____.
0580	611.0612 Inlet Covers Type C	1.000 EACH	_____.	_____.
0590	611.0642 Inlet Covers Type MS	3.000 EACH	_____.	_____.
0600	611.3004 Inlets 4-FT Diameter	1.000 EACH	_____.	_____.
0610	611.3901 Inlets Median 1 Grate	3.000 EACH	_____.	_____.
0620	612.0406 Pipe Underdrain Wrapped 6-Inch	430.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20170509018 Project(s): 4150-17-71

Federal ID(s): WISC 2017274

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0630	614.0397 Guardrail Mow Strip Emulsified Asphalt	300.000 SY	_____.	_____.
0640	614.2300 MGS Guardrail 3	300.000 LF	_____.	_____.
0650	614.2500 MGS Thrie Beam Transition	158.000 LF	_____.	_____.
0660	614.2610 MGS Guardrail Terminal EAT	4.000 EACH	_____.	_____.
0670	618.0100 Maintenance And Repair of Haul Roads (project) 01. Project 4150-17-71	1.000 EACH	_____.	_____.
0680	619.1000 Mobilization	1.000 EACH	_____.	_____.
0690	624.0100 Water	10.000 MGAL	_____.	_____.
0700	625.0100 Topsoil	3,650.000 SY	_____.	_____.
0710	628.1504 Silt Fence	2,750.000 LF	_____.	_____.
0720	628.1520 Silt Fence Maintenance	2,750.000 LF	_____.	_____.
0730	628.1905 Mobilizations Erosion Control	5.000 EACH	_____.	_____.
0740	628.1910 Mobilizations Emergency Erosion Control	2.000 EACH	_____.	_____.
0750	628.2004 Erosion Mat Class I Type B	2,315.000 SY	_____.	_____.
0760	628.2008 Erosion Mat Urban Class I Type B	1,330.000 SY	_____.	_____.
0770	628.7010 Inlet Protection Type B	4.000 EACH	_____.	_____.
0780	628.7504 Temporary Ditch Checks	100.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20170509018 Project(s): 4150-17-71

Federal ID(s): WISC 2017274

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0790	628.7555 Culvert Pipe Checks	45.000 EACH	_____.	_____.
0800	628.7570 Rock Bags	250.000 EACH	_____.	_____.
0810	629.0210 Fertilizer Type B	1.850 CWT	_____.	_____.
0820	630.0130 Seeding Mixture No. 30	63.000 LB	_____.	_____.
0830	630.0140 Seeding Mixture No. 40	11.000 LB	_____.	_____.
0840	630.0200 Seeding Temporary	42.000 LB	_____.	_____.
0850	633.5200 Markers Culvert End	32.000 EACH	_____.	_____.
0860	634.0612 Posts Wood 4x6-Inch X 12-FT	5.000 EACH	_____.	_____.
0870	634.0614 Posts Wood 4x6-Inch X 14-FT	90.000 EACH	_____.	_____.
0880	634.0616 Posts Wood 4x6-Inch X 16-FT	15.000 EACH	_____.	_____.
0890	637.2210 Signs Type II Reflective H	443.390 SF	_____.	_____.
0900	637.2230 Signs Type II Reflective F	252.500 SF	_____.	_____.
0910	638.2602 Removing Signs Type II	102.000 EACH	_____.	_____.
0920	638.3000 Removing Small Sign Supports	107.000 EACH	_____.	_____.
0930	642.5401 Field Office Type D	1.000 EACH	_____.	_____.
0940	643.0100 Traffic Control (project) 01. Project 4150-17-71	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20170509018 Project(s): 4150-17-71

Federal ID(s): WISC 2017274

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0950	643.0300 Traffic Control Drums	350.000 DAY	_____.	_____.
0960	643.0310.S Temporary Portable Rumble Strips	1.000 LS	_____.	_____.
0970	643.0420 Traffic Control Barricades Type III	1,124.000 DAY	_____.	_____.
0980	643.0705 Traffic Control Warning Lights Type A	1,868.000 DAY	_____.	_____.
0990	643.0900 Traffic Control Signs	3,698.000 DAY	_____.	_____.
1000	643.0920 Traffic Control Covering Signs Type II	4.000 EACH	_____.	_____.
1010	643.1050 Traffic Control Signs PCMS	28.000 DAY	_____.	_____.
1020	643.2000 Traffic Control Detour (project) 01. Project 4150-17-71	1.000 EACH	_____.	_____.
1030	643.3000 Traffic Control Detour Signs	2,838.000 DAY	_____.	_____.
1040	645.0120 Geotextile Type HR	190.000 SY	_____.	_____.
1050	646.2304.S Pavement Marking Grooved Wet Reflective Epoxy 4-Inch	123,155.000 LF	_____.	_____.
1060	646.2308.S Pavement Marking Grooved Wet Reflective Epoxy 8-Inch	540.000 LF	_____.	_____.
1070	647.0566 Pavement Marking Stop Line Epoxy 18- Inch	20.000 LF	_____.	_____.
1080	648.0100 Locating No-Passing Zones	7.950 MI	_____.	_____.
1090	649.0402 Temporary Pavement Marking Paint 4- Inch	54,450.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20170509018 Project(s): 4150-17-71

Federal ID(s): WISC 2017274

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
1100	650.4000 Construction Staking Storm Sewer	7.000 EACH	_____.	_____.
1110	650.6000 Construction Staking Pipe Culverts	14.000 EACH	_____.	_____.
1120	650.6500 Construction Staking Structure Layout (structure) 01. Structure B-15-26	LS	LUMP SUM	_____.
1130	650.8000 Construction Staking Resurfacing Reference	41,977.000 LF	_____.	_____.
1140	650.9910 Construction Staking Supplemental Control (project) 01. Project 4150-17-71	LS	LUMP SUM	_____.
1150	650.9920 Construction Staking Slope Stakes	3,234.000 LF	_____.	_____.
1160	690.0150 Sawing Asphalt	3,340.000 LF	_____.	_____.
1170	690.0250 Sawing Concrete	12.000 LF	_____.	_____.
1180	715.0502 Incentive Strength Concrete Structures	732.000 DOL	1.00000	732.00
1190	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	2,400.000 HRS	5.00000	12,000.00
1200	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	2,100.000 HRS	5.00000	10,500.00
1210	SPV.0060 Special 01. Grading, Shaping, and Finishing Cross Culverts	15.000 EACH	_____.	_____.
1220	SPV.0060 Special 02. HMA Percent Within Limits (PWL) Test Strip	2.000 EACH	_____.	_____.
1230	SPV.0090 Special 01. 16 Gauge Galvanized Metal Flashing	71.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20170509018 Project(s): 4150-17-71

Federal ID(s): WISC 2017274

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
1240	SPV.0090 Special 02. Prestressed Girders Box Type 17-Inch	347.000 LF	_____.	_____.
1250	SPV.0120 Special 01. Water for Seeded Areas	15.000 MGAL	_____.	_____.
Section: 0001			Total:	_____.
			Total Bid:	_____.