



Wisconsin Department of Transportation

February 8, 2018

Division of Transportation Systems Development

Bureau of Project Development
4802 Sheboygan Avenue, Rm 601
P O Box 7916
Madison, WI 53707-7916

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #08: 2250-16-70, WISC 2018176
Washington Ave, V Mount Pleasant
IH 94 to CTH H
STH 20
Racine County

Letting of February 13, 2018

This is Addendum No. 02, which provides for the following:

Special Provisions:

Revised Special Provisions	
Article No.	Description
3	Prosecution and Progress
8	Other Contracts

Added Special Provisions	
Article No.	Description
33	Notice to Contractor - Safety
34	Notice to Contractor – Media Relations
35	Traffic Meetings and Traffic Control Scheduling
36	Field Office Special, Item SPV.0060.02

Schedule of Items:

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
SPV.0060.02	Field Office Special	EACH	0	1	1

Deleted Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
642.5201	Field Office Type C	EACH	1	-1	0

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
84	Replaced miscellaneous quantity for Field Office Type C with Field Office Special

Other

Revise the contract time for completion from a completion date of June 1, 2018 to a completion date of May 15, 2018.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 02

2250-16-70

February 8, 2018

Special Provisions

3. Prosecution and Progress

Add the following after paragraph five:

Replace standard spec 108.11 paragraph (3) with the following:

The department will assess \$10,000 in daily liquidated damages. These liquidated damages reflect the cost of engineering, supervision, and a portion of road user costs.

108-055 (20130615)

The department will not grant time extensions to the completion date for the following:

1. Severe weather as specified in standard spec 108.10.2.2.
2. Labor disputes that are not industry wide.
3. Delays in material deliveries.

*Add the following under section titled **Work Restrictions**:*

Construction activities on this project are anticipated to consist of night work, occurring between 6:00 PM and 6:00 AM. Do not perform work on the project outside of these hours unless otherwise approved by the engineer.

7. Other Contracts

Replace entire article language with the following:

The following contracts have the potential to be under construction within the time period of the contract:

<u>Project ID</u>	<u>Roadway</u>	<u>Limits</u>
2340-00-76	STH 20	Intersection with CTH C
1320-25-00	International Drive	STH 11 – STH 20
1320-25-00	Braun Road	~2,000 FT West of IH 94 – 90 th Street
1320-25-00	CTH KR	~2,000 FT West of IH 94 – 90 th Street
2018-16-70	CTH H (Racine Co)	CTH KR to STH 20
2018-16-70	CTH H (Kenosha Co)	CTH A to CTH KR
2018-16-70	CTH H (Kenosha Co)	IH 41/94 EFR to CTH H

Other projects not listed here may be under construction within the time period of the contract and coordination with those projects is required.

33. Notice to Contractor – Safety

All workers shall wear OSHA and ANSI compliant safety head protection, safety glasses, safety-toe protective footwear, and safety vest at all times while within the project footprint.

The contractor and respective subcontractors shall provide a copy of their current Company Safety Plans to the Department at the preconstruction meeting. All workers shall comply with the Safety Plans of their employer.

Noncompliance with this contract provision may result in removal of contractor personnel from the project or suspension of work in accordance with Wisconsin Department of Transportation Standard Specification 108.6 applicable under the contract.

34. Notice to Contractor – Media Relations

- a. The Contractor shall not disseminate or publicize this Agreement, information relating to this Agreement, their work responsibilities, or generally comment about the entire project without prior written consent from one of the Department's designated Project Communications Leaders listed under Section 1(d).
- b. The Contractor will refer all information requests or interview requests made by external parties, including media sources, to all of the Department's designated Project Communications Leaders listed under Section 1(d).
- c. The Contractor agrees to coordinate with the Department as to the form, content and timing of any public announcement of this Agreement.
- d. The Project Communications Leaders for the Department shall be:
 - i. The Department's Project Manager
 - ii. Becky Kikkert
4802 Sheboygan Avenue
Madison, WI 53705
Phone: (608) 266-3581
Email: rebecca.kikkert@dot.wi.gov
 - iii. Michael Pyritz
141 NW Barstow Street
P.O. Box 798
Waukesha, WI 53188
Phone: (262) 521-5373
Email: michael.pyritz@dot.wi.gov
- e. Noncompliance with this contract provision may result in removal of contractor personnel from the project or suspension of work in accordance with Wisconsin Department of Transportation Standard Specification 108.6 applicable under the contract.
- f. Notwithstanding anything to the contrary contained herein, no provision of this Agreement shall be interpreted to impede the Contractor, or any individual, from reporting possible violations of state or federal law to any governmental agency or entity, or from making other disclosures under the whistleblower provisions of state or federal law. The Contractor does not need the prior authorization of the Department to make any such reports or disclosures and the Contractor shall not be required to notify the Department that such reports or disclosures have been made.

35. Traffic Meetings and Traffic Control Scheduling

Every Wednesday by 9:00 AM, submit a detailed proposed 2-week look-ahead traffic closure schedule to the engineer. Type the detailed proposed 2-week look-ahead closure schedule into an excel spreadsheet provided by the engineer. Enter information such as closure dates, duration, work causing the closure and detours to be used. Also enter information such as ongoing long-term closures, emergency contacts and general 2-month look-ahead closure information into the excel spreadsheet.

Meet with the engineer between 10:00 -11:00 AM on Thursdays to discuss and answer questions on the proposed schedule. The location of this meeting will be determined at the preconstruction meeting associated with this project. Edit, delete and add closures to the detailed proposed 2-week look-ahead schedule, as directed by the engineer, so that proposed closures meet specification requirements. Other edits, deletions, or additions unrelated to meeting specification requirements may also be agreed upon with the engineer during the 10:00 AM meeting.

Every Thursday at 2:00 PM, or as scheduled by the engineer, attend a weekly traffic meeting. The meeting will bring local agencies, project stakeholders, owner managers, owner engineers, contractors, document control and construction engineering personnel together to discuss traffic staging, closures and general impacts. Upon obtaining feedback from the meeting attendees, edit, delete and add information to the detailed 2-week look-ahead closure schedule, as needed. Submit the revised 2-week look-ahead to the engineer.

Obtain approval from the engineer for any mid-week changes to the closure schedule. Revise the 2-week look-ahead as required and obtain engineer approval.

sef-643-040 (20150319)

36. Field Office Special, Item SPV.0060.02

A Description

This special provision describes furnishing, placing or erecting, equipping, and maintaining a field office at an engineer-approved location.

B Materials

Furnish materials according to section 642.2.

Furnish a facility with minimum exterior dimensions of 20' x 30' (600 sq ft) and equipped as specified in 642.2.2.1 except as modified: A modem router with a capacity for 8 or more personal computers. A connection speed of 3 Mbps or more with 8 computers operating simultaneously. Also, include the following:

1. 8 suitable office desks with drawers and locks
2. 10 ergonomically correct office chairs in working condition with the following features: Five legged base with casters, high backrest, adjustable arms or no arms, seat adjustable from 15 inches to 22 inches from the floor with seamless waterfall rounded front edge
3. Three folding tables
4. 12 folding chairs
5. 4 drawer file cabinet

C Construction

Conform to the specifications in section 642.3.

D Measurement

The department will pay for Field Office Special as each field office acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.02	Field Office Special	EACH

Payment for the Field Office Special bid item is full compensation for providing, equipping, securing, and maintaining the facility; for telecommunications equipment, installation, and service fees; and for providing bottled water, utilities, fuel, ventilation, and toilet facilities as required, either independently or jointly, for the time specified in 642.3. The department will pay for the cost of telecommunications usage fees incurred by department staff.

Schedule of Items

Attached, dated February 8, 2018, are the revised Schedule of Items Pages 1 – 10.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:
Revised: 84

END OF ADDENDUM

Addendum No. 02
 ID 2250-16-70
 Revised Sheet 84
 February 8, 2018

FIELD OFFICE

SPV. 0060. 02	REMARKS
FIELD OFFICE SPECIAL	
EACH	1
TOTAL	1

PROJECT	REMARKS
2250-16-70	

TRAFFIC CONTROL SUMMARY

STAGE	DURATION DAYS	LOCATION	643. 5000	643. 0300	643. 0420	643. 0705	643. 0715	643. 0800	643. 0900	643. 1050	643. 0910	643. 0920	REMARKS
			TRAFFIC CONTROL EACH	TRAFFIC DRUMS NO. IN	BARRICADES TYPE III NO. IN	TRAFFIC CONTROL WARNING LIGHTS TYPE C NO. IN	TRAFFIC CONTROL TRAFFIC CONTROL LIGHTS TYPE C NO. IN	ARROW BOARDS NO. IN	TRAFFIC CONTROL SIGNS NO. IN	TRAFFIC CONTROL SIGNS POMS NO. IN	TRAFFIC CONTROL COVERING SIGNS NO. IN	TRAFFIC CONTROL COVERING SIGNS NO. IN	TYPE I EACH
1	7	PRE WARNING	--	--	--	--	--	--	--	6	--	--	--
1	13	ADVANCE WARNING EB/WB STH 20	--	--	--	--	--	--	76	988	--	--	--
2	13	ALTERNATE ROUTE	--	110	65	130	26	6	66	858	--	--	--
2	14	ADVANCED WARNING EB/WB STH 20	--	--	--	--	--	--	109	1,417	--	--	--
3	2	ALTERNATE ROUTE	--	1,030	55	110	26	2	58	812	--	--	--
3	2	ADVANCED WARNING EB/WB STH 20	--	--	--	--	--	--	66	924	--	--	--
4	2	ALTERNATE ROUTE	--	--	--	--	--	--	109	1,526	--	--	--
4	2	ADVANCED WARNING EB/WB STH 20	--	1,110	65	130	26	6	76	152	--	--	--
4	18	ALTERNATE ROUTE	--	--	--	--	--	--	109	218	--	--	--
4	18	ADVANCED WARNING EB/WB STH 20	--	1,030	55	110	26	2	58	1,044	--	--	--
4	18	ALTERNATE ROUTE	--	--	--	--	--	--	66	1,188	--	--	--
4	21	PRE WARN RAMP CLOSURES	--	--	--	--	--	--	109	1,962	--	--	--
4	7	NB IH-94 RAMP CLOSURES	--	120	10	20	--	--	26	182	1	7	98
4	7	SB IH-94 RAMP CLOSURES	--	110	10	20	--	--	26	182	1	7	98
4	7	UNDISTRIBUTED	1	--	290	--	--	15	--	1,159	--	20	1
TOTAL			1	42,050	3,165	6,325	1,344	169	12,744	98	216	3	



Proposal Schedule of Items

Proposal ID: 20180213008 Project(s): 2250-16-70

Federal ID(s): WISC 2018176

SECTION: 0001 Roadway Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	204.0105 Removing Pavement Butt Joints	130.000 SY	_____.	_____.
0004	204.0110 Removing Asphaltic Surface	34.000 SY	_____.	_____.
0006	204.0115 Removing Asphaltic Surface Butt Joints	3,525.000 SY	_____.	_____.
0008	204.0120 Removing Asphaltic Surface Milling	117,193.000 SY	_____.	_____.
0010	204.0150 Removing Curb & Gutter	1,858.000 LF	_____.	_____.
0012	204.0155 Removing Concrete Sidewalk	50.000 SY	_____.	_____.
0014	204.0165 Removing Guardrail	318.000 LF	_____.	_____.
0016	204.0180 Removing Delineators and Markers	17.000 EACH	_____.	_____.
0018	204.0195 Removing Concrete Bases	4.000 EACH	_____.	_____.
0020	204.0245 Removing Storm Sewer (size) 01. 12-Inch	8.000 LF	_____.	_____.
0022	205.0100 Excavation Common	138.000 CY	_____.	_____.
0024	213.0100 Finishing Roadway (project) 01. 2250-16-70	1.000 EACH	_____.	_____.
0026	305.0110 Base Aggregate Dense 3/4-Inch	4,117.000 TON	_____.	_____.
0028	305.0120 Base Aggregate Dense 1 1/4-Inch	660.000 TON	_____.	_____.
0030	305.0500 Shaping Shoulders	260.000 STA	_____.	_____.
0032	390.0403 Base Patching Concrete Shes	3,089.000 SY	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20180213008 Project(s): 2250-16-70

Federal ID(s): WISC 2018176

SECTION: 0001 Roadway Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0034	416.0610 Drilled Tie Bars	1,066.000 EACH	_____.	_____.
0036	416.0620 Drilled Dowel Bars	2,395.000 EACH	_____.	_____.
0038	416.1715 Concrete Pavement Repair SHES	179.000 SY	_____.	_____.
0040	416.1725 Concrete Pavement Replacement SHES	2,525.000 SY	_____.	_____.
0042	420.1000 Continuous Diamond Grinding Concrete Pavement	7,900.000 SY	_____.	_____.
0044	440.4410 Incentive IRI Ride	18,889.000 DOL	1.00000	18,889.00
0046	450.4000 HMA Cold Weather Paving	40,103.000 TON	_____.	_____.
0048	455.0605 Tack Coat	4,497.000 GAL	_____.	_____.
0050	460.2000 Incentive Density HMA Pavement	25,570.000 DOL	1.00000	25,570.00
0052	460.4110.S Reheating HMA Pavement Longitudinal Joints	25,145.000 LF	_____.	_____.
0054	460.7223 HMA Pavement 3 HT 58-28 S	24,151.000 TON	_____.	_____.
0056	460.7424 HMA Pavement 4 HT 58-28 H	15,800.000 TON	_____.	_____.
0058	465.0120 Asphaltic Surface Driveways and Field Entrances	151.000 TON	_____.	_____.
0060	465.0305 Asphaltic Surface Safety Islands	6.000 TON	_____.	_____.
0062	465.0315 Asphaltic Flumes	12.000 SY	_____.	_____.
0064	465.0400 Asphaltic Shoulder Rumble Strips	34,640.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20180213008 Project(s): 2250-16-70

Federal ID(s): WISC 2018176

SECTION: 0001 Roadway Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0066	520.8000 Concrete Collars for Pipe	2.000 EACH	_____.	_____.
0068	602.0405 Concrete Sidewalk 4-Inch	360.000 SF	_____.	_____.
0070	608.0312 Storm Sewer Pipe Reinforced Concrete Class III 12-Inch	8.000 LF	_____.	_____.
0072	611.8110 Adjusting Manhole Covers	2.000 EACH	_____.	_____.
0074	614.0010 Barrier System Grading Shaping Finishing	2.000 EACH	_____.	_____.
0076	614.2300 MGS Guardrail 3	382.000 LF	_____.	_____.
0078	614.2610 MGS Guardrail Terminal EAT	2.000 EACH	_____.	_____.
0080	614.2620 MGS Guardrail Terminal Type 2	2.000 EACH	_____.	_____.
0082	618.0100 Maintenance And Repair of Haul Roads (project) 01. 2250-16-70	1.000 EACH	_____.	_____.
0084	619.1000 Mobilization	1.000 EACH	_____.	_____.
0086	620.0300 Concrete Median Sloped Nose	26.000 SF	_____.	_____.
0088	624.0100 Water	17.000 MGAL	_____.	_____.
0090	625.0100 Topsoil	972.000 SY	_____.	_____.
0092	628.1504 Silt Fence	611.000 LF	_____.	_____.
0094	628.1520 Silt Fence Maintenance	611.000 LF	_____.	_____.
0096	628.1905 Mobilizations Erosion Control	4.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20180213008 Project(s): 2250-16-70

Federal ID(s): WISC 2018176

SECTION: 0001 Roadway Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0098	628.1910 Mobilizations Emergency Erosion Control	4.000 EACH	_____.	_____.
0100	628.2002 Erosion Mat Class I Type A	1,190.000 SY	_____.	_____.
0102	628.7005 Inlet Protection Type A	5.000 EACH	_____.	_____.
0104	628.7015 Inlet Protection Type C	33.000 EACH	_____.	_____.
0106	628.7020 Inlet Protection Type D	2.000 EACH	_____.	_____.
0108	629.0210 Fertilizer Type B	1.000 CWT	_____.	_____.
0110	630.0120 Seeding Mixture No. 20	26.000 LB	_____.	_____.
0112	633.0100 Delineator Posts Steel	17.000 EACH	_____.	_____.
0114	633.0500 Delineator Reflectors	31.000 EACH	_____.	_____.
0116	634.0618 Posts Wood 4x6-Inch X 18-FT	6.000 EACH	_____.	_____.
0118	637.2210 Signs Type II Reflective H	179.500 SF	_____.	_____.
0120	637.2215 Signs Type II Reflective H Folding	74.600 SF	_____.	_____.
0122	637.2230 Signs Type II Reflective F	20.000 SF	_____.	_____.
0124	638.2102 Moving Signs Type II	3.000 EACH	_____.	_____.
0126	638.2602 Removing Signs Type II	16.000 EACH	_____.	_____.
0128	638.3000 Removing Small Sign Supports	3.000 EACH	_____.	_____.
0132	643.0300 Traffic Control Drums	42,050.000 DAY	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20180213008 Project(s): 2250-16-70

Federal ID(s): WISC 2018176

SECTION: 0001 Roadway Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0134	643.0420 Traffic Control Barricades Type III	3,165.000 DAY	_____.	_____.
0136	643.0705 Traffic Control Warning Lights Type A	6,325.000 DAY	_____.	_____.
0138	643.0715 Traffic Control Warning Lights Type C	1,344.000 DAY	_____.	_____.
0140	643.0800 Traffic Control Arrow Boards	169.000 DAY	_____.	_____.
0142	643.0900 Traffic Control Signs	12,744.000 DAY	_____.	_____.
0144	643.0910 Traffic Control Covering Signs Type I	216.000 EACH	_____.	_____.
0146	643.0920 Traffic Control Covering Signs Type II	3.000 EACH	_____.	_____.
0148	643.1050 Traffic Control Signs PCMS	98.000 DAY	_____.	_____.
0150	643.5000 Traffic Control	1.000 EACH	_____.	_____.
0152	646.1020 Marking Line Epoxy 4-Inch	4,697.000 LF	_____.	_____.
0154	646.1040 Marking Line Grooved Wet Ref Epoxy 4-Inch	57,245.000 LF	_____.	_____.
0156	646.1545 Marking Line Grooved Wet Ref Contrast Epoxy 4-Inch	7,092.000 LF	_____.	_____.
0158	646.3020 Marking Line Epoxy 8-Inch	2,052.000 LF	_____.	_____.
0160	646.3545 Marking Line Grooved Wet Ref Contrast Epoxy 8-Inch	7,528.000 LF	_____.	_____.
0162	646.5020 Marking Arrow Epoxy	58.000 EACH	_____.	_____.
0164	646.5120 Marking Word Epoxy	33.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20180213008 Project(s): 2250-16-70

Federal ID(s): WISC 2018176

SECTION: 0001 Roadway Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0166	646.6120 Marking Stop Line Epoxy 18-Inch	943.000 LF	_____.	_____.
0168	646.7120 Marking Diagonal Epoxy 12-Inch	560.000 LF	_____.	_____.
0170	649.0105 Temporary Marking Line Paint 4-Inch	112,640.000 LF	_____.	_____.
0172	649.0205 Temporary Marking Line Paint 8-Inch	1,200.000 LF	_____.	_____.
0174	650.5500 Construction Staking Curb Gutter and Curb & Gutter	1,858.000 LF	_____.	_____.
0176	650.8000 Construction Staking Resurfacing Reference	12,597.000 LF	_____.	_____.
0178	650.8500 Construction Staking Electrical Installations (project) 01. 2250-16-70	LS	LUMP SUM	_____.
0180	650.9910 Construction Staking Supplemental Control (project) 01. 2250-16-70	LS	LUMP SUM	_____.
0182	652.0225 Conduit Rigid Nonmetallic Schedule 40 2-Inch	78.000 LF	_____.	_____.
0184	652.0235 Conduit Rigid Nonmetallic Schedule 40 3-Inch	40.000 LF	_____.	_____.
0186	652.0615 Conduit Special 3-Inch	50.000 LF	_____.	_____.
0188	652.0700.S Install Conduit into Existing Item	21.000 EACH	_____.	_____.
0190	652.0800 Conduit Loop Detector	5,710.000 LF	_____.	_____.
0192	653.0154 Pull Boxes Non-Conductive 24x36-Inch	4.000 EACH	_____.	_____.
0194	653.0164 Pull Boxes Non-Conductive 24x42-Inch	7.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20180213008 Project(s): 2250-16-70

Federal ID(s): WISC 2018176

SECTION: 0001 Roadway Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0196	653.0905 Removing Pull Boxes	11.000 EACH	_____.	_____.
0198	654.0113 Concrete Bases Type 13	4.000 EACH	_____.	_____.
0200	655.0230 Cable Traffic Signal 5-14 AWG	720.000 LF	_____.	_____.
0202	655.0240 Cable Traffic Signal 7-14 AWG	2,060.000 LF	_____.	_____.
0204	655.0260 Cable Traffic Signal 12-14 AWG	2,165.000 LF	_____.	_____.
0206	655.0305 Cable Type UF 2-12 AWG Grounded	1,050.000 LF	_____.	_____.
0208	655.0515 Electrical Wire Traffic Signals 10 AWG	2,765.000 LF	_____.	_____.
0210	655.0610 Electrical Wire Lighting 12 AWG	1,080.000 LF	_____.	_____.
0212	655.0700 Loop Detector Lead In Cable	17,035.000 LF	_____.	_____.
0214	655.0800 Loop Detector Wire	21,270.000 LF	_____.	_____.
0216	655.0900 Traffic Signal EVP Detector Cable	2,355.000 LF	_____.	_____.
0218	657.0100 Pedestal Bases	9.000 EACH	_____.	_____.
0220	657.0420 Traffic Signal Standards Aluminum 13-FT	3.000 EACH	_____.	_____.
0222	657.0425 Traffic Signal Standards Aluminum 15-FT	6.000 EACH	_____.	_____.
0224	657.1355 Install Poles Type 12	1.000 EACH	_____.	_____.
0226	657.1360 Install Poles Type 13	3.000 EACH	_____.	_____.
0228	657.1535 Install Monotube Arms 35-FT	2.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20180213008 Project(s): 2250-16-70

Federal ID(s): WISC 2018176

SECTION: 0001 Roadway Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0230	657.1540 Install Monotube Arms 40-FT	1.000 EACH	_____.	_____.
0232	657.1555 Install Monotube Arms 55-FT	1.000 EACH	_____.	_____.
0234	657.1812 Install Luminaire Arms Steel 12-FT	6.000 EACH	_____.	_____.
0236	658.0173 Traffic Signal Face 3S 12-Inch	19.000 EACH	_____.	_____.
0238	658.0174 Traffic Signal Face 4S 12-Inch	9.000 EACH	_____.	_____.
0240	658.5069 Signal Mounting Hardware (location) 01. CTH H/Renaissance Blvd	LS	LUMP SUM	_____.
0242	659.1125 Luminaires Utility LED C	8.000 EACH	_____.	_____.
0244	661.0200 Temporary Traffic Signals for Intersections (location) 01. CTH H/Renaissance Blvd	LS	LUMP SUM	_____.
0246	690.0150 Sawing Asphalt	200.000 LF	_____.	_____.
0248	690.0250 Sawing Concrete	19,115.000 LF	_____.	_____.
0250	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	1,500.000 HRS	5.00000	7,500.00
0252	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	1,800.000 HRS	5.00000	9,000.00
0254	SPV.0060 Special 01. Strapping C-51-0017	4.000 EACH	_____.	_____.
0256	SPV.0090 Special 01. Concrete Joint and Crack Cleaning	6,050.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20180213008 Project(s): 2250-16-70

Federal ID(s): WISC 2018176

SECTION: 0001 Roadway Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0258	SPV.0090 Special 02. Removing HMA Pavement Notched Wedge Longitudinal Joint Milling	25,145.000 LF	_____.	_____.
0260	SPV.0090 Special 03. EVP Confirmation Light Cable Type 2-14 AWG Grounded	1,110.000 LF	_____.	_____.
0262	SPV.0090 Special 04. Concrete Curb & Gutter 6-inch Sloped 30-Inch Type G Modified	1,858.000 LF	_____.	_____.
0264	SPV.0105 Special 01. Cleaning Box Culvert C-51-0017	LS	LUMP SUM	_____.
0266	SPV.0105 Special 02. Temporary Infrared EVP System, STH 20 & CTH H/Renaissance Blvd	LS	LUMP SUM	_____.
0268	SPV.0105 Special 03. Remove Traffic Signal CTH H/Renaissance Blvd	LS	LUMP SUM	_____.
0270	SPV.0105 Special 04. Transport and Install State Furnished Emergency Vehicle Preemption (EVP) Det	LS	LUMP SUM	_____.
0272	SPV.0105 Special 05. Remove Loop Detector Wire and Lead-in Cable (STH 20 & IH 41/94)	LS	LUMP SUM	_____.
0274	SPV.0105 Special 06. Remove Loop Detector Wire and Lead-in Cable (STH 20 & East Frontage Road)	LS	LUMP SUM	_____.
0276	SPV.0105 Special 07. Remove Loop Detector Wire and Lead-in Cable (STH 20 & CTH H/Renaissance Blvd)	LS	LUMP SUM	_____.
0278	SPV.0105 Special 08. Transporting Traffic Signal and Intersection Lighting Materials (CTH H/Renai	LS	LUMP SUM	_____.



Proposal Schedule of Items

Proposal ID: 20180213008 Project(s): 2250-16-70

Federal ID(s): WISC 2018176

SECTION: 0001 Roadway Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0280	SPV.0105 Special 09. Transport & Inst St Furn Emergency Veh Preemp Det Heads STH 20 & CTH V	LS	LUMP SUM	_____.
0282	SPV.0060 Special 02. Field Office Special	1.000 EACH	_____.	_____.
Section: 0001			Total:	_____.
			Total Bid:	_____.

