

# **Wisconsin Department of Transportation**

August 9, 2018

# **Division of Transportation Systems Development**

Bureau of Project Development 4822 Madison Yards Way, 4<sup>th</sup> Floor South Madison, WI 53705

Telephone: (608) 266-1631 Facsimile (FAX): (608) 266-8459

## **NOTICE TO ALL CONTRACTORS:**

Proposal #02: 5990-00-34

C Janesville, W Milwaukee Street Rock River Bridge B-53-0294

Local Street Rock County

# Letting of August 14, 2018

This is Addendum No. 01, which provides for the following:

# **Special Provisions:**

Revised Special Provisions				
Article	Description			
No.	Description			
23	Abutment and Pier Construction			
71	Removing Old Structure Over Waterway With Minimal Debris Station 14+54, SPV.0105.05			

# **Schedule of Items:**

Revised Bid Item Quantities						
Did Itom	Unit	Old	Revised	Proposal		
Bid Item	Item Description	Ullit	Quantity	Quantity	Total	
505.0400	00 Bar Steel Reinforcement HS Structures		28,200	210	28,410	
550.2146	Piling CIP Concrete 14 x 0.375-Inch	LF	5,020	600	5,620	

	Added Bid Item Quantities						
	Bid Item	Item Description	Unit	Old	Revised	Proposal	
Bid itom		nom Beedipaen	• • • • • • • • • • • • • • • • • • • •	Quantity	Quantity	Total	
	502.1100	Concrete Masonry Seal	CY	0	435	435	

## **Plan Sheets:**

Revised Plan Sheets				
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)			
156	General Plan (Added Concrete Masonry Seal details)			
157	Cross Section (Added Concrete Masonry Seal details)			

158	Quantities, Profile & Notes (Updated quantity table to add Concrete Masonry Seal bid item;
	revised piling and bar steel quantities at the piers)
159	Subsurface Investigation (Added Concrete Masonry Seal details)
165	Pier 1 (Added Concrete Masonry Seal details; modified piling and bar steel)
166	Pier 1 Details (Added Concrete Masonry Seal details; modified bill of bars)
167	Pier 2 (Added Concrete Masonry Seal details; modified piling and bar steel)
168	Pier 2 Details (Added Concrete Masonry Seal details; modified bill of bars)
169	Pier 3 (Added Concrete Masonry Seal details; modified piling and bar steel)
170	Pier 3 Details (Added Concrete Masonry Seal details; modified bill of bars)

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist Proposal Management Section

# ADDENDUM NO. 01 5990-00-34 August 9, 2018

#### **Special Provisions**

#### 23. Abutment and Pier Construction.

Replace entire article language with the following:

Determine the method of construction, and observe the following conditions:

- Cofferdams are required at the abutments and piers. Build the cofferdams of non-erodable material.
- 2. Concrete poured under water will not be allowed at the piers. Dewater and place all pier concrete under dry conditions.
- 3. Concrete poured under water will be allowed at the abutments. Pour the concrete conforming to standard spec 502.3.5.3. Ensure that the forms are tight to prevent leakage of concrete into the stream. Treat all displaced water by filtration, settling basin, or other means sufficient to reduce the cement content before discharging the water into the stream.

Prior to driving abutment piling, prebore to a depth of 20'-0" below the bottom of the abutments.

### 71. Removing Old Structure Over Waterway With Minimal Debris Station 14+54, SPV.0105.05.

Add the following sentence to the end of section "A":

Remove existing piers to the limits noted in the standard specifications, but no lower than elevation 752.5 as noted in the plans.

Add the following section "M" after section "L":

M. Localized dewatering, if required, for river wall saw cuts. Saw cuts below the normal water elevation are anticipated.


#### Schedule of Items


Attached, dated August 9, 2018, are the revised Schedule of Items Pages 3 and 15.


#### Plan Sheets


The following  $8\frac{1}{2}$  x 11-inch sheets are attached and made part of the plans for this proposal: Revised: 156, 157, 158, 159, 165, 166, 167, 168, 169 and 170.


**END OF ADDENDUM** 


































# Proposal Schedule of Items

Page 3 of 15

Federal ID(s): N/A

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0064	502.2000 Compression Joint Sealer Preformed Elastomeric (width) 01. 2 1/4-Inch	24.000 LF	·	·
0066	502.3200 Protective Surface Treatment	1,450.000 SY		·
0068	502.3210 Pigmented Surface Sealer	450.000 SY		
0070	505.0400 Bar Steel Reinforcement HS Structures	28,410.000 LB		
0072	505.0600 Bar Steel Reinforcement HS Coated Structures	183,390.000 LB	·	·
0074	506.2605 Bearing Pads Elastomeric Non- Laminated	6.000 EACH	·	·
0076	511.1200 Temporary Shoring (structure) 01. B-53- 294	300.000 SF	·	
0078	516.0500 Rubberized Membrane Waterproofing	40.000 SY	·	·
0800	522.1060 Apron Endwalls for Culvert Pipe Reinforced Concrete 60-Inch	1.000 EACH	·	·
0082	550.0010 Pre-Boring Unconsolidated Materials	320.000 LF		·
0084	550.0500 Pile Points	55.000 EACH		
0086	550.2146 Piling CIP Concrete 14 X 0.375-Inch	5,620.000 LF		
0088	601.0417 Concrete Curb & Gutter 30-Inch Type K	585.000 LF		
0090	601.0419 Concrete Curb & Gutter 30-Inch Type L	125.000 LF		
0092	601.0600 Concrete Curb Pedestrian	25.000 LF		<u></u>



08/09/2018 08:01:37



# Proposal Schedule of Items

Page 15 of 15

Federal ID(s): N/A

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0420	SPV.0165	50.000		
	Special 07. Abandoned Vault Removal Reinforced Concrete 10"+, Depth to 5'	SF	<del>-</del>	·
0422	SPV.0165	50.000		
	Special 08. Abandoned Vault Removal Reinforced Concrete 10"+, Depth Over 5'	SF	<del>-</del>	·
0424	SPV.0165	210.000		
	Special 09. Structural Sidewalk Special	SF	·	
0426	SPV.0165	150.000		
	Special 10. Construction Staking Sidewalk	SF	<del>-</del>	·
0428	SPV.0180	28.000		
	Special 01. Shredded Hardwood Bark Mulch	SY	<del>-</del>	·
0430	SPV.0195	400.000		
	Special 01. Excavation, Hauling, and Disposal of PAH Contaminated Soil	TON	<del>-</del>	·
0432	502.1100	435.000		
	Concrete Masonry Seal	CY		

Section:	0001	Total:	
Cootion.	0001	Total.	 

Total Bid: \_\_\_\_\_.