



Wisconsin Department of Transportation

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

November 8, 2018

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #21: 4501-00-71, WISC 2018 443
C New Holstein
Clark Street-Manitowoc Calumet Co
CTH X
Calumet County

Letting of November 13, 2018

This is Addendum No. 01, which provides for the following:

Special Provisions:

Revised Special Provisions	
Article No.	Description
4	Traffic

Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
643.0300	Traffic Control Drums	Days	802	942	942
643.0420	Traffic Control Barricades Type III	Days	793	1017	1017
643.0705	Traffic Control Warning Lights Type A	Days	1336	1686	1686
643.0900	Traffic Control Signs	Days	1189	1434	1434

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
18	Updated "Traffic Control" table to reflect change for CTH X full closure

Other:

Revise the contract time for completion from 20 working days to 25 working days (an increase of 5 working days).

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01

4501-00-71

November 8, 2018

Special Provisions

4. Traffic

Replace paragraph four with the following:

A full closure of CTH X will be allowed for up to 12 calendar days for the replacement of the Pine Creek culverts. This closure will be isolated to the immediate area of the culvert replacements. Continue to maintain access to side roads, residences, and businesses located within the construction limits during this closure.

Schedule of Items

Attached, dated November 8, 2018, are the revised Schedule of Items Page 4.

Plan Sheets

The following 8 ½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 18

END OF ADDENDUM

TRAFFIC CONTROL SUMMARY

LOCATION	APPROXIMATE SERVICE DAYS	643.0300 DRUMS NO. IN SERVICE	643.0420 BARRICADES TYPE II NO. IN SERVICE	643.0705 WARNING LIGHTS TYPE A NO. IN SERVICE	643.0900 SIGNS NO. IN SERVICE	643.1050 SIGNS PCMS NO. IN SERVICE	REMARKS
CTH X / CLARK DRIVE	7	3	21	-	-	1	BEFORE CLOSURE OF ROADWAY
CTH X / MEGGERS ROAD	7	3	21	-	-	1	BEFORE CLOSURE OF ROADWAY
CTH X / STH 32/STH 57	45	-	4	180	6	270	BARRICADES AND SIGNS FOR MAINLINE CLOSURES - DETAIL A & C
STATION 107+00	45	-	2	90	4	180	BARRICADES AND SIGNS FOR MAINLINE CLOSURES - DETAIL E
RABE HILLTOP ROAD / CTH X	45	-	3	135	4	180	BARRICADES AND SIGNS FOR SIDEROAD CLOSURES - DETAIL 4
CTH T / CTH X	33	-	4	132	8	264	BARRICADES AND SIGNS FOR SIDEROAD CLOSURES - DETAIL 3
CTH T / CTH X	33	-	-	-	2	66	TEMPORARY STOP SIGNS FOR CTH T & 7 CORNERS ROAD
CTH T / STH 151	12	-	-	-	1	12	ROAD CLOSED AHEAD (FOR USE DURING CTH T INTERSECTION WORK)
CTH T / TEQUISH ROAD	12	-	2	24	4	48	ROAD CLOSED 1 MILE AHEAD (FOR USE DURING CTH T INTERSECTION WORK)
CTH T / CTH X	12	-	5	60	8	96	BARRICADES AND SIGNS FOR SIDEROAD CLOSURES - DETAIL 4 (FOR USE DURING CTH T INTERSECTION WORK)
CTH X / CTH T	12	-	4	48	8	96	BARRICADES AND SIGNS FOR MAINLINE CLOSURES - DETAIL C
STATION 164+00	12	-	7	84	8	96	BARRICADES AND SIGNS FOR MAINLINE CLOSURES - DETAIL D (FOR USE DURING CULVERT REPLACEMENTS)
STATION 175+00	12	-	7	84	8	96	BARRICADES AND SIGNS FOR MAINLINE CLOSURES - DETAIL D (FOR USE DURING CULVERT REPLACEMENTS)
STATION 197+00	45	-	2	90	4	180	BARRICADES AND SIGNS FOR MAINLINE CLOSURES - DETAIL E
CTH X / MEGGERS ROAD	45	-	2	90	4	180	BARRICADES AND SIGNS FOR MAINLINE CLOSURES - DETAIL B
CTH X / MEGGERS ROAD	45	-	-	-	2	90	TEMPORARY STOP SIGN
UNDISTRIBUTED	45	20	900	-	-	-	
TOTALS		942	1,017	1,686	1,434	14	

MARKING LINE

STATION TO	STATION	LOCATION	646.1020 EPOXY 4-INCH YELLOW L F	646.1020 EPOXY 4-INCH WHITE L F
107+10	-	197+00	8,000	17,750
		RABE HILLTOP ROAD	20	-
		CTH T	300	480
TOTAL			26,550	

CONSTRUCTION STAKING

STATION TO	STATION	LOCATION	650.5500 CURB, GUTTER AND CURB & GUTTER L F	650.6000 PIPE CULVERTS EACH	650.8000 RESURFACING L F	650.9910 SUPPLEMENTAL CONTROL L S	650.9920 SLOPE STAKES L F
107+10	-	197+00	320	3	8,990	1	1,930
TOTALS			320	3	8,990	1	1,930

SAWING PAVEMENT

STATION	LOCATION	690.0150 SAWING ASPHALT L F	690.0250 SAWING CONCRETE L F
107+10	CTH X	40	-
197+00	CTH X	25	-
	RABE HILLTOP ROAD	25	-
	CTH T	50	-
	DRIVEWAYS	40	-
	CURE & GUTTER REPAIR	-	100
TOTAL		180	100

Addendum No. 01
 ID 4501-00-71
 Revised Sheet 18
 November 8, 2018

EXCAVATION AND HAULING OF EXCESS RULVERIZED MATERIAL

STATION TO	STATION	LOCATION	SPV.0035.01 CY
111+48	-	127+73	663
132+66	-	140+23	343
187+61	-	193+75	244
TOTAL			1,250

LOCATING NO-PASSING ZONES

STATION TO	STATION	LOCATION	648.0100 MI
107+10	-	197+00	1.7
TOTAL			1.7

ALL ITEMS ARE CATEGORY 0010 UNLESS OTHERWISE STATED



Proposal Schedule of Items

Proposal ID: 20181113021 Project(s): 4501-00-71

Federal ID(s): WISC 2018443

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0094	630.0140 Seeding Mixture No. 40	40.000 LB	_____.	_____.
0096	630.0200 Seeding Temporary	105.000 LB	_____.	_____.
0098	633.0100 Delineator Posts Steel	4.000 EACH	_____.	_____.
0100	633.5200 Markers Culvert End	6.000 EACH	_____.	_____.
0102	637.2230 Signs Type II Reflective F	2.000 SF	_____.	_____.
0104	638.2102 Moving Signs Type II	10.000 EACH	_____.	_____.
0106	638.4000 Moving Small Sign Supports	4.000 EACH	_____.	_____.
0108	642.5001 Field Office Type B	1.000 EACH	_____.	_____.
0110	643.0300 Traffic Control Drums	942.000 DAY	_____.	_____.
0112	643.0420 Traffic Control Barricades Type III	1,017.000 DAY	_____.	_____.
0114	643.0705 Traffic Control Warning Lights Type A	1,686.000 DAY	_____.	_____.
0116	643.0900 Traffic Control Signs	1,434.000 DAY	_____.	_____.
0118	643.1050 Traffic Control Signs PCMS	14.000 DAY	_____.	_____.
0120	643.5000 Traffic Control	1.000 EACH	_____.	_____.
0122	645.0120 Geotextile Type HR	90.000 SY	_____.	_____.
0124	646.1020 Marking Line Epoxy 4-Inch	26,550.000 LF	_____.	_____.
0126	648.0100 Locating No-Passing Zones	1.700 MI	_____.	_____.

