



Wisconsin Department of Transportation

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

November 8, 2019

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

**Proposal #23: 4992-00-57, WISC 2018 445
C Menasha, CTH LP
USH 10/STH 114 to CTH AP
CTH LP
Calumet County**

Letting of November 13, 2018

This is Addendum No. 1, which provides for the following:

Special Provisions:

Revised Special Provisions	
Article No.	Description
33	Removing Signs Type II
34	Removing Small Sign Supports

Added Special Provisions	
Article No.	Description
56	Notice to Contractor – United States Post Office.

Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
204.0155	Removing Sidewalk	SY	12	94	106
638.2602	Removing Signs Type II	EA	28	33	61
638.3000	Removing Small Sign Supports	EA	29	33	62

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
105	Miscellaneous Quantities – Update Removing Sidewalk
120	Miscellaneous Quantities – Update Removing Signs Type II and Removing Small Sign Supports

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01

4992-00-57

November 8, 2018

Special Provisions

33. Removing Signs Type II.

Replace entire article language with the following:

Replace subsection 638.3.4 (2) and 638.3.4 (3) of the standard specifications with the following:

All signs removed within the project limits will become the property of Calumet County, City of Menasha, or Village of Harrison. Carefully remove sign from their supports, sort by base material, palletize them by material type, and stockpile on the site. The municipality will load the salvaged materials onto their vehicles. Notify the following people three working days prior to pickup of signs:

- Calumet County – Brian Glaeser, Highway Commissioner at 920-849-1463
- City of Menasha – Thad Brown, Public Works Superintendent at 920-967-3620
- Village of Harrison – Bob Kesler, Public Works Director at 920-989-1139

34. Removing Small Sign Supports.

Replace entire article language with the following:

Replace subsection 638.3.5 (2) of the standard specifications with the following:

All sign supports removed within the project limits will become the property of Calumet County, City of Menasha, or Village of Harrison. Carefully remove sign supports, sort by length and type, and stockpile on the east side of the site. The municipality will load the salvaged materials onto their vehicles. Notify the following people three working days prior to pickup of supports:

- Calumet County – Brian Glaeser, Highway Commissioner at 920-849-1463
- City of Menasha – Thad Brown, Public Works Superintendent at 920-967-3620
- Village of Harrison – Bob Kesler, Public Works Director at 920-989-1139

56. Notice to Contractor – United States Post Office.

Contact the United States Post Office at least 14 days before the start of construction to coordinate mail delivery during construction. Access must be maintained for mail delivery. The project area is served by two different post offices. Contact the following people to coordinate.

Neenah Post Office – Brian Smoot at 920-725-0577

Appleton Post Office – Dawn Thiel at 920-993-3057

Schedule of Items

Attached, dated November 8, 2018, are the revised Schedule of Items Pages 1 and 10.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 105 and 120.

END OF ADDENDUM

Addendum No. 01
ID 4992-00-57
Revised Sheet 105
November 8, 2018

CLEARING AND GRUBBING

STATION	TO	STATION	LOCATION	201.0105 CLEARING STA	201.0205 GRUBBING STA	201.0120 CLEARING ID	201.0220 GRUBBING ID
47+00	-	59+00	CTH LP, NB, RT	-	-	170	170
59+00	-	69+00	CTH LP, NB, RT	-	-	110	110
59+00	-	69+00	CTH LP, NB, LT	-	-	80	80
73+00	-	74+00	CTH LP, NB, RT	1	1	-	-
600+00	-	601+00	ETHAN DR, RT	1	1	-	-
496+00	-	499+00	MANITOWOC RD, EB, LT	3	3	-	-
501+00	-	504+00	MANITOWOC RD, EB, LT	3	3	-	-
UNDISTRIBUTED				1	1	40	40
TOTALS				9	9	400	400

REMOVING CURB AND GUTTERS

STATION	TO	STATION	LOCATION	204.0150 LF
20+16	-	20+60	CTH LP, NB, LT	60
21+88	-	22+26	CTH LP, NB, RT	53
21+88	-	22+34	CTH LP, NB, LT	65
47+05	-	62+17	CTH LP, NB, RT	1,513
58+35	-	61+57	CTH LP, NB, LT	322
73+12	-	74+89	CTH LP, NB, LT	167
198+60	-	199+70	SONNY DR, LT	112
198+60	-	199+70	SONNY DR, RT	114
199+14	-	199+50	SONNY DR, MEDIAN	84
200+29	-	201+44	SONNY DR, LT	140
200+29	-	201+44	SONNY DR, RT	142
298+35	-	299+72	VILLA WAY, LT	161
298+35	-	299+72	VILLA WAY, RT	163
300+29	-	301+70	VILLA WAY, LT	166
300+29	-	301+70	VILLA WAY, RT	158
398+35	-	399+72	WINNEPEG ST, LT	160
398+60	-	399+72	WINNEPEG ST, RT	141
498+43	-	499+72	MANITOWOC RD, EB, LT	154
499+44	-	499+84	MANITOWOC RD, EB, RT	55
500+16	-	500+65	MANITOWOC RD, EB, LT	60
500+34	-	500+62	MANITOWOC RD, EB, RT	74
598+25	-	599+75	ETHAN DR, LT	171
598+25	-	599+75	ETHAN DR, RT	178
600+27	-	601+25	ETHAN DR, LT	119
600+27	-	601+25	ETHAN DR, RT	120
TOTAL				4,652

REMOVING SMALL PIPE CULVERTS

STATION	LOCATION	203.0100 EACH
22+23	CTH LP, NB	1
43+01	CTH LP, NB	1
99+63	COMMUNITY WAY	1
200+70	SONNY DR	1
500+42	MANITOWOC RD, EB	1
504+26	MANITOWOC RD, EB	1
599+57	ETHAN DR	1
23+20	CTH LP, NB, LT	1
24+10	CTH LP, NB, RT	1
27+90	CTH LP, NB, RT	1
38+00	CTH LP, NB, RT	1
39+85	CTH LP, NB, RT	1
63+60	CTH LP, NB, RT	1
64+65	CTH LP, NB, LT	1
65+24	CTH LP, NB, RT	1
67+45	CTH LP, NB, LT	1
67+50	CTH LP, NB, RT	1
90+35	CTH LP, NB, LT	1
90+50	CTH LP, NB, RT	1
496+00	MANITOWOC RD, EB, LT	1
503+25	MANITOWOC RD, EB, RT	1
504+35	MANITOWOC RD, EB, RT	1
504+90	MANITOWOC RD, EB, LT	1
TOTAL		23

REMOVING SURFACE DRAINS

STATION	LOCATION	204.0190 SY
95+10	CTH LP, NB, LT	10
TOTAL		10

REMOVING CONCRETE SIDEWALKS

STATION	LOCATION	204.0155 SY
96+09	CTH LP, NB, LT	12
200+29	SONNY DR	82
288+35	VILLA WAY	12
TOTAL		106

REMOVING PAVEMENT

STATION	TO	STATION	LOCATION	204.0100 SY	REMARKS
95+14	-	95+30	CTH LP, NB	68	
95+14	-	96+32	CTH LP, NB, LT	23	
95+14	-	96+42	CTH LP, NB, RT	60	
54+00	-	54+00	CTH LP, NB, RT	34	PE
64+75	-	64+75	CTH LP, NB, LT	13	PE
67+50	-	67+50	CTH LP, NB, LT	23	PE
399+00	-	399+00	WINNEPEG ST, LT	62	PE
TOTAL				283	

REMOVING MANHOLES AND INLETS

STATION	LOCATION	204.0210 REMOVING MANHOLES EA	204.0220 REMOVING INLETS EA
25+82	CTH LP, NB, RT	-	2
30+00	CTH LP, NB, LT	1	-
46+15	CTH LP, NB, LT	1	-
46+65	CTH LP, NB, LT	-	1
46+72	CTH LP, NB, RT	-	1
47+03	CTH LP, NB, RT	-	1
48+16	CTH LP, NB, LT	-	1
51+10	CTH LP, NB, RT	-	1
54+85	CTH LP, NB, RT	-	1
55+30	CTH LP, NB, RT	-	1
56+86	CTH LP, NB, RT	-	1
57+47	CTH LP, NB, LT	-	1
57+99	CTH LP, NB, LT	-	1
59+10	CTH LP, NB, LT	-	1
59+22	CTH LP, NB, LT	1	-
59+75	CTH LP, NB, RT	-	1
61+33	CTH LP, NB, LT	1	-
86+45	CTH LP, NB, RT	1	-
95+15	CTH LP, NB, RT	-	1
TOTALS		5	15

ALL ITEMS ARE CATEGORY 0010 UNLESS OTHERWISE STATED

ERECTOR & REMOVAL OF PERMANENT SIGNING - TYPE II

SIGN NO.	LOCATION	SIGN CODE	W X H	637. 2210 SIGNS TYPE II REFLECTIVE TYPE H S. F.	637. 2230 SIGNS TYPE II REFLECTIVE TYPE F S. F.	634. 0612 POSTS WOOD 4x6x12 EACH	634. 0614 POSTS WOOD 4x6x14 EACH	634. 0616 POSTS WOOD 4x6x16 EACH	638. 2102 MOVING SIGNS TYPE II EACH	638. 2602 REMOVING SIGNS TYPE II EACH	638. 3000 REMOVING SMALL SIGN SUPPORTS EACH	REMARKS
57	N. OF MANI TOWOC ROAD	R1-2	38" X 31"	3.88			1					
57A	"	R1-54	24" X 15"	2.50								MOUNT BELOW SIGN #57
58	"	R1-2	36" X 31"	3.88				1				
58A	"	R6-2R	24" X 30"	5.00								MOUNT BELOW SIGN #58
59	"	D1-62	78" X 15"	8.13		2						SEE SIGN DETAIL
59A	"	R3-17	30" X 24"	5.00			1					
60	"	R2-1								1		
61	"	R2-2	36" X 36"		9.00		1					
62	N. OF MANI TOWOC ROAD	R4-7	24" X 30"	5.00			1					
63	"	R2-1	24" X 30"	5.00			1					35 MPH
63A	"	R3-17	30" X 24"	5.00			1					
64	ETHAN DRIVE	R1-1	30" X 30"	5.18			1			1		
65	PRIVATE ROAD	R1-1	30" X 30"	5.18			1			1		
65A	N. OF ETHAN DRIVE	R3-17	30" X 24"	5.00			1					
66	S. OF CTH AP	R2-1	24" X 30"	5.00			1					35 MPH
67	S. OF CTH AP	R2-1	24" X 30"	5.00			1					35 MPH
68	S. OF CTH AP	W2-6	30" X 30"						1			MOVE 12-2 AND W13-1 ALSO
68A	"	12-2							1			MIDWAY ROAD
68B	"	W13-1	18" X 18"						1			15 MPH
69	"	JV								1		SEE PLAN SHEET
70	"	J1-1	24" X 39"	6.50			1					
71	"	R3-17	30" X 24"	5.00			1					
72	"	J4-1									1	
73	CTH AP, W. OF CTH LP	J1-1									1	
74	CTH AP, E. OF CTH LP	J1-1									1	
	CITY OF MENASHA SIGNS									3	3	CITY LIMIT SIGN & STREET SIGNS
	VILLAGE OF HARRISON SIGNS										30	VILLAGE LIMIT SIGN, FIRE NUMBERS & STREET SIGNS
PAGE SUBTOTALS				80.25	9.00	2	13	1	3	40	40	
PROJECT TOTALS				416.49	70.50	9	58	11	5	61	62	

Addendum No. 01
ID 4992-00-57
Revised Sheet 120
November 8, 2018

ALL ITEMS ARE CATEGORY 0010 UNLESS OTHERWISE STATED



Proposal Schedule of Items

Proposal ID: 20181113023 Project(s): 4992-00-57

Federal ID(s): WISC 2018445

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	201.0105 Clearing	9.000 STA	_____.	_____.
0004	201.0120 Clearing	400.000 ID	_____.	_____.
0006	201.0205 Grubbing	9.000 STA	_____.	_____.
0008	201.0220 Grubbing	400.000 ID	_____.	_____.
0010	203.0100 Removing Small Pipe Culverts	23.000 EACH	_____.	_____.
0012	204.0100 Removing Pavement	283.000 SY	_____.	_____.
0014	204.0150 Removing Curb & Gutter	4,652.000 LF	_____.	_____.
0016	204.0155 Removing Concrete Sidewalk	106.000 SY	_____.	_____.
0018	204.0190 Removing Surface Drains	10.000 EACH	_____.	_____.
0020	204.0195 Removing Concrete Bases	2.000 EACH	_____.	_____.
0022	204.0210 Removing Manholes	5.000 EACH	_____.	_____.
0024	204.0220 Removing Inlets	15.000 EACH	_____.	_____.
0026	204.0245 Removing Storm Sewer (size) 01. 12-Inch or Less	861.000 LF	_____.	_____.
0028	204.0245 Removing Storm Sewer (size) 02. 15-Inch	161.000 LF	_____.	_____.
0030	204.0245 Removing Storm Sewer (size) 03. 18-Inch	5.000 LF	_____.	_____.
0032	204.0245 Removing Storm Sewer (size) 04. 24-Inch	1,330.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20181113023 Project(s): 4992-00-57

Federal ID(s): WISC 2018445

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0280	634.0612 Posts Wood 4x6-Inch X 12-FT	9.000 EACH	_____.	_____.
0282	634.0614 Posts Wood 4x6-Inch X 14-FT	58.000 EACH	_____.	_____.
0284	634.0616 Posts Wood 4x6-Inch X 16-FT	11.000 EACH	_____.	_____.
0286	637.2210 Signs Type II Reflective H	416.490 SF	_____.	_____.
0288	637.2230 Signs Type II Reflective F	70.500 SF	_____.	_____.
0290	638.2102 Moving Signs Type II	5.000 EACH	_____.	_____.
0292	638.2602 Removing Signs Type II	61.000 EACH	_____.	_____.
0294	638.3000 Removing Small Sign Supports	62.000 EACH	_____.	_____.
0296	642.5001 Field Office Type B	1.000 EACH	_____.	_____.
0298	643.0300 Traffic Control Drums	5,640.000 DAY	_____.	_____.
0300	643.0420 Traffic Control Barricades Type III	4,174.000 DAY	_____.	_____.
0302	643.0705 Traffic Control Warning Lights Type A	5,998.000 DAY	_____.	_____.
0304	643.0715 Traffic Control Warning Lights Type C	406.000 DAY	_____.	_____.
0306	643.0800 Traffic Control Arrow Boards	42.000 DAY	_____.	_____.
0308	643.0900 Traffic Control Signs	2,543.000 DAY	_____.	_____.
0310	643.1050 Traffic Control Signs PCMS	98.000 DAY	_____.	_____.
0312	643.1070 Traffic Control Cones 42-Inch	3,960.000 DAY	_____.	_____.

