



Wisconsin Department of Transportation

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

December 6, 2018

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #19: 4140-19-71
Gibraltar – Sister Bay
Bluff Ln - Country Walk Dr
STH 42
Door County

Letting of December 11, 2018

This is Addendum No. 03, which provides for the following:

Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
205.0100	Common Excavation	CY	7,135	-290	6,845

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
220	Miscellaneous Quantities – Common Excavation and Salvaged/Unusable Pavement Material adjusted.
502	Earthwork Quantities – Localized earthwork areas modified.
503	Earthwork Quantities – Localized earthwork areas modified.
504	Earthwork Quantities – Localized earthwork areas modified.
505	Earthwork Quantities – Localized earthwork areas modified.
506	Earthwork Quantities – Localized earthwork areas modified.

Schedule of Items

Attached, dated December 6, 2018, are the revised Schedule of Items Page 2.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 220, 502, 503, 504, 505, and 506.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

END OF ADDENDUM

Division	From/To Station	205.0100 Common Excavation		Salvaged/Unusable Pavement Material (11)	Available Material (12)	205.0200 Rock Excavation	Expanded Rock (13)		Unexpanded Fill	Expanded Fill (14)		Mass Ordinate +/- (15)	Waste	208.0100 Borrow	Comment:
		Cut	EBS Excavation (9)				Factor 1.10	Factor 1.25							
CATG 0010-Division 1	47+31.659+085+32.44	478	---	---	478	---	---	---	268	335	142	142	0		
STH 42 BEAMGUARD		478	---	---	478	---	---	---	268	335	142	142	0		
CATG 0010-Division 1 Subtotal		478	---	---	478	---	---	---	268	335	142	142	0		
CATG 0010-Division 2	19+81.430+20+88.42	38	---	1	37	---	---	175	218	218	-181	---	0		
CURB RETURN - CTH F NORTH		38	---	1	37	---	---	175	218	218	-181	---	0		
CATG 0010-Division 2 Subtotal		38	---	1	37	---	---	175	218	218	-181	---	0		
CATG 0010-Division 3	10+007+11+32.22	43	---	14	29	---	---	64	80	80	-51	---	0		
CURB RETURN - CTH F SOUTH		43	---	14	29	---	---	64	80	80	-51	---	0		
CATG 0010-Division 3 Subtotal		43	---	14	29	---	---	64	80	80	-51	---	0		
CATG 0010-Division 4	00+000+01+61.51	28	---	4	24	---	---	11	14	14	10	10	0		
CURB RETURN - GIBRALTAR RD NORTH		28	---	4	24	---	---	11	14	14	10	10	0		
CATG 0010-Division 4 Subtotal		28	---	4	24	---	---	11	14	14	10	10	0		
CATG 0010-Division 5	10+257+0+76.39	84	---	27	57	---	---	29	36	36	20	20	0		
GIBRALTAR SCHOOL NORTH DRIVEWAY		84	---	27	57	---	---	29	36	36	20	20	0		
CATG 0010-Division 5 Subtotal		84	---	27	57	---	---	29	36	36	20	20	0		
CATG 0010-Division 6	00+01.430+0+82.29	2	---	---	2	---	---	55	68	68	-66	---	0		
GIBRALTAR SCHOOL NORTH PATH		2	---	---	2	---	---	55	68	68	-66	---	0		
CATG 0010-Division 6 Subtotal		2	---	---	2	---	---	55	68	68	-66	---	0		
CATG 0010-Division 7	00+07.330+0+97.85	31	---	10	21	---	---	32	41	41	-20	---	0		
CURB RETURN - GIBRALTAR RD SOUTH		31	---	10	21	---	---	32	41	41	-20	---	0		
CATG 0010-Division 7 Subtotal		31	---	10	21	---	---	32	41	41	-20	---	0		
CATG 0010-Division 8	425+46.59+469+19.96	347	---	---	347	---	---	99	81	81	266	266	0		
STH 42 - OCHARD RD SHOULDER WIDENING		347	---	---	347	---	---	99	81	81	266	266	0		
CATG 0010-Division 8 Subtotal		347	---	---	347	---	---	99	81	81	266	266	0		
CATG 0010-Division 10	97+30+158+55	5,203	---	1,258	3,944	---	---	1,327	1,324	1,324	2,620	2,620	0		
STH 42 - GIBRALTAR		5,203	---	1,258	3,944	---	---	1,327	1,324	1,324	2,620	2,620	0	SEE NOTE 16	
CATG 0010-Division 10 Subtotal		5,203	---	1,258	3,944	---	---	1,327	1,324	1,324	2,620	2,620	0		
CATG 0010-Division 11	144+60+148+30 RT	73	---	27	46	---	---	---	---	---	46	46	0		
GIBBALTAR RD TEMPORARY CONNECTION		73	---	27	46	---	---	---	---	---	46	46	0		
CATG 0010-Division 11 Subtotal		73	---	27	46	---	---	---	---	---	46	46	0		
CATG 0010-Division 12	15+1+33 RT	26	---	---	26	---	---	---	---	---	26	26	0		
FISH CREEK GRILL TEMP DWY		26	---	---	26	---	---	---	---	---	26	26	0		
CATG 0010-Division 12 Subtotal		26	---	---	26	---	---	---	---	---	26	26	0		
CATG 0010-Division 13	370+75+371+00 LT	2	---	---	2	---	---	---	---	---	2	2	0		
EPHRAIM ANDERSON HOUSE		2	---	---	2	---	---	---	---	---	2	2	0		
CATG 0010-Division 13 Subtotal		2	---	---	2	---	---	---	---	---	2	2	0		
CATG 0010 SUBTOTAL		6,354	---	1,342	5,012	192	---	1,970	2,198	2,198	2,814	3,133	0		
CATG 0060-Division 1	10+00+15+12	463	---	59	404	---	---	65	81	81	323	323	81	SEE NOTE 17	
SHORE ROAD		463	---	59	404	---	---	65	81	81	323	323	81	SEE NOTE 17	
CTH F SIDEWALK	0+00+2+24	21	---	1	20	---	---	26	32	32	-12	-12	0	SEE NOTE 18	
SPRING ROAD	0+00+1+04	7	---	7	7	---	---	24	30	30	-23	-23	0	SEE NOTE 18	
CATG 0060 SUBTOTAL		491	---	67	424	---	---	115	143	143	323	323	81		
TOTAL		6,845	---	1,375	5,099	192	---	2,084	2,341	2,341	3,096	3,096	81		

Notes:
(11) Asphalt not removed by milling unsalvageable due to shallow fills.
(12) Available material excludes salvaged/unsalvageable pavement material
(13) Expanded Rock Factor = 1.1
(14) Expanding Fill Factor = 1.25
Depending on selections: Expanded Fill = (Unexpanded Fill - Rock* Rock Factor - Reduced EBS) * Fill Factor
(15) The Mass Ordinate +/- or - City calculated for the Division. Plus quantity indicates an excess of material within the Division. Minus indicates a shortage of material within the Division.
(16) Excavation to proposed subgrade above storm sewer from 125+00 - 154+50 paid under common excavation bid item. All other storm sewer excavation shall be incidental to the storm sewer bid item.
(17) Frost free borrow required due to timeframe of construction.
(18) Use available material from Division 10 and 12.

Addendum No. 03
 ID 4140-19-71
 Revised Sheet 502
 December 6, 2018

STATION	Real Station	Distance	AREA (SF)			Incremental Vol (CY) (Unadjusted)			Expanded Vol (CY)			Cumulative Vol (CY)			Mass Ordinate
			Cut	Salvaged/Unusable Pavement Material	Fill	Marsh Exc	Rock Exc	EBS	Expanded Marsh Backfill	Expanded Rock Backfill	Expanded EBS Backfill	Expanded Marsh Backfill	Expanded Rock Backfill	Expanded EBS Backfill	
10+20	1020.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
10+30	1030.00	10.00	42.06	3.83	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
10+40	1040.00	10.00	48.86	12.27	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
10+50	1050.00	10.00	62.38	13.84	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
11+00	1100.00	50.00	37.86	2.13	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
11+50	1150.00	50.00	38.61	2.24	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
12+00	1200.00	50.00	34.47	2.38	0.22	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
12+25	1225.00	25.00	27.45	2.47	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
12+50	1250.00	25.00	27.45	2.47	1.07	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
12+83.26	1283.26	33.26	16.85	2.54	0.78	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
13+00	1300.00	16.74	16.05	2.59	1.07	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
13+39.65	1339.65	39.65	12.35	2.71	5.20	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
13+62.83	1362.83	23.18	1.21	3.71	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
13+85.71	1385.71	22.88	1.21	3.71	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
14+00	1400.00	14.29	8.82	1.21	12.12	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
14+64.99	1464.99	14.99	9.30	1.46	13.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
15+12	1512.00	47.01	10.36	2.07	7.36	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
463					59	65	0	0	0	0	0	0	0	0	0

STATION	Real Station	Distance	AREA (SF)			Incremental Vol (CY) (Unadjusted)			Expanded Vol (CY)			Cumulative Vol (CY)			Mass Ordinate
			Cut	Salvaged/Unusable Pavement Material	Fill	Marsh Exc	Rock Exc	EBS	Expanded Marsh Backfill	Expanded Rock Backfill	Expanded EBS Backfill	Expanded Marsh Backfill	Expanded Rock Backfill	Expanded EBS Backfill	
99+30 RT	9930.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
99+69 RT	9969.00	39.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
99+70 LT	9970.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
99+69A LT	9969.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
102+66 RT	10266.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
103+21 RT	10321.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
103+26 LT	10326.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
106+36 LT	10636.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
107+91 LT	10791.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
108+12 LT	10812.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
112+71 RT	11271.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
117+54 LT	11754.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
118+74 RT	11874.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
120+00 RT	12000.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
123+00 LT	12300.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
119 - 124			0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
126+28 LT	12628.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
128+62 RT	12862.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
127+00 LT	12700.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
129+26 LT	12926.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
129+67 RT	12967.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
130+57 RT	13057.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
131+38 RT	13138.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
132+13 LT	13213.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
133+57 RT	13357.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
135+12 LT	13512.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
108+71.5	10871.50	0.13	20.59	3.89	1.89	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
108+86.54	10886.54	15.04	17.51	4.72	4.56	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
109+00	10900.00	13.46	22.19	16.45	2.72	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
109+14	10914.00	14.00	21.21	16.47	2.80	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
109+40.86	10940.86	26.86	46.05	15.84	3.51	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
109+50	10950.00	9.14	18.82	3.93	0.69	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
109+61.21	10961.21	31.21	19.94	3.89	0.16	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
109+81.55	10981.55	0.34	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
125+27.41	12527.41	1545.87	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
125+50	12550.00	22.59	9.66	1.34	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
126+42.89	12642.89	42.89	27.22	1.28	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
126+50	12650.00	7.11	16.56	5.08	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
126+60	12660.00	10.00	3.83	1.29	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

Continued

Addendum No. 03
 ID 4140-19-71
 Revised Sheet 506
 December 6, 2018

STATION	Real Station	Distance	Salvage/Diversion		AREA (SF)		Incremental Vol (CY) (Unadjusted)			Expanded			Cumulative Vol (CY)			Revised Marsh In Fill	Revised EBS In Fill	Mass Ordinate				
			Cut	Fill	Marsh	Exc	Rock	Exc	EBS	Exc	Exc	Exc	Exc	Exc	Exc				Exc	Exc		
152+73.26	15273.26	7.93	42.44	12.33	59.27	0.00	0.00	0.00	0.00	4	15	0	0	0	1.00	1.00	1.10	1.30	0	0	0	2.265
152+78.17	15278.17	4.90	42.09	12.55	48.70	0.00	0.00	0.00	0.00	2	9	0	0	0	4.386	4.386	1.17	0	0	0	0	2.265
152+82.89	15282.89	11.73	40.32	13.81	34.37	0.00	0.00	0.00	0.00	6	18	0	0	0	4.406	4.406	1.17	0	0	0	0	2.245
152+89.07	15289.07	0.17	30.81	7.85	13.33	0.00	0.00	0.00	0.00	0	0	0	0	0	4.406	4.406	1.17	0	0	0	0	2.245
153+00.00	15300.00	0.83	28.84	6.50	4.14	0.00	0.00	0.00	0.00	1	3	0	0	0	1.042	1.042	1.17	0	0	0	0	2.245
153+04.00	15304.00	1.66	33.46	6.50	0.00	0.00	0.00	0.00	0.00	0	0	0	0	0	4.417	4.417	1.17	0	0	0	0	2.245
153+09.00	15309.00	4.96	33.46	6.50	0.00	0.00	0.00	0.00	0.00	12	4	0	0	0	4.475	4.475	1.17	0	0	0	0	2.260
153+14.00	15314.00	5.81	38.04	6.50	0.00	0.00	0.00	0.00	0.00	6	0	0	0	0	4.506	4.506	1.17	0	0	0	0	2.316
153+19.00	15319.00	10.66	38.04	6.50	0.00	0.00	0.00	0.00	0.00	39	0	0	0	0	4.545	4.545	1.17	0	0	0	0	2.348
154+00.00	15400.00	26.51	41.67	6.50	0.00	0.00	0.00	0.00	0.00	14	0	0	0	0	4.559	4.559	1.17	0	0	0	0	2.381
154+05.00	15405.00	31.41	20.78	0.00	0.00	0.00	0.00	0.00	0.00	15	0	0	0	0	4.574	4.574	1.17	0	0	0	0	2.381
154+10.00	15410.00	36.31	44.89	6.50	0.00	0.00	0.00	0.00	0.00	0	0	0	0	0	4.575	4.575	1.17	0	0	0	0	2.375
154+15.00	15415.00	41.21	44.89	6.50	14.27	0.00	0.00	0.00	0.00	0	0	0	0	0	4.607	4.607	1.17	0	0	0	0	2.388
154+20.00	15420.00	46.11	42.90	5.22	21.33	0.00	0.00	0.00	0.00	4	13	0	0	0	4.635	4.635	1.17	0	0	0	0	2.393
154+25.00	15425.00	51.01	33.59	4.45	22.32	0.00	0.00	0.00	0.00	28	4	0	0	0	4.642	4.642	1.17	0	0	0	0	2.393
154+30.00	15430.00	55.91	35.32	5.97	22.92	0.00	0.00	0.00	0.00	1	4	0	0	0	4.643	4.643	1.17	0	0	0	0	2.393
154+35.00	15435.00	60.81	38.34	5.94	23.04	0.00	0.00	0.00	0.00	1	0	0	0	0	4.643	4.643	1.17	0	0	0	0	2.393
154+40.00	15440.00	65.71	32.57	5.06	27.72	0.00	0.00	0.00	0.00	4	19	0	0	0	4.674	4.674	1.17	0	0	0	0	2.381
154+45.00	15445.00	70.61	29.70	4.02	31.07	0.00	0.00	0.00	0.00	26	54	0	0	0	4.732	4.732	1.17	0	0	0	0	2.375
154+50.00	15450.00	75.51	39.58	4.07	25.15	0.00	0.00	0.00	0.00	8	42	0	0	0	4.763	4.763	1.17	0	0	0	0	2.366
154+55.00	15455.00	80.41	43.27	4.10	23.29	0.00	0.00	0.00	0.00	2	9	0	0	0	4.789	4.789	1.17	0	0	0	0	2.366
154+60.00	15460.00	85.31	45.79	4.12	21.40	0.00	0.00	0.00	0.00	18	8	0	0	0	4.815	4.815	1.17	0	0	0	0	2.375
154+65.00	15465.00	90.21	45.79	4.12	21.40	0.00	0.00	0.00	0.00	2	8	0	0	0	4.815	4.815	1.17	0	0	0	0	2.375
154+70.00	15470.00	95.11	51.92	6.15	21.41	0.00	0.00	0.00	0.00	1	0	0	0	0	4.831	4.831	1.17	0	0	0	0	2.375
154+75.00	15475.00	100.01	69.17	17.15	17.32	0.00	0.00	0.00	0.00	19	21	0	0	0	4.897	4.897	1.17	0	0	0	0	2.375
154+80.00	15480.00	104.91	76.53	17.15	8.79	0.00	0.00	0.00	0.00	7	5	0	0	0	4.925	4.925	1.17	0	0	0	0	2.413
154+85.00	15485.00	109.81	63.87	17.16	0.00	0.00	0.00	0.00	0.00	5	1	0	0	0	4.946	4.946	1.17	0	0	0	0	2.427
154+90.00	15490.00	114.71	67.72	17.21	0.14	0.00	0.00	0.00	0.00	5	0	0	0	0	4.963	4.963	1.17	0	0	0	0	2.427
154+95.00	15495.00	119.61	55.38	17.17	1.23	0.00	0.00	0.00	0.00	5	2	0	0	0	4.970	4.970	1.17	0	0	0	0	2.441
155+00.00	15500.00	124.51	55.38	17.18	0.00	0.00	0.00	0.00	0.00	10	0	0	0	0	4.990	4.990	1.17	0	0	0	0	2.441
155+05.00	15505.00	129.41	55.27	17.18	0.00	0.00	0.00	0.00	0.00	5	0	0	0	0	4.992	4.992	1.17	0	0	0	0	2.454
155+10.00	15510.00	134.31	69.75	17.18	0.00	0.00	0.00	0.00	0.00	1	0	0	0	0	5.017	5.017	1.17	0	0	0	0	2.454
155+15.00	15515.00	139.21	68.85	17.20	0.05	0.00	0.00	0.00	0.00	6	0	0	0	0	5.017	5.017	1.17	0	0	0	0	2.488
155+20.00	15520.00	144.11	87.72	17.21	0.14	0.00	0.00	0.00	0.00	5	0	0	0	0	5.039	5.039	1.17	0	0	0	0	2.488
155+25.00	15525.00	149.01	68.85	17.21	0.14	0.00	0.00	0.00	0.00	6	0	0	0	0	5.039	5.039	1.17	0	0	0	0	2.488
155+30.00	15530.00	153.91	32.89	4.26	0.91	0.00	0.00	0.00	0.00	6	1	0	0	0	5.094	5.094	1.17	0	0	0	0	2.537
155+35.00	15535.00	158.81	28.51	4.29	1.52	0.00	0.00	0.00	0.00	5	1	0	0	0	5.129	5.129	1.17	0	0	0	0	2.565
155+40.00	15540.00	163.71	26.87	4.31	1.22	0.00	0.00	0.00	0.00	3	1	0	0	0	5.148	5.148	1.17	0	0	0	0	2.581
155+45.00	15545.00	168.61	4.31	4.37	2.85	0.00	0.00	0.00	0.00	8	4	0	0	0	5.197	5.197	1.17	0	0	0	0	2.616
155+50.00	15550.00	173.51	25.44	4.37	2.98	0.00	0.00	0.00	0.00	3	0	0	0	0	5.200	5.200	1.17	0	0	0	0	2.616
155+55.00	15555.00	178.41	25.44	4.37	3.04	0.00	0.00	0.00	0.00	1	0	0	0	0	5.202	5.202	1.17	0	0	0	0	2.616
155+60.00	15560.00	183.31	25.46	4.37	3.04	0.00	0.00	0.00	0.00	0	1,237	0	0	0	5.203	5.203	1.17	0	0	0	0	2.616

5,203

1,269

PROJECT NO: 4140-19-71

HWY: STH 42

COUNTY: DOOR

EARTHWORK QUANTITIES

PLOT NAME:

PLOT SCALE: 1:1

SHEET: 506

E



Proposal Schedule of Items

Proposal ID: 20181211019 Project(s): 4140-19-71

Federal ID(s): N/A

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0034	204.0245 Removing Storm Sewer (size) 01. 12-Inch	1,109.000 LF	_____.	_____.
0036	204.0245 Removing Storm Sewer (size) 02. 15-Inch	954.000 LF	_____.	_____.
0038	204.0245 Removing Storm Sewer (size) 03. 18-Inch	120.000 LF	_____.	_____.
0040	204.0245 Removing Storm Sewer (size) 04. 24-Inch	558.000 LF	_____.	_____.
0042	204.0245 Removing Storm Sewer (size) 05. 30-Inch	246.000 LF	_____.	_____.
0044	204.0245 Removing Storm Sewer (size) 06. 36-Inch	67.000 LF	_____.	_____.
0046	204.0280 Sealing Pipes	3.000 EACH	_____.	_____.
0048	204.0291.S Abandoning Sewer	3.000 CY	_____.	_____.
0050	204.9001.S Removing Advance Flasher Assemblies Type 1	2.000 EACH	_____.	_____.
0052	204.9002.S Removing Advance Flasher Assemblies Type 2	2.000 EACH	_____.	_____.
0054	204.9090.S Removing (item description) 01. Cables or Conduit	5,628.000 LF	_____.	_____.
0056	205.0100 Excavation Common	6,845.000 CY	_____.	_____.
0058	205.0200 Excavation Rock	192.000 CY	_____.	_____.
0060	205.1300 Presplitting Rock	199.000 LF	_____.	_____.

