

January 25, 2021

Wisconsin Department of Transportation

Division of Transportation Systems Development

Bureau of Project Development 4822 Madison Yards Way, 4th Floor South Madison, WI 53705

Telephone: (608) 266-1631 Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #31: 7831-07-70, WISC 2021 187 CTH AF – STH 27 Bridge Creek Bridge B-18-0238 CTH V Eau Claire County

Letting of February 9, 2021

This is Addendum No. 01, which provides for the following:

Special Provisions:

	Added Special Provisions								
Article	Description								
No.	Description								
16	Seismograph, Item 999.1000.S								
17	Crack and Damage Survey, Item 999.1500.S								

Schedule of Items:

Revised Bid Item Quantities											
Bid Item	Item Description	Unit	Old	Revised	Proposal						
Did item	nem Description		Quantity	Quantity	Total						
643.0420	Traffic Control Barricades Type III	DAY	1,425	665	2,090						
643.0705	Traffic Control Warning Lights Type A	DAY	2,250	1,050	3,300						
643.0900	Traffic Control Signs	DAY	8,475	3,955	12,430						

Added Bid Item Quantities											
Bid Item	Item Description	Unit	Old	Revised	Proposal						
	nem Description		Quantity	Quantity	Total						
511.1200	Temporary Shoring 01. B-18-238	SF	-	390	390						
999.1000.S	Seismograph	LS	-	1	1						
999.1500.S	Crack and Damage Survey	LS	-	1	1						

Plan Sheets:

	Revised Plan Sheets										
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)										
15	Miscellaneous Quantities: Revised traffic control quantities										
46	Structure B-18-238 General Plan: Added Temporary Shoring to Plan View										
48	Structure B-18-238 Quantities, Notes and Details Plan: Added Temporary Shoring, Seismograph, and Crack and Damage Survey to quantities table										

Other

Revise Contract Completion Time from 40 working days to 60 working days (an increase of 20 working days).

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist Proposal Management Section

ADDENDUM NO. 01 7831-07-70 January 25, 2021

Special Provisions

16. Seismograph, Item 999.1000.S.

A Description

This special provision describes furnishing seismographs and employing trained operators to monitor construction-induced vibrations on buildings/structures, and submittal of all required documentation.

B Material

Use seismographs conforming to Wisconsin Department of Safety and Professional Services (SPS) 307.43, Wisconsin Administrative Code that are continuous data recorders supplied with all the accessories necessary for making vibration and noise monitoring observations.

C Construction

Conduct monitoring procedures conforming to SPS 307.44 and as follows: Take seismograph readings before construction activities to establish an ambient or background index.

During construction, place seismographs to monitor all vibration-inducing construction activities or as the engineer directs. At a minimum utilize one seismograph. If more than one major construction activity per day is taking place, multiple seismographs may be required. Place seismographs on a stable surface within 3 feet of the building/structure nearest to the construction operation. Provide data recorded for each vibration occurrence to the engineer which includes the following:

- 1. Identification of vibration monitoring instrument used.
- 2. Description of equipment used by the contractor.
- 3. Name of qualified observer and interpreter.
- 4. Distance and direction of recording station from the vibration area.
- 5. Type of ground at recording station and material on which the instrument is sitting.
- 6. Peak particle velocity and principal frequency in each component.
- 7. A dated and signed copy of records of seismograph readings.
- 8. A comparison of measured seismograph readings to maximum allowable readings identified in SPS 307.43 or as specified in this special provision.

If construction activities generate ground vibration in excess of the peak particle velocity limits as shown in SPS 307.44, stop the construction operation in progress and implement alternate construction methods to produce results within the allowable peak particle velocity limits.

D Measurement

The department will measure Seismograph as a single complete lump sum unit of work, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNI
999.1000.S	Seismograph	LS

Payment is full compensation for furnishing and operating seismographs, operators, and for producing documentation reports

stp-999-005 (20161130)

17. Crack and Damage Survey, Item 999.1500.S.

A Description

This special provision describes conducting a crack and damage survey of the residences and business located at E18855 County Road V.

This Crack and Damage Survey shall consist of two parts. The first part, performed before construction activities, shall include a visual inspection, digital images, and a written report describing the existing defects in the building(s) being inspected. The second part, performed after the construction activities, shall also include a visual inspection, digital images, and written report describing any change in the building's condition.

B (Vacant)

C Construction

Before any construction activities, thoroughly inspect the building structures for existing defects, including interior and exterior walls. Electronically submit a written report with the inspector's name, date of inspection, descriptions and locations of defects, and digital images. The intent of the written report and digital images is to procure a record of the general physical condition of the building's interior and exterior walls and foundation.

Use a digital camera capable of producing sharp, grain free, high-contrast colored digital images with good shadow details. Label each digital image with the following information:

ID:	<u>7831-07-70</u>
Building Location:	
View looking:	
Date:	
Photographer:	

Before the start of any construction activities related to this survey, submit a copy of the written report and digital images to the engineer electronically.

After the construction activities are complete, conduct another survey in the same manner, take digital images, and submit another written report to the engineer electronically.

Instead of digital images, a digital video camera capable of producing sharp, high contrast, colored digital video with good shadow detail may be used to perform this work.

D Measurement

The department will measure Crack and Damage Survey as single complete lump sum unit of work, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBE	R DESCRIPTION	UNIT
999.1500.S	Crack and Damage Survey	LS

Payment is full compensation for providing the before and after written reports, and for photographs or video.

stp-999-010 (20170615)

Schedule of Items


Attached, dated January 25, 2021, are the revised Schedule of Items Pages 1 - 6.


Plan Sheets

The following $8\frac{1}{2} \times 11$ -inch sheets are attached and made part of the plans for this proposal: Revised: 15, 46, and 48.

END OF ADDENDUM

	HECKS	628.7504		20 20	50																F	D Re	78 vis	31 sed	-0 I S	7-7 She	lo. 70 et 7 202	15		ALL QUANTITIES CATEGORY 0010 UNLESS OTHERWISE NOTED	
	TEMPORARY DITCH CHECKS	9		UNDISTRIBUTED	TOTAL																									JANTITIES CATEGORY 0010	
										SIGNAGE TYPE	W5-52R	W5-52L	W5-52L	W5-52R	W5-52R	W5-52L	W5-52R	W5-52R			ſ	643.0900	SIGNS		NO. DAY	15 1,650 \checkmark	98 10,780			ALL QL	
	628.7020	INLET	PROTECTION TYPE D	EACH		2		638.3000	REMOVING SMALL SIGN	SUPPORTS EACH	:	:	1	1	1	1	:	:	4			643.0705	WARNING LIGHTS	ТҮРЕА	DAY	3,300	1	3 200			
INLET PROTECTION	628	Z	TVI		RT RT	TOTAL		638.2602	REMOVING SIGNS TYPE II	EACH	:	1	1	1	1	1	:	:	4	DLITEMS			BARRICADES WAI	'PEIII	DAY NO.	2,090 30	:	0 Dan		PPROVAL	
INLE				STATION LOCATION	10+90 11+00		SIGNAGE	637.2230	SIGNS TYPE II REFLECTIVE F	SF	£	ŝ	1	I	I	ł	m	m	12	TRAFFIC CONTROL ITEMS		64		z	DAYS NO.	110 19			1	TO ENGINEER AF	
								634.0612	POSTS WOOD 4X6-INCH X 12-FT	EACH	1	1	:	1	ł	ł	1	1	4		<u>-</u>					S AND SIGNS	USUKES LAN			TRAFFIC CONTROL PLACEMENT SUBJECT TO ENGINEER APPROVAL	
									7	LOCATION	RT	LT	LT	RT	LT	RT		RT							LOCATION	PER SDD "BARRICADES AND SIGNS	PER DETOUR PLAN	TOTALS	5	IC CONTROL PLA	
<u>IN ITEMS</u>	628.1910	EMERGENCY	EROSION	CONTROL	4	4				STATION	9+15	9+17	9+29	9+29	10+71	10+71	10+83	10+84	TOTALS							PERS	L	. - -		IRAFF	
EROSION CONTROL MOBILIZATION ITEMS		MUBILIZATIUNS IV EROSION			4	4															ں		r	٦		r	r	r)		
EROSION CONT) J	MUE		NOLEVIOL	ID 7831-07-70	TOTALS																									
				r,	i																										





\$PATE \$PATE 8



	Proposal Schedule of Items	Page 1 of 6
Proposal ID: 2021020	09031 Project(s): 7831-07-70	
	Federal ID(s): WISC 2021187	
SECTION: 0001	Contract Items	
Alt Set ID:	Alt Mbr ID:	

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	201.0105 Clearing	2.000 STA	i	
0004	201.0205 Grubbing	2.000 STA		
0006	203.0600.S Removing Old Structure Over Waterway With Minimal Debris (station) 01. 10+01	LS	LUMP SUM	·
0008	204.0165 Removing Guardrail	150.000 LF		
0010	205.0100 Excavation Common	137.000 CY		·
0012	206.1000 Excavation for Structures Bridges (structure) 01. B-18-238	LS	LUMP SUM	
0014	210.1500 Backfill Structure Type A	770.000 TON	i	·
0016	213.0100 Finishing Roadway (project) 01. 7831- 07-70	1.000 EACH		
0018	305.0110 Base Aggregate Dense 3/4-Inch	10.000 TON	i	i
0020	305.0120 Base Aggregate Dense 1 1/4-Inch	190.000 TON	·	i
0022	455.0605 Tack Coat	21.000 GAL		·
0024	465.0105 Asphaltic Surface	80.000 TON	·	i
0026	502.0100 Concrete Masonry Bridges	354.000 CY	i	
0028	502.3200 Protective Surface Treatment	525.000 SY	ii	·
0030	502.3210 Pigmented Surface Sealer	85.000 SY	<u>.</u>	·
0032	503.0172 Prestressed Girder Type I 72W-Inch	484.000 LF		



	Proposal Schedule of Items	Page 2 of 6
Proposal ID: 2021020	09031 Project(s): 7831-07-70	
	Federal ID(s): WISC 2021187	
SECTION: 0001	Contract Items	
Alt Set ID:	Alt Mbr ID:	

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0034	505.0400 Bar Steel Reinforcement HS Structures	6,860.000 LB		
0036	505.0600 Bar Steel Reinforcement HS Coated Structures	46,710.000 LB	·	
0038	506.2605 Bearing Pads Elastomeric Non- Laminated	8.000 EACH	·	;
0040	506.4000 Steel Diaphragms (structure) 01. B-18- 238	6.000 EACH		·
0042	513.2001 Railing Pipe	22.000 LF	<u> </u>	
0044	513.7084 Railing Steel Type NY4	168.000 LF		
0046	516.0500 Rubberized Membrane Waterproofing	27.000 SY		<u>.</u>
0048	517.1015.S Concrete Staining Multi-Color (structure) 01. B-18-238	235.000 SF		·
0050	517.1050.S Architectural Surface Treatment (structure) 01. B-18-238	235.000 SF		<u> </u>
0052	520.1018 Apron Endwalls for Culvert Pipe 18-Inch	1.000 EACH		
0054	550.0020 Pre-Boring Rock or Consolidated Materials	240.000 LF		;
0056	550.1100 Piling Steel HP 10-Inch X 42 Lb	290.000 LF		
0058	601.0411 Concrete Curb & Gutter 30-Inch Type D	159.000 LF	<u>.</u>	
0060	602.0405 Concrete Sidewalk 4-Inch	264.000 SF		
0062	606.0300 Riprap Heavy	100.000 CY		



	Proposal Schedule of Items	Page 3 of 6
Proposal ID: 2021020	9031 Project(s): 7831-07-70	
	Federal ID(s): WISC 2021187	
SECTION: 0001	Contract Items	
Alt Set ID:	Alt Mbr ID:	

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0064	608.3012 Storm Sewer Pipe Class III-A 12-Inch	10.000 LF		
0066	608.3018 Storm Sewer Pipe Class III-A 18-Inch	74.000 LF		
0068	611.0530 Manhole Covers Type J	1.000 EACH		
0070	611.0624 Inlet Covers Type H	2.000 EACH		
0072	611.2004 Manholes 4-FT Diameter	1.000 EACH		
0074	611.3230 Inlets 2x3-FT	2.000 EACH		
0076	612.0406 Pipe Underdrain Wrapped 6-Inch	165.000 LF		
0078	614.0115 Anchorages for Steel Plate Beam Guard Type 2	1.000 EACH		<u> </u>
0080	614.0150 Anchor Assemblies for Steel Plate Beam Guard	2.000 EACH	·	
0082	614.0305 Steel Plate Beam Guard Class A	62.500 LF		
0084	618.0100 Maintenance And Repair of Haul Roads (project) 01. 7831-07-70	1.000 EACH	·	·
0086	619.1000 Mobilization	1.000 EACH		
0088	624.0100 Water	8.000 MGAL	i	ii
0090	625.0100 Topsoil	100.000 SY		
0092	627.0200 Mulching	105.000 SY		
0094	628.1504 Silt Fence	440.000 LF		



	Proposal Schedule of Items	Page 4 of 6
Proposal ID: 2021020	9031 Project(s): 7831-07-70	
	Federal ID(s): WISC 2021187	
SECTION: 0001	Contract Items	
Alt Set ID:	Alt Mbr ID:	

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0096	628.1520 Silt Fence Maintenance	880.000 LF	i	·
0098	628.1905 Mobilizations Erosion Control	4.000 EACH		
0100	628.1910 Mobilizations Emergency Erosion Control	4.000 EACH		
0102	628.2027 Erosion Mat Class II Type C	65.000 SY		
0104	628.7020 Inlet Protection Type D	2.000 EACH		
0106	628.7504 Temporary Ditch Checks	50.000 LF		
0108	629.0210 Fertilizer Type B	0.100 CWT		·
0110	630.0120 Seeding Mixture No. 20	5.000 LB		
0112	630.0200 Seeding Temporary	5.000 LB		·
0114	630.0500 Seed Water	4.000 MGAL		
0116	634.0612 Posts Wood 4x6-Inch X 12-FT	4.000 EACH		
0118	637.2230 Signs Type II Reflective F	12.000 SF		
0120	638.2602 Removing Signs Type II	4.000 EACH		
0122	638.3000 Removing Small Sign Supports	4.000 EACH		
0124	642.5001 Field Office Type B	1.000 EACH		
0126	643.0420 Traffic Control Barricades Type III	2,090.000 DAY		
0128	643.0705 Traffic Control Warning Lights Type A	3,300.000 DAY		



	Proposal Schedule of Items	Page 5 of 6
Proposal ID: 2021020	99031 Project(s): 7831-07-70	
	Federal ID(s): WISC 2021187	
SECTION: 0001	Contract Items	
Alt Set ID:	Alt Mbr ID:	

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0130	643.0900 Traffic Control Signs	12,430.000 DAY	·	
0132	643.5000 Traffic Control	1.000 EACH		
0134	645.0111 Geotextile Type DF Schedule A	60.000 SY		
0136	645.0120 Geotextile Type HR	255.000 SY		
0138	646.1020 Marking Line Epoxy 4-Inch	940.000 LF		
0140	650.4000 Construction Staking Storm Sewer	4.000 EACH		
0142	650.4500 Construction Staking Subgrade	100.000 LF		
0144	650.5000 Construction Staking Base	100.000 LF	<u>.</u>	
0146	650.5500 Construction Staking Curb Gutter and Curb & Gutter	264.000 LF	·	
0148	650.6500 Construction Staking Structure Layout (structure) 01. B-18-238	LS	LUMP SUM	
0150	650.9910 Construction Staking Supplemental Control (project) 01. 7831-07-70	LS	LUMP SUM	. <u></u>
0152	650.9920 Construction Staking Slope Stakes	100.000 LF	·	i
0154	690.0150 Sawing Asphalt	64.000 LF		<u>.</u>
0156	715.0502 Incentive Strength Concrete Structures	2,124.000 DOL	1.00000	2,124.00
0158	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	300.000 HRS	5.00000	1,500.00



Proposal Schedule of Items		Page 6 of 6
Proposal ID: 2021020	9031 Project(s): 7831-07-70	
	Federal ID(s): WISC 2021187	
SECTION: 0001	Contract Items	
Alt Set ID:	Alt Mbr ID:	

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0160	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	300.000 HRS	5.00000	1,500.00
0162	511.1200 Temporary Shoring (structure) 01. B-18- 238	390.000 SF		·
0164	999.1000.S Seismograph	LS	LUMP SUM	
0166	999.1500.S Crack and Damage Survey	LS	LUMP SUM	·
	Section: 00	01	Total: Total Bid:	·