



Wisconsin Department of Transportation

September 3, 2021

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #15: 1590-18-61
Monico – Laona
Oneida County Line to Boulevard Ave
USH 8
Forest County

1590-18-62
Monico – Laona
Wolf & Peshtigo Bridges B-21-1,10
USH 8
Forest County

Letting of September 14, 2021

This is Addendum No. 01, which provides for the following:

Plan Sheets:

Revised Plan Sheets – 1590-18-61	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
26	Miscellaneous Quantity chart had information cut off

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

END OF ADDENDUM

643-TRAFFIC CONTROL

CATEGORY	STATION	TO	STATION	LOCATION	USAGE	DURATION DAYS**	CULVERT WORK EACH	TRAFFIC CONTROL DELUIMS		TRAFFIC CONTROL SIGNS		REMARKS
								EACH**	DAY	FIXED MESSAGE SF	DAY	
0010	20+00	-	369+82	USH 8 (PROJECT)	---	---	---	---	---	---	0.4	
0010	---	---	---	W PROJECT LIMITS	ADVANCED WARNING	65	---	---	---	325	18	PLACE G20-57 SIGN 7 DAYS PRIOR TO START OF CONSTRUCTION
0010	---	---	---	E PROJECT LIMITS	ADVANCED WARNING	65	---	---	---	325	18	PLACE G20-57 SIGN 7 DAYS PRIOR TO START OF CONSTRUCTION
0010	---	---	---	SIDE ROADS	ADVANCED WARNING	65	---	---	---	780	---	
0010	---	---	---	ROADWAY	INTERMEDIATE SIGNING	65	---	---	---	260	---	
0010	---	---	---	BEAMGUARD WORK	SHOULDER CLOSURES	8	54	432	9	72	---	G20-1 SIGNS
0010	---	---	---	CULVERTS	CULVERT WORK	6	28	168	8	48	---	
0010	---	---	---	CULVERTS	CULVERT REPLACEMENTS	6	4	342	8	48	---	
0010	---	---	---	ROADWAY	MILLED SURFACE	15	---	---	---	450	---	CONSTRUCTION DETAIL
							TOTAL 0010	4	942	2,308	36	0.4

**INFORMATION ONLY

Addendum No. 01
ID 1590-18-61
Revised Sheet 26
September 3, 2021

646-PAVEMENT MARKING

CATEGORY	STATION	TO	STATION	LOCATION	MARKING LINE EPOXY 4-INCH LF	GROOVED WET REF EPOXY 4- INCH LF	GROOVED WET MARKING LINE REF EPOXY 8- INCH LF	MARKING LINE SAME DAY EPOXY 4-INCH LF	LOCATING NO- PASSING ZONES MI	TEMPORARY MARKING LINE	
										PAINT 4-INCH LF	EPOXY 4-INCH LF
0010	20+00	-	91+36.76	USH 8	1,820	14,090	---	---	1.35	3,630	1,820
0010	91+36.76	-	277+00	USH 8	12,320	36,490	240	---	3.52	24,640	12,320
0010	277+00	-	322+96	USH 8	1,630	8,990	---	---	0.87	3,260	1,630
0010	322+96	-	336+14.58	USH 8	---	2,550	---	350	0.25	700	---
0010	336+14.58	-	369+82	USH 8	---	6,480	---	840	---	1,680	---
TOTAL 0010					15,770	88,600	240	1,190	5.99	33,910	15,770

NOTES:
 - TEMPORARY PAVEMENT MARKING PAINT 4-INCH FOR CENTERLINE APPLIED TO MILLED SURFACE AND TO TAPERED JOINT IN THE HMA PAVEMENT PASS #1, IF REQUIRED.
 - TEMPORARY PAVEMENT MARKING EPOXY 4-INCH FOR CENTERLINE APPLIED TO FINAL SURFACE BEFORE CENTERLINE RUMBLE STRIPS PLACED.
 - PAVEMENT MARKING EPOXY 4-INCH FOR FINAL CENTERLINE APPLICATION AFTER CENTERLINE RUMBLE STRIPS PLACED.
 - MARKING LINE SAME DAY EPOXY 4-INCH FOR FINAL CENTERLINE APPLICATION WHERE NO CENTERLINE RUMBLE STRIPS ARE TO BE PLACED.

*ADDITIONAL QUANTITIES SHOWN ELSEWHERE