# HIGHWAY WORK PROPOSAL

Wisconsin Department of Transportation DT1502 01/2020 s.66.0901(7) Wis. Stats

COUNTY STATE PROJECT FEDERAL PROJECT DESCRIPTION <u>HIGHWAY</u> Dane 5728-00-73 N/A Town Of Perry, Drammen Vallery Rd; LOC STR Pleasant Valley Br Bridge, B-13-0691

# ADDENDUM REQUIRED ATTACHED AT BACK

This proposal, submitted by the undersigned bidder to the Wisconsin Department of Transportation, is in accordance with the advertised request for proposals. The bidder is to furnish and deliver all materials, and to perform all work for the improvement of the designated project in the time specified, in accordance with the appended Proposal Requirements and Conditions.

Proposal Guaranty Required: \$20,000.00 Payable to: Wisconsin Department of Transportation	Attach Proposal Guaranty on back of this PAGE.
Bid Submittal	Firm Name, Address, City, State, Zip Code
Date: December 14, 2021 Time (Local Time): 11:00 am	SAMPLE
Contract Completion Time	NOT FOR BIDDING PURPOSES
25 Working Days 40 Working Days	
Assigned Disadvantaged Business Enterprise Goal 0%	This contract is exempt from federal oversight.

This certifies that the undersigned bidder, duly sworn, is an authorized representative of the firm named above; that the bidder has examined and carefully prepared the bid from the plans, Highway Work Proposal, and all addenda, and has checked the same in detail before submitting this proposal or bid; and that the bidder or agents, officer, or employees have not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with this proposal bid.

Do not sign, notarize, or submit this Highway Work Proposal when submitting an electronic bid on the Internet.

Subscribed and sworn to before me this date \_\_\_\_

(Signature, Notary Public, State of Wisconsin)

(Print or Type Name, Notary Public, State Wisconsin)

(Date Commission Expires)

Notary Seal

Type of Work:

For Department Use Only

Excavation Common, Backfill Structure, Base Aggregate Dense, Select Crushed Material, Concrete Masnry Bridges, HS Bar Steel Reinforcement, HS Bar Steel Reinforcement Coated, Piling Steel HP 10 inch, HMA Pavement, Tack Coat, Construction Staking, Signs

Notice of Award Dated

Date Guaranty Returned

017 Proposal Number:

(Bidder Signature)

(Print or Type Bidder Name)

(Bidder Title)

# PLEASE ATTACH PROPOSAL GUARANTY HERE

# Effective with November 2007 Letting

# PROPOSAL REQUIREMENTS AND CONDITIONS

The bidder, signing and submitting this proposal, agrees and declares as a condition thereof, to be bound by the following conditions and requirements.

If the bidder has a corporate relationship with the proposal design engineering company, the bidder declares that it did not obtain any facts, data, or other information related to this proposal from the design engineering company that was not available to all bidders.

The bidder declares that they have carefully examined the site of, and the proposal, plans, specifications and contract forms for the work contemplated, and it is assumed that the bidder has investigated and is satisfied as to the conditions to be encountered, as to the character, quality, and quantities of work to be performed and materials to be furnished, and as to the requirements of the specifications, special provisions and contract. It is mutually agreed that submission of a proposal shall be considered conclusive evidence that the bidder has made such examination.

The bidder submits herewith a proposal guaranty in proper form and amount payable to the party as designated in the advertisement inviting proposals, to be retained by and become the property of the owner of the work in the event the undersigned shall fail to execute the contract and contract bond and return the same to the office of the engineer within fourteen (14) days after having been notified in writing to do so; otherwise to be returned.

The bidder declares that they understand that the estimate of quantities in the attached schedule is approximate only and that the attached quantities may be greater or less in accordance with the specifications.

The bidder agrees to perform the said work, for and in consideration of the payment of the amount becoming due on account of work performed, according to the unit prices bid in the following schedule, and to accept such amounts in full payment of said work.

The bidder declares that all of the said work will be performed at their own proper cost and expense, that they will furnish all necessary materials, labor, tools, machinery, apparatus, and other means of construction in the manner provided in the applicable specifications and the approved plans for the work together with all standard and special designs that may be designed on such plans, and the special provisions in the contract of which this proposal will become a part, if and when accepted. The bidder further agrees that the applicable specifications and all plans and working drawings are made a part hereof, as fully and completely as if attached hereto.

The bidder, if awarded the contract, agrees to begin the work not later than ten (10) days after the date of written notification from the engineer to do so, unless otherwise stipulated in the special provisions.

The bidder declares that if they are awarded the contract, they will execute the contract agreement and begin and complete the work within the time named herein, and they will file a good and sufficient surety bond for the amount of the contract for performance and also for the full amount of the contract for payment.

The bidder, if awarded the contract, shall pay all claims as required by Section 779.14, Statutes of Wisconsin, and shall be subject to and discharge all liabilities for injuries pursuant to Chapter 102 of the Statutes of Wisconsin, and all acts amendatory thereto. They shall further be responsible for any damages to property or injury to persons occurring through their own negligence or that of their employees or agents, incident to the performance of work under this contract, pursuant to the Standard Specifications for Road and Bridge Construction applicable to this contract.

In connection with the performance of work under this contract, the contractor agrees to comply with all applicable state and federal statutes relating to non-discrimination in employment. No otherwise qualified person shall be excluded from employment or otherwise be subject to discrimination in employment in any manner on the basis of age, race, religion, color, gender, national origin or ancestry, disability, arrest or conviction record (in keeping with s.111.32), sexual orientation, marital status, membership in the military reserve, honesty testing, genetic testing, and outside use of lawful products. This provision shall include, but not be limited to the following: employment, upgrading, demotion or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation, and selection for training, including apprenticeship. The contractor further agrees to ensure equal opportunity in employment to all applicants and employees and to take affirmative action to attain a representative workforce.

The contractor agrees to post notices and posters setting forth the provisions of the nondiscrimination clause, in a conspicuous and easily accessible place, available for employees and applicants for employment.

If a state public official (section 19.42, Stats.) or an organization in which a state public official holds at least a 10% interest is a party to this agreement, this contract is voidable by the state unless appropriate disclosure is made to the State of Wisconsin Ethics Board.

# Effective with August 2015 Letting BID PREPARATION

# Preparing the Proposal Schedule of Items

#### A General

- (1) Obtain bidding proposals as specified in section 102 of the standard specifications prior to 11:45 AM of the last business day preceding the letting. Submit bidding proposals using one of the following methods:
  - 1. Electronic bid on the internet.
  - 2. Electronic bid on a printout with accompanying diskette or CD ROM.
  - 3. Paper bid under a waiver of the electronic submittal requirements.
- (2) Bids submitted on a printout with accompanying diskette or CD ROM or paper bids submitted under a waiver of the electronic submittal requirements govern over bids submitted on the internet.
- (3) The department will provide bidding information through the department's web site at: <u>https://wisconsindot.gov/Pages/doing-bus/contractors/hcci/bid-let.aspx</u>

The contractor is responsible for reviewing this web site for general notices as well as information regarding proposals in each letting. The department will also post special notices of all addenda to each proposal through this web site no later than 4:00 PM local time on the Thursday before the letting. Check the department's web site after 5:00 PM local time on the Thursday before the letting to ensure all addenda have been accounted for before preparing the bid. When bidding using methods 1 and 2 above, check the Bid Express<sup>TM</sup> on-line bidding exchange at <u>http://www.bidx.com/</u>after 5:00 PM local time on the Thursday before the letting to ensure that the latest schedule of items Expedite file (\*.ebs or \*.00x) is used to submit the final bid.

<sup>(4)</sup> Interested parties can subscribe to the Bid Express<sup>TM</sup> on-line bidding exchange by following the instructions provided at the www.bidx.com web site or by contacting:

Info Tech Inc. 5700 SW 34th Street, Suite 1235 Gainesville, FL 32608-5371 email: <u>mailto:customer.support@bidx.com</u>

(5) The department will address equipment and process failures, if the bidder can demonstrate that those failures were beyond their control.

(6) Contractors are responsible for checking on the issuance of addenda and for obtaining the addenda. Notice of issuance of addenda is posted on the department's web site at: <u>https://wisconsindot.gov/Pages/doing-bus/contractors/hcci/bid-let.aspx</u>

or by calling the department at (608) 266-1631. Addenda can ONLY be obtained from the departments web site listed above or by picking up the addenda at the Bureau of Highway Construction, 4<sup>th</sup> floor, 4822 Madison Yards Way, Madison, WI, during regular business hours.

(7) Addenda posted after 5:00 PM on the Thursday before the letting will be emailed to the eligible bidders for that proposal. All eligible bidders shall acknowledge receipt of the addenda whether they are bidding on the proposal or not. Not acknowledging receipt may jeopardize the awarding of the project.

# **B** Submitting Electronic Bids

#### B.1 On the Internet

- (1) Do the following before submitting the bid:
  - 1. Have a properly executed annual bid bond on file with the department.

- 2. Have a digital ID on file with and enabled by Info Tech Inc. Using this digital ID will constitute the bidder's signature for proper execution of the bidding proposal.
- (2) In lieu of preparing, delivering, and submitting the proposal as specified in 102.6 and 102.9 of the standard specifications, submit the proposal on the internet as follows:
  - 1. Download the latest schedule of items reflecting all addenda from the Bid Express<sup>TM</sup> web site.
  - 2. Use Expedite<sup>TM</sup> software to enter a unit price for every item in the schedule of items.
  - 3. Submit the bid according to the requirements of Expedite<sup>TM</sup> software and the Bid Express<sup>TM</sup> web site. Do not submit a bid on a printout with accompanying diskette or CD ROM or a paper bid. If the bidder does submit a bid on a printout with accompanying diskette or a paper bid in addition to the internet submittal, the department will disregard the internet bid.
  - 4. Submit the bid before the hour and date the Notice to Contractors designates.
  - 5. Do not sign, notarize, and return the bidding proposal described in 102.2 of the standard specifications.
- (3) The department will not consider the bid accepted until the hour and date the Notice to Contractors designates.

#### B.2 On a Printout with Accompanying Diskette or CD ROM

(1) Download the latest schedule of items from the Wisconsin pages of the Bid Express<sup>TM</sup> web site reflecting the latest addenda posted on the department's web site at: https://wisconsindot.gov/Pages/doing-bus/contractors/hcci/bid-let.aspx

Use Expedite <sup>TM</sup> software to prepare and print the schedule of items. Provide a valid amount for all price fields. Follow instructions and review the help screens provided on the Bid Express<sup>TM</sup> web site to assure that the schedule of items is prepared properly.

<sup>(2)</sup> Staple an 8 1/2 by 11 inch printout of the Expedite<sup>™</sup> generated schedule of items to the other proposal documents submitted to the department as a part of the bidder's sealed bid. As a separate submittal, not in the sealed bid envelop but due at the same time and place as the sealed bid, also provide the Expedite<sup>™</sup> generated schedule of items on a 3 1/2 inch computer diskette or CD ROM. Label each diskette or CD ROM with the bidder's name, the 4 character department-assigned bidder identification code from the top of the bidding proposal, and a list of the proposal numbers included on that diskette or CD ROM as indicated in the following example:

#### **Bidder Name**

**BN00** 

#### Proposals: 1, 12, 14, & 22

- (3) If bidding on more than one proposal in the letting, the bidder may include all proposals for that letting on one diskette or CD ROM. Include only submitted proposals with no incomplete or other files on the diskette or CD ROM.
- (4) The bidder-submitted printout of the Expedite<sup>TM</sup> generated schedule of items is the governing contract document and must conform to the requirements of section 102 of the standard specifications. If a printout needs to be altered, cross out the printed information with ink or typewriter and enter the new information and initial it in ink. If there is a discrepancy between the printout and the diskette or CD ROM, the department will analyze the bid using the printout information.
- (5) In addition to the reasons specified in section 102 of the standard specifications, proposals are irregular and the department may reject them for one or more of the following:
  - 1. The check code printed on the bottom of the printout of the Expedite<sup>TM</sup> generated schedule of items is not the same on each page.
  - 2. The check code printed on the printout of the Expedite<sup>TM</sup> generated schedule of items is not the same as the check code for that proposal provided on the diskette or CD ROM.

3. The diskette or CD ROM is not submitted at the time and place the department designates.

#### C Waiver of Electronic Submittal

- <sup>(1)</sup> The bidder may request a waiver of the electronic submittal requirements. Submit a written request for a waiver in lieu of bids submitted on the internet or on a printout with accompanying diskette or CD ROM. Use the waiver that was included with the paper bid document sent to the bidder or type up a waiver on the bidder's letterhead. The department will waive the electronic submittal requirements for a bidding entity (individual, partnership, joint venture, corporation, or limited liability company) for up to 4 individual proposals in a calendar year. The department may allow additional waivers for equipment malfunctions.
- (2) Submit a schedule of items on paper conforming to section 102 of the standard specifications. The department charges the bidder a \$75 administrative fee per proposal, payable at the time and place the department designates for receiving bids, to cover the costs of data entry. The department will accept a check or money order payable to: "Wisconsin, Dept. of Transportation."
- (3) In addition to the reasons specified in section 102 of the standard specifications, proposals are irregular and the department may reject them for one or more of the following:
  - 1. The bidder fails to provide the written request for waiver of the electronic submittal requirements.
  - 2. The bidder fails to pay the \$75 administrative fee before the time the department designates for the opening of bids unless the bidder requests on the waiver that theybe billed for the \$75.
  - 3. The bidder exceeds 4 waivers of electronic submittal requirements within a calendar year.
- (4) In addition to the reasons specified in section 102 of the standard specifications, the department may refuse to issue bidding proposals for future contracts to a bidding entity that owes the department administrative fees for a waiver of electronic submittal requirements.

# **PROPOSAL BID BOND**

DT1303 1/2006

Proposal Number	Project Number		Letting Date
Name of Principal			
Name of Surety		State in Which Surety is	Organized

We, the above-named Principal and the above-named Surety,	are held and firmly bound unto the State of Wisconsin in the sum
equal to the Proposal Guaranty for the total bid submitted for the	payment to be made; we jointly and severally bind ourselves, our
heirs, executors, administrators, successors and assigns. The co	ondition of this obligation is that the Principal has submitted a bid
proposal to the State of Wisconsin acting through the Department	of Transportation for the improvement designated by the Proposal
Number and Letting Date indicated above.	

If the Principal is awarded the contract and, within the time and manner required by law after the prescribed forms are presented for signature, enters into a written contract in accordance with the bid, and files the bond with the Department of Transportation to guarantee faithful performance and payment for labor and materials, as required by law, or if the Department of Transportation shall reject all bids for the work described, then this obligation shall be null and void; otherwise, it shall be and remain in full force and effect. In the event of failure of the Principal to enter into the contract or give the specified bond, the Principal shall pay to the Department of Transportation within 10 business days of demand a total equal to the Proposal Guaranty as liquidated damages; the liability of the Surety continues for the full amount of the obligation as stated until the obligation is paid in full.

The Surety, for value received, agrees that the obligations of it and its bond shall not be impaired or affected by any extension of time within which the Department of Transportation may accept the bid; and the Surety does waive notice of any such extension.

IN WITNESS, the Principal and Surety have agreed and have signed by their proper officers and have caused their corporate seals to be affixed this date: (DATE MUST BE ENTERED)

PRINCIPAL	
(Company Name) (Affix Corporate Seal)	
(Signature and Title)	
(Company Name)	
(Signature and Title)	
(Company Name)	
(Signature and Title)	(Name of Surety) (Affix Seal)
(Company Name)	(Signature of Attorney-in-Fact)
(Signature and Title)	
NOTARY FOR PRINCIPAL	NOTARY FOR SURETY
(Date)	(Date)
State of Wisconsin )	State of Wisconsin )
) ss. County )	) ss. County )
On the above date, this instrument was acknowledged before me by the named person(s).	On the above date, this instrument was acknowledged before me by the named person(s).
(Signature, Notary Public, State of Wisconsin)	(Signature, Notary Public, State of Wisconsin)
(Print or Type Name, Notary Public, State of Wisconsin)	(Print or Type Name, Notary Public, State of Wisconsin)
(Date Commission Expires)	(Date Commission Expires)
Notary Seal	Notary Seal

IMPORTANT: A certified copy of Power of Attorney of the signatory agent must be attached to the bid bond.

# **CERTIFICATE OF ANNUAL BID BOND**

DT1305 8/2003

Time Period Valid (From/To)
Name of Surety
Name of Contractor
Certificate Holder
Wisconsin Department of Transportation

This is to certify that an annual bid bond issued by the above-named Surety is currently on file with the Wisconsin Department of Transportation.

This certificate is issued as a matter of information and conveys no rights upon the certificate holder and does not amend, extend or alter the coverage of the annual bid bond.

**Cancellation**: Should the above policy be cancelled before the expiration date, the issuing surety will give thirty (30) days written notice to the certificate holder indicated above.

(Signature of Authorized Contractor Representative)

(Date)

# March 2010

# LIST OF SUBCONTRACTORS

Section 66.0901(7), Wisconsin Statutes, provides that as a part of the proposal, the bidder also shall submit a list of the subcontractors the bidder proposes to contract with and the class of work to be performed by each. In order to qualify for inclusion in the bidder's list a subcontractor shall first submit a bid in writing, to the general contractor at least 48 hours prior to the time of the bid closing. The list may not be added to or altered without the written consent of the municipality. A proposal of a bidder is not invalid if any subcontractor and the class of work to be performed by the subcontractor has been omitted from a proposal; the omission shall be considered inadvertent or the bidder will perform the work personally.

No subcontract, whether listed herein or later proposed, may be entered into without the written consent of the Engineer as provided in Subsection 108.1 of the Standard Specifications.

Name of Subcontractor	<b>Class of Work</b>	<b>Estimated Value</b>

# **DECEMBER 2000**

# **CERTIFICATION REGARDING DEBARMENT, SUSPENSION, AND OTHER RESPONSIBILITY MATTERS - PRIMARY COVERED TRANSACTIONS**

# Instructions for Certification

- 1. By signing and submitting this proposal, the prospective contractor is providing the certification set out below.
- 2. The inability of a person to provide the certification required below will not necessarily result in denial of participation in this covered transaction. The prospective contractor shall submit an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective contractor to furnish a certification or an explanation shall disqualify such person from participation in this transaction.
- 3. The certification in this clause is a material representation of fact upon which reliance was placed when the department determined to enter into this transaction. If it is later determined that the contractor knowingly rendered an erroneous certification in addition to other remedies available to the Federal Government the department may terminate this transaction for cause or default.
- 4. The prospective contractor shall provide immediate written notice to the department to whom this proposal is submitted if at any time the prospective contractor learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.
- 5. The terms "covered transaction," "debarred," "suspended," "ineligible," "lower tier covered transaction," "participant," "person," "primary covered transaction," "principal," "proposal," and "voluntarily excluded," as used in this clause, have the meanings set out in the Definitions and Coverage sections of the rules implementing Executive Order 12549. You may contact the department to which this proposal is being submitted for assistance in obtaining a copy of those regulations.
- 6. The prospective contractor agrees by submitting this proposal that, should this contract be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department entering into this transaction.
- 7. The prospective contractor further agrees by submitting this proposal that it will include the clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," which is included as an addendum to PR-1273 "Required Contract Provisions Federal Aid Construction Contracts," without

modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions.

- 8. The contractor may rely upon a certification of a prospective subcontractor/materials supplier that it is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A contractor may decide the method and frequency by which it determines the eligibility of its principals. Each contractor may, but is not required to, check the Disapproval List (telephone # 608/266/1631).
- 9. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of a contractor is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
- 10. Except for transactions authorized under paragraph 6 of these instructions, if a contractor in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department may terminate this transaction for cause or default.

Certification Regarding Debarment, Suspension, and Other Responsibility Matters - Primary Covered Transactions

- (1) The prospective contractor certifies to the best of its knowledge and belief, that it and its principals:
  - (a) Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from covered transactions by any Federal department or agency;
  - (b) Have not within a three-year period preceding this proposal been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements or receiving stolen property;
  - (c) Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offense enumerated in paragraph (1)(b) of this certification; and
  - (d) Have not within a three-year period preceding this proposal had one or more public transactions (Federal, State or local) terminated for cause or default.
- (2) Where the prospective contractor is unable to certify to any of the statements in this certification, such prospective contractor shall attach an explanation to this proposal.

# Special Provisions Table of Contents

	Article	Description	Page #
1.	General		2
2.	Scope of Work		2
3.	Prosecution and Progress		2
4.	Traffic.		3
5.	Holiday and Special Event Work Restrictions.		3
6.	Utilities		3
7.	Information to Bidders, U.S. Army Corps of Er	ngineers Section 404 Permit	4
8.	Environmental Protection, Aquatic Exotic Spe	cies Control	4
9.	Erosion Control Structures.		5
10.	Notice to Contractor, Notification of Demolition	n and/or Renovation No Asbestos Found	5
11.	Construction Over or Adjacent to Navigable W	/aters	5
12.	Removing Concrete Posts, Item 204.9060.S.C	1	5
13.	Installing and Maintaining Bird Deterrent System	em Sta. 11+26, Item 999.2000.S.01	6

# STSP'S Revised July 8, 2021 SPECIAL PROVISIONS

# 1. General.

Perform the work under this construction contract for Project 5728-00-73, Town of Perry, Drammen Valley Rd, Pleasant Valley Br Bridge, B-13-0691, Local Street, Dane County, Wisconsin as the plans show and execute the work as specified in the State of Wisconsin, Department of Transportation, Standard Specifications for Highway and Structure Construction, 2022 Edition, as published by the department, and these special provisions.

If all or a portion of the plans and special provisions are developed in the SI metric system and the schedule of prices is developed in the US standard measure system, the department will pay for the work as bid in the US standard system.

100-005 (20210708)

# 2. Scope of Work.

The work under this contract shall consist of grading, base aggregate dense, HMA pavement, removal of Structure P-13-224, erosion control items, finishing items, Structure B-13-0691 and all incidental items necessary to complete the work as shown on the plans and included in the proposal and contract.

104-005 (20090901)

### 3. **Prosecution and Progress.**

Begin work within 10 calendar days after the engineer issues a written notice to do so.

Provide the time frame for construction of the project within the 2022 construction season to the engineer in writing within a month after executing the contract but at least 14 calendar days before the preconstruction conference. Assure that the time frame is consistent with the contract completion time. Upon approval, the engineer will issue the notice to proceed within 10 calendar days before the beginning of the approved time frame.

To revise the time frame, submit a written request to the engineer at least two weeks before the beginning of the intended time frame. The engineer will approve or deny that request based on the conditions cited in the request and its effect on the department's scheduled resources.

#### Coordination

Invite local EMS and first responders to the pre-construction meeting. Notify local officials from Town of Perry, local first responders, and the United States Postal Service two weeks prior to closing Drammen Valley Road. Notifications shall be confirmed will all parties one week prior to implementation. Parties shall also be notified when the roadway is re-opened to through traffic.

#### **Fish Spawning**

There shall be no instream disturbance of Kittleson Valley Creek at Station 11+26 as a result of construction activity under or for this contract, from September 15 to May 15 both dates inclusive, in order to avoid adverse impacts upon the spawning of trout.

Any change to this limitation will require submitting a written request by the contractor to the engineer, subsequent review and concurrence by the Department of Natural Resources in the request, and final approval by the engineer. The approval will include all conditions to the request as mutually agreed upon by WisDOT and DNR.

#### **Migratory Birds**

Swallow or other migratory bird nests have been observed on or under the existing structure(s). All active nests (when eggs or young are present) of migratory birds are protected under the federal Migratory Bird Treaty Act. The nesting season for swallows and other birds is from April 15 to August 31.

Either prevent active nests from becoming established or prevent birds from nesting by installing and/or maintaining a suitable deterrent device on the remaining structure prior to nesting activity under the bid item Installing and Maintaining Bird Deterrent System. As a last resort, apply for a depredation permit from the US Fish and Wildlife Service for work that may disturb or destroy active nests. The need for a permit may be avoided by removing the existing bridge structure prior to nest occupation by birds or clearing nests from all structures before the nests become active in early spring.

Working day assessments will not be charged for work associated with installing and maintaining bird deterrent system prior to Notice to Proceed.

#### Northern Long-eared Bat (Myotis septentrionalis)

Northern Long-eared Bats (NLEB) have the potential to inhabit the project limits because they roost in trees. Roosts may not have been observed on this project, but conditions to support the species exist. The species and all active roosts are protected by the Federal Endangered Species Act. If an individual bat or active roost is encountered during construction operations, stop work and notify the engineer and the WisDOT Regional Environmental Coordinator (REC).

If additional construction activities beyond what was originally specified are required to complete the work, approval from the engineer, following coordination with WisDOT REC, is required prior to initiating these activities.

#### Blanding's Turtle (Emydoidea blandingii)

Blanding's Turtle is a special concern species that has the potential to be encountered within the project limits. In order to avoid impacting this species, follow amphibian and reptile exclusion fencing protocols. Place fencing and turnarounds as shown on the plans prior to active periods for the listed species and extend fencing far enough past any drainage ditch, wet meadow, or other wetland so as to prevent listed species from accessing the construction zone. The active periods for the species of concern can begin in early March and continue through mid-November.

### 4. Traffic.

Close Drammen Valley Road during construction operations. Maintain access to existing driveways and field entrances during construction.

# 5. Holiday and Special Event Work Restrictions.

Do not perform work on, nor haul materials of any kind along or across any portion of the highway carrying Drammen Valley Road traffic, and entirely clear the traveled way and shoulders of such portions of the highway of equipment, barricades, signs, lights, and any other material that might impede the free flow of traffic during the following holiday and special event periods:

- From noon Friday, May 27, 2022 to 6:00 AM Tuesday, May 31, 2022 for Memorial Day;
- From noon Friday, July 1, 2022 to 6:00 AM Tuesday, July 5, 2022 for Independence Day;
- From noon Friday, September 2, 2022 to 6:00 AM Tuesday, September 6, 2022 for Labor Day.

stp-107-005 (20210113)

#### 6. Utilities.

This contract does not come under the provision of Administrative Rule Trans 220.

stp-107-066 (20080501)

There are underground and overhead utility facilities within the construction limits of this project. Use caution so that the integrity of underground facilities and OSHA code clearances from overhead facilities are maintained at all times.

The following companies have facilities within the project area.

**Alliant Energy (electric)** has overhead facilities located along the west side of Drammen Valley Road at an approximate offset of 22 to 24 feet within the project limits. There is a pole located at approximately Station 10+88, 24' LT where the line crosses to the east side of the roadway, south of the project limits. The intent is to leave the pole and overhead lines in place during construction. Alliant plans to install facilities during summer 2021 so the overhead line can be de-energized during construction and add markers to the overhead lines, so they are more visible during construction.

**TDS Telecom (communications)** has underground facilities along the east side of Drammen Valley Road at an approximate offset of 20 feet. No adjustments are anticipated.

# 7. Information to Bidders, U.S. Army Corps of Engineers Section 404 Permit.

The department has obtained a U.S. Army Corps of Engineers Section 404 permit. Comply with the requirements of the permit in addition to requirements of the special provisions. A copy of the permit is available from the regional office by contacting Travis Buros at (608) 789-5702.

stp-107-054 (20210708)

# 8. Environmental Protection, Aquatic Exotic Species Control.

Exotic invasive organisms such as VHS, zebra mussels, purple loosestrife, and Eurasian water milfoil are becoming more prolific in Wisconsin and pose adverse effects to waters of the state. Wisconsin State Statutes 30.07, "Transportation of Aquatic Plants and Animals; Placement of Objects in Navigable Waters", details the state law that requires the removal of aquatic plants and zebra mussels each time equipment is put into state waters.

At construction sites that involve navigable water or wetlands, use the follow cleaning procedures to minimize the chance of exotic invasive species infestation. Use these procedures for all equipment that comes in contact with waters of the state and/or infested water or potentially infested water in other states.

Ensure that all equipment that has been in contact with waters of the state, or with infested or potentially infested waters, has been decontaminated for aquatic plant materials and zebra mussels before being used in other waters of the state. Before using equipment on this project, thoroughly disinfect all equipment that has come into contact with potentially infested waters. Guidelines from the Wisconsin Department of Natural Resources for disinfection are available at:

### http://dnr.wi.gov/topic/invasives/disinfection.html

Use the following inspection and removal procedures:

- 1. Before leaving the contaminated site, wash machinery and ensure that the machinery is free of all soil and other substances that could possibly contain exotic invasive species;
- 2. Drain all water from boats, trailers, bilges, live wells, coolers, bait buckets, engine compartments, and any other area where water may be trapped;
- 3. Inspect boat hulls, propellers, trailers and other surfaces. Scrape off any attached mussels, remove any aquatic plant materials (fragments, stems, leaves, seeds, or roots), and dispose of removed mussels and plant materials in a garbage can before leaving the area or invested waters; and
- 4. Disinfect your boat, equipment and gear by either:
  - 4.1. Washing with ~212°F water (steam clean), or
  - 4.2. Drying thoroughly for five days after cleaning with soap and water and/or high pressure water, or
  - 4.3. Disinfecting with either 200 ppm (0.5 oz per gallon or 1 Tablespoon per gallon) Chlorine for 10-minute contact time or 1:100 solution (38 grams per gallon) of Virkon Aquatic for 20- to 30-minute contact time. Note: Virkon is not registered to kill zebra mussel veligers nor invertebrates like spiny water flea. Therefore, this disinfect should be used in conjunction with a hot water (>104°F) application.

Complete the inspection and removal procedure before equipment is brought to the project site and before the equipment leaves the project site.

stp-107-055 (20130615)

# 9. Erosion Control Structures.

Within three calendar days after completing the excavation for a substructure unit, place riprap or other permanent erosion control items required by the contract or deemed necessary by the engineer around the unit at a minimum to a height equivalent to the calculated water elevation resulting from a storm that occurs on the average of once every two years (Q2) as shown on the plan, or as the engineer directs.

In the event that construction activity does not disturb the existing ground below the Q2 elevation, the above timing requirements for permanent erosion control shall be waived.

stp-107-070 (20191121)

# 10. Notice to Contractor, Notification of Demolition and/or Renovation No Asbestos Found.

Paul Garvey, License Number All-117079, inspected Structure P-13-0224 for asbestos on 6/17/2019. No regulated Asbestos Containing Material (RACM) was found on this structure. A copy of the inspection report is available from: Travis Buros, (608) 789-5702.

According to NR447 and DHS159, ensure that DNR or DHS receives a completed Notification of Demolition and/or Renovation (DNR Form 4500-113 (R 4/11), or subsequent revision) via U.S. mail, hand-delivery, or using the online notification system at least 10 working days before beginning any construction or demolition. Pay all associated fees. Provide a copy of the completed 4500-113 form to Travis Buros, (608) 789-5702 and DOT BTS-ESS attn: Hazardous Materials Specialist, PO Box 7965, Madison, WI 53707-7965. In addition, comply with all local or municipal asbestos requirements.

Use the following information to complete WisDNR form 4500-113:

- Site Name: Structure P-13-0224, Drammen Valley Rd over Pleasant Valley Branch
- Site Address: 2.0M S JCT CTH A
- Ownership Information: 10084 County Road A, Mount Horeb, WI 53572-3237
- Contact: Travis Buros, P.E., WisDOT
- Phone: (608) 789-5702
- Age: 92 years old. This structure was constructed in 1929.
- Area: 747 SF of deck

Insert the following paragraph in Section 6.g.:

If asbestos not previously identified is found or previously non-friable asbestos becomes crumbled, pulverized, or reduced to a powder, stop work immediately, notify the engineer, and the engineer will notify the department's Bureau of Technical Services at (608) 266-1476 for an emergency response as specified in standard spec 107.24. Keep material wet until it is abated or until it is determined to be non-asbestos containing material.

stp-107-125 (20120615)

# 11. Construction Over or Adjacent to Navigable Waters.

The Kittleson Valley Creek is classified as a state navigable waterway under standard spec 107.19.

#### 12. Removing Concrete Posts, Item 204.9060.S.01

#### **A** Description

This special provision describes removing concrete posts conforming to standard spec 204.

B (Vacant)

#### C (Vacant)

#### **D** Measurement

The department will measure Removing Concrete Posts in each, acceptably completed.

# E Payment

Add the following to standard spec 204.5:

ITEM NUMBER DESCRIPTION 204.9060.S Removing Concrete Posts stp-204-025 (20150630)

UNIT EACH

# 13. Installing and Maintaining Bird Deterrent System Sta. 11+26, Item 999.2000.S.01.

#### A Description

This special provision describes inspecting, installing and/or maintaining approved deterrents that prevent migratory bird nesting on bridges and culverts. Swallows or other migratory birds' nests have been observed on or under the existing culvert or bridge at the station identified. All active nests (when eggs or young are present) of migratory birds are protected under the federal Migratory Bird Treaty Act.

#### **B** Materials

#### **B.1 Hardware and Lumber**

Pressure treated lumber shall conform to the requirements of standard spec 507.

Hardware and fastening devices shall be either galvanized or stainless steel. Fastening device and system must be approved by the engineer prior to installation on culverts and bridges that will remain in service after removal of deterrent systems. The method of fastening should not compromise the culvert or bridge concrete surfaces or steel protection systems. The attachment locations must be restored and repaired as needed by use of engineer approved fillers, sealers and paint systems.

#### **B.2 Netting Materials**

Exclusion netting is material either wrapped around or draped and fastened to bridge decks/abutments and culvert corners to prevent bird entry.

Furnish exclusionary netting to deter nesting in bridge decks and abutments and corners of box culverts, consisting of either:

- a. 1/2" x 1/2" or 3/4" x 3/4" knotless, flame resistant, U.V. stabilized polyethylene netting with minimum 40-pound breaking strength per strand, or engineer proved equal.
- b. Galvanized wire mesh (hardware cloth) with a wire diameter of .040 inches (19-gauge) and opening width of 1/2-inch.

Furnish 1" x 2" pressure treated lumber of equal length as the netting.

#### **B.3 Plastic Strip Curtain**

Plastic strip curtains are strips of plastic attached to vertical surfaces in areas suitable for nesting.

Furnish 3-foot wide lengths of 6 mil minimum plastic sheeting with the lower 2 feet cut into vertical strips 2 inches wide.

Furnish 1" x 2" treated wood and galvanized staples to attach plastic strips to wood to fabricate the strip curtain.

Furnish concrete screws to attach strip curtain to structure.

#### **B.4 Corner Slope Materials**

Corner slopes are pieces of curved plastic placed in corners suitable for nesting. They are particularly effective in preventing nesting in top corners of box culverts.

Furnish U.V. stabilized pre-fabricated PVC or polycarbonate corner slopes from commercial bird-deterrent manufacturers or an approved equal.

# **C** Construction

# C.1 General

If active nests are observed after construction starts, or if a trapped bird or an active nest is found, stop work that may affect birds or their nests, and notify the engineer to consult with the Wisconsin Department of Natural Resources transportation liaison at Eric Heggelund at (608) 228-7927, or the department regional environmental coordinator Brian Taylor at (608) 245-2630.

Efforts should be made to release trapped birds, unharmed.

### C.2 Nest Removal

Remove unoccupied nests prior to the beginning of the nesting season as designated in Prosecution and Progress. Nest removal involves the removal and disposal of unoccupied or partially constructed nests without eggs or nestlings. Removing all evidence of nesting (e.g. cleaning droppings from structures) eliminates a visual cue for a potential breeding location, especially for first-time breeders. Nest removal is not a type of deterrent and does not prevent nest establishment but can delay the process. As such, it should only be used in conjunction with other methods. It cannot be used on its own to ensure compliance. However, nest removal is not required if deterrents are installed before the start of the avoidance window.

Remove nests on the structure by scraping or pressure washing prior to established avoidance windows to deter nesting. Remove only unoccupied or partially constructed nests without eggs or nestlings. Remove newly built nests every two days before eggs are laid. Nest removal is intended to be used prior to and in conjunction with other nesting deterrents.

#### **C.3 Exclusion Netting**

#### C.3.1 Installation

Using concrete screws, anchor lumber to bridge or culvert along perimeter of intended netting. Fasten netting to lumber until netting is held taut. Eliminate any loose pockets or wrinkles that could trap and entangle birds. Ensure the net is pulled taut in order to prevent flapping in the wind, which results in tangles or breakage at mounting points.

For culverts, attach netting at a 45-degree angle at the culvert corner so it extends at least 12 inches below the corner.

#### **C.4 Plastic Curtains**

#### C.4.1 Installation

Attach plastic curtains along the entire length of vertical surface or corner on which nest building is to be deterred. Affix plastic curtain strips to treated lumber with staples spaced a minimum of 1 foot O.C. Wrap plastic curtains around lumber prior to attaching it to the structure to reduce the likelihood of it tearing out at the staples. Screw lumber into the underside of the bridge deck or top of box culvert with concrete screws placed 24 inches O.C. minimum.

#### C.5 Corner Slopes

#### C.5.1 Installation

Attach corner slopes to the structure per the manufacturer's recommendations. Use urethane-based adhesives if manufacturer supplied hardware or adhesives are not available or no recommendations are provided. Install end caps or seal ends of corner slopes to prevent entry of birds or other animals.

#### C.6 Inspection and Maintenance

Inspect bird deterrent devices every two weeks both during and prior to construction when deterrents have been installed to exclude birds prior to nesting windows, and after large storm events or high winds. Ensure that netting is taut, that no gaps or holes have formed, and that the nets are functioning properly. Ensure that corner slopes are not cracked or otherwise damaged and are functioning properly. Ensure that curtains are undamaged, with no tears, holes, or creases. Repair any damaged or loose deterrent devices. Inspect, maintain, and repair nesting deterrents whether installed by the contractor or others. Repair, replace, supplement deterrents as necessary with materials meeting the requirements of this specification.

Remove any unoccupied or partially constructed nests without eggs or nestlings.

Repair deterrents to prevent birds from attempting to nest again.

Record all inspection, removal, and maintenance activities. Provide inspection, removal and maintenance records to the engineer upon request.

#### C.7 Removal and Structure Repair

Maintain the deterrent until the engineer determines that the deterrent is deemed no longer necessary. Upon completion of the project, remove any remaining migratory bird deterrent from the project site. If the existing bridge or culvert is to remain after construction, restore and repair as needed by use of engineer approved fillers, sealers and paint systems.

#### **D** Measurement

The department will measure Installing and Maintaining Bird Deterrent System (Station) as a single unit at each structure, acceptably completed.

The department will measure Maintaining Bird Deterrent System (Station) as a single unit at each structure, acceptably completed.

#### E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
999.2000.S.01	Installing and Maintaining Bird Deterrent System Sta. 11+26	EACH

Payment for Installing and Maintaining Bird Deterrent System is full compensation for providing and installing deterrents that prevent migratory bird nesting; removing and disposing of unoccupied or partially constructed nests without eggs or nestlings; maintaining, repairing, replacing, supplementing, existing deterrent materials; repairing damage to structures resulting from installation of deterrents; removal and disposal of materials.

stp-999-200 (20210708)

# **Effective December 2020 Letting**

# **ADDITIONAL SPECIAL PROVISION 4**

This special provision does not limit the right of the department, prime contractor, or subcontractors at any tier to withhold payment for work not acceptably completed or work subject to an unresolved contract dispute.

# **Payment to First-Tier Subcontractors**

Within 10 calendar days of receiving a progress payment for work completed by a subcontractor, pay the subcontractor for that work. The prime contractor may withhold payment to a subcontractor if, within 10 calendar days of receipt of that progress payment, the prime contractor provides written notification to the subcontractor and the department documenting "just cause" for withholding payment.

The prime contractor is not allowed to withhold retainage from payments due subcontractors.

# Payment to Lower-Tier Subcontractors

Ensure that subcontracting agreements at all tiers provide prompt payment rights to lowertier subcontractors that parallel those granted first-tier subcontractors in this provision.

# **Additional Special Provision 6**

# ASP 6 - Modifications to the standard specifications

Make the following revisions to the standard specifications:

# 415.3.16 Tolerance in Pavement Thickness

Replace the entire text with the following effective with the November 2021 letting:

#### 415.3.16.1 General

(1) Construct the plan thickness or thicker. The department will accept pavement thickness based on the results of department-performed acceptance testing conforming to:

Magnetic Pulse Induction	CMM 870: ASTM E3209 WTM
Probing	CMM 870: WTP C-002
Preplacement Measurement	CMM 870: WTP C-003

#### 415.3.16.2 Pavement Units

#### 415.3.16.2.1 Basic Units

(1) Basic unit is defined as a slip formed, single lane, with a minimum lane width of 10 feet, measured, from the pavement edge to the adjacent longitudinal joint; from one longitudinal joint to the next; or between pavement edges if there is no longitudinal joint.

#### 415.3.16.2.2 Special Units

(2) Establish special units for areas of fillets, intersections, gaps, gores, shoulders, ramps, pavement lanes less than 10 feet wide and other areas not included in basic units.

#### 415.3.16.3 Test Plate Locations

(1) Place department-furnished test plates. Within 5 business days after paving, enter the sequential number and associated position data into MRS available at:

#### http://www.atwoodsystems.com/

(2) Contractor will maintain plate location markings for 10 business days after paving.

# 415.3.16.4 Acceptance Testing

#### 415.3.16.4.1 Basic Units

#### 415.3.16.4.1.2 Magnetic Pulse Induction

- (1) The department will measure thickness within 10 business days of paving. Upon completion of the project thickness testing, the department will provide the test results to the contractor within 5 business days.
- (2) Department will establish a project reference plate at the start of each paving stage. Project reference plate will be measured before each day of testing. Department will notify the contractor of project reference plate locations before testing.
- (3) If the random plate test result falls within 80 to 50 percent pay range specified in 415.5.2, the department will measure the second plate in that unit. The department will notify the contractor immediately if the average of the 6 readings falls within the 80 to 50 percent pay range.
- (4) If an individual random plate test result is more than 1 inch thinner than contract plan thickness, the pavement is unacceptable. Department will determine limits of unacceptable pavement by performing the following:
  - The engineer will test each consecutive plate stationed ahead and behind until the thickness test result is plan thickness or greater.
  - The engineer will direct the contractor to core the hardened concrete to determine the extent of the unacceptable area. In each direction, the contractor shall take cores at points approximately 20 feet from the furthest out of specification plate towards the plate that is plan thickness of greater. Once a core is within 80 to 100 percent pay range, the coring is complete and the limits of unacceptable pavement extend from the stationing between the core test results of 80 to 100 percent payment, inclusive of all unacceptable core and plate test results.
  - The contractor shall perform coring according to AASHTO T24. The department will evaluate the results according to AASHTO T148
  - The contractor shall fill core holes with concrete or mortar.

# 415.3.16.4.2.1 Magnetic Pulse Induction

- (1) The department will measure thickness within 10 business days of paving. Upon completion of the project thickness testing, the department will provide the test results to the contractor within 5 business days.
- (2) Department will establish a project reference plate at the start of each paving stage. Project reference plate will be measured before each day of testing. Department will notify the contractor of project reference plate locations before testing.
- (3) If the random plate test result falls within 80 to 50 percent pay range specified in 415.5.2, the department will measure the second plate in that unit. The department will notify the contractor immediately if the average of the 6 readings falls within the 80 to 50 percent pay range.
- (4) If an individual random plate test result is more than 1 inch thinner than contract plan thickness, the department will measure the second plate in that unit. If both plates are required to be measured, then all six thickness measurements will be averaged for that unit. If the average of the six measurements is more than 1 inch thinner than contract plan thickness, the pavement is unacceptable.

# 415.3.16.4.2.2 Probing

- (1) The department will measure slip form special units during concrete placement. Upon completion of the project thickness testing, the department will provide the test results to the contractor within 5 business days.
- (2) Department will probe 2 random locations within the special unit. The average of the two readings will be the reported measurement for the special unit.

# 415.3.16.4.2.3 Preplacement Measurement

- (1) The department will measure non-slip form special units before concrete placement.
- (2) Thickness corrections will be made to a conforming thickness by reshaping the base aggregate before the pavement is placed.

# 415.5.2 Adjusting Pay for Thickness

Replace the entire text with the following effective with the November 2021 letting:

(1) The department will adjust pay for pavement thickness under the Nonconforming Thickness Concrete Pavement administrative item as follows:

FOR PAVEMENT	PERCENT OF THE
THINNER THAN PLAN THICKNESS BY:	CONTRACT UNIT PRICE
> 1/4 inch but <= 1/2 inch	80
> 1/2 inch but <= 3/4 inch	60
> 3/4 inch but <= 1 inch	50

- (2) When pavement of unacceptable final thickness is determined, as specified in 415.3.16.4, the department will direct the contractor to either:
  - 1. Remove and replace unacceptable concrete pavement to the nearest joint with new concrete pavement of conforming thickness. The department will pay once for the area at the full contract price.
  - 2. If the unacceptable pavement is less than 100 LF, the department may allow the concrete to remain in place without payment for the unacceptable area.

# 460.2.6 Recovered Asphaltic Binders

Replace paragraph two with the following effective with the November 2021 letting:

- (2) The contractor may replace virgin binder with recovered binder up to the maximum percentage allowed under 460.2.5 without further testing. When the design percent asphalt binder replaced exceeds the allowable limits in 460.2.5, the contractor must:
  - Document adjustments made to the mix design in the mix design submittal.
  - Submit test results that indicate the mixture's asphaltic binder meets or exceeds the upper and lower temperature grade requirements the bid item designates.
    - If only one recycled asphaltic material source is used, furnish one of the following:
      - Test results from extracted and recovered binder from the resultant mixture.
      - Blending charts that indicate the resultant mixture's high and low temperature PG as an interpolation of the percent binder replaced between the virgin binder's and the recycled asphaltic material source binder's high and low temperature PG.
    - If two or more recycled asphaltic material sources are used, furnish test results from extracted and

recovered binder from the resultant mixture.

#### 501.2.6 Water

Retitle with the following effective with the November 2021 letting:

501.2.6 Mixing Water

#### 501.2.6.2 Requirements

Replace paragraph two with the following effective with the November 2021 letting:

(2) Water from other sources must comply with the following:

Acidity, maximum of 0.1N NaOH to neutralize 200 mL of water; CMM 870: WTP C-001	2 mL
Alkalinity, maximum of 0.1N HCL to neutralize 200 mL of water; CMM 870: WTP C-001	15 mL
Maximum sulphate (S0 <sub>4</sub> ); CMM 870: WTP C-001	0.05 percent
Maximum chloride; CMM 870: WTP C-001	0.10 percent
Maximum total solids; CMM 870: WTP C-001	
Organic	0.04 percent
Inorganic	0.15 percent

# 501.3.2.4.2 Air Entrainment

Replace paragraph two with the following effective with the November 2021 letting:

(2) Test fresh concrete air content according to AASHTO T152 or AASHTO TP118 at the contract-required frequency and as the engineer directs. Test concrete placed by pumping or belting at the point of discharge from the pump line or belt.

# 501.3.7.1 Slump

Replace paragraph one with the following effective with the November 2021 letting:

(1) Use a 1-inch to 4-inch slump for concrete used in structures or placed in forms, except as follows:

- Do not exceed a slump of 2 inches for grade E concrete.
- Increase slump as specified in 502.3.5.3 for concrete placed underwater.
- If BTS approves a concrete mixture using a superplasticizer, the contractor may increase slump for that mixture to a maximum of 9 inches without exceeding the maximum mix water allowed for that grade.

# 531.5 Payment

Replace paragraph two with the following effective with the November 2021 letting:

(2) Payment for Concrete Masonry Ancillary Structures Type NS is full compensation for providing concrete for non-standard sign structure foundations; and for anchor rod assemblies. The department will pay separately for excavating and backfilling drilled shafts under the Drilling Shafts bid items.

Replace paragraph five with the following effective with the November 2021 letting:

(5) Payment for the Foundation bid items is full compensation for providing concrete foundations; for anchor rod assemblies; for reinforcing steel; and for embedded conduit and electrical components. The department will pay separately for excavating and backfilling drilled shafts under the Drilling Shafts bid items.

# 642.2.2.1 General

Replace paragraph one with the following effective with the November 2021 letting:

(1) Provide each field office with two rooms, separated by an interior door with a padlock. Ensure that each room has a separate exterior door and its own air conditioner. Locate the office where a quality internet connection can be achieved. Ensure quality cell phone reception is achievable inside the field office.

#### 701.3.1 General

Replace table 701-1 with the following effective with the November 2021 letting:

TEST	TEST	MINIMUM REQUIRED CERTIFICATION		
	STANDARD	(any one of the certifications listed for each test)		
		Transportation Materials Sampling Technician (TMS)		
		TMS Assistant Certified Technician (ACT-TMS)		
		Aggregate Technician I (AGGTEC-I)		
Dandom Compling	CMM 830.9.2	AGGTEC-I Assistant Certified Technician (ACT-AGG)		
Random Sampling	CIVIIVI 030.9.2	PCC Technician I (PCCTEC-I)		
		PCCTEC-I Assistant Certified Technician (ACT-PCC) Grading Technician I (GRADINGTEC-I)		
		Grading Assistant Certified Technician (ACT-		
		GRADING)		
Sampling Aggregates	AASHTO T2 <sup>[1] [4]</sup>	TMS, ACT-TMS, AGGTECT-1, ACT-AGG		
Percent passing the No. 200 sieve	AASHTO T11 <sup>[1]</sup>			
Fine & coarse aggregate gradation	AASHTO T27 <sup>[1]</sup>			
Aggregate moisture content	AASHTO T255 <sup>[1]</sup>	AGGTEC-I, ACT-AGG		
Fractured faces	ASTM D5821 <sup>[1]</sup>			
Liquid limit	AASHTO T89	Aggregate Testing for Transportation Systems (ATTS)		
Plasticity index	AASHTO T90 <sup>[3]</sup>	GRADINGTEC-I, or ACT-GRADING		
Sampling freshly mixed concrete	AASHTO R60			
Air content of fresh concrete	AASHTO T152 <sup>[2]</sup> AASHTO TP118 <sup>[5]</sup>			
Air void system of fresh concrete	AASHTO TP118 <sup>[5]</sup>	PCCTEC-1		
Concrete slump	AASHTO T119 <sup>[2]</sup>	ACT-PCC		
Concrete temperature	ASTM C1064			
Making and curing concrete specimens	AASHTO T23			
Moist curing for concrete specimens	AASHTO M201			
Concrete compressive strength	AASHTO T22			
Concrete flexural strength	AASHTO T97	Concrete Strength Tester (CST) CST Assistant Certified Technician (ACT-CST)		
Concrete surface resistivity <sup>[2]</sup>	AASHTO T358	CST ASSISTANT CERTINED TECHNICIAN (ACT-CST)		
Voids in aggregate	AASHTO T19	PCCTEC-II		
Profiling		PROFILER		

<sup>[1]</sup> As modified in CMM 860.

<sup>[2]</sup> As modified in CMM 870.

<sup>[3]</sup> A plasticity check, if required under individual QMP specifications, may be performed by an AGGTEC-I in addition to the certifications listed for liquid limit and plasticity index tests.

<sup>[4]</sup> Plant personnel may operate equipment to obtain samples under the direct observation of a TMS or higher.

<sup>[5]</sup> Consolidate by rodding.

# 710.2 Small Quantities

Replace the entire text with the following effective with the November 2021 letting:

(1) The department defines small quantities as follows:

- As specified in 715.1.1.2 for class I concrete.
- Less than 50 cubic yards of class II ancillary concrete placed under a single bid item.
- (2) For contracts with only small quantities of material subject to testing, modify the requirements of 710 as follows:
  - 1. The contractor may submit an abbreviated quality control plan as allowed in 701.1.2.3.
  - 2. Provide one of the following for aggregate process control:
    - Documented previous testing dated within 120 calendar days. Provide gradation test results to the engineer before placing material.
    - Non-random start-up gradation testing.

# 710.4 Concrete Mixes

Replace paragraph two with the following effective with the November 2021 letting:

(2) At least 7 business days before producing concrete, document that materials conform to 501 unless the engineer allows or individual QMP specifications provide otherwise. Include the following:

# Effective with November 2021 Letting (revised)

- 1. For mixes: quantities per cubic yard expressed as SSD weights and net water, water to cementitious material ratio, air content, and SAM number.
- 2. For cementitious materials and admixtures: type, brand, and source.
- 3. For aggregates: absorption, SSD bulk specific gravity, wear, soundness, freeze thaw test results if required, and air correction factor. Also include aggregate production records dated within 2 years if using those results in the design. Submit component aggregate gradations, aggregate proportions, and target combined blended aggregate gradations using the following:
  - DT2220 for combined aggregate gradations.
  - DT2221 for optimized aggregate gradations.
- 4. For optimized concrete mixtures:
  - Complete the worksheets within DT2221 according to the directions.
  - Ensure the optimized aggregate gradations and the optimized mix design conform to WisDOT specifications and pass the built-in tests within DT2221.
  - Verify slip-form mixture workability according to AASHTO TP137 and conformance to specifications through required trial batching.
  - Submit the completed DT2221 to the engineer electronically. Include the trial batch test results with the mix design submittal.

#### Replace paragraph four with the following effective with the November 2021 letting:

- (4) Prepare and submit modifications to a concrete mix to the engineer for approval 3 business days before using that modified mix. Modifications requiring the engineer's approval include changes in:
  - 1. Source of any material. For paving and barrier mixes, a source change for fly ash of the same class does not constitute a mix design change.
  - 2. Quantities of cementitious materials.
  - 3. Addition or deletion of admixtures. Minor admixture dosage adjustments required to maintain air content or slump do not require engineer review or approval.

#### 710.5.5 Strength

Replace paragraph one with the following effective with the November 2021 letting:

(1) Cast all 6" x 12" cylinders or all 6" x 6" x 21" beams in a set from the same sample. Do not cast more than one set of specimens from a single truckload of concrete. Mark each specimen to identify the lot and sublot or location on the project it represents.

# 710.5.6 Aggregate Testing

Retitle and replace the entire text with the following effective with the November 2021 letting:

#### 710.5.6 Aggregate Testing During Concrete Production

#### 710.5.6.1 General

- (1) The department will accept gradation based on the results of department-performed acceptance testing.
- (2) The department and contractor will obtain samples using the same method. When belt sampling, contractor personnel shall obtain samples for the department under the direct observation of the department personnel. Contractor will define sampling method in the QMP or abbreviated QMP.

#### 710.5.6.2 Contractor Control Charts

#### 710.5.6.2.1 General

- (1) Test aggregate gradations during concrete production except as allowed for small quantities under 710.2. Required contractor testing will be performed using non-random samples.
- (2) Sample aggregates from either the conveyor belt or from the working face of the stockpiles.
- (3) Sample aggregates within 2 business days before placement for each mix design. Include this gradation on the control charts.
- (4) Report gradation test results and provide control charts to the engineer within 1 business day of obtaining the sample. Submit results to the engineer and electronically into MRS as specified in 701.1.2.7.
- (5) Conduct aggregate testing at the minimum frequency shown based on the anticipated daily cumulative plant production for each mix design. The contractor's concrete production tests can be used for the same mix design on multiple contracts.

#### TABLE 710-1 CONTRACTOR GRADATION TESTING FREQUENCY - CLASS I

DAILY PLANT PRODUCTION RATE FOR WisDOT WORK	MINIMUM FREQUENCY		
Gradation Report Before Placement			
1000 cubic yards or less one test per day			
more than 1000 cubic yards	two tests per day		

# TABLE 710-2 CONTRACTOR GRADATION TESTING FREQUENCY - CLASS II

MINIMUM FREQUENCY
Gradation Report Before Placement
One test per calendar week of production

# 710.5.6.2.2 Optimized Aggregate Gradation Control Charts

- (1) Determine the complete gradation using a washed analysis for both fine and coarse aggregates. Report results for the following:
  - 1 1/2", 1", 3/4", 1/2", 3/8", #4, #8, #16, #30, #50, #100, and #200 sieves.
  - Sum of volumetric percentages retained on No. 8, No. 16, and No. 30 sieves.
  - Sum of volumetric percentages retained on No. 30, No. 50, No. 100, and No. 200 sieves.
- <sup>(2)</sup> Calculate blended aggregate gradations using the mix design batch percentages for the component aggregates. Ensure the blended aggregate gradation conforms to the volumetric percent retained of the optimized aggregate gradation limits specified in table 501-4.
- <sup>(3)</sup> Throughout the contract, construct a 4-point running average of the volumetric percent retained for each sieve to determine if the blended aggregate gradation is within the tarantula curve limits specified in table 501-4.

# 710.5.6.2.3 Combined Aggregate Gradation Control Charts

- (1) Determine the complete gradation using a washed analysis for both fine and coarse aggregates. Report results for the 1 1/2", 1", 3/4", 1/2", 3/8", #4, #8, #16, #30, #50, #100, and #200 sieves.
- <sup>(2)</sup> Calculate blended aggregate gradations using the mix design batch percentages for the component aggregates. Ensure the blended aggregate gradation conforms to the percent passing by weight requirements of the combined aggregate gradation limits specified in table 501-4.
- <sup>(3)</sup> Throughout the contract, construct a 4-point running average of the percent passing by weight for each sieve to determine if the blended aggregate gradation is within the combined aggregate gradation limits specified in table 501-4.

# 710.5.6.3 Department Acceptance Testing

- (1) Department testing frequency is based on the quantity of each mix design placed under each individual WisDOT contract.
- (2) The department will split each sample, test for acceptance, and retain the remainder for a minimum of 10 calendar days.
- (3) The department will obtain the sample and deliver to regional testing lab in the same day. Department will report gradation test results to the contractor within 1 business day of being delivered to the lab. Department and contractor can agree to an alternative test result reporting timeframe; alternative timeframe is required to be documented in the QMP.
- (4) Additional samples may be taken at the engineer's discretion due to change in condition.

TABLE / 10-3 DEPARTMENT GRADATION TESTING FREQUENCE				
CONCRETE CLASSIFICATION	CATION MINIMUM DEPARTMENT FREQUENCY			
Class I: Pavement	1 test per placement day for first 5 days of placement. If all samples are passing, reduced frequency is applied.			
	Reduced frequency: 1 test per calendar week of placement			
Class I: Structures	<ol> <li>test per 250 CY placed</li> <li>Minimum of 1 test per substructure</li> <li>Minimum of 1 test per superstructure</li> </ol>			

# TABLE 710-3 DEPARTMENT GRADATION TESTING FREQUENCY

# Effective with November 2021 Letting (revised)

Class I: Cast-in-Place Barrier	1 test per 500 CY placed
Class II	No minimum testing

# 710.5.7 Corrective Action

Replace the entire text with the following effective with the November 2021 letting:

# 710.5.7.1 Optimized Aggregate Gradations

- (1) If the contractor's 4-point running average or a department test result of the volumetric percent retained exceeds the tarantula curve limits by less than or equal to 1.0 percent on a single sieve size, do the following:
  - 1. Notify the other party immediately.
  - 2. Perform corrective action documented in the QC plan or as the engineer approves.
  - 3. Document and provide corrective action results to the engineer as soon as they are available.
  - 4. Department will conduct two tests within the next business day after corrective action is complete.
  - 5. If blended aggregate gradations are within the tarantula curve limits by the second department test:
    - Continue with concrete production.
    - Contractor will include a break in the 4-point running average.
    - For Class I: Pavements, department will discontinue reduced frequency testing and will test at a frequency of 1 test per placement day. Once 5 consecutive samples are passing at the 1 test per placement day frequency, the reduced frequency testing will be reapplied.
  - 6. If blended aggregate gradations are not within the tarantula curve limits by the second department test:
    - Provide a new mix design with an increased cementitious content.
    - If the mix design already has a cementitious content of 565 or more pounds per cubic yard, provide a new mix design.
    - If the contract requires optimized aggregate gradations under 501.2.7.4.2.1(2), stop concrete production and submit a new mix design.
- (2) If the contractor's 4-point running average or a department test result of the volumetric percent retained exceeds the tarantula curve limits by more than 1.0 percent on one or more sieves, stop concrete production and submit a new mix design.
- <sup>(3)</sup> Department and contractor will sample and test aggregate of the new mix design at the frequency defined in 710.5.6.1.

# 710.5.7.2 Combined Aggregate Gradations

- (1) If the contractor's 4-point running average or a department test result of the percent passing by weight exceeds the combined aggregate gradation limits by less than or equal to 1.0 percent on a single sieve size, do the following:
  - 1. Notify the other party immediately.
  - 2. Perform corrective action documented in the QC plan or as the engineer approves.
  - 3. Document and provide corrective action results to the engineer as soon as they are available.
  - 4. Department will conduct two tests within the next business day after corrective action is complete.
  - 5. If blended aggregate gradations are within the combined aggregate gradation limits by the second department test:
    - Continue with concrete production.
    - Contractor will include a break in the 4-point running average.
    - For Class I: Pavements, department will discontinue reduced frequency testing and will test at a frequency of 1 test per placement day. Once 5 consecutive samples are passing at the 1 test per placement day frequency, the reduced frequency testing will be reapplied.
  - 6. If blended aggregate gradations are not within the combined aggregate gradation limits by the second department test, stop concrete production and submit a new mix design.
- (2) If the contractor's 4-point running average or a department test result of the percent passing by weight exceeds the combined aggregate gradation limits by more than 1.0 percent on one or more sieves, stop concrete production and submit a new mix design.
- <sup>(3)</sup> Department and contractor will sample and test aggregate of the new mix design at the frequency defined in 710.5.6.1.

# 715.3.1.1 General

Replace paragraphs three and four with the following effective with the November 2021 letting:

- (3) Cast a set of 3 additional 6"x12" cylinders and test the concrete surface resistivity according to AASHTO T358. Perform this testing at least once per lot if total contract quantities are greater than or equal to the following:
  - 20,000 square yards for pavements.
  - 5,000 linear feet for barriers.
  - 500 cubic yards for structure concrete.

Submit the resistivity to the nearest tenth into MRS for information only. Resistivity testing is not required for the following:

- Lot with less than 3 sublots.
- Concrete items classified as ancillary.
- Concrete placed under the following bid items:
  - Concrete Pavement Approach Slab
  - Concrete Masonry Culverts
  - Concrete Masonry Retaining Walls
- (4) Test the air void system at least once per lot and enter the SAM number in MRS for information only. SAM testing is not required for the following:
  - For lots with less than 3 sublots.
  - High early strength (HES) concrete.
  - Special high early strength (SHES) concrete.
  - Concrete placed under the following bid items:
    - Concrete Pavement Approach Slab
    - Concrete Masonry Culverts
    - Concrete Masonry Retaining Walls
    - Steel Grid Floor Concrete Filled
    - Crash Cushions Permanent
    - Crash Cushions Permanent Low Maintenance
    - Crash Cushions Temporary

# 715.3.1.2.3 Lots by Cubic Yard

Replace the entire text with the following effective with the November 2021 letting:

(1) Define standard lots and sublots conforming to the following:

#### TABLE 715-1 CLASS I - LOT AND SUBLOT SIZES

CONCRETE CLASSIFICATION	LOT SIZE	SUBLOT SIZE	NUMBER OF SUBLOTS PER LOT	
Class I: Pavement	1250 cubic yards	250 cubic yards	5	
Class I: Structures	250 cubic yards	50 cubic yards	5	
Class I: Cast-in-Place Barrier	500 cubic yards	100 cubic yards	5	

(2) The contractor may include sublots less than or equal to 25 percent of the standard volume in the previous sublot. For partial sublots exceeding 25 percent of the standard volume, notify the engineer who will direct additional testing to represent that partial sublot.

(3) An undersized lot is eligible for incentive payment under 715.5 if the lot has 3 or more sublots for that lot.

# 715.3.2 Strength Evaluation

Replace the entire text with the following effective with the November 2021 letting:

### 715.3.2.1 General

(1) The department will make pay adjustments for strength on a lot-by-lot basis using the compressive strength of contractor QC cylinders or the flexural strength of contractor QC beams.

# Effective with November 2021 Letting (revised)

- (2) Randomly select 2 QC specimens to test at 28 days for percent within limits (PWL). Compare the strengths of the 2 randomly selected QC specimens and determine the 28-day sublot average strength as follows:
  - If the lower strength divided by the higher strength is 0.9 or more, average the 2 QC specimens.
  - If the lower strength divided by the higher strength is less than 0.9, break one additional specimen and average the 2 higher strength specimens.

# 715.3.2.2 Removal and Replacement

#### 715.3.2.2.1 Pavement

- (1) If a sublot strength is less than 2500 psi in compressive strength or 500 psi in flexural strength, the department may direct the contractor to core that sublot to determine its structural adequacy and whether to direct removal.
- (2) If the engineer directs coring, obtain three cores from the sublot in question. Have an HTCP-certified PCC technician I perform or observe core sampling according to AASHTO T24.
- (3) Have an independent consultant test cores according to AASHTO T24.
- (4) The department will assess concrete for removal and replacement based on a sublot-by-sublot analysis of core strength. Perform coring and testing, fill core holes with an engineer-approved non-shrink grout or concrete, and provide traffic control during coring.
- (5) The sublot pavement is conforming if the compressive strengths of all cores from the sublot are 2500 psi or greater.
- (6) The sublot pavement is nonconforming if the compressive strengths of any core from the sublot is less than 2500 psi. The department may direct removal and replacement or otherwise determine the final disposition of nonconforming material as specified in 106.5.

# 715.3.2.2.2 Structures and Cast-in-Place Barrier

- (1) The department will evaluate the sublot for possible removal and replacement if the 28-day sublot average compressive strength is lower than f'c minus 500 psi. The value of f'c is the design stress the plans show. The department may assess further strength price reductions or require removal and replacement only after coring the sublot.
- (2) The engineer may initially evaluate the sublot strength using a non-destructive method. Based on the results of non-destructive testing, the department may accept the sublot at the previously determined pay for the lot, or direct the contractor to core the sublot.
- (3) If the engineer directs coring, obtain three cores from the sublot in question. Have an HTCP-certified PCC technician I perform or observe core sampling according to AASHTO T24. Determine core locations, subject to the engineer's approval, that do not interfere with structural steel.
- (4) Have an independent consultant test cores according to AASHTO T24.
- <sup>(5)</sup> The department will assess concrete for removal and replacement based on a sublot-by-sublot analysis of core strength. Perform coring and testing, fill core holes with an engineer-approved non-shrink grout or concrete, and provide traffic control during coring.
- <sup>(6)</sup> If the 3-core average is greater than or equal to 85 percent of f'c, and no individual core is less than 75 percent of f'c, the engineer will accept the sublot at the previously determined pay for the lot. If the 3-core average is less than 85 percent of f'c, or an individual core is less than 75 percent of f'c, the engineer may require the contractor to remove and replace the sublot. The department may direct removal and replacement or otherwise determine the final disposition of nonconforming material as specified in 106.5.

# 715.3.3 Aggregate

Replace the entire text with the following effective with the November 2021 letting:

# 715.3.3.1 General

(1) Except as allowed for small quantities in 710.2, test aggregate conforming to 710.5.6.

# 715.3.3.2 Structures

- (1) In addition to the aggregate testing required under 710.5.6, determine the fine and coarse aggregate moisture content for each sample.
- <sup>(2)</sup> Calculate target batch weights for each mix when production of that mix begins. Whenever the moisture content of the fine or coarse aggregate changes by more than 0.5 percent, adjust the batch weights to maintain the design w/cm ratio.

# 715.5 Payment

Replace the entire text with the following effective with the November 2021 letting:
--

#### 715.5.1 General

(1) The department will pay incentive for compressive strength under the following bid items:

ITEM NUMBER	DESCRIPTION	UNIT
715.0502	Incentive Strength Concrete Structures	DOL
715.0603	Incentive Strength Concrete Barrier	DOL
715.0715	Incentive Flexural Strength Concrete Pavement	DOL
715.0720	Incentive Compressive Strength Concrete Pavement	DOL

(2) Incentive payment may be more or less than the amount the schedule of items shows.

- <sup>(3)</sup> The department will administer disincentives for strength under the Disincentive Strength Concrete Structures, Disincentive Strength Concrete Barrier, Disincentive Flexural Strength Concrete Pavement, and Disincentive Compressive Strength Concrete Pavement, administrative items.
- (4) The pay factor that is calculated from the equations in 715.5.2(2) and 715.5.3(2) will be applied to the unit costs listed below:
  - Pavement: \$45 per SY.
  - Structure: \$635 per CY.
  - Cast-in-place barrier: \$75 per LF.
- (5) 28-day strength average for a lot is the average of the individual sublot strengths within the given lot.
- <sup>(6)</sup> The department will not pay a strength incentive for concrete that is nonconforming in another specified property, for ancillary concrete accepted based on tests of class I concrete, or for high early strength concrete unless placed in pavement gaps as allowed under 715.3.1.2.2.
- (7) Submit test results to the department electronically using MRS software. The department will validate contractor data before determining pay adjustments.
- (8) All coring and testing costs under 715.3.2.2 including filling core holes and providing traffic control during coring are incidental to the contract.

# 715.5.2 Compressive Strength

- (1) The department will measure PWL relative to strength lower specification limits as follows:
  - Compressive strength of 3700 psi for pavements.
  - Compressive strength of 4000 psi for structures and cast-in-place barrier.
- (2) The department will adjust pay for each lot using equation "Comp2022" as follows:

Percent within Limits (PWL)	Pay Factor (%)
>= 90 to 100	(1/5 x PWL) + 82
>= 85 to < 90	100
>= 50 to < 85	(5/7 x PWL) + (275/7)
< 50	50 <sup>[1]</sup>

<sup>[1]</sup> Any material resulting in a lot PWL value less than 50 will be evaluated according to 715.3.2. In the event the material remains in place, it will be paid at 50 percent of the contract unit price of the concrete bid item.

(3) The department will not pay incentive if the lot standard deviation is greater than the following:

- 400 psi for pavement.
- 350 psi for structure and cast-in-place barrier
- (4) For lots with less than 3 sublots, there is no incentive but the department will reduce pay by 50 percent of the contract unit price for sublots with an average compressive strength below the following:
  - 3700 psi for pavements.
  - 4000 psi for structures and cast-in-place barrier.

# 715.5.3 Flexural Strength

(1) The department will measure PWL relative to strength lower specification limits as follows:

- Flexural strength of 650 psi for pavements.

(2) The department will adjust pay for each lot using equation "Flex2022" as follows:

Percent within Limits (PWL)	Pay Factor (%)
>= 90 to 100	(2/5 x PWL) + 64
>= 85 to < 90	100

>= 50 to < 85

< 50

(5/7 x PWL) + (275/7) 50<sup>[1]</sup>

<sup>[1]</sup> Material resulting in a lot PWL value less than 50 will be evaluated according to 715.3.2. In the event the material remains in place, it will be paid at 50 percent of the contract unit price of the concrete bid item.

(3) The department will not pay incentive if the lot standard deviation is greater than 60 psi.

(4) For lots with less than 3 sublots, there is no incentive but the department will reduce pay by 50 percent of the contract unit price for sublots with an average flexural strength below 650 psi.

ERRATA

# 460.2.2.3 Aggregate Gradation Master Range

Correct errata by adding US Standard equivalent sieve sizes.

(1) Ensure that the aggregate blend, including recycled material and mineral filler, conforms to the gradation requirements in table 460-1. The values listed are design limits; production values may exceed those limits.

# TABLE 460-1 AGGREGATE GRADATION MASTER RANGE AND VMA REQUIREMENTS

	PERCENT PASSING DESIGNATED SIEVES							
	NOMINAL SIZE							
SIEVE	No. 1 (37.5 mm) (1 1/2 inch)	No. 2 (25.0 mm) (1 inch)	No.3 (19.0 mm) (3/4 inch)	No. 4 (12.5 mm) (1/2 inch)	No. 5 (9.5 mm) (3/8 inch)	No. 6 (4.75 mm) (3/16 inch)	SMA No. 4 (12.5 mm) (1/2 inch)	SMA No. 5 (9.5 mm) (3/8 inch)
50.0-mm (2-inch)	100							
37.5-mm (1 1/2-inch)	90 - 100	100						
25.0-mm (1-inch)	90 max	90 - 100	100					
19.0-mm (3/4-inch)		90 max	90 - 100	100			100	
12.5-mm (1/2-inch)			90 max	90 - 100	100		90 - 97	100
9.5-mm (3/8-inch)				90 max	90 - 100	100	58 - 80	90 - 100
4.75-mm (No. 4)		_	_		90 max	90 - 100	25 - 35	35 - 45
2.36-mm (No. 8)	15 - 41	19 - 45	23 - 49	28 - 58	32 - 67	90 max	15 - 25	18 - 28
1.18-mm (No. 16)						30 - 55		
0.60-mm (No. 30)							18 max	18 max
0.075-mm (No. 200)	0 - 6.0	1.0 - 7.0	2.0 - 8.0	2.0 - 10.0	2.0 - 10.0	6.0 - 13.0	8.0 - 11.0	8.0 - 12.0
% VMA	11.0 min	12.0 min	13.0 min	14.0 min <sup>[1]</sup>	15.0 min <sup>[2]</sup>	16.0 - 17.5	16.0 min	17.0 min

<sup>[1]</sup> 14.5 for LT and MT mixes.

<sup>[2]</sup> 15.5 for LT and MT mixes.

#### 715.5.1 General

Correct the bid item number for Incentive Compressive Strength Concrete Pavement.

(1) The department will pay incentive for compressive strength under the following bid items:

ITEM NUMBER	DESCRIPTION	UNIT
715.0502	Incentive Strength Concrete Structures	DOL
715.0603	Incentive Strength Concrete Barrier	DOL
715.0715	Incentive Flexural Strength Concrete Pavement	DOL
715.0720	Incentive Compressive Strength Concrete Pavement	DOL

# Effective with December 2017 Letting

# ADDITIONAL SPECIAL PROVISION 7

- A. Reporting 1<sup>st</sup> Tier and DBE Payments During Construction
  - 1. Comply with reporting requirements specified in the department's Civil Rights Compliance, Contractor's User Manual, Sublets and Payments.
  - Report payments to all DBE firms within 10 calendar days of receipt of a progress payment by the department or a contractor for work performed, materials furnished, or materials stockpiled by a DBE firm. Report the payment as specified in A(1) for all work satisfactorily performed and for all materials furnished or stockpiled.
  - 3. Report payments to all first tier subcontractor relationships within 10 calendar days of receipt of a progress payment by the department for work performed. Report the payment as specified in A(1) for all work satisfactorily performed.
  - 4. All tiers shall report payments as necessary to comply with the DBE payment requirement as specified in A(2).
  - 5. Require all first tier relationships, DBE firms and all other tier relationships necessary to comply with the DBE payment requirement in receipt of a progress payment by contractor to acknowledge receipt of payment as specified in A(1), (2), (3) and (4).
  - 6. All agreements made by a contractor shall include the provisions in A(1), (2), (3), (4) and (5), and shall be binding on all first tier subcontractor relationships and all contractors and subcontractors utilizing DBE firms on the project.
- B. Costs for conforming to this special provision are incidental to the contract.

NOTE: CRCS Prime Contractor payment is currently not automated and will need to be manually loaded into the Civil Rights Compliance System. Copies of prime contractor payments received (check or ACH) will have to be forwarded to <a href="mailto:paul.ndon@dot.wi.gov">paul.ndon@dot.wi.gov</a> within 5 days of payment receipt to be logged manually.

\*\*\*Additionally, for information on Subcontractor Sublet assignments, Subcontractor Payments and Payment Tracking, please refer to the CRCS Payment and Sublets manual at:

https://wisconsindot.gov/Documents/doing-bus/civil-rights/labornwage/crcs-payments-subletsmanual.pdf

# ADDITIONAL SPECIAL PROVISION 9

# Electronic Certified Payroll or Labor Data Submittal

(1) Use the department's Civil Rights Compliance System (CRCS) to electronically submit certified payroll reports for contracts with federal funds and labor data for contracts with state funds only. Details are available online through the department's highway construction contractor information (HCCI) site on the Labor, Wages, and EEO Information page at:

https://wisconsindot.gov/Pages/doing-bus/civil-rights/labornwage/default.aspx

(2) Ensure that all tiers of subcontractors, including all trucking firms, either submit their weekly certified payroll reports (contracts with federal funds) or labor data (contracts with state funds only) electronically through CRCS. These payrolls or labor data are due within seven calendar days following the close of the payroll period. Every firm providing physical labor towards completing the project is a subcontractor under this special provision.

(3) Upon receipt of contract execution, promptly make all affected firms aware of the requirements under this special provision and arrange for them to receive CRCS training as they are about to begin their submittals. The department will provide training either in a classroom setting at one of our regional offices or by telephone. Contact Paul Ndon at (414) 438-4584 to schedule the training.

(4) The department will reject all paper submittals for information required under this special provision. All costs for conforming to this special provision are incidental to the contract.

(5) Firms wishing to export payroll/labor data from their computer system into CRCS should have their payroll coordinator contact Paul Ndon at <u>paul.ndon@dot.wi.gov</u>. Not every contractor's payroll system is capable of producing export files. For details, see Section 4.8 CPR Auto Submit (Data Mapping) on pages 49-50; 66-71 of the CRCS Payroll Manual at:

https://wisconsindot.gov/Documents/doing-bus/civil-rights/labornwage/crcs-payroll-manual.pdf

### **Non-discrimination Provisions**

During the performance of this contract, the contractor, for itself, its assignees, and successors in interest (hereinafter referred to as the "contractor") agrees as follows:

**1. Compliance with Regulations:** The contractor (hereinafter includes consultants) will comply with the Acts and the Regulations relative to Non-discrimination in Federally-assisted programs of the U.S. Department of Transportation, Federal Highway Administration, as they may be amended from time to time, which are herein incorporated by reference and made a part of this contract.

**2. Non-discrimination:** The contractor, with regard to the work performed by it during the contract, will not discriminate on the grounds of race, color, or national origin in the selection and retention of subcontractors, including procurements of materials and leases of equipment. The contractor will not participate directly or indirectly in the discrimination prohibited by the Acts and the Regulations, including employment practices when the contract covers any activity, project, or program set forth in Appendix B of 49 CFR Part 21.

**3.** Solicitations for Subcontracts, Including Procurements of Materials and Equipment: In all solicitations, either by competitive bidding, or negotiation made by the contractor for work to be performed under a subcontract, including procurements of materials, or leases of equipment, each potential subcontractor or supplier will be notified by the contractor of the contractor's obligations under this contract and the Acts and the Regulations relative to Non-discrimination on the grounds of race, color, or national origin.

**4. Information and Reports:** The contractor will provide all information and reports required by the Acts, the Regulations, and directives issued pursuant thereto and will permit access to its books, records, accounts, other sources of information, and its facilities as may be determined by the Recipient or the Federal Highway Administration to be pertinent to ascertain compliance with such Acts, Regulations, and instructions. Where any information required of a contractor is in the exclusive possession of another who fails or refuses to furnish the information, the contractor will so certify to the Recipient or the Federal Highway Administration, as appropriate, and will set forth what efforts it has made to obtain the information.

**5. Sanctions for Noncompliance:** In the event of a contractor's noncompliance with the Nondiscrimination provisions of this contract, the Recipient will impose such contract sanctions as it or the Federal Highway Administration may determine to be appropriate, including, but not limited to:

- a. Withholding payments to the contractor under the contract until the contractor complies; and/or
- b. Cancelling, terminating, or suspending a contract, in whole or in part.

**6. Incorporation of Provisions:** The contractor will include the provisions of paragraphs one through six in every subcontract, including procurements of materials and leases of equipment, unless exempt by the Acts, the Regulations and directives issued pursuant thereto. The contractor will take action with respect to any subcontract or procurement as the Recipient or the Federal Highway Administration may direct as a means of enforcing such provisions including sanctions for noncompliance. Provided, that if the contractor becomes involved in, or is threatened with litigation by a subcontractor, or supplier because of such direction, the contractor may request the Recipient to enter into any litigation to protect the interests of the Recipient. In addition, the contractor may request the United States to enter into the litigation to protect the interests of the united States.

# During the performance of this contract, the contractor, for itself, its assignees, and successors in interest (hereinafter referred to as the "contractor") agrees to comply with the following non-discrimination statutes and authorities; including but not limited to:

#### **Pertinent Non-Discrimination Authorities:**

- Title VI of the Civil Rights Act of 1964 (42 U.S.C. § 2000d et seq., 78 stat. 252), (prohibits discrimination on the basis of race, color, national origin); and 49 CFR Part 21.
- The Uniform Relocation Assistance and Real Property Acquisition Policies Act of 1970, (42 U.S.C. § 4601), (prohibits unfair treatment of persons displaced or whose property has been acquired because of Federal or Federal-aid programs and projects);
- Federal-Aid Highway Act of 1973, (23 U.S.C. § 324 et seq.), (prohibits discrimination on the basis of sex);
- Section 504 of the Rehabilitation Act of 1973, (29 U.S.C. § 794 et seq.), as amended, (prohibits discrimination on the basis of disability); and 49 CFR Part 27;
- The Age Discrimination Act of 1975, as amended, (42 U.S.C. § 6101 et seq.), (prohibits discrimination on the basis of age);
- Airport and Airway Improvement Act of 1982, (49 USC § 471, Section 47123), as amended, (prohibits discrimination based on race, creed, color, national origin, or sex);
- The Civil Rights Restoration Act of 1987, (PL 100-209), (Broadened the scope, coverage and applicability of Title VI of the Civil Rights Act of 1964, The Age Discrimination Act of 1975 and Section 504 of the Rehabilitation Act of 1973, by expanding the definition of the terms "programs or activities" to include all of the programs or activities of the Federal-aid recipients, sub-recipients and contractors, whether such programs or activities are Federally funded or not);
- Titles II and III of the Americans with Disabilities Act, which prohibit discrimination on the basis of disability in the operation of public entities, public and private transportation systems, places of public accommodation, and certain testing entities (42 U.S.C. §§ 12131-12189) as implemented by Department of Transportation regulations at 49 C.F.R. parts 37 and 38;
- The Federal Aviation Administration's Non-discrimination statute (49 U.S.C. § 47123) (prohibits discrimination on the basis of race, color, national origin, and sex);

- Executive Order 12898, Federal Actions to Address Environmental Justice in Minority Populations and Low-Income Populations, which ensures Non-discrimination against minority populations by discouraging programs, policies, and activities with disproportionately high and adverse human health or environmental effects on minority and low-income populations;
- Executive Order 13166, Improving Access to Services for Persons with Limited English Proficiency, and resulting agency guidance, national origin discrimination includes discrimination because of Limited English proficiency (LEP). To ensure compliance with Title VI, you must take reasonable steps to ensure that LEP persons have meaningful access to your programs (70 Fed. Reg. at 74087 to 74100);
- Title IX of the Education Amendments of 1972, as amended, which prohibits you from discriminating because of sex in education programs or activities (20 U.S.C. 1681 et seq).

#### **Effective November 2020 letting**

#### **BUY AMERICA PROVISION**

All steel and iron materials permanently incorporated in this project shall be domestic products and all manufacturing and coating processes for these materials from smelting forward in the manufacturing process must have occurred within the United States. Coating includes epoxy coating, galvanizing, painting and any other coating that protects or enhances the value of a material subject to the requirements of Buy America. The exemption of this requirement is the minimal use of foreign materials if the total cost of such material permanently incorporated in the product does not exceed one-tenth of one percent (1/10 of 1%) of the total contract cost or \$2,500.00, whichever is greater. For purposes of this paragraph, the cost is that shown to be the value of the subject products as they are delivered to the project. The contractor shall take actions and provide documentation conforming to CMM 2-28.5 to ensure compliance with this "Buy America" provision.

https://wisconsindot.gov/rdwy/cmm/cm-02-28.pdf

Upon completion of the project certify to the engineer, in writing using department form DT4567, that all steel, iron, and coating processes for steel or iron incorporated into the contract work conform to these "Buy America" provisions. Attach a list of exemptions and their associated costs to the certification form. Department form DT4567 is available at:

https://wisconsindot.gov/Documents/formdocs/dt4567.docx



	Proposal Schedule of Items	Page 1 of 4
Proposal ID: 2021121	14017 Project(s): 5728-00-73	
	Federal ID(s): N/A	
SECTION: 0001	Contract Items	
Alt Set ID:	Alt Mbr ID:	

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	203.0260 Removing Structure Over Waterway Minimal Debris (structure) 01. P-13-224	1.000 EACH	·	·
0004	204.9060.S Removing (item description) 01. Concrete Posts	6.000 EACH		·
0006	205.0100 Excavation Common	187.000 CY	··	·
0008	206.1000 Excavation for Structures Bridges (structure) 01. B-13-691	LS	LUMP SUM	
0010	210.1500 Backfill Structure Type A	216.000 TON		
0012	213.0100 Finishing Roadway (project) 01. 5728- 00-73	1.000 EACH	·	
0014	305.0110 Base Aggregate Dense 3/4-Inch	10.000 TON		
0016	305.0120 Base Aggregate Dense 1 1/4-Inch	118.000 TON	·	·
0018	312.0110 Select Crushed Material	204.000 TON	·	·
0020	455.0605 Tack Coat	10.000 GAL	·	
0022	460.2000 Incentive Density HMA Pavement	30.000 DOL	1.00000	30.00
0024	460.5223 HMA Pavement 3 LT 58-28 S	25.000 TON	·	
0026	460.5224 HMA Pavement 4 LT 58-28 S	19.000 TON		
0028	502.0100 Concrete Masonry Bridges	154.000 CY	·	·
0030	502.3200 Protective Surface Treatment	116.000 SY	·	·
0032	502.3210 Pigmented Surface Sealer	62.000 SY		



	Proposal Schedule of Items	Page 2 of 4
Proposal ID: 2021121	4017 Project(s): 5728-00-73	
	Federal ID(s): N/A	
SECTION: 0001	Contract Items	
Alt Set ID:	Alt Mbr ID:	

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0034	505.0400 Bar Steel Reinforcement HS Structures	3,160.000 LB		
0036	505.0600 Bar Steel Reinforcement HS Coated Structures	22,070.000 LB	;	
0038	516.0500 Rubberized Membrane Waterproofing	18.000 SY		
0040	550.0500 Pile Points	8.000 EACH	·	
0042	550.1100 Piling Steel HP 10-Inch X 42 Lb	220.000 LF		
0044	606.0300 Riprap Heavy	129.000 CY		
0046	612.0406 Pipe Underdrain Wrapped 6-Inch	134.000 LF		
0048	618.0100 Maintenance And Repair of Haul Roads (project) 01. 5728-00-73	1.000 EACH		
0050	619.1000 Mobilization	1.000 EACH		
0052	624.0100 Water	3.000 MGAL		
0054	625.0500 Salvaged Topsoil	390.000 SY		
0056	627.0200 Mulching	610.000 SY		
0058	628.1504 Silt Fence	405.000 LF		
0060	628.1520 Silt Fence Maintenance	615.000 LF		
0062	628.1905 Mobilizations Erosion Control	3.000 EACH	·	
0064	628.1910 Mobilizations Emergency Erosion Control	3.000 EACH		



	Proposal Schedule of Items	Page 3 of 4
Proposal ID: 2021121	4017 Project(s): 5728-00-73	
	Federal ID(s): N/A	
SECTION: 0001	Contract Items	
Alt Set ID:	Alt Mbr ID:	

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0066	628.2033 Erosion Mat Class III Type B	24.000 SY	·	
0068	628.6005 Turbidity Barriers	164.000 SY	·	
0070	628.6505 Soil Stabilizer Type A	0.010 ACRE		
0072	628.7504 Temporary Ditch Checks	15.000 LF		
0074	628.7560 Tracking Pads	2.000 EACH		
0076	629.0205 Fertilizer Type A	0.300 CWT		
0078	630.0120 Seeding Mixture No. 20	10.000 LB		
0080	630.0160 Seeding Mixture No. 60	3.000 LB		
0082	630.0300 Seeding Borrow Pit	6.000 LB		
0084	630.0500 Seed Water	16.000 MGAL		·
0086	634.0612 Posts Wood 4x6-Inch X 12-FT	4.000 EACH		
0088	637.2230 Signs Type II Reflective F	12.000 SF		
0090	638.2602 Removing Signs Type II	8.000 EACH		
0092	638.3000 Removing Small Sign Supports	8.000 EACH		·
0094	642.5001 Field Office Type B	1.000 EACH		
0096	643.0420 Traffic Control Barricades Type III	528.000 DAY		
0098	643.0705 Traffic Control Warning Lights Type A	968.000 DAY		



	Proposal Schedule of Items	Page 4 of 4
Proposal ID: 20211214	1017 Project(s): 5728-00-73	
	Federal ID(s): N/A	
SECTION: 0001	Contract Items	
Alt Set ID:	Alt Mbr ID:	

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0100	643.0900 Traffic Control Signs	616.000 DAY		
0102	643.1050 Traffic Control Signs PCMS	14.000 DAY		
0104	643.5000 Traffic Control	1.000 EACH	·	·
0106	645.0111 Geotextile Type DF Schedule A	70.000 SY		
0108	645.0120 Geotextile Type HR	244.000 SY		
0110	645.0220 Geogrid Type SR	240.000 SY	·	
0112	650.4500 Construction Staking Subgrade	120.000 LF	·	
0114	650.5000 Construction Staking Base	120.000 LF		
0116	650.6500 Construction Staking Structure Layout (structure) 01. B-13-0691	LS	LUMP SUM	
0118	650.9910 Construction Staking Supplemental Control (project) 01. 5728-00-73	LS	LUMP SUM	
0120	650.9920 Construction Staking Slope Stakes	120.000 LF	·	
0122	690.0150 Sawing Asphalt	31.000 LF		
0124	715.0502 Incentive Strength Concrete Structures	924.000 DOL	1.00000	924.00
0126	999.2000.S Installing and Maintaining Bird Deterrent System (station) 01. Sta. 11+26	1.000 EACH		
	Section: 00	01	Total:	
			Total Bid:	·

## PLEASE ATTACH ADDENDA HERE



December 2, 2021

## Division of Transportation Systems Development

Bureau of Project Development 4822 Madison Yards Way, 4<sup>th</sup> Floor South Madison, WI 53705

Telephone: (608) 266-1631 Facsimile (FAX): (608) 266-8459

#### NOTICE TO ALL CONTRACTORS:

#### Proposal #17: 5728-00-73 Town of Perry, Drammen Vallery Rd Pleasant Valley Br Bridge,B-13-0691 Local Street Dane County

#### Letting of December 14, 2021

This is Addendum No. 01, which provides for the following:

#### Schedule of Items:

Revised Bid Item Quantities					
Pid Itom Itom Deparintion			Old	Revised	Proposal
Bid Item	Item Description	Unit	Quantity	Quantity	Total
643.0420	Traffic Control Barricades Type III	DAY	528	288	816
643.0705	Traffic Control Warning Lights Type A	DAY	968	528	1496
643.0900	Traffic Control Signs	DAY	616	336	952

#### Plan Sheets:

Revised Plan Sheets			
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)		
13	Miscellaneous Quantities (revisions to traffic control bid item quantities due to changes to the contract time)		

#### Other

Revise the Contract Completion Time from 25 working days to 40 working days (an increase of 15 working days).

#### Schedule of Items

Attached, dated December 2, 2021, are the revised Schedule of Items Pages 1-4.

#### **Plan Sheets**

The following  $8\frac{1}{2} \times 11$ -inch sheets are attached and made part of the plans for this proposal: Revised: 13.


The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist Proposal Management Section

END OF ADDENDUM



e



	Proposal Schedule of Items	Page 1 of 4
Proposal ID: 2021121	4017 Project(s): 5728-00-73	
	Federal ID(s): N/A	
SECTION: 0001	Contract Items	
Alt Set ID:	Alt Mbr ID:	

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	203.0260 Removing Structure Over Waterway Minimal Debris (structure) 01. P-13-224	1.000 EACH		
0004	204.9060.S Removing (item description) 01. Concrete Posts	6.000 EACH		
0006	205.0100 Excavation Common	187.000 CY	·	·
0008	206.1000 Excavation for Structures Bridges (structure) 01. B-13-691	LS	LUMP SUM	
0010	210.1500 Backfill Structure Type A	216.000 TON		
0012	213.0100 Finishing Roadway (project) 01. 5728- 00-73	1.000 EACH	·	
0014	305.0110 Base Aggregate Dense 3/4-Inch	10.000 TON		
0016	305.0120 Base Aggregate Dense 1 1/4-Inch	118.000 TON		
0018	312.0110 Select Crushed Material	204.000 TON		·
0020	455.0605 Tack Coat	10.000 GAL		·
0022	460.2000 Incentive Density HMA Pavement	30.000 DOL	1.00000	30.00
0024	460.5223 HMA Pavement 3 LT 58-28 S	25.000 TON		·
0026	460.5224 HMA Pavement 4 LT 58-28 S	19.000 TON		
0028	502.0100 Concrete Masonry Bridges	154.000 CY		
0030	502.3200 Protective Surface Treatment	116.000 SY		
0032	502.3210 Pigmented Surface Sealer	62.000 SY		



	Proposal Schedule of Items	Page 2 of 4
Proposal ID: 2021121	4017 Project(s): 5728-00-73	
	Federal ID(s): N/A	
SECTION: 0001	Contract Items	
Alt Set ID:	Alt Mbr ID:	

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0034	505.0400 Bar Steel Reinforcement HS Structures	3,160.000 LB		
0036	505.0600 Bar Steel Reinforcement HS Coated Structures	22,070.000 LB		
0038	516.0500 Rubberized Membrane Waterproofing	18.000 SY		
0040	550.0500 Pile Points	8.000 EACH		·
0042	550.1100 Piling Steel HP 10-Inch X 42 Lb	220.000 LF	·	. <u></u>
0044	606.0300 Riprap Heavy	129.000 CY	·	
0046	612.0406 Pipe Underdrain Wrapped 6-Inch	134.000 LF		
0048	618.0100 Maintenance And Repair of Haul Roads (project) 01. 5728-00-73	1.000 EACH		
0050	619.1000 Mobilization	1.000 EACH		
0052	624.0100 Water	3.000 MGAL		
0054	625.0500 Salvaged Topsoil	390.000 SY		
0056	627.0200 Mulching	610.000 SY	·	
0058	628.1504 Silt Fence	405.000 LF		
0060	628.1520 Silt Fence Maintenance	615.000 LF		
0062	628.1905 Mobilizations Erosion Control	3.000 EACH		. <u></u>
0064	628.1910 Mobilizations Emergency Erosion Control	3.000 EACH		



	Proposal Schedule of Items	Page 3 of 4
Proposal ID: 2021121	4017 Project(s): 5728-00-73	
	Federal ID(s): N/A	
SECTION: 0001	Contract Items	
Alt Set ID:	Alt Mbr ID:	

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0066	628.2033 Erosion Mat Class III Type B	24.000 SY		
0068	628.6005 Turbidity Barriers	164.000 SY		
0070	628.6505 Soil Stabilizer Type A	0.010 ACRE		<u> </u>
0072	628.7504 Temporary Ditch Checks	15.000 LF		
0074	628.7560 Tracking Pads	2.000 EACH		
0076	629.0205 Fertilizer Type A	0.300 CWT		
0078	630.0120 Seeding Mixture No. 20	10.000 LB		
0080	630.0160 Seeding Mixture No. 60	3.000 LB		
0082	630.0300 Seeding Borrow Pit	6.000 LB		
0084	630.0500 Seed Water	16.000 MGAL		
0086	634.0612 Posts Wood 4x6-Inch X 12-FT	4.000 EACH		
0088	637.2230 Signs Type II Reflective F	12.000 SF		
0090	638.2602 Removing Signs Type II	8.000 EACH		
0092	638.3000 Removing Small Sign Supports	8.000 EACH		
0094	642.5001 Field Office Type B	1.000 EACH		
0096	643.0420 Traffic Control Barricades Type III	816.000 DAY		
0098	643.0705 Traffic Control Warning Lights Type A	1,496.000 DAY		



Proposal Schedule of Items		Page 4 of 4
Proposal ID: 2021121	4017 Project(s): 5728-00-73	
	Federal ID(s): N/A	
SECTION: 0001	Contract Items	
Alt Set ID:	Alt Mbr ID:	

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0100	643.0900 Traffic Control Signs	952.000 DAY		
0102	643.1050 Traffic Control Signs PCMS	14.000 DAY		
0104	643.5000 Traffic Control	1.000 EACH	·	
0106	645.0111 Geotextile Type DF Schedule A	70.000 SY	·	
0108	645.0120 Geotextile Type HR	244.000 SY	·	
0110	645.0220 Geogrid Type SR	240.000 SY	·	
0112	650.4500 Construction Staking Subgrade	120.000 LF	·	
0114	650.5000 Construction Staking Base	120.000 LF	·	
0116	650.6500 Construction Staking Structure Layout (structure) 01. B-13-0691	LS	LUMP SUM	
0118	650.9910 Construction Staking Supplemental Control (project) 01. 5728-00-73	LS	LUMP SUM	
0120	650.9920 Construction Staking Slope Stakes	120.000 LF	·	·
0122	690.0150 Sawing Asphalt	31.000 LF	·	·
0124	715.0502 Incentive Strength Concrete Structures	924.000 DOL	1.00000	924.00
0126	999.2000.S Installing and Maintaining Bird Deterrent System (station) 01. Sta. 11+26	1.000 EACH		
	Section: 00	01	Total:	
			Total Bid:	