

December 6, 2022

Division of Transportation Systems Development

Bureau of Project Development 4822 Madison Yards Way, 4th Floor South Madison, WI 53705

Telephone: (608) 266-1631 Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #29: 1590-12-73, WISC 2023113 Rhinelander - Monico USH 8 AND USH 45 South Intersection USH 8 Oneida County

Letting of December 13, 2022

This is Addendum No. 02, which provides for the following:

Special Provisions:

Revised Special Provisions							
Article No.		Description					
3	Prosecution and Progress						

Schedule of Items:

Revised Bid Item Quantities									
			Proposal	Proposal	Proposal				
Bid Item	Item Description	Lloit	Unit Total Prior Quantity to Change (-)	Total After					
Did item	Item Description	Offic		Addendum					
			Addendum						
204.0120	Removing Asphaltic Surface Milling	SY	2985	-75	2910				

Added Bid Item Quantities									
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Quantity Added	Proposal Total After Addendum				
201.0115	Removing Asphaltic Surface Butt Joints	SY	0	75	75				

Plan Sheets:

Revised Plan Sheets							
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)						
6	Removed Shaping Shoulders Typ from Typical Section.						
10	Added Construction Detail for Butt Joint.						
26	Replaced any reference to STA 443+50 to STA 443+00.						
62	Added item of Removing Asphaltic Surface Butt Joints and revised quantity of Removing Asphaltic Surface Milling						

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist Proposal Management Section

ADDENDUM NO. 02 1590-12-73 December 6, 2022

Special Provisions

3. Prosecution and Progress

Replace entire article language with the following (revised STA 443+50 to STA 443+00):

Begin work within 10 calendar days after the engineer issues a written notice to do so.

Provide the time frame for construction of the project within the 2023 construction season to the engineer in writing within a month after executing the contract but at least 14 calendar days before the preconstruction conference. Assure that the time frame is consistent with the contract completion time. Upon approval, the engineer will issue the notice to proceed within 10 calendar days before the beginning of the approved time frame.

To revise the time frame, submit a written request to the engineer at least two weeks before the beginning of the intended time frame. The engineer will approve or deny that request based on the conditions cited in the request and its effect on the department's scheduled resources.

Traffic shall not be allowed to run on a milled surface during mainline removing asphaltic pavement milling operations following the conclusion of the working day because there will be less than 2 inches of remaining pavement.

The contractor shall cease or alter their work operations if traffic delays become longer than 15 minutes. If the contractor fails to comply with this special provision within a timely manner, the engineer shall suspend work operations according to Standard spec 108.5 (Limiting Operations) until the contractor complies with the 15-minute delay period. If the contractor continues operations, standard spec 105.3.2.3 (Unauthorized Work) may be enforced for any work completed during that time, and no additional compensation or additional time will be allowed due to such suspension of operations.

Stage 1

Complete the following construction operations under single lane closures with flagging operations:

- Remove USH 45 northbound stop sign and flashing beacon and replace the installation with a temporary stop sign with flags.
- Construct temporary asphalt pavement necessary to support traffic in future stages.

Stage 2

Complete the following construction operations with traffic staged as shown in the traffic control plans and utilizing single lane closures with flagging operations as necessary.

- Reconstruct the southern portion of USH 8 from Station 429+50 to Station 434+61 and from Station 436+77 to Station 443+00 up to and including the lower and middle layer of HMA pavement.
- Remove the radial turn lanes in the southwest and southeast quadrants of the USH 8 and USH 45 intersection.
- Begin preparation for removal and replacement of the culvert pipes carrying Monico Creek below USH 45.

Stage 3

Complete the following construction operations with USH 8 traffic staged as shown in the traffic control plans and utilizing single lane closures with flagging operations as necessary. Close USH 45 to traffic within the project limits and detour USH 45 traffic as shown in the project plans. Close USH 45 no earlier than noon on Monday and reopen USH 45 no later than noon on the following Friday.

- Continue work as described under Stage 2 above.
- Reconstruct the southern portion of USH 8 from Station 429+50 to Station 443+00 up to and including lower and middle layer of HMA pavement.
- Reconstruct USH 45 north of the culvert installations, from Station 1415+00 to the USH 8 intersection, up to and including lower and middle layer of HMA pavement.
- Remove and replace two culvert pipes carrying Monico Creek below USH 45 as shown in the plans, repave the roadway temporary asphalt, and install concrete barrier wall and crash cushions prior to reopening the road to traffic.

Stage 4

Complete the following construction operations with USH 8 and USH 45 traffic staged as shown in the traffic control plans and utilizing single lane closures with flagging operations as necessary.

- Reconstruct the median and left turn lane portions of USH 8 from Station 429+50 to Station 434+61 and Station 436+10 to Station 443+00 up to the lower and middle layer of HMA pavement.
- Continue work on Structure B-43-64 and preparation for removal and replacement of the second pair of culvert pipes carrying Monico Creek below USH 45.

Stage 5

Complete the following construction operations with USH 8 and USH 45 traffic staged as shown in the traffic control plans and utilizing single lane closures with flagging operations as necessary.

- Reconstruct the USH 8 westbound lane and shoulder from Station 429+50 to Station 443+00 up to the lower and middle layer of HMA pavement along the north side of USH 8.
- Continue work on Structure B-43-64 and preparation for removal and replacement of the second pair of culvert pipes carrying Monico Creek below USH 45.

Stage 6

Complete the following construction operations with USH 8 traffic staged as shown in the traffic control plans and utilizing single lane closures with flagging operations as necessary. Close USH 45 to traffic within the project limits and detour USH 45 traffic as shown in the project plans. Close USH 45 no earlier than noon on Monday and reopen USH 45 no later than noon on the following Friday.

- Continue reconstruction of USH 8 westbound lane and shoulder from Station 429+50 to Station 443+00 up to the lower and middle layer of HMA pavement along the north side of USH 8.
- Remove and replace the remaining two culvert pipes carrying Monico Creek below USH 45, repave any portions of USH 45 not previously reconstructed with both lower layers of HMA pavement, and install concrete barrier wall and crash cushions prior to reopening the road to traffic.

Stage 7

Begin Stage 7 by maintaining traffic configuration on USH 8 from previous stage to complete USH 8 westbound construction. Completed the following construction operations with traffic staged as per the previous stage configuration.

• Complete USH 8 westbound construction, including HMA pavement upper layer surfacing and guardrail installation.

Upon completion of USH 8 westbound work, switch traffic to Stage 7 configuration as shown in the traffic control plans and utilize single lane closures with flagging operations and shoulder closures with flagging operations to complete remaining construction operations.

• Complete remainder of HMA pavement upper layer surfacing on USH 8 and USH 45.

Complete all remaining incidental construction.

Fish Spawning

There shall be no instream disturbance of Monico Creek at Station 1413+12 as a result of construction activity under or for this contract, from March 1, 2023 to June 15, 2023 both dates inclusive, in order to avoid adverse impacts upon the spawning of fish.

Any change to this limitation will require submitting a written request by the contractor to the engineer, subsequent review and concurrence by the Department of Natural Resources in the request, and final approval by the engineer. The approval will include all conditions to the request as mutually agreed upon by WisDOT and DNR.

Northern Long-eared Bat (Myotis septentrionalis)

Northern long-eared bats (NLEB) have the potential to inhabit the project limits because they roost in trees, bridges and culverts. Roosts may not have been observed on this project, but conditions to support the species exist. The species and all active roosts are protected by the Federal Endangered Species Act. If an individual bat or active roost is encountered during construction operations, stop work and notify the engineer and the WisDOT Regional Environmental Coordinator (REC).

Ensure all operators, employees, and subcontractors working in areas of known or presumed bat habitat are aware of environmental commitments and avoidance and minimization measures (AMMs) to protect both bats and their habitat.

Direct temporary lighting, if used, away from wooded areas during the bat active season: April 1 to October 31, both dates inclusive. To avoid adverse impacts upon the NLEBs, no tree clearing is allowed between April 1 and October 31, both dates inclusive.

If the required tree clearing is not completed by March 31, the department will suspend all tree clearing and associated work directly impacted by clearing. The department will issue a notice to proceed with clearing and associated work directly impacted by clearing after consulting with the United States Fish and Wildlife Service (USFWS).

Tree clearing is limited to that which is specified in the plans. If additional trees with a 3-inch or greater diameter at breast height (dbh) need to be removed, no tree clearing shall occur without prior approval from the engineer, following coordination with the WisDOT REC. Additional tree removal beyond the area originally specified will require consultation with the USFWS and may require a bat presence/absence or visual emergency survey. Notify the engineer if additional clearing cannot be avoided to begin coordination with the WisDOT REC. The WisDOT REC will initiate consultation with the USFWS and determine if a survey is necessary. Submit a schedule and description of clearing operations with the ECIP 14 days prior to any clearing operations. The department will determine, based on schedule and scope of work, what additional erosion control measures shall be implemented prior to the start of clearing operations, and list those additional measures in the ECIP.


Schedule of Items


Attached, dated December 6, 2022, are the revised Schedule of Items Pages 1 and 9.


Plan Sheets

The following $8\frac{1}{2} \times 11$ -inch sheets are attached and made part of the plans for this proposal: Revised: 6, 10, 26, and 62.

END OF ADDENDUM







		L															IC R) 1 evi	59 ise	0- d	12-1 She	No. 02 73 eet 62 , 2022] <mark>1</mark>
204.0120	MILLING Sy 1,960 1,960	2,910		204.0165	REMOVING GUARDRAIL	LF	130	086		1,265						204.0245	SEWER 12-INCH	LF	53	77	40	170	SHEFT
ALTIC SURFACE 204.0110 204.0115	SURFACE BUTTJOINTS SY SY 960 70 37	1,065	REMOVING GUARDRAIL			LOCATION	USH 45, LT	USH 45, LT		TOTAL				REMOVING STORM SEWER		204.0220	REMOVING INLETS	EACH	1	1	1	m	
REMOVING ASPHALTIC SURFACE 204.0110	LOCATION LOCATION USH8 USH8 USH8 USH8	TOTALS 1.	REMOVING				1418+18 USH							REMOVING S				LOCATION	USH 45, LT	USH 45, RT	USH 8, RT	TOTAL	
	STATION STATION 427+00 - 429+50 429+50 - 439+13 423+50 - 448+14					SE STATION	3 1412+48 - 3 1417±10 -	429+19 -										5E STATION		+	437+35		MISCELLANFOLIS OLIANTITIES
						<u>S1</u>												STAGE	2	2	2		MISCELLAR
	. g			204.0100 REMOVING	CONCRETE	PAVEMENT		-	1	45C	1	20	150	001	-	667	1114	720	488	1	-	4,995	COLINTY: ONFIDA
	201.0105 201.0205 CLEARING GRUBBING STA STA 2 2 3 3	s.		204.0150 REMOVING	CURB &	GUITER	518	57	131	703	595		1	52	160	1		1	1	150	292	2,685	
CLEARING & GRUBBING	2 STATION LOCATION 433400 USH 8, RT 443400 USH 8, RT	TOTALS	CONCRETE REMOVAL ITEMS			LOCATION	USH 45 MEDIAN ISLAND	USH 45, RT	USH 45, LT	USH 45 NB TO USH 8 EB RT	USH 8 EB TO USH 45 SB RT	USH 8, RT	USH 45 LISH 45	USH 45, LT	USH, 45, RT	USH 8	USH 8 LISH 8	USH 45	USH 45	USH 8, LT	USH 8, RT	тота	HMV- LISH R
	STATION TO 431+00 - 440+00 -					STATION	1418+18	1418+44	1418+28	1418+60	1417+59	443+00	1413+23	1417+37	1418+20	434+60	443+00	1412+69	1415+05	428+91	447+83		
	I					STATION	1415+62 -	1418+20 -	1417+37 -		1416+50 -	442+15 -	1412+69 -		1416+65 -	429+50 -	436+10 - 479+50 -	1410+00 -	1413+23 -	427+40 -	444+91 -		1590-12-73
						ST	-	-		-	-					-	-	-					



	Proposal Schedule of Items	Page 1 of 9
Proposal ID: 202212	13029 Project(s): 1590-12-73	
	Federal ID(s): WISC 2023113	
SECTION: 0001	Contract Items	
Alt Set ID:	Alt Mbr ID:	

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	201.0105 Clearing	5.000 STA		
0004	201.0205 Grubbing	5.000 STA		
0006	203.0220 Removing Structure (structure) 01. Culvert 43045004481	1.000 EACH	;	·
0008	204.0100 Removing Concrete Pavement	4,995.000 SY		
0010	204.0110 Removing Asphaltic Surface	1,065.000 SY		
0012	204.0120 Removing Asphaltic Surface Milling	2,910.000 SY	·	·
0014	204.0150 Removing Curb & Gutter	2,685.000 LF	ii	
0016	204.0165 Removing Guardrail	1,265.000 LF	·	·
0018	204.0180 Removing Delineators and Markers	2.000 EACH	·	
0020	204.0195 Removing Concrete Bases	1.000 EACH		
0022	204.0220 Removing Inlets	3.000 EACH	·	·
0024	204.0245 Removing Storm Sewer (size) 01. 12- Inch	170.000 LF		
0026	205.0100 Excavation Common	12,696.000 CY	·	·
0028	205.0200 Excavation Rock	271.000 CY		
0030	206.2001 Excavation for Structures Culverts (structure) 01. B-43-64	1.000 EACH	. <u> </u>	
0032	206.5001 Cofferdams (structure) 01. B-43-64	1.000 EACH		



	Proposal Schedule of Items	Page 9 of 9
Proposal ID: 202212	13029 Project(s): 1590-12-73	
	Federal ID(s): WISC 2023113	
SECTION: 0001	Contract Items	
Alt Set ID:	Alt Mbr ID:	

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0254	SPV.0060 Special 01. Install State Furnished Flasher Cabinet	1.000 EACH	<u>.</u>	
0256	SPV.0060 Special 02. Remove Flashing Beacon Assembly (USH 8 & USH 45 West Jct)	1.000 EACH		
0258	450.4000 HMA Cold Weather Paving	385.000 TON	·	
0260	204.0115 Removing Asphaltic Surface Butt Joints	75.000 SY	·	
	Section: 000	01	Total:	
			Total Bid:	·