



# Wisconsin Department of Transportation

## Division of Transportation Systems Development

Bureau of Project Development  
4822 Madison Yards Way, 4<sup>th</sup> Floor South  
Madison, WI 53705

January 26, 2023

Telephone: (608) 266-1631  
Facsimile (FAX): (608) 266-8459

### NOTICE TO ALL CONTRACTORS:

**Proposal #09: 5420-02-72, WISC 2023221**  
**Madison – Lodi**  
**Knutson Drive to STH 19**  
**STH 113**  
**Dane County**

### Letting of February 14, 2023

This is Addendum No. 01, which provides for the following:

#### Special Provisions:

Added Special Provisions	
Article No.	Description
38	Pipe Grates, 42-Inch, Item 611.9800.S.01

Deleted Special Provisions	
Article No.	Description
26	Pipe Grates

#### Schedule of Items:

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Quantity Added	Proposal Total After Addendum
611.9800.S.01	Pipe Grates, 42-Inch	Each	0	4	4

Deleted Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Proposal Quantity Change (-)	Proposal Total After Addendum
611.9800.S	Pipe Grates	Each	4	-4	0

**Plan Sheets:**

<b>Revised Plan Sheets</b>	
<b>Plan Sheet</b>	<b>Plan Sheet Title (brief description of changes to sheet)</b>
167	Miscellaneous Quantities (updated Pipe Grates bid item)

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

*Mike Coleman*

Proposal Development Specialist  
Proposal Management Section

**ADDENDUM NO. 01**

**5420-02-72**

**January 26, 2023**

**Special Provisions**

**26. DELETED**

**38. Pipe Grates, 42-Inch, Item 611.9800.S.01.**

**A Description**

This special provision describes providing pipe grates for pipe apron endwalls as detailed in the plans.

**B Materials**

Furnish steel conforming to the requirements of standard spec 506.2.2.1. Furnish steel pipe conforming to the requirements of standard spec 506.2.3.6.

Furnish pipe grates galvanized according to ASTM A123.

Furnish angles and brackets galvanized according to ASTM A123.

Furnish required hardware galvanized according to ASTM A153.

**C Construction**

Repair pipes, rods, angles and brackets on which the galvanized coating has been damaged according to the requirements of AASHTO M36.

**D Measurement**

The department will measure Pipe Grates in units of work, where one unit is one grate, completed and accepted.

**E Payment**

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
611.9800.S.01	Pipe Grates, 42-Inch	EACH

Payment is full compensation for furnishing and installing all materials; and for drilling and connecting grates to apron endwalls.

stp-611-010 (20230113)

**Schedule of Items**

Attached, dated January 26, 2023, are the revised Schedule of Items Pages 1 – 16.

**Plan Sheets**

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 167

END OF ADDENDUM

Addendum No. 01  
ID 5420-02-72  
Revised Sheet 167  
January 26, 2023

CULVERT PIPE ITEMS

CATEGORY	STATION	OUTLET	ELEV.	STATION	INLET	ELEV.	DESCRIPTION	QUANTITY	UNIT	MARKS	QUANTITY	UNIT
0030	413+47.65	RNB', 54.0' LT	908.63	413+86.93	RNB', 55.7' RT	909.22	APRON ENDWALLS FOR CULVERT PIPE	2	EACH		2	EACH
	413+54.83	RNB', 56.6' LT	908.63	413+94.34	RNB', 53.0' RT	909.22	APRON ENDWALLS FOR CULVERT PIPE	2	EACH		2	EACH
0040	62+88.14	NB', 45.29' RT	861.86	63+10.25	NB', 46.17' RT	861.93	APRON ENDWALLS FOR CULVERT PIPE	4	EACH		4	EACH
							APRON ENDWALLS FOR CULVERT PIPE	0	EACH		0	EACH
TOTAL 0030								4	EACH		4	EACH
TOTAL 0040								0	EACH		0	EACH
PROJECT TOTAL								4	EACH		4	EACH

\* ADDITIONAL QUANTITIES LISTED ELSEWHERE



Proposal Schedule of Items

Proposal ID: 20230214009 Project(s): 5420-02-72

Federal ID(s): WISC 2023221

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	203.0100 Removing Small Pipe Culverts	4.000 EACH	_____.	_____.
0004	203.0220 Removing Structure (structure) 01. B-13-233	1.000 EACH	_____.	_____.
0006	204.0100 Removing Concrete Pavement	100.000 SY	_____.	_____.
0008	204.0150 Removing Curb & Gutter	1,930.000 LF	_____.	_____.
0010	204.0165 Removing Guardrail	1,140.000 LF	_____.	_____.
0012	204.0195 Removing Concrete Bases	6.000 EACH	_____.	_____.
0014	204.0210 Removing Manholes	2.000 EACH	_____.	_____.
0016	204.0220 Removing Inlets	2.000 EACH	_____.	_____.
0018	204.0245 Removing Storm Sewer (size) 01. 18-Inch	782.000 LF	_____.	_____.
0020	204.9060.S Removing (item description) 01. Traffic Signals (STH 113 & CTH M)	1.000 EACH	_____.	_____.
0022	204.9060.S Removing (item description) 02. Traffic Signals (STH 113 & River Road)	1.000 EACH	_____.	_____.
0024	205.0100 Excavation Common	145,700.000 CY	_____.	_____.
0026	213.0100 Finishing Roadway (project) 01. 5420-02-72	1.000 EACH	_____.	_____.
0028	305.0110 Base Aggregate Dense 3/4-Inch	7,485.000 TON	_____.	_____.
0030	305.0120 Base Aggregate Dense 1 1/4-Inch	118,600.000 TON	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20230214009 Project(s): 5420-02-72

Federal ID(s): WISC 2023221

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0032	312.0110 Select Crushed Material	98,100.000 TON	_____.	_____.
0034	371.2000.S QMP Base Aggregate Dense 1 1/4-Inch Compaction	104.000 EACH	_____.	_____.
0036	405.0100 Coloring Concrete WisDOT Red	170.000 CY	_____.	_____.
0038	415.0080 Concrete Pavement 8-Inch	66.000 SY	_____.	_____.
0040	415.0410 Concrete Pavement Approach Slab	80.000 SY	_____.	_____.
0042	416.0160 Concrete Driveway 6-Inch	48.000 SY	_____.	_____.
0044	416.0512 Concrete Truck Apron 12-Inch	505.000 SY	_____.	_____.
0046	416.0610 Drilled Tie Bars	48.000 EACH	_____.	_____.
0048	416.1010 Concrete Surface Drains	10.000 CY	_____.	_____.
0050	455.0605 Tack Coat	6,320.000 GAL	_____.	_____.
0052	460.0105.S HMA Percent Within Limits (PWL) Test Strip Volumetrics	2.000 EACH	_____.	_____.
0054	460.0110.S HMA Percent Within Limits (PWL) Test Strip Density	2.000 EACH	_____.	_____.
0056	460.2000 Incentive Density HMA Pavement	2,690.000 DOL	1.00000	2,690.00
0058	460.2005 Incentive Density PWL HMA Pavement	22,500.000 DOL	1.00000	22,500.00
0060	460.2007 Incentive Density HMA Pavement Longitudinal Joints	9,710.000 DOL	1.00000	9,710.00
0062	460.2010 Incentive Air Voids HMA Pavement	38,260.000 DOL	1.00000	38,260.00



Proposal Schedule of Items

Proposal ID: 20230214009 Project(s): 5420-02-72

Federal ID(s): WISC 2023221

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0064	460.6223 HMA Pavement 3 MT 58-28 S	24,830.000 TON	_____.	_____.
0066	460.6224 HMA Pavement 4 MT 58-28 S	15,900.000 TON	_____.	_____.
0068	460.6424 HMA Pavement 4 MT 58-28 H	1,750.000 TON	_____.	_____.
0070	465.0105 Asphaltic Surface	27.000 TON	_____.	_____.
0072	465.0120 Asphaltic Surface Driveways and Field Entrances	67.000 TON	_____.	_____.
0074	465.0125 Asphaltic Surface Temporary	52.000 TON	_____.	_____.
0076	465.0310 Asphaltic Curb	117.000 LF	_____.	_____.
0078	465.0315 Asphaltic Flumes	92.000 SY	_____.	_____.
0080	465.0400 Asphaltic Shoulder Rumble Strips	29,300.000 LF	_____.	_____.
0082	465.0425 Asphaltic Shoulder Rumble Strips 2-Lane Rural	14,410.000 LF	_____.	_____.
0084	465.0475 Asphalt Centerline Rumble Strips 2-Lane Rural	5,370.000 LF	_____.	_____.
0086	502.0100 Concrete Masonry Bridges	24.000 CY	_____.	_____.
0088	502.3210 Pigmented Surface Sealer	121.000 SY	_____.	_____.
0090	502.4205 Adhesive Anchors No. 5 Bar	720.000 EACH	_____.	_____.
0092	505.0600 Bar Steel Reinforcement HS Coated Structures	3,170.000 LB	_____.	_____.
0094	509.9050.S Cleaning Parapets	224.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20230214009 Project(s): 5420-02-72

Federal ID(s): WISC 2023221

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0096	520.1042 Apron Endwalls for Culvert Pipe 42-Inch	4.000 EACH	_____.	_____.
0098	520.3142 Culvert Pipe Class III 42-Inch	234.000 LF	_____.	_____.
0100	520.8000 Concrete Collars for Pipe	1.000 EACH	_____.	_____.
0102	521.1515 Apron Endwalls for Culvert Pipe Sloped Side Drains Steel 15-Inch 6 to 1	2.000 EACH	_____.	_____.
0104	522.1012 Apron Endwalls for Culvert Pipe Reinforced Concrete 12-Inch	3.000 EACH	_____.	_____.
0106	522.1018 Apron Endwalls for Culvert Pipe Reinforced Concrete 18-Inch	1.000 EACH	_____.	_____.
0108	601.0405 Concrete Curb & Gutter 18-Inch Type A	245.000 LF	_____.	_____.
0110	601.0407 Concrete Curb & Gutter 18-Inch Type D	108.000 LF	_____.	_____.
0112	601.0411 Concrete Curb & Gutter 30-Inch Type D	2,709.000 LF	_____.	_____.
0114	601.0553 Concrete Curb & Gutter 4-Inch Sloped 36-Inch Type D	5,926.000 LF	_____.	_____.
0116	601.0580 Concrete Curb & Gutter 4-Inch Sloped 36-Inch Type R	333.000 LF	_____.	_____.
0118	601.0588 Concrete Curb & Gutter 4-Inch Sloped 36-Inch Type TBT	162.000 LF	_____.	_____.
0120	601.0600 Concrete Curb Pedestrian	168.000 LF	_____.	_____.
0122	602.0405 Concrete Sidewalk 4-Inch	19,605.000 SF	_____.	_____.
0124	602.0410 Concrete Sidewalk 5-Inch	3,860.000 SF	_____.	_____.





Proposal Schedule of Items

Proposal ID: 20230214009 Project(s): 5420-02-72

Federal ID(s): WISC 2023221

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0126	602.0515 Curb Ramp Detectable Warning Field Natural Patina	288.000 SF	_____.	_____.
0128	606.0200 Riprap Medium	23.000 CY	_____.	_____.
0130	608.0412 Storm Sewer Pipe Reinforced Concrete Class IV 12-Inch	823.000 LF	_____.	_____.
0132	608.0415 Storm Sewer Pipe Reinforced Concrete Class IV 15-Inch	546.000 LF	_____.	_____.
0134	608.0418 Storm Sewer Pipe Reinforced Concrete Class IV 18-Inch	294.000 LF	_____.	_____.
0136	608.3015 Storm Sewer Pipe Class III-A 15-Inch	15.000 LF	_____.	_____.
0138	611.0530 Manhole Covers Type J	2.000 EACH	_____.	_____.
0140	611.0624 Inlet Covers Type H	4.000 EACH	_____.	_____.
0142	611.0627 Inlet Covers Type HM	1.000 EACH	_____.	_____.
0144	611.0636 Inlet Covers Type HM-S	6.000 EACH	_____.	_____.
0146	611.0639 Inlet Covers Type H-S	1.000 EACH	_____.	_____.
0148	611.0645 Inlet Covers Type MS-A	2.000 EACH	_____.	_____.
0150	611.0652 Inlet Covers Type T	2.000 EACH	_____.	_____.
0152	611.2004 Manholes 4-FT Diameter	2.000 EACH	_____.	_____.
0154	611.2005 Manholes 5-FT Diameter	1.000 EACH	_____.	_____.
0156	611.3004 Inlets 4-FT Diameter	3.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20230214009 Project(s): 5420-02-72

Federal ID(s): WISC 2023221

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0158	611.3225 Inlets 2x2.5-FT	2.000 EACH	_____.	_____.
0160	611.3230 Inlets 2x3-FT	8.000 EACH	_____.	_____.
0162	611.3901 Inlets Median 1 Grate	2.000 EACH	_____.	_____.
0164	611.8110 Adjusting Manhole Covers	2.000 EACH	_____.	_____.
0168	612.0106 Pipe Underdrain 6-Inch	10,960.000 LF	_____.	_____.
0170	612.0206 Pipe Underdrain Unperforated 6-Inch	700.000 LF	_____.	_____.
0172	612.0806 Apron Endwalls for Underdrain Reinforced Concrete 6-Inch	14.000 EACH	_____.	_____.
0174	614.2300 MGS Guardrail 3	650.000 LF	_____.	_____.
0176	614.2500 MGS Thrie Beam Transition	316.000 LF	_____.	_____.
0178	614.2610 MGS Guardrail Terminal EAT	8.000 EACH	_____.	_____.
0180	618.0100 Maintenance And Repair of Haul Roads (project) 01. 5420-02-72	1.000 EACH	_____.	_____.
0182	619.1000 Mobilization	1.000 EACH	_____.	_____.
0184	620.0100 Concrete Corrugated Median	870.000 SF	_____.	_____.
0186	620.0300 Concrete Median Sloped Nose	1,109.000 SF	_____.	_____.
0188	624.0100 Water	3,020.000 MGAL	_____.	_____.
0190	625.0500 Salvaged Topsoil	62,500.000 SY	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20230214009 Project(s): 5420-02-72

Federal ID(s): WISC 2023221

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0192	627.0200 Mulching	56,000.000 SY	_____.	_____.
0194	628.1504 Silt Fence	2,400.000 LF	_____.	_____.
0196	628.1520 Silt Fence Maintenance	2,400.000 LF	_____.	_____.
0198	628.1905 Mobilizations Erosion Control	9.000 EACH	_____.	_____.
0200	628.1910 Mobilizations Emergency Erosion Control	6.000 EACH	_____.	_____.
0202	628.2004 Erosion Mat Class I Type B	6,080.000 SY	_____.	_____.
0204	628.2023 Erosion Mat Class II Type B	475.000 SY	_____.	_____.
0206	628.7005 Inlet Protection Type A	6.000 EACH	_____.	_____.
0208	628.7015 Inlet Protection Type C	17.000 EACH	_____.	_____.
0210	628.7504 Temporary Ditch Checks	220.000 LF	_____.	_____.
0212	628.7515.S Stone Ditch Checks	200.000 CY	_____.	_____.
0214	628.7555 Culvert Pipe Checks	24.000 EACH	_____.	_____.
0216	628.7560 Tracking Pads	6.000 EACH	_____.	_____.
0218	629.0210 Fertilizer Type B	50.000 CWT	_____.	_____.
0220	630.0130 Seeding Mixture No. 30	1,120.000 LB	_____.	_____.
0222	630.0140 Seeding Mixture No. 40	10.000 LB	_____.	_____.
0224	630.0200 Seeding Temporary	840.000 LB	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20230214009 Project(s): 5420-02-72

Federal ID(s): WISC 2023221

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0226	630.0500 Seed Water	350.000 MGAL	_____.	_____.
0228	633.5200 Markers Culvert End	10.000 EACH	_____.	_____.
0230	634.0614 Posts Wood 4x6-Inch X 14-FT	19.000 EACH	_____.	_____.
0232	634.0616 Posts Wood 4x6-Inch X 16-FT	20.000 EACH	_____.	_____.
0234	634.0618 Posts Wood 4x6-Inch X 18-FT	4.000 EACH	_____.	_____.
0236	634.0814 Posts Tubular Steel 2x2-Inch X 14-FT	12.000 EACH	_____.	_____.
0238	637.2210 Signs Type II Reflective H	377.170 SF	_____.	_____.
0240	637.2230 Signs Type II Reflective F	54.250 SF	_____.	_____.
0242	638.2102 Moving Signs Type II	47.000 EACH	_____.	_____.
0244	638.2602 Removing Signs Type II	5.000 EACH	_____.	_____.
0246	638.3000 Removing Small Sign Supports	5.000 EACH	_____.	_____.
0248	638.4000 Moving Small Sign Supports	51.000 EACH	_____.	_____.
0250	642.5201 Field Office Type C	1.000 EACH	_____.	_____.
0252	643.0300 Traffic Control Drums	20,010.000 DAY	_____.	_____.
0254	643.0410 Traffic Control Barricades Type II	770.000 DAY	_____.	_____.
0256	643.0420 Traffic Control Barricades Type III	10,158.000 DAY	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20230214009 Project(s): 5420-02-72

Federal ID(s): WISC 2023221

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0258	643.0500 Traffic Control Flexible Tubular Marker Posts	408.000 EACH	_____.	_____.
0260	643.0600 Traffic Control Flexible Tubular Marker Bases	408.000 EACH	_____.	_____.
0262	643.0705 Traffic Control Warning Lights Type A	12,978.000 DAY	_____.	_____.
0264	643.0715 Traffic Control Warning Lights Type C	8,225.000 DAY	_____.	_____.
0266	643.0800 Traffic Control Arrow Boards	281.000 DAY	_____.	_____.
0268	643.0900 Traffic Control Signs	59,841.000 DAY	_____.	_____.
0270	643.0910 Traffic Control Covering Signs Type I	3.000 EACH	_____.	_____.
0272	643.0920 Traffic Control Covering Signs Type II	35.000 EACH	_____.	_____.
0274	643.1050 Traffic Control Signs PCMS	42.000 DAY	_____.	_____.
0276	643.3105 Temporary Marking Line Paint 4-Inch	19,810.000 LF	_____.	_____.
0278	643.3150 Temporary Marking Line Removable Tape 4-Inch	27,856.000 LF	_____.	_____.
0280	643.3250 Temporary Marking Line Removable Tape 8-Inch	155.000 LF	_____.	_____.
0282	643.3550 Temporary Marking Arrow Removable Tape	2.000 EACH	_____.	_____.
0284	643.3805 Temporary Marking Stop Line Paint 18-Inch	63.000 LF	_____.	_____.
0286	643.3850 Temporary Marking Stop Line Removable Tape 18-Inch	168.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20230214009 Project(s): 5420-02-72

Federal ID(s): WISC 2023221

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0288	643.5000 Traffic Control	1.000 EACH	_____.	_____.
0290	645.0120 Geotextile Type HR	45.000 SY	_____.	_____.
0292	645.0130 Geotextile Type R	400.000 SY	_____.	_____.
0294	645.0220 Geogrid Type SR	147,800.000 SY	_____.	_____.
0296	646.1020 Marking Line Epoxy 4-Inch	57,522.000 LF	_____.	_____.
0298	646.1040 Marking Line Grooved Wet Ref Epoxy 4-Inch	21,635.000 LF	_____.	_____.
0300	646.3020 Marking Line Epoxy 8-Inch	311.000 LF	_____.	_____.
0302	646.3040 Marking Line Grooved Wet Ref Epoxy 8-Inch	4,995.000 LF	_____.	_____.
0304	646.5020 Marking Arrow Epoxy	19.000 EACH	_____.	_____.
0306	646.5120 Marking Word Epoxy	9.000 EACH	_____.	_____.
0308	646.5220 Marking Symbol Epoxy	1.000 EACH	_____.	_____.
0310	646.5520 Marking Outfall Epoxy	14.000 EACH	_____.	_____.
0312	646.6120 Marking Stop Line Epoxy 18-Inch	327.000 LF	_____.	_____.
0314	646.6320 Marking Dotted Extension Epoxy 18-Inch	67.000 LF	_____.	_____.
0316	646.7120 Marking Diagonal Epoxy 12-Inch	1,123.000 LF	_____.	_____.
0318	646.7420 Marking Crosswalk Epoxy Transverse Line 6-Inch	252.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20230214009 Project(s): 5420-02-72

Federal ID(s): WISC 2023221

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0320	646.8020 Marking Corrugated Median Epoxy	376.000 SF	_____.	_____.
0322	646.8120 Marking Curb Epoxy	444.000 LF	_____.	_____.
0324	646.8220 Marking Island Nose Epoxy	15.000 EACH	_____.	_____.
0326	646.9000 Marking Removal Line 4-Inch	7,615.000 LF	_____.	_____.
0328	646.9200 Marking Removal Line Wide	250.000 LF	_____.	_____.
0330	646.9300 Marking Removal Special Marking	4.000 EACH	_____.	_____.
0332	650.4000 Construction Staking Storm Sewer	22.000 EACH	_____.	_____.
0334	650.4500 Construction Staking Subgrade	49,662.000 LF	_____.	_____.
0336	650.5000 Construction Staking Base	49,662.000 LF	_____.	_____.
0338	650.5500 Construction Staking Curb Gutter and Curb & Gutter	4,961.000 LF	_____.	_____.
0340	650.6000 Construction Staking Pipe Culverts	3.000 EACH	_____.	_____.
0342	650.8501 Construction Staking Electrical Installations (project) 01. 5420-02-72	1.000 EACH	_____.	_____.
0344	650.9000 Construction Staking Curb Ramps	18.000 EACH	_____.	_____.
0346	650.9500 Construction Staking Sidewalk (project) 01. 5420-02-72	1.000 EACH	_____.	_____.
0348	650.9911 Construction Staking Supplemental Control (project) 01. 5420-02-72	1.000 EACH	_____.	_____.
0350	650.9920 Construction Staking Slope Stakes	3,224.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20230214009 Project(s): 5420-02-72

Federal ID(s): WISC 2023221

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0352	652.0225 Conduit Rigid Nonmetallic Schedule 40 2-Inch	3,722.000 LF	_____.	_____.
0354	652.0235 Conduit Rigid Nonmetallic Schedule 40 3-Inch	928.000 LF	_____.	_____.
0356	652.0325 Conduit Rigid Nonmetallic Schedule 80 2-Inch	391.000 LF	_____.	_____.
0358	652.0800 Conduit Loop Detector	692.000 LF	_____.	_____.
0360	653.0164 Pull Boxes Non-Conductive 24x42-Inch	44.000 EACH	_____.	_____.
0362	653.0900 Adjusting Pull Boxes	11.000 EACH	_____.	_____.
0364	653.0905 Removing Pull Boxes	6.000 EACH	_____.	_____.
0366	654.0101 Concrete Bases Type 1	1.000 EACH	_____.	_____.
0368	654.0102 Concrete Bases Type 2	3.000 EACH	_____.	_____.
0370	654.0105 Concrete Bases Type 5	14.000 EACH	_____.	_____.
0372	654.0120 Concrete Bases Type 10-Special	2.000 EACH	_____.	_____.
0374	654.0230 Concrete Control Cabinet Bases Type L30	1.000 EACH	_____.	_____.
0376	655.0210 Cable Traffic Signal 3-14 AWG	15.000 LF	_____.	_____.
0378	655.0230 Cable Traffic Signal 5-14 AWG	464.000 LF	_____.	_____.
0380	655.0240 Cable Traffic Signal 7-14 AWG	923.000 LF	_____.	_____.
0382	655.0250 Cable Traffic Signal 9-14 AWG	1,140.000 LF	_____.	_____.





Proposal Schedule of Items

Proposal ID: 20230214009 Project(s): 5420-02-72

Federal ID(s): WISC 2023221

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0384	655.0260 Cable Traffic Signal 12-14 AWG	712.000 LF	_____.	_____.
0386	655.0305 Cable Type UF 2-12 AWG Grounded	1,050.000 LF	_____.	_____.
0388	655.0515 Electrical Wire Traffic Signals 10 AWG	1,610.000 LF	_____.	_____.
0390	655.0610 Electrical Wire Lighting 12 AWG	16,898.000 LF	_____.	_____.
0392	655.0700 Loop Detector Lead In Cable	6,456.000 LF	_____.	_____.
0394	655.0800 Loop Detector Wire	2,848.000 LF	_____.	_____.
0396	656.0201 Electrical Service Meter Breaker Pedestal (location) 01. Station 10+56'RAB', 53.80' RT	1.000 EACH	_____.	_____.
0398	657.0100 Pedestal Bases	1.000 EACH	_____.	_____.
0400	657.0255 Transformer Bases Breakaway 11 1/2-Inch Bolt Circle	17.000 EACH	_____.	_____.
0402	657.0305 Poles Type 2	2.000 EACH	_____.	_____.
0404	657.0315 Poles Type 4	1.000 EACH	_____.	_____.
0406	657.0322 Poles Type 5-Aluminum	14.000 EACH	_____.	_____.
0408	657.0352 Poles Type 10-Special	2.000 EACH	_____.	_____.
0410	657.0420 Traffic Signal Standards Aluminum 13-FT	1.000 EACH	_____.	_____.
0412	657.0546 Monotube Arms 45-FT-Special	2.000 EACH	_____.	_____.
0414	657.0585 Trombone Arms 15-FT	2.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20230214009 Project(s): 5420-02-72

Federal ID(s): WISC 2023221

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0416	657.0709 Luminaire Arms Truss Type 4-Inch Clamp 12-FT	1.000 EACH	_____.	_____.
0418	657.0715 Luminaire Arms Truss Type 4 1/2-Inch Clamp 15-FT	14.000 EACH	_____.	_____.
0420	657.0815 Luminaire Arms Steel 15-FT	2.000 EACH	_____.	_____.
0422	657.0820 Luminaire Arms Steel Type 10 Pole Clamp 15-FT	2.000 EACH	_____.	_____.
0424	658.0173 Traffic Signal Face 3S 12-Inch	8.000 EACH	_____.	_____.
0426	658.0174 Traffic Signal Face 4S 12-Inch	4.000 EACH	_____.	_____.
0428	658.0416 Pedestrian Signal Face 16-Inch	1.000 EACH	_____.	_____.
0430	658.0500 Pedestrian Push Buttons	2.000 EACH	_____.	_____.
0432	658.5070 Signal Mounting Hardware (location) 01. STH 113 & CTH M	1.000 EACH	_____.	_____.
0434	658.5070 Signal Mounting Hardware (location) 02. STH 113 & River Road	1.000 EACH	_____.	_____.
0436	659.1120 Luminaires Utility LED B	14.000 EACH	_____.	_____.
0438	659.1125 Luminaires Utility LED C	3.000 EACH	_____.	_____.
0440	659.2130 Lighting Control Cabinets 120/240 30- Inch	1.000 EACH	_____.	_____.
0442	659.5000.S Lamp, Ballast, LED, Switch Disposal by Contractor	11.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20230214009 Project(s): 5420-02-72

Federal ID(s): WISC 2023221

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0444	661.0201 Temporary Traffic Signals for Intersections (location) 01. STH 113 & CTH M	1.000 EACH	_____.	_____.
0446	690.0150 Sawing Asphalt	1,910.000 LF	_____.	_____.
0448	690.0250 Sawing Concrete	80.000 LF	_____.	_____.
0450	740.0440 Incentive IRI Ride	18,718.000 DOL	1.00000	18,718.00
0452	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	1,500.000 HRS	5.00000	7,500.00
0454	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	1,050.000 HRS	5.00000	5,250.00
0456	SPV.0060 Special 01. Retroreflective Backplate 3S	4.000 EACH	_____.	_____.
0458	SPV.0060 Special 02. Retroreflective Backplate 4S	4.000 EACH	_____.	_____.
0460	SPV.0060 Special 03. Adjusting Concrete Bases	6.000 EACH	_____.	_____.
0462	SPV.0060 Special 04. Construction Staking Roundabout	1.000 EACH	_____.	_____.
0464	SPV.0060 Special 05. Landmark Reference Monuments Special	1.000 EACH	_____.	_____.
0466	SPV.0060 Special 06. Verify Landmark Reference Monuments	2.000 EACH	_____.	_____.
0468	SPV.0090 Special 01. Concrete Curb & Gutter 24-Inch Type D Special	127.000 LF	_____.	_____.
0470	611.9800.S Pipe Grates (size) 01. 42-Inch	4.000 EACH	_____.	_____.
Section: 0001			Total:	_____.

Total Bid: \_\_\_\_\_.