



Wisconsin Department of Transportation

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

February 6, 2023

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #30: 4677-10-71, WISC 2023232
T Grand Chute – V Little Chute
French Rd Intersection
CTH OO
Outagamie County

Letting of February 14, 2023

This is Addendum No. 01, which provides for the following:

Special Provisions:

Revised Special Provisions	
Article No.	Description
12	Removing Traffic Signals STH 441 NB Ramps & CTH OO

Deleted Special Provisions	
Article No.	Description
28	Poles Type 4 Short

Schedule of Items:

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
657.0315	Poles Type 4	EACH	0	2	2

Deleted Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
SPV.0060.08	Poles Type 4 Short	EACH	2	-2	0

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
43	Miscellaneous Quantities (removed item SPV.0060.08 and added item 657.0315)

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01

4677-10-71

February 6, 2023

Special Provisions

12. Removing Traffic Signals STH 441 NB Ramps & CTH OO, Item 204.9060.S.01.

Replace entire section titled A Description with the following:

A Description

This work shall consist of removing the existing monotube arm at the intersection of STH 441 NB off ramp & CTH OO as the plans show, conforming to standard spec 204.

Replace entire section titled C Construction with the following:

C Construction

Coordinate with NE Region Electrical Unit, Randy Asman (920) 360-3107 prior to removal. Disconnect and dispose all materials resulting from the removal of the monotube arm and any other necessary items such as but not limited to heads and wires off the job site. The removed signal equipment is the contractor's property. If any part of the signal that is to be remain is damaged, the contractor is responsible for fixing or replacing the damaged component at their cost. This work would need to conform to standard spec 657 and 658.

Replace entire section titled E Payment with the following:

E Payment

Add the following to standard spec 204.5:

ITEM NUMBER	DESCRIPTION	UNIT
204.9060.S.01	Removing Traffic Signals STH 441 NB Ramps & CTH OO	EACH

Payment for Removing Traffic Signals is full compensation for removal and for proper disposal of equipment.

28. DELETED

Schedule of Items

Attached, dated February 6, 2023, are the revised Schedule of Items Page 9.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 43

END OF ADDENDUM

Addendum No. 01
ID 4677-10-71
Revised Sheet 43
February 6, 2023

CONCRETE BASES

LOCATION	SIGNAL BASE NO.	ALIGNMENT	STATION	OFFSET	SPV.0060.01		SPV.0060.02		654.0105		654.0110		654.0120		654.0113		SPV.0060.03		
					CONCRETE BASES TYPE 1	SPECIAL EACH	CONCRETE BASES TYPE 2	SPECIAL EACH	CONCRETE BASES TYPE 5	EACH	CONCRETE BASES TYPE 10	EACH	CONCRETE BASES TYPE 10	SPECIAL EACH	CONCRETE BASES TYPE 13	EACH	CONCRETE BASES TYPE 13	EACH	CONCRETE BASES TYPE 13
CTH OO & FRENCH ROAD	CB1	CTH OO	703+39.0	85.6'	LT	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	SB1	CTH OO	703+39.6	59.5'	LT	-	1	-	-	-	-	-	-	-	-	-	-	-	-
	SB2	CTH OO	703+45.6	44.9'	RT	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	SB3	FRENCH ROAD	591+38.1	25.9'	RT	1	-	-	-	-	-	-	-	-	-	-	-	-	-
	SB4	FRENCH ROAD	591+18.5	41.8'	LT	-	-	-	-	-	-	-	-	1	-	-	-	-	-
	SB5	CTH OO	701+68.8	43.1'	RT	-	1	-	-	-	-	-	-	-	-	-	-	-	-
	SB6	CTH OO	701+55.4	75.1'	LT	-	-	-	-	-	-	-	-	-	1	-	-	-	
	SB7	FRENCH ROAD	592+79.9	34.4'	LT	1	-	-	-	-	-	-	-	-	-	-	-	-	
	SB8	FRENCH ROAD	592+76.1	37.3'	RT	-	-	-	-	-	-	1	-	-	-	-	-	-	
	SB9	CTH OO	699+99.4	19.0'	LT	-	-	-	-	1	-	-	-	-	-	-	-	-	
SB10	FRENCH ROAD	593+20.2	32.3'	LT	-	-	-	-	1	-	-	-	-	-	-	-	-		
INTERSECTION TOTAL						2	2	2	2	2	1	1	1	2	2	2	2	1	

SIGNAL BASES, POLES, AND MAST ARMS

LOCATION	SIGNAL BASE NO.	DESCRIPTION	657.0322		657.0420		SPV.0060.09		SPV.0060.10		SPV.0060.11		SPV.0060.12		SPV.0060.14		SPV.0060.15		657.0610		657.0615		657.0616		657.0618				
			PEDESTAL BASE	TRANSFORMER BASES BREAKAWAY BOLT CIRCLE	TRAFFIC SIGNAL STANDARDS ALUMINUM 13-FT	EACH	INSTALL POLES TYPE 9	EACH	INSTALL POLES TYPE 10 SPECIAL	EACH	INSTALL MONOTUBE ARMS 30-FT	EACH	INSTALL MONOTUBE ARMS 45-FT SPECIAL	EACH	INSTALL MONOTUBE ARMS 55-FT	EACH	LUMINAIRE ARMS SINGLE MEMBER 4-1/2-INCH CLAMP	EACH	LUMINAIRE ARMS SINGLE MEMBER 4-1/2-INCH CLAMP	EACH	LUMINAIRE ARMS SINGLE MEMBER 4-1/2-INCH CLAMP	EACH	LUMINAIRE ARMS SINGLE MEMBER 4-1/2-INCH CLAMP	EACH	INSTALL LUMINAIRE ARMS 12-FT	EACH	LUMINAIRE UTILITY LED C	EACH	
CTH OO & FRENCH ROAD	SB1	11 1/2-INCH BOLT CIRCLE	1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-		
	SB2	PEDESTAL BASE	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-		
	SB3	TRANSFORMER BASES BREAKAWAY	1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-		
	SB4	TRAFFIC SIGNAL STANDARDS	-	-	1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
	SB5	PEDESTAL BASE	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
	SB6	TRANSFORMER BASES BREAKAWAY	1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
	SB7	TRAFFIC SIGNAL STANDARDS	-	-	1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
	SB8	PEDESTAL BASE	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
	SB9	TRANSFORMER BASES BREAKAWAY	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
	SB10	TRAFFIC SIGNAL STANDARDS	-	-	1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	
INTERSECTION TOTAL			2	4	2	2	1	1	1	1	1	1	1	2	2	2	2	2	2	2	2	1	1	3	3	2	8		

657.0315
POLES
TYPE 4
EACH

CTH OO & FRENCH ROAD
TOWN OF GRAND CHUTE/
VILLAGE OF LITTLE CHUTE
OUTAGAMIE COUNTY



Proposal Schedule of Items

Proposal ID: 20230214030 Project(s): 4677-10-71

Federal ID(s): WISC 2023232

SECTION: 0001 Roadway Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0252	SPV.0060 Special 06. Traffic Signal Controller and Cabinet Assembly Special Cth OO & French Road	1.000 EACH	_____.	_____.
0254	SPV.0060 Special 07. Install Signal Mounting Hardware CTH OO & French Road	1.000 EACH	_____.	_____.
0258	SPV.0060 Special 09. Install Poles Type 9	1.000 EACH	_____.	_____.
0260	SPV.0060 Special 10. Install Poles Type 10 Special	1.000 EACH	_____.	_____.
0262	SPV.0060 Special 11. Intall Poles Type 13	2.000 EACH	_____.	_____.
0264	SPV.0060 Special 12. Install Monotube Arms 30-Ft	1.000 EACH	_____.	_____.
0266	SPV.0060 Special 13. Install Monotube Arms 45-Ft	1.000 EACH	_____.	_____.
0268	SPV.0060 Special 14. Install Monotube Arms 45-Ft Special	1.000 EACH	_____.	_____.
0270	SPV.0060 Special 15. Install Monotube Arms 55-Ft	2.000 EACH	_____.	_____.
0272	SPV.0060 Special 16. Install Luminaire Arms Steel 12-Ft	3.000 EACH	_____.	_____.
0274	SPV.0090 Special 01. Tray Cable For Street Lighting 3 Conductor 12 AWG	2,964.000 LF	_____.	_____.
0276	SPV.0090 Special 02. Cable Traffic Signal 16-14 AWG	1,799.000 LF	_____.	_____.
0278	657.0315 Poles Type 4	2.000 EACH	_____.	_____.

Section: 0001 Total: _____.

Total Bid: _____.

