



Wisconsin Department of Transportation

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

January 26, 2023

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #44: 7140-00-70
La Crosse – Trempealeau
La Crosse/Tremp Co Ln to 10th St
STH 35
Trempealeau County

Letting of February 14, 2023

This is Addendum No. 02, which provides for the following:

Special Provisions:

Added Special Provisions	
Article No.	Description
33	Pipe Grates, 24-Inch, Item 611.9800.S.01

Deleted Special Provisions	
Article No.	Description
15	Pipe Grates

Schedule of Items:

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Quantity Added	Proposal Total After Addendum
611.9800.S.01	Pipe Grates, 24-Inch	Each	0	1	1

Deleted Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Proposal Quantity Change (-)	Proposal Total After Addendum
611.9800.S	Pipe Grates	Each	1	-1	0

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
84	Miscellaneous Quantities (updated Pipe Grates bid item)

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 02

7140-00-70

January 26, 2023

Special Provisions

15. DELETED

33. Pipe Grates, 24-Inch, Item 611.9800.S.01.

A Description

This special provision describes providing pipe grates for pipe apron endwalls as detailed in the plans.

B Materials

Furnish steel conforming to the requirements of standard spec 506.2.2.1. Furnish steel pipe conforming to the requirements of standard spec 506.2.3.6.

Furnish pipe grates galvanized according to ASTM A123.

Furnish angles and brackets galvanized according to ASTM A123.

Furnish required hardware galvanized according to ASTM A153.

C Construction

Repair pipes, rods, angles and brackets on which the galvanized coating has been damaged according to the requirements of AASHTO M36.

D Measurement

The department will measure Pipe Grates in units of work, where one unit is one grate, completed and accepted.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
611.9800.S.01	Pipe Grates, 24-Inch	EACH

Payment is full compensation for furnishing and installing all materials; and for drilling and connecting grates to apron endwalls.

stp-611-010 (20230113)

Schedule of Items

Attached, dated January 26, 2023, are the revised Schedule of Items Pages 1 – 12.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 84

END OF ADDENDUM



Proposal Schedule of Items

Proposal ID: 20230214044 Project(s): 7140-00-70

Federal ID(s): N/A

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	201.0120 Clearing	42.000 ID	_____.	_____.
0004	201.0205 Grubbing	2.000 STA	_____.	_____.
0006	201.0220 Grubbing	42.000 ID	_____.	_____.
0008	203.0100 Removing Small Pipe Culverts	2.000 EACH	_____.	_____.
0010	204.0100 Removing Concrete Pavement	14.000 SY	_____.	_____.
0012	204.0110 Removing Asphaltic Surface	1,287.000 SY	_____.	_____.
0014	204.0115 Removing Asphaltic Surface Butt Joints	1,319.000 SY	_____.	_____.
0016	204.0120 Removing Asphaltic Surface Milling	61,900.000 SY	_____.	_____.
0018	204.0150 Removing Curb & Gutter	1,198.000 LF	_____.	_____.
0020	204.0155 Removing Concrete Sidewalk	455.000 SY	_____.	_____.
0022	204.0195 Removing Concrete Bases	2.000 EACH	_____.	_____.
0024	204.9060.S Removing (item description) 01. Apron Endwall for CPCS 24-Inch	1.000 EACH	_____.	_____.
0026	204.9090.S Removing (item description) 01. CPRC 24-Inch	8.000 LF	_____.	_____.
0028	204.9090.S Removing (item description) 02. CPRC 72-Inch	8.000 LF	_____.	_____.
0030	205.0100 Excavation Common	1,348.000 CY	_____.	_____.
0032	208.1500.S Temporary Lane Shift During Culvert Work	4.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20230214044 Project(s): 7140-00-70

Federal ID(s): N/A

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0034	211.0101 Prepare Foundation for Asphaltic Paving (project) 01. 7140-00-70	1.000 EACH	_____.	_____.
0036	211.0700.S Prepare Foundation for CIR Base Layer (project) 01. 7140-00-70	1.000 EACH	_____.	_____.
0038	211.0800.S Base Repair for CIR Layer	800.000 CY	_____.	_____.
0040	213.0100 Finishing Roadway (project) 01. 7140-00-70	1.000 EACH	_____.	_____.
0042	305.0110 Base Aggregate Dense 3/4-Inch	4,970.000 TON	_____.	_____.
0044	305.0120 Base Aggregate Dense 1 1/4-Inch	1,070.000 TON	_____.	_____.
0046	305.0500 Shaping Shoulders	494.000 STA	_____.	_____.
0048	327.1000.S CIR Asphaltic Base Layer	94,430.000 SY	_____.	_____.
0050	405.1000 Stamping Colored Concrete	4.400 CY	_____.	_____.
0052	415.0060 Concrete Pavement 6-Inch	14.000 SY	_____.	_____.
0054	416.0610 Drilled Tie Bars	135.000 EACH	_____.	_____.
0056	455.0605 Tack Coat	20,824.000 GAL	_____.	_____.
0058	455.0770.S Asphalt Stabilizing Agent	495.000 TON	_____.	_____.
0060	460.0105.S HMA Percent Within Limits (PWL) Test Strip Volumetrics	1.000 EACH	_____.	_____.
0062	460.0110.S HMA Percent Within Limits (PWL) Test Strip Density	4.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20230214044 Project(s): 7140-00-70

Federal ID(s): N/A

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0064	460.6645 HMA Pavement 5 MT 58-34 V	21,725.000 TON	_____.	_____.
0066	460.9000.S Material Transfer Vehicle 01. 7140-00-70	1.000 EACH	_____.	_____.
0068	465.0105 Asphaltic Surface	994.000 TON	_____.	_____.
0070	465.0110 Asphaltic Surface Patching	179.000 TON	_____.	_____.
0072	465.0120 Asphaltic Surface Driveways and Field Entrances	131.000 TON	_____.	_____.
0074	465.0425 Asphaltic Shoulder Rumble Strips 2-Lane Rural	44,758.000 LF	_____.	_____.
0076	465.0475 Asphalt Centerline Rumble Strips 2-Lane Rural	21,506.000 LF	_____.	_____.
0078	520.1024 Apron Endwalls for Culvert Pipe 24-Inch	2.000 EACH	_____.	_____.
0080	520.1036 Apron Endwalls for Culvert Pipe 36-Inch	2.000 EACH	_____.	_____.
0082	520.2024 Culvert Pipe Temporary 24-Inch	8.000 LF	_____.	_____.
0084	520.2030 Culvert Pipe Temporary 30-Inch	8.000 LF	_____.	_____.
0086	520.3324 Culvert Pipe Class III-A 24-Inch	88.000 LF	_____.	_____.
0088	520.4136 Culvert Pipe Class IV 36-Inch	56.000 LF	_____.	_____.
0090	520.8700 Cleaning Culvert Pipes	5.000 EACH	_____.	_____.
0092	520.9700.S Culvert Pipe Liners (size) 01. 36-Inch	86.000 LF	_____.	_____.
0094	520.9750.S Cleaning Culvert Pipes for Liner Verification	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20230214044 Project(s): 7140-00-70

Federal ID(s): N/A

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0096	521.1024 Apron Endwalls for Culvert Pipe Steel 24-Inch	1.000 EACH	_____.	_____.
0098	522.0124 Culvert Pipe Reinforced Concrete Class III 24-Inch	8.000 LF	_____.	_____.
0100	522.0172 Culvert Pipe Reinforced Concrete Class III 72-Inch	8.000 LF	_____.	_____.
0102	522.1024 Apron Endwalls for Culvert Pipe Reinforced Concrete 24-Inch	6.000 EACH	_____.	_____.
0104	522.1030 Apron Endwalls for Culvert Pipe Reinforced Concrete 30-Inch	2.000 EACH	_____.	_____.
0106	522.1054 Apron Endwalls for Culvert Pipe Reinforced Concrete 54-Inch	2.000 EACH	_____.	_____.
0108	522.1072 Apron Endwalls for Culvert Pipe Reinforced Concrete 72-Inch	6.000 EACH	_____.	_____.
0110	601.0407 Concrete Curb & Gutter 18-Inch Type D	32.000 LF	_____.	_____.
0112	601.0409 Concrete Curb & Gutter 30-Inch Type A	31.000 LF	_____.	_____.
0114	601.0411 Concrete Curb & Gutter 30-Inch Type D	1,159.000 LF	_____.	_____.
0116	601.0600 Concrete Curb Pedestrian	121.000 LF	_____.	_____.
0118	602.0405 Concrete Sidewalk 4-Inch	4,800.000 SF	_____.	_____.
0120	602.0505 Curb Ramp Detectable Warning Field Yellow	408.000 SF	_____.	_____.
0122	602.0605 Curb Ramp Detectable Warning Field Radial Yellow	17.000 SF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20230214044 Project(s): 7140-00-70

Federal ID(s): N/A

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0124	606.0200 Riprap Medium	25.000 CY	_____.	_____.
0126	606.0400 Riprap Extra-Heavy	11.000 CY	_____.	_____.
0128	611.0530 Manhole Covers Type J	6.000 EACH	_____.	_____.
0130	611.8110 Adjusting Manhole Covers	10.000 EACH	_____.	_____.
0132	611.8115 Adjusting Inlet Covers	20.000 EACH	_____.	_____.
0134	611.8120.S Cover Plates Temporary	33.000 EACH	_____.	_____.
0138	618.0100 Maintenance And Repair of Haul Roads (project) 01. 7140-00-70	1.000 EACH	_____.	_____.
0140	619.1000 Mobilization	1.000 EACH	_____.	_____.
0142	624.0100 Water	89.000 MGAL	_____.	_____.
0144	625.0100 Topsoil	6,450.000 SY	_____.	_____.
0146	628.1504 Silt Fence	8,275.000 LF	_____.	_____.
0148	628.1520 Silt Fence Maintenance	8,275.000 LF	_____.	_____.
0150	628.1905 Mobilizations Erosion Control	4.000 EACH	_____.	_____.
0152	628.1910 Mobilizations Emergency Erosion Control	2.000 EACH	_____.	_____.
0154	628.2004 Erosion Mat Class I Type B	5,850.000 SY	_____.	_____.
0156	628.2006 Erosion Mat Urban Class I Type A	600.000 SY	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20230214044 Project(s): 7140-00-70

Federal ID(s): N/A

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0158	628.7005 Inlet Protection Type A	5.000 EACH	_____.	_____.
0160	628.7015 Inlet Protection Type C	45.000 EACH	_____.	_____.
0162	628.7504 Temporary Ditch Checks	200.000 LF	_____.	_____.
0164	628.7555 Culvert Pipe Checks	17.000 EACH	_____.	_____.
0166	628.7570 Rock Bags	175.000 EACH	_____.	_____.
0168	629.0210 Fertilizer Type B	4.500 CWT	_____.	_____.
0170	630.0110 Seeding Mixture No. 10	90.000 LB	_____.	_____.
0172	630.0140 Seeding Mixture No. 40	10.000 LB	_____.	_____.
0174	630.0200 Seeding Temporary	25.000 LB	_____.	_____.
0176	630.0500 Seed Water	115.000 MGAL	_____.	_____.
0178	633.5200 Markers Culvert End	24.000 EACH	_____.	_____.
0180	634.0618 Posts Wood 4x6-Inch X 18-FT	2.000 EACH	_____.	_____.
0182	638.2102 Moving Signs Type II	11.000 EACH	_____.	_____.
0184	638.3000 Removing Small Sign Supports	1.000 EACH	_____.	_____.
0186	638.4000 Moving Small Sign Supports	8.000 EACH	_____.	_____.
0188	642.5001 Field Office Type B	1.000 EACH	_____.	_____.
0190	643.0300 Traffic Control Drums	15,100.000 DAY	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20230214044 Project(s): 7140-00-70

Federal ID(s): N/A

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0192	643.0420 Traffic Control Barricades Type III	200.000 DAY	_____.	_____.
0194	643.0705 Traffic Control Warning Lights Type A	400.000 DAY	_____.	_____.
0196	643.0715 Traffic Control Warning Lights Type C	300.000 DAY	_____.	_____.
0198	643.0900 Traffic Control Signs	8,800.000 DAY	_____.	_____.
0200	643.0920 Traffic Control Covering Signs Type II	12.000 EACH	_____.	_____.
0202	643.1000 Traffic Control Signs Fixed Message	64.000 SF	_____.	_____.
0204	643.3105 Temporary Marking Line Paint 4-Inch	25,038.000 LF	_____.	_____.
0206	643.3120 Temporary Marking Line Epoxy 4-Inch	22,551.000 LF	_____.	_____.
0208	643.5000 Traffic Control	1.000 EACH	_____.	_____.
0210	644.1440 Temporary Pedestrian Surface Matting	1,025.000 SF	_____.	_____.
0212	644.1601 Temporary Pedestrian Curb Ramp	900.000 DAY	_____.	_____.
0214	644.1605 Temporary Pedestrian Detectable Warning Field	410.000 SF	_____.	_____.
0216	644.1810 Temporary Pedestrian Barricade	5,500.000 LF	_____.	_____.
0218	645.0120 Geotextile Type HR	100.000 SY	_____.	_____.
0220	646.1020 Marking Line Epoxy 4-Inch	24,796.000 LF	_____.	_____.
0222	646.1040 Marking Line Grooved Wet Ref Epoxy 4-Inch	48,617.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20230214044 Project(s): 7140-00-70

Federal ID(s): N/A

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0224	646.3040 Marking Line Grooved Wet Ref Epoxy 8-Inch	1,152.000 LF	_____.	_____.
0226	646.4520 Marking Line Same Day Epoxy 4-Inch	7,035.000 LF	_____.	_____.
0228	646.5020 Marking Arrow Epoxy	2.000 EACH	_____.	_____.
0230	646.5120 Marking Word Epoxy	1.000 EACH	_____.	_____.
0232	646.5220 Marking Symbol Epoxy	1.000 EACH	_____.	_____.
0234	646.6120 Marking Stop Line Epoxy 18-Inch	20.000 LF	_____.	_____.
0236	646.7120 Marking Diagonal Epoxy 12-Inch	325.000 LF	_____.	_____.
0238	646.7420 Marking Crosswalk Epoxy Transverse Line 6-Inch	417.000 LF	_____.	_____.
0240	646.8120 Marking Curb Epoxy	2,000.000 LF	_____.	_____.
0242	646.8320 Marking Parking Stall Epoxy	306.000 LF	_____.	_____.
0244	646.9000 Marking Removal Line 4-Inch	12,100.000 LF	_____.	_____.
0246	650.6000 Construction Staking Pipe Culverts	2.000 EACH	_____.	_____.
0248	650.8000 Construction Staking Resurfacing Reference	31,908.000 LF	_____.	_____.
0250	650.8501 Construction Staking Electrical Installations (project) 01. 7140-00-70	1.000 EACH	_____.	_____.
0252	650.9000 Construction Staking Curb Ramps	37.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20230214044 Project(s): 7140-00-70

Federal ID(s): N/A

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0254	650.9500 Construction Staking Sidewalk (project) 01. 7140-00-70	1.000 EACH	_____.	_____.
0256	650.9911 Construction Staking Supplemental Control (project) 01. 7140-00-70	1.000 EACH	_____.	_____.
0258	652.0215 Conduit Rigid Nonmetallic Schedule 40 1 1/4-Inch	30.000 LF	_____.	_____.
0260	654.0105 Concrete Bases Type 5	2.000 EACH	_____.	_____.
0262	655.0610 Electrical Wire Lighting 12 AWG	250.000 LF	_____.	_____.
0264	655.0625 Electrical Wire Lighting 6 AWG	500.000 LF	_____.	_____.
0266	690.0150 Sawing Asphalt	2,553.000 LF	_____.	_____.
0268	690.0250 Sawing Concrete	344.000 LF	_____.	_____.
0270	715.0720 Incentive Compressive Strength Concrete Pavement	500.000 DOL	1.00000	500.00
0272	740.0440 Incentive IRI Ride	23,740.000 DOL	1.00000	23,740.00
0274	SPV.0055 Special 01. Incentive Density PWL HMA Pavement	13,400.000 DOL	_____.	_____.
0276	SPV.0055 Special 02. Incentive Air Voids HMA Pavement	16,800.000 DOL	_____.	_____.
0278	SPV.0055 Special 03. Incentive Density HMA Pavement Longitudinal Joints	33,170.000 DOL	_____.	_____.
0280	SPV.0060 Special 01. 6-Inch Gate Valve and Box	9.000 EACH	_____.	_____.
0282	SPV.0060 Special 02. Hydrant	2.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20230214044 Project(s): 7140-00-70

Federal ID(s): N/A

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0284	SPV.0060 Special 03. Relocate Existing Light Pole	2.000 EACH	_____.	_____.
0286	SPV.0060 Special 04. Adjusting Water Valve Box	11.000 EACH	_____.	_____.
0288	SPV.0060 Special 05. Adjusting Sanitary Manhole Cover	17.000 EACH	_____.	_____.
0290	SPV.0060 Special 06. Grading and Shaping Apron Endwall Installation	17.000 EACH	_____.	_____.
0292	SPV.0060 Special 07. Grading and Shaping Curb Ramps	37.000 EACH	_____.	_____.
0294	SPV.0060 Special 08. Inlet Covers, Type H-D	4.000 EACH	_____.	_____.
0296	SPV.0090 Special 01. Ditch Cleaning	1,075.000 LF	_____.	_____.
0298	SPV.0090 Special 02. Concrete Gutter 48-inch	27.000 LF	_____.	_____.
0300	SPV.0090 Special 03. Temporary Marking Line Removable Tape 6-Inch	1,000.000 LF	_____.	_____.
0320	611.9800.S Pipe Grates (size) 01. 24-Inch	1.000 EACH	_____.	_____.
Section: 0001			Total:	_____.
			Total Bid:	_____.