



Wisconsin Department of Transportation

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

June 28, 2023

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #07: 6866-06-70
Wautoma – Mt Morris
North Townline Road to CTH G
CTH 152
Waushara County

Letting of July 11, 2023

This is Addendum No. 02, which provides for the following:

Special Provisions:

Revised Special Provisions	
Article No.	Description
3	Prosecution and Progress

Added Special Provisions	
Article No.	Description
25	Asphaltic Surface

Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Proposal Quantity Change (-)	Proposal Total After Addendum
460.2007	Incentive Density HMA Pavement Longitudinal Joints	DOL	18,570.00	-11,140	7,430
460.2010	Incentive Air Voids HMA Pavement	DOL	14,587.00	-437	14,150
460.5224	HMA Pavement 4 LT 58-28 S	TON	14,587.00	-437	14,150

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Quantity Added	Proposal Total After Addendum
465.0105	Asphaltic Surface	TON	0	438	438

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
4	Typical Sections – Finished Typical Section Culvert Replacement changed to show Asphaltic Surface instead of HMA Pavement.
24	Miscellaneous Quantities – HMA Pavement Table modified due to quantity changes and the PWL Mix Use Table changed due to quantity changes.

Other

Revise Contract Completion Time from a 25 working day contract to a completion date of November 15, 2023.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 02

6866-06-70

June 28, 2023

Special Provisions

3. Prosecution and Progress.

Replace paragraphs two and three with the following:

Provide the start date to the engineer in writing within a month after executing the contract but at least 14 calendar days before the preconstruction conference. Upon approval, the engineer will issue the notice to proceed within ten calendar days before the approved start date.

To revise the start date, submit a written request to the engineer at least two weeks before the intended start date. The engineer will approve or deny that request based on the conditions cited in the request and its effect on the department's scheduled resources.

25. Asphaltic Surface.

Replace paragraph one (1) of Standard Spec 465.2 with the following:

Under the Asphaltic Surface, Asphaltic Surface Detours, and Asphaltic Surface Patching bid items; submit a mixture design. Furnish asphaltic mixture meeting the requirements specified for type 4-LT mix under 460.2; except the engineer will not require the contractor to conform to the quality management program specified under 460.2.8. Use tack coat as required under 450.3.2.7.

Schedule of Items


Attached, dated June 28, 2023, are the revised Schedule of Items Pages 3 and 6.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:
Revised: 4 and 24.


END OF ADDENDUM

* SEE CULVERT REPLACEMENT PLAN DETAILS FOR LIMITS




FINISHED TYPICAL SECTION MILL AND OVERLAY

STA. 1492+14 TO STA. 364+13.41
STA. 367+27.77 TO STA. 373+13.10




FINISHED TYPICAL SECTION SLOPE STABILIZATION

STA. 329+38 TO STA. 331+31



FINISHED TYPICAL SECTIONS CULVERT REPLACEMENTS


STA. 11+53.81 TO STA. 12+57.81
STA. 56+42.14 TO STA. 57+06
STA. 66+82.40 TO STA. 67+86.90
STA. 91+17.39 TO STA. 92+21.39
STA. 111+38.79 TO STA. 112+43.11
STA. 301+39.98 TO STA. 302+43.98
STA. 353+27.97 TO STA. 354+32.07



FINISHED TYPICAL SECTION MGS LOCATION

STA. 364+13.41 TO STA. 367+27.77

NOTE:
SEE "PLAN DETAILS: GUARDRAIL REPLACEMENT" PLAN SHEET FOR
LOCATIONS OF 4" ASPHALTIC SURFACE PAVEMENT



EXISTING TYPICAL SECTION

STA. 1492 TO STA. 373+13

Addendum No. 02
ID 6866-06-70
Revised Sheet 4
June 28, 2023



Proposal Schedule of Items

Proposal ID: 20230711007 Project(s): 6866-06-70

Federal ID(s): N/A

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0058	460.2005 Incentive Density PWL HMA Pavement	12,246.000 DOL	1.00000	12,246.00
0060	460.2007 Incentive Density HMA Pavement Longitudinal Joints	7,430.000 DOL	1.00000	7,430.00
0062	460.2010 Incentive Air Voids HMA Pavement	14,150.000 DOL	1.00000	14,150.00
0064	460.5224 HMA Pavement 4 LT 58-28 S	14,150.000 TON	_____.	_____.
0066	465.0110 Asphaltic Surface Patching	130.000 TON	_____.	_____.
0068	522.0424 Culvert Pipe Reinforced Concrete Class IV 24-Inch	166.000 LF	_____.	_____.
0070	522.1024 Apron Endwalls for Culvert Pipe Reinforced Concrete 24-Inch	10.000 EACH	_____.	_____.
0072	522.2314 Culvert Pipe Reinforced Concrete Horizontal Elliptical Class HE-III 14x23- Inch	29.000 LF	_____.	_____.
0074	522.2324 Culvert Pipe Reinforced Concrete Horizontal Elliptical Class HE-III 24x38- Inch	34.000 LF	_____.	_____.
0076	522.2614 Apron Endwalls for Culvert Pipe Reinforced Concrete Horizontal Elliptical 14x23-Inch	2.000 EACH	_____.	_____.
0078	522.2624 Apron Endwalls for Culvert Pipe Reinforced Concrete Horizontal Elliptical 24x38-Inch	2.000 EACH	_____.	_____.
0080	601.0411 Concrete Curb & Gutter 30-Inch Type D	193.000 LF	_____.	_____.
0082	606.0200 Riprap Medium	2.000 CY	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20230711007 Project(s): 6866-06-70

Federal ID(s): N/A

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0148	646.4520 Marking Line Same Day Epoxy 4-Inch	60,287.000 LF	_____.	_____.
0150	646.6464 Cold Weather Marking Epoxy 4-Inch	134,380.000 LF	_____.	_____.
0152	650.5500 Construction Staking Curb Gutter and Curb & Gutter	193.000 LF	_____.	_____.
0154	650.6000 Construction Staking Pipe Culverts	7.000 EACH	_____.	_____.
0156	650.8000 Construction Staking Resurfacing Reference	37,121.000 LF	_____.	_____.
0158	650.9911 Construction Staking Supplemental Control (project) 01. 6866-06-70	1.000 EACH	_____.	_____.
0160	650.9920 Construction Staking Slope Stakes	1,196.000 LF	_____.	_____.
0162	690.0150 Sawing Asphalt	1,100.000 LF	_____.	_____.
0164	740.0440 Incentive IRI Ride	28,122.000 DOL	1.00000	28,122.00
0166	SPV.0060 Special 01. Reestablish Section Corner Monuments	7.000 EACH	_____.	_____.
0168	465.0105 Asphaltic Surface	438.000 TON	_____.	_____.
Section: 0001			Total:	_____.
			Total Bid:	_____.

