



Wisconsin Department of Transportation

January 4, 2024

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #12: 2310-13-70, WISC 2024117
Main St, Village Jackson
CTH P to Eagle Dr
STH 60
Washington County

2310-13-71, WISC 2024118
V Jackson, Eagle Dr
Intersection with STH 60
Local Street
Washington County

Letting of January 9, 2024

This is Addendum No. 03, which provides for the following:

Schedule of Items:

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Quantity Added	Proposal Total After Addendum
204.0100	Removing Concrete Pavement	SY	0	1,565	1,565

Plan Sheets:

Revised Plan Sheets 2310-13-70	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
61	Miscellaneous Quantities (add pay item 204.0100)

Schedule of Items

Attached, dated January 4, 2024, are the revised Schedule of Items Page 17.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

2310-13-71

Revised: 61

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

END OF ADDENDUM

Addendum No. 03
ID 2310-13-71
Revised Sheet 61
January 4, 2024

REMOVING CONCRETE PAVEMENT

204.0100	REMOVING CONCRETE PAVEMENT	SY	1,565
TOTAL 1000			1,565

DIVISION	FROM/TO STATION	LOCATION	COMMON EXCAVATION		SALVAGED/UNUSABLE PAVEMENT MATERIAL (4)	AVAILABLE MATERIAL (5)	UNEXPANDED FILL	EXPANDED FILL (13)		MASS ORDNATE +/- (14)	WASTE (15)	COMMENT
			CUT (2)	EBS EXCAVATION (3)				FACTOR	1.25			
205.0100												
STAGE2 - RWB WEST LEG	301+06.49/303+63.08	L/RT	908	45	98	810	355	444	366	0		
STAGE2 - RWB EAST LEG	304+91.77/306+96.16	L/RT	1,010	51	147	863	264	330	533	0		
STAGE2 - RNB NORTH LEG	402+61.69/403+87.00	L/RT	589	30	96	493	25	31	462	0		
STAGE2 - RSB NORTH LEG	402+63.87/403+22.95	LT	182	10	29	153	5	6	147	0		
STAGE2 - RAB	10+00.00/12+85.84	L/RT	876	44	270	606	513	641	-35	0		USE WASTE MATERIAL FROM OTHER AREAS
STAGE 2 SUB TOTAL			3,565	180	640	2,925	1,162	1,453	1,473	1,473	1,473	
STAGE 3												
STAGE 3 - REB WEST LEG	301+04.26/303+60.30	L/RT	979	50	186	793	3	4	789	0		
STAGE 3 - REB EAST LEG	304+86.54/306+93.45	RT	613	31	106	507	83	104	403	0		
STAGE 3 - RNB SOUTH LEG	400+00.00/401+32.77	L/RT	423	21	76	347	2	3	345	0		
STAGE 3 - RSB SOUTH LEG	400+10.26/401+35.28	LT	270	15	39	231	8	10	221	0		
STAGE 3 - RAB	11+82.35/12+80.93	L/RT	523	30	132	391	45	56	335	0		
STAGE 3 SUB TOTAL			2,808	147	539	2,269	141	176	2,093	2,093	2,093	
GRAND TOTAL			6,373	327	1,179	5,194	1,303	1,629	3,565	3,565	3,565	

NOTES:

- (1) COMMON EXCAVATION IS THE SUM OF THE CUT AND EBS EXCAVATION COLUMNS. ITEM NUMBER 205.0100
 - (2) SALVAGED/UNUSABLE PAVEMENT MATERIAL IS INCLUDED IN CUT.
 - (3) EBS VOLUME ASSUMED TO BE 5% OF CUT VOLUME. EBS EXCAVATION TO BE BACKFILLED WITH SELECT CRUSH MATERIAL. EBS MATERIAL IS ASSUMED TO BE UNUSABLE IN FILLS.
 - (4) SALVAGED/UNUSABLE PAVEMENT MATERIAL INCLUDES EXISTING ASPHALTIC PAVEMENT
 - (5) AVAILABLE MATERIAL = CUT - SALVAGED/UNUSABLE PAVEMENT MATERIAL
 - (13) EXPANDED FILL FACTOR = 1.25 - EXPANDED FILL = (UNEXPANDED FILL)*FILL FACTOR
 - (14) THE MASS ORDNATE + OR - QTY CALCULATED FOR THE DIVISION. PLUS QUANTITY INDICATES AN EXCESS OF MATERIAL WITHIN THE DIVISION. MINUS INDICATES A SHORTAGE OF MATERIAL WITHIN THE DIVISION.
 - (15) FACTORS USED TO COMPUTE ANTICIPATED WASTE AND THE COMPUTED WASTE VOLUME IDENTIFIED ARE FOR GENERAL INFORMATION ONLY.
- UNDISTRIBUTED QUANTITY FOR REMOVING CONCRETE PAVEMENT WAS NOT FACTORED INTO THE EARTHWORK TABLE.

PROJECT NO: 2310-13-71

HWY: EAGLE DRIVE

COUNTY: WASHINGTON

MISCELLANEOUS QUANTITIES

SHEET: 61

E



Proposal Schedule of Items

Proposal ID: 20240109012 Project(s): 2310-13-70, 2310-13-71

Federal ID(s): WISC 2024117, WISC 2024118

SECTION: 0001 Roadway Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0464	SPV.0060 Special 23. Construction Staking Roundabout	1.000 EACH	_____.	_____.
0466	SPV.0060 Special 25. Section Corner Monuments	4.000 EACH	_____.	_____.
0468	SPV.0060 Special 26. Pedestrian Shuttle Service	1.000 EACH	_____.	_____.
0470	SPV.0060 Special 27. Utility Line Opening (ULO)	12.000 EACH	_____.	_____.
0472	SPV.0165 Special 01. Wall Modular Block Mechanically Stabilized Earth (R-66-87)	106.000 SF	_____.	_____.
0474	SPV.0165 Special 02. Wall Modular Block Gravity Landscape	45.000 SF	_____.	_____.
0476	SPV.0195 Special 01. Asphalt Repair	315.000 TON	_____.	_____.
0478	204.0100 Removing Concrete Pavement	1,565.000 SY	_____.	_____.
Section: 0001			Total:	_____.
			Total Bid:	_____.