HIGHWAY WORK PROPOSAL

Notice of Award Dated

Wisconsin Department of Transportation DT1502 01/2020 s.66.0901(7) Wis. Stats Proposal Number:

COUNTY	STATE PROJECT	<u>FEDERAL</u>	PROJECT DESCRIPTION	<u>HIGHWAY</u>
Washington	2310-13-70	WISC 2024117	Main St, Village Jackson; CTH P to Eagle Dr	STH 060
Washington	2310-13-71	WISC 2024118	V Jackson, Eagle Dr; Intersection With STH 60	LOC STR

ADDENDUM REQUIRED

ATTACHED AT BACK

This proposal, submitted by the undersigned bidder to the Wisconsin Department of Transportation, is in accordance with the advertised request for proposals. The bidder is to furnish and deliver all materials, and to perform all work for the improvement of the designated project in the time specified, in accordance with the appended Proposal Requirements and Conditions.

Proposal Guaranty Required: \$100,000.00 Payable to: Wisconsin Department of Transportation	Attach Proposal Guaranty on back of this PAGE.
Bid Submittal Date: January 9, 2024 Time (Local Time): 11:00 am	Firm Name, Address, City, State, Zip Code SAMPLE
Contract Completion Time August 23, 2024	NOT FOR BIDDING PURPOSES
Assigned Disadvantaged Business Enterprise Goal 8%	This contract is exempt from federal oversight.

This certifies that the undersigned bidder, duly sworn, is an authorized representative of the firm named above; that the bidder has examined and carefully prepared the bid from the plans, Highway Work Proposal, and all addenda, and has checked the same in detail before

submitting this proposal or bid; and that the bidder or agents, officer, or employees have not, either directly or indirectly, entered into any agreement, participated in any collusion, or otherwise taken any action in restraint of free competitive bidding in connection with this proposal bid. Do not sign, notarize, or submit this Highway Work Proposal when submitting an electronic hid on the Internet

Subscribed and sworn to before me this date	
(Signature, Notary Public, State of Wisconsin)	(Bidder Signature)
(Print or Type Name, Notary Public, State Wisconsin)	(Print or Type Bidder Name)
(Date Commission Expires)	(Bidder Title)
Notary Seal	
Type of Work: For Department U	se Only
Grading, Base, Milling, Asphalt Pavement, Concrete Truck Apron, Culvert F Pavement Markings, Traffic Signals, Street Lighting, Modular Block Wall.	Pipe, Curb and Gutter, Sidewalk, Storm Sewer, Signs,

Date Guaranty Returned

PLEASE ATTACH PROPOSAL GUARANTY HERE

PROPOSAL REQUIREMENTS AND CONDITIONS

The bidder, signing and submitting this proposal, agrees and declares as a condition thereof, to be bound by the following conditions and requirements.

If the bidder has a corporate relationship with the proposal design engineering company, the bidder declares that it did not obtain any facts, data, or other information related to this proposal from the design engineering company that was not available to all bidders.

The bidder declares that they have carefully examined the site of, and the proposal, plans, specifications and contract forms for the work contemplated, and it is assumed that the bidder has investigated and is satisfied as to the conditions to be encountered, as to the character, quality, and quantities of work to be performed and materials to be furnished, and as to the requirements of the specifications, special provisions and contract. It is mutually agreed that submission of a proposal shall be considered conclusive evidence that the bidder has made such examination.

The bidder submits herewith a proposal guaranty in proper form and amount payable to the party as designated in the advertisement inviting proposals, to be retained by and become the property of the owner of the work in the event the undersigned shall fail to execute the contract and contract bond and return the same to the office of the engineer within fourteen (14) days after having been notified in writing to do so; otherwise to be returned.

The bidder declares that they understand that the estimate of quantities in the attached schedule is approximate only and that the attached quantities may be greater or less in accordance with the specifications.

The bidder agrees to perform the said work, for and in consideration of the payment of the amount becoming due on account of work performed, according to the unit prices bid in the following schedule, and to accept such amounts in full payment of said work.

The bidder declares that all of the said work will be performed at their own proper cost and expense, that they will furnish all necessary materials, labor, tools, machinery, apparatus, and other means of construction in the manner provided in the applicable specifications and the approved plans for the work together with all standard and special designs that may be designed on such plans, and the special provisions in the contract of which this proposal will become a part, if and when accepted. The bidder further agrees that the applicable specifications and all plans and working drawings are made a part hereof, as fully and completely as if attached hereto.

The bidder, if awarded the contract, agrees to begin the work not later than ten (10) days after the date of written notification from the engineer to do so, unless otherwise stipulated in the special provisions.

The bidder declares that if they are awarded the contract, they will execute the contract agreement and begin and complete the work within the time named herein, and they will file a good and sufficient surety bond for the amount of the contract for performance and also for the full amount of the contract for payment.

The bidder, if awarded the contract, shall pay all claims as required by Section 779.14, Statutes of Wisconsin, and shall be subject to and discharge all liabilities for injuries pursuant to Chapter 102 of the Statutes of Wisconsin, and all acts amendatory thereto. They shall further be responsible for any damages to property or injury to persons occurring through their own negligence or that of their employees or agents, incident to the performance of work under this contract, pursuant to the Standard Specifications for Road and Bridge Construction applicable to this contract.

In connection with the performance of work under this contract, the contractor agrees to comply with all applicable state and federal statutes relating to non-discrimination in employment. No otherwise qualified person shall be excluded from employment or otherwise be subject to discrimination in employment in any manner on the basis of age, race, religion, color, gender, national origin or ancestry, disability, arrest or conviction record (in keeping with s.111.32), sexual orientation, marital status, membership in the military reserve, honesty testing, genetic testing, and outside use of lawful products. This provision shall include, but not be limited to the following: employment, upgrading, demotion or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation, and selection for training, including apprenticeship. The contractor further agrees to ensure equal opportunity in employment to all applicants and employees and to take affirmative action to attain a representative workforce.

The contractor agrees to post notices and posters setting forth the provisions of the nondiscrimination clause, in a conspicuous and easily accessible place, available for employees and applicants for employment.

If a state public official (section 19.42, Stats.) or an organization in which a state public official holds at least a 10% interest is a party to this agreement, this contract is voidable by the state unless appropriate disclosure is made to the State of Wisconsin Ethics Board.

BID PREPARATION

Preparing the Proposal Schedule of Items

A. General

- (1) Obtain bidding proposals as specified in section 102 of the standard specifications prior to 11:45 AM of the last business day preceding the letting. Submit bidding proposals using one of the following methods:
 - 1. Electronic bid on the internet.
 - 2. Electronic bid on a printout with accompanying diskette or CD ROM.
 - 3. Paper bid under a waiver of the electronic submittal requirements.
- (2) Bids submitted on a printout with accompanying diskette or CD ROM or paper bids submitted under a waiver of the electronic submittal requirements govern over bids submitted on the internet.
- (3) The department will provide bidding information through the department's web site at:

https://wisconsindot.gov/Pages/doing-bus/contractors/hcci/bid-let.aspx

The contractor is responsible for reviewing this web site for general notices as well as information regarding proposals in each letting. The department will also post special notices of all addenda to each proposal through this web site no later than 4:00 PM local time on the Thursday before the letting. Check the department's web site after 5:00 PM local time on the Thursday before the letting to ensure all addenda have been accounted for before preparing the bid. When bidding using methods 1 and 2 above, check the Bid ExpressTM on-line bidding exchange at http://www.bidx.com/ after 5:00 PM local time on the Thursday before the letting to ensure that the latest schedule of items Expedite file (*.ebs or *.00x) is used to submit the final bid.

(4) Interested parties can subscribe to the Bid ExpressTM on-line bidding exchange by following the instructions provided at the www.bidx.com web site or by contacting:

Info Tech Inc.
5700 SW 34th Street, Suite 1235
Gainesville, FL 32608-5371
email: mailto:customer.support@bidx.com

- (5) The department will address equipment and process failures, if the bidder can demonstrate that those failures were beyond their control.
- (6) Contractors are responsible for checking on the issuance of addenda and for obtaining the addenda. Notice of issuance of addenda is posted on the department's web site at:

https://wisconsindot.gov/Pages/doing-bus/contractors/hcci/bid-let.aspx

- or by calling the department at (608) 266-1631. Addenda can ONLY be obtained from the department's web site listed above or by picking up the addenda at the Bureau of Highway Construction, 4th floor, 4822 Madison Yards Way, Madison, WI, during regular business hours.
- (7) Addenda posted after 5:00 PM on the Thursday before the letting will be emailed to the eligible bidders for that proposal. All eligible bidders shall acknowledge receipt of the addenda whether they are bidding on the proposal or not. Not acknowledging receipt may jeopardize the awarding of the project.

B. Submitting Electronic Bids

B.1 On the Internet

- (1) Do the following before submitting the bid:
 - 4. Have a properly executed annual bid bond on file with the department.
 - 5. Have a digital ID on file with and enabled by Info Tech Inc. Using this digital ID will constitute the bidder's signature for proper execution of the bidding proposal.
- (2) In lieu of preparing, delivering, and submitting the proposal as specified in 102.6 and 102.9 of the standard specifications, submit the proposal on the internet as follows:
 - 1. Download the latest schedule of items reflecting all addenda from the Bid Express TM web site.
 - 2. Use ExpediteTM software to enter a unit price for every item in the schedule of items.
 - 3. Submit the bid according to the requirements of ExpediteTM software and the Bid ExpressTM web site. Do not submit a bid on a printout with accompanying diskette or CD ROM or a paper bid. If the bidder does submit a bid on a printout with accompanying diskette or a paper bid in addition to the internet submittal, the department will disregard the internet bid
 - 4. Submit the bid before the hour and date the Notice to Contractors designates
 - 5. Do not sign, notarize, and return the bidding proposal described in 102.2 of the standard specifications.
- (3) The department will not consider the bid accepted until the hour and date the Notice to Contractors designates.

B.2 On a Printout with Accompanying Diskette or CD ROM

- (1) Download the latest schedule of items from the Wisconsin pages of the Bid Express web site reflecting the latest addenda posted on the department's web site at:
 - https://wisconsindot.gov/Pages/doing-bus/contractors/hcci/bid-let.aspx
 - Use ExpediteTM software to prepare and print the schedule of items. Provide a valid amount for all price fields. Follow instructions and review the help screens provided on the Bid ExpressTM web site to assure that the schedule of items is prepared properly.
- (2) Staple an 8 1/2 by 11 inch printout of the Expedite □ □ generated schedule of items to the other proposal documents submitted to the department as a part of the bidder's sealed bid. As a separate submittal, not in the sealed bid envelop but due at the same time and place as the sealed bid, also provide the Expedite TM generated schedule of items on a 3 1/2 inch computer diskette or CD ROM. Label each diskette or CD ROM with the bidder's name, the 4 character department-assigned bidder identification code from the top of the bidding proposal, and a list of the proposal numbers included on that diskette or CD ROM as indicated in the following example:

Bidder Name BN00

Proposals: 1, 12, 14, & 22

- (3) If bidding on more than one proposal in the letting, the bidder may include all proposals for that letting on one diskette or CD ROM. Include only submitted proposals with no incomplete or other files on the diskette or CD ROM.
- (4) The bidder-submitted printout of the Expedite □ □ generated schedule of items is the governing contract document and must conform to the requirements of section 102 of the standard specifications. If a printout needs to be altered, cross out the printed information with ink or typewriter and enter the new information and initial it in ink. If there is a discrepancy between the printout and the diskette or CD ROM, the department will analyze the bid using the printout information.

- (5) In addition to the reasons specified in section 102 of the standard specifications, proposals are irregular and the department may reject them for one or more of the following:
 - 1. The check code printed on the bottom of the printout of the Expedite TM generated schedule of items is not the same on each page.
 - 2. The check code printed on the printout of the Expedite TM generated schedule of items is not the same as the check code for that proposal provided on the diskette or CD ROM.
 - 3. The diskette or CD ROM is not submitted at the time and place the department designates.

B Waiver of Electronic Submittal

- (1) The bidder may request a waiver of the electronic submittal requirements. Submit a written request for a waiver in lieu of bids submitted on the internet or on a printout with accompanying diskette or CD ROM. Use the waiver that was included with the paper bid document sent to the bidder or type up a waiver on the bidder's letterhead. The department will waive the electronic submittal requirements for a bidding entity (individual, partnership, joint venture, corporation, or limited liability company) for up to 4 individual proposals in a calendar year. The department may allow additional waivers for equipment malfunctions.
- (2) Submit a schedule of items on paper conforming to section 102 of the standard specifications. The department charges the bidder a \$75 administrative fee per proposal, payable at the time and place the department designates for receiving bids, to cover the costs of data entry. The department will accept a check or money order payable to: "Wisconsin, Dept. of Transportation."
- (3) In addition to the reasons specified in section 102 of the standard specifications, proposals are irregular and the department may reject them for one or more of the following:
 - 1. The bidder fails to provide the written request for waiver of the electronic submittal requirements.
 - 2. The bidder fails to pay the \$75 administrative fee before the time the department designates for the opening of bids unless the bidder requests on the waiver that they be billed for the \$75.
 - 3. The bidder exceeds 4 waivers of electronic submittal requirements within a calendar year.
- (4) In addition to the reasons specified in section 102 of the standard specifications, the department may refuse to issue bidding proposals for future contracts to a bidding entity that owes the department administrative fees for a waiver of electronic submittal requirements.

DT1303 1/2006

Proposal Number	Project Number		Letting Date
Name of Principal			
Name of Surety		State in Which Surety is	Organized

We, the above-named Principal and the above-named Surety, are held and firmly bound unto the State of Wisconsin in the sum equal to the Proposal Guaranty for the total bid submitted for the payment to be made; we jointly and severally bind ourselves, our heirs, executors, administrators, successors and assigns. The condition of this obligation is that the Principal has submitted a bid proposal to the State of Wisconsin acting through the Department of Transportation for the improvement designated by the Proposal Number and Letting Date indicated above.

If the Principal is awarded the contract and, within the time and manner required by law after the prescribed forms are presented for signature, enters into a written contract in accordance with the bid, and files the bond with the Department of Transportation to guarantee faithful performance and payment for labor and materials, as required by law, or if the Department of Transportation shall reject all bids for the work described, then this obligation shall be null and void; otherwise, it shall be and remain in full force and effect. In the event of failure of the Principal to enter into the contract or give the specified bond, the Principal shall pay to the Department of Transportation within 10 business days of demand a total equal to the Proposal Guaranty as liquidated damages; the liability of the Surety continues for the full amount of the obligation as stated until the obligation is paid in full.

The Surety, for value received, agrees that the obligations of it and its bond shall not be impaired or affected by any extension of time within which the Department of Transportation may accept the bid; and the Surety does waive notice of any such extension.

IN WITNESS, the Principal and Surety have agreed and have signed by their proper officers and have caused their corporate seals to be affixed this date: **(DATE MUST BE ENTERED)**

PRINCIPAL

(Company Name) (Affix Corporate Seal)			
(Signature and Title)			
(Company Name)			
(Signature and Title)			
(Company Name)			
(Signature and Title)		(Name of Surety) (Affix Seal)	
(Company Name)		(Signature of Attorney-in-Fact)	
(Signature and Title)			
NOTARY FOR PRINCIPAL		NOTARY FO	R SURETY
(Date)		(Dat	te)
State of Wisconsin)		State of Wisconsin)
County)	SS.) ss. _County)
On the above date, this instrument was acknowledged before me by the named person(s).		On the above date, this instrument w named person(s).	as acknowledged before me by the
(Signature, Notary Public, State of Wisco	onsin)	(Signature, Notary Publ	ic, State of Wisconsin)
(Print or Type Name, Notary Public, State of V	Visconsin)	(Print or Type Name, Notary	Public, State of Wisconsin)
(Date Commission Expires)		(Date Commis	sion Expires)

Notary Seal Notary Seal

IMPORTANT: A certified copy of Power of Attorney of the signatory agent must be attached to the bid bond.

CERTIFICATE OF ANNUAL BID BOND

DT1305 8/2003

Wisconsin Department of Transportation

(Date)

Time Period Valid (From/To)
Name of Surety	
Name of Contractor	
Certificate Holder	Wisconsin Department of Transportation
•	y that an annual bid bond issued by the above-named Surety is currently on file with the artment of Transportation.
	is issued as a matter of information and conveys no rights upon the certificate holder mend, extend or alter the coverage of the annual bid bond.
Cancellation:	Should the above policy be cancelled before the expiration date, the issuing surety will give thirty (30) days written notice to the certificate holder indicated above.

(Signature of Authorized Contractor Representative)

LIST OF SUBCONTRACTORS

Section 66.0901(7), Wisconsin Statutes, provides that as a part of the proposal, the bidder also shall submit a list of the subcontractors the bidder proposes to contract with and the class of work to be performed by each. In order to qualify for inclusion in the bidder's list a subcontractor shall first submit a bid in writing, to the general contractor at least 48 hours prior to the time of the bid closing. The list may not be added to or altered without the written consent of the municipality. A proposal of a bidder is not invalid if any subcontractor and the class of work to be performed by the subcontractor has been omitted from a proposal; the omission shall be considered inadvertent or the bidder will perform the work personally.

No subcontract, whether listed herein or later proposed, may be entered into without the written consent of the Engineer as provided in Subsection 108.1 of the Standard Specifications.

Name of Subcontractor	Class of Work	Estimated Value

CERTIFICATION REGARDING DEBARMENT, SUSPENSION, AND OTHER RESPONSIBILITY MATTERS - PRIMARY COVERED TRANSACTIONS

Instructions for Certification

- By signing and submitting this proposal, the prospective contractor is providing the certification set out below.
- 2. The inability of a person to provide the certification required below will not necessarily result in denial of participation in this covered transaction. The prospective contractor shall submit an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective contractor to furnish a certification or an explanation shall disqualify such person from participation in this transaction.
- 3. The certification in this clause is a material representation of fact upon which reliance was placed when the department determined to enter into this transaction. If it is later determined that the contractor knowingly rendered an erroneous certification in addition to other remedies available to the Federal Government the department may terminate this transaction for cause or default.
- 4. The prospective contractor shall provide immediate written notice to the department to whom this proposal is submitted if at any time the prospective contractor learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.
- 5. The terms "covered transaction," "debarred," "suspended," "ineligible," "lower tier covered transaction," "participant," "person," "primary covered transaction," "principal," "proposal," and "voluntarily excluded," as used in this clause, have the meanings set out in the Definitions and Coverage sections of the rules implementing Executive Order 12549. You may contact the department to which this proposal is being submitted for assistance in obtaining a copy of those regulations.
- 6. The prospective contractor agrees by submitting this proposal that, should this contract be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department entering into this transaction.
- 7. The prospective contractor further agrees by submitting this proposal that it will include the clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," which is included as an addendum to PR- 1273 "Required Contract Provisions Federal Aid Construction Contracts," without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions.
- 8. The contractor may rely upon a certification of a prospective subcontractor/materials supplier that it is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A contractor may decide the method and frequency by which it determines the eligibility of its principals. Each contractor may, but is not required to, check the Disapproval List (telephone # 608/266/1631).

- 9. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of a contractor is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
- 10. Except for transactions authorized under paragraph 6 of these instructions, if a contractor in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department may terminate this transaction for cause or default.

<u>Certification Regarding Debarment, Suspension, and Other Responsibility Matters - Primary Covered Transactions</u>

- 1. The prospective contractor certifies to the best of its knowledge and belief, that it and its principals:
 - (a) Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from covered transactions by any Federal department or agency;
 - (b) Have not within a three-year period preceding this proposal been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements or receiving stolen property;
 - (c) Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offense enumerated in paragraph (1)(b) of this certification; and
 - (d) Have not within a three-year period preceding this proposal had one or more public transactions (Federal, State or local) terminated for cause or default.
- 2. Where the prospective contractor is unable to certify to any of the statements in this certification, such prospective contractor shall attach an explanation to this proposal.

Special Provisions

Table of Contents

	Article	Description I	Page #
1.	General		3
2.	Scope of Work		3
3.	Prosecution and Progress		3
4.	Traffic		7
5.	Holiday and Special Event Work Res	trictions.	11
6.	Utilities		12
7.	Work by Others – Village of Jackson.		20
8.	Work by Others – Washington Count	y Highway Department	20
9.	Railroad Insurance and Coordination	- Wisconsin and Southern Railroad Company	20
10.	Information to Bidders, U.S. Army Co	orps of Engineers Section 404 Permit	21
11.	Construction Over or Adjacent to Nav	vigable Waters	22
12.	Environmental Protection, Aquatic Ex	cotic Species Control.	22
13.	Archaeological Site		23
14.	Historic Boundary		23
15.	Notice to Contractor – Railroad Coord	dination – Wisconsin and Southern Railroad Company	23
16.	Notice to Contractor – Traffic Signal I	Equipment Lead Time	23
17.	Material Stockpile and Equipment Sto	orage	23
18.	Timely Decision-Making Manual		24
19.	Coordination with Businesses and Re	esidents	24
20.	Public Convenience and Safety		24
21.	60 & Industrial Dr, Item 204.9060.S.0	CTH P, Item 204.9060.S.01; Removing Traffic Signals STH 02; Removing Traffic Signals STH 60 & Jackson Dr, Item	24
22.	Loop Detector Wire & Lead In Cable	d In Cable STH 60 & CTH P, Item 204.9060.S.04; Removing STH 60 & Industrial Dr, Item 204.9060.S.05; Removing Loop 60 & Jackson Dr, Item 204.9060.S.06	25
23.	Excavation, Hauling, and Disposal of	Petroleum Contaminated Soil, Item 205.0501.S	26
24.	Base Aggregate Dense 1 1/4-Inch for	r Lower Base Layers	29
25.	Adjusting Storm Sewer Structures		29
26.	Inlets 4-FT Diameter, Item 611.3004.		29
27.	Cover Plates Temporary, Item 611.8	120.S	29
28.	Pipe Grates 48-Inch, Item 611.9850.	S.01	30
29.	Fertilizer Type B		30
30.	Signs Type I and II		31
31.	General Requirements for Electrical	Work	32
32.	Electrical Conduit		32
33.	Electrical Wiring		32
34.	Meter Breaker Pedestal STH 60 & In-	estal STH 60 & CTH P, Item 656.0201.01; Electrical Service dustrial Dr, Item 656.0201.02; Electrical Service Meter Dr, Item 656.0201.03.	32

35.	Traffic Signals, General	32
36.	Signal Mounting Hardware.	33
37.	Traffic Signal Faces	33
38.	Lamp, Ballast, LED, Switch Disposal by Contractor, Item 659.5000.S.	33
39.	Temporary Traffic Signals for Intersections STH 60 & CTH P, Item 661.0201.01; Temporary Traffic Signals for Intersections STH 60 & Industrial Dr, Item 661.0201.02; Temporary Traffic Signals for Intersections STH 60 & Jackson Dr, Item 661.0201.03	34
40.	Install Type 9 Pole, Item SPV.0060.01; Install Type 10 Pole, Item SPV.0060.03; Install Type 10 Special Pole, Item SPV.0060.04; Install Monotube Arms 25-FT, Item SPV.0060.05; Install Monotube Arms 30-FT, Item SPV.0060.06; Install Monotube Arms 35-FT Special, Item SPV.0060.07; Install Monotube Arms 40-FT Special, Item SPV.0060.08; Install Luminaire Arms Steel 15-FT, Item SPV.0060.09.	36
41.	Transport and Install State Furnished EVP Detector Heads STH 60 & CTH P, Item SPV.0060.10; Transport and Install State Furnished EVP Detector Heads STH 60 & Industrial Dr, Item SPV.0060.11; Transport and Install State Furnished EVP Detector Heads STH 60 & Jackson Dr, Item SPV.0060.12.	36
42.	Transport and Install State Furnished Traffic Signal Cabinet STH 60 & CTH P, Item SPV.0060.13; Transport and Install State Furnished Traffic Signal Cabinet STH 60 & Industrial Dr, Item SPV.0060.14; Transport and Install State Furnished Traffic Signal Cabinet STH 60 & Jackson Dr, Item SPV.0060.15.	37
43.	Temporary Infrared EVP System STH 60 & CTH P, Item SPV.0060.16; Temporary Infrared EVP System STH 60 & Industrial Dr, Item SPV.0060.17; Temporary Infrared EVP System STH 60 & Jackson Dr, Item SPV.0060.18.	38
44.	Transport Traffic Signal and Lighting Materials STH 60 & CTH P, Item SPV.0060.19; Transport Traffic Signal and Lighting Materials STH 60 & Industrial Dr, Item SPV.0060.20; Transport Traffic Signal and Lighting Materials STH 60 & Jackson Dr, Item SPV.0060.21	39
45.	Saddle Inlet, Item SPV.0060.22.	39
46.	Construction Staking Roundabout, Item SPV.0060.23	40
47.	Section Corner Monuments, Item SPV.0060.25	40
48.	Pedestrian Shuttle Service, Item SPV.0060.26.	42
49.	Utility Line Opening (ULO), Item SPV.0060.27.	42
50.	Wall Modular Block Mechanically Stabilized Earth (R-66-87), Item SPV.0165.01.	43
51.	Wall Modular Block Gravity Landscape, Item SPV.0165.02	54
52.	Asphalt Repair, Item SPV.0195.01	58

2310-13-70, 2310-13-71 2 of 59

STSP'S Revised June 29, 2023 SPECIAL PROVISIONS

1. General.

Perform the work under this construction contract for Project 2310-13-70, Main St, Village of Jackson, CTH P to Eagle Dr, STH 60, Washington County; 2310-13-71, V Jackson, Eagle Dr, Intersection with STH 60, Local Street, Washington County, Wisconsin as the plans show and execute the work as specified in the State of Wisconsin, Department of Transportation, Standard Specifications for Highway and Structure Construction, 2024 Edition, as published by the department, and these special provisions.

If all or a portion of the plans and special provisions are developed in the SI metric system and the schedule of prices is developed in the US standard measure system, the department will pay for the work as bid in the US standard system.

100-005 (20230629)

2. Scope of Work.

The work under this contract shall consist of 2310-13-70: HMA milling and resurfacing, curb and gutter, curb ramps, sidewalk, traffic signals, lighting, signs, traffic control, pavement markings, restoration; 2310-13-71: Excavation common, retaining wall removal and replacement, culvert pipe extensions, storm sewer, grading, base aggregate, curb and gutter, curb ramps, sidewalk, HMA surface, lighting, signs, traffic control, pavement markings, restoration and all incidental items necessary to complete the work as shown on the plans and included in the proposal and contract.

104-005 (20090901)

3. Prosecution and Progress.

Begin work within 10 calendar days after the engineer issues a written notice to do so.

Provide the start date to the engineer in writing within a month after executing the contract but at least 14 calendar days before the preconstruction conference. Upon approval, the engineer will issue the notice to proceed within ten calendar days before the approved start date.

Do not begin construction prior to March 1, 2024, without written consent from the engineer.

Furnish a written request to the engineer for approval to begin work prior to March 1, 2024. The request for a conditional notice to proceed shall be specific and include description of work, work zones, schedule, haul routes and traffic impacts. The department will not consider requests for contract time extensions as specified in Standard Specification 108 or additional compensation for delay specified in standard spec 109 related to early construction until a full notice to proceed is issued.

If construction is allowed before March 1, 2024, by the engineer, the contractor is responsible for any additional costs related to early start.

Attend weekly scheduling meetings to discuss the near-term schedule activities, address any long-term schedule issues, and discuss any relevant technical issues. Develop a rolling three-week schedule identifying the previous week worked and a two week "look ahead". Provide sufficient detail to include actual and planned activities and all the subcontractors for offsite and construction activities, addressing all activities including curb ramp, intersection, and lane closure schedules to be performed and identifying issues requiring engineering action or input. Subcontractors shall be in attendance at the weekly progress meetings if identified on the two week "look ahead".

The contract time for completion is based on an expedited work schedule and may require extraordinary forces and equipment.

2310-13-70, 2310-13-71 3 of 59

Construction ID 2310-13-70

Interim Completion and Liquidated Damages – STH 60 - CTH P to Eagle Drive shall have all work except traffic signal installation completed: July 31, 2024

Complete construction operations on STH 60 to the stage necessary to reopen it to through traffic by 11:59 PM on July 31, 2024. Do not reopen until completing the following work: installation of permanent signing and pavement markings.

If the contractor fails to complete the work necessary to reopen STH 60 to traffic by 11:59 PM on July 31, 2024, the department will assess the contractor \$2,175 in interim liquidated damages for each calendar day the contract work remains incomplete beyond 12:01 AM on August 1, 2024. An entire calendar day will be charged for any period of time within a calendar day that the road remains closed beyond 12:01 AM.

Construction ID 2310-13-71

Interim Completion and Liquidated Damages – Eagle Dr, Intersection with STH 60 Roundabout shall have culvert extensions and retaining wall R-66-87 completed: May 1, 2024

Complete construction operations on Eagle Dr, Intersection with STH 60 Roundabout to the stage necessary to reopen it to through traffic by 11:59 PM on May 1, 2024. Do not reopen until completing the following work: installation of culvert extensions and retaining wall R-66-87.

If the contractor fails to complete the work necessary to reopen Eagle Dr, Intersection with STH 60 Roundabout to traffic by 11:59 PM on May 1, 2024, the department will assess the contractor \$2,175 in interim liquidated damages for each calendar day the contract work remains incomplete beyond 12:01 AM on May 2, 2024. An entire calendar day will be charged for any period of time within a calendar day that the road remains closed beyond 12:01 AM.

If contract time expires prior to completing all work specified in the contract, additional liquidated damages will be affixed according to standard spec 108.11.

A Contractor Coordination

Coordinate the work according to standard spec 105.5.2.

Do not commence work under this contract until the required traffic control devices and markings are in place and the engineer approves the installations.

Arrange and conduct weekly progress meetings. The contractor's superintendent or representative, designated materials representative, subcontractor's representatives for ongoing subcontract work or subcontract work expected to begin within the next three weeks shall attend. Provide and discuss the schedule and updates at the weekly progress meetings. Agenda items at the meeting shall include, but not be limited to, the following:

- Review of the contractor's and subcontractors' schedule. Indicate if the project is on, ahead or behind schedule. If behind, indicate why, how much behind, and how the project will get back on schedule.
- Utility conflicts and relocation schedule.
- Evaluation of progress to date.
- Outstanding Requests for Information (RFIs) or issues that may cause contract modifications.
- Shop drawing submittal status.
- Materials submittal status.
- Materials sampling and testing activities and results.
- Lane, road, and ramp closure schedules.
- Impacts to businesses and private properties.
- Impacts to bus routes, emergency services, postal services.
- Equipment status of orders and deliveries.

2310-13-70, 2310-13-71 4 of 59

Provide proposed sequence of operations and methods of handling traffic. Submit revisions in traffic handling to the engineer for approval at least 48-hours in advance of making any changes in traffic operations.

Once the work has started on the contract, work continually until the contract work is complete. The contract will not be considered complete until all items on the contract are completed, including sodding and roadway finishing.

Obtain permission from the engineer a minimum of 48 hours prior to any construction schedule change.

If the contractor desires to work on Saturday, Sunday, or nationally recognized legal holidays, he must obtain approval from the engineer at least 24 hours in advance. If scheduling changes after approval has been obtained, notify the engineer as soon as possible, but not later than 3:00 PM of the prior day.

Except where noted, always keep the intersection accessible. Include any costs associated with staging operations at intersections that are to always remain accessible in the unit bid price for Traffic Control (Project).

Maintain or provide pedestrian access to adjacent properties, businesses, and at bus stops where necessary, as directed by the engineer.

At locations where pedestrian access will be maintained, provide temporary means to prevent grade differences greater than 1/4-inch. Bridge vertical differences using slopes of 12:1 or greater through temporary asphalt wedging or through other means approved by the engineer. Temporary asphalt wedging placed separately from mainline HMA paving operations to be paid for as temporary pedestrian surface asphalt. Work to maintain and remove temporary pavements incidental to temporary pedestrian surface asphalt.

No extra cost will be allowed for "cold weather protection" as addressed in standard spec 415.13.

Store drums, buckets and other containers related to construction operations in a secure area to prevent vandalism, spills, and unwanted dumping. If an abandoned container is discovered on the project site, notify the WDNR at (800) 943-0003.

The labor and materials required to restore concrete sidewalk, after saw cutting, will be deemed incidental to the bid item 690.0250, Sawing Concrete.

B Work Restrictions

B.1 General

Comply with all local ordinances which apply to work operations, including those pertaining to work during night-time hours. Furnish all ordinance variances issued by the municipality or required permits. to the engineer in writing three working days before performing such work. Night-time and weekend work will not be allowed without written approval from the engineer and the Village of Jackson at least three days in advance of the planned work during night-time and weekend hours.

Do not store equipment, vehicles, or materials on adjacent streets beyond the project limits without specific approval from the engineer. Park and store equipment and material only at work sites approved by the engineer.

Where the engineer in conjunction with the contractor's work schedule has permitted lane closure(s), make a continuous effort to complete the work within said lane closure(s) in a timely manner. If, in the engineer's judgment, the contractor's operations fail to meet the approved schedule, permission for a full-time parking lane closure will be rescinded.

Do not begin or continue any work that closes traffic lanes outside the allowed time periods specified in the Traffic article in these special provisions.

At locations that vehicular traffic and access will be maintained, provide temporary means to prevent grade differences greater than 2 inches between milled surfaces and existing or newly paved surfaces (both longitudinal and transverse) and temporary means to accommodate traffic across staged construction of concrete pavement. Bridge vertical differences using slopes of 12:1 or greater through milling of existing HMA pavement, through temporary asphalt wedging, through the use of wedge/tapered joint as part of mainline HMA paving, or through other means as approved by the engineer. Work to remove temporary pavements or to remove longitudinal wedge/tapered joints to be paid for as removing asphaltic surface butt joints. Temporary asphalt wedging placed separately from mainline HMA paving operations to be paid for as asphaltic surface temporary.

2310-13-70, 2310-13-71 5 of 59

Maintain or provide pedestrian access to adjacent properties, businesses, and bus stops where necessary, as directed by the engineer. When closing or relocating crosswalks or sidewalks, provide detectable temporary facilities and include accessibility features consistent with existing pedestrian facilities. Construction of the new curb ramps at each intersection shall be performed in a manner to minimize pedestrian disruption to the extent practical. Provide temporary curb ramps and/or bridging between the curb and right-of-way line over new pavement and other obstructions on the sidewalk area at the entrances to buildings or as directed by the engineer. The cost to maintain pedestrian access shall be incidental to the following bid item: Concrete Sidewalk 5-Inch.

Maintain emergency access to the project area at all times.

Upon completion of the normal workday and when work is not in progress, provide a minimum 3:1 slope off the edge of existing pavements. Sloping shall consist of materials suitable for carrying a vehicle.

Add the following to standard spec 107.18 Environmental Protection:

When performing the roadway cleaning operation, use equipment having vacuum or water spray mechanisms to eliminate the dispersion of dust. If vacuum equipment is employed, it shall have suitable, self-contained particulate collectors to prevent discharge from collection bin into the atmosphere.

Store drums, buckets and other containers related to construction operations in a secure area to prevent vandalism, spills, and unwanted dumping. If an abandoned container is discovered on the project site, notify the WDNR at (800) 943-0003.

Add the following to standard spec 108.9.4 Contract Time for Completion Date Contracts:

Work on Saturday, Sunday, or nationally recognized legal holidays will not be allowed without approval from the engineer and the Village of Jackson at least 24 hours in advance. If scheduling changes after approval has been obtained, notify the engineer as soon as possible, but not later than 3:00 PM of the prior day.

Fish Spawning

There shall be no instream disturbance of Cedar Creek as a result of construction activity under or for this contract, from March 1 to June 15 both dates inclusive, in order to avoid adverse impacts upon the spawning of fish species and other aquatic organisms.

There shall be no instream disturbance of unnamed tributary at Station 301+75RWB to 307+00RWB as a result of construction activity under or for this contract from June 1, 2024, to August 15, 2024, both dates inclusive, in order to avoid adverse impacts upon the spawning of Redfin Shiner.

Any change to this limitation will require submitting a written request by the contractor to the engineer, subsequent review, and concurrence by the Department of Natural Resources in the request, and final approval by the engineer. The approval will include all conditions to the request as mutually agreed upon by WisDOT and DNR.

Migratory Birds

No evidence of swallow or other migratory bird nests have been observed on or under the following structures(s) during the preconstruction inspection. However, if nesting is later observed prior to or during construction, the contractor shall implement avoidance/deterrent measures or obtain a depredation permit. All active nests (when eggs or young are present) of migratory birds are protected under the federal Migratory Bird Treaty Act. The nesting season for swallows and other birds is from April 15 to August 31.

Project ID: 2310-13-71, Structure R-66-87

2310-13-70, 2310-13-71 6 of 59

Northern Long-eared Bat (Myotis septentrionalis)

Northern long-eared bats (NLEB) have the potential to inhabit the project limits because they roost in trees, bridges, and culverts. Roosts may not have been observed on this project, but conditions to support the species exist. The species and all active roosts are protected by the federal Endangered Species Act. If an individual bat or active roost is encountered during construction operations, stop work, and notify the engineer and the WisDOT Regional Environmental Coordinator (REC).

Ensure all operators, employees, and subcontractors working in areas of known or presumed bat habitat are aware of environmental commitments and avoidance and minimization measures (AMMs) to protect both bats and their habitat.

Direct temporary lighting, if used, away from wooded areas during the bat active season: April 1 to October 31, both dates inclusive.

Contractor means and methods to remove trees will not be allowed. If it is determined that trees with a 3-inch or greater diameter at breast height (dbh) need to be removed beyond contractor means and methods, notify the engineer to coordinate with the WisDOT REC to determine if consultation with United States Fish and Wildlife Service (USFWS) is required. The contractor must be aware that the WisDOT REC and/or USFWS may not permit modifications.

4. Traffic.

Supplement standard spec 643.3.1 with the following:

2310-13-70: STH 60 - CTH P to Eagle Drive; 2310-13-71: Eagle Drive - Intersection with STH 60 Roundabout is not a designated OSOW route. However, if required all fixed message and width restricted signs must be in place prior to the beginning of the width restricted stage to inform multi trip permit holders to utilize alternate routes. See Wisconsin Lane Closure System Advance Notification article to address lane restrictions in LCS.

Provide the Washington County Sheriff's Department, the Wisconsin State Patrol, Village of Jackson Police Department, and the engineer a current telephone number with which the contractor or his representative can be contacted during non-working hours in the event a safety hazard develops.

Yield to all through traffic at all locations. Equip all vehicles or equipment operating in the live traffic lanes with a hazard identification beam (flashing yellow signal light) that is visible from 360 degrees. Operate the flashing yellow beam only when merging or exiting live traffic lanes or when parked or operating on shoulders, except when parked behind barrier wall.

Do not park personal vehicles within the right-of-way limits of STH 60.

Do not cross live traffic lanes of 2310-13-70: STH 60 - CTH P to Eagle Drive; 2310-13-71: Eagle Drive - Intersection with STH 60 Roundabout with equipment or vehicles.

Obtain prior approval from the engineer for the locations of egress or ingress for construction vehicles to prosecute the work.

Provide minimum 24-hour advance notification to the engineer for any LCS cancellations (not related to weather).

Do not disturb, remove, or obliterate any traffic control signs, advisory signs, sand barrel array, shoulder delineators or beam guard in place along the traveled roadways without the approval of the engineer.

SER-643-001 (20230214)

2310-13-70, 2310-13-71 7 of 59

Wisconsin Lane Closure System Advance Notification

Provide the following advance notification to the engineer for incorporation into the Wisconsin Lane Closure System (LCS).

TABLE 108-1 CLOSURE TYPE AND REQUIRED MINIMUM ADVANCE NOTIFICATION

Closure type with height, weight, or width restrictions (available width, all lanes in one direction < 16 feet)	MINIMUM NOTIFICATION
Lane and shoulder closures	7 calendar days
Full roadway closures	7 calendar days
Ramp closures	7 calendar days
Detours	7 calendar days
Closure type without height, weight, or width restrictions (available width, all lanes in one direction ≥ 16 feet)	MINIMUM NOTIFICATION
Shoulder closures	3 calendar days
Lane closures	3 business days
Pamp alaquraa	3 business days
Ramp closures	

Discuss LCS completion dates and provide changes in the schedule to the engineer at weekly project meetings in order to manage closures nearing their completion date.

Temporary Regulatory Speed Limit Reduction

During engineer-approved regulatory speed limit reductions, install temporary speed limit signs on the inside and outside shoulders of divided roadways to enhance visibility. On two-lane, two-way roadways, install temporary speed limit signs on shoulders. When construction activities impede the location of a post-mounted regulatory speed limit sign, relocate the sign for maximum visibility to motorists. If work lasts less than seven days, mount the regulatory speed limit sign on a portable sign support.

Post temporary regulatory speed limit signs in work zone only during continuous worker activity. During periods of no work activity or when the traffic controls are removed from the roadway, cover, or remove the temporary speed limit signs.

A General

Perform this work according to standard spec 643, the Manual on Uniform Traffic Control Devices (MUTCD), and as shown on the plans or as approved by the engineer.

Accomplish the construction sequence, including the associated traffic control as detailed in the Construction Staging section of the plans, and as described in the Prosecution and Progress article, and in this Traffic article.

Employ flaggers, signs, barricades, and drums as necessary to safeguard and direct traffic at all locations where construction operations may interfere with or restrict the smooth flow of traffic.

Use drums and barricades to direct vehicular and pedestrian traffic in the work zone and to protect and delineate hazards such as open excavations and abrupt drop-offs.

Coordinate traffic requirements under this project with other adjacent department or local municipality projects. Contractor is responsible for implementing and coordinating with other contractors all traffic control shown in the plans. Modifications to the traffic control plan may be required by the engineer to be safe and consistent with adjacent work by others.

Submit to the engineer for approval a detailed traffic control plan if different than the traffic control plan provided in the plan set. Submit this plan ten days prior to the pre-construction conference.

No operation may proceed until all traffic control devices for such work are in the proper location.

2310-13-70, 2310-13-71 8 of 59

Have available at all times sufficient experienced personnel to promptly install, remove, and reinstall the required traffic control devices to reroute traffic during the construction operations.

During all construction operations, maintain adequate turning provisions for vehicles, including buses and trucks, at the intersections that are to remain open.

All construction vehicles and equipment entering or leaving traffic lanes shall yield to through traffic.

When an area of the roadway is temporarily closed to traffic, sign and delineate the portion of the roadway that is to remain open, according to Part 6 of the Manual on Uniform Traffic Control Devices (MUTCD), and the WisDOT manual titled "Guidelines for Construction, Maintenance, & Utility Operations".

Do not store equipment, vehicles, or materials beyond the project limits without specific approval by the engineer.

Construction Contact Information

Designate an individual responsible for traffic control maintenance including access of local traffic, and 24-hour emergency traffic control repair. Provide the name and telephone number of this individual to the engineer.

Provide Village of Jackson Police Department with a 24-hour emergency contact number for when traffic control maintenance is required.

In no case may any barricade, light, sign or other traffic control device be out of service for more than 2 hours. The cost to maintain and restore the above items is incidental to the bid item Traffic Control and no additional payment will be made.

Vehicle Access

Maintain emergency vehicular access at all times to roadways located within the project limits.

Provide access for mail service, utility meter reading, and garbage pick-up.

Local access to residences and businesses within the project area shall be maintained to the maximum extent possible. No residential or commercial drive approach shall be closed without sufficient notice given to the occupants of the premise to remove their vehicles prior to removal or closing of the drive approach access. Reasonable access to abutting business locations shall be maintained at all times.

On-street parking will not be allowed during construction.

B Definitions

The following definitions shall apply to this contract:

Night-Time Periods

- 10:00 PM to 6:00 AM Monday, Tuesday, Wednesday, Thursday, and Friday
 Weekend Periods
- 10:00 PM Friday to 6:00 AM Monday

C Traffic Control Description

Construction IDs 2310-13-70 and 2310-13-71

Pedestrian Work Zone Traffic Control - STH 60 - CTH P to Eagle Drive

With the number of residences and businesses located within the project limits, maintaining pedestrian access during construction is vital and required at all times. The construction work will require limiting the curb ramp construction at each intersection to one ramp at a time. This allows for pedestrian traffic to be maintained at the other locations within the intersections. Refer to the Traffic Control Curb Ramp Construction Sequence Detail for additional information. The curb ramp numbering sequences are as follows:

Sequence #1 – northwest quadrant curb ramps

Sequence #2 – northeast quadrant curb ramps

Sequence #3 – southeast quadrant curb ramps

2310-13-70, 2310-13-71 9 of 59

Stage 1A: STH 60 - CTH P to Eagle Drive / Eagle Drive Roundabout

- Maintain two-way traffic eastbound and westbound along STH 60 through project limits.
- Northern leg of STH 60 and Eagle Drive intersection (2310-13-71) open with shoulder/lane closures for twin culvert pipe construction.
- CTH NN railroad crossing closed for improvements. CTH NN traffic detoured (see detour description).

Stage 1B: STH 60 - CTH P to Eagle Drive / Eagle Drive Roundabout

- Maintain two-way traffic eastbound and westbound along STH 60 through project limits.
- Northern leg of STH 60 and Eagle Drive intersection (2310-13-71) open with shoulder/lane closures for twin culvert pipe construction.

Stage 2A: STH 60 - CTH P to Eagle Drive / Eagle Drive Roundabout

- Maintain one-way traffic eastbound direction on southern half of roadway.
- Westbound traffic is detoured from STH 60 to CTH G to CTH NN to CTH P to CTH PV to USH 45 to STH 60.
- Remove north side sidewalk at STH 60 WSOR at-grade crossing, north side curb ramps (one quadrant at a time to maintain existing pedestrian traffic).
- Construct north side curb ramp (on quadrant at a time). Maintain pedestrian access at all other locations.
- Mill and pave north side of STH 60.
- At railroad crossing, mill and pave up to STH 60 railroad crossing profile change.
- WSOR (railroad company) constructs temporary railroad signals on north side of STH 60.
- Eagle Drive Intersections (2310-13-71) construct north side of roundabout and retaining wall.
- All south legs of minor intersections are restricted to right turn only onto STH 60. All north legs of minor intersections are restricted to left turn only onto STH 60. This is due to westbound detour route.
- North legs of minor intersections intermittent openings in the work zone to provide access to residential and business areas.

Stage 2B: STH 60 - CTH P to Eagle Drive / Eagle Drive Roundabout

- STH 60 full detour (24-36 hours) for railroad crossing. Eastbound and westbound traffic utilize CTH G, CTH NN, CTH P, CTH PV and USH 45. Local traffic only maintained one-way eastbound direction on northern half of roadway.
- WSOR (railroad company) constructs railroad crossing on STH 60.
- WSOR (railroad company) constructs temporary signal and gate arm for use in Stage 3.
- Construct STH 60 gap (profile change area) at railroad crossing to prepare for next stage.
 Continue to construct north side curb ramps. Construct north side sidewalk and Type 8 ramps at railroad crossing.
- Continue Eagle Drive Intersections (2310-13-71) construct north side of roundabout and retaining wall.

2310-13-70, 2310-13-71 10 of 59

- Temporary Pedestrian accommodations at railroad crossing are maintained via shuttle service during the 24–36-hour closure.
- All south legs of minor intersections are restricted to right turn only onto STH 60. All north legs of minor intersections are restricted to left turn only onto STH 60. This is due to westbound detour route.
- North legs of minor intersections intermittent openings in the work zone to provide access to residential and business areas.

Stage 3: STH 60 - CTH P to Eagle Drive / Eagle Drive Roundabout

- Maintain one-way traffic eastbound direction on northern half of roadway (traffic switch).
- Westbound traffic is detoured from STH 60 to CTH G to CTH NN to CTH P to CTH PV to USH 45 to STH 60.
- Construct south side curb ramp (one quadrant at a time). Construct south side sidewalk and Type 8 ramps at railroad crossing. Maintain pedestrian access at all other locations.
- Mill and pave south side of STH 60.
- Eagle Drive Intersections (2310-13-71) construct south side of roundabout.
- At railroad crossing, construct south side curb ramps (one quadrant at a time).
- WSOR (railroad company) removes temporary signal and gate arms.
- All south legs of minor intersections are restricted to right turn only onto STH 60. All north legs of minor intersections are restricted to left turn only onto STH 60. This is due to westbound detour route.
- South legs of minor intersections intermittent openings in the work zone to provide access to residential and business areas.

Stage 4: STH 60 - CTH P to Eagle Drive / Eagle Drive Roundabout

- STH 60 open to two-way traffic.
- Eagle Drive Roundabout (2310-13-71) open to traffic.
- Lane/shoulder closures as needed to install traffic signal monotubes and restoration/finishing items.
- Complete all remaining works items.

5. Holiday and Special Event Work Restrictions.

Do not perform work on, nor haul materials of any kind along or across any portion of the highway carrying STH 60 traffic, and entirely clear the traveled way and shoulders of such portions of the highway of equipment, barricades, signs, lights, and any other material that might impede the free flow of traffic during the following holiday and special event periods:

- From noon Friday, May 24, 2024 to 6:00 AM Tuesday, May 28, 2024 for Memorial Day;
- From noon Wednesday, July 3, 2024 to 6:00 AM Monday, July 8, 2024 for Independence Day;
- From noon Friday, August 30, 2024 to 6:00 AM Tuesday, September 3, 2024 for Labor Day.

stp-107-005 (20210113)

2310-13-70, 2310-13-71 11 of 59

6. Utilities.

A General

Construction ID 2310-13-70 does come under the provision of Administrative Rule Trans 220. Construction ID 2310-13-71 does not come under the provision of Administrative Rule Trans 220.

Additional detailed information regarding the location of utility facilities is available at the Southeast Region WisDOT office during normal working hours.

Some of the utility work described below is dependent on prior work being performed by the contractor at a specific site. In such situations, provide the engineer and the affected utility a good faith notice of when the utility is to start work at the site. Provide this notice 14 to 16 calendar days in advance of when the prior work will be completed, and the site will be available to the utility owner. Follow-up with a confirmation notice to the engineer and the utility owner not less than three working days before the site will be ready for the utility owner to begin its work.

Coordinate construction activities with a call to Digger's Hotline or a direct call to the utilities that have facilities in the area as required by statutes. Use caution to ensure the integrity of underground facilities and always maintain code clearances from overhead facilities.

Note: Bidders are advised to contact each utility company listed in the plans prior to preparing their bid to obtain current information on the status of each utility company's work required in association with the project. Conduct an on-site visit prior to bidding to determine any special measures required for proper clearance between the signal poles, other utilities and any other physical structures and the construction equipment. During construction operations, keep all manholes accessible to utility companies for emergencies.

B Utilities

Construction ID 2310-13-70

A. ANR Pipeline Co

ANR Pipeline Co has underground facilities within the construction limits. The existing facilities are located as follows:

 Underground 14-inch and 20-inch high pressure gas pipelines crossing STH 60 at approximately Station 168+05 about 1600 W. of Eagle Dr.

There are no anticipated conflicts with this construction project and no adjustments required.

B. ATC Management, Inc.

ATC Management, Inc. has overhead facilities within the construction limits. The existing facilities are located as follows:

• 138 kV and 345 kV transmission lines crossing STH 60 east of Eagle Rd. near the project end limits.

There are no anticipated conflicts with this construction project and no adjustments required.

C. AT&T Wisconsin

AT&T Wisconsin has overhead and underground facilities within the project limits. Existing facilities are located as follows:

- Underground along the north side of STH 60 from CTH P to east of Jackson Street.
- Underground along the south side of STH 60 from east of Jackson Street to Eagle Dr.
- Underground along the east side of Glen Brooke Dr. (north-south)
- Underground along the west side of Center St. (north-south)
- Underground along the west side of Jackson Street running north from STH 60
- Underground along the east side of Jackson Street running south from STH 60
- Overhead along the north side of STH 60 east of Eagle Dr.

2310-13-70, 2310-13-71 12 of 59

Proposed facility adjustments to resolve conflicts are as follows, and will be completed during construction:

- Pedestal located at approximately Station 133+10, 25' RT requires adjustment (within new sidewalk). Will be adjusted 1-foot to the south.
- Manhole located at approximately Station 162+15, 18' LT requires adjustment (within pavement).
 Will be adjusted to grade before final paving.

Note: Provide the utility advance notification that the site is ready for adjustment.

D. Midwest Fiber Networks, LLC

Midwest Fiber Networks, LLC has underground facilities within the construction limits. The existing facilities are located as follows:

- Underground crossing of STH 60 at CTH P running north south.
- Underground along the south side of STH 60 from CTH P to Glen Brooke Rd.
- Underground crossing of STH 60 at Glen Brooke Rd running north south.
- Underground along the south side of STH 60 from Jackson Dr. to Eagle Dr.

Proposed facility adjustments to resolve conflicts are as follows, and will be completed prior to construction and estimated to take 60 working days after permits are received:

Relocating fiber line that crosses STH 60 and runs along the east side of Jackson Dr at approx RT 31'. The new runline will be from approx Station 152+78, 21.4' RT to Station 152+75.5, 14.6' RT, then west to Station 152+63, 14.6' RT, Station 152+54.3, 12.9' RT, Station 152+21.8, 14' RT. From here will turn north and continue to Station 20+03.7, 5.2' LT, Station 20+51.4, 5.5' LT, Station 20+89.6, 10.6' LT, Station 23+40, 11.8' LT, and into existing hand hole at Station 23+44.4, 32.8' LT. The new run line will consist of (2) 1.25" HDPE and we will discontinue the existing 2" duct in place.

Note: Provide the utility advance notification prior to construction starting.

E. Spectrum

Spectrum has overhead and underground facilities within the project limits. Existing facilities are located as follows:

- An overhead crossing of STH 60, east of CTH P, approximately Station 100+00 & 103+00
- Overhead along the north side of STH 60 from CTH P to Glen Brooke Dr.
- Overhead along the north side of STH 60 from CNRR to Jackson Dr.
- Overhead along the north side of STH 60 from west of Ridgeway Rd. to east of Eagle Dr.
- Overhead along the north side of STH 60 crossing Eagle Dr.
- Underground along the north side of STH 60 from east of Glen Brooke Rd to CNRR.
- Underground along the north and south sides of STH 60 from Ridgeway Rd to Eagle Dr.
- Underground crossing STH 60 east of CTH P approximate Station 97+75.
- Underground crossing STH 60 east of Glen Brooke Rd. approximate Station 123+00.

Overhead lines are mounted on WE Energies poles. There are no anticipated conflicts with this construction project and no adjustments required.

2310-13-70, 2310-13-71 13 of 59

Proposed facility adjustments to resolve underground conflicts are as follows, and will be completed during construction:

Existing fiber optic and coax facilities located near proposed signal bases SB4 and SB2 at
the intersection of Industrial Drive. Notify Spectrum before installation. Spectrum will be
present during installation of both bases and will work with contractor to make any necessary
adjustments during construction. Work anticipated to take approximately one day at each
location.

Note: Provide the utility advance notification that the site is ready for adjustment.

F. Sprint Communications Co LP

Sprint Communications Co LP has underground facilities within the construction limits. The existing facilities are located as follows:

Underground crossing of STH 60 along the east side of the WSOR railroad corridor.

There are no anticipated conflicts with this construction project and no adjustments required.

Note: Provide the utility advance notification prior to construction starting.

G. Village of Jackson DPW - Sewer

Village of Jackson DPW – Sewer has underground facilities within the construction limits. Existing facilities are located as follows:

- Along the north side of STH 60 from CTH P to east of Green Valley Dr.
- Crossing STH 60 east of CTH P.
- Crossing STH 60 east of Green Valley Dr.
- Crossing STH 60 running north to south along Glen Brooke Rd.
- Along the south side of STH 60 from east Green Valley Dr. to S. Center Street.
- Along the center of STH 60 from east of S. Center St. to Eagle Dr.
- Crossing STH 60 at N. Center St.
- Crossing STH 60 at S. Center St.
- Crossing STH 60 running north to south along Jackson Dr.
- Crossing STH 60 at Ridgeway Dr.

Proposed facility adjustments/relocations to resolve conflicts are as follows and will be completed during construction, unless otherwise noted:

Manhole adjustments at approximately the following Stations: 96+50, LT; 122+90, RT; 134+80 RT; 138+75, RT; 139+55, RT; 142+15, RT; 142+70, RT; 146+60, RT; 149+60, RT; 152+30, CL; 155+30, CL; 159+90, CL; 165+20, CL; 19+20 and 19+60 Glen Brooke Dr.; 19+80, LT, S. Center St.; 19+60, LT, Jackson Dr.; 19+45, LT, Eagle Dr.

Adjustments will be completed by Village DPW crews during construction. Work anticipated to take approximately one day at each location noted above.

Note: Provide the utility advance notification that the site is ready for adjustment.

2310-13-70, 2310-13-71 14 of 59

H. Village of Jackson DPW - Water

Village of Jackson DPW – Water has underground facilities within the construction limits. Existing facilities are located as follows:

- Along the north side of STH 60 from CTH P to Green Valley Dr.
- Crossing STH 60 at Green Valley Dr.
- Along the south side of STH 60 from Green Valley Dr. west of Glen Brooke Dr.
- Crossing STH 60 west of Glen Brooke Dr.
- Along the north side of STH 60 from west of Glen Brooke Dr. to Glen Brooke Dr.
- Along the south side of STH 60 from Glenn Brooke Dr. to Eagle Dr.

Proposed facility adjustments/relocations to resolve conflicts are as follows and will be completed during construction, unless otherwise noted:

Water valves will require adjustment at approximately:

- intersection of STH 60 & CTH P
- intersection of STH 60 & Glen Brooke Dr.
- intersection of STH 60 & Western Ave.
- intersection of STH 60 & Jackson Dr.
- at approximately Station 159+00
- Water Hydrant at Station 152+65, RT

Adjustments will be completed by Village DPW crews during construction. Work anticipated to take approximately one day at each location noted above.

Note: Provide the utility advance notification that the site is ready for adjustment.

I. WE Energies - Electric

WE Energies - Electric has overhead facilities within the project limits. Existing facilities are located as follows:

- Overhead along the north side of STH 60 from CTH P to Glen Brooke Dr.
- Underground along the north side of STH 60 from Glen Brooke Dr. to Center St.
- Overhead crossing of STH 60 along the west side of Jackson Dr.
- Underground crossing of STH 60 east of Jackson Dr.
- Overhead along the north side of STH 60 from west side of Ridgeway Dr to Eagle Dr.

There are no anticipated conflicts with this construction project and no adjustments required.

Note: Provide the utility advance notification that the site is ready for adjustment.

J. WE Energies – Gas/Petroleum

WE Energies - Gas has underground facilities within the project limits. Existing facilities are located as follows:

- Crossing of STH 60 just west of CTH P
- Crossing of STH 60 just east of CTH P
- Along the north side of STH 60 from east of CTH P to Eagle Dr.
- Along the south side of STH 60 from west of WSOR to east of Jackson Dr.
- Crossing of STH 60 at approximately Station 168+00 and Station 168+30.

2310-13-70, 2310-13-71 15 of 59

There are no anticipated conflicts with this construction project and no adjustments required.

Note: Provide the utility advance notification that the site is ready for adjustment.

K. Windstream NTI, LLC

Windstream NTI, LLC has underground facilities within the construction limits. The existing facilities are located as follows:

• Underground crossing of STH 60 along the west side of the WSOR railroad corridor

There are no anticipated conflicts with this construction project and no adjustments required.

Note: Provide the utility advance notification prior to construction starting.

Construction ID 2310-13-71

A. AT&T Wisconsin

AT&T Wisconsin has overhead and underground facilities within the project limits. Existing facilities are located as follows:

- Underground Fiber Optic along the south side of STH 60 from approximately Station 299+61 REB RT to Station 305+00 REB, RT.
- Underground Fiber Optic along the west side of Eagle Dr from approximately Station 400+00 RNB LT to Station 401+25 RNB, LT.
- Underground Fiber Optic along the east side of Eagle Dr from approximately Station 400+25 RNB RT to Station 403+00 RNB, RT.
- Underground telephone along the south side of STH 60 from approximately Station 299+61 REB RT to Station 307+00 REB, RT.
- Underground telephone along the north side of STH 60 from approximately Station 299+61 RWB LT to Station 303+50 RWB, LT.
- Underground telephone along the west side of Eagle Dr from approximately Station 402+50 RSB LT to Station 405+00 RSB, LT.
- Overhead along the east side of Eagle Dr from approximately Station 400+00 RNB RT to Station 401+25 RNB RT.

Proposed facility relocations (prior to construction) and adjustments (during construction) to resolve conflicts are as follows:

- Station 400+97RSB, 19' LT remove handhole and place new handhole 4' south and 2' west into green space. Work to be completed prior to construction and anticipated to take 1 working day.
- Station 401+18RNB, 29' RT remove existing pole and relocate 13' south and 3.5' east. Work to be completed prior to construction and anticipated to take 2 working days.
- Station 401+20RNB, 30' RT remove existing ped. Work to be completed prior to construction and anticipated to take 1 working day.
- Station 401+35RNB, 25' RT discontinue existing 900 pair copper cable from manhole to existing pole at Station 401+18RNB, 29' RT. Work to be completed prior to construction and anticipated to take 1 working day.
- Place new 400 pair copper cable from existing manhole to new pedestal location at new pole.
 Work to be completed prior to construction and anticipated to take 5 working days.
- Station 402+80RNB, 26' RT remove existing handhole and place new handhole approximately 2' west to rest in proposed green space between back of curb and sidewalk. Work to be completed during construction and anticipated to take 1 working day.
- Adjustments to handholes and manhole frame and covers once final grades are determined.
 Work to be completed during construction and anticipated to take approximately one day per location.

2310-13-70, 2310-13-71 16 of 59

Note: Provide the utility advance notification that the site is ready for adjustment.

B. Midwest Fiber Networks, LLC

Midwest Fiber Networks, LLC has underground facilities within the construction limits. The existing facilities are located as follows:

 Underground crossing of STH 60 at Eagle Dr. running north-south and Eagle Drive running eastwest that meet in a handhole in the SE corner at approximately Station 304+75RWB, 75' +/- RT.

Proposed facility adjustments to resolve conflicts are as follows and will be completed prior to construction and during construction:

- Relocating fiber line that is within the SE corner. The fiber line that extends from the handhole to
 the south will shift east approx. 10 ft for about 40 ft. beginning at Station 400+88RNB, RT 32' and
 ending at approx. Station 401+28RNB, RT 38'. Work to be completed prior to construction.
 Estimated to take 20 working days after permits are received.
- Handhole to remain in the proposed sidewalk and adjust during construction. Work anticipated to take approximately one day.

Note: Provide the utility advance notification prior to construction starting.

C. Spectrum

Spectrum has underground facilities within the project limits. Existing facilities are located as follows:

- Underground facilities along the east side of Eagle Drive from approximately Station 401+28 RNB RT to Station 404+75 RNB RT.
- Underground facilities along the northeast quadrant of STH 60 and Eagle Drive intersection from approximately Station 302+18 RWB LT to Station 403+06 RSB RT buried along the WE Energies pole line.
- Overhead along the north side of STH 60 crossing Eagle Dr. attached to WE Energies poles.

Proposed facility relocation and adjustments to resolve conflicts are as follows, and will be completed prior to and during construction:

- Relocate underground facilities along the east side of Eagle Drive from approximately Station 400+75 RNB RT to Station 403+50 RNB RT. Work to be completed prior to construction and anticipated to take 5 working days.
- Relocate underground facilities along the northeast quadrant of STH 60 and Eagle Drive intersection from Station 302+18 RWB LT to Station 403+06 RSB RT to parallel the R/W line.
 Work to be completed prior to construction and anticipated to take 10 working days.
- Relocate overhead lines along the north side of STH 60 crossing Eagle Dr. attached to WE
 Energies poles once they have installed new poles. Work to be completed prior to construction
 and anticipated to take 5 working days.
- Adjustments to handholes and manhole frame and covers may be necessary once final grades are determined. Work to be completed during construction and anticipated to take 1 day at each location.
- Existing facilities left in place are to be discontinued.

Note: Provide the utility advance notification that the site is ready for adjustment.

D. Village of Jackson DPW - Sewer

Village of Jackson DPW – Sewer has underground facilities within the construction limits. Existing facilities are located as follows:

Crossing STH 60 at Eagle Dr.

2310-13-70, 2310-13-71 17 of 59

Proposed facility adjustments/relocations to resolve conflicts are as follows and will be completed during construction, unless otherwise noted:

Manhole adjustments at approximately: 401+24 RNB, 11' LT; 401+31 RSB, 2' LT; 10+92 RAB, 1' RT; 405+21 RNB, 2'LT.

Adjustments will be completed by Village DPW crews during construction. Work anticipated to take approximately one day at each location noted above.

Note: Provide the utility advance notification that the site is ready for adjustment.

E. Village of Jackson DPW - Water

Village of Jackson DPW – Water has underground facilities within the construction limits. Existing facilities are located as follows:

Crossing STH 60 at Eagle Dr.

Proposed facility adjustments/relocations to resolve conflicts are as follows and will be completed during construction, unless otherwise noted:

- Water valves will require adjustment at approximately: Station 31+52 SW, 6' RT; Station 31+60 SW, 11.5 LT, Station 31+68 SW, 23' LT; Station 20+78, 1.5' LT; Station 404+70 RSB, 8.5' LT; Station 404+80, 12' LT.
- Fire hydrant installed at Station 399+90RNB, 29' LT. Work is complete.
- Fire hydrant at Station 31+63.6 SW, 18' RT to be removed during construction and anticipated to take one day.
- Fire hydrant at Station 20+78 NW, 8' LT to be relocated Station 404+06RNB, 22' LT. Work is complete.
- Water line connecting water valve and hydrant at Station 20+78 NW, 8' LT. Work is complete.

Adjustments will be completed by Village DPW crews during construction. Work anticipated to take approximately one day at each location noted above.

Note: Provide the utility advance notification that the site is ready for adjustment.

F. WE Energies – Electric

WE Energies - Electric has overhead and underground facilities within the project limits. Existing facilities are located as follows:

- Overhead facilities along the north side of STH 60 from approximately Station 299+61REB, RT to Station 308+73REB, LT.
- Overhead facilities along the east side of Eagle Dr. from approximately Station 399+00RNB to Station 401+19RNB, RT.
- Underground service lines to adjacent properties.

Proposed facility relocation and adjustments to resolve conflicts are as follows and will be completed prior to construction. Work is anticipated to take approximately 95 working days:

- Station 181+44.77, 75.60' RT Install anchor guy for pole 91-02255.
- Station 183+33.95, 59.20' LT Remove pole 01-07027.
- Station 183+33.05, 59.70' LT Remove pedestal 04U1970.
- Station 183+24.28, 78.01' LT New pole.
- Station 183+26.76, 76.64' LT New pedestal.
- Station 183+24.28, 97.43' LT Anchor for new pole.
- Station 183+24.28, 78.01' LT to Station 183+26.76, 76.64' LT New Cable from new pole to new pedestal.

2310-13-70, 2310-13-71 18 of 59

- Station 183+26.76, 76.64' LT to Station 183+26.73, 105.80' LT New Cable from new pedestal to bore pit.
- Station 183+26.73, 105.80' LT to 403RSB+14.83, 40.32' LT New Cable from bore pit to bore pit. Parallel to ROW line, 1' inside ROW.
- Station 403RSB+14.83, 40.32' LT to Station 403RSB+35.13, 38.78' LT New Cable from bore pit to bore pit. Parallel to ROW line, 1' inside ROW.
- Station 403RSB+35.13, 38.78' LT to Station 403RSB+35.58, 42.70' LT New Cable from bore pit to meter ped at Sign.
- Station 403RSB+35.58, 42.70' LT to Station 403RSB+80.74, 34.94' LT New Cable from bore pit to bore pit. Parallel to ROW line, 1' inside ROW
- Station 403RSB+80.74, 34.94' LT to Station 403RSB+86.28, 20.44' LT New Cable from bore pit to splice pit. Splice to existing cable at Station 403RSB+86.28, 20.44' LT
- Station 403RSB+86.28, 20.44' LT Splice Pit for connection to existing 6DX cable
- Station 403RSB+86.28, 20.44' LT to Station 183+93.88, 72.62' LT discontinue cable, leave in place.
- Station 183+93.88, 72.62' LT 04-L-01006 Light pole to be removed.
- Station 184+54.88, 75.41' LT 01-L-02505 Light pole to be removed.
- Station 403RNB+48.89, 19.67' RT 01-L-02504 Light pole to be removed.
- Station 403RNB+48.87, 25.02' RT New Light Pole
- Station 403RNB+77.91, 21.04' RT Splice Pit for connection to existing 6DX cable
- Station 403RNB+77.91, 21.04' RT to Station 403RNB+48.87, 25.02' RT New Cable from Splice Pit to New Light Pole
- Station 403RNB+77.91, 21.04' RT to Station 184+54.88, 75.41' LT discontinue cable, leave in place.
- Station 184+94.60, 59.17' LT 01-07208 Pole to be removed.
- Station 185+7.26, 67.85' LT New Pole
- Station 186+72.51, 52.64' LT New Anchor for existing pole 21-5742 at Station 186+72.53, 58.67'
 LT
- Station 401RNB+32.18, 28.82' RT 92-06020 Pole to be removed.
- Station 399RNB+10.67, 18.88' RT 80-04268 Pole to be replaced / Light Transferred
- Station 399RNB+36.38, 19.23' RT Anchor for Pole # 80-04268 to be replaced.
- Station 399RNB+12.53, 18.88' RT New Pole
- Station 399RNB+37.46, 19.23' RT Anchor for new pole at Station 399RNB+ 12.53, 18.88' RT
- Station 399RNB+12.53, 18.88' RT to Station 399RNB+10.44, 32.12' RT New Cable from new pole to bore pit.
- Station 399RNB+10.44, 32.12' RT to Station 399RNB+36.69, 32.00' New Cable from bore pit to bore pit. Parallel to ROW line, 1' inside ROW
- Station 399RNB+36.69, 32.00' RT to Station 399RNB+36.62, 36.00' New Cable from bore pit to bore pit.
- Station 399RNB+36.62, 36.00' RT to Station 401RNB+24.44, 39.77' New Cable from bore pit to meter pedestal. Installed in conduit, Private Property.

Note: Provide the utility advance notification that the site is ready for adjustment.

2310-13-70, 2310-13-71 19 of 59

G. WE Energies - Gas

WE Energies - Gas has underground facilities within the project limits. Existing facilities are located as follows:

• Along the north side of STH 60 running west to east and crossing the Eagle Dr. intersection.

Proposed facility adjustments to resolve conflicts are as follows, and will be completed prior to construction and anticipated to take approximately 30 working days:

- Relocate gas main along STH 60 from Station 301+32 RWB, 29' LT to Station 306+92RWB, 22' LT.
- Relocate gas main along Eagle Dr. from Station 400+89RNB, 14' LT to Station 20+66NW, 16' RT.

Note: Provide the utility advance notification that the site is ready for adjustment.

7. Work by Others – Village of Jackson.

The Village of Jackson Public Works Department work force will adjust all sanitary sewer manhole covers, water valve box covers, and water service box covers. The contractor shall notify the Village of Jackson Department of Public Works a minimum of five business days in advance.

It is expected that routine maintenance by Village of Jackson personnel may be required at certain times that is concurrent with the work being done under this contract.

8. Work by Others – Washington County Highway Department.

Modifications to the traffic control plan may be required by the engineer to be safe and consistent with adjacent work by others.

It is expected that routine maintenance by Washington County Highway personnel may be required at certain times that is concurrent with the work being done under this contract.

The Washington County Highway Department has two projects anticipated to be under construction within the time of this contract. Both projects are on CTH P from STH 165 to STH 60, and coordination of the traffic control/staging will be required. CTH P projects will be constructed under a full closure from STH 145 to STH 60. The detour for CTH P will utilize STH 145, USH 45, and STH 60. Below is the project information for the two projects.

2711-06-70 HWY 24-01
Polk – Jackson Polk - Jackson

STH 145 to Sherman Road Sherman Road to STH 60

CTH P CTH P

Washington County Washington County

The traffic signal loop detector installation south of STH 60 requires coordination with the CTH P projects contractor/construction activities.

Notify the engineer two weeks in advance of completion of each stage so the engineer can coordinate with projects.

9. Railroad Insurance and Coordination – Wisconsin and Southern Railroad Company.

A Description

Comply with standard spec 107.17 for all work affecting Wisconsin and Southern Railroad Company property and any existing tracks.

2310-13-70, 2310-13-71 20 of 59

A.1 Railroad Insurance Requirements

In addition to standard spec 107.26, provide railroad protective liability insurance coverage as specified in standard spec 107.17.3. Insurance is filed in the name of Wisconsin and Southern Railroad Company.

Notify evidence of the required coverage, and duration to Justin Mahr, Senior Manger Real Estate - Contracts; 315 W. 3rd Street, Pittsburg, KS 66762; Telephone (402) 651-8238; E-mail: iustin.mahr@watco.com.

Also send a copy to the following: Jason Kazmierski, SE Region Railroad Coordinator, 141 NW Barstow Street, Waukesha, WI 53188; Telephone (262) 548-6700; E-mail jason.kazmierski@dot.wi.gov.

Include the following information on the insurance document:

- Project ID: 2310-13-70, 2310-13-71
- Work Performed on or within 50' of RR right-of-way:
 - 1 Removal and replacement of curb and gutter and sidewalks, milling and overlaying of existing asphaltic pavement.
 - 2 Milling and overlaying of existing asphaltic pavement.

#	Route Name	City/County	Crossing ID	RR Subdivision	RR Milepost
1	STH 60 / Main Street	Jackson/Washington	178932R	West Bend Sub	110.34
2	CTH NN	West Bend/Washington	178940H	West Bend Sub	113.44

A.2 Train Operation

#	Passenger Train Volume	Passenger Train Speed	Freight Train Volume	Freight Train Speed	Frequency	Switch Train Comment*
1	N/A	N/A	4	10	Weekly	No switch trains
2	N/A	N/A	4	10	Weekly	No switch trains

^{*} Switch trains are in addition to freight and passenger trains.

A.3 Names and Addresses of Railroad Representatives for Consultation and Coordination

Justin Mahr, Senior Manger Real Estate - Contracts; 315 W. 3rd Street, Pittsburg, KS 66762; Telephone (402) 651-8238; E-mail: justin.mahr@watco.com.

A.4 Work by Railroad

The railroad will perform the work described in this section, except for work described in other special provisions, and will be accomplished without cost to the contractor. Replace railroad surface and signals at DOT # 178932R. Replace railroad surface at DOT # 178940H.

A.5 Temporary Grade Crossing

If a temporary grade crossing is desired, submit a written request to the railroad representative named in A.3 at least 40 days prior to the time needed. Approval is subject to the discretion of the railroad. The department has made no arrangements for a temporary grade crossing. Wisconsin and Southern Railroad Company

stp-107-026 (20230629)

10. Information to Bidders, U.S. Army Corps of Engineers Section 404 Permit.

The department has received written verification of coverage under the Section 404 Transportation Regional General Permit from the U.S. Army Corps of Engineers. Comply with the requirements of the permit in addition to requirements of the special provisions.

A copy of the permit is available from the regional office by contacting Tim McElmeel, Environmental Coordinator at WisDOT DTSD SE Region, (262) 548-6458; timothy.mcelmeel@dot.wi.gov.

2310-13-70, 2310-13-71 21 of 59

If the contractor requires work outside the proposed slope intercepts, based on their method of operation to construct the project, it is the contractor's responsibility to determine whether a U.S. Army Corps of Engineers Section 404 permit modification is required. If a Section 404 permit modification is necessary, obtain the permit modification prior to beginning construction operations requiring the permit. No time extensions as discussed in standard spec 108.10 will be granted for the time required to apply for and obtain the permit modification. The contractor must be aware that the U.S. Army Corps of Engineers may not grant the permit modification request.

stp-107-054 (20230629)

11. Construction Over or Adjacent to Navigable Waters.

The Cedar Creek is classified as a state navigable waterway under standard spec 107.19. stp-107-060 (20171130)

12. Environmental Protection, Aquatic Exotic Species Control.

Exotic invasive organisms such as VHS, zebra mussels, purple loosestrife, and Eurasian water milfoil are becoming more prolific in Wisconsin and pose adverse effects to waters of the state. Wisconsin State Statutes 30.07, "Transportation of Aquatic Plants and Animals; Placement of Objects in Navigable Waters", details the state law that requires the removal of aquatic plants and zebra mussels each time equipment is put into state waters.

At construction sites that involve navigable water or wetlands, use the follow cleaning procedures to minimize the chance of exotic invasive species infestation. Use these procedures for all equipment that comes in contact with waters of the state and/or infested water or potentially infested water in other states.

Ensure that all equipment that has been in contact with waters of the state, or with infested or potentially infested waters, has been decontaminated for aquatic plant materials and zebra mussels before being used in other waters of the state. Before using equipment on this project, thoroughly disinfect all equipment that has come into contact with potentially infested waters. Guidelines from the Wisconsin Department of Natural Resources for disinfection are available at:

http://dnr.wi.gov/topic/invasives/disinfection.html

Use the following inspection and removal procedures:

- 1. Before leaving the contaminated site, wash machinery and ensure that the machinery is free of all soil and other substances that could possibly contain exotic invasive species;
- 2. Drain all water from boats, trailers, bilges, live wells, coolers, bait buckets, engine compartments, and any other area where water may be trapped;
- 3. Inspect boat hulls, propellers, trailers and other surfaces. Scrape off any attached mussels, remove any aquatic plant materials (fragments, stems, leaves, seeds, or roots), and dispose of removed mussels and plant materials in a garbage can before leaving the area or invested waters; and
- 4. Disinfect your boat, equipment and gear by either:
 - 4.1. Washing with ~212 F water (steam clean), or
 - 4.2. Drying thoroughly for five days after cleaning with soap and water and/or high pressure water, or
 - 4.3. Disinfecting with either 200 ppm (0.5 oz per gallon or 1 Tablespoon per gallon) Chlorine for 10-minute contact time or 1:100 solution (38 grams per gallon) of Virkon Aquatic for 20- to 30-minute contact time. Note: Virkon is not registered to kill zebra mussel veligers nor invertebrates like spiny water flea. Therefore, this disinfect should be used in conjunction with a hot water (>104° F) application.

Complete the inspection and removal procedure before equipment is brought to the project site and before the equipment leaves the project site.

stp-107-055 (20130615)

2310-13-70, 2310-13-71 22 of 59

13. Archaeological Site.

47WT87 (Flute) site is located approximately Station 172+00 to Station 178+00, 60' LT within the limits shown on the plans.

Notify the Bureau of Technical Services – Environmental Process and Document Section (BTS-EPDS) at (608) 266-0099 at least two weeks before commencement of any ground disturbing activities beyond the existing right-of-way limits. BTS-EPDS will determine if a qualified archaeologist will need to be on site during construction of this area.

Do not use the site for borrow or waste disposal. Do not use the site area not currently capped by asphalt/concrete for the staging of personnel, equipment and/or supplies.

47WT348 site is located approximately Station 186+00 to Station 187+00, 100' LT within the limits shown on the plans.

Do not use the site for borrow or waste disposal. Do not use the site area not currently capped by asphalt/concrete for the staging of personnel, equipment and/or supplies.

stp-107-220 (20180628)

14. Historic Boundary.

The Jackson Elementary School is located on STH 60 approximately Station 152+50 to Station 154+25, 25' LT and located on Jackson Drive approximately Station 20+25 to Station 25+25, 25' RT within the limits as shown on the plans.

No entry nor work is allowed beyond the existing right-of-way limits for this site. Do not use the site for borrow or waste disposal.

15. Notice to Contractor – Railroad Coordination – Wisconsin and Southern Railroad Company.

The Wisconsin and Southern Railroad Company operates the track crossings located approximately 300' east of Center Street on STH 60. This rail line provides freight deliveries approximately 20 times per week.

Contractor shall not place work zone traffic control devices within 25 feet of the rail crossings.

Contractor shall coordinate with WSOR for any additional requirements for maintaining the Work Zone Traffic Control area within the track crossing.

16. Notice to Contractor – Traffic Signal Equipment Lead Time.

Order traffic signal equipment as soon as possible to assure the equipment is procured in a timely fashion and, therefore, installed, inspected, and ready for turn-on at the required date.

17. Material Stockpile and Equipment Storage.

Submit a map showing all proposed material stockpile and equipment storage locations to the engineer 14 calendar days before either the preconstruction conference or proposed use, whichever comes first. Identify the purpose; length, width, and height; and duration of material stockpile or equipment storage at each location. Do not stockpile material or store equipment until the engineer approves.

SER-107-011 (20220412)

2310-13-70, 2310-13-71 23 of 59

18. Timely Decision-Making Manual.

Use the Timely Decision-Making Manual (TDM) on this contract. Coordinate with the department to modify the various published tools as necessary to meet the particular project needs and determine how to implement those tools under the contract. Ensure the full participation of the contractor and its principal subcontractors throughout the term of the contract.

Forms and associated guidance are published in the TDM available at the department's Highway Construction Contract Information (HCCI) web site at:

https://wisconsindot.gov/rdwy/admin/tdm.doc

stp-105-005 (20151210)

19. Coordination with Businesses and Residents.

The contractor shall arrange and conduct a meeting between the contractor, the department, affected residents, local officials, and business people to discuss the project schedule of operations including vehicular and pedestrian access during construction operations. Hold the first meeting at least one week before the start of work under this contract and hold a meeting one week prior to each traffic staging change. The contractor shall arrange for a suitable location for meetings that provides reasonable accommodation for public involvement. The department will prepare and coordinate publication of the meeting notices and mailings for meetings. The contractor shall schedule meetings with at least two weeks' prior notice to the engineer to allow for these notifications.

stp-108-060 (20141107)

20. Public Convenience and Safety.

Revise standard spec 107.8(6) as follows:

Check for and comply with local ordinances governing the hours of operation of construction equipment. Do not operate motorized construction equipment from 8:00 PM until the following 6:00 AM, unless prior written approval is obtained from the engineer.

stp-107-001 (20060512)

21. Removing Traffic Signals STH 60 & CTH P, Item 204.9060.S.01; Removing Traffic Signals STH 60 & Industrial Dr, Item 204.9060.S.02; Removing Traffic Signals STH 60 & Jackson Dr, Item 204.9060.03.

A Description

This special provision describes removing the existing traffic signals at the intersections of STH 60 & CTH P, STH 60 & Industrial Dr, and STH 60 & Jackson Dr, conforming to standard spec 204 and as follows. Specific removal items are noted in the plans.

B (Vacant)

C Construction

Arrange for the de-energizing of the traffic signals with the local electrical utility after receiving approval from the engineer that the existing traffic signals can be removed.

Notify the department's Electrical Field Unit at (414) 266-1170 at least five working days prior to the removal of the traffic signals. Complete the removal work as soon as possible following shut down of this equipment.

All existing equipment shall remain in operation until the temporary traffic signal is energized and fully operational. The existing signal equipment shall only be de-energized when the temporary equipment is energized and fully operational. The de-energizing and removal of the existing equipment may only take place after receiving the approval from the engineer. The existing equipment shall be removed the same day as to not obstruct the newly operating equipment. Any remaining existing signal heads shall be bagged while the temporary signal is in operation.

2310-13-70, 2310-13-71 24 of 59

Remove all designated standards and poles per plan from their concrete footings and disassemble out of traffic. Remove the transformer or pedestal bases from each pole. Remove the signal heads, mast arms, luminaires, wiring/cabling, and traffic signal mounting devices from each signal standard, arm, or pole. Ensure that all access hand hole doors and all associated hardware remain intact. Properly dispose of the underground signal cable, internal wires, and street lighting cable. Deliver the remaining materials as directed by the department.

D Measurement

Removing Traffic Signals will be measured as a single unit of work for each intersection, acceptably completed.

E Payment

Removing Traffic Signals will be paid for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
204.9060.S.01	Removing Traffic Signals STH 60 & CTH P	EACH
204.9060.S.02	Removing Traffic Signals STH 60 & Industrial Dr	EACH
204.9060.S.03	Removing Traffic Signals STH 60 & Jackson Dr	EACH

Payment is full compensation for removing specified traffic signal components, disassembly, and delivery of parts to the department.

The department will pay separately for the detachment and disposal of luminaires and lamps under the item Lamp, Ballast, LED, Switch Disposal by Contractor.

22. Removing Loop Detector Wire & Lead In Cable STH 60 & CTH P, Item 204.9060.S.04; Removing Loop Detector Wire & Lead In Cable STH 60 & Industrial Dr, Item 204.9060.S.05;

Removing Loop Detector Wire & Lead In Cable STH 60 & Jackson Dr, Item 204.9060.S.06.

A Description

This special provision describes removing loop detector wire and lead-in cable at the intersections of STH 60 & CTH P, STH 60 & Industrial Dr, and STH 60 & Jackson Dr as the plans show, conforming to standard spec 204, and as follows.

B (Vacant)

C Construction

Remove and dispose of detector lead-in cable including loop wire for abandoned loops off the project site.

D Measurement

Removing Loop Detector Wire & Lead In Cable will be measured as a single unit of work for each intersection, acceptably completed.

E Payment

Removing Loop Detector Wire & Lead In Cable will be paid for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
204.9060.S.04	Removing Loop Detector Wire & Lead In Cable STH 60 & CTH P	EACH
204.9060.S.05	Removing Loop Detector Wire & Lead In Cable STH 60 & Industrial Dr	EACH
204.9060.S.06	Removing Loop Detector Wire & Lead In Cable STH 60 & Jackson Dr	EACH

Payment is full compensation for removing and properly disposing of loop detector wire and lead-in cable.

2310-13-70, 2310-13-71 25 of 59

23. Excavation, Hauling, and Disposal of Petroleum Contaminated Soil, Item 205.0501.S.

A Description

A.1 General

This special provision describes excavating, loading, hauling, and disposing of petroleum contaminated soil at a DNR approved bioremediation facility or landfill. The closest DNR approved bioremediation facility or landfill are:

Waste Management Orchard Ridge Security Landfill W124 N9355 Boundary Road Menomonee Falls, WI 53051 (262) 509-5629

GFL Environmental Glacier Ridge N7296 Co Rd V Horicon, WI 53032 (920) 387-0987

GFL Environmental Emerald Park Landfill W124 S10629 124th Street Muskego, WI 53150 (414) 529-1360

Waste Management Metro Landfill 10712 South 124th Street Franklin, WI 53132 (414) 529-6180

Perform this work conforming to standard spec 205 and Chapters NR 700-754 of the Wisconsin Administrative Code, as supplemented herein. Per NR 718.07, a solid waste collection and transportation service-operating license is required under NR 502.06 for each vehicle used to transport contaminated soil

A.2 Notice to the Contractor - Contaminated Soil Locations

The department completed testing for soil and groundwater contamination for locations within this project where excavation is required. Testing indicated that petroleum-contaminated soil is present at the following locations the plans show:

- 1. STH 60 Station 95+35 to 96+45, from 70 feet left of reference line to project limits right, from 12' below ground surface (bgs) to maximum depth of excavation. Soil contains lead; however, contaminated soils are not anticipated to be encountered during construction operations based on excavation limits anticipated at this location.
- 2. STH 60 Station 121+15 to 122+35, from reference line to project limits left, from 1' bgs to maximum depth of excavation. Soil contains petroleum volatile organic compounds (PVOCs) and lead and must be managed. Approximately 169 cubic yards (approximately 288 tons at an estimated 1.7 tons per cubic yard) of soil will be excavated from this location.
- 3. STH 60 Station 122+35 to 122+58, from reference line to project limits right, from 1' to maximum depth of excavation. Soil contains PVOCs; however, contaminated soils are not anticipated to be encountered during construction operations based on excavation limits anticipated at this location.
- 4. STH 60 Station 122+58 to 123+78, from reference line to project limits right, from 1' to 5' bgs. Soil contains PVOCs and lead and must be managed. Approximately 81 cubic yards (approximately 138 tons at an estimated 1.7 tons per cubic yard) of soil will be excavated from this location.

2310-13-70, 2310-13-71 26 of 59

- 5. STH 60 Station 123+78 to 124+70, from reference line to project limits right, from 1' to maximum depth of excavation. Soil contains PVOCs; however, contaminated soils are not anticipated to be encountered during construction operations based on excavation limits anticipated at this location.
- 6. STH 60 Station 151+40 to 152+30, from reference line to 45 feet right, from 3' to 10' bgs. Soil contains PVOCs and must be managed. Approximately 3 cubic yards (approximately 5 tons at an estimated 1.7 tons per cubic yard) of soil will be excavated from this location.
- 7. Jackson Dr. Station 18+45 to 20+00, from reference line to project limits left, from 1' bgs to maximum depth of excavation. Soil contains PVOCs and lead and must be managed. Approximately 0.5 cubic yards (approximately 1 ton at an estimated 1.7 tons per cubic yard) of soil will be excavated from this location.

Directly load soil excavated by the project at the above locations into trucks that will transport the soil to a WDNR-licensed bioremediation facility for treatment and disposal.

If contaminated soils are encountered elsewhere on the project, terminate excavation activities in the area and notify the engineer. If dewatering is required at the above locations, conduct the dewatering according to Section C below.

The excavation management plan for this project has been designed to minimize the offsite treatment or disposal of contaminated material. The excavation management plan, including these special provisions, has been developed in cooperation with the WDNR. The WDNR concurrence letter is on file at the Wisconsin Department of Transportation. For further information regarding previous investigation and remediation activities near this project, contact:

Name: Mr. Andrew Malsom

Address: 141 NW Barstow Street, PO Box 798, Waukesha, WI 53187-0798

Phone: (262) 548-6705 Fax: (262) 548-6891

E-mail: Andrew.Malsom@dot.wi.gov

A.3 Coordination

Coordinate work under this contract with the environment consultant:

Consultant: Ramboll

Address: 234 W. Florida Street, Fifth Floor, Milwaukee, WI 53204

Contact: Mr. Mark Walter, PE Phone: (414) 837-3563 Fax: (414) 837-3608

E-mail: Mark.Walter@ramboll.com

The role of the environmental consultant will be limited to:

- 1. Determining the location and limits of contaminated soil to be excavated based on soil analytical results from previous investigations, visual observations, and field screening of soil that is excavated.
- 2. Identifying contaminated soils to be hauled to the bioremediation facility or landfill.
- 3. Documenting that activities associated with management of contaminated soil are in conformance with the contaminated soil management methods for this project as specified herein; and
- Obtaining the necessary approvals for disposal of contaminated soil from the bioremediation facility or landfill.

Provide at least a 14-calendar day notice of the preconstruction conference date to the environmental consultant. At the preconstruction conference, provide a schedule for all excavation activities in the areas of contamination to the environmental consultant. Also notify the environmental consultant at least three calendar days before beginning excavation activities in each of the contaminated areas.

Coordinate with the environmental consultant to ensure that the environmental consultant is present during excavation activities in the contaminated areas. Perform excavation work in each of the contaminated areas on a continuous basis until excavation work is completed.

2310-13-70, 2310-13-71 27 of 59

Identify the DNR approved bioremediation facility or landfill that will be used for disposal of contaminated soils and provide this information to the environmental consultant no later than 30 calendar days before beginning excavation activities in the contaminated areas or at the preconstruction conference, whichever comes first. The environmental consultant will be responsible for obtaining the necessary approvals for disposal of contaminated soils from the bioremediation facility or landfill. Do not transport contaminated soil offsite without prior approval from the environmental consultant.

A.4 Health and Safety Requirements

Add the following to standard spec 107.1:

During excavation activities, expect to encounter soil contaminated with gasoline, diesel fuel, fuel oil, or other petroleum related products. Site workers taking part in activities that will result in the reasonable probability of exposure to safety and health hazards associated with hazardous materials shall have completed health and safety training that meets the Occupational Safety and Health Administration (OSHA) requirements for Hazardous Waste Operations and Emergency Response (HAZWOPER), as provided in 29 CFR 1910.120.

Prepare a site-specific Health and Safety Plan, and develop, delineate, and enforce the health and safety exclusion zones for each contaminated site location as required by 29 CFR 1910.120. Submit the site-specific health and safety plan and written documentation of up-to-date OSHA training to the engineer before the start of work.

B (Vacant)

C Construction

Add the following to standard spec 205.3:

Control operations in the contaminated areas to minimize the quantity of contaminated soil excavated.

The environmental consultant will periodically evaluate soil excavated from the contaminated areas to determine if the soil will require offsite bioremediation. The environmental consultant will evaluate excavated soil based on field screening results, visual observations, and soil analytical results from previous environmental investigations. Assist the environmental consultant in collecting soil samples for evaluation using excavation equipment. The sampling frequency shall be a maximum of one sample for every 15 cubic yards excavated.

Directly load and haul soils designated by the environmental consultant for offsite bioremediation or landfilling to the DNR approved bioremediation facility or landfill. Use loading and hauling practices that are appropriate to prevent any spills or releases of petroleum-contaminated soils or residues. Before transport, sufficiently dewater soils designated for off-site bioremediation or landfilling so as not to contain free liquids.

D Measurement

The department will measure Excavation, Hauling, and Disposal of Petroleum Contaminated Soil in tons of contaminated soil, accepted by the bioremediation facility or landfill as documented by weight tickets generated by the bioremediation facility or landfill.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER DESCRIPTION UNIT

205.0501.S Excavation, Hauling, and Disposal of Petroleum Contaminated Soil TON

Payment is full compensation for excavating, segregating, loading, hauling, and treatment via bioremediation, or landfilling of contaminated soil; obtaining solid waste collection and transportation service operating licenses; assisting in the collection soil samples for field evaluation; and dewatering of soils before transport, if necessary.

stp-205-003 (20230113)

2310-13-70, 2310-13-71 28 of 59

24. Base Aggregate Dense 1 1/4-Inch for Lower Base Layers.

Replace standard spec 305.2.2.1(2) with the following:

- (2) Unless the plans or special provisions specify otherwise, do the following:
 - 1. Use 1 1/4-inch base throughout the full base depth.
 - 2. Use 3/4-inch base in the top 3 inches of the unpaved portion of shoulders. Use 3/4-inch base or 1 1/4-inch base elsewhere in shoulders.

stp-305-020 (20080902)

25. Adjusting Storm Sewer Structures.

Add the following text to standard spec 611.3.1:

Remove covers and frames prior to milling. Cover openings with a Cover Plates Temporary of sufficient thickness to carry traffic and at a depth to accommodate the milling operations. Backfill excavated areas with an asphalt surface mix to an elevation that will match the adjacent pavement. Cover Plates Temporary will be paid for as separate contract bid item.

Add the following text to 611.3.7 of the standard specs:

The replacement of Grade A concrete when adjusting manhole covers in areas of bituminous resurfacing shall be to the top of the existing concrete base as shown on the detail for adjusting manhole covers. Use construction methods that conform to the requirements set forth in 611.3.3 of the standard specs.

Add the following text to standard spec 611.5:

Removal and replacement of concrete pavement to accomplish the work shall be incidental to the cost of work. Removal and replacement of concrete curb and gutter will be paid for under items Removing Curb and Gutter, Concrete Curb and Gutter, 30-Inch Type D, and Concrete Curb and Gutter, 6-Inch Sloped 36-Inch Type D.

SER-611-001 (20161216)

26. Inlets 4-FT Diameter, Item 611.3004.

Supplement standard spec 611.2 with the following:

Furnish rubber adjustment riser rings from the department's approved product list. Use manufacturer approved mastic adhesive and polyurethane adhesive with a flexible set. Supply manufacturer's recommendations prior to installation.

Replace standard spec 611.3.3(1) with the following:

(1) Set inlet cover on rubber adjustment riser ring. Use mastic adhesive between the ring and the inlet structure. Use polyurethane adhesive with a flexible set between the ring and the inlet cover. Use two 5/16-inch beads of adhesive placed 1 inch and 2 inches in from the outside edge of the ring. If multiple adjustment rings are necessary, a maximum of two adjustment rings can be used. A maximum 3-inch adjustment is allowed. Use manufacturer approved polyurethane adhesive with a flexible set to join the two rings. If the adjustment rings must be cut, the joints must be staggered, and a polyurethane adhesive used to reattach the cut ends. No concrete adjustment rings, or mortar is to be placed between the top of the structure and the inlet cover.

27. Cover Plates Temporary, Item 611.8120.S.

A Description

This special provision describes providing and removing steel plates to cover and support asphaltic pavement and traffic loading at manholes, inlets, and similar structures during milling and paving operations.

2310-13-70, 2310-13-71 29 of 59

B Materials

Provide a 0.25-inch minimum thickness steel plate that extends to the outside edge of the existing masonry.

C (Vacant)

D Measurement

The department will measure Cover Plates Temporary as each individual unit, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER

DESCRIPTION

UNIT

611.8120.S Cover Plates Temporary EACH

Payment is full compensation for furnishing, installing, and removing the cover plates.

The steel plates shall become the property of the contractor when no longer needed in the contract work. stp-611-006 (20151210)

28. Pipe Grates 48-Inch, Item 611.9850.S.01.

A Description

This special provision describes providing pipe grates for pipe apron end walls as detailed in the plans.

B Materials

Furnish steel conforming to the requirements of standard spec 506.2.2.1. Furnish steel pipe conforming to the requirements of standard spec 506.2.3.6.

Furnish pipe grates galvanized according to ASTM A123.

Furnish angles and brackets galvanized according to ASTM A123.

Furnish required hardware galvanized according to ASTM A153.

C Construction

Repair pipes, rods, angles, and brackets on which the galvanized coating has been damaged according to the requirements of AASHTO M36.

D Measurement

The department will measure Pipe Grates 48-Inch in units of work, where one unit is one grate, completed and accepted.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBERDESCRIPTIONUNIT611.9850.S.01Pipe Grates 48-InchEACH

Payment is full compensation for furnishing and installing all materials; and for drilling and connecting grates to apron end walls.

29. Fertilizer Type B.

Replace standard spec 629.2.1.3 with the following:

(1) Fertilizer Type B will conform to the following requirements:

Nitrogen, not less than 24% with 6% percent of the nitrogen being slow release.

Phosphorus, not less than 15%

Potash, not less than 9%

2310-13-70, 2310-13-71 30 of 59

⁽²⁾ The total nitrogen, phosphorus, and potash shall equal at least 48 percent.

Replace standard spec 629.3.1.3 with the following:

(1) Apply fertilizer containing at least 48 percent total nitrogen, phosphorus, and potash at 5 pounds per 1,000 square feet unless otherwise directed by the engineer. For Fertilizer Type B that contains a different percentage of components, determine the new application rate by multiplying the specified rate by a dimensionless conversion factor determined as follows:

Conversion Factor = 48 / New Percentage of Components

Replace standard spec 629.4(1):

(1) The department will measure Fertilizer Type B by the hundred pounds (CWT) acceptably completed, measured based on the application rate of 5 pounds per 1,000 square feet. The department will not measure fertilizer used for the bid items under 632. The measured quantity equals the number of hundred-weight (CWT) of material determined by multiplying the actual number of CWT of material incorporated by the ratio of the actual percentage of fertilizer components used to 48 percent for Fertilizer Type B.

SER-629-001 (20230109)

30. Signs Type I and II.

Furnish and install mounting brackets per approved product list for type II signs on overhead sign supports incidental to sign. For type II signs on sign bridges use aluminum vertical support beams noted above incidental to sign.

Supplement standard spec 637.2.4 with the following:

Use stainless steel bolts, washers, and nuts for type I and type II signs mounted on sign bridges or type I signs mounted on overhead sign supports. Use clips on every joint for Sign Plate A 4-6 when mounted on a sign bridge or overhead sign support. Inspect installation of clips and assure bolts and nuts are tightened to manufacturer's recommended torque values.

Use aluminum vertical sign support beams that have a 5-inch-wide flange and weigh 3.7 pounds per foot, if the L-brackets are 4 inches wide then use 4-inch-wide flange beams weighing 3.06 pounds per foot. Contractor shall measure the width of the L-brackets on existing structures of determine the width needed for sign support beams.

Use beams a minimum of six feet in length or equal to the height of the sign to be supported, whichever is greater. Use U-bolts that are made of stainless steel, one-half inch diameter and of the proper size to fit the truss cords of each sign bridge. Install vertical sign support beams on each sign and use new U-bolts to attach each beam to the top and bottom cord of the sign bridge truss.

For type II signs on overhead sign supports follow the approved product list for mounting brackets.

Replace standard spec 637.3.3.2(2) with the following:

(2) Install Type I Signs at the offset stated in the plan, which shall be the clear distance between the edge of mainline pavement right edge line and the near edge of the sign.

Supplement standard spec 637.3.3.3(3) with the following:

Furnish and install new aluminum vertical sign support beams on each sign and new U-bolts to attach each beam to the top and bottom cord of the sign bridge truss for Type I or Type II Signs and Type I signs on overhead sign supports incidental to sign.

Add the following to standard spec 641.2:

Submit shop drawings for sign bridges and overhead sign supports to SE Region Traffic Operations Engineer, Tom Heydel and Bureau of Structures Design.

SER-637-001 (20170621)

2310-13-70, 2310-13-71 31 of 59

31. General Requirements for Electrical Work.

Replace standard spec 651.3.3(3) with the following:

Request a signal inspection of the completed signal installation to the engineer at least five working days prior to the time of the requested inspection. Notify the department's Electrical Field Unit at (414) 266-1170 to coordinate the inspection. The department's Region Electrical personnel will perform the inspection. In the event of deficiencies, request a re-inspection when the work is corrected. The engineer will not authorize turn-on until the contractor corrects all deficiencies.

32. Electrical Conduit.

Replace standard spec 652.5(2) with the following:

(2) Payment for Conduit Rigid Metallic, Conduit Rigid Nonmetallic, Conduit Reinforced Thermosetting Resin, and Conduit Special bid items is full compensation for providing the conduit, conduit bodies, and fittings; for providing all conduit hangers, clips, attachments, and fittings used to support conduit on structures; for pull wires or ropes; for expansion fittings and caps; for making necessary connections into an existing pull box, manhole, junction box or communication vault; for excavating, bedding, and backfilling, including any sand, concrete, or other required materials; for disposing of surplus materials; and for making inspections.

33. Electrical Wiring.

Append standard spec 655.5 with the following:

(3) Payment for Traffic Signal EVP Detector Cable is full compensation for providing emergency vehicle preemption detector cable and for making all necessary connections.

34. Electrical Service Meter Breaker Pedestal STH 60 & CTH P, Item 656.0201.01; Electrical Service Meter Breaker Pedestal STH 60 & Industrial Dr, Item 656.0201.02; Electrical Service Meter Breaker Pedestal STH 60 & Jackson Dr, Item 656.0201.03.

Append standard spec 656.2.3 with the following:

- (2) The department will be responsible for the electrical service installation or relocation request for any department-maintained facility. Notify the maintaining authority if the signal is not state maintained that it is their responsibility to arrange for the electrical service installation.
- (3) Electrical utility company service installation and energy cost will be billed to and paid for by the department.
- (4) Install the cabinet base and meter breaker pedestal first, so the electrical utility company can install the service lateral. Install a 3" conduit from the point of service from the utility to the meter breaker pedestal. Finish grades the service trench, replace topsoil that is lost or contaminated with other materials, fertilize, seed, and mulch all areas that are disturbed by the electrical utility company.

Append standard spec 656.5 with the following:

(8) Payment is full compensation for grading the service trench; replacing topsoil; and for fertilizing, seeding, and mulching to restore the disturbed area of the service trench.

35. Traffic Signals, General.

All traffic signal work shall be according to the State of Wisconsin Department of Transportation Standard Specifications for Highway and Structure Construction, 2024 edition, the plans, and these special provisions.

Note that the failure to comply with the state standards and specifications may result in the cost of corrections to be made at the contractor's expense. Also, any additional disruption of State-owned facilities shall be repaired or relocated as needed at the contractor's expense.

2310-13-70, 2310-13-71 32 of 59

Notify the department's Electrical Field Unit at (414) 266-1170 at least three weeks prior to the beginning of the traffic signal work.

36. Signal Mounting Hardware.

Add the following to standard spec 658.2(7):

Use an approved type of pole or standard vertical mounting brackets/clamps for signal faces from an approved manufacturer. Pedestrian traffic signal heads mounted in the median shall use federal yellow aluminum side of pole 2-way upper and lower arm assemblies providing 16 ½-inch center to center spacing.

37. Traffic Signal Faces.

Append standard spec 658.3 with the following:

(5) Connect all ungrounded conductors with wire nuts in the appropriate sections of the signal heads, when directed by WisDOT personnel. Connect the neutral conductors to the terminal strip. Be certain to twist wires prior to installing the wire nuts. All wire nuts must be installed facing up to prevent the entrance of water.

38. Lamp, Ballast, LED, Switch Disposal by Contractor, Item 659.5000.S.

A Description

This special provision describes the packaging of lamps, ballasts, LEDs, and mercury containing switches (e.g., overhead roadway lighting, underdeck bridge, wall packs, pedestrian signals, traffic control stop lights and warning flashers, fluorescent bulbs, and thermostats) removed under this contract for disposal as hazardous materials.

For Lamp, Ballast, LED, Switch Disposal by Contractor, coordinate removal from the work site by the department's hazardous waste disposal vendor.

B Materials

Items removed under this contract will be considered the property of the department for waste generator identification. The contractor is responsible for coordinating with the department's hazardous waste vendor for disposal:

https://wisconsindot.gov/Documents/doing-bus/eng-consultants/cnslt-rsrces/environment/hazwaste-contacts.pdf

C Construction

Provide a secure, level location removed from the travelled way for storage of the material for disposal.

Pack intact fixtures in the packaging of the new lamps used to replace them, or packaging affording the equivalent protection. Place in full, closed stackable cartons.

Pile cartons no more than four high if palletized and secure cartons with shrink wrap to prevent shifting or falling of the loads. Clearly mark each pallet with the words "Universal Waste Lamps" or "Universal Waste Ballasts", the date, and the number of fixtures on each pallet.

Pack broken fixtures into (min.) 6 mil thick plastic bags and place inside sturdy cardboard boxes or the equivalent. Mark the outer packaging with the term "Broken Fixtures/Lamps", the date and the number of broken fixtures clearly marked on the box.

The hazardous waste vendor will not accept fixtures improperly packaged. The vendor will reject any fixtures not removed as part of a contract pay item or otherwise required under this contract.

Pack ballasts and mercury containing switches in appropriate containers.

2310-13-70, 2310-13-71 33 of 59

Complete the lamp and ballast inventory (https://wisconsindot.gov/Documents/doing-bus/eng-consultants/cnslt-rsrces/environment/dotlampballastinventory.dotx) and contact the hazardous waste vendor to coordinate pickup and disposal at a location specified by the contractor. Consolidate all pallets and boxes from one project at a single location. Contact the hazardous waste vendor to set up an appointment for pickup. The hazardous waste vendor requires a minimum of one-week advance notice to schedule pickup.

D Measurement

The department will measure Lamp, Ballast, LED, Switch Disposal by Contractor as each individual unit received by the hazardous waste vendor, properly packaged and acceptably completed, matching the total number of units provided on the inventory form. The department will not measure broken fixtures that exceed a total of 10 percent of all fixtures to be disposed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item: ITEM NUMBER DESCRIPTION UNIT

659.5000.S Lamp, Ballast, LED, Switch Disposal by Contractor EACH

Payment for Lamp, Ballast, LED, Switch Disposal by Contractor is full compensation for handling, packaging, labeling, and scheduling disposal with the hazardous waste vendor; and scrapping and disposal of all other materials.

stp-659-500 (20220628)

39. Temporary Traffic Signals for Intersections STH 60 & CTH P, Item 661.0201.01; Temporary Traffic Signals for Intersections STH 60 & Industrial Dr, Item 661.0201.02; Temporary Traffic Signals for Intersections STH 60 & Jackson Dr, Item 661.0201.03.

Replace standard spec 661.2.1 (1) with the following:

(1) Furnish control cabinet and control equipment. The department will supply, maintain, and install a signal controller, cellular modem, and ethernet switch to establish remote communication to the signal controller. The cabinet must be equipped with a 6-circuit Isotel independent of the GFI receptacles. Provide a cabinet with a Corbin #2 door lock and an access door that allows placing the controller in emergency flash. Provide keys to the access door to the engineer and law enforcement agencies as required. Also provide a manual control accessible by the police. Test traffic signal control cabinets before installation. The department will provide the signal controller with the initial traffic signal timing, and the department will be responsible for all subsequent signal timing changes.

Replace standard spec 661.2.1 (3) with the following:

(3) Use existing underground electric service and meter breaker pedestal for the operation of the Temporary Traffic Signal. The contractor will be responsible for arranging any additional service connection to the temporary signal. The department will pay for all Energy Costs for the operation of the Temporary Traffic Signal.

Furnish and install a generator to operate the temporary traffic signals for the times required to switch the existing permanent traffic signal over to the temporary traffic signal and for the time required to switch the temporary traffic signal back over to the permanent traffic signal.

Contact the local electrical utility at least four days prior to making the switch from the Temporary Traffic Signal to the new Permanent Traffic Signal.

Append standard spec 661.2.1 (6) with the following:

(6) Control equipment or controller equipment is defined as anything inside the control cabinet excluding the department furnished signal controller, cellular modem, and ethernet switch.

Replace standard spec 661.3.1 (2) with the following:

(2) Request a signal inspection of the completed temporary traffic signal installation to the engineer at least five working days prior to the time of the requested inspection. Notify the SE Region Electrical Field Unit at (414) 266-1170 to coordinate the inspection. The SE Region electrical personnel will perform the inspection.

2310-13-70, 2310-13-71 34 of 59

Append standard spec 661.3.1.4 (4) with the following:

(4) Arrange for every other week inspections with the engineer to check the height of the span wire above the roadways to ensure that the bottom of the traffic signal heads remain within the minimum and maximum heights allowed above the roadway. Make all height adjustments within 1-hour of an inspection indicating that adjustments are required. Notify the engineer in writing upon completion of all necessary adjustments. Maintain a written log to properly document the date of each inspection on every other week inspection, the heights above the roadway, the roadway clearance after adjustments have been made, and acceptance by the engineer. Provide all documentation related to the every other week span wire height checks as well as all records related to maintenance performed on the temporary traffic signal installations to the engineer.

Replace standard spec 661.3.2.2 (2) with the following:

(2) Install the tether wire at 20 feet to 22 feet over the roadway.

Replace standard spec 661.3.2.4 (1) with the following:

(1) Install the span wires free of any splices or kinks. Install the span wire mounted signal faces so the bottom is a maximum of 22 feet above the roadway (minimum height is 20 feet). Compute the vertical height of the span wire on the span pole using the following formula:

$$HD (0.05) + RC + HH = SH$$

Replace standard spec 661.3.2.6 (2) with the following:

(2) Upon acceptance of new signal and completion of work, the department will switch control of the intersection over to the permanent cabinet installation. Remove signal cable and wires, wood poles, wood posts, control cabinet, control equipment, and incidental materials. Upon deactivation of the controller, call the electrical utility immediately for the temporary electrical service disconnect. The department shall remove the signal controller, cellular modem, and ethernet switch.

Append standard spec 661.3.2.6 (6) with the following:

(6) Remove the CCTV camera, hardware, mounting brackets and cabling from the temporary traffic signal installation and return it to the department.

Replace standard spec 661.3.2.7 (2) with the following:

(2) Respond within one hour of notification to provide corrective action to any emergency such as but not limited to knockdowns, signal cable problems, and controller equipment failures. If equipment becomes damaged or faulty beyond repair, replace it within one working day. In order to fulfill this requirement, maintain, in stock, sufficient materials and equipment to provide repairs. Replace the traffic signal control equipment including the cabinet and cabinet accessories within 4 hours. If the outcome of the response identifies damage to the department furnished signal controller, notify the Traffic Management Center at (800) 375-7302 who will then dispatch the SE Region Electrical Field Unit.

Replace standard spec 661.5 (2) with the following:

- (2) Payment for the Temporary Traffic Signals for Intersections bid item is full compensation for providing, maintaining, and repairing the complete temporary installation, and for removal. Payment also includes the following:
 - 1. Furnishing and installing replacement equipment.
 - 2. The cost of delivery and pick-up of the cabinet assemblies.

Payment is full compensation for drilling holes; furnishing and installing all materials, including bricks, and coarse aggregate; for excavation, bedding, and backfilling, including any sand or other required materials; furnishing and placing topsoil, fertilizer, seed, and mulch in disturbed areas; for properly disposing of surplus materials; for making inspections; for cleaning up and properly disposing of waste; for removing and delivering the CCTV camera, hardware, mounting brackets and cabling from the temporary traffic signal installation to the department.

2310-13-70, 2310-13-71 35 of 59

40. Install Type 9 Pole, Item SPV.0060.01;

Install Type 10 Pole, Item SPV.0060.03;

Install Type 10 Special Pole, Item SPV.0060.04;

Install Monotube Arms 25-FT, Item SPV.0060.05;

Install Monotube Arms 30-FT, Item SPV.0060.06;

Install Monotube Arms 35-FT Special, Item SPV.0060.07;

Install Monotube Arms 40-FT Special, Item SPV.0060.08;

Install Luminaire Arms Steel 15-FT, Item SPV.0060.09.

A Description

This special provision describes installing department furnished monotube poles, monotube arms, and luminaire arms as shown on the plans and as directed by the engineer.

B Materials

Conform to the pertinent requirements of standard spec 657.2 and as shown on the plans.

C Construction

Conform to the pertinent requirements of standard spec 657.3 and as shown on the plans.

D Measurement

Installing department furnished monotube poles, monotube arms, and luminaire arms shall be measured as each individual pole or arm, installed and acceptably completed.

E Payment

Installing department furnished monotube poles, monotube arms, and luminaire arms shall be paid for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.01	Install Type 9 Pole	EACH
SPV.0060.03	Install Type 10 Pole	EACH
SPV.0060.04	Install Type 10 Special Pole	EACH
SPV.0060.05	Install Monotube Arms 25-FT	EACH
SPV.0060.06	Install Monotube Arms 30-FT	EACH
SPV.0060.07	Install Monotube Arms 35-FT Special	EACH
SPV.0060.08	Install Monotube Arms 40-FT Special	EACH
SPV.0060.09	Install Luminaire Arms Steel 15-FT	EACH

Payment is full compensation for installing all materials, including all associated hardware, fittings, mounting devices, and attachments necessary to completely install the pole and arms.

41. Transport and Install State Furnished EVP Detector Heads STH 60 & CTH P, Item SPV.0060.10;

Transport and Install State Furnished EVP Detector Heads STH 60 & Industrial Dr, Item SPV.0060.11:

Transport and Install State Furnished EVP Detector Heads STH 60 & Jackson Dr, Item SPV.0060.12.

A Description

This special provision describes transporting and installing department furnished Emergency Vehicle Preemption (EVP) Detector Heads, confirmation lights, and mounting brackets as the plans show and as follows.

B Materials

Pick up the department furnished materials at the department's Electrical Shop located at 935 South 60th Street, West Allis. Notify the department's Electrical Field Unit at (414) 266-1170 and make arrangements for picking up the department furnished materials five working days prior to picking the materials up.

2310-13-70, 2310-13-71 36 of 59

C Construction

Install the EVP detector heads as shown on the plans. The department will determine the exact location to ensure that the installation does not create a sight obstruction. Mount the EVP detector heads and wire them per manufacturer instructions. For a cabinet that is not operating the signal, the contractor will terminate the ends and install the discriminators and card rack in the cabinet. If the cabinet is operating the signal, the cabinet wiring will be done by the department.

Notify the department's Electrical shop at (414) 266-1170 upon completion of the installation of the Emergency Vehicle Preemption (EVP) Detector Heads with Confirmation Beacons.

D Measurement

Transporting and installing state furnished EVP detector heads and confirmation lights [Location] will be measured as each unit, acceptably completed.

E Payment

Transporting and Installing State Furnished EVP Detector Heads [Location] will be paid for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.10	Transport and Install State Furnished EVP Detector Heads STH 60 & CTH P	EACH
SPV.0060.11	Transport and Install State Furnished EVP Detector Heads STH 60 & Industrial Dr	EACH
SPV.0060.12	Transport and Install State Furnished EVP Detector Heads STH 60 & Jackson Dr	EACH

Payment is full compensation for transporting and installing department furnished Emergency Vehicle Preemption (EVP) Detector Heads and mounting brackets.

42. Transport and Install State Furnished Traffic Signal Cabinet STH 60 & CTH P, Item SPV.0060.13;

Transport and Install State Furnished Traffic Signal Cabinet STH 60 & Industrial Dr, Item SPV.0060.14:

Transport and Install State Furnished Traffic Signal Cabinet STH 60 & Jackson Dr, Item SPV.0060.15.

A Description

This special provision describes the transporting and installing of state furnished traffic signal cabinet, signal controller, and other cabinet equipment for traffic signals, and for making the cabinet fully operational as shown in the plans.

B Materials

Use materials furnished by the department including: the traffic signal controller and the traffic signal cabinet.

Pick up the state furnished materials at the department's Electrical Shop located at 935 South 60th Street, West Allis. Notify the department's Electrical Field Unit at (414) 266-1170 and make arrangements for picking up the state furnished materials five working days prior to picking up the materials.

Provide all other needed materials in conformance with standard spec 651.2, 652.2, 653.2, 654.2, 655.2, 656.2, 657.2, 658.2 and 659.2.

C Construction

Perform work according to standard spec 651.3, 652.3, 653.3, 654.3, 655.3, 656.3, 657.3, 658.3 and 659.3 except as specified below.

Install the state furnished traffic signal cabinet on the concrete control cabinet base the same day it is delivered to the site location.

Request a signal inspection of the completed signal installation to the engineer at least five (5) working days prior to the time of the requested inspection. The department's Region Electrical personnel will perform the inspection.

2310-13-70, 2310-13-71 37 of 59

D Measurement

Transporting and installing state furnished traffic signal cabinet will be measured as a single unit of work, acceptably completed.

E Payment

Transport and Install State Furnished Traffic Signal Cabinet will be paid for measured quantities at the contract unit price under the following bid items:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.13	Transport and Install State Furnished Traffic Signal Cabinet STH 60 & CTH P	EACH
SPV.0060.14	Transport and Install State Furnished Traffic Signal Cabinet STH 60 & Industrial Dr	EACH
SPV.0060.15	Transport and Install State Furnished Traffic Signal Cabinet STH 60 & Jackson Dr	EACH

Payment is full compensation for installing and testing the traffic signal cabinet and cabinet equipment; for furnishing and installing all other items necessary (such as, wire nuts, splice kits and/or connectors, tape, insulating varnish, ground lug fasteners, etc.) to make the proposed system complete from the source of supply to the most remote unit; and for clean-up and waste disposal.

43. Temporary Infrared EVP System STH 60 & CTH P, Item SPV.0060.16; Temporary Infrared EVP System STH 60 & Industrial Dr, Item SPV.0060.17; Temporary Infrared EVP System STH 60 & Jackson Dr, Item SPV.0060.18.

A Description

This special provision describes furnishing, installing, maintaining, and placing into operation temporary infrared EVP systems at the temporary signalized intersections as shown in the plans.

B Materials

Furnish an infrared emergency vehicle preemption system compatible with the temporary traffic signal controller.

C Construction

The temporary infrared EVP system, as shown in the temporary traffic signal plans or as directed by the engineer, shall be complete in place, tested, and in full operation during each stage of construction.

Install the temporary infrared EVP system as shown in the plans and according to the manufacturer's recommendations. Detectors may be mounted on the temporary traffic signal span wire or wood poles. It shall be the contractor's responsibility to relocate the temporary infrared EVP detectors to a suitable location if there is impedance on the sensor operation. Arrange for testing of equipment prior to acceptance of the installation for each construction stage.

All cables associated with the temporary infrared EVP system shall be routed to the cabinet. Each lead shall be appropriately marked as to which EVP channel it is associated.

Periodic adjustment and/or moving of the temporary infrared EVP detectors may be required due to changes in traffic control, staging, or other construction operations.

Ensure that the temporary infrared EVP system stays in clean working order. Periodic cleaning of the equipment may be required due to dirt and dust build-up.

D Measurement

Temporary Infrared EVP System will be measured as a single unit of work for each intersection, acceptably completed.

E Payment

Temporary Infrared EVP System will be paid for measured quantities at the contract unit price under the following bid items:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.16	Temporary Infrared EVP System STH 60 & CTH P	EACH
SPV.0060.17	Temporary Infrared EVP System STH 60 & Industrial Dr	EACH
SPV.0060.18	Temporary Infrared EVP System STH 60 & Jackson Dr	EACH

2310-13-70, 2310-13-71 38 of 59

Payment is full compensation for furnishing and installing all required equipment, materials, and supplies; for maintaining and changing the EVP detectors to match the plans, traffic control, and construction staging; for relocating the temporary EVP detectors due to construction activities, if required; for testing the EVP system for each stage and sub-stage of construction; for periodically cleaning all temporary EVP detectors; and for removing the equipment at the completion of the project.

44. Transport Traffic Signal and Lighting Materials STH 60 & CTH P, Item SPV.0060.19; Transport Traffic Signal and Lighting Materials STH 60 & Industrial Dr, Item SPV.0060.20; Transport Traffic Signal and Lighting Materials STH 60 & Jackson Dr, Item SPV.0060.21.

A Description

This special provision describes the transporting of department furnished materials for traffic signals and intersection lighting.

B Materials

Transport materials furnished by the department including: Monotube arms/poles and luminaire arms (to be installed on monotube assemblies).

Pick up the department furnished materials at the department's Electrical Shop located at 935 South 60th Street, West Allis. Notify the department's Electrical Field Unit at (414) 266-1170 and make arrangements for picking up the department furnished materials five (5) working days prior to picking the materials up.

Provide all other needed materials in conformance with standard spec 651.2, 652.2, 653.2, 654.2, 655.2, 656.2, 657.2, 658.2 and 659.2.

C Construction

Perform work according to standard spec 651.3, 652.3, 653.3, 654.3, 655.3, 656.3, 657.3, 658.3 and 659.3 except as specified below.

D Measurement

Transport Traffic Signal and Lighting Materials [Location] will be measured as each unit, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid items:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.19	Transport Traffic Signal and Lighting Materials STH 60 & CTH P	EACH
SPV.0060.20	Transport Traffic Signal and Lighting Materials STH 60 & Industrial Dr	EACH
SPV.0060.21	Transport Traffic Signal and Lighting Materials STH 60 & Jackson Dr	EACH

Payment is full compensation for transporting the monotube poles/arms and luminaire arms (to be installed on monotubes). Installation of these materials is included under a separate pay item.

45. Saddle Inlet, Item SPV.0060.22.

A Description

Work under this item includes the construction of a saddle inlet on top of an existing culvert pipe. This work will conform to standard spec 611, the detail provided in the plan, and as hereinafter provided.

B Materials

Conform to the requirements of standard spec 611 and the detail provided in the plan.

C Construction

Construct the saddle inlet according to standard spec 611 and the detail provided in the plan.

D Measurement

The department will measure Saddle Inlet as each single unit, acceptably completed.

2310-13-70, 2310-13-71 39 of 59

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER

DESCRIPTION

UNIT

SPV.0060.22

Saddle Inlet

EACH

Payment is full compensation for providing required materials, including masonry, compressed butyl gasket, rubber adjustment rings, fittings, and reinforcement; for sawing the pipe, and repairing areas to remain that are damaged by sawing; for necessary excavation; backfilling, disposing of surplus materials, and cleaning out and restoring the site as detailed in the plans.

46. Construction Staking Roundabout, Item SPV.0060.23.

A Description

This special provision describes providing the contractor-performed construction staking required to establish the horizontal and vertical position of the following items contained within the roundabout. The limit of this item extends from Station 301+04.26'REB' to Station 306+93.49'REB' and from Station 400+00.00'RNB' to Station 403+89.48'RNB'. The standard Construction Staking bid items will be used in areas outside the limits of this special provision.

- Subgrade
- Base
- · Curb and gutter
- Curb ramps
- Sidewalk
- Supplemental Control
- Slope Stakes

B (Vacant)

C Construction

Perform Construction Staking Roundabout according to the pertinent provisions of standard spec 650.

D Measurement

The department will measure Construction Staking Roundabout as a single lump sum unit for roundabout, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBERDESCRIPTIONUNITSPV.0060.23Construction Staking RoundaboutEACH

Payment is full compensation for Construction Staking Roundabout work necessary to locate and set all construction stakes; for maintaining, relocating, and resetting construction stakes at the roundabout throughout all project stages.

The department will not make final payment for this bid item until the contractor submits all survey notes and computations used to establish the required lines and grades to the engineer within 21 days of completing this work. The department will deduct from payments due the contractor for the additional costs specified in standard spec 105.6.

47. Section Corner Monuments, Item SPV.0060.25.

A Description

Coordinate with Southeastern Wisconsin Regional Planning Commission (SEWRPC) and the Washington County Surveyor for the perpetuation and replacement of a section corner (Public Land Survey System-PLSS) monument.

2310-13-70, 2310-13-71 40 of 59

B Materials

SEWRPC or the Washington County Surveyor will provide a pre-cast concrete monument or brass disk to be used to mark the PLSS corner.

Furnish base aggregate dense materials that conform to standard spec 305 and possibly concrete depending on the road surface.

C Construction

SEWRPC or the Washington County Surveyor will perpetuate existing section corner monument. The contractor will contact the engineer, SEWRPC at 920-912-1036, and the Washington County Surveyor, Scott Schmidt at (262) 335-6881 two weeks before starting construction operations or before the preconstruction meeting to allow for section corner perpetuation. Contractor must excavate and completely remove the existing monument. Contractor is responsible for providing a backfilled 3- to 4-foot-deep hole where existing monument was removed if roadway surface is concrete, contractor will be responsible to provide either a 2 foot by 2 foot "box out" or 24" inch diameter core hole to facilitate setting the new monument. The contractor is responsible to coordinate with SEWRPC, Washington County and the WisDOT Project Manager throughout the perpetuation and replacement process.

Contact Information:

Attn: Rob Merry

Southeastern Wisconsin Regional Planning Commission

W239 N1812 Rockwood Drive

P.O. Box 1607

Waukesha, WI 53187-1607 Phone: (262) 953-4289 Cell: (920) 912-1036 Fax: (262) 547-1103

rmerry@sewrpc.org

Scott M. Schmidt, PE, RLS

Washington County Engineer/Surveyor
Washington County Highway Commissioner

Vehicle Maintenance Storage Facility

West Bend, WI 53090 Phone: 262-335-6881 Fax: 262-335-4439

900 Lang Street

scott.schmidt@co.washington.wi.us

D Measurement

The department will measure Section Corner Monuments by the individual unit, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER

DESCRIPTION

UNIT

SPV.0060.25

Section Corner Monuments

EACH

Payment is full compensation for all excavating; removal of existing monument, for placing and compacting backfill material; for disposing of surplus materials; for concrete or asphalt material, finishing

of roadway surface, for all coordination with SEWRPC and the Washington County Surveyor.

SER-621-003 (20210924)

2310-13-70, 2310-13-71 41 of 59

48. Pedestrian Shuttle Service, Item SPV.0060.26.

A Description

This special provision describes providing a shuttle service for pedestrians and bicyclists during the construction of the STH 60 Wisconsin Southern Railroad crossing conforming to standard specifications, as the plans show, and as follows.

B Materials

Furnish two vehicles equipped to transport pedestrians, including handicapped individuals, and bicyclists including their bicycles and if attached, bike trailer. The vehicles shall be clean, and clearly marked as shuttle service. Vehicles shall be ADA compliant. Vehicles and individuals shall meet the insurance required as specified in standard spec 107.

C Construction

Vehicle drivers shall assist all pedestrians and bicyclists along with their accessories in transporting them from one end of the construction zone to the other end by means of vehicle transportation. Shuttle service shall be provided for a 24-hour to 36-hour period, while the Wisconsin Southern Railroad crossing is closed and reconstructed.

Contractor shall coordinate with the Wisconsin Southern Railroad Company (WSOR) to verify railroad crossing closure/reconstruction timeline prior to scheduling pedestrian shuttle services.

Contractor shall coordinate pickup and drop-off locations with the engineer and Village of Jackson two weeks prior to service being implemented.

D Measurement

The department will measure Pedestrian Shuttle Service as a single lump sum unit for pedestrian shuttle services, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item: ITEM NUMBER DESCRIPTION UNIT

SPV.0060.26 Pedestrian Shuttle Service EACH

Payment is full compensation for coordinating with WSOR, engineer and Village of Jackson, providing/installing temporary shuttle pickup and drop-off signs as directed by the engineer, providing shuttle vehicles, shuttle vehicle markings, and shuttle vehicle drivers.

49. Utility Line Opening (ULO), Item SPV.0060.27.

A Description

This special provision describes excavating to uncover utilities/infrastructure for the purpose of determining location and elevation and potential conflicts with proposed work as directed by the engineer. The location of existing utilities and infrastructure needed to complete the contract work shall be addressed independent of this provision. This item does not remove the contractor's obligation to locate utilities as specified by Wisconsin Administrative code Trans 220.

B (Vacant)

C Construction

Comply with s.182.0175 (2), Stats., with respect to precautions to be taken to avoid and prevent damage to utility facilities.

All ULO shall be directed by the engineer in writing. Notify the engineer and infrastructure/utility owner or their agents 3 working days in advance so that they may be present when excavation work commences.

Provide documentation to the engineer including coordinates/elevations or referenced to alignment/offset. Document the size and/or diameter, composition, and a description of each infrastructure/utility. Supply digital photographs of the uncovered infrastructure to the engineer in .jpeg format for future reference.

Backfill the excavation with suitable backfill, thoroughly compact, replace pavement over utility line opening trenches which are within the staged traffic area as directed by the engineer. Replace pavement and open to traffic within 24 hours of the excavation.

2310-13-70, 2310-13-71 42 of 59

D Measurement

The department will measure Utility Line Opening (ULO) by each individual unit, acceptably completed. Where utilities are within 6 feet of each other at a potential conflict location, only one utility line opening will be called for. In these cases, a single utility line opening will be considered full payment to locate multiple utilities. ULO includes a trench up to 10 feet long as measured at the trench bottom, and of any depth required to locate the intended utility.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBERDESCRIPTIONUNITSPV.0060.27Utility Line Opening (ULO)EACH

Payment is full compensation for the excavation required to expose the utility line; measuring lateral and depth measurements of the utility line; providing required documentation of measurements to the engineer; backfilling with engineer approved material; compacting the backfill material; restoring the site; cleanup, and maintenance of ULO location during construction.

Existing pavement, concrete curb and gutter, and sidewalk removals necessary to facilitate utility line openings are not considered part of or paid for under ULO but are considered separate and measured and paid for separately as removal items. Granular backfill, pavement replacement material, concrete curb, gutter, and sidewalk items will also be considered separate from ULO and will be measured and paid for separately.

50. Wall Modular Block Mechanically Stabilized Earth (R-66-87), Item SPV.0165.01.

A Description

This special provision describes designing, furnishing materials, and erecting a permanent earth retention system according to the lines, dimension, elevations, and details as shown on the plans and provided in the contract. The design life of the wall and all wall components shall be 75 years minimum.

This special provision describes the quality management program (QMP) for Mechanically Stabilized Earth (MSE) walls. A quality management program is defined as all activities, including process control, inspection, sampling and testing, and necessary adjustments in the process that are related to the construction of the MSE wall, which meets all the requirements of this provision.

This special provision describes contractor quality control (QC) sampling and testing for backfill density testing, documenting those results, and documenting related production and placement process changes. This special provision also describes department quality verification (QV), independent assurance (IA), and dispute resolution.

Chapter 8 of the department's construction and materials manual (CMM) provides additional detailed guidance for QMP work and describes sampling and testing procedures.

B Materials

B.1 Proprietary Wall Systems

The supplied wall system must be from the department's approved list of Modular Block Mechanically Stabilized Earth Wall systems. Proprietary wall systems must conform to the requirements of this specification and be pre-approved for use by the department's Bureau of Structures. The department maintains a list of pre-approved proprietary wall systems. See the approved products list titled "Proprietary Retaining Wall System Vendors." The name of the pre-approved proprietary wall system selected shall be furnished to the engineer within 25 days after the award of contract. The department also maintains a separate list of plants pre-approved by the department to provide wall facing units. See the approved products list titled "Precast Concrete and Block Fabricators." The identity of the plant manufacturing the facing units shall be furnished to the engineer at least 14 days prior to the project delivery.

To be eligible for use on this project, a system must have been pre-approved by the Bureau of Structures and added to that list prior to the bid closing date. To receive pre-approval, the retaining wall system must comply with all pertinent requirements of this provision and be prepared according to the requirements of Chapter 14 of the department's LRFD Bridge Manual. Information and assistance with the pre-approval process can be obtained by contacting the Bureau of Structures, Structures Maintenance Section at the following email address: DOTDLStructuresFabrication@dot.wi.gov.

2310-13-70, 2310-13-71 43 of 59

To be eligible to provide wall facing units for this project, a block manufacturing plant must be preapproved by the Bureau of Technical Services and added to that list prior to the bid closing date. Information and assistance with the pre-approval process can be obtained by contacting the Bureau of Technical Services at the following email address: DOTProductSubmittal@wisconsin.gov.

B.2 Design Requirements

It is the responsibility of the contractor to submit a design and supporting documentation as required by this special provision, for review and acceptance by the department, to show the proposed wall design conforms to the design specifications. The submittal shall include the following items for review: detailed plans and shop drawings, complete design calculations, explanatory notes, supporting materials, and specifications. The detailed plans and shop drawings shall include all details, dimensions, quantities, and cross-sections necessary to construct the walls. Submit shop drawings to the engineer conforming to 105.2 with electronic submittal to the fabrication library under 105.2.2. Certify that shop drawings conform to quality control standards by submitting department form DT2329 with each set of shop drawings. Department review does not relieve the contractor from responsibility for errors or omissions on shop drawings. Submit no later than 60 days from the date of notification to proceed with the project and a minimum of 30 days prior to the date proposed to begin wall construction.

The plans and shop drawings shall be prepared on reproducible sheets 11-inch x 17-inch, including borders. Each sheet shall have a title block in the lower right corner. The title block shall include the WisDOT project identification number and structure number. Design calculations and notes shall be on 8 ½ inch x 11-inch sheets, and shall contain the project identification number, name or designation of the wall, date of preparation, initials of designer and checker, and page number at the top of the page. All plans, shop drawings, and calculations shall be signed, sealed, and dated by a professional engineer licensed in the State of Wisconsin.

The design of the wall shall be in compliance with the current American Association of State Highway and Transportation Officials LRFD (AASHTO LRFD) Bridge Design Specifications with latest interim specifications for Mechanically Stabilized Earth Walls, WisDOT's current Standard Specifications for Highway and Structure Construction (standard spec), Chapter 14 of the WisDOT LRFD Bridge Manual and standard engineering design procedures as determined by the department. Loads, load combinations, load and resistance factors shall be as specified in AASHTO LRFD Section 11. The associated resistance factors shall be defined according to Table 11.5.7-1 in AASHTO LRFD.

Design and construct the walls according to the lines, grades, heights, and dimensions shown on the plans, as herein specified, and as directed by the engineer.

Walls parallel to supporting highway traffic shall be designed for the effects of highway surcharge loading equivalent of 2 feet soil surcharge weight or 240 psf. The design shall also consider the traffic barrier impact where applicable. Walls that do not carry highway traffic shall be designed for a live load surcharge of 100 psf according to Chapter 14 of the WisDOT LRFD Bridge Manual or as stated on the plans.

A maximum value of the angle of internal friction of the wall backfill material used for design shall be assumed to be 30 degrees without a certified report of tests. If a certified report of tests yields an angle of internal friction greater than 30 degrees, the larger test value may be used for design, up to a maximum value of 36 degrees.

An external stability check at critical wall stations showing Capacity Demand Ratio (CDR) for sliding, eccentricity, and bearing checks is provided by the department and are provided on the wall plans.

The design of the wall by the contractor shall consider the internal and compound stability of the wall mass according to AASHTO LRFD 11.10.6. The internal stability shall include soil reinforcement pullout, soil reinforcement rupture, and wall facing-reinforcement connection failure at each soil reinforcement level. The design shall be performed using the Simplified Method or Coherent Gravity Method. Calculations for factored stresses and resistances shall be based upon assumed conditions at the end of the design life. Compound stability shall be computed for the applicable strength limits. Sample analyses and hand calculations shall be submitted to verify the output of any software used. The design calculations and notes shall clearly indicate the Capacity to Demand Ratios (CDR) for all internal and external stabilities as defined in AASHTO LRFD.

Wall facing units shall be designed according to AASHTO LRFD 11.10.2.3.

2310-13-70, 2310-13-71 44 of 59

The minimum length of soil reinforcement measured from the back face of the wall shall be equal to 0.7 of the wall height, or as shown on the plan. In no case shall this length be less than 6.0 feet. The soil reinforcement length shall be the same from the bottom to the top of the wall. All soil reinforcement layers shall be connected to facings. The soil reinforcement shall extend a minimum of 3.0 feet beyond the theoretical failure plane in all cases. The maximum vertical spacing of soil reinforcement layers shall be two times the block width (front face to back face) or 32 inches, whichever is less. The first (bottom) layer of reinforcement shall be placed no further than 12 inches above the top of the leveling pad or the height of the block, but at least one block height above the leveling pad. The last (top) layer of soil reinforcement shall be no further than 21 inches below the top of the uppermost block.

All soil reinforcement required for the reinforced soil zone shall be connected to the wall facing.

Soil reinforcement shall be fabricated or designed to avoid piling, drainage structures or other obstacles in the fill without field modifications. Unless approved by the Bureau of Structures cutting or altering of the basic structural section of either the strip or grid at the site is prohibited, a minimum clearance of 3" shall be maintained between any obstruction and reinforcement, and splicing reinforcement is not allowed.

The minimum embedment of the wall shall be 1 foot 6 inches below finished grade, or as given on the plans. All walls shall be provided with a concrete leveling pad. Minimum wall embedment does not include the leveling pad depth. Step the leveling pad to follow the general slope of the ground line. Frost depth shall not be considered in designing the wall for depth of leveling pad.

Wall facing units shall be installed on a leveling pad.

B.3 Wall System Components

Materials furnished for wall system components under this contract shall conform to the requirements of this specification. All documentation related to material and components of the wall systems specified in this subsection shall be submitted to the engineer.

B.3.1 Wall Facing

Wall facing units shall consist of precast modular concrete blocks. Furnish concrete produced by a dry-cast or wet-cast process. Concrete for all blocks shall not contain less than 565 pounds of cementitious materials per cubic yard. The contractor may use cement conforming to standard spec. 501.2.1 or may substitute for Portland cement at the time of batching conforming to standard spec. 501.2.6 for fly, 501.2.7 for slag, or 501.2.8 for other pozzolans. In either case the maximum total supplementary cementitious content is limited to 30% of the total cementitious content by weight.

Dry-cast concrete blocks shall be manufactured according to ASTM C1372 and this specification.

All units shall incorporate a mechanism or devices that develop a mechanical connection between vertical block layers. Units that are broken, have cracks wider than 0.02" and longer than 25% of the nominal height of the unit, chips larger than 1", have excessive efflorescence, or are otherwise deemed unacceptable by the engineer, shall not be used within the wall. A single block front face style shall be used throughout each wall. The color and surface texture of the block shall be as given on the plan.

The top course of facing units shall be as noted on the plans, either.

- Solid precast concrete unit designed to be compatible with the remainder of the wall. The finishing course shall be bonded to the underlying facing units with a durable, high strength, flexible adhesive compound compatible with the block material.
- A formed cast-in-place concrete cap. A cap of this type shall have texture, color, and appearance, as noted on the plans. The vertical dimension of the cap shall not be less than 3 1/2 inches. Expansion joints shall be placed in the cap at a maximum spacing of 20 feet unless noted otherwise on the plan. Use Grade A concrete conforming to standard spec 501 as modified in standard spec 716. Provide QMP for cast in place cap and coping concrete as specified in standard spec 716, Class II Concrete.

Block dimensions may vary no more than ±1/8 inch from the standard values published by the manufacturer. Blocks must have a minimum width (front face to back face) of 8 inches. The minimum front face thickness of blocks shall be 4 inches measured perpendicular from the front face to inside voids greater than 4 square inches. The minimum allowed thickness of any other portions of the block is 1¾ inches. The front face of the blocks shall conform to plan requirements for color, texture, or patterns.

2310-13-70, 2310-13-71 45 of 59

If pins are used to align modular block facing units, they shall consist of a non-degrading polymer, or hot dipping galvanized steel and be made for the express use with the modular block units supplied, to develop mechanical interlock between facing unit block layers. Connecting pins shall be capable of holding the wall in the proper position during backfilling. Furnish documentation that establishes and substantiates the design life of such devices.

All block materials shall be furnished palleted and banded, with every pallet marked for quantity, lot number, lot size, manufacturing plant, and manufacturing date(s). Materials furnished loose or unmarked will be rejected. Rejected materials shall be removed from the project at no cost to the department.

B.3.1.1 Material Testing

Perform or procure quality control testing of project materials according to the following requirements:

Toot	Method	Requirement	
Test		Dry cast	Wet cast
Compressive Strength (psi)	ASTM C140 or ASTM C39 [4]	5000 min.	4000 min.
Air Content (%)	AASHTO T152 [4]	N/A	6.0 +/-1.5
Water Absorption (%)	ASTM C140 [3]	6 max.	N/A
Freeze-Thaw Loss (%) 40 cycles, 5 of 5 samples 50 cycles, 4 of 5 samples	ASTM C1262 ^{[1][2][3]}	1.0 max. 1.5 max.	N/A

^[1] Test shall be run using a 3% saline solution and blocks greater than 45 days old.

- An independent testing laboratory shall control and conduct all sampling and testing under ASTM C140/Water Absorption and ASTM C1262. Prior to sampling, the manufacturer shall identify materials by lot. Five blocks per lot shall be randomly selected for testing. Solid blocks used as a finishing or top course shall not be selected. The selected blocks shall remain under the control of the person who conducted the sampling until shipped or delivered to the testing laboratory.
- The manufacturer may perform their own quality control testing under ASTM C140/Compressive Strength, ASTM C39, and AASHTO T152, if qualified for this work under the requirements for plant certification.

The contractor and fabricator shall coordinate with the independent testing agent (if used) to ensure that strength and air content samples can be taken appropriately during manufacturing. At the time of delivery of materials, furnish the engineer a certified report of test from an AASHTO-registered or ASTM-accredited independent testing laboratory for each lot furnished.

The certified test report shall include the following:

- Project ID
- Production process used (dry-cast or wet-cast)
- Name and location of testing facility
- Name of sampling technician
- Lot number, lot size, and date(s) of fabrication.

Quality control testing of project materials shall be completed not more than 18 months prior to delivery. Lot size shall not exceed the maximum testing frequencies, which shall not exceed 5000 blocks for dry-cast blocks and the lesser of 150 CY or 1 day's production for wet-cast blocks. Test results will represent all blocks within the lot. Each pallet of blocks delivered shall bear lot identification information. Block lots that do not meet the requirements of this specification or blocks without supporting reports will be rejected and shall be removed from the project at no expense to the department.

Nonconforming materials will be subject to evaluation according to standard spec 106.5.

B.3.2 Leveling Pad

Provide an unreinforced cast-in-place concrete leveling pad. Use Grade A concrete conforming to standard spec 501 as modified in standard spec 716. Provide QMP for leveling pad concrete as specified in standard spec 716, Class III Concrete.

2310-13-70, 2310-13-71 46 of 59

^[2] Test results that meet either of the listed requirements for Freeze-Thaw Loss are acceptable.

The minimum width of the concrete leveling pad shall be as wide as the proposed blocks plus 6-inches, with 6-inches of the leveling pad extending beyond the front face of the blocks. The minimum thickness of the leveling pad shall be 6-inches.

B.3.3 Backfill

Furnish and place backfill for the wall as shown on the plans and as hereinafter provided.

Wall Backfill, Type A, shall comply with the requirements for Coarse Aggregate No. 1 as given in standard spec 501.2.7.4.2. All backfill placed within a zone from the top of the leveling pad to the top of the final layer of wall facing units and within 1 foot behind the back face of the wall shall be Wall Backfill, Type A. This includes all material used to fill openings in the wall facing units.

Wall Backfill, Type B, shall be placed in a zone extending horizontally from 1 foot behind the back face of the wall to 1 foot beyond the end of the reinforcement and extending vertically from the top of the leveling pad to a minimum of 3 inches above the final reinforcement layer.

Use natural sand or a mixture of sand with gravel, crushed gravel, or crushed stone. Do not use foundry sand, bottom ash, blast furnace slag, crushed/recycled concrete, crushed/milled asphaltic concrete or other potentially corrosive material.

Provide material conforming to the following graduation requirements as per AASHTO T27.

Sieve Size	% By Weight Passing
1 inch	100
No. 40	0 - 60
No. 200	0 - 15

The material shall have a liquid limit not greater than 25, as per AASHTO T89, and a plasticity index not greater than 6, as per AASHTO T90. Provide the percent by weight, passing the #4 sieve.

In addition, backfill material Type A and Type B shall meet the following requirements.

Test	Method	Value
pH	AASHTO T-289	4.5-9.0
Sulfate content [1]	AASHTO T-290	200 ppm max.
Chloride content [1]	AASHTO T-291	100 ppm max.
Electrical Resistivity [1]	AASHTO T-288	3000 ohm-cm min.
Organic Content [1]	AASHTO T-267	1.0% max.
Angle of Internal Friction	AASHTO T-236 ^[2]	30 degrees min. (At 95.0% of maximum density and optimum moisture, per AASHTO T99, or as modified by C.2)

^[1] Requirement does not apply to walls with non-metallic reinforcement and non-metallic connectors.

[2] If the amount of P-4 material is greater than 60%, use AASHTO 236 with a standard-size shear box. Test results of this method may allow the use of larger angles of internal friction, up to the maximum allowed by this specification.

If the amount of P-4 material is less than or equal to 60%, two options are available to determine the angle of internal friction. The first method is to perform a fractured faces count, per ASTM D5821, on the R-4 material. If more than 90% of the material is fractured on one face and more than 50% is fractured on two faces, the material meets the specifications, and the angle of internal friction can be assumed to be 30 degrees. The second method allows testing all P-1" material, as per AASHTO T-236, with a large shear box. Test results of this second method may allow the use of larger angles of internal friction, up to the maximum allowed by this specification.

Prior to placement of the backfill, obtain, and furnish to the engineer a certified report of test results that the backfill material complies with the requirements of this specification. Specify the method used to determine the angle of internal friction. This certified report of test shall be less than 6 months old. Tests will be performed by a certified independent laboratory. In addition, when backfill characteristics and/or

2310-13-70, 2310-13-71 47 of 59

sources change, provide a certified report of tests for the new backfill material. Additional certified report of tests is also required. These additional backfill tests may be completed at the time of material production or material placement, with concurrence of the engineer. If this additional testing is completed at the time of material production, complete testing for every 2000 cubic yards of backfill or portion thereof. If this additional testing is completed at the time of material placement, complete testing for every 2000 cubic yards of backfill, or portion thereof, used per wall. For the additional required testing for every 2000 cubic yards of backfill placement, if the characteristic of the backfill and/or the source has not changed then Angle of Internal Friction tests are not included in the additional required testing. All certified reports of test results shall be less than 6 months old and performed by a certified independent laboratory.

B.3.4 Soil Reinforcement

B.3.4.1 Geogrids

Geogrid supplied as reinforcing members shall be manufactured from long chain polymers limited to polypropylene, high-density polyethylene, polyaramid, and polyester. Geogrids shall form a uniform rectangular grid of bonded, formed, or fused polymer tensile strands crossing with a nominal right-angle orientation. The minimum grid aperture shall be 0.5 inch. The geogrid shall maintain dimension stability during handling, placing, and installation. The geogrid shall be insect, rodent, mildew, and rot resistant. The geogrid shall be furnished in a protective wrapping that shall prevent exposure to ultraviolet radiation and damage from shipping or handling. The geogrid shall be kept dry until installed. Each roll shall be clearly marked to identify the material contained.

The wall supplier shall provide the nominal long-term design strength (T_{al}) and nominal long-term connection strength, Talc as discussed below.

Nominal Long-Term Design Strength (Tal)

The wall supplier shall supply the nominal long-term design strength (T_{al}) used in the design for each reinforcement layer and shall be determined by dividing the Ultimate Tensile Strength (T_{ult}) by the factors RF_{ID}, RF_{CR}, RF_D.

Hence,

$$T_{al} = \frac{T_{ult}}{RF_{ID} xRF_{CR} xRF_{D}}$$

where:

 T_{ult} = Ultimate tensile strength of the reinforcement determined from wide width tensile tests (ASTM D6637) for geogrids based on the minimum average roll value (MARV) for the product.

 RF_{ID} = Strength reduction factor to account for installation damage to the reinforcement. In no case shall RF_{ID} be less than 1.1.

 RF_{CR} = Strength reduction factor to prevent long-term creep rupture of the reinforcement. In no case shall RF_{CR} be less than 1.2.

 RF_D = Strength reduction factor to prevent rupture of the reinforcement due to chemical and biological degradation. In no case shall RF_D be less than 1.1.

Values for RF_{ID} , RF_{CR} , and RF_{D} shall be determined from product specific test results. Guidelines for determining RF_{ID} , RF_{CR} , and RF_{D} from product specific data are provided in FHWA Publication No. FHWA-NHI-10-024 and FHWA-NHI-10-025 "Design and Construction of Mechanically Stabilized Earth Walls and Reinforced Soil Slopes".

Nominal Long-term Connection Strength Tac

The nominal long term connection strength, T_{ac} , shall be based on laboratory geogrid connection tests between wall facing and geogrids. T_{ac} shall be as given below:

2310-13-70, 2310-13-71 48 of 59

$$T_{ac} = \frac{T_{ult} * CR_{cr}}{RF_{D}}$$

where:

T_{ac} = Nominal long-term reinforcement facing connection strength per unit reinforcement width at a specified confining pressure.
 T_{ult} = Ultimate tensile strength of the reinforcement for geogrids defined as the minimum average roll value (MARV) for the product.

CR_{cr} = Long term connection strength reduction factor to account for reduced ultimate strength resulting from connection.

RF_D = Strength reduction factor to prevent rupture of the reinforcement due to chemical and biological degradation.

 $T_{\rm ac}$ shall be developed from the tests conducted by an independent laboratory on the same facing blocks and geogrids as proposed for the wall and shall cover a range of overburden pressures comparable to those anticipated in the proposed wall. The connection strength reduction factor CR_{cr} shall be determined according to long-term connection test as described in Appendix B of FHWA Publication No. FHWA-NHI 10-025 "Design and Construction of Mechanically Stabilized Earth Walls and Reinforced Soil Slopes". CR_{cr} may also be obtained from the short-term connection test meeting the requirements of NCMA test method SRWU-1 in Simac et al 1993 or ASTM D4884.

The contractor shall provide a manufacturer's certificate that the Tult (MARV) of the supplied geogrid has been determined according to ASTM D4595 or ASTM D6637 as appropriate. Contractor shall also provide block to block and block to reinforcement connection test reports prepared and certified by an independent laboratory. Also provide calculations according to AASHTO LRFD, and using the results of laboratory tests, that the block-geogrid connections shall be capable of resisting 100% of the maximum tension load in the soil reinforcements at any level within the wall, for the design life of the wall system.

B.3.4.2 Galvanized Metal Reinforcement

In lieu of polymeric geogrid earth reinforcement, galvanized metal reinforcement may be used. Design and materials shall be according to AASHTO LRFD 11.10.6.4.2. The design life of steel soil reinforcements shall also comply with AASHTO LRFD. Steel soil reinforcement shall be prefabricated into single or multiple elements before galvanizing.

C Construction

C.1 Excavation and Backfill

Excavation and preparation of the foundation for the MSE wall and the leveling pad shall be according to standard spec 206. The volume of excavation covered is limited to the width of the reinforced mass and to the depth of the leveling pad unless shown or noted otherwise on the plan. At the end of each working day, provide good temporary drainage such that the backfill shall not become contaminated with run-off soil or water if it should rain. Do not stockpile or store materials or large equipment within 10 feet of the back of the wall.

Places backfill materials in the areas as indicated on the plans and as detailed in this specification. Backfill lifts shall be no more than 8-inches in depth, after compaction. Backfilling shall closely follow erection of each course of wall facing units.

Conduct backfilling operations in such a manner as to prevent damage or misalignment of the wall facing units, soil reinforcement, or other wall components. At no expense to the department, correct any such damage or misalignment as directed by the engineer. A field representative of the wall supplier shall be available during wall construction to provide technical assistance to the contractor and the engineer.

Place and compact the MSE backfill to the level of the next higher layer of MSE reinforcement before placing the MSE reinforcement or connecting it to the wall facing. Place and compact material beyond the reinforced soil zone to allow for proper compaction of material within the reinforced zone. The MSE reinforcement shall lay horizontally on top of the most recently placed and compacted layer of MSE backfill.

2310-13-70, 2310-13-71 49 of 59

Do not operate tracked or wheeled equipment on the backfill within 3 feet from the back face of modular blocks. The engineer may order the removal of any large or heavy equipment that may cause damage or misalignment of the wall facing units.

C.2 Compaction

Compact walls backfill Type A with at least three passes of lightweight manually operated compaction equipment acceptable to the engineer.

Compact all backfill Type B as specified in standard spec 207.3.6. Compact the backfill Type B to 95.0% of maximum dry density as determined by AASHTO T-99 (modified to compute densities to the nearest 0.1 pcf).

Ensure adequate moisture is present in the backfill during placement and compaction to prevent segregation and to help achieve compaction.

Compaction of backfill within 3 feet of the back face of the wall should be accomplished using lightweight compaction devices. Use of heavy compaction equipment or vehicles should be avoided within 3 feet of the modular blocks. Do not use sheepsfoot or padfoot rollers within the reinforced soil zone.

A minimum of 6 inches of backfill shall be placed over the MSE reinforcement prior to working above the reinforcement.

C.3 Wall Components

C.3.1 General

Erect wall facing units and other associated elements according to the wall manufacturer's construction guide and to the lines, elevations, batter, and tolerances as shown on the plans. Center the initial layer of facing units on the leveling pad; then level them and properly align them. Fill formed voids or openings in the facing units with wall backfill, Type A. Remove all debris on the top of each layer of facing units, before placing the next layer of facing units.

Install all pins, rods, clips, or other devices used to develop mechanical interlock between facing unit layers according to the manufacturer's directions.

The MSE reinforcement shall lay horizontally on the top of the most recently placed and compacted layer of MSE backfill. Bending of MSE reinforcement that result in a kink in the reinforcement shall not be allowed. If skewing of the reinforcement is required due to obstructions in the reinforced fill, the maximum skew angle shall not exceed 15 degrees from the normal position unless a greater angle is shown on the plans. The adequacy of the skewed reinforcement in such a case shall be addressed by supporting calculations.

C.3.2 Leveling Pad

Provide an unreinforced cast-in-place concrete leveling pad as shown on the plans. Vertical tolerances shall not exceed 3/4-inch when measured along a 10-foot straight edge. Allow the concrete to set at least 12 hours prior to placing wall facing units.

The bottom row of wall facing units shall be horizontal and 100% of the unit surface shall bear on the leveling pad.

C.3.3 Soil Reinforcement

C.3.3.1 Geogrid Layers

Place soil reinforcement at the positions and to the lengths as indicated on the accepted shop drawings. Take care that backfill placement over the positioned soil reinforcement elements does not cause damage or misalignment of these elements. Correct any such damage or misalignment as directed by the engineer. Do not operate wheeled or tracked equipment directly on the soil reinforcement. A minimum cover of 6 inches is required before such operation is allowed.

Place and anchor geogrid material between wall unit layers in the same manner as used to determine the Geogrid Block-to-Connection Strength. Place the grid material so that the machine direction of the grid is perpendicular to the wall face. Each grid layer shall be continuous throughout the lengths indicated on the plans. Join grid strips with straps, rings, hooks, or other mechanical devices to prevent movement during backfilling operations. Prior to placing backfill on the grid, pull the grid taunt, and hold in position with pins, stakes or other methods approved by the engineer.

2310-13-70, 2310-13-71 50 of 59

C.3.3.2 Steel Layers

Place the steel reinforcement full width in one piece as shown on the plans. No splicing will be allowed. Maintain elements in position during backfilling.

C.4 Quality Management Program

C.4.1 Quality Control Plan

Submit a comprehensive written quality control plan to the engineer at or before the pre-construction meeting. Do not perform MSE wall construction work before the engineer reviews and accepts the plan. Construct the project as the plan provides.

Do not change the quality control plan without the engineer's review and acceptance. Update the plan with changes as they become effective. Provide a current copy of the plan to the engineer and post in the contractor's laboratory as changes are adopted. Ensure that the plan provides the following elements:

- 1. An organizational chart with names, telephone numbers, current certifications and/or titles, and roles and responsibilities of QC personnel.
- The process used to disseminate QC information and corrective action efforts to the appropriate persons. Include a list of recipients, the communication process that will be used, and action time frames.
- 3. A list of source locations, section, and quarter descriptions, for all aggregate materials requiring QC testing.
- 4. Descriptions of stockpiling and hauling methods.
- 5. An outline for resolving a process control problem. Include responsible personnel, required documentation, and appropriate communication steps.
- 6. Location of the QC laboratory retained sample storage, and other documentation.
- 7. A summary of the locations and calculated quantities to be tested under this provision.
- 8. A proposed sequencing plan of wall construction operations and random test locations.

C.4.2 Quality Control Personnel

Perform the quality control sampling, testing, and documentation required under this provision using HTCP certified technicians. Have a HTCP Grading Technician I (GRADINGTEC-I); or Assistant Certified Technician, Grading (ACT-GRADING); or Aggregate Technician I (AGGTEC-I); or Assistant Certified Technician, Aggregate (ACT-AGG) present at each grading site during all walls backfill placement, compaction, and nuclear testing activities. Have a HTCP Nuclear Density Technician I (NUCDENSITYTEC-I) or Assistant Certified Technician, Nuclear Density Gauge Operator (ACT-NUC) perform field density and field moisture content testing.

If an Assistant Certified Technician (ACT) is performing sampling or testing, a certified technician must coordinate and take responsibility for the work an ACT performs. Have a certified technician Ensure that all sampling and testing is performed correctly, analyze test results, and post resulting data. No more than one ACT can work under a single certified technician.

C.4.3 Equipment

Furnish the necessary equipment and supplies for performing quality control testing. Ensure that all testing equipment conforms to the equipment specifications applicable to the required testing methods. The engineer may inspect the measuring and testing devices to confirm both calibration and condition. Calibrate all testing equipment according to the CMM and maintain a calibration record at the laboratory.

Furnish nuclear gauges from the department's approved product list at:

https://wisconsindot.gov/Pages/doing-bus/eng-consultants/cnslt-rsrces/tools/appr-prod/default.aspx

Ensure that the nuclear gauge manufacturer or an approved calibration service calibrates the gauge the same calendar year it is used on the project. Retain a copy of the calibration certificate with the gauge.

Conform to AASHTO T310 and CMM 8-15 for density testing and gauge monitoring methods.

Split each Proctor sample and identify so as to provide comparison with the department's test results. Unless the engineer directs otherwise, retain the QC split samples for 14 calendar days and promptly deliver the department's split samples to the department.

2310-13-70, 2310-13-71 51 of 59

C.4.4 Documentation

- Document all observations, inspection records, and process adjustments daily. Submit test results to the department's project materials coordinator on the same day they become available.
- (2) Use forms provided in CMM Chapter 8. Note other information in a permanent field record and as a part of process control documentation enumerated in the contractor's quality control plan. Enter QC data and backfill material certified report results into the applicable materials reporting system (MRS) software within 5 business days after results are available.
- (3) Submit final testing records and other documentation to the engineer electronically within 10 business days after all contract-required information becomes available. The engineer may allow submission of scanned copies of hand-written documentation.

C.4.5 Quality Control (QC) Testing

Perform compaction testing on the backfill. Conform to CMM 8-15 for testing and gauge monitoring methods. Conduct testing at a minimum frequency of 1 test per 150 cubic yards of backfill, or major portion thereof in each lift. A minimum of one test for every lift is required. Deliver documentation of all compaction testing results to the engineer at the time of testing.

Perform 1 gradation test every 750 cubic yards of fill and one 5-point Proctor test (or as modified in C.2) every 2,250 cubic yards of fill. Provide the region split samples of both within 72 hours of sampling, at the region laboratory. Test sites shall be selected using ASTM Method D3665. Provide Proctor test results to the engineer within 48 hours of sampling. Provide gradation test results to the engineer within 24 hours of sampling.

C.4.6 Department Testing

C.4.6.1 General

(1) The department will conduct verification testing to validate the quality of the product and independent assurance testing to evaluate the sampling and testing. The department will provide the contractor with a listing of names and telephone numbers of all QV and IA personnel for the project and provide test results to the contractor within 2 business days after the department obtains the sample.

C.4.6.2 Quality Verification (QV) Testing

- The department will have an HTCP technician, or ACT working under a certified technician, perform QV sampling and testing. Department verification testing personnel must meet the same certification level requirements specified in C.4.2 for contractor testing personnel for each test result being verified. The department will notify the contractor before sampling so the contractor can observe QV sampling.
- (2) The department will conduct QV tests at the minimum frequency of 30% of the required contractor density, Proctor and gradation tests.
- (3) The department will locate density tests and gradation samples randomly, at locations independent of the contractor's QC work. The department will split each Proctor and gradation QV sample, testing half for QV, and retaining the remaining half for 10 business days.
- (4) The department will conduct QV Proctor and gradation tests in a separate laboratory and with separate equipment from the contractor's QC tests. The department will use the same methods specified for QC testing.
- (5) The department will assess QV results by comparing to the appropriate specification limits. If QV test results conform to this special provision, the department will take no further action. If density QV test results are nonconforming, the area shall be reworked until the density requirements of this special provision are met. If the gradation test results are nonconforming, standard spec 106.5 will apply. Differing QC and QV nuclear density values of more than 1.5 pcf will be investigated and resolved. QV density tests will be based on the appropriate QC Proctor test results unless the QV and QC Proctor result difference is greater than 3.0 pcf. Differing QC and QV Proctor values of more than 3.0 pcf will be investigated and resolved.

C.4.6.3 Independent Assurance (IA)

(1) Independent assurance is unbiased testing the department performs to evaluate the department's QV and the contractor's QC sampling and testing, including personnel qualifications, procedures, and equipment. The department will perform an IA review according to the department's independent assurance program. That review may include one or more of the following:

2310-13-70, 2310-13-71 52 of 59

- 1. Split sample testing.
- 2. Proficiency sample testing.
- 3. Witnessing sampling and testing.
- 4. Test equipment calibration checks.
- 5. Reviewing required worksheets and control charts.
- 6. Requesting that testing personnel perform additional sampling and testing.
- (2) If the department identifies a deficiency, and after further investigation confirms it, correct that deficiency. If the contractor does not correct or fails to cooperate in resolving identified deficiencies, the engineer may suspend placement until action is taken. Resolve disputes as specified in C.4.6.4.

C.4.6.4 Dispute Resolution

- The engineer and contractor should make every effort to avoid conflict. If a dispute between some aspect of the contractor's and the engineer's testing program does occur, seek a solution mutually agreeable to the project personnel. The department and contractor may review the data, examine data reduction and analysis methods, evaluate sampling and testing procedures, and perform additional testing. Use ASTM E178 to evaluate potential statistically outlying data.
- Production test results, and results from other process control testing, may be considered when resolving a dispute.
- (3) If the project personnel cannot resolve a dispute, and the dispute affects payment or could result in incorporating non-conforming product or work, the department will use third party testing to resolve the dispute. The department's central office laboratory, or a mutually agreed on independent testing laboratory, will provide this testing. The engineer and contractor will abide by the results of the third-party tests. The party in error will pay service charges incurred for testing by an independent laboratory. The department may use third party test results to evaluate the quality of questionable materials and determine the appropriate payment. The department may reject material or otherwise determine the final disposition of nonconforming material as specified in standard spec 106.5.

C.5 Geotechnical Information

Geotechnical data to be used in the design of the wall is given on the wall plan. After completing wall excavation of the entire reinforced soil zone, notify the department and allow the Regional Soils Engineer two working days to review the foundation.

D Measurement

The department will measure Wall Modular Block Mechanically Stabilized Earth by the square foot, acceptably completed. The department will compute the measured quantity from the theoretical pay limits the contract plans show. The department will make no allowance for wall area constructed above or below the theoretical pay limits. All work beyond the theoretical pay limits is incidental to the cost of work. The department will make no allowance for as-built quantities.

E Payment

The department will pay for accepted measured quantities at the contract unit price under the following bid item:

ITEM NUMBER DESCRIPTION UNIT SPV.0165.01 Wall Modular Block Mechanically Stabilized Earth (R-66-87) SF

Payment is full compensation for supplying a design and shop drawings; preparing the site, including all necessary excavation and disposal of materials; supplying all necessary wall components to produce a functional wall system including cap, copings, leveling pad, and leveling pad steps; constructing the retaining system and providing temporary drainage; providing backfill, backfilling, compacting, developing/completing/documenting the quality management program, and performing compaction testing.

The department will pay separately for parapets, traffic barriers, railings, and other items above the wall cap or coping.

SPV.0165.01 (20230310)

2310-13-70, 2310-13-71 53 of 59

51. Wall Modular Block Gravity Landscape, Item SPV.0165.02.

A Description

This special provision describes designing, furnishing materials, and erecting a permanent earth retention system according to the lines, dimension, elevations, and details as shown on the plans and provided in the contract. The design life of the wall and all wall components shall be 75 years minimum.

B Materials

B.1 Proprietary Wall Systems

The supplied wall system must be from the department's approved list of Modular Block Gravity Landscape Wall systems. Proprietary wall systems must conform to the requirements of this specification and be pre-approved for use by the department's Bureau of Structures. The department maintains a list of pre-approved proprietary wall systems. The name of the pre-approved proprietary wall system selected shall be furnished to the engineer within 25 days after the award of contract. The location of the plant manufacturing the facing units shall be furnished to the engineer at least 14 days prior to the project delivery.

To be eligible for use on this project, a system must have been pre-approved by the Bureau of Structures and added to that list prior to the bid closing date. To receive pre-approval, the retaining wall system must comply with all pertinent requirements of this provision and be prepared according to the requirements of Chapter 14 of the department's LRFD Bridge Manual. Information and assistance with the pre-approval process can be obtained by contacting the Bureau of Structures, Structures Maintenance Section at the following email address: DOTDLStructuresFabrication@dot.wi.gov.

B.2 Design Requirements

It is the responsibility of the contractor to submit a design and supporting documentation as required by this special provision, for review and acceptance by the department, to show the proposed wall design is in compliance with the design specifications. The submittal shall include the following items for review: detailed plans and shop drawings, complete design calculations, explanatory notes, supporting materials, and specifications. The detailed plans and shop drawings shall include all details, dimensions, quantities, and cross-sections necessary to construct the walls. Submit electronically to the engineer and Bureau of Structures for review and acceptance. Submit no later than 60 days from the date of notification to proceed with the project and a minimum of 30 days prior to the date proposed to begin wall construction.

The plans and shop drawings shall be prepared on reproducible sheets 11-inch x 17-inch, including borders. Each sheet shall have a title block in the lower right corner. The title block shall include the WisDOT project identification number and structure number. Design calculations and notes shall be on 8½ inch x 11-inch sheets, and shall contain the project identification number, name or designation of the wall, date of preparation, initials of designer and checker, and page number at the top of the page. All plans, shop drawings, and calculations shall be signed, sealed, and dated by a professional engineer licensed in the State of Wisconsin.

The design of the wall shall be in compliance with the current American Association of State Highway and Transportation Officials LRFD (AASHTO LRFD) Bridge Design Specifications with latest interim specifications for Mechanically Stabilized Earth Walls, WisDOT's current Standard Specifications for Highway and Structure Construction (standard spec), Chapter 14 of the WisDOT LRFD Bridge Manual and standard engineering design procedures as determined by the department. Loads, load combinations, load and resistance factors shall be as specified in AASHTO LRFD Section 11. The associated resistance factors shall be defined according to Table 11.5.7-1 in AASHTO LRFD.

Design and construct the walls according to the lines, grades, heights, and dimensions shown on the plans, as herein specified, and as directed by the engineer.

Walls shall be designed for a minimum live load surcharge of 100 psf according to Chapter 14 of the WisDOT LRFD Bridge Manual or as shown on the plans.

A maximum value of the angle of internal friction of the wall backfill material used for design shall be assumed to be 30 degrees without a certified report of tests. If a certified report of tests yields an angle of internal friction greater than 30 degrees, the larger test value may be used for design, up to a maximum value of 36 degrees.

An external stability check at critical wall stations showing Capacity Demand Ratio (CDR) for sliding, eccentricity, and bearing checks is provided by the department and are provided on the wall plans.

2310-13-70, 2310-13-71 54 of 59

The design of the wall by the contractor shall consider the internal and compound stability of the wall mass according to AASHTO LRFD 11.10.6. Internal stability shall also be considered at each block level. Calculations for factored stresses and resistances shall be based upon assumed conditions at the end of the design life. The width of the modular block from front face to back face of the wall shall be included in the design computations and shown on the wall shop drawings. Compound stability shall be computed for the applicable strength limits. Sample analyses and hand calculations shall be submitted to verify the output of any software program used. The design calculations and notes shall clearly indicate the Capacity to Demand Ratios (CDR) for all internal and external stabilities as defined in AASHTO LRFD.

Wall facing units shall be designed according to AASHTO LRFD 11.10.2.3.

The minimum embedment of the wall shall be 1 foot 6 inches below finished grade, or as given on the plans. All walls shall be provided with a concrete or base aggregate leveling pad. Minimum wall embedment does not include the leveling pad depth. Step the leveling pad to follow the general slope of the ground line. Frost depth shall not be considered in designing the wall for depth of leveling pad.

Wall facing units shall be installed on a concrete leveling pad or base aggregate leveling pad. The bottom row of blocks shall be horizontal and 100% of the block surface shall bear on the leveling pad.

Concrete leveling pads shall be as wide as the proposed blocks plus 6 inches, with 6 inches of the leveling pad extending beyond the front face of the blocks. The minimum thickness of the leveling pad shall be 6-inches.

Base aggregate leveling pads shall be as wide as the blocks plus 12 inches, and the modular blocks shall be centered on the leveling pad. The minimum thickness of the leveling pad shall be 12-inches after compaction. The leveling pad shall be made from base aggregate dense 1 1/4-inch in conformance with standard spec 305.

B.3 Wall System Components

Materials furnished for wall system components under this contract shall conform to the requirements of this specification. All documentation related to material and components of the wall systems specified in this subsection shall be submitted to the engineer.

B.3.1 Wall Facing

Wall facing units shall consist of precast modular concrete blocks. Furnish concrete produced by a dry-cast or wet-cast process. Concrete for all blocks shall not contain less than 565 pounds of cementitious materials per cubic yard. The contractor may use cement conforming to standard spec 501.2.1 or may substitute for portland cement at the time of batching conforming to standard spec 501.2.6 for fly, for slag, or 501.2.8 for other pozzolans. In either case the maximum total supplementary cementitious content is limited to 30% of the total cementitious content by weight.

Dry-cast concrete blocks shall be manufactured according to ASTM C1372 and this specification.

All units shall incorporate a mechanism or devices that develop a mechanical connection between vertical block layers. Units that are broken, have cracks wider than 0.02" and longer than 25% of the nominal height of the unit, chips larger than 1", have excessive efflorescence, or are otherwise deemed unacceptable by the engineer, shall not be used within the wall. A single block type and style shall be used throughout each wall. The color and surface texture of the block shall be as given on the plan.

The top course of facing units shall be as noted on the plans, either.

- Solid precast concrete unit designed to be compatible with the remainder of the wall. The finishing course shall be bonded to the underlying facing units with a durable, highstrength, flexible adhesive compound compatible with the block material.
- A formed cast-in-place concrete cap. A cap of this type shall have texture, color, and appearance, as noted on the plans. The vertical dimension of the cap shall not be less than 3 1/2 inches. Expansion joints shall be placed in the cap at a maximum spacing of 20 feet unless noted otherwise on the plan. Use Grade A, A-FA, A-S, A-T, A-IS, A-IP or A-IT concrete conforming to standard spec 501 as modified in standard spec 716. Provide QMP for cast in place cap and coping concrete as specified in standard spec 716. Class II Concrete.

Block dimensions may vary no more than ±1/8 inch from the standard values published by the manufacturer. Blocks must have a minimum depth (front face to back face) of 8 inches. The minimum front face thickness of blocks shall be 4 inches measured perpendicular from the front face to inside voids greater than 4 square inches. The minimum allowed thickness of any other portions of the block is 1¾ inches. The front face of the blocks shall conform to plan requirements for color, texture, or patterns.

2310-13-70, 2310-13-71 55 of 59

If pins are used to align modular block facing units, they shall consist of a non-degrading polymer, or hot dipping galvanized steel and be made for the express use with the modular block units supplied, to develop mechanical interlock between facing unit block layers. Connecting pins shall be capable of holding the wall in the proper position during backfilling. Furnish documentation that establishes and substantiates the design life of such devices.

For concrete leveling pad, use Grade A, A-FA, A-S, A-T, A-IS, A-IP, or A-IT concrete conforming to standard spec 501 as modified in standard spec 716. Provide QMP for leveling pad concrete as specified in standard spec 716, Class III Concrete.

For base aggregate leveling pad conform to item 305.0120 Base Aggregate Dense 1 1/4-Inch.

B.3.2 Material Testing

Provide independent quality verification testing of project materials according to the following requirements:

Tool	Made a d	Requirement		
Test	Method	Dry cast	Wet cast	
Compressive Strength (psi)	ASTM C140	5000 min.	4000 min.	
Air Content (%)	AASHTO T152	N/A	6.0 +/-1.5	
Water Absorption (%)	ASTM C140	6 max. [3]	N/A	
Freeze-Thaw Loss (%) 40 cycles, 5 of 5 samples 50 cycles, 4 of 5 samples	ASTM C1262 ^[1]	1.0 max. ^{[2][3]} 1.5 max. ^{[2][3]}	N/A	

- [1] Test shall be run using a 3% saline solution and blocks greater than 45 days old.
- [2] Test results that meet either of the listed requirements for Freeze-Thaw Loss are acceptable.
- The independent testing laboratory shall control and conduct all sampling and testing. Prior to sampling, the manufacturer's representative shall identify materials by lot. Five blocks per lot shall be randomly selected for testing. Solid blocks used as a finishing or top course shall not be selected. The selected blocks shall remain under the control of the person who conducted the sampling until shipped or delivered to the testing laboratory. All pallets of blocks within a lot shall be strapped or wrapped to secure the contents and tagged or marked for identification. The engineer will reject any pallet of blocks delivered to the project without intact security measures. At no expense to the department, the contractor shall remove all rejected blocks from the project. If a random sample of five blocks of any lot tested by the department fails to meet any of the above testing requirements, the entire lot will be considered non-conforming.

The contractor and fabricator shall coordinate with the independent testing agency to ensure that strength and air content samples can be taken appropriately during manufacturing. At the time of delivery of materials, furnish the engineer a certified report of test from an AASHTO-registered or ASTM- accredited independent testing laboratory for each lot.

The certified test report shall include the following:

- Project ID
- Production process used (dry-cast or wet-cast)
- Name and location of testing facility
- · Name of sampling technician
- Lot number and lot size

Testing of project materials shall be completed not more than 18 months prior to delivery. Independent testing frequency shall not exceed 5000 blocks for dry-cast blocks and the lesser of 150 CY or 1 day's production for wet-cast blocks. The certified test results will represent all blocks within the lot. Each pallet of blocks delivered shall bear lot identification information. Block lots that do not meet the requirements of

2310-13-70, 2310-13-71 56 of 59

this specification or blocks without supporting certified test reports will be rejected and shall be removed from the project at no expense to the department.

Nonconforming materials will be subject to evaluation according to standard spec 106.5.

B.3.3 Backfill

Furnish and place backfill for the wall as shown on the plans and as hereinafter provided.

Wall Backfill, Type A, shall comply with the requirements for Coarse Aggregate Size No. 1 as given in standard spec 501.2.5.4. All backfill placed within a zone from the top of the leveling pad to the top of the final layer of wall facing units and within 1 foot behind the back face of the wall shall be Wall Backfill, Type A. This includes all material used to fill openings in the wall facing units.

A layer of Geotextile Type "DF" (Schedule B) shall be placed vertically between the backfill and the Type A backfill. The geotextile shall extend from the top of the leveling pad to 6 inches below the surface of the retained soil. The geotextile shall then wrap across the top of the Type A backfill to the back of block wall facing.

Backfill placed between retained soil and Type A backfill shall comply with the requirements for Granular Backfill Grade 1 as contained in standard spec 209.2.2. The contractor may substitute Type A Backfill for Granular Backfill Grade 1.

C Construction

C.1 Excavation and Backfill

Excavation and preparation of the foundation for the wall and the leveling pad shall be according to standard spec 206. At the end of each working day, provide good temporary drainage such that the backfill shall not become contaminated with run-off soil or water if it should rain. Do not stockpile or store materials or large equipment within 10 feet of the back of the wall.

Place backfill materials in the areas as indicated on the plans and as detailed in this specification. Backfill lifts shall be no more than 8-inches in depth, after compaction. Backfilling shall closely follow erection of each course of wall facing units.

Conduct backfilling operations in such a manner as to prevent damage or misalignment of the wall facing units or other wall components. At no expense to the department, correct any such damage or misalignment as directed by the engineer. A field representative of the wall supplier shall be available during wall construction to provide technical assistance to the contractor and the engineer.

Do not operate tracked or wheeled equipment on the backfill within 3 feet from the back face of modular blocks. The engineer may order the removal of any large or heavy equipment that may cause damage or misalignment of the wall facing units.

C.2 Compaction

Compact walls backfill Type A with at least three passes of lightweight manually operated compaction equipment acceptable to the engineer.

Ensure adequate moisture is present in the backfill during placement and compaction to prevent segregation and to help achieve compaction.

Compaction of backfill within 3 feet of the back face of the wall should be accomplished using lightweight compaction devices. Use of heavy compaction equipment or vehicles should be avoided within 3 feet of the modular blocks.

C.3 Wall Components

Erect wall facing units and other associated elements according to the wall manufacturer's construction guide and to the lines, elevations, batter, and tolerances as shown on the plans. Center the initial layer of facing units on the leveling pad; then level them and properly align them. Fill formed voids or openings in the facing units with wall backfill, Type A. Remove all debris on the top of each layer of facing units, before placing the next layer of facing units.

Install all pins, rods, clips, or other devices used to develop mechanical interlock between facing unit layers according to the manufacturer's directions.

2310-13-70, 2310-13-71 57 of 59

C.4 Geotechnical Information

Geotechnical data to be used in the design of the wall is to be provided and determined by the contractor. This information shall be provided to the department and engineer for approval prior to completion of the wall design.

D Measurement

The department will measure Wall Modular Block Gravity Landscape by the square foot, acceptably completed, measured at the front face of wall as defined by the pay limits the contract plans show. Unless the engineer directs in writing, a change to the limits indicated on the contract plan, wall area constructed above or below these limits will not be measured for payment.

E Payment

The department will pay for accepted measured quantities at the contract unit price under the following bid item:

ITEM NUMBERDESCRIPTIONUNITSPV.0165.02Wall Modular Block Gravity LandscapeSF

Payment is full compensation for supplying a design and shop drawings; preparing the site, including all necessary excavation and disposal of materials; supplying all necessary wall components to produce a functional wall system including cap, copings, and leveling pad; constructing the retaining system including drainage system; providing backfill, backfilling, compacting, and performing compaction testing.

Payment limit for all walls is the line of minimum embedment per section B.2. No payment will be made for additional embedment detailed for construction purposes.

Parapets, railings, and other items above the wall cap or coping will be paid for separately. Vehicle barrier and its support will be paid separately.

Any required topsoil, fertilizer, seeding or sodding and mulch will be paid for at the contract unit price for those items.

52. Asphalt Repair, Item SPV.0195.01.

A Description

This special provision describes repairing areas of existing asphalt pavement with asphaltic mixtures for overlaying with new pavement.

B Material

Furnish nominal size No. 3 (19mm) aggregate blend graded as specified in standard spec 460.2.2.3 and conform to the other material and mixture requirements specified for asphaltic surface in standard spec 465. Use tack coat as required under standard spec 450.3.2.7.

C Construction

- (1) Remove areas of existing asphalt pavement, including existing patching or surfacing materials, at locations the plans show, or the engineer directs in the field as specified for removing asphaltic surface milling in standard spec 204.3.2.2.2. Mill the connecting edges as true and perpendicular as possible, both parallel and perpendicular to the roadway, creating a vertical edge on all sides. Remove the pavement without injury to the remaining pavement. Dispose of removed material as specified in standard spec 204.3.1.3.
- (2) As an option for areas of full depth removal, the contractor may remove areas of existing asphalt pavement, including existing patching or surfacing materials, as specified for removing asphaltic surface in 204.3.2.2.1. Saw cut the connecting edges as true and perpendicular as possible, as specified for sawing pavement in 690. Remove the pavement without injury to the remaining pavement. Dispose of removed material as specified in standard spec 204.3.1.3.
- (3) Construct as specified for asphaltic surface under 465.3 except as modified here.

2310-13-70, 2310-13-71 58 of 59

Replace standard spec 465.3.1(2) with the following:

(2) Place using self-propelled pavers. Pave at a constant speed, appropriate for the paver and mixture, that ensures uniform spreading and strike-off with a smooth, dense texture and no tearing or segregation.

Replace standard spec 465.3.1(3) with the following:

(3) Immediately after placement, compact the mixture to produce a dense smooth surface using ordinary compaction procedures as specified in standard spec 450.3.2.6. Unless the engineer directs otherwise, compact each layer to a thickness of 6 inches or less so that the finished surface is 1/16 inch to 1/8 inch above the existing pavement surface.

D Measurement

The department will measure Asphalt Repair by the ton, acceptably completed, as specified for asphaltic pavement in standard spec 450.4.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBERDESCRIPTIONUNITSPV.0195.01Asphalt RepairTON

Payment is full compensation for removing old pavement; for preparing the foundation; and for providing and compacting asphaltic mixture including asphaltic binder. Sawing existing asphalt pavement as a contractor option is incidental to the Asphaltic Repair bid item.

The department will pay separately for tack coat under the Tack Coat bid item as specified in standard spec 455.5.

SER-390-001 (20220408)

2310-13-70, 2310-13-71 59 of 59

ADDITIONAL SPECIAL PROVISION 1 (ASP 1) FOR TRANSPORTATION ALLIANCE FOR NEW SOLUTIONS (TrANS) PROGRAM EMPLOYMENT PLACEMENTS AND APPRENTICESHIPS

The Safe, Accountable, Flexible, Efficient Transportation Equity Act: A Legacy for Users (SAFETEA-LU), Section 5204(e) – Surface Transportation Workforce Development Training and Education, provides for 100 percent Federal funding if the core program funds are used for training, education, or workforce development purposes, including "pipeline" activities. The core programs includes: Congestion Mitigation and Air Quality Improvement (CMAQ) Program, Highway Bridge Program (HBP), Interstate Maintenance (IM), National Highway System (NHS), and Surface Transportation Program (STP). These workforce development activities cover surface transportation workers, including OJT/SS programs for women and minorities as authorized in 23 U.S.C. §140(b).

TrANS is an employment program originally established in 1995 in Southeastern Wisconsin. Currently TrANS has expanded to include TrANS program locations to serve contractors in Southeast (Milwaukee and surrounding counties), Southcentral (Dane County and surrounding counties including Rock County), and most Northeastern Wisconsin counties from locations in Keshena, Rhinelander and surrounding far Northern areas. TrANS attempts to meet contractor's needs in other geographic locations as possible. It is an industry driven plan of services to address the outreach, preparation, placement and retention of women, minorities and non-minorities as laborers and apprentices in the highway skilled trades. These candidate preparation and contractor coordination services are provided by community based organizations. For a list of the TrANS Coordinators contact the Disadvantaged Business Enterprise Office at (414) 438-4583 in Milwaukee or (608) 266-6961 in Madison. These services are provided to you at no cost.

I. BASIC CONCEPTS

contract.

Training reimbursements to employing contractors for new placements, rehires or promotions to apprentice of TrANS Program graduates will be made as follows:

1)	On-the-Job Training, Item ASP.1T0G, ASP 1 Graduate. At the rate of \$5.00 per hour
	on federal aid projects when TrANS graduates are initially hired, or seasonally rehired, as unskilled laborers or the equivalent.
	<u>Eligibility and Duration:</u> To the employing contractor, for up to 2000 hours from the point of initial hire as a TrANS program placement.
	Contract Goal: To maintain the intent of the Equal Employment Opportunity

program, it is a goal that ____2 ___ (number) TrANS Graduate(s) be utilized on this

On-the-Job Training, Item ASP.1T0A, ASP 1 Apprentice. At the rate of \$5.00 per hour on federal aid projects at the point when an employee who came out of the TrANS Program is subsequently entered into an apprenticeship contract in an underutilized skilled trade (this will include the Skilled Laborer Apprenticeship when that standard is implemented).

<u>Eligibility and Duration:</u> To the employing contractor, for the length of time the TrANS graduate is in apprentice status.

<u>Contract Goal:</u> To maintain the intent of the Equal Employment Opportunity program, it is a goal that ___3__ (number) TrANS Apprentice(s) be utilized on this contract.

3) The maximum duration of reimbursement is two years as a TrANS graduate plus time in apprentice status.

- If a TrANS program is not available in the contractor's area and another training program is utilized, payment of On-the-Job Training hours may be approved by the Wisconsin Department of Transportation (WisDOT) if the training program meets the established acceptance criteria. Only On-the-Job Training Hours accumulated after WisDOT approval will be reimbursed as specified under Items ASP.1T0G and ASP.1T0A. For more information, contact the Disadvantaged Business Enterprise Office at the phone numbers listed above.
- 5) WisDOT reserves the right to deny payments under items ASP.1T0G and ASP.1T0A if the contractor either fails to provide training or there is evidence of a lack of good faith in meeting the requirements of this training special provision.

II. RATIONALE AND SPECIAL NOTE

The \$5.00 per hour now being paid for TrANS placements is intended to cover the duration of two years to allow for reaching entry-level laborer status. An additional incentive, the \$5.00 rate, would promote movement into the underutilized skilled trades' apprenticeships and applies until the individual completes their apprenticeship. These incentives benefit TrANS candidates by giving them a better opportunity to enter a skilled trade; benefits contractors who will be assisted in meeting their EEO profiles and goals; and benefits the public who will see the program reinforce larger public-private employment reform in Wisconsin. The pool of TrANS graduates was created for the purpose of addressing underutilization in the skilled trades, an objective that is further reinforced by a parallel retention pilot program, known as the Companywide Reporting. Whether or not reimbursement is involved, the WisDOT reassures contractors who are in the Companywide Program that TrANS placements still contribute toward fulfilling the new hire goal of 50% women and minorities. Based on data administered by United States Department of Labor (US DOL), the highway skilled trades remain underutilized for women statewide (less than 6.9%); and for minorities in all counties (% varies by county).

<u>NOTE</u>: Unless using other advancement strategies, contractors are encouraged to use some or all of this monetary incentive to offset the cut in hourly wages an individual may incur when entering an apprenticeship if the full general laborer hourly rate has been previously paid. No special accounting measures are required.

III. IMPLEMENTATION

The implementation of ASP 1 is intended to cover only the amount of time it takes for underutilization to be resolved across the trades. This will be measured annually at the county and/or state levels using data administered by WisDWD in relation to goals set by the USDOL-OFCCP. With appropriate state and federal approvals, we may also do some measurement at the company level.

It is the contractor's responsibility to note on their Certified Payrolls if their employee is a TrANS graduate or a TrANS apprentice. The District EEO Coordinators utilize the information on the Certified Payrolls to track the hours accumulated by TrANS Graduates and TrANS apprentices on WisDOT contracts. Payment under this ASP 1 is made based on the hours recorded off of the Certified Payrolls. Tracking may eventually include improved linkages with the WisDWD apprentice database, information from company and committee level sources.

TrANS is nondiscriminatory by regulation, and is a tool for optional use by contractors to address the underutilization of women and minorities as laborers and apprentices in our industry's skilled trades.

IV. TRANS TRAINING

As part of the contractor's equal employment opportunity affirmative action program, training shall be provided to employees enrolled in apprenticeship and on-the-job training programs as follows:

The contractor shall provide on-the-job training aimed at developing full journey workers in the type of trade or job classifications involved. In the event the contractor subcontracts a portion of the contract work, the contractor shall determine how many, if any, of the trainees are to be trained by the subcontractor provided, however, that the contractor shall retain the primary responsibility for meeting the training requirements imposed by this special provision. The contractor shall also insure that this training special provision is made applicable to such subcontract.

Training and upgrading of minorities and women toward journey workers status is a primary objective of this training special provision. Accordingly, the contractor shall make every effort to enroll minority trainees and women (e.g., by conducting systematic and direct recruitment through public and private sources likely to yield minority trainees and women trainees); to the extent such persons are available within a reasonable area of recruitment. The contractor will be given an opportunity and will be responsible for demonstrating the steps that they have taken in pursuance thereof, prior to determination as to whether the contractor is in compliance with this training special provision. This training commitment is not intended, and shall not be used, to discriminate against any applicant for training, whether a member of a minority group or not.

No employee shall be employed as a trainee in any classification in which they have successfully completed a training course leading to journey workers status or in which they have been employed as a journey worker. The contractor should satisfy this requirement by including appropriate questions in the employee application or by other suitable means. Regardless of the method used, the contractor's records should document the findings in each case.

V. APPRENTICESHIP TRAINING

The Federal Highway Administration's (FHWA) policy is to require full use of all available training and skill improvement opportunities to assure increased participation of minority groups,

disadvantaged persons and women in all phases of the highway construction industry. The FHWA On-the-Job Training (OJT) Program requires the State transportation agencies (STAs) to establish apprenticeships and training programs targeted to move women, minorities, and disadvantaged individuals into journey-level positions to ensure that a competent workforce is available to meet highway construction hiring needs, and to address the historical under-representation of members of these groups in highway construction skilled crafts.

The OJT Supportive Services (OJT/SS) Program was established in Title 23 Code of Federal

Regulations (CFR), Part 230) to supplement the OJT program and support STA training programs by providing services to highway construction contractors and assistance to highway construction apprentices and trainees. The primary objectives of OJT/SS are:

- (1) To increase the overall effectiveness of the State highway agencies' approved training programs.
- (2) To seek other ways to increase the training opportunities for women, minorities, and disadvantaged individuals.

The STAs are responsible for establishing procedures, subject to the availability of Surface Transportation and Bridge Funds under 23 U.S.C. §140(b) (Nondiscrimination), for the provision of supportive services with respect to training programs approved under 23 CFR, Part 230(a) (Equal Employment Opportunity on Federal and Federal-aid Construction Contracts – including Supportive Services).

The contractor and subcontractor shall maintain records to demonstrate compliance with these apprenticeship requirements. Reasonable exemptions and modifications to and from any or all of these requirements will be determined by the Wisconsin Department of Transportation-Civil Rights Office. A request for an exemption or modification, with justification, shall be made in writing, addressed to WisDOT Civil Rights Office, 4802 Sheboygan Avenue, P.O. Box 7965, Rm. 451, Madison, WI 53707.

ADDITIONAL SPECIAL PROVISION 3

DISADVANTAGED BUSINESS ENTERPRISE (DBE) PROGRAM IMPLEMENTATION

Authority

Wisconsin Department of Transportation (WisDOT) is a recipient of funds from the US Department of Transportation's Federal Highway Administration. The DBE program is a federal program applicable on all contracts administered by WisDOT that include federal-aid highway funds. The authority for the DBE program is the Transportation Bill as approved by Congress periodically. DBE program guidance and requirements are outlined in the Code of Federal Regulations at 49 CFR Part 26. This contract is subject to DBE provisions because it is financed with federal-aid-highway funds. Additionally, this contract is subject to the *State of Wisconsin Standard Specifications for Highway and Structure Construction* and all applicable contract documents.

Requirements

Pursuant to the federal DBE program regulation at 49 CFR Part 26, a contractor's failure to comply with any provision of the DBE program regulatory provisions will be considered a material breach of contract. This is nonnegotiable.

If a contractor fails to carry out the DBE program requirements and/or the Required Contract Provisions for Federal Aid Contracts (FHWA 1273) referenced in this document, sanctions will be assessed depending upon the facts, reasoning, severity, and remedial efforts of the contractor that may include: termination of contract, withholding payment, assessment of monetary sanctions, and/or suspension/debarment proceedings that could result in the disqualification of the contractor from bidding for a designated period of time.

- (1) The Commitment to Subcontract to DBE (Form DT1506 or digital submittal), Attachments A, and Good Faith Effort Documentation (Form DT1202) will be submitted as described in Section 2.
- (2) Any change to DBE Commitments thereafter must follow modification of DBE subcontracting commitment as described in Section 9.
- (3) The Department requires this list of DBE subcontractors from all bidders at time of bid to ensure the lowest possible cost to taxpayers and fairness to other bidders and subcontractors. Bid shopping is prohibited.
- (4) The contractor must utilize the specific DBE firms listed in the approved DBE Commitment to perform the work and/or supply the materials for which the DBE firm is listed unless the contractor obtains written consent in advance from WisDOT. The contractor will not be entitled to payment for any work or materials on the approved DBE Commitment that is not performed or supplied by the listed DBE without WisDOT's written consent.

Description

The Wisconsin Department of Transportation is committed to the compliant administration of the DBE Program. The DBE provisions work in tandem with FHWA 1273 and WisDOT's *Standard Specifications for Highway and Structure Construction* and *Construction and Materials Manual*. The WisDOT Secretary is signatory to assurances of department-wide compliance.

The Department assigns the contract DBE goal as a percentage of work items that could be performed by certified DBE firms on the contract. The assigned DBE goal is expressed on the bid proposal as a percentage applicable to the total contract bid amount.

(1) WisDOT identifies the assigned DBE goal in its contract advertisements and posts the contract DBE goal on the cover of the bidding proposal. The contractor can meet the assigned contract DBE goal by subcontracting work to a DBE firm or by procuring services or materials from a DBE firm.

- (2) Under the contract, the prime contractor should inform, advise, and develop participating DBE firms to be more knowledgeable contractors who are prepared to successfully complete their contractual agreement through the proactive provision of assistance in the following areas:
 - Produce accurate and complete quotes
 - Understand highway plans applicable to their work
 - Understand specifications and contract requirements applicable to their work
 - Understand contracting reporting requirements
- (3) The Department encourages contractors to assist DBE subcontractors more formally by participating in WisDOT's Business Development program as a mentor, coach, or resource. For comprehensive information on the Disadvantaged Business Enterprise Program, visit the Department's Civil Rights and Compliance Section website at: http://wisconsindot.gov/Pages/doing-bus/civil-rights/dbe/default.aspx

1. Definitions

Interpret these terms, used throughout this additional special provision, as follows:

- a. Assigned DBE Contract Goal: The percentage shown on the cover of the Highway Work Proposal that represents the feasible level of DBE participation for each contract. The goal is calculated using the Engineer's Estimate and DBE Interest Report. Goal assignment includes review of FHWA funds, analyzes bid items for subcontract opportunity and compatibility with DBE certified firm work codes. Additional factors considered include proximity, proportion, and regulations.
- b. **Bid Shopping:** In construction law, bid shopping is the practice of divulging a subcontractor's bid to another prospective contractor(s) before or after the award of a contract to secure a lower bid.
- c. **DBE:** Disadvantaged Business Enterprise A for-profit small business concern where socially and economically disadvantaged individuals own at least a 51% interest and control management and daily business operations.
- d. DBE Commitment: The DBE Commitment is identified in the Commitment to Subcontract to DBE (Form DT1506) and is expressed as the amount of DBE participation the prime contractor has secured. The DT1506, a contract document completed by the bidder, is required to be considered a responsive bidder on an FHWA-funded contract that has an assigned DBE goal. The prime contractor will have the option to submit the DT1506 digitally, as an entry with the bid in Bid Express, or as an attachment to the bid.
- e. **DBE Utilization:** The actual participation of a DBE subcontractor on a project. WisDOT verifies DBE utilization through review of the DBE Commitment, payments to subcontractors, and contract documentation. The Prime Contractor receives DBE credit for payments made to the DBE firms performing the work listed on the approved DBE Commitment, and those submitted after approved commitment with Attachment A.
- f. **Good Faith Effort:** Legal term describing a diligent and honest effort taken by a reasonable person under the same set of facts or circumstances. For DBE subcontracting, the bidder must show that it took all necessary and reasonable steps to achieve the assigned DBE goal by the scope, intensity, and appropriateness of effort that could reasonably be expected for a contractor to obtain sufficient DBE participation.
- g. **Manufacturer:** A firm that operates or maintains a factory or establishment that produces, on the premises, the materials, supplies, articles, or equipment required under the contract.
- h. **Reasonable Price:** Contractors are expected to assess reasonable price by analyzing the contract scope for DBE subcontract feasibility and comparing common line items in DBE and non-DBE subcontract quotes for the same work. Per federal regulation, reasonable price is not necessarily the lowest price.
- Supplier: A firm that owns, operates, or maintains a store, warehouse, or other establishment in which the
 materials, supplies, articles, or equipment required under the contract are bought, kept in stock, and regularly sold
 or leased to the public.
- j. **Tied quote:** Subcontractor quote that groups multiple bid/line items at a bundled/package price with a notation that the items within the quote will not be separated.

2. WisDOT DBE Program Compliance

a. Documentation Submittal

- The Commitment to Subcontract to DBE (Form DT1506 or digital submittal) must be submitted at the time
 of bid (Tuesday) by all prime contractors.
- Attachments A OR quotes from all DBEs included in the Commitment must be submitted at bid (Tuesday)
 OR
- Within one-hour following bid submittal by ALL prime contractors via eSubmit (Tuesday).
- If only DBE quotes were submitted, all remaining signed Attachments A must be submitted within 24-hours of bid closing via eSubmit (Wednesday).
- If the assigned DBE contract goal is not met, Documentation of Good Faith Effort (Form DT1202) and supporting documentation must be submitted within 24-hours of bid closing (Wednesday) via eSubmit.
 Instructions for eSubmit.

**Bidders have the option of submitting the DBE Commitment at the time of bid via direct entry through Bid Express OR with attachment of Form DT1506 (Commitment to Subcontract to DBE). The DBE Commitment entered with bid is the digital form of the DT1506. Separate submission of Form DT1506 is not required if the DBE Commitment is entered in Bid Express. Form DT1202, if applicable, is no longer required to be submitted at time of bid; submit DT1202 within the 24-hour supplemental time frame following bid closing.

The DBE Office will not certify Good Faith Effort and the Bureau of Project Development will consider the bid nonresponsive if the contractor fails to furnish the DBE Commitment (digitally entered into the bid OR Form DT1506 as an attachment), Attachments A, and Form DT1202 if applicable, as required. See sample forms in the Appendix.

b. Verification of DBE Commitment

The documentation related to DBE subcontract commitment submitted prior to contract award is evaluated as follows:

(1) DBE Goal Met

If the bidder indicates that the contract DBE goal is met, the Department will evaluate the DBE Commitment submitted with bid OR Form DT1506, and Attachments A to verify the actual DBE percentage calculation. If the DBE Commitment is verified, the contract is eligible for award with respect to the DBE Commitment.

(2) DBE Goal Not Met

- a) If the bidder indicates a bid percentage on the DBE Commitment that does not meet the assigned DBE contract goal, the bidder must request alternative evaluation of good faith effort through submission of Form DT1202 (Documentation of Good Faith Effort) within 24-hours of bid including narrative description. Supplementary documentation of good faith effort that supports the DT1202 submission is also due within 24-hours of bid submission and prior to bid posting. The Department will review the bidder's DBE Commitment and evaluate the bidder's good faith efforts submission.
- b) Following evaluation of the bidder's Good Faith Effort documentation the bidder will be notified that the Department intends to:
 - 1. Approve the request (adequate documentation of GFE has been submitted) no conditions placed on the contract with respect to the DBE Commitment;
 - 2. *Deny* the request (inadequate documentation of GFE has been submitted) the contract is viewed as non-responsive per Wisconsin Standard Specifications for Highway and Structure Construction and will not be executed.

c) If the Department denies the bidder's request, the contract is ineligible for award. The Department will provide a written explanation for denying the request to the bidder. The bidder may appeal the Department's denial (see Section 4).

Supplemental good faith effort documentation must be submitted through eSubmit.

3. Department's Criteria for Good Faith Effort Documentation

The Federal-aid Construction Contract Provision, referenced as FHWA-1273, explicitly states that the prime contractor shall be responsible for all work performed on the contract by piecework, station work, or subcontract.

The contractor shall take all necessary and reasonable steps to ensure nondiscrimination in the administration of the contract including assurances of equal employment opportunity laws, DBE regulations, and affirmative action. Compliance encompasses responsible and responsive action, documentation, and good faith effort.

Contractually, all contractors, subcontractors, and service providers on the contract are bound by FHWA 1273 and DBE program provisions. **Prime contractors should encourage subcontractors to utilize DBE firms whenever possible to contribute to the assigned DBE contract goal.**

Bidders are required to document good faith effort. Per 49 CFR Part 26.53, good faith effort is demonstrated in one of two ways. The bidder:

- (1) Documents that it has obtained enough DBE participation to meet the goal; OR
- (2) Documents that it made adequate good faith efforts to meet the goal, even though it did not succeed

Appendix A of 49 CFR Part 26 provides guidance concerning good faith efforts. WisDOT evaluates good faith effort on a contract basis just as each contract award is evaluated individually.

The efforts employed by the bidder should be those that WisDOT can reasonably expect a bidder to take to actively and aggressively obtain DBE participation sufficient to meet the DBE contract goal. The Department will only approve demonstration of good faith effort if the bidder documents the quality, quantity, and intensity of the variety of activities undertaken that are commensurate with expected efforts to meet the stated goal.

The Department, in conjunction with industry stakeholders, has developed the following guidance for contractor good faith effort activity. The guidance and the attached appendices provide a framework for the actions required by all parties in the processing and evaluation of bidder's total efforts to achieve the project specific DBE goal prior to the bid letting date.

a. Solicitation Guidance for Prime Contractors:

- (1) Document all efforts and decisions made toward achieving the DBE goal on the contract. The bidder should use WisDOT-approved DBE outreach tools, including the UCP DBE Directory and the Bid Express Small Business Network to foster DBE participation on all applicable contracts.
- (2) As needed, request assistance with DBE outreach and follow-up by contacting the Department's DBE Support Services Office by phone or email request at least 14 days prior to the bid letting date. Phone numbers are (414) 438-4584 and/or (608) 267-3849; Fax: (414) 438-5392; E-mail: DBE_Alert@dot.wi.gov
- (3) Participate in and document a substantive conversation with at least one DBE firm per Let, to discuss questions, concerns, and any other contract related matters that may be applicable to the DBE firm. Guidelines for this conversation are provided in Appendix A of ASP-3.
- (4) Request quotes by identifying potential items to subcontract and solicit. In their initial contacts, contractors are strongly encouraged to include a single page, detailed list of items for which they are accepting quotes, by project, within a letting. See attached sample entitled "Sample Contractor Solicitation Letter" in Appendix B. Prime contractors should also indicate a willingness to accept quotes in areas they are planning to perform themselves, as required by federal rules. In some cases, it might be appropriate to use DBE firms to do work in a prime contractor's area of specialization.

- i. Solicit quotes from certified DBE firms who match possible items to subcontract using all reasonable and available means. Additionally, forward copies of solicitations highlighting the work areas for which quotes are being sought to DBE Alert@dot.wi.gov
- ii. Acceptable outreach tools include SBN (Small Business Network, see Appendix C): https://www.bidx.com/wi/main, postal mail, email, fax, and phone.
 - a. Contractors must ask DBE firms for a response in their solicitations. See Sample Contractor Solicitation Letter, Appendix B. This letter may be included as an attachment to the sub-quote request.
 - b. Solicit quotes at least 10 calendar days prior to the letting date to allow DBE firms sufficient time to respond. Prime contractors should contact DBE firms early, asking if they need help organizing their quote, assistance confirming equipment needs, or other assistance supporting their submission of a competitive quote for their services.
 - c. A follow up solicitation should take place within 5 calendar days of the letting date. Email and/or SBN are the preferred method for the solicitation.
- iii. Upon request, provide interested DBE firms with adequate information about plans, specifications, and the requirements of the contract by letter, information session, email, phone call, and/or referral.
- iv. When potential exists, the contractor should advise interested DBE firms on how to obtain bonding, line of credit, or insurance if requested.
- v. Document DBE firm's interest in quoting by taking appropriate steps to follow up initial solicitation with:
 - a. Email to all prospective DBE firms in relevant work areas
 - b. Phone call log to DBE firms who express interest via written response or call
 - c. Fax/letter confirmation
 - d. Signed copy of record of subcontractor outreach effort

b. Guidance for Evaluating DBE quotes

- (1) Quote evaluation practices required to evaluate DBE quotes:
 - i. Reasonable Price: Contractors are expected to assess reasonable price by analyzing the contract scope for DBE subcontract feasibility and comparing common line items in DBE and non-DBE subcontract quotes for the same work. Per federal regulation, reasonable price is not necessarily the lowest price. See 49 CFR Part 26, Appendix A. IV.D(2).
- (2) Documentation submitted by the prime of the following evaluation is required to evaluate DBE quotes by contractors:
 - i. Evaluation of DBE firm's ability to perform "possible items to subcontract" using legitimate reasons, including but not limited to, a discussion between the prime and DBE firm regarding its capabilities prior to the bid letting. If lack of capacity is the reason for not utilizing the DBE firm's quote, the prime is required to contact the DBE by phone and email regarding their ability to perform the work indicated in the UCP directory listed as their work area by NAICS code. Only the work area indicated by the NAICS code(s) listed in the UCP directory can be counted toward DBE credit. Documentation of the conversation is required.
 - a In striving to meet an assigned DBE contract goal, contractors are expected to use DBE quotes that are responsive and reasonable. This includes DBE quotes that are not the low quote.
 - Additional evaluation Evaluation of DBE quotes with <u>tied bid items</u>. Typically, this type of quoting represents a cost saving but is not clearly stated as a discount. Tied quotes are usually presented as an 'all or none' quote. When non-DBE subcontractors submit tied bid items in their quotes, the DBE firm's quote may not appear competitive. In such a case, the following steps are taken in comparing the relevant quotes. These are qualitative examples:

- i Compare bid items common to both quotes, noting the reasonableness in the price comparison.
- Review quotes from other firms for the bid items not quoted by the DBE firm to see if combining both can provide the same competitive advantage that the tied bid items offered.

See Appendix D - Good Faith Effort Evaluation Measures and Appendix E - Good Faith Effort Best Practices.

- c. Requesting Good Faith Effort Evaluation At the time of bid- if the DBE goal is not met in full, the prime contractor must indicate they will file form DT1202- Documentation of Good Faith Effort within 24-hours of bid submission. Supplementary documentation of good faith effort that supports the DT1202 submission is also due within 24-hours of bid submission and prior to bid posting. Supporting documentation for the DT1202 is to include the following:
 - (1) Solicitation Documentation: The names, addresses, email addresses, and telephone numbers of DBE firms contacted along with the dates of both initial and follow-up contact; electronic copies of all written solicitations to DBE firms. A printed copy of SBN solicitation is acceptable.
 - (2) Selected Work Items Documentation: Identify economically feasible work units to be performed by DBEs to include activities such as: list of work items to be performed; breaking up of large work items into smaller tasks or quantities; flexible time frames for performance and delivery schedules.
 - (3) Documentation of Project Information provided to interested DBEs: A description of information provided to the DBE firms regarding the plans, specifications, and estimated quantities for portions of the work to be performed by that DBE firm.
 - (4) Documentation of Negotiation with Interested DBEs: Provide sufficient evidence to demonstrate that good faith negotiations took place. Merely sending out solicitations requesting bids from DBEs does not constitute sufficient good faith efforts.
 - (5) Documentation of Sound Reasoning for Rejecting DBEs and copies of each quote received from a DBE firm and, if rejected, copies of quotes from non-DBEs for same items.
 - (6) Documentation of Assistance to Interested DBEs- Bonding, Credit, Insurance, Equipment, Supplies/Materials
 - (7) Documentation of outreach to Minority, Women, and Community Organizations and other DBE Business Development Support: Contact organizations and agencies for assistance in contacting, recruiting, and providing support to DBE subcontractors, suppliers, manufacturers, and truckers at least 14 days before bid opening. Participate in or host activities such as networking events, mentor-protégé programs, small business development workshops, and others consistent with DBE support.

If the Good Faith Effort documentation is deemed adequate, the request will be approved and the DBE office will promptly notify the Prime Contractor and Bureau of Project Development.

If the DBE Office denies the request, the Prime Contractor will receive written correspondence outlining the reasons. The Department encourages the Prime Contractor to communicate with DBE staff to clarify any questions related to meeting goals and/or contractor demonstration of good faith efforts.

If the contract is awarded, the Prime Contractor must obtain written consent from the DBE Office to change or replace any DBE firm listed on the approved DBE Commitment. No contractor, prime or subsequent tier, shall be paid for completing work assigned to a DBE subcontractor on an approved DBE Commitment <u>unless</u> WisDOT has granted permission for the reduction, replacement, or termination of the assigned DBE in writing. If a prime contractor or a subcontractor on any tier uses its own forces to perform work assigned to a DBE on an approved DBE Commitment, **they will not be paid for the work**. Any changes to DBE Commitment after the approval of the DBE Commitment must be reviewed and approved by the DBE Office prior to the change (see Section 9).

Additional resources for demonstrating and tracking good faith effort can be found on the "Contracting with a DBE" webpage in the <u>ASP-3 and Good Faith Effort Guidance</u> section.

4. Bidder's Documentation of Good Faith Effort Evaluation Request Appeal Process

A bidder can appeal the Department's decision to deny the bidder's demonstration of Good Faith Effort through Administrative Reconsideration. The bidder must provide a written justification refuting the specific reasons for denial as stated in the Department's denial notice. The bidder may meet in person with the Department if so requested. Failure to appeal within 5 business days after receiving the Department's written notice denying the request constitutes a forfeiture of the bidder's right of appeal. Receipt of appeal is confirmed by email date stamp or certified mail signed by WisDOT staff. A contract will not be executed without documentation that the DBE provisions have been fulfilled.

The Department will appoint a representative who did not participate in the original good faith effort determination, to assess the bidder's appeal. The Department will issue a written decision within 5 business days after the bidder presents all written and oral information. In that written decision, the Department will explain the basis for finding that the bidder did or did not demonstrate an adequate good faith effort to meet the contract DBE goal. The Department's decision is final.

5. Determining DBE Eligibility

Directory of DBE firms

- a. The only resource for DBE firms certified in the State of Wisconsin is the Wisconsin Unified Certification Program (UCP) DBE Directory. WisDOT maintains a current list of certified DBE firms at: http://wisconsindot.gov/Documents/doing-bus/civil-rights/dbe/dbe-ucp-directory.xlsx
- b. The DBE Program office is available to assist with contracting DBE firms:(608) 267-3849.
- c. DBE firms are certified based on various factors including the federal standards from the Small Business Administration that assigns a North American Industrial Classification (NAICS) Codes. DBE firms are only eligible for credit when performing work in their assigned NAICS code(s). If a DBE subcontractor performs work that is not with its assigned NAICS code, the prime contractor should contact the DBE Office to inquire about compatibility with the Business Development Program.

6. Counting DBE Participation

Assessing DBE Work

The Department will only count the DBE usage towards the contract DBE goal if the DBE firm is certified as a DBE by one of the UCP agencies. The Department only counts the value of the work a DBE actually performs towards the DBE goal. The Department assesses the DBE work as follows:

- a. The Department counts work performed by the DBE firm's own resources. The Department includes the cost of materials and supplies the DBE firm obtains for the work. The Department also includes the cost of equipment the DBE firm leases for the work. The Department will not include the cost of materials, supplies, or equipment the DBE firm purchases or leases from the prime contractor or its affiliate, with the exception of non-project specific leases the DBE has in place before the work is advertised.
- b. The Department counts fees and commissions the DBE subcontractor charges for providing bona fide professional, technical, consultant, or managerial services. The Department also counts fees and commissions the DBE charges for providing bonds or insurance. The Department will only count costs the program engineer deems reasonable based on experience or prevailing market rates.
- c. If a DBE firm subcontracts work, the Department counts the value of the work subcontracted to a DBE subcontractor.
- **d.** The contractor will maintain records and may be required to furnish periodic reports documenting its performance under this item.
- e. It is the Prime Contractor's responsibility to determine whether the work that is committed and/or contracted to a DBE firm can be counted for DBE credit by referencing the work type and NAICS code listed for the DBE firm on the Wisconsin UCP DBE Directory.

- f. It is the Prime Contractor's responsibility to assess the DBE firm's ability to perform the work for which it is committing/contracting the DBE to do. Note that the Department encourages the Prime Contractor to assist and develop DBE firms to become fully knowledgeable contractors to successfully perform on its contracts.
- **g.** The Prime Contractor will inform the DBE office via email of all DBE subcontractors added to the project following execution of the contract. The Prime Contractor may omit submission of another form DT1506, but must submit signed Attachment A forms for additional DBE firms.
- **h.** See Section 7 for DBE credit evaluation for Trucking and Section 8 for DBE credit evaluation for Manufacturers, Suppliers, and Brokers

Naming conventions: When emailing files, please use the following language to identify your submission- "Project #, Proposal #, Let date, Business Name, Attachment A" Email: DBE Alert@dot.wi.gov

*Note: A sublet request is required for DBE work, regardless of subcontract tier, and also for reporting materials or supplies furnished by a DBE.

- Sublet Requests via form DT1925 or WS1925 are required for 1st Tier DBEs
- For all 2nd Tier and below notification of DBE sublet is indicated by the contractor entering them in CRCS

7. Credit Evaluation for Trucking

All bidders are expected to adhere to the Department's current trucking policy posted on the HCCl website at: http://wisconsindot.gov/Documents/doing-bus/civil-rights/dbe/trucking-utilization-policy.pdf

The prime contractor is responsible for ensuring that all subcontractors including trucking firms, receive Form FHWA 1273: https://www.fhwa.dot.gov/programadmin/contracts/1273/1273.pdf

See Section 8 for Broker credit.

8. Credit Evaluation for Manufacturers, Suppliers, Brokers

The Department will calculate the amount of DBE credit awarded to a prime using a DBE firm for the provisions of materials and supplies on a contract-by-contract basis. The Department will count the material and supplies that a DBE firm provides under the contract for DBE credit based on whether the DBE firm is a manufacturer, supplier, or broker. Generally, DBE credit is determined through evaluation of the DBE owner's role, responsibility, and contribution to the transaction. Maximum DBE credit is awarded when the DBE firm manufactures materials or supplies. DBE credit decreases when the DBE firm solely supplies materials, and minimal credit is allotted when the DBE firm's role is administrative or transactional. It is the bidder's responsibility to confirm that the DBE firm is considered a supplier or a manufacturer before listing them on Commitment to Subcontract to DBE form DT1506 or DBE Commitment submitted with the bid.

a. Manufacturers

- (1) A manufacturer is a firm that operates or maintains a factory or establishment that produces, on the premises, the materials, supplies, articles, or equipment required under the contract and of the general character described by the specifications.
- (2) If the materials or supplies are obtained from a DBE manufacturer, **100**% percent of the cost of the materials or supplies counts toward DBE goals.

b. Regular Dealers of Material and/or Supplies

(1) A regular dealer is a firm that owns, operates, or maintains a store, warehouse, or other establishment in which the materials, supplies, articles or equipment of the general character described by the specifications

- and required under the contract are bought, kept in stock, and regularly sold or leased to the public in the usual course of business.
- (2) If the materials or supplies are purchased from a DBE regular dealer, count **60%** percent of the cost of the materials or supplies toward DBE goals.
- (3) At a minimum, a regular dealer must meet the following criteria to be counted for DBE credit:
 - i. The DBE firm must be an established, regular business that engages, as its principal business and under its own name, in the purchase and sale or lease of the products in question.
 - ii. The DBE firm must both own and operate distribution equipment for the product--bulk items such as petroleum products, steel, cement, gravel, stone, or asphalt. If some of the distribution equipment is leased, the lease agreement must accompany the DBE Commitment form for evaluation of the dealer's control before the DBE office approves the DBE credit.
- (4) When DBE suppliers are contracted, additional documentation must accompany the DBE Commitment and Attachment A forms. An invoice or bill-of-sale that includes names of the bidder and the DBE supplier, along with documentation of the calculations used as the basis for the purchase agreement, subcontract, or invoice. WisDOT recognizes that the amount on the Attachment A form may be more or less than the amount on the invoice per b.(1) above.
 - i. The bidder should respond to the following questions and include with submission of form DT1506 or the DBE Commitment entered with bid:
 - a. What is the product or material?
 - b. Is this item in the prime's inventory or was the item purchased when contract was awarded?
 - c. Which contract line items were referenced to develop this quote?
 - d. What is the amount of material or product used on the project?
- (5) Supplies purchased in **bulk** from DBE firms at the beginning of the season may be credited to current contracts if submitted with appropriate documentation to the DBE office.
 - i. To ensure that the appropriate credit is assigned, follow the procedure below:
 - a. When DBE suppliers are contracted for bulk supply or commodity purchases, an invoice or bill-of-sale that includes names of the contractor and the DBE supplier should be submitted to the DBE Office via eSubmit (preferred during letting) or the DBE_Alert email box. The supply/commodity credit may be applied during the federal fiscal year (October- September) in which the purchase was made.
 - b. When the contractor intends to apply the credit to a particular project, submit a copy of the original invoice, documentation of the calculations for supplies/commodities to be used on the project, and an Attachment A. Indicate on the Attachment A:
 - c. This supply/commodity is in the prime's inventory or pre-paid in case of commodities
 - d. The full value of the original invoice submitted to the DBE Office, above in (1)
 - e. The amount of material or product used on this project
 - f. Fuel estimate listed on Attachment A will be recorded as a deduction from the full fuel purchase amount shown on the invoice
 - ii. DBE Office Process (Applies only to bulk purchases)
 - Supply/Commodity commitment is received
 - Engineer verifies amount listed on invoice and enters the full amount into spreadsheet
 - c. The amount of credit applied for each project is updated on the spreadsheet until the bulk purchase is exhausted
 - d. Engineer informs contractor when full amount of bulk purchase has been applied

c. Brokers, Transaction Expediters, Packagers, Manufacturers' Representatives

- (1) No portion of the cost of the materials, supplies, services themselves will count for DBE credit. However, WisDOT will evaluate the fees or commissions charged when a prime purchases materials, supplies, or services from a DBE certified firm which is neither a manufacturer nor a regular dealer, namely: brokers, packagers, manufacturers' representatives, or other persons who arrange or expedite transactions.
- (2) Brokerage fees are calculated as 10% of the purchase amount.
- (3) WisDOT may count the amount of fees or commissions charged for assistance in the procurement of the materials and supplies, fees, or transportation charges for the delivery of materials or supplies required on a job site.
- (4) Evaluation of DBE credit includes review of the contract need for the item/service, the sub-contract or invoice for the item/service, and a comparison of the fees customarily allowed for similar services to determine whether they are reasonable.

9. DBE Commitment Modification Policy (Formerly "DBE Replacement Policy")

a. Issuing a Contract Change Order

Any changes or modifications to the contract once executed are considered contract modifications and as such require a change order. In addition, the DBE office must provide consent for reduction, termination, or replacement of subcontractors approved on the DBE Commitment *in advance* of the modification for the prime contractor to receive payment for work or supplies. Additions to the DBE Commitment do not require advance notification of the DBE office. (see below e. DBE Utilization beyond the approved DBE Commitment)

b. Contractor Considerations

- (1) A prime contractor cannot modify the DBE Commitment through reduction in participation, termination, or replacement of a DBE subcontractor listed on the approved DBE Commitment without prior written consent from the DBE Office. This includes, but is not limited to, instances in which a prime contractor seeks to perform work originally designated for a DBE subcontractor with its own forces or those of an affiliate, a non-DBE firm, or with another DBE firm.
- (2) If a prime contractor reduces participation, replaces, or terminates a DBE subcontractor who has been approved for DBE credit toward its contract, the prime is required to provide documentation supporting its inability to fulfill the contractual commitment made to the Department regarding the DBE utilization.
- (3) The Prime Contractor is required to demonstrate efforts to find another DBE subcontractor to perform at least the same amount of work under the contract as the DBE subcontractor that was terminated, to the extent needed to meet the assigned DBE contract goal. When additional opportunity is available by contract modifications, the Prime Contractor must utilize DBE subcontractors that were committed to equal work items, in the original contract.
- (4) In circumstances when a DBE subcontractor fails to complete its work on the contract for any reason, or is terminated from a contract, the Prime Contractor must undertake efforts to maintain its commitment to the assigned DBE goal.
- (5) The DBE subcontractor should communicate with the Prime Contractor regarding its schedule and capacity in the context of the contract. If the DBE firm anticipates that it cannot fulfill its subcontract, they will advise the Prime Contractor and suggest a DBE subcontractor that may replace their services and provide written consent to be released from its subcontract.
 - i. Before the Prime Contractor can request modification to the approved DBE Commitment, the Prime Contractor must:
 - a. Make every effort to fulfill the DBE Commitment by working with the listed DBE subcontractor to ensure that the firm is fully knowledgeable of the Prime Contractor's expectations for successful performance on the contract. Document these efforts in writing.

- b. If those efforts fail, provide written notice to the DBE subcontractor of the Prime Contractor's intent to request to modify the Commitment through reduction in participation, termination, and/or replacement of the subcontractor including the reason(s) for pursuing this action.
- c. Copy the DBE Office on all correspondence related to changing a DBE subcontractor who has been approved for DBE credit on a contract, including preparation and coordination efforts.
- d. Clearly state the amount of time the DBE firm has to remedy and/or respond to the notice of intent to replace/terminate. The DBE must be allowed five days from the date notice was received as indicated by email time stamp or signed certified mail, to respond, in writing. EXCEPTION: The Prime Contractor must provide a verifiable reason for a response period shorter than five days. For example, a WisDOT project engineer or project manager confirms that WisDOT has eliminated an item the DBE subcontractor was contracted for.
- e. The DBE subcontractor must acknowledge the contract modification with written response to the Prime Contractor and the DBE Office. If objecting to the subcontract modification, the DBE subcontractor must outline the basis for objection to the proposed modification, providing sound reasoning for WisDOT to reject the prime's request.

c. Request to Modify DBE Subcontracting Commitment

The written request referenced above may be delivered by email or fax. The request must contain the following:

- (1) Project ID number
- (2) WisDOT Contract Project Engineer's name and contact information
- (3) DBE subcontractor name and work type and/or NAICS code
- (4) Contract's progress schedule
- (5) Reason(s) for requesting that the DBE subcontractor be replaced or terminated
- (6) Attach/include all communication with the DBE subcontractor to deploy/address/resolve work completion

Naming conventions: When emailing files, please use the following language to identify your submission- "Project #, Proposal #, Let date, Business Name, MODIFICATION" Email: DBE Alert@dot.wi.gov + Project Engineer

WisDOT will review the request and any supporting documentation submitted to evaluate if the circumstance and the reasons constitute good cause for replacing or terminating the approved DBE subcontractor.

Good Causes to Replace a DBE subcontractor according to the federal DBE program guidelines {49 CFR part 26.53}

- The listed DBE subcontractor fails or refuses to execute a written contract
- The listed DBE subcontractor fails or refuses to perform the work of its subcontract in a way consistent with normal industry standards. Provided, however, that good cause does not exist if the failure or refusal of the DBE subcontractor to perform its work on the subcontract results from the bad faith or discriminatory action of the prime contractor
- The listed DBE subcontractor fails or refuses to meet the prime contractor's reasonable, nondiscriminatory bond requirements
- The listed DBE subcontractor becomes bankrupt, insolvent, or exhibits credit unworthiness
- The listed DBE subcontractor is ineligible to work on public works projects because of suspension and debarment proceedings pursuant 2 CFR Parts 180, 215, and 1,200 or applicable state law
- The prime has determined that the listed DBE subcontractor is not a responsible contractor
- The listed DBE subcontractor voluntarily withdraws from the project and provides written notice of its withdrawal
- The listed DBE subcontractor is ineligible to receive DBE credit for the type of work required

• A DBE firm owner dies or becomes disabled with the result that the listed DBE subcontractor is unable to complete its work on the contract.

d. Evaluation and Response to the Request

WisDOT's timely response to the Prime Contractor's request for modification of the approved DBE Commitment will be provided to the prime and the WisDOT project engineer via email.

If WisDOT determines that the Prime Contractor's basis for reduction in participation, replacement, or termination of the DBE subcontractor is not consistent with the good cause guidelines, the DBE office will provide a response via email within 48-hours of receipt of request from the Prime Contractor as indicated by email time stamp. The communication will include: the requirement to utilize the committed DBE, actions to support the completion of the contractual commitment, a list of available WisDOT support services, and administrative remedies, including withholding payment to the prime, that may be invoked for failure to comply with federal DBE guidelines for DBE replacement.

The WisDOT contact for all actions related to modification of the approved DBE Commitment is the DBE Program Engineer who can be reached at DBE_Alert@dot.wi.gov or (414) 335-0413.

e. DBE Utilization beyond the approved DBE Commitment

When the prime or a subcontractor increases the scope of work for an approved DBE subcontractor or adds a DBE subcontractor who was not on the approved form DT1506 or DBE Commitment submitted with bid at any time after contract execution, this is referred to as voluntary DBE contract goal achievement. The contractor must follow these steps to ensure that the participation is accurately credited toward the DBE goal:

- (1) Forward a complete, signed Attachment A form to the DBE Office. A complete Attachment A includes DBE subcontractor contact information, signatures, subcontract value, and description of the work areas to be performed by the DBE. The DBE Office will verify the DBE participation and revise the DBE Commitment based on the email/discussion and the new Attachment A.
- (2) When adding to an existing DBE Commitment, submit a new Attachment A to the DBE Alert mailbox
- (3) OR Submit a final Attachment A to DBE Alert during the Finals Process when Compliance receives notice of "Substantially Complete"

Naming conventions: When emailing files, please use the following language to identify your submission-"Project #. Proposal #. Let date, Business Name, New Attachment A" Email: DBE Alert@dot.wi.gov

Special note on trucking

- DBE truckers added to the sublets in CRCS will be approved without DBE credit (You will see a "N" in CRCS instead of "Y")
- Prime Contractors may enter a "place holder" e.g. \$1000.00, for DBE Trucking in CRCS if the full amount of trucking is unknown for sublet purposes only
- The hiring contractor may obtain the Attachment A with DBE signature included but the **Prime Contractor** must sign the Attachment A before submitting
- DBE truckers need to be added to the DBE commitment once. If the DBE trucker is on the initial commitment (DT1506/E1506) there is no requirement to submit another Attachment A for that trucker for that contract.

10. Commercially Useful Function

- **a.** Commercially Useful Function (CUF) is evaluated after the contract has been executed, while the DBE certified firm is performing contracted work items.
- **b.** The Department uses Form DT1011, DBE Commercially Useful Function Review and Certification to evaluate if the DBE is performing a commercially useful function. WisDOT counts expenditures of a DBE toward the DBE goal only if the DBE is performing a commercially useful function on that contract.

- c. A DBE firm is performing a commercially useful function if the following conditions are met:
 - (1) For contract work, the DBE is responsible for executing a distinct portion of the work and is carrying out its responsibilities by actually performing, managing, and supervising that work.
 - (2) For materials and supplies, the DBE is responsible for negotiating price, determining quality and quantity, ordering, and paying for those materials and supplies.
- d. Offsite Hauling when DBE truck will haul between a pit and plant or location other than the construction site associated with the commitment
 - (1) Indicate Offsite Hauling on Attachment A
 - (2) Discuss offsite hauling at weekly progress meetings with Project Engineer (PE)
 - (3) PE conducts spot checks of pits/plants to verify DBE truck is hauling and/or verifying hauling log
 - (4) Prime should be prepared to submit haul tickets, plant/pit tickets, timecards, and other pertinent documentation if requested by PE or DBE Office

11. Credit Evaluation for DBE Primes

WisDOT calculates DBE credit based on the amount and type of work performed by DBE certified firms for work submitted with required documentation. If the prime contractor is a DBE certified firm, the Department will only count the work that the DBE prime performs with its own forces for DBE neutral credit. The Department will also calculate DBE credit for work performed by any other DBE certified subcontractor, DBE certified supplier, and DBE certified manufacturer on the contract in each firm's approved NAICS code/work areas that are submitted with required documentation. Crediting for manufacturers and suppliers is calculated consistent with Section 8 of this document and 49 CFR Part 26.

12. Joint Venture

A joint venture is an association of a DBE firm and one or more other firms to carry out a single, for-profit business enterprise, for which the parties combine their property, capital, efforts, skills and knowledge, and in which the DBE is responsible for a distinct, clearly defined portion of the work of the contract and whose share in the capital contribution, control, management, risks, and profits of the joint venture are commensurate with its ownership interest. If a DBE performs as a participant in a joint venture, the Department will only credit the portion of the total dollar value of the contract equal to the portion of the work that the DBE performs with its own forces.

13. Mentor-Protégé

- **a.** If a DBE performs as a participant in a mentor-protégé agreement, the Department will credit the portion of the work performed by the DBE protégé firm.
- **b.** DBE credit is evaluated and confirmed by the DBE Office for any contracts on which the mentor-protégé team identifies itself to the DBE Office as a current participant of the Mentor-Protégé Program.
 - (1) DBE credit may only be awarded to a non-DBE mentor firm for using its own protégé firm for less than one half of its goal on any contract; and
 - (2) Not award DBE credit to a non-DBE mentor firm for using its own protégé firm for more than every other contract performed by the protégé firm.
- **c.** A DBE protégé firm may be eligible for conditional NAICS code extension for training with the mentor. Request permission from the DBE Office- Certification area.
- **d.** Refer to WisDOT's Mentor-Protégé guidelines for guidance on the number of contracts and amount of DBE credit allowed on WisDOT projects.

14. Use of Joint Checks

The use of joint checks is allowable if it is a commonly recognized business practice in the material industry. A joint check is defined as a two-party check between a DBE subcontractor, a prime contractor, and the regular dealer or materials supplier who is neither the prime nor an affiliate of the prime. Typically, the prime contractor issues one check as payor to the DBE subcontractor and to the supplier jointly (to guarantee payment to the supplier) as payment for the material/supplies used by the DBE firm in cases where the DBE subcontractor and materials have been approved for DBE credit. The DBE subcontractor gains the opportunity to establish a direct contracting relationship with the supplier to potentially facilitate a business rapport that results in a line of credit or increased partnering opportunities.

The cost of material and supplies purchased by the DBE firm is part of the value of work performed by the DBE to be counted toward the goal. To receive credit, the DBE firm must be responsible for negotiating price, determining quality and quantity, ordering the materials, and installing (where applicable) and "paying for the material itself." See 49 CFR 26.55(c)(1).

The approval to use joint checks constitutes a commitment to provide further information to WisDOT, upon request by staff. WisDOT will allow the use of joint checks when the following conditions are met:

- **a.** The Prime Contractor must request permission to use joint checks from the DBE Office by submitting the Application to Use Joint Checks.
 - (1) Request should be made when the DBE Commitment or the Request to Sublet is submitted; the request will not be considered if submitted after the DBE Subcontractor starts its work.
 - (2) Approval/Permission must be granted prior to the issuance of any joint checks.
 - (3) The payment schedule for the supplier must be presented to the DBE office before the first check is issued.
 - (4) The joint check for supplies must be strictly for the cost of approved supplies.
- b. The DBE subcontractor is responsible for furnishing and/or installing the material/work item and is not an 'extra participant' in the transaction. The DBE firm's role in the transaction cannot be limited solely to signing the check(s) to release payment to the material supplier. At a minimum, the DBE subcontractor's tasks should include the following:
 - (1) The DBE subcontractor (not the prime/payor) negotiates the quantities, price, and delivery of materials.
 - (2) The DBE subcontractor consents to sign/release the check to the supplier by signing the <u>Application to Use</u> <u>Joint Checks</u> after establishing the conditions and documentation of payment within the subcontract terms or in a separate written document.
- c. The Prime contractor/payor acts solely as a guarantor.
 - (1) The Prime Contractor agrees to furnish the check used for the payment of materials/supplies under the contract.
 - (2) The prime contractor/payor cannot require the subcontractor to use a specific supplier or the prime contractor's negotiated unit price.

15. Payment

Costs for conforming to this Additional Special Provision (ASP) and any associated DBE requirements are incidental to the contract.

Appendix A Substantive Conversation Guidelines

The substantive conversation is critical to all bidders' demonstration of good faith effort to meet the DBE goal prior to bid opening. Relationship building between primes and subcontractors is crucial to DBE goal attainment. Responsible bidders seek to build rapport with potential DBE subcontractors to understand capacity, areas of expertise, and assess contracting feasibility. Bidders who compete for WisDOT contracts are specialty contractors responding to a growing and changing contract environment. Just as these specialists are responsible for care of the roads, they are likewise responsible for contributing to the health of the industry. The substantive conversation drives collaboration that will build industry health and capacity. The following is intended to provide guidance for such discussions but is not an exhaustive list. Contractors are encouraged to incorporate their existing strategies for cultivating business relationships as well.

Prior to Bid Opening- this discussion should happen as early as possible (WisDOT advertisements are released weeks prior to each Let)

- 1. Determine DBE subcontractor's interest in quoting
- 2. If response indicates inexperience with quoting- offer support/assistance to the DBE in understanding the industry including fundamentals a subcontractor needs to know, required reading and/or resources.
- 3. Assess their interest and experience in the road construction industry by asking questions such as:
 - Have you competed for other WisDOT contracts? Ratio of competed/to wins
 - Have you performed on any transportation industry contracts (locally or with other states)?
 - What the largest contract you've completed?
 - Have you worked in the industry: apprentice, journeyman, safety, inspection etc.?
 - Does this project fit into your schedule? Are you working on any contracts now?
 - Have you reviewed a copy of the plans? Are you comfortable performing within the scope and quantity considerations of this contract?
 - What region do you work in? Home base?
 - Which line items are you considering?
 - Have you read/are you familiar with WisDOT Standard Specifications? Construction Material Manual?
 - Do you understand where your work fits in the project schedule, project phases?

Following Bid Opening- this discussion can happen at any time

- 1. After reviewing their quote, note the following in your discussion:
 - Does the quote look complete? Irregular?
 - Are there errors in the quote? Are items very high or very low?
 - In general, does the quote look competitive?
- 2. Questions and Advice for the bidder to share with the potential DBE subcontractor:
 - What line items would typically be in a competitive quote for a subcontractor of their specialty?
 - How many employees and what is their role/experience/expertise in your firm?
 - Do you have resources for labor (union member, family-based, community-resourced) and capital (banking relationship, bond agent, CPA)?
 - Where have you worked: cities, states, government, commercial, residential/private sector, etc. Explain similarities or differences.
 - Refer them to reliable, trusted, industry resources that can educate or connect them to relevant resources, education/certification resources, more appropriate contract opportunities.
 - Discussion about prime contract and subcontract liability, critical path items, contract quantities, schedule risks, and potential profit/loss (for upcoming known projects or in general).
 - Discussion of bonding, insurance, and overall business risk considerations.

Appendix B

Sample Contractor Solicitation Letter Page 1 (This sample is provided as a guide, not a formatting requirement)

DBE Solicitation - [Month] [Day], [Year] WisDOT Bid Letting

- Attention all DBEs. [Prime Contractor] is actively seeking your quote for the [Month][Day], [Year] Bid Letting. [Prime Contractor] is considering bidding on the projects listed on page 2 as a prime contractor. Please see page 2 for instructions and the sub-contractable opportunities for each proposal.
- **Does [Prime Contractor] accept quotes in areas we might self-perform?** Yes, we do! We support this federal rule and (if needed) we consider areas we might self-perform an opportunity to provide in the field assistance and training if we award your quote.
- Where can DBEs find the plans, specifications & addenda? Please visit [Prime Contractor's] plan room [LINK] or on WisDOT's Highway Construction Contract Information HCCI website: Wisconsin Department of Transportation Highway Construction Contract Information (wisconsindot.gov). This same website can be checked for the contract status.
- What should your quote include? All the costs required to complete the items you propose to perform including labor, equipment, material, and related bonding or insurance. The quote should also note items that you are DBE certified to perform, tied items, and any special terms. Please use page 2 as your cover sheet for your quote.
- Do you have a question regarding bonding, credit, insurance, equipment, or supplies/materials? We welcome all DBE questions! Please call [Prime Contractor] and ask to speak with [Contact]. [Prime Contractor] can provide basic information as well as a referral to a trusted industry partner for insurance and bonding needs.

When are quotes due?

- [Month] [Day], [Year] at [Time]. We accept quotes via SBN, email, or fax. Please make every effort to have your quotes in by this time or earlier. Quality check your quote so it includes the correct letting date, project ID, proposal number, unit price and extension.
- Who can DBEs contact for questions, information, clarification or for a quote evaluation? [Project Manager Name] [Phone] [Email]. If you are quoting [Prime Contractor] for the first time, we encourage you to come meet with us in person to discuss the project. Our office hours are 7:30 a.m. 5:00 p.m. On bid day, we are in the office by 6:30 a.m.

Why partner with [Prime Contractor]?

DBE partnership is a core part of [Prime Contractor's] mission. Including DBEs at the beginning of each project is essential in the success of each project. We consider DBEs to be important industry partners who bring dedication and knowledge at various stages during construction. We are proud to be an industry leader with our DBE partnership. Your success as a DBE is our success.

Please check all that apply:

Signs/Posts/Markers

Survey/Staking

Yes, we will be quoting the projects & items listed below

Please take our name off your monthly DBE contact list

No, we are not interested in quoting on the letting or its items referenced below

Sample Contractor Solicitation Letter Page 2

(This sample is provided as a guide, not a formatting requirement)

REQUEST FOR QUOTE

[Prime Contractor] Letting Date: [Month] [Day], [Year] Project IDs: 1234-56-00 (Proposal #1) & 1234-01-78 (Proposal #6)

rime Contractor Contact:	DBE:	
none:		
mail:		
Please circle the proposals an	nd items you will be quoting below and	d contact us with any question
Proposal	1	6
County	Dane County	Crawford County
Clearing & Grubbing	X	X
Dump Truck Hauling	X	Х
Curb/Gutter/Sidewalk	X	
Erosion Control Items		Х
Excavation	X	Х
Pavement Marking		Х
Traffic Control	X	
Sawing	X	Х
QMP, Base		Х
Pipe Underdrain	X	
Landscape		Х
Beam Guard	X	
Electrical	X	

Again, please make every effort to have your quotes into our office by time deadline prior to the letting date.

X

X

Sample Contractor Solicitation Email - Simplified

(This sample is provided as a guide, not a formatting requirement)

ATTENTION DBEs

- [Prime Contractor] specializes in municipal projects in the XX Region(s)
- We have successfully competed for and completed XX WisDOT projects over the past XX years
- Consider [Prime Contractor] your partner on WisDOT Projects

[Prime Contractor] is seeking <u>your</u> subcontractor quote for the XX/XX/20XX WisDOT bid letting on the below projects:

Project	Proposal	County	Region
1234-56-00	2	Dane	SW
1234-01-78	6	Crawford	SW

- Please review the attachments [attach Solicitation Letter] and respond with your intent to quote (or not) along with the work items you are interested in performing and respond via fax or email by <u>date</u>. The quote should note items that you are DBE certified to perform, tied items, and any special terms. Please include labor, equipment, material, and related bonding or insurance.
- If you have any questions regarding bonding, credit, insurance, equipment and/or materials/supplies, please feel free to call [Prime Contractor] and ask for [Contact]. (Include if your company is willing to answer these types of DBE questions)
- o Plans and Specifications can be found: WisDOT HCCI Website: List webpage where plans are located
- If you do choose to quote, please make every effort to have your quote into our office by <u>time and date.</u>
 Make sure the correct letting date, project number, unit price and extension are included in your quote.
- Should you have questions regarding the mentioned project, please call our office at (414) 555-5555 and we will direct you to the correct estimator/project manager.
 Our office hours are 7:30 a.m. 5:00 p.m.

Thank you - we look forward to working with your company on this project!

Prime Contractor Project Manager

Direct: 414-555-555 Cell: 414-555-556

Sample Contractor Solicitation Email to non-DBE WisDOT Subcontractors -Simplified

(This sample is provided as a guide, not a formatting requirement)

ATTENTION WISDOT SUBCONTRACTORS

[Prime Contractor] is considering bidding on the below projects for the XX/XX/20XX WisDOT Bid Letting:

Project	Proposal	County	Region	DBE Goal
1234-56-00	2	Dodge	SW	6.00%
1234-01-78	11	Adams	NC	3.00%
1234-00-99	20	Buffalo	NW	5.00%
1234-00-98	33	Portage	NC	6.00%

The above projects have DBE goals and [Prime Contractor] is committed to DBE inclusion with every project. As such, we are requesting:

- All WisDOT Subcontractors to **solicit and utilize** DBEs in your quotes.
- DBE participation can be achieved through purchasing materials from DBE suppliers, using DBE subcontractors and/or DBE trucking firms or any combination of these.
- If there is an opportunity to untie an item in your quote so a DBE can be utilized, please look for those opportunities as well.
- Your quote will be evaluated based on the amount of DBE participation your company is able to provide when compared to other quotes for the same work.

If you do choose to quote, please make every effort to have your quote into our office by time and date. Please submit all quotes to [Email]. Make sure the correct letting date, project number, unit price and extension are included in your quote.

Should you have guestions regarding the mentioned project, the Project Manager contact is: [Name] [Phone Number] [Email]

Thank you for utilizing DBEs who are trusted industry partners with WisDOT projects.

Prime Contractor Project Manager Direct: 414-555-555 Cell: 414-555-556

Page 19 of 36

Appendix C Small Business Network (SBN) Overview

The Small Business Network is a part of the Bid Express® service that was created to ensure that prime bidders have a centralized online location to find subs - including small and disadvantaged business enterprises (DBEs). It is available for prime bidders to use as part of their Basic Service subscription. Within the Small Business Network, **Prime Contractors** can:

- 1. Easily select proposals, work types and items:
 - a. After adding applicable work types, select items that you wish to quote. Enter the sub-quote quantities and add comments, if desired. Adding or removing items and work types can be done quickly. If needed, you can save the sub-quote for later completion.
- 2. Create sub-quotes for the subcontracting community:
 - a. Create sub-quotes with ease using the intuitive sub-quote creator. In seven short steps, you can rapidly create a custom sub-quote directed to all subcontractors that bid on the applicable work types. Steps include: provide contact information and sub-quote expiration date, select letting and proposal, add work types and items, specify terms and conditions, upload attachments, and select vendors.
 - b. Create a sub-quote to send to subcontractors or suppliers that lists the items in a proposal that you want quoted
 - c. Create an unlimited number of sub-quotes for items you want quoted, and optionally mark them as a DBE preferred request.
 - d. Add attachments to sub-quotes.
- 3. View sub-quote requests & responses:
 - a. After logging into the Bid Express service, you can quickly review all of your sub-quote requests and all unsolicited sub-quote requests from subcontractors. To simplify the Small Business Network home screen, sub-quote requests can be hidden with one click if they are not applicable.
 - b. View or receive unsolicited sub-quotes that subcontractors have posted, complete with terms, conditions and pricing.
- 4. View Record of Subcontractor Outreach Effort:
 - a. For each sub-quote produced, a *Record of Subcontractor Outreach Effort* is generated that shows the response statistics for a particular sub-quote. If accepted by the letting agency, this report may serve as proof of a "Good Faith" effort in reaching out to the DBE community.
 - b. Easily locate pre-qualified and certified small and disadvantaged businesses.
 - c. Advertise to small and disadvantaged businesses more efficiently and cost effectively.
 - d. Document your interactions with subs/DBEs by producing an Outreach Report (may be accepted as proof of DBE outreach at the discretion of each agency).

The Small Business Network help small businesses learn more about opportunities, compete more effectively, network with other contractors and subcontractors, and win more jobs. The DBE will provide free SBN accounts to DBEs when requested. Use DBE_Alert@dot.wi.gov to request an account. **DBE firms can:**

- 1. View and reply to sub-quote requests from primes:
 - a. After logging into the Bid Express service, you can quickly review all incoming sub-quote requests and all unsolicited sub-quotes created by your company. Receive notifications by selected work type. To simplify on the Small Business Network home screen, sub-quote requests can be filtered by work types relevant to your interests or hidden with one click if they are not applicable.
- 2. Select items when responding to sub-quote requests from primes:
 - a. You have the freedom to choose and price any number of items when responding to a sub-quote request. Quantities can be modified, and per-item comments are also available.
 - b. View requests for sub-quotes for work that primes have posted for projects they are bidding, add your pricing, terms, and conditions, and submit completed sub-quotes to the requesting primes. c. Add attachments to a sub-quote.
- 3. Create and send unsolicited sub-quotes to specific contractors:
 - a. Create unsolicited sub-quotes with ease using the intuitive sub-quote creator. In eight short steps, you can rapidly create a custom sub-quote directed at any number of specific vendors of your choosing. Steps include: provide contact information and sub-quote expiration date, select letting and proposal, add work types and items, specify terms and conditions, upload attachments, and select vendors.
- 4. Easily select and price items for unsolicited sub-quotes:
 - a. After adding applicable work types, select items that you wish to quote. The extended price calculates automatically, cutting out costly calculation errors. Comments can be provided on a per-item basis as well.
 - b. Create an unsolicited sub-quote that lists the items from a proposal that you want to quote, include pricing, terms and conditions, and send it to selected prime/plan holder.
 - c. Add attachments to a sub-quote.
 - d. Add unsolicited work items to sub-quotes that you are responding to.
- 5. Easy Access to Valuable Information
 - a. Receive a confirmation that your sub-quote was opened by a prime.
 - b. View Bid Tab Analysis data from past bids, including the high, average and low prices of items.
 - c. View important notices and publications from DOT targeted to small and disadvantaged businesses.
- 6. Accessing Small Business Network for WisDOT contracting opportunities
 - a. If you are a contractor not yet subscribing to the Bid Express service, go to **www.bidx.com** and select "Order Bid Express." The Small Business Network is a part of the Bid Express Basic Service.

Appendix D

Good Faith Effort Evaluation Measures by categories referenced in DBE regulations

Bidders must demonstrate that they took all necessary and reasonable steps to achieve the assigned DBE contract goal. For each contract, all bidders must submit documentation indicating the goal has been met <u>or</u> if falling short of meeting the assigned goal, must request a DBE Goal Waiver and document all efforts employed to secure DBE subcontractor participation on Form DT1202.

DBE staff analyze the bidder's documented good faith efforts to determine if action taken was sufficient to meet the goal. Sufficiency is measured contract-by-contract. WisDOT evaluates active and aggressive efforts, quality, quantity, scope, intensity, and appropriateness of the bidder's efforts as a scale of the principles of Good Faith outlined in 49 CFR Part 26, Appendix A. Additional emphasis is placed on the bidder's demonstration of timely submission of documentation and communication with DBE subcontractors, and business development initiatives undertaken to support DBE firm growth.

The following is a sample of good faith effort activities that are rated according to the accompanying rubric. Contractors are encouraged to identify additional activities that align with their business type(s).

- Personal, tailored solicitation to firms that specialize in work types planned or desired for subcontracting
- Follow up to initial solicitation via email or phone
- Substantive conversation including topics such as contract liability, critical path work items, schedule risks, and potential profit/loss
- SBN utilization including posting quotes
- Review and response to DBE quotes including provision of information about plans, specifications, and requirements as applicable
- Documentation requesting subcontractors support DBE goal by solicitation and inclusion of DBE subcontractor quotes
- Responsive and timely submission of organized documentation
- Analysis of number of DBE firms who do work types that you typically subcontract
- Analysis of number of DBE firms who reside in geographical areas where prime seeks work
- Analysis of firms who express interest in bidding/quoting including the number of firms who declined your solicitation
- Reference check of DBE subcontractor work or training (documentation of questions and response required)
- Number of different efforts undertaken to meet the assigned DBE goal as documented in accompanying Form DT1202
- Submission of all DBE quotes received matched with a variety of work to be performed by DBEs
- Number and names of DBE firms provided written advice, or referral to industry-specific business development resources
- Overall pattern of DBE utilization on all WisDOT contracts which may include contracting with municipalities
- Documentation of resources expended to meet assigned DBE goal (#of hours, staff titles, average pay rate, actions taken)
- Analysis of subcontractable work items to be completed by prime beyond prime contractor's 30%
- Risk analysis of work items that are typically in tied quotes that could be unbundled
- List of contract work items in smallest economically feasible units, identifying schedule impact
- Submission of a Gap Analysis identifying DBE skillset and/or industry needs
- Staff training in EEO and Civil Rights laws as documented in training logs
- Written Capacity Assessment completed with DBE firm documenting its ability to perform the work quoted
- DBE engagement efforts beyond simple solicitation that include a substantive discussion, initiated as early in the acquisition process as possible (points added for each day prior to letting)
- Outreach and marketing efforts with minority, women, and veteran-focused organizations at least 10 days prior to bid opening
- Active involvement in WisDOT's Business Development Program, TrANS training, facilitated networking efforts, workshops
- Customized teaching/training efforts for future opportunities with DBE subcontractor, contract specific and/or annually
- Introduction and reference provided for DBE subcontractor to a prime who has not previously contracted with the DBE firm
- Prime utilization of a DBE subcontractor the prime has not contracted with previously
- Written referral/recommendation to bond/insurance agents, manufacturer, supplier
- Documented efforts fostering DBE participation through administrative and/or technical assistance
- Evidence of negotiation with the DBE firm about current and future Let opportunities
- Recommendation of local and state services that support small business and access to opportunity: DOA, SBA, WEDC, WPI, etc.
- Advice on bonding, lines of credit, or insurance as required to complete the items quoted and contract requirements.
 Page 22 of 36

GFE Evaluation Rubric – Phase 1 – Initial Review

DT1202	Examples	Rating	OBOEC Feedback
Solicitation Documentation	Identify all reasonable and available activities performed to solicit the interest of all certified DBEs who have capacity and ability to perform work on the project. Such as: Updated solicitation letter and email, timely solicitation, and follow-up, and/or utilized various methods to communicate solicitation (ex: letter, email,		
Selected Work Items	publication, posting and/or website) All work items are broken out into economically feasible		
Documentation	units to facilitate DBE participation.		
	Such as: Selected work items are <u>specific</u> to each proposal and clearly identified in all solicitation(s)		
Documentation of Project Information provided to Interested DBEs	Provide interested DBEs with adequate information about the plans, specifications, and any other contractual requirements in a timely manner to assist DBEs in response to solicitation.		
	Such as: Project information is clearly identified in all solicitation(s)		
Documentation of Negotiation with Interested DBEs	Provide sufficient evidence demonstrating that good faith negotiations took place during the bid letting.		
	Such as: Documented attempts with DBEs or on behalf of DBEs to increase DBE participation		
Documentation of Sound Reason for Rejecting DBEs	Provide sufficient evidence demonstrating that DBEs are rejected for sound reasons.		
	Such as: Detailed and thoughtful analysis that considers both the percentage and dollar difference when rejecting a DBE including past performance, relevant business experience and stability, safety record, business ethic and integrity, technical capacity, and other tangible factors.		
Documentation of Assistance to Interested DBEs- bonding, credit, insurance, equipment, supplies/materials	Documented assistance in both solicitation(s) and outreach to DBEs.		
Documentation of Outreach to Minority, Women, and Community organizations and other DBE Business Development Support	Effectively use the services of minority, women, and community organizations as well as contractors' groups, local, state, and federal business assistance offices and organization that provide assistance in recruiting and supporting DBEs, as well participation in activities that support DBE business development.		
	Such as: Variety of activities that translate into meaningful DBE participation		
Documentation of other GFE activities	Such as: Used DT1202 Excel Workbook, Diversity & Inclusion company policy, Mentor-Protégé participant, awarded neutral DBE after bid submission, included company GFE overview/strategy information and/or company website highlights DBE opportunities and participation		
Overall Demonstration of GFE			

GFE EVALUATION RATING LEGEND – PHASE 1 – Initial Review

Documentation provided by bidder is evaluated and rated on the rubric. Bidders should include activities characterized by the following types of effort:

ACTIVE & AGGRESSIVE: Demonstrated through engaged and assertive activity

QUALITY: Demonstrated through essential character of conscientious and serious activity

QUANTITY: Demonstrated through a measurable number of activities

SCOPE & INTENSITY: Demonstrated through a rigorous approach to an appropriate and purposeful range of activities

TIMING: Demonstrated through engagement efforts beyond simple solicitation, initiated early in the process

GFE EVALUATION - PHASE 2 - Team Review

GFE Team completes:

- Review of activities included on the rubric
- Review of the intent to award and sound reasoning submitted by Prime
- Bid analysis to confirm if any bid submitted met the DBE goal
- Review average of other bidders DBE goal achievement
- Team review of combined efforts documented in Phase 1 and 2 constitute final GFE determination

Rating Scale:

GFE Approval:

Bona Fide = 6 or more categories color coded green.

Genuine effort characterized by sincere and earnest activities - "Solicitation" and "Sound Reasoning" must be green

GFE Approval:

Sufficient = 5 or more categories color coded green or yellow

Adequate effort documented with a variety of quality activities – "Solicitation" and "Sound Reasoning" must be green or yellow

GFE Denial:

Pro Forma efforts = 4 or less categories color coded green or yellow. Perfunctory effort characterized by routine or superficial activities

Green = Exceeds expectations

Yellow = Meets expectations

Red = Areas in need of attention and/or absence of documentation

See OBOEC Rubric Analysis Feedback

Excerpt from Appendix A to 49 CFR Part 26:

V. In determining whether a bidder has made good faith efforts, it is essential to scrutinize its documented efforts. At a minimum, you must review the performance of other bidders in meeting the contract goal. For example, when the apparent successful bidder fails to meet the contract goal, but others meet it, you may reasonably raise the question of whether, with additional efforts, the apparent successful bidder could have met the goal. If the apparent successful bidder fails to meet the goal but meets or exceeds the average DBE participation obtained by other bidders, you may view this, in conjunction with other factors, as evidence of the apparent successful bidder having made good faith efforts. As provided in §26.53(b)(2)((vi), you must also require the contractor to submit copies of each DBE and non-DBE subcontractor quote submitted to the bidder when a non-DBE subcontractor was selected over a DBE for work on the contract to review whether DBE prices were substantially higher; and contact the DBEs listed

GFE RUBRIC ANALYSIS	GFE RUBRIC ANALYSIS				
OBOEC DECISION	APPROVAL OR DENIAL				
Prime Contractor					
Proposal					
Project					
Bid Letting					
DBE Goal Amount					
DBE Goal Amount Achieved					
Bid Analysis					
Goal %	Achieved %				
Apparent Low Bidder	%				
Bidder B					
Bidder C					
Average of OTHER Bidders (Not including Apparent Low Bidder)					
DBE Quotes Received					
DBE Quotes Awarded					
DBE Quote(s) Rejected	Rejected Quote Analysis				
DBE Quote(s) Awarded	Awarded DBE Amount				

Appendix E Good Faith Effort Best Practices

This list is not a set of requirements; it is a list of potential strategies

Primes

- > Prime contractor open houses inviting DBE firms to see the bid "war room" or providing technical assistance.
- Participate in speed networking and mosaic exercises as arranged by DBE office.
- Host information sessions not directly associated with a bid letting.
- Participate in a formal mentor protégé or joint venture with a DBE firm.
- Participate in WisDOT advisory committees i.e. TRANSAC, or Mega Project committee meetings.
- Facilitate a small group DBE 'training session' clarifying how your firm prepares for bid letting, evaluates subcontractors, preferred qualifications, and communication methods.
- > Encourage subcontractors to solicit and highlight DBE participation in their quotes to you.
- Quality of communication, not quantity creates the best results. Contractors should be thorough in communicating with DBE firms before the bid and provide any assistance requested to assure best possible bid.

DBE

- ➤ DBE firms should contact primes as soon as possible with questions regarding their quotes or bid; seven days prior is optimal.
- Continually check for contract addendums on the HCCI website through the Thursday prior to letting to stay abreast of changes.
- Review the status of contracts on the HCCI website reviewing the 'apparent low bidder' list and bid tabs at a minimum.
- Prepare a portfolio or list of related projects and prime and supplier references; be sure to note transportation related projects of similar size and scope, firm expertise and staffing.
- Participate in DBE office assessment programs.
- Participate on advisory and mega-project committees.
- Sign up to receive the DBE Contracting Update.
- Consider membership in relevant industry or contractor organizations.
- Active participation is a must. Quote as many projects as you can reasonably work on; quoting the primes and bidding as a prime with the Department are the only ways to get work.

Appendix F Good Faith Effort Evaluation Guidance Appendix A of 49 CFR Part 26

I. When, as a recipient, you establish a contract goal on a DOT-assisted contract for procuring construction, equipment, services, or any other purpose, a bidder must, in order to be responsible and/or responsive, make sufficient good faith efforts to meet the goal. The bidder can meet this requirement in either of two ways. First, the bidder can meet the goal, documenting commitments for participation by DBE firms sufficient for this purpose. Second, even if it doesn't meet the goal, the bidder can document adequate good faith efforts. This means that the bidder must show that it took all necessary and reasonable steps to achieve a DBE goal or other requirement of this part which, by their scope, intensity, and appropriateness to the objective, could reasonably be expected to obtain sufficient DBE participation, even if they were not fully successful.

II. In any situation in which you have established a contract goal, Part 26 requires you to use the good faith efforts mechanism of this part. As a recipient, you have the responsibility to make a fair and reasonable judgment whether a bidder that did not meet the goal made adequate good faith efforts. It is important for you to consider the quality, quantity, and intensity of the different kinds of efforts that the bidder has made, based on the regulations and the guidance in this Appendix.

The efforts employed by the bidder should be those that one could reasonably expect a bidder to take if the bidder were actively and aggressively trying to obtain DBE participation sufficient to meet the DBE contract goal. Mere pro forma efforts are not good faith efforts to meet the DBE contract requirements. We emphasize, however, that your determination concerning the sufficiency of the firm's good faith efforts is a judgment call. Determinations should not be made using quantitative formulas.

- III. The Department also strongly cautions you against requiring that a bidder meet a contract goal (i.e., obtain a specified amount of DBE participation) in order to be awarded a contract, even though the bidder makes an adequate good faith efforts showing. This rule specifically prohibits you from ignoring bona fide good faith efforts.
- IV. The following is a list of types of actions which you should consider as part of the bidder's good faith efforts to obtain DBE participation. It is not intended to be a mandatory checklist, nor is it intended to be exclusive or exhaustive. Other factors or types of efforts may be relevant in appropriate cases.
- A. (1) Conducing market research to identify small business contractors and suppliers and soliciting through all reasonable and available means the interest of all certified DBEs that have the capability to perform the work of the contract. This may include attendance at pre-bid and business matchmaking meetings and events, advertising and/or written notices, posting of Notices of Sources Sought and/or Requests for Proposals, written notices or emails to all DBEs listed in the State's directory of transportation firms that specialize in the areas of work desired (as noted in the DBE directory) and which are located in the area or surrounding areas of the project.
- (2) The bidder should solicit this interest as early in the acquisition process as practicable to allow the DBEs to respond to the solicitation and submit a timely offer for the subcontract. The bidder should determine with certainty if the DBEs are interested by taking appropriate steps to follow up initial solicitations.

- B. Selecting portions of the work to be performed by DBEs in order to increase the likelihood that the DBE goals will be achieved. This includes, where appropriate, breaking out contract work items into economically feasible units (for example, smaller tasks or quantities) to facilitate DBE participation, even when the prime contractor might otherwise prefer to perform these work items with its own forces. This may include, where possible, establishing flexible timeframes for performance and delivery schedules in a manner that encourages and facilitates DBE participation.
- C. Providing interested DBEs with adequate information about the plans, specifications, and requirements of the contract in a timely manner to assist them in responding to a solicitation with their offer for the subcontract.
- D. (1) Negotiating in good faith with interested DBEs. It is the bidder's responsibility to make a portion of the work available to DBE subcontractors and suppliers and to select those portions of the work or material needs consistent with the available DBE subcontractors and suppliers, so as to facilitate DBE participation. Evidence of such negotiation includes the names, addresses, and telephone numbers of DBEs that were considered; a description of the information provided regarding the plans and specifications for the work selected for subcontracting; and evidence as to why additional Agreements could not be reached for DBEs to perform the work.
- (2) A bidder using good business judgment would consider a number of factors in negotiating with subcontractors, including DBE subcontractors, and would take a firm's price and capabilities as well as contract goals into consideration. However, the fact that there may be some additional costs involved in finding and using DBEs is not in itself sufficient reason for a bidder's failure to meet the contract DBE goal, as long as such costs are reasonable. Also, the ability or desire of a prime contractor to perform the work of a contract with its own organization does not relieve the bidder of the responsibility to make good faith efforts. Prime contractors are not, however, required to accept higher quotes from DBEs if the price difference is excessive or unreasonable.
- E. (1) Not rejecting DBEs as being unqualified without sound reasons based on a thorough investigation of their capabilities. The contractor's standing within its industry, membership in specific groups, organizations, or associations and political or social affiliations (for example union vs. non-union status) are not legitimate causes for the rejection or non-solicitation of bids in the contractor's efforts to meet the project goal. Another practice considered an insufficient good faith effort is the rejection of the DBE because its quotation for the work was not the lowest received. However, nothing in this paragraph shall be construed to require the bidder or prime contractor to accept unreasonable quotes in order to satisfy contract goals.
- (2) A prime contractor's inability to find a replacement DBE at the original price is not alone sufficient to support a finding that good faith efforts have been made to replace the original DBE. The fact that the contractor has the ability and/or desire to perform the contract work with its own forces does not relieve the contractor of the obligation to make good faith efforts to find a replacement DBE, and it is not a sound basis for rejecting a prospective replacement DBE's reasonable quote.
- F. Making efforts to assist interested DBEs in obtaining bonding, lines of credit, or insurance as required by the recipient or contractor.
- G. Making efforts to assist interested DBEs in obtaining necessary equipment, supplies, materials, or related assistance or services.

H. Effectively using the services of available minority/women community organizations; minority/women contractors' groups; local, State, and Federal minority/women business assistance offices; and other organizations as allowed on a case-by-case basis to provide assistance in the recruitment and placement of DBEs.

V. In determining whether a bidder has made good faith efforts, it is essential to scrutinize its documented efforts. At a minimum, you must review the performance of other bidders in meeting the contract goal. For example, when the apparent successful bidder fails to meet the contract goal, but others meet it, you may reasonably raise the question of whether, with additional efforts, the apparent successful bidder could have met the goal. If the apparent successful bidder fails to meet the goal, but meets or exceeds the average DBE participation obtained by other bidders, you may view this, in conjunction with other factors, as evidence of the apparent successful bidder having made good faith efforts. As provided in §26.53(b)(2)((vi), you must also require the contractor to submit copies of each DBE and non-DBE subcontractor quote submitted to the bidder when a non-DBE subcontractor was selected over a DBE for work on the contract to review whether DBE prices were substantially higher; and contact the DBEs listed on a contractor's solicitation to inquire as to whether they were contacted by the prime. Pro forma mailings to DBEs requesting bids are not alone sufficient to satisfy good faith efforts under the rule.

VI. A promise to use DBEs after contract award is not considered to be responsive to the contract solicitation or to constitute good faith efforts.

[79 FR 59600, Oct. 2, 2014]

Appendix G

(SAMPLE) Forms DT1506 and DT1202

Official Form DT1506 can be found here: https://wisconsindot.gov/Documents/formdocs/dt1506.pdf

COMMITMENT TO S DT1506 12/2021 s.84.06(2)				Clear Project ID:		• • • • • • • • • • • • • • • • • • • •		sportation
			W-5	Proposal #				
Prime Contractor: County:				Letting Date:				
This contract requires that a spe	cified percentage	e of the work be subcontra	acted to a	Total \$ Value of	Φ.			
disadvantaged business enterprise and that this information be submitted as described in ASP-3. The submittal of this form with the bid proposal constitutes your		Prime Contract: \$ DBE Contract Goal: %						
DBE commitment. Include Attacl	hment A for DBE	s included on commitmen	t.	DBE Goal Achiev	-	0.00%		
This form must be complete	ed and returne	d for this proposal.			1			
1. DBE Firm	2. Work or Ite	ems to be subcontracted	3. Supplier Y/N	4. Trucking Only	5. DBE F Subcontr		6. DBE .	
				O# L#				
				O# L#				
				O# L#				
				O# L#				
				0#				
				L# O#				
				L# O#				
				L#				
				O# L#				
				O# L#				
				O# L#				
				O# L#				
				O#				
				L# O#				
				L# O#				
				L# O#				
				L#				
				L#				
				O# L#				
		_		O# L#				
				O# L#				
				O#				
				L# O#				
				L# O#				
				L#				
					\$	0.00	\$	0.00
Government Approved A	mounts							
A = \$ V = \$	%			Bulling Bullingston				
V = \$ Total = \$	<u>%</u>			Prime Representa	ive Sign	ature & [Jate	
Signature:								
Date:	Voc 🗆 .	- Io -		DBE Office Signat	ure & Da	te Appro	ved	3.5
Good faith effort approved:	ies 🔲 – l	10 🗌						

1

COMMITMENT TO SUBCONTRACT TO DBE ATTACHMENT A

CONFIRMATION OF PARTICIPATION

Project I.D.:		Proposal Number:			
Letting Date:					
Name of DBE Firm Participat	ing in this Contract:				
Name of the Prime/Subcontra	actor who hired the DBE	Firm:	(list all names of tiers if more th	an one)	
Type of Work or Type of Mate	erial Supplied:				
Total Subcontract Value:			Total DBE Credit Value:		
		Prime	e Contractor Representative's Sigr	ature	
FOR PRIME CONTRACTORS ONLY: I certify that I made arrangements with the participating DBE firm to perform the type of work listed or supply the material indicated above for the subcontract value listed above.		Prime Contractor Representative's Name (Print Name)			
		Prime Contractor (Print Company Name)			
		Date			
FOR PARTICIPATING DBE FIR	s with the Prime	Parti	cipating DBE Firm Representative	s Signature	Date
Contractor or the Hiring Contractor to perform the type of work or supply the material indicated above for the subcontract value listed above.		Participating DBE Firm Representative's Name (Print Name)			
FOR DBE TRUCKING FIRMS ONLY: I certify that I will utilize, for DBE credit, only trucks listed on my WisDOT approved Schedule of Owned/Leased Vehicles for DBE Credit form and I will be utilizing the number of trucks as listed below.		Participating DBE Firm (Print Company Name)			
		DBE Firm's Address:			
#Owned Trucks	# Leased Trucks		# DBE-Owned Leased Trucks	00 00000	-DBE-Owned sed Trucks
Off site Hauling					



DOCUMENTATION:OF:GOOD:FAITH:EFFORT:

Wisconsin-Department-of-Transportation DT1202......3/2020

+

Project ID Proposal No.		Letting
Prime Contractor	County	
Person Submitting Document		Telephone Number
Address		Email-Address

All-bidders-must-undertake-necessary-and-reasonable-steps-to-achieve-the-assigned-DBE-contract-goal-per-federal-regulatory-guidance-at-49-CFR-Part-26.-Bidders-use-this-form-to-document-all-efforts-employed-to-meet-the-assigned-goal-as-a-record-of-contractor-good-faith-efforts-(GFE).-Refer-to-ASP3-or-49-CFR-Part-26-for-guidance-on-actions-that-demonstrate-good-faith-effort.

It is critical to list-all-efforts, attach-documentation, and follow the instructions to complete this submission.

Documentation of good faith effort includes copies of each DBE and non-DBE subcontractor quote submitted to the bidder for the same line items. Utilize the sample documentation logs to document and organize efforts.

Submit-good faith effort documentation per ASP-3 guidelines.

Instructions: Provide a narrative description of all activities pursued to demonstrate good faith efforts, any corresponding documentation, and applicable explanation on separate pages. Include the following items, organized in the order listed below.

1.→ Solicitation Documentation:

- a. Purpose: To identify all-reasonable and available activities the bidder-performed to solicit the interest of all-certified DBEs who have the capacity and ability to perform work on the project. All-solicitation efforts should begin as early as possible to ensure DBEs have ample time to respond and ask-questions.
- b. Action: Identify and list-all activities engaged in to solicit DBEs using all reasonable and available means such as written notice and follow-up communications; substantive conversations; pre-bid-meetings; networking events; market-research; advertising.

2.→ Selected·Work·Items·Documentation:

- a.→ Purpose: To ensure that all work items are broken out into economically feasible units to facilitate DBE participation. This must occur-even when you prefer to perform the work yourself.
- b. Action: Identify economically feasible work units to be performed by DBEs to include activities such as: list of work items to be performed; breaking up of large work items into smaller tasks or quantities; flexible time frames for performance and delivery schedules.

3.→ Documentation of Project Information provided to Interested DBEs:

- a.→ Purpose: To provide interested DBEs with adequate information about the plans, specifications, and any other contractual requirements in a timely manner to assist DBEs in response to solicitation.
- b.→ Action: Provide DBEs · access · to · plans, · specifications, · and · other · contract · requirements . · Early · solicitation · allows · ample · opportunity · to · provide · project · information, · links · to · Let · advertisements, · and · substantive · engagement · with · DBEs.

4.→ Documentation of Negotiation with Interested DBEs:

- a.→ Purpose: To ensure that negotiations with interested DBEs were made in good faith providing evidence as to why agreements could not be reached for DBEs to perform work.
- b. Action: Provide-sufficient evidence to demonstrate that good-faith negotiations took-place. Merely-sending-out-solicitations requesting-bids from DBEs does not constitute sufficient good-faith efforts. A bidder using good-business judgment considers a number of factors in negotiating with all subcontractors, and the firm's price and capabilities in addition to contract goals are taken into consideration. However, the fact that there may be some additional costs involved in finding and using DBEs is not in itself sufficient reason for failing to meet the DBE goal as long as costs are reasonable. (see 49 CFR Part 26 Appendix A)

5.→ Documentation·of·Sound·Reason·for·Rejecting·DBEs:

- a.→ Purpose: To ensure that bidders avoid rejecting DBEs as unqualified without sound reasons. Reasons for rejection must be based on thorough investigation of DBE capabilities.
- b. Action: Provide-sufficient-evidence to demonstrate that DBE-was rejected for sound reasons such as past-performance, relevant business experience and stability, safety record, business ethic and integrity, technical capacity, other tangible factors.

6.→ Documentation·of·Assistance·to·Interested·DBEs-·Bonding,·Credit,·Insurance,·Equipment,· Supplies/Materials:·

- a.→ Purpose: To assist interested DBEs in obtaining bonds, lines of credit, insurance, equipment, supplies, materials, and other assistance or services.
- b. Action: Assist-interested DBEs in obtaining bonding, lines of credit or insurance, and provide technical assistance or information related to plans, specifications, and project requirements. Assist DBEs in obtaining equipment, supplies, materials or other services related to meeting project requirements (excluding supplies or equipment the DBE purchases from the prime).

7.→ Documentation of outreach to Minority, Women, and Community Organizations and other DBE Business Development Support:

- a.→ Purpose: To effectively use the services of minority, women, and community organizations as well as contractors groups, local, state, and federal business assistance offices and organization that provide assistance in recruiting and supporting DBEs, as well as participation in activities that support DBE business development.
- b.→Action: Contact-organizations and agencies for assistance in contacting, recruiting, and providing support to DBE subcontractors, suppliers, manufacturers, and truckers at least 14 days before bid opening. Participate in or host activities such as networking events, mentor-protégé programs, small business development workshops, and others consistent with DBE support.

Return to: Wisconsin-Department of Transportation DBE-Program-Office PO-Box-7965 Madison, WI-53707-7965 DBE_Alert@dot.wi.gov

I-certify-that-I-have-utilized-comprehensive-good-faith-efforts-to-solicit-and-utilize-DBE-firms-to-meet-the-DBE-participation-requirements-of-this-contract-proposal, as-demonstrated-by-my-responses-and-as-specified-in-Additional-Special-Provision-3-(ASP-3). I-certify-that-the-information-given-in-the-Documentation-of-Good-Faith-Efforts-is-true-and-correct-to-the-best-of-my-knowledge-and-belief I-further-understand-that-any-willful-falsification,-fraudulent-statement,-or-misrepresentation-will-result-in-appropriate-sanctions,-which-may				
involve debarment and/or prosecution under applicable state (Trans	s-504) and Federal laws.			
	(Bidder/Authorized Representative Signature)			
	00000			
	(Print-Name)			
	99 99 9			
	(Title)			

Good·Faith·Effort·-·Sample·Documentation·Logs

The sample logs below are provided as guides rather than exhaustive list. See ASP3, Appendix A for additional examples of demonstrable good faith efforts. Attach documentation for each activity listed.

Acceptable forms of documentation include copies of solicitations sent to DBEs, notes from substantive conversations and negotiations with DBEs, copies of advertisements placed, email-communications, all quotes received from DBEs and from all subcontractors who were considered alongside DBE quotes, proof of attendance at applicable networking events; flyers for events or workshops for DBEs offered by the prime, and other physical records of good faith efforts activities.

SOLICITATION-LOG-

Date	Activity	Name-of-DBE-Solicited	Follow-up
4/1/2020	Sent-May-Let-solicitation	Winterland Electric	Spoke-with-Mark-Winterland-on-4/15/20-to-ask-if- he-would-quote-

SELECTED WORK-ITEMS-SOLICITED LOG

Work-Type	DBE-Firm	Contact-Person	Date	Contact·Mode
Payament Madrine	ABC-Marking	Leslie·Lynch	4/1/2020	Email; phone
Pavement-Marking	#1-Marking-Co.	Mark-Smart	4/1/2020	Email;·left·VM
Flactrical	Winterland·Electric	Tabitha-Tinker	4/3/2020	Email,·left·VM
Electrical	Superstar-Wiring	Jose-Huascar	4/3/2020	Email; phone

INFORMATION-PROVIDED-LOG

Request- Date	DBE-Firm	Information·Requested·&·Provided	Response- Date
4/1/2020		Requested-info-on-electrical-requirements;-provided- plan-and-link-to-specs	4/3/2020
4/21/2020	Absolute-Construction	Wanted to know how and when supplies are paid for by WisDOT; referred to spec that covers stockpiling	4/21/2020

NEGOTIATIONS:LOG

Date	DBE-Firm	Contact-Name	Work-Type	Quotes- Rec'd?	Considere d-for- project?	If-not-selected, why?
4/12/2020	ABC-Landscape	John-Dean	Erosion-Control	Yes	No	Cannot-perform-all-items
4/17/2020	Wild-Ferns	Sandy-Lynn	Erosion-Control	Yes	Yes	
4/20/2020	#1·Marking	Mark-Smart	Electrical	Yes	Yes	

ASSISTANCE-LOG

Date	DBE-Firm	Contact-Person	Assistance-Provided
4/1/2020	ABC-Sawing	Jackie-Swiggle	Informed·DBE·on·how·to·obtain·bonding
4/17/2020	Supreme-Construction		Provided-contact-for-wholesale-supply- purchase

OUTREACH & BUSINESS DEVELOPMENT LOG

Date	Agency/Organization· Contacted	Contact-Person	Assistance Requested
4/1/2020	Women-in-Construction	LaTonya·Klein	Contact-information-for-woman-owned-suppliers
4/28/2020	WBIC	Sam-Smith	Asked-for-information-to-provide-to-DBE-regarding- financing-programs-through-WBIC

Official Form DT1202 can be found here: https://wisconsindot.gov/pages/global-footer/formdocs/default.aspx

ADDITIONAL SPECIAL PROVISION 4

This special provision does not limit the right of the department, prime contractor, or subcontractors at any tier to withhold payment for work not acceptably completed or work subject to an unresolved contract dispute.

Payment to First-Tier Subcontractors

Within 10 calendar days of receiving a progress payment for work completed by a subcontractor, pay the subcontractor for that work. The prime contractor may withhold payment to a subcontractor if, within 10 calendar days of receipt of that progress payment, the prime contractor provides written notification to the subcontractor and the department documenting "just cause" for withholding payment.

The prime contractor is not allowed to withhold retainage from payments due subcontractors.

Payment to Lower-Tier Subcontractors

Ensure that subcontracting agreements at all tiers provide prompt payment rights to lower-tier subcontractors that parallel those granted first-tier subcontractors in this provision.

Acceptance and Final Payment

Within 30 calendar days of receiving the semi-final estimate from the department, submit written certification that subcontractors at all tiers are paid in full for acceptably completed work.

Additional Special Provision 6 ASP 6 - Modifications to the standard specifications

Make the following revisions to the standard specifications:

108 Prosecution and Progress

Add subsection 108.9.4.1 effective with the November 2023 letting:

108.9.4.1 Winter Suspension for Completion Date Contracts

- (1) The contractor may request a winter suspension for a completion date contract. If the department determines weather conditions do not allow for the completion of the remaining work, the department may approve the contractor's request and determine the start date of the winter suspension. The end date of the winter suspension is March 31 or a date mutually agreed upon by both parties. For multi-year contracts, the department will only consider winter suspension for the final year of the contract.
- (2) During winter suspension, store all materials in a manner that does not obstruct vehicular and pedestrian traffic and protect the materials from damage. Install traffic control and other safety devices necessary to protect the traveling public and pedestrians. Provide suitable drainage and install temporary erosion control where necessary. If the winter suspension begins when liquidated damages are being assessed, or when the work has not progressed as scheduled and would not have been completed prior to the completion date, the cost of necessary pre-suspension work is incidental. If the winter suspension begins prior to the contract completion date, and the work has progressed as scheduled and would have been completed prior to the completion date, the cost of pre-suspension work will be paid as specified under 109.4.
- (3) For a winter suspension that begins prior to the contract completion date and the work has progressed as scheduled and would have been completed prior to the completion date, the engineer will extend contract time to correspond with the end of the winter suspension and liquidated damages will not be assessed during the winter suspension.
- (4) For a winter suspension that begins when liquidated damages are being assessed or when the work has not progressed as scheduled and would not have been completed prior to the completion date, the engineer will not extend contract time. Time will be suspended until the end of the winter suspension. Liquidated damages will not be assessed during the winter suspension and liquidated damages will resume at the end of the winter suspension.

310 Open Graded Base

310.2 Materials

Replace paragraph two with the following effective with the November 2023 letting:

(2) The contractor may substitute material conforming to the gradation requirements for crushed aggregate specified in Table 310-01 if that material conforms to the fracture requirements for open-graded crushed gravel specified in 301.2.4.5.

TABLE 310-01 COARSE AGGREGATE (% passing by weight)

AASHTO No. 67^[1]

COARSE AGGREGATE (% PASSING by WEIGHT) **SEIVE** AASHTO No. 67 2-inch 1 1/2-inch _ 1-inch 100 90 - 1003/4-inch 1/2-inch 3/8-inch 20 - 55No. 4 0 - 10No. 8 0 - 5No. 16 No. 30

No. 50	-
No. 100	-
No. 200	<=1.5

[1] Size according to AASHTO M43.

390 Base Patching

390.4 Measurement

Replace entire section with the following effective with the November 2023 letting:

- (1) The department will measure Removing Pavement for Base Patching by the cubic yard acceptably completed. Measure the depth from the bottom of the adjacent pavement to the top of the patch.
- (2) The department will measure Base Patching Asphaltic by the ton acceptably completed as specified for asphaltic pavement in 450.4.
- (3) The department will measure Base Patching Concrete HES and Base Patching Concrete SHES by the cubic yard acceptably completed. Measure the depth from the bottom of the adjacent pavement to the top of the patch.

390.5 Payment

Replace entire section with the following effective with the November 2023 letting:

(1) The department will pay for measured quantities at the contract unit price under the following bid items:

ITEM NUMBER	DESCRIPTION	<u>UNIT</u>
390.0100	Removing Pavement for Base Patching	CY
390.0201	Base Patching Asphaltic	TON
390.0305	Base Patching Concrete HES	CY
390.0405	Base Patching Concrete SHES	CY

- (2) Payment for Removing Pavement for Base Patching is full compensation for removing old pavement; for preparing the foundation and bringing up to grade. If the engineer orders the contractor to excavate yielding or unstable subgrade materials and backfill with suitable materials, the department will pay for that work with contract bid items or as agreed upon using 109.4.
- (3) Payment for Base Patching Asphaltic is full compensation for providing and compacting asphaltic mixture including asphaltic binder.
- (4) Payment for Base Patching Concrete HES and Base Patching Concrete SHES is full compensation for providing, curing, and protecting concrete. Payment also includes providing tie bars and dowel bars in unhardened concrete and steel within the patch. For tie bars and dowel bars provided in concrete not placed under the contract, the department will pay separately under the Drilled Tie Bars and Drilled Dowel Bars bid items as specified in 416.5.
- (5) Payment for Base Patching SHES also includes providing test data to the engineer as specified in 416.2.4.
- (6) The department will pay for sawing existing concrete pavement for removal under the Sawing Concrete bid item as specified in 690.5.

460 Hot Mix Asphalt Pavement

460.2.8.2.1.3.1 Contracts with 5000 Tons of Mixture or Greater

Replace paragraph four with the following effective with the November 2023 letting:

(4) Use the test methods identified below, or other methods the engineer approves, to perform the following tests at the frequency indicated:

Blended aggregate gradations:

Drum plants:

- Field extraction by ignition oven according to WTM T308, chemical extraction according to AASHTO T-164 method A or B; or automated extraction according to WTM D8159. Gradation of resulting aggregate sample determined according to WTM T30.
- Belt samples, optional for virgin mixtures, obtained from stopped belt or from the belt discharge using an engineer-approved sampling device and performed according to WTM T11 and T27.

Batch plants:

 Field extraction by ignition oven according to WTM T308, chemical extraction according to AASHTO T-164 method A or B; or automated extraction according to WTM D8159. Gradation of resulting aggregate sample determined according to WTM T30.

Asphalt content (AC) in percent:

Determine AC using one of the following methods:

- AC by ignition oven according to WTM T308.
- AC by chemical extraction according to AASHTO T-164 method A or B.
- AC by automated extraction according to WTM D8159.
- If the department is using an ignition oven to determine AC, conform to WTP H003.
- If the department is not using an ignition oven to determine AC, ignition oven correction factor (IOCF) must still be reverified for any of the reasons listed in WTP H003 Table 2 and conform to WTP H-003 sections 3 through 6.
- Gradation of resulting aggregate sample determined according to WTM T30.

Bulk specific gravity of the compacted mixture:

According to WTM T166.

Theoretical maximum specific gravity:

According to WTM T209.

Air voids (Va) by calculation according to WTM T269.

VMA by calculation according to WTM R35.

460.2.8.3.1.4 Department Verification Testing Requirements

Replace paragraph three with the following effective with the November 2023 letting:

(3) The department will perform testing conforming to the following standards:

Bulk specific gravity (G_{mb}) of the compacted mixture according to WTM T166.

Maximum specific gravity (Gmm) according to WTM T209.

Air voids (Va) by calculation according to WTM T269.

VMA by calculation according to WTM R35.

Asphalt content by ignition oven according to WTM T308, chemical extraction according to AASHTO T-164 method A or B, or automated extraction according to WTM D8159. If using an ignition oven to determine AC, conform to WTP H-003.

503 Prestressed Concrete Members

503.2.2 Concrete

Replace paragraph five with the following effective with the November 2023 letting:

(5) Furnish prestressed concrete members cast from air-entrained concrete, except I-type girders may use non-air-entrained concrete. Use type I, IL, IS, IP, IT, II, or III cement. The contractor may replace up to 30 percent of type I, IL, II, or III cement with an equal weight of fly ash, slag, or a combination of fly ash and slag. Ensure that fly ash conforms to 501.2.4.2.2 and slag conforms to 501.2.4.2.3. Use only one source and replacement rate for work under a single bid item. Use a department-approved air-entraining admixture conforming to 501.2.5.2 for air-entrained concrete. Use only coarse aggregate conforming to 310.2(2).

604 Slope Paving

604.2 Materials

Replace paragraph three with the following effective with the November 2023 letting:

(3) Under the Slope Paving Crushed Aggregate bid item, furnish crushed stone or crushed gravel conforming to the gradation in Table 604-01, but with the additional requirements that at least 75 percent of the particles, by count, have at least one fractured face. Determine fracture according to WTM D5821.

TABLE 604-01 COARSE AGGREGATE (% passing by weight)

AASHTO No. 4^[1]

SEIVE	COARSE AGGREGATE (% PASSING by WEIGHT) AASHTO No. 4
2-inch	100
1 1/2-inch	90 - 100
1-inch	20 - 55
3/4-inch	0 - 15
1/2-inch	-
3/8-inch	0 - 5
No. 4	-
No. 8	-
No. 16	-
No. 30	-
No. 50	-
No. 100	-
No. 200	<=1.5

^[1] Size according to AASHTO M43.

612 Underdrains

612.3.9 Trench Underdrains

Replace paragraph one with the following effective with the November 2023 letting:

(1) Under the Underdrain Trench bid item, excavate and backfill underdrain trenches. Backfill with coarse aggregate gradation conforming to 604.2(3). Before backfilling place geotextile as the plans show.

614 Semi-rigid Barrier Systems and End Treatments

614.2.6 Sand Barrel Arrays

Replace paragraph one with the following effective with the November 2023 letting:

(1) Furnish sand barrels from the APL. Use fine aggregate conforming to gradation shown in Table 614-2 mixed with sodium chloride conforming to AASHTO M143. Apply an object marker to front-most barrel in the array.

TABLE 614-2 FINE AGGREGATE GRADATION

SEIVE	FINE AGGREGATE (% PASSING by WEIGHT)
3/8-inch	100
No. 4	90 - 100
No. 8	-
No. 16	45 - 85
No. 30	-
No. 50	5 - 30
No. 100	0 - 10
No. 200	<=3.5

628 Erosion Control

628.2.13 Rock Bags

Replace paragraph two with the following effective with the November 2023 letting:

(2) Fill the bags with a clean, sound, hard, durable, engineer-approved coarse aggregate conforming by visual inspection to the gradation specified for coarse aggregate gradation in 604.2(3).

639 Drilling Wells

639.2.1 General

Replace paragraph two with the following effective with the November 2023 letting:

(2) For grout use fine aggregate conforming to 501.2.7.2; and gradation conforming to 614.2.6(1); and type I, IL, IS, IP, or IT cement.

652 Electrical Conduit

652.3.1.2 Installing Underground

Replace paragraph two with the following effective with the November 2023 letting:

(2) Excavate trenches true to line and grade to provide the conduit uniform bearing throughout its length. Do not backfill the trench before inspecting the conduit. Carefully tamp the backfill in place as specified for placing backfill in layers in 651.3. Place at least 0.7 cubic feet of coarse aggregate gradation conforming to 604.2(3) directly under each drainage hole.

ERRATA

390.3.4 Special High Early Strength Concrete Patching

Correct errata link in paragraph (1) by changing from 416.3.8 to 416.3.7.

- (1) Construct as specified for special high early strength repairs under 416.3.7 except as follows:
 - The contractor may delay removal for up to 14 calendar days after cutting the existing pavement.
 - Open to traffic as specified for concrete base in 320.3.

ADDITIONAL SPECIAL PROVISION 7

- A. Reporting 1st Tier and DBE Payments During Construction
 - 1. Comply with reporting requirements specified in the department's Civil Rights Compliance, Contractor's User Manual, Sublets and Payments.
 - 2. Report payments to all DBE firms within 10 calendar days of receipt of a progress payment by the department or a contractor for work performed, materials furnished, or materials stockpiled by a DBE firm. Report the payment as specified in A(1) for all work satisfactorily performed and for all materials furnished or stockpiled.
 - 3. Report payments to all first tier subcontractor relationships within 10 calendar days of receipt of a progress payment by the department for work performed. Report the payment as specified in A(1) for all work satisfactorily performed.
 - 4. All tiers shall report payments as necessary to comply with the DBE payment requirement as specified in A(2).
 - 5. DBE firms must enter all payments to DBE and non-DBE firms regardless of tier.
 - 6. Require all first tier relationships, DBE firms and all other tier relationships necessary to comply with the DBE payment requirement in receipt of a progress payment by contractor to acknowledge receipt of payment as specified in A(1), (2), (3) and (4).
 - 7. All agreements made by a contractor shall include the provisions in A(1), (2), (3), (4), (5), and (6), and shall be binding on all first tier subcontractor relationships, all contractors and subcontractors utilizing DBE firms on the project, and all payments from DBE firms.
- B. Costs for conforming to this special provision are incidental to the contract.

NOTE: CRCS Prime Contractor payment is currently not automated and will need to be manually loaded into the Civil Rights Compliance System. Copies of prime contractor payments received (check or ACH) will have to be forwarded to paul.ndon@dot.wi.gov within 5 days of payment receipt to be logged manually.

***Additionally, for information on Subcontractor Sublet assignments, Subcontractor Payments and Payment Tracking, please refer to the CRCS Payment and Sublets manual at:

https://wisconsindot.gov/Documents/doing-bus/civil-rights/labornwage/crcs-payments-sublets-manual.pdf

ADDITIONAL SPECIAL PROVISION 9

Electronic Certified Payroll or Labor Data Submittal

- (1) Use the department's Civil Rights Compliance System (CRCS) to electronically submit certified payroll reports for contracts with federal funds and labor data for contracts with state funds only. Details are available online through the department's highway construction contractor information (HCCI) site on the Labor, Wages, and EEO Information page at:
 - https://wisconsindot.gov/Pages/doing-bus/civil-rights/labornwage/default.aspx
- (2) Ensure that all tiers of subcontractors, including all trucking firms, either submit their weekly certified payroll reports (contracts with federal funds) or labor data (contracts with state funds only) electronically through CRCS. These payrolls or labor data are due within seven calendar days following the close of the payroll period. Every firm providing physical labor towards completing the project is a subcontractor under this special provision.
- (3) Upon receipt of contract execution, promptly make all affected firms aware of the requirements under this special provision and arrange for them to receive CRCS training as they are about to begin their submittals. The department will provide training either in a classroom setting at one of our regional offices or by telephone. Contact Paul Ndon at (414) 438-4584 to schedule the training.
- (4) The department will reject all paper submittals for information required under this special provision. All costs for conforming to this special provision are incidental to the contract.
- (5) Firms wishing to export payroll/labor data from their computer system into CRCS should have their payroll coordinator contact Paul Ndon at paul.ndon@dot.wi.gov. Not every contractor's payroll system is capable of producing export files. For details, see Section 4.8 CPR Auto Submit (Data Mapping) on pages 49-50; 66-71 of the CRCS Payroll Manual at:
 - https://wisconsindot.gov/Documents/doing-bus/civil-rights/labornwage/crcs-payroll-manual.pdf

REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS

- I General
- II. Nondiscrimination
- III. Non-segregated Facilities
- IV. Davis-Bacon and Related Act Provisions
- Contract Work Hours and Safety Standards Act Provisions
- VI. Subletting or Assigning the Contract
- VII. Safety: Accident Prevention
- VIII. False Statements Concerning Highway Projects
- IX. Implementation of Clean Air Act and Federal Water Pollution Control Act
- X. Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion
- Certification Regarding Use of Contract Funds for Lobbying
- XII. Use of United States-Flag Vessels:

ATTACHMENTS

A. Employment and Materials Preference for Appalachian Development Highway System or Appalachian Local Access Road Contracts (included in Appalachian contracts only)

I. GENERAL

1. Form FHWA-1273 must be physically incorporated in each construction contract funded under title 23, United States Code, as required in 23 CFR 633.102(b) (excluding emergency contracts solely intended for debris removal). The contractor (or subcontractor) must insert this form in each subcontract and further require its inclusion in all lower tier subcontracts (excluding purchase orders, rental agreements and other agreements for supplies or services). 23 CFR 633.102(e).

The applicable requirements of Form FHWA-1273 are incorporated by reference for work done under any purchase order, rental agreement or agreement for other services. The prime contractor shall be responsible for compliance by any subcontractor, lower-tier subcontractor or service provider. 23 CFR 633.102(e).

Form FHWA-1273 must be included in all Federal-aid designbuild contracts, in all subcontracts and in lower tier subcontracts (excluding subcontracts for design services, purchase orders, rental agreements and other agreements for supplies or services) in accordance with 23 CFR 633.102. The design-builder shall be responsible for compliance by any subcontractor, lower-tier subcontractor or service provider.

Contracting agencies may reference Form FHWA-1273 in solicitation-for-bids or request-for-proposals documents, however, the Form FHWA-1273 must be physically incorporated (not referenced) in all contracts, subcontracts and lower-tier subcontracts (excluding purchase orders, rental agreements and other agreements for supplies or services related to a construction contract). 23 CFR 633.102(b).

2. Subject to the applicability criteria noted in the following sections, these contract provisions shall apply to all work

performed on the contract by the contractor's own organization and with the assistance of workers under the contractor's immediate superintendence and to all work performed on the contract by piecework, station work, or by subcontract. 23 CFR 633.102(d).

- 3. A breach of any of the stipulations contained in these Required Contract Provisions may be sufficient grounds for withholding of progress payments, withholding of final payment, termination of the contract, suspension / debarment or any other action determined to be appropriate by the contracting agency and FHWA.
- 4. Selection of Labor: During the performance of this contract, the contractor shall not use convict labor for any purpose within the limits of a construction project on a Federal-aid highway unless it is labor performed by convicts who are on parole, supervised release, or probation. 23 U.S.C. 114(b). The term Federal-aid highway does not include roadways functionally classified as local roads or rural minor collectors. 23 U.S.C. 101(a).
- II. NONDISCRIMINATION (23 CFR 230.107(a); 23 CFR Part 230, Subpart A, Appendix A; EO 11246)

The provisions of this section related to 23 CFR Part 230, Subpart A, Appendix A are applicable to all Federal-aid construction contracts and to all related construction subcontracts of \$10,000 or more. The provisions of 23 CFR Part 230 are not applicable to material supply, engineering, or architectural service contracts.

In addition, the contractor and all subcontractors must comply with the following policies: Executive Order 11246, 41 CFR Part 60, 29 CFR Parts 1625-1627, 23 U.S.C. 140, Section 504 of the Rehabilitation Act of 1973, as amended (29 U.S.C. 794), Title VI of the Civil Rights Act of 1964, as amended (42 U.S.C. 2000d et seq.), and related regulations including 49 CFR Parts 21, 26, and 27; and 23 CFR Parts 200, 230, and 633.

The contractor and all subcontractors must comply with: the requirements of the Equal Opportunity Clause in 41 CFR 60-1.4(b) and, for all construction contracts exceeding \$10,000, the Standard Federal Equal Employment Opportunity Construction Contract Specifications in 41 CFR 60-4.3.

Note: The U.S. Department of Labor has exclusive authority to determine compliance with Executive Order 11246 and the policies of the Secretary of Labor including 41 CFR Part 60, and 29 CFR Parts 1625-1627. The contracting agency and the FHWA have the authority and the responsibility to ensure compliance with 23 U.S.C. 140, Section 504 of the Rehabilitation Act of 1973, as amended (29 U.S.C. 794), and Title VI of the Civil Rights Act of 1964, as amended (42 U.S.C. 2000d et seq.), and related regulations including 49 CFR Parts 21, 26, and 27; and 23 CFR Parts 200, 230, and 633.

The following provision is adopted from 23 CFR Part 230, Subpart A, Appendix A, with appropriate revisions to conform to the U.S. Department of Labor (US DOL) and FHWA requirements.

- 1. Equal Employment Opportunity: Equal Employment Opportunity (EEO) requirements not to discriminate and to take affirmative action to assure equal opportunity as set forth under laws, executive orders, rules, regulations (see 28 CFR Part 35, 29 CFR Part 1630, 29 CFR Parts 1625-1627, 41 CFR Part 60 and 49 CFR Part 27) and orders of the Secretary of Labor as modified by the provisions prescribed herein, and imposed pursuant to 23 U.S.C. 140, shall constitute the EEO and specific affirmative action standards for the contractor's project activities under this contract. The provisions of the Americans with Disabilities Act of 1990 (42 U.S.C. 12101 et seq.) set forth under 28 CFR Part 35 and 29 CFR Part 1630 are incorporated by reference in this contract. In the execution of this contract, the contractor agrees to comply with the following minimum specific requirement activities of EEO:
- a. The contractor will work with the contracting agency and the Federal Government to ensure that it has made every good faith effort to provide equal opportunity with respect to all of its terms and conditions of employment and in their review of activities under the contract. 23 CFR 230.409 (g)(4) & (5).
- b. The contractor will accept as its operating policy the following statement:

"It is the policy of this Company to assure that applicants are employed, and that employees are treated during employment, without regard to their race, religion, sex, sexual orientation, gender identity, color, national origin, age or disability. Such action shall include: employment, upgrading, demotion, or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship, pre-apprenticeship, and/or on-the-job training."

- 2. EEO Officer: The contractor will designate and make known to the contracting officers an EEO Officer who will have the responsibility for and must be capable of effectively administering and promoting an active EEO program and who must be assigned adequate authority and responsibility to do so.
- 3. Dissemination of Policy: All members of the contractor's staff who are authorized to hire, supervise, promote, and discharge employees, or who recommend such action or are substantially involved in such action, will be made fully cognizant of and will implement the contractor's EEO policy and contractual responsibilities to provide EEO in each grade and classification of employment. To ensure that the above agreement will be met, the following actions will be taken as a minimum:
- a. Periodic meetings of supervisory and personnel office employees will be conducted before the start of work and then not less often than once every six months, at which time the contractor's EEO policy and its implementation will be reviewed and explained. The meetings will be conducted by the EEO Officer or other knowledgeable company official.
- b. All new supervisory or personnel office employees will be given a thorough indoctrination by the EEO Officer, covering all major aspects of the contractor's EEO obligations within thirty days following their reporting for duty with the contractor.
- c. All personnel who are engaged in direct recruitment for the project will be instructed by the EEO Officer in the contractor's procedures for locating and hiring minorities and women

- d. Notices and posters setting forth the contractor's EEO policy will be placed in areas readily accessible to employees, applicants for employment and potential employees.
- e. The contractor's EEO policy and the procedures to implement such policy will be brought to the attention of employees by means of meetings, employee handbooks, or other appropriate means.
- **4. Recruitment:** When advertising for employees, the contractor will include in all advertisements for employees the notation: "An Equal Opportunity Employer." All such advertisements will be placed in publications having a large circulation among minorities and women in the area from which the project work force would normally be derived.
- a. The contractor will, unless precluded by a valid bargaining agreement, conduct systematic and direct recruitment through public and private employee referral sources likely to yield qualified minorities and women. To meet this requirement, the contractor will identify sources of potential minority group employees and establish with such identified sources procedures whereby minority and women applicants may be referred to the contractor for employment consideration.
- b. In the event the contractor has a valid bargaining agreement providing for exclusive hiring hall referrals, the contractor is expected to observe the provisions of that agreement to the extent that the system meets the contractor's compliance with EEO contract provisions. Where implementation of such an agreement has the effect of discriminating against minorities or women, or obligates the contractor to do the same, such implementation violates Federal nondiscrimination provisions.
- c. The contractor will encourage its present employees to refer minorities and women as applicants for employment. Information and procedures with regard to referring such applicants will be discussed with employees.
- **5. Personnel Actions:** Wages, working conditions, and employee benefits shall be established and administered, and personnel actions of every type, including hiring, upgrading, promotion, transfer, demotion, layoff, and termination, shall be taken without regard to race, color, religion, sex, sexual orientation, gender identity, national origin, age or disability. The following procedures shall be followed:
- a. The contractor will conduct periodic inspections of project sites to ensure that working conditions and employee facilities do not indicate discriminatory treatment of project site personnel.
- b. The contractor will periodically evaluate the spread of wages paid within each classification to determine any evidence of discriminatory wage practices.
- c. The contractor will periodically review selected personnel actions in depth to determine whether there is evidence of discrimination. Where evidence is found, the contractor will promptly take corrective action. If the review indicates that the discrimination may extend beyond the actions reviewed, such corrective action shall include all affected persons.
- d. The contractor will promptly investigate all complaints of alleged discrimination made to the contractor in connection with its obligations under this contract, will attempt to resolve such complaints, and will take appropriate corrective action

within a reasonable time. If the investigation indicates that the discrimination may affect persons other than the complainant, such corrective action shall include such other persons. Upon completion of each investigation, the contractor will inform every complainant of all of their avenues of appeal.

6. Training and Promotion:

- a. The contractor will assist in locating, qualifying, and increasing the skills of minorities and women who are applicants for employment or current employees. Such efforts should be aimed at developing full journey level status employees in the type of trade or job classification involved.
- b. Consistent with the contractor's work force requirements and as permissible under Federal and State regulations, the contractor shall make full use of training programs (i.e., apprenticeship and on-the-job training programs for the geographical area of contract performance). In the event a special provision for training is provided under this contract, this subparagraph will be superseded as indicated in the special provision. The contracting agency may reserve training positions for persons who receive welfare assistance in accordance with 23 U.S.C. 140(a).
- c. The contractor will advise employees and applicants for employment of available training programs and entrance requirements for each.
- d. The contractor will periodically review the training and promotion potential of employees who are minorities and women and will encourage eligible employees to apply for such training and promotion.
- 7. Unions: If the contractor relies in whole or in part upon unions as a source of employees, the contractor will use good faith efforts to obtain the cooperation of such unions to increase opportunities for minorities and women. 23 CFR 230.409. Actions by the contractor, either directly or through a contractor's association acting as agent, will include the procedures set forth below:
- a. The contractor will use good faith efforts to develop, in cooperation with the unions, joint training programs aimed toward qualifying more minorities and women for membership in the unions and increasing the skills of minorities and women so that they may qualify for higher paying employment.
- b. The contractor will use good faith efforts to incorporate an EEO clause into each union agreement to the end that such union will be contractually bound to refer applicants without regard to their race, color, religion, sex, sexual orientation, gender identity, national origin, age, or disability.
- c. The contractor is to obtain information as to the referral practices and policies of the labor union except that to the extent such information is within the exclusive possession of the labor union and such labor union refuses to furnish such information to the contractor, the contractor shall so certify to the contracting agency and shall set forth what efforts have been made to obtain such information.
- d. In the event the union is unable to provide the contractor with a reasonable flow of referrals within the time limit set forth in the collective bargaining agreement, the contractor will, through independent recruitment efforts, fill the employment vacancies without regard to race, color, religion, sex, sexual orientation, gender identity, national origin, age, or disability; making full efforts to obtain qualified and/or qualifiable minorities and women. The failure of a union to provide

sufficient referrals (even though it is obligated to provide exclusive referrals under the terms of a collective bargaining agreement) does not relieve the contractor from the requirements of this paragraph. In the event the union referral practice prevents the contractor from meeting the obligations pursuant to Executive Order 11246, as amended, and these special provisions, such contractor shall immediately notify the contracting agency.

- 8. Reasonable Accommodation for Applicants / Employees with Disabilities: The contractor must be familiar with the requirements for and comply with the Americans with Disabilities Act and all rules and regulations established thereunder. Employers must provide reasonable accommodation in all employment activities unless to do so would cause an undue hardship.
- 9. Selection of Subcontractors, Procurement of Materials and Leasing of Equipment: The contractor shall not discriminate on the grounds of race, color, religion, sex, sexual orientation, gender identity, national origin, age, or disability in the selection and retention of subcontractors, including procurement of materials and leases of equipment. The contractor shall take all necessary and reasonable steps to ensure nondiscrimination in the administration of this contract.
- a. The contractor shall notify all potential subcontractors, suppliers, and lessors of their EEO obligations under this contract.
- b. The contractor will use good faith efforts to ensure subcontractor compliance with their EEO obligations.

10. Assurances Required:

- a. The requirements of 49 CFR Part 26 and the State DOT's FHWA-approved Disadvantaged Business Enterprise (DBE) program are incorporated by reference.
- b. The contractor, subrecipient or subcontractor shall not discriminate on the basis of race, color, national origin, or sex in the performance of this contract. The contractor shall carry out applicable requirements of 49 CFR part 26 in the award and administration of DOT-assisted contracts. Failure by the contractor to carry out these requirements is a material breach of this contract, which may result in the termination of this contract or such other remedy as the recipient deems appropriate, which may include, but is not limited to:
 - (1) Withholding monthly progress payments;
 - (2) Assessing sanctions;
 - (3) Liquidated damages; and/or
- (4) Disqualifying the contractor from future bidding as non-responsible.
- c. The Title VI and nondiscrimination provisions of U.S. DOT Order 1050.2A at Appendixes A and E are incorporated by reference. 49 CFR Part 21.
- 11. Records and Reports: The contractor shall keep such records as necessary to document compliance with the EEO requirements. Such records shall be retained for a period of three years following the date of the final payment to the contractor for all contract work and shall be available at reasonable times and places for inspection by authorized representatives of the contracting agency and the FHWA.
- a. The records kept by the contractor shall document the following:

- (1) The number and work hours of minority and nonminority group members and women employed in each work classification on the project;
 - (2) The progress and efforts being made in cooperation with unions, when applicable, to increase employment opportunities for minorities and women; and
 - (3) The progress and efforts being made in locating, hiring, training, qualifying, and upgrading minorities and women.
- b. The contractors and subcontractors will submit an annual report to the contracting agency each July for the duration of the project indicating the number of minority, women, and non-minority group employees currently engaged in each work classification required by the contract work. This information is to be reported on Form FHWA-1391. The staffing data should represent the project work force on board in all or any part of the last payroll period preceding the end of July. If on-the-job training is being required by special provision, the contractor will be required to collect and report training data. The employment data should reflect the work force on board during all or any part of the last payroll period preceding the end of July.

III. NONSEGREGATED FACILITIES

This provision is applicable to all Federal-aid construction contracts and to all related construction subcontracts of more than \$10,000. 41 CFR 60-1.5.

As prescribed by 41 CFR 60-1.8, the contractor must ensure that facilities provided for employees are provided in such a manner that segregation on the basis of race, color, religion, sex, sexual orientation, gender identity, or national origin cannot result. The contractor may neither require such segregated use by written or oral policies nor tolerate such use by employee custom. The contractor's obligation extends further to ensure that its employees are not assigned to perform their services at any location under the contractor's control where the facilities are segregated. The term "facilities" includes waiting rooms, work areas, restaurants and other eating areas, time clocks, restrooms, washrooms, locker rooms and other storage or dressing areas, parking lots, drinking fountains, recreation or entertainment areas, transportation, and housing provided for employees. The contractor shall provide separate or single-user restrooms and necessary dressing or sleeping areas to assure privacy between sexes.

IV. DAVIS-BACON AND RELATED ACT PROVISIONS

This section is applicable to all Federal-aid construction projects exceeding \$2,000 and to all related subcontracts and lower-tier subcontracts (regardless of subcontract size), in accordance with 29 CFR 5.5. The requirements apply to all projects located within the right-of-way of a roadway that is functionally classified as Federal-aid highway. 23 U.S.C. 113. This excludes roadways functionally classified as local roads or rural minor collectors, which are exempt. 23 U.S.C. 101. Where applicable law requires that projects be treated as a project on a Federal-aid highway, the provisions of this subpart will apply regardless of the location of the project. Examples include: Surface Transportation Block Grant Program projects funded under 23 U.S.C. 133 [excluding recreational trails projects], the Nationally Significant Freight and Highway

Projects funded under 23 U.S.C. 117, and National Highway Freight Program projects funded under 23 U.S.C. 167.

The following provisions are from the U.S. Department of Labor regulations in 29 CFR 5.5 "Contract provisions and related matters" with minor revisions to conform to the FHWA-1273 format and FHWA program requirements.

1. Minimum wages (29 CFR 5.5)

- a. Wage rates and fringe benefits. All laborers and mechanics employed or working upon the site of the work (or otherwise working in construction or development of the project under a development statute), will be paid unconditionally and not less often than once a week, and without subsequent deduction or rebate on any account (except such payroll deductions as are permitted by regulations issued by the Secretary of Labor under the Copeland Act (29 CFR part 3)), the full amount of basic hourly wages and bona fide fringe benefits (or cash equivalents thereof) due at time of payment computed at rates not less than those contained in the wage determination of the Secretary of Labor which is attached hereto and made a part hereof, regardless of any contractual relationship which may be alleged to exist between the contractor and such laborers and mechanics. As provided in paragraphs (d) and (e) of 29 CFR 5.5, the appropriate wage determinations are effective by operation of law even if they have not been attached to the contract. Contributions made or costs reasonably anticipated for bona fide fringe benefits under the Davis-Bacon Act (40 U.S.C. 3141(2)(B)) on behalf of laborers or mechanics are considered wages paid to such laborers or mechanics, subject to the provisions of paragraph 1.e. of this section; also, regular contributions made or costs incurred for more than a weekly period (but not less often than quarterly) under plans, funds, or programs which cover the particular weekly period, are deemed to be constructively made or incurred during such weekly period. Such laborers and mechanics must be paid the appropriate wage rate and fringe benefits on the wage determination for the classification(s) of work actually performed, without regard to skill, except as provided in paragraph 4. of this section. Laborers or mechanics performing work in more than one classification may be compensated at the rate specified for each classification for the time actually worked therein: Provided, That the employer's payroll records accurately set forth the time spent in each classification in which work is performed. The wage determination (including any additional classifications and wage rates conformed under paragraph 1.c. of this section) and the Davis-Bacon poster (WH-1321) must be posted at all times by the contractor and its subcontractors at the site of the work in a prominent and accessible place where it can be easily seen by the workers.
- b. Frequently recurring classifications. (1) In addition to wage and fringe benefit rates that have been determined to be prevailing under the procedures set forth in 29 CFR part 1, a wage determination may contain, pursuant to § 1.3(f), wage and fringe benefit rates for classifications of laborers and mechanics for which conformance requests are regularly submitted pursuant to paragraph 1.c. of this section, provided that:
 - (i) The work performed by the classification is not performed by a classification in the wage determination for which a prevailing wage rate has been determined;

- (ii) The classification is used in the area by the construction industry; and
- (iii) The wage rate for the classification bears a reasonable relationship to the prevailing wage rates contained in the wage determination.
- (2) The Administrator will establish wage rates for such classifications in accordance with paragraph 1.c.(1)(iii) of this section. Work performed in such a classification must be paid at no less than the wage and fringe benefit rate listed on the wage determination for such classification.
- c. Conformance. (1) The contracting officer must require that any class of laborers or mechanics, including helpers, which is not listed in the wage determination and which is to be employed under the contract be classified in conformance with the wage determination. Conformance of an additional classification and wage rate and fringe benefits is appropriate only when the following criteria have been met:
 - (i) The work to be performed by the classification requested is not performed by a classification in the wage determination; and
 - (ii) The classification is used in the area by the construction industry; and
- (iii) The proposed wage rate, including any bona fide fringe benefits, bears a reasonable relationship to the wage rates contained in the wage determination.
- (2) The conformance process may not be used to split, subdivide, or otherwise avoid application of classifications listed in the wage determination.
- (3) If the contractor and the laborers and mechanics to be employed in the classification (if known), or their representatives, and the contracting officer agree on the classification and wage rate (including the amount designated for fringe benefits where appropriate), a report of the action taken will be sent by the contracting officer by email to DBAconformance@dol.gov. The Administrator, or an authorized representative, will approve, modify, or disapprove every additional classification action within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30–day period that additional time is necessary.
- (4) In the event the contractor, the laborers or mechanics to be employed in the classification or their representatives, and the contracting officer do not agree on the proposed classification and wage rate (including the amount designated for fringe benefits, where appropriate), the contracting officer will, by email to <code>DBAconformance@dol.gov</code>, refer the questions, including the views of all interested parties and the recommendation of the contracting officer, to the Administrator for determination. The Administrator, or an authorized representative, will issue a determination within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30–day period that additional time is necessary.
- (5) The contracting officer must promptly notify the contractor of the action taken by the Wage and Hour Division

- under paragraphs 1.c.(3) and (4) of this section. The contractor must furnish a written copy of such determination to each affected worker or it must be posted as a part of the wage determination. The wage rate (including fringe benefits where appropriate) determined pursuant to paragraph 1.c.(3) or (4) of this section must be paid to all workers performing work in the classification under this contract from the first day on which work is performed in the classification.
- d. Fringe benefits not expressed as an hourly rate. Whenever the minimum wage rate prescribed in the contract for a class of laborers or mechanics includes a fringe benefit which is not expressed as an hourly rate, the contractor may either pay the benefit as stated in the wage determination or may pay another bona fide fringe benefit or an hourly cash equivalent thereof.
- e. Unfunded plans. If the contractor does not make payments to a trustee or other third person, the contractor may consider as part of the wages of any laborer or mechanic the amount of any costs reasonably anticipated in providing bona fide fringe benefits under a plan or program, Provided, That the Secretary of Labor has found, upon the written request of the contractor, in accordance with the criteria set forth in § 5.28, that the applicable standards of the Davis-Bacon Act have been met. The Secretary of Labor may require the contractor to set aside in a separate account assets for the meeting of obligations under the plan or program.
- f. *Interest*. In the event of a failure to pay all or part of the wages required by the contract, the contractor will be required to pay interest on any underpayment of wages.

2. Withholding (29 CFR 5.5)

- a. Withholding requirements. The contracting agency may, upon its own action, or must, upon written request of an authorized representative of the Department of Labor, withhold or cause to be withheld from the contractor so much of the accrued payments or advances as may be considered necessary to satisfy the liabilities of the prime contractor or any subcontractor for the full amount of wages and monetary relief, including interest, required by the clauses set forth in this section for violations of this contract, or to satisfy any such liabilities required by any other Federal contract, or federally assisted contract subject to Davis-Bacon labor standards, that is held by the same prime contractor (as defined in § 5.2). The necessary funds may be withheld from the contractor under this contract, any other Federal contract with the same prime contractor, or any other federally assisted contract that is subject to Davis-Bacon labor standards requirements and is held by the same prime contractor, regardless of whether the other contract was awarded or assisted by the same agency, and such funds may be used to satisfy the contractor liability for which the funds were withheld. In the event of a contractor's failure to pay any laborer or mechanic, including any apprentice or helper working on the site of the work all or part of the wages required by the contract, or upon the contractor's failure to submit the required records as discussed in paragraph 3.d. of this section, the contracting agency may on its own initiative and after written notice to the contractor. take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds until such violations have ceased.
- b. Priority to withheld funds. The Department has priority to funds withheld or to be withheld in accordance with paragraph

- 2.a. of this section or Section V, paragraph 3.a., or both, over claims to those funds by:
- (1) A contractor's surety(ies), including without limitation performance bond sureties and payment bond sureties;
 - (2) A contracting agency for its reprocurement costs;
- (3) A trustee(s) (either a court-appointed trustee or a U.S. trustee, or both) in bankruptcy of a contractor, or a contractor's bankruptcy estate;
 - (4) A contractor's assignee(s);
 - (5) A contractor's successor(s); or
- (6) A claim asserted under the Prompt Payment Act, <u>31</u> U.S.C. 3901–3907.

3. Records and certified payrolls (29 CFR 5.5)

- a. Basic record requirements (1) Length of record retention. All regular payrolls and other basic records must be maintained by the contractor and any subcontractor during the course of the work and preserved for all laborers and mechanics working at the site of the work (or otherwise working in construction or development of the project under a development statute) for a period of at least 3 years after all the work on the prime contract is completed.
- (2) Information required. Such records must contain the name; Social Security number; last known address, telephone number, and email address of each such worker; each worker's correct classification(s) of work actually performed; hourly rates of wages paid (including rates of contributions or costs anticipated for bona fide fringe benefits or cash equivalents thereof of the types described in 40 U.S.C. 3141(2)(B) of the Davis-Bacon Act); daily and weekly number of hours actually worked in total and on each covered contract; deductions made; and actual wages paid.
- (3) Additional records relating to fringe benefits. Whenever the Secretary of Labor has found under paragraph 1.e. of this section that the wages of any laborer or mechanic include the amount of any costs reasonably anticipated in providing benefits under a plan or program described in 40 U.S.C. 3141(2)(B) of the Davis-Bacon Act, the contractor must maintain records which show that the commitment to provide such benefits is enforceable, that the plan or program is financially responsible, and that the plan or program has been communicated in writing to the laborers or mechanics affected, and records which show the costs anticipated or the actual cost incurred in providing such benefits.
- (4) Additional records relating to apprenticeship. Contractors with apprentices working under approved programs must maintain written evidence of the registration of apprenticeship programs, the registration of the apprentices, and the ratios and wage rates prescribed in the applicable programs.
- b. Certified payroll requirements (1) Frequency and method of submission. The contractor or subcontractor must submit weekly, for each week in which any DBA- or Related Actscovered work is performed, certified payrolls to the contracting

- agency. The prime contractor is responsible for the submission of all certified payrolls by all subcontractors. A contracting agency or prime contractor may permit or require contractors to submit certified payrolls through an electronic system, as long as the electronic system requires a legally valid electronic signature; the system allows the contractor, the contracting agency, and the Department of Labor to access the certified payrolls upon request for at least 3 years after the work on the prime contract has been completed; and the contracting agency or prime contractor permits other methods of submission in situations where the contractor is unable or limited in its ability to use or access the electronic system.
- (2) Information required. The certified payrolls submitted must set out accurately and completely all of the information required to be maintained under paragraph 3.a.(2) of this section, except that full Social Security numbers and last known addresses, telephone numbers, and email addresses must not be included on weekly transmittals. Instead, the certified payrolls need only include an individually identifying number for each worker (e.g., the last four digits of the worker's Social Security number). The required weekly certified payroll information may be submitted using Optional Form WH-347 or in any other format desired. Optional Form WH-347 is available for this purpose from the Wage and Hour Division website at https://www.dol.gov/sites/dolgov/files/WHD/ legacy/files/wh347/.pdf or its successor website. It is not a violation of this section for a prime contractor to require a subcontractor to provide full Social Security numbers and last known addresses, telephone numbers, and email addresses to the prime contractor for its own records, without weekly submission by the subcontractor to the contracting agency.
- (3) Statement of Compliance. Each certified payroll submitted must be accompanied by a "Statement of Compliance," signed by the contractor or subcontractor, or the contractor's or subcontractor's agent who pays or supervises the payment of the persons working on the contract, and must certify the following:
 - (i) That the certified payroll for the payroll period contains the information required to be provided under paragraph 3.b. of this section, the appropriate information and basic records are being maintained under paragraph 3.a. of this section, and such information and records are correct and complete;
 - (ii) That each laborer or mechanic (including each helper and apprentice) working on the contract during the payroll period has been paid the full weekly wages earned, without rebate, either directly or indirectly, and that no deductions have been made either directly or indirectly from the full wages earned, other than permissible deductions as set forth in 29 CFR part 3; and
 - (iii) That each laborer or mechanic has been paid not less than the applicable wage rates and fringe benefits or cash equivalents for the classification(s) of work actually performed, as specified in the applicable wage determination incorporated into the contract.
- (4) Use of Optional Form WH–347. The weekly submission of a properly executed certification set forth on the reverse side of Optional Form WH–347 will satisfy the requirement for submission of the "Statement of Compliance" required by paragraph 3.b.(3) of this section.

- (5) Signature. The signature by the contractor, subcontractor, or the contractor's or subcontractor's agent must be an original handwritten signature or a legally valid electronic signature.
- (6) Falsification. The falsification of any of the above certifications may subject the contractor or subcontractor to civil or criminal prosecution under 18 U.S.C. 1001 and 31 U.S.C. 3729.
- (7) Length of certified payroll retention. The contractor or subcontractor must preserve all certified payrolls during the course of the work and for a period of 3 years after all the work on the prime contract is completed.
- c. Contracts, subcontracts, and related documents. The contractor or subcontractor must maintain this contract or subcontract and related documents including, without limitation, bids, proposals, amendments, modifications, and extensions. The contractor or subcontractor must preserve these contracts, subcontracts, and related documents during the course of the work and for a period of 3 years after all the work on the prime contract is completed.
- d. Required disclosures and access (1) Required record disclosures and access to workers. The contractor or subcontractor must make the records required under paragraphs 3.a. through 3.c. of this section, and any other documents that the contracting agency, the State DOT, the FHWA, or the Department of Labor deems necessary to determine compliance with the labor standards provisions of any of the applicable statutes referenced by § 5.1, available for inspection, copying, or transcription by authorized representatives of the contracting agency, the State DOT, the FHWA, or the Department of Labor, and must permit such representatives to interview workers during working hours on the job.
- (2) Sanctions for non-compliance with records and worker access requirements. If the contractor or subcontractor fails to submit the required records or to make them available, or refuses to permit worker interviews during working hours on the job, the Federal agency may, after written notice to the contractor, sponsor, applicant, owner, or other entity, as the case may be, that maintains such records or that employs such workers, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds. Furthermore, failure to submit the required records upon request or to make such records available, or to permit worker interviews during working hours on the job, may be grounds for debarment action pursuant to § 5.12. In addition, any contractor or other person that fails to submit the required records or make those records available to WHD within the time WHD requests that the records be produced will be precluded from introducing as evidence in an administrative proceeding under 29 CFR part 6 any of the required records that were not provided or made available to WHD. WHD will take into consideration a reasonable request from the contractor or person for an extension of the time for submission of records. WHD will determine the reasonableness of the request and may consider, among other things, the location of the records and the volume of production.
- (3) Required information disclosures. Contractors and subcontractors must maintain the full Social Security number and last known address, telephone number, and email address

of each covered worker, and must provide them upon request to the contracting agency, the State DOT, the FHWA, the contractor, or the Wage and Hour Division of the Department of Labor for purposes of an investigation or other compliance action

4. Apprentices and equal employment opportunity (29 CFR 5.5)

- a. Apprentices (1) Rate of pay. Apprentices will be permitted to work at less than the predetermined rate for the work they perform when they are employed pursuant to and individually registered in a bona fide apprenticeship program registered with the U.S. Department of Labor, Employment and Training Administration, Office of Apprenticeship (OA), or with a State Apprenticeship Agency recognized by the OA. A person who is not individually registered in the program, but who has been certified by the OA or a State Apprenticeship Agency (where appropriate) to be eligible for probationary employment as an apprentice, will be permitted to work at less than the predetermined rate for the work they perform in the first 90 days of probationary employment as an apprentice in such a program. In the event the OA or a State Apprenticeship Agency recognized by the OA withdraws approval of an apprenticeship program, the contractor will no longer be permitted to use apprentices at less than the applicable predetermined rate for the work performed until an acceptable program is approved.
- (2) Fringe benefits. Apprentices must be paid fringe benefits in accordance with the provisions of the apprenticeship program. If the apprenticeship program does not specify fringe benefits, apprentices must be paid the full amount of fringe benefits listed on the wage determination for the applicable classification. If the Administrator determines that a different practice prevails for the applicable apprentice classification, fringe benefits must be paid in accordance with that determination.
- (3) Apprenticeship ratio. The allowable ratio of apprentices to journeyworkers on the job site in any craft classification must not be greater than the ratio permitted to the contractor as to the entire work force under the registered program or the ratio applicable to the locality of the project pursuant to paragraph 4.a.(4) of this section. Any worker listed on a payroll at an apprentice wage rate, who is not registered or otherwise employed as stated in paragraph 4.a.(1) of this section, must be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed. In addition, any apprentice performing work on the job site in excess of the ratio permitted under this section must be paid not less than the applicable wage rate on the wage determination for the work actually performed.
- (4) Reciprocity of ratios and wage rates. Where a contractor is performing construction on a project in a locality other than the locality in which its program is registered, the ratios and wage rates (expressed in percentages of the journeyworker's hourly rate) applicable within the locality in which the construction is being performed must be observed. If there is no applicable ratio or wage rate for the locality of the project, the ratio and wage rate specified in the contractor's registered program must be observed.
- b. Equal employment opportunity. The use of apprentices and journeyworkers under this part must be in conformity with

the equal employment opportunity requirements of Executive Order 11246, as amended, and 29 CFR part 30.

c. Apprentices and Trainees (programs of the U.S. DOT).

Apprentices and trainees working under apprenticeship and skill training programs which have been certified by the Secretary of Transportation as promoting EEO in connection with Federal-aid highway construction programs are not subject to the requirements of paragraph 4 of this Section IV. 23 CFR 230.111(e)(2). The straight time hourly wage rates for apprentices and trainees under such programs will be established by the particular programs. The ratio of apprentices and trainees to journeyworkers shall not be greater than permitted by the terms of the particular program.

- **5. Compliance with Copeland Act requirements.** The contractor shall comply with the requirements of 29 CFR part 3, which are incorporated by reference in this contract as provided in 29 CFR 5.5.
- **6. Subcontracts**. The contractor or subcontractor must insert FHWA-1273 in any subcontracts, along with the applicable wage determination(s) and such other clauses or contract modifications as the contracting agency may by appropriate instructions require, and a clause requiring the subcontractors to include these clauses and wage determination(s) in any lower tier subcontracts. The prime contractor is responsible for the compliance by any subcontractor or lower tier subcontractor with all the contract clauses in this section. In the event of any violations of these clauses, the prime contractor and any subcontractor(s) responsible will be liable for any unpaid wages and monetary relief, including interest from the date of the underpayment or loss, due to any workers of lower-tier subcontractors, and may be subject to debarment, as appropriate. 29 CFR 5.5.
- **7. Contract termination: debarment.** A breach of the contract clauses in 29 CFR 5.5 may be grounds for termination of the contract, and for debarment as a contractor and a subcontractor as provided in 29 CFR 5.12.
- **8.** Compliance with Davis-Bacon and Related Act requirements. All rulings and interpretations of the Davis-Bacon and Related Acts contained in 29 CFR parts 1, 3, and 5 are herein incorporated by reference in this contract as provided in 29 CFR 5.5.
- 9. Disputes concerning labor standards. As provided in 29 CFR 5.5, disputes arising out of the labor standards provisions of this contract shall not be subject to the general disputes clause of this contract. Such disputes shall be resolved in accordance with the procedures of the Department of Labor set forth in 29 CFR parts 5, 6, and 7. Disputes within the meaning of this clause include disputes between the contractor (or any of its subcontractors) and the contracting agency, the U.S. Department of Labor, or the employees or their representatives.
- 10. Certification of eligibility. a. By entering into this contract, the contractor certifies that neither it nor any person or firm who has an interest in the contractor's firm is a person or firm ineligible to be awarded Government contracts by virtue of $\underline{40}$ $\underline{\text{U.S.C. }3144(b)}$ or § 5.12(a).

- b. No part of this contract shall be subcontracted to any person or firm ineligible for award of a Government contract by virtue of 40 U.S.C. 3144(b) or § 5.12(a).
- c. The penalty for making false statements is prescribed in the U.S. Code, Title 18 Crimes and Criminal Procedure, $\underline{18}$ U.S.C. 1001.
- **11. Anti-retaliation**. It is unlawful for any person to discharge, demote, intimidate, threaten, restrain, coerce, blacklist, harass, or in any other manner discriminate against, or to cause any person to discharge, demote, intimidate, threaten, restrain, coerce, blacklist, harass, or in any other manner discriminate against, any worker or job applicant for:
- a. Notifying any contractor of any conduct which the worker reasonably believes constitutes a violation of the DBA, Related Acts, this part, or 29 CFR part 1 or 3;
- b. Filing any complaint, initiating or causing to be initiated any proceeding, or otherwise asserting or seeking to assert on behalf of themselves or others any right or protection under the DBA, Related Acts, this part, or 29 CFR part 1 or 3;
- c. Cooperating in any investigation or other compliance action, or testifying in any proceeding under the DBA, Related Acts, this part, or 29 CFR part 1 or 3; or
- d. Informing any other person about their rights under the DBA, Related Acts, this part, or 29 CFR part 1 or 3.

V. CONTRACT WORK HOURS AND SAFETY STANDARDS ACT

Pursuant to 29 CFR 5.5(b), the following clauses apply to any Federal-aid construction contract in an amount in excess of \$100,000 and subject to the overtime provisions of the Contract Work Hours and Safety Standards Act. These clauses shall be inserted in addition to the clauses required by 29 CFR 5.5(a) or 29 CFR 4.6. As used in this paragraph, the terms laborers and mechanics include watchpersons and guards.

- 1. Overtime requirements. No contractor or subcontractor contracting for any part of the contract work which may require or involve the employment of laborers or mechanics shall require or permit any such laborer or mechanic in any workweek in which he or she is employed on such work to work in excess of forty hours in such workweek unless such laborer or mechanic receives compensation at a rate not less than one and one-half times the basic rate of pay for all hours worked in excess of forty hours in such workweek. 29 CFR 5.5.
- 2. Violation; liability for unpaid wages; liquidated damages. In the event of any violation of the clause set forth in paragraph 1. of this section the contractor and any subcontractor responsible therefor shall be liable for the unpaid wages and interest from the date of the underpayment. In addition, such contractor and subcontractor shall be liable to the United States (in the case of work done under contract for the District of Columbia or a territory, to such District or to such territory), for liquidated damages shall be computed with respect to each individual laborer or

mechanic, including watchpersons and guards, employed in violation of the clause set forth in paragraph 1. of this section, in the sum currently provided in 29 CFR 5.5(b)(2)* for each calendar day on which such individual was required or permitted to work in excess of the standard workweek of forty hours without payment of the overtime wages required by the clause set forth in paragraph 1. of this section.

* \$31 as of January 15, 2023 (See 88 FR 88 FR 2210) as may be adjusted annually by the Department of Labor, pursuant to the Federal Civil Penalties Inflation Adjustment Act of 1990.

3. Withholding for unpaid wages and liquidated damages

- a. Withholding process. The FHWA or the contracting agency may, upon its own action, or must, upon written request of an authorized representative of the Department of Labor, withhold or cause to be withheld from the contractor so much of the accrued payments or advances as may be considered necessary to satisfy the liabilities of the prime contractor or any subcontractor for any unpaid wages; monetary relief, including interest; and liquidated damages required by the clauses set forth in this section on this contract, any other Federal contract with the same prime contractor, or any other federally assisted contract subject to the Contract Work Hours and Safety Standards Act that is held by the same prime contractor (as defined in § 5.2). The necessary funds may be withheld from the contractor under this contract, any other Federal contract with the same prime contractor, or any other federally assisted contract that is subject to the Contract Work Hours and Safety Standards Act and is held by the same prime contractor, regardless of whether the other contract was awarded or assisted by the same agency, and such funds may be used to satisfy the contractor liability for which the funds were withheld.
- b. *Priority to withheld funds*. The Department has priority to funds withheld or to be withheld in accordance with Section IV paragraph 2.a. or paragraph 3.a. of this section, or both, over claims to those funds by:
- (1) A contractor's surety(ies), including without limitation performance bond sureties and payment bond sureties;
 - (2) A contracting agency for its reprocurement costs;
- (3) A trustee(s) (either a court-appointed trustee or a U.S. trustee, or both) in bankruptcy of a contractor, or a contractor's bankruptcy estate;
 - (4) A contractor's assignee(s);
 - (5) A contractor's successor(s); or
- (6) A claim asserted under the Prompt Payment Act, <u>31</u> U.S.C. 3901–3907.
- **4. Subcontracts.** The contractor or subcontractor must insert in any subcontracts the clauses set forth in paragraphs 1. through 5. of this section and a clause requiring the subcontractors to include these clauses in any lower tier subcontracts. The prime contractor is responsible for compliance by any subcontractor or lower tier subcontractor with the clauses set forth in paragraphs 1. through 5. In the

event of any violations of these clauses, the prime contractor and any subcontractor(s) responsible will be liable for any unpaid wages and monetary relief, including interest from the date of the underpayment or loss, due to any workers of lower-tier subcontractors, and associated liquidated damages and may be subject to debarment, as appropriate.

- **5. Anti-retaliation.** It is unlawful for any person to discharge, demote, intimidate, threaten, restrain, coerce, blacklist, harass, or in any other manner discriminate against, or to cause any person to discharge, demote, intimidate, threaten, restrain, coerce, blacklist, harass, or in any other manner discriminate against, any worker or job applicant for:
- a. Notifying any contractor of any conduct which the worker reasonably believes constitutes a violation of the Contract Work Hours and Safety Standards Act (CWHSSA) or its implementing regulations in this part;
- b. Filing any complaint, initiating or causing to be initiated any proceeding, or otherwise asserting or seeking to assert on behalf of themselves or others any right or protection under CWHSSA or this part;
- c. Cooperating in any investigation or other compliance action, or testifying in any proceeding under CWHSSA or this part; or
- d. Informing any other person about their rights under CWHSSA or this part.

VI. SUBLETTING OR ASSIGNING THE CONTRACT

This provision is applicable to all Federal-aid construction contracts on the National Highway System pursuant to 23 CFR 635.116.

- 1. The contractor shall perform with its own organization contract work amounting to not less than 30 percent (or a greater percentage if specified elsewhere in the contract) of the total original contract price, excluding any specialty items designated by the contracting agency. Specialty items may be performed by subcontract and the amount of any such specialty items performed may be deducted from the total original contract price before computing the amount of work required to be performed by the contractor's own organization (23 CFR 635.116).
- a. The term "perform work with its own organization" in paragraph 1 of Section VI refers to workers employed or leased by the prime contractor, and equipment owned or rented by the prime contractor, with or without operators. Such term does not include employees or equipment of a subcontractor or lower tier subcontractor, agents of the prime contractor, or any other assignees. The term may include payments for the costs of hiring leased employees from an employee leasing firm meeting all relevant Federal and State regulatory requirements. Leased employees may only be included in this term if the prime contractor meets all of the following conditions: (based on longstanding interpretation)
- the prime contractor maintains control over the supervision of the day-to-day activities of the leased employees;
 - (2) the prime contractor remains responsible for the quality of the work of the leased employees;

- (3) the prime contractor retains all power to accept or exclude individual employees from work on the project; and
 - (4) the prime contractor remains ultimately responsible for the payment of predetermined minimum wages, the submission of payrolls, statements of compliance and all other Federal regulatory requirements.
- b. "Specialty Items" shall be construed to be limited to work that requires highly specialized knowledge, abilities, or equipment not ordinarily available in the type of contracting organizations qualified and expected to bid or propose on the contract as a whole and in general are to be limited to minor components of the overall contract. 23 CFR 635.102.
- 2. Pursuant to 23 CFR 635.116(a), the contract amount upon which the requirements set forth in paragraph (1) of Section VI is computed includes the cost of material and manufactured products which are to be purchased or produced by the contractor under the contract provisions.
- 3. Pursuant to 23 CFR 635.116(c), the contractor shall furnish (a) a competent superintendent or supervisor who is employed by the firm, has full authority to direct performance of the work in accordance with the contract requirements, and is in charge of all construction operations (regardless of who performs the work) and (b) such other of its own organizational resources (supervision, management, and engineering services) as the contracting officer determines is necessary to assure the performance of the contract.
- 4. No portion of the contract shall be sublet, assigned or otherwise disposed of except with the written consent of the contracting officer, or authorized representative, and such consent when given shall not be construed to relieve the contractor of any responsibility for the fulfillment of the contract. Written consent will be given only after the contracting agency has assured that each subcontract is evidenced in writing and that it contains all pertinent provisions and requirements of the prime contract. (based on long-standing interpretation of 23 CFR 635.116).
- 5. The 30-percent self-performance requirement of paragraph (1) is not applicable to design-build contracts; however, contracting agencies may establish their own self-performance requirements. 23 CFR 635.116(d).

VII. SAFETY: ACCIDENT PREVENTION

This provision is applicable to all Federal-aid construction contracts and to all related subcontracts.

- 1. In the performance of this contract the contractor shall comply with all applicable Federal, State, and local laws governing safety, health, and sanitation (23 CFR Part 635). The contractor shall provide all safeguards, safety devices and protective equipment and take any other needed actions as it determines, or as the contracting officer may determine, to be reasonably necessary to protect the life and health of employees on the job and the safety of the public and to protect property in connection with the performance of the work covered by the contract. 23 CFR 635.108.
- 2. It is a condition of this contract, and shall be made a condition of each subcontract, which the contractor enters into pursuant to this contract, that the contractor and any subcontractor shall not permit any employee, in performance of the contract, to work in surroundings or under conditions which are unsanitary, hazardous or dangerous to his/her health or safety, as determined under construction safety and

health standards (29 CFR Part 1926) promulgated by the Secretary of Labor, in accordance with Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C. 3704). 29 CFR 1926.10.

3. Pursuant to 29 CFR 1926.3, it is a condition of this contract that the Secretary of Labor or authorized representative thereof, shall have right of entry to any site of contract performance to inspect or investigate the matter of compliance with the construction safety and health standards and to carry out the duties of the Secretary under Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C. 3704).

VIII. FALSE STATEMENTS CONCERNING HIGHWAY PROJECTS

This provision is applicable to all Federal-aid construction contracts and to all related subcontracts.

In order to assure high quality and durable construction in conformity with approved plans and specifications and a high degree of reliability on statements and representations made by engineers, contractors, suppliers, and workers on Federal-aid highway projects, it is essential that all persons concerned with the project perform their functions as carefully, thoroughly, and honestly as possible. Willful falsification, distortion, or misrepresentation with respect to any facts related to the project is a violation of Federal law. To prevent any misunderstanding regarding the seriousness of these and similar acts, Form FHWA-1022 shall be posted on each Federal-aid highway project (23 CFR Part 635) in one or more places where it is readily available to all persons concerned with the project:

18 U.S.C. 1020 reads as follows:

"Whoever, being an officer, agent, or employee of the United States, or of any State or Territory, or whoever, whether a person, association, firm, or corporation, knowingly makes any false statement, false representation, or false report as to the character, quality, quantity, or cost of the material used or to be used, or the quantity or quality of the work performed or to be performed, or the cost thereof in connection with the submission of plans, maps, specifications, contracts, or costs of construction on any highway or related project submitted for approval to the Secretary of Transportation; or

Whoever knowingly makes any false statement, false representation, false report or false claim with respect to the character, quality, quantity, or cost of any work performed or to be performed, or materials furnished or to be furnished, in connection with the construction of any highway or related project approved by the Secretary of Transportation; or

Whoever knowingly makes any false statement or false representation as to material fact in any statement, certificate, or report submitted pursuant to provisions of the Federal-aid Roads Act approved July 11, 1916, (39 Stat. 355), as amended and supplemented;

Shall be fined under this title or imprisoned not more than 5 years or both."

IX. IMPLEMENTATION OF CLEAN AIR ACT AND FEDERAL WATER POLLUTION CONTROL ACT (42 U.S.C. 7606; 2 CFR 200.88; EO 11738)

This provision is applicable to all Federal-aid construction contracts in excess of \$150,000 and to all related subcontracts. 48 CFR 2.101; 2 CFR 200.327.

By submission of this bid/proposal or the execution of this contract or subcontract, as appropriate, the bidder, proposer, Federal-aid construction contractor, subcontractor, supplier, or vendor agrees to comply with all applicable standards, orders or regulations issued pursuant to the Clean Air Act (42 U.S.C. 7401-7671q) and the Federal Water Pollution Control Act, as amended (33 U.S.C. 1251-1387). Violations must be reported to the Federal Highway Administration and the Regional Office of the Environmental Protection Agency. 2 CFR Part 200, Appendix II.

The contractor agrees to include or cause to be included the requirements of this Section in every subcontract, and further agrees to take such action as the contracting agency may direct as a means of enforcing such requirements. 2 CFR 200.327.

X. CERTIFICATION REGARDING DEBARMENT, SUSPENSION, INELIGIBILITY AND VOLUNTARY EXCLUSION

This provision is applicable to all Federal-aid construction contracts, design-build contracts, subcontracts, lower-tier subcontracts, purchase orders, lease agreements, consultant contracts or any other covered transaction requiring FHWA approval or that is estimated to cost \$25,000 or more – as defined in 2 CFR Parts 180 and 1200. 2 CFR 180.220 and 1200.220.

1. Instructions for Certification – First Tier Participants:

- a. By signing and submitting this proposal, the prospective first tier participant is providing the certification set out below.
- b. The inability of a person to provide the certification set out below will not necessarily result in denial of participation in this covered transaction. The prospective first tier participant shall submit an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective first tier participant to furnish a certification or an explanation shall disqualify such a person from participation in this transaction. 2 CFR 180.320.
- c. The certification in this clause is a material representation of fact upon which reliance was placed when the contracting agency determined to enter into this transaction. If it is later determined that the prospective participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the contracting agency may terminate this transaction for cause of default. 2 CFR 180.325.
- d. The prospective first tier participant shall provide immediate written notice to the contracting agency to whom this proposal is submitted if any time the prospective first tier participant learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances. 2 CFR 180.345 and 180.350.

- e. The terms "covered transaction," "debarred,"
 "suspended," "ineligible," "participant," "person," "principal,"
 and "voluntarily excluded," as used in this clause, are defined
 in 2 CFR Parts 180, Subpart I, 180.900-180.1020, and 1200.
 "First Tier Covered Transactions" refers to any covered
 transaction between a recipient or subrecipient of Federal
 funds and a participant (such as the prime or general contract).
 "Lower Tier Covered Transactions" refers to any covered
 transaction under a First Tier Covered Transaction (such as
 subcontracts). "First Tier Participant" refers to the participant
 who has entered into a covered transaction with a recipient or
 subrecipient of Federal funds (such as the prime or general
 contractor). "Lower Tier Participant" refers any participant who
 has entered into a covered transaction with a First Tier
 Participant or other Lower Tier Participants (such as
 subcontractors and suppliers).
- f. The prospective first tier participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency entering into this transaction. 2 CFR 180.330.
- g. The prospective first tier participant further agrees by submitting this proposal that it will include the clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transactions," provided by the department or contracting agency, entering into this covered transaction, without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions exceeding the \$25,000 threshold. 2 CFR 180.220 and 180.300.
- h. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. 2 CFR 180.300; 180.320, and 180.325. A participant is responsible for ensuring that its principals are not suspended, debarred, or otherwise ineligible to participate in covered transactions. 2 CFR 180.335. To verify the eligibility of its principals, as well as the eligibility of any lower tier prospective participants, each participant may, but is not required to, check the System for Award Management website (https://www.sam.gov/). 2 CFR 180.300, 180.320, and 180.325.
- i. Nothing contained in the foregoing shall be construed to require the establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of the prospective participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
- j. Except for transactions authorized under paragraph (f) of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency may terminate this transaction for cause or default. 2 CFR 180.325.

* * * * *

2. Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion – First Tier Participants:

- a. The prospective first tier participant certifies to the best of its knowledge and belief, that it and its principals:
- (1) Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participating in covered transactions by any Federal department or agency, 2 CFR 180.335;.
- (2) Have not within a three-year period preceding this proposal been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State, or local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements, or receiving stolen property, 2 CFR 180.800;
- (3) Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offenses enumerated in paragraph (a)(2) of this certification, 2 CFR 180.700 and 180.800: and
- (4) Have not within a three-year period preceding this application/proposal had one or more public transactions (Federal, State or local) terminated for cause or default. 2 CFR 180.335(d).
- (5) Are not a corporation that has been convicted of a felony violation under any Federal law within the two-year period preceding this proposal (USDOT Order 4200.6 implementing appropriations act requirements); and
- (6) Are not a corporation with any unpaid Federal tax liability that has been assessed, for which all judicial and administrative remedies have been exhausted, or have lapsed, and that is not being paid in a timely manner pursuant to an agreement with the authority responsible for collecting the tax liability (USDOT Order 4200.6 implementing appropriations act requirements).
- b. Where the prospective participant is unable to certify to any of the statements in this certification, such prospective participant should attach an explanation to this proposal. 2 CFR 180.335 and 180.340.

* * * * *

3. Instructions for Certification - Lower Tier Participants:

(Applicable to all subcontracts, purchase orders, and other lower tier transactions requiring prior FHWA approval or estimated to cost \$25,000 or more - 2 CFR Parts 180 and 1200). 2 CFR 180.220 and 1200.220.

- a. By signing and submitting this proposal, the prospective lower tier participant is providing the certification set out below.
- b. The certification in this clause is a material representation of fact upon which reliance was placed when this transaction was entered into. If it is later determined that the prospective lower tier participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the department, or agency with which

this transaction originated may pursue available remedies, including suspension and/or debarment.

- c. The prospective lower tier participant shall provide immediate written notice to the person to which this proposal is submitted if at any time the prospective lower tier participant learns that its certification was erroneous by reason of changed circumstances. 2 CFR 180.365.
- d. The terms "covered transaction," "debarred," "suspended," "ineligible," "participant," "person," "principal," and "voluntarily excluded," as used in this clause, are defined in 2 CFR Parts 180, Subpart I, 180.900 – 180.1020, and 1200. You may contact the person to which this proposal is submitted for assistance in obtaining a copy of those regulations. "First Tier Covered Transactions" refers to any covered transaction between a recipient or subrecipient of Federal funds and a participant (such as the prime or general contract). "Lower Tier Covered Transactions" refers to any covered transaction under a First Tier Covered Transaction (such as subcontracts). "First Tier Participant" refers to the participant who has entered into a covered transaction with a recipient or subrecipient of Federal funds (such as the prime or general contractor). "Lower Tier Participant" refers any participant who has entered into a covered transaction with a First Tier Participant or other Lower Tier Participants (such as subcontractors and suppliers).
- e. The prospective lower tier participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency with which this transaction originated. 2 CFR 1200.220 and 1200.332.
- f. The prospective lower tier participant further agrees by submitting this proposal that it will include this clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions exceeding the \$25,000 threshold. 2 CFR 180.220 and 1200.220.
- g. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant is responsible for ensuring that its principals are not suspended, debarred, or otherwise ineligible to participate in covered transactions. To verify the eligibility of its principals, as well as the eligibility of any lower tier prospective participants, each participant may, but is not required to, check the System for Award Management website (https://www.sam.gov/), which is compiled by the General Services Administration. 2 CFR 180.300, 180.320, 180.330, and 180.335.
- h. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.
- i. Except for transactions authorized under paragraph e of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily

excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment. 2 CFR 180.325.

* * * * *

4. Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion--Lower Tier Participants:

- a. The prospective lower tier participant certifies, by submission of this proposal, that neither it nor its principals:
- (1) is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participating in covered transactions by any Federal department or agency, 2 CFR 180.355;
- (2) is a corporation that has been convicted of a felony violation under any Federal law within the two-year period preceding this proposal (USDOT Order 4200.6 implementing appropriations act requirements); and
- (3) is a corporation with any unpaid Federal tax liability that has been assessed, for which all judicial and administrative remedies have been exhausted, or have lapsed, and that is not being paid in a timely manner pursuant to an agreement with the authority responsible for collecting the tax liability. (USDOT Order 4200.6 implementing appropriations act requirements)
- b. Where the prospective lower tier participant is unable to certify to any of the statements in this certification, such prospective participant should attach an explanation to this proposal.

* * * * *

XI. CERTIFICATION REGARDING USE OF CONTRACT FUNDS FOR LOBBYING

This provision is applicable to all Federal-aid construction contracts and to all related subcontracts which exceed \$100,000. 49 CFR Part 20, App. A.

- 1. The prospective participant certifies, by signing and submitting this bid or proposal, to the best of his or her knowledge and belief. that:
- a. No Federal appropriated funds have been paid or will be paid, by or on behalf of the undersigned, to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with the awarding of any Federal contract, the making of any Federal grant, the making of any Federal loan, the entering into of any cooperative agreement, and the extension, continuation, renewal, amendment, or modification of any Federal contract, grant, loan, or cooperative agreement.
- b. If any funds other than Federal appropriated funds have been paid or will be paid to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with this Federal contract, grant, loan, or

cooperative agreement, the undersigned shall complete and submit Standard Form-LLL, "Disclosure Form to Report Lobbying," in accordance with its instructions.

- 2. This certification is a material representation of fact upon which reliance was placed when this transaction was made or entered into. Submission of this certification is a prerequisite for making or entering into this transaction imposed by 31 U.S.C. 1352. Any person who fails to file the required certification shall be subject to a civil penalty of not less than \$10,000 and not more than \$100,000 for each such failure.
- 3. The prospective participant also agrees by submitting its bid or proposal that the participant shall require that the language of this certification be included in all lower tier subcontracts, which exceed \$100,000 and that all such recipients shall certify and disclose accordingly.

XII. USE OF UNITED STATES-FLAG VESSELS:

This provision is applicable to all Federal-aid construction contracts, design-build contracts, subcontracts, lower-tier subcontracts, purchase orders, lease agreements, or any other covered transaction. 46 CFR Part 381.

This requirement applies to material or equipment that is acquired for a specific Federal-aid highway project. 46 CFR 381.7. It is not applicable to goods or materials that come into inventories independent of an FHWA funded-contract.

When oceanic shipments (or shipments across the Great Lakes) are necessary for materials or equipment acquired for a specific Federal-aid construction project, the bidder, proposer, contractor, subcontractor, or vendor agrees:

- 1. To utilize privately owned United States-flag commercial vessels to ship at least 50 percent of the gross tonnage (computed separately for dry bulk carriers, dry cargo liners, and tankers) involved, whenever shipping any equipment, material, or commodities pursuant to this contract, to the extent such vessels are available at fair and reasonable rates for United States-flag commercial vessels. 46 CFR 381.7.
- 2. To furnish within 20 days following the date of loading for shipments originating within the United States or within 30 working days following the date of loading for shipments originating outside the United States, a legible copy of a rated, 'on-board' commercial ocean bill-of-lading in English for each shipment of cargo described in paragraph (b)(1) of this section to both the Contracting Officer (through the prime contractor in the case of subcontractor bills-of-lading) and to the Office of Cargo and Commercial Sealift (MAR-620), Maritime Administration, Washington, DC 20590. (MARAD requires copies of the ocean carrier's (master) bills of lading, certified onboard, dated, with rates and charges. These bills of lading may contain business sensitive information and therefore may be submitted directly to MARAD by the Ocean Transportation Intermediary on behalf of the contractor). 46 CFR 381.7.

ATTACHMENT A - EMPLOYMENT AND MATERIALS PREFERENCE FOR APPALACHIAN DEVELOPMENT HIGHWAY SYSTEM OR APPALACHIAN LOCAL ACCESS ROAD CONTRACTS (23 CFR 633, Subpart B, Appendix B) This provision is applicable to all Federal-aid projects funded under the Appalachian Regional Development Act of 1965.

- 1. During the performance of this contract, the contractor undertaking to do work which is, or reasonably may be, done as on-site work, shall give preference to qualified persons who regularly reside in the labor area as designated by the DOL wherein the contract work is situated, or the subregion, or the Appalachian counties of the State wherein the contract work is situated, except:
- a. To the extent that qualified persons regularly residing in the area are not available.
- b. For the reasonable needs of the contractor to employ supervisory or specially experienced personnel necessary to assure an efficient execution of the contract work.
- c. For the obligation of the contractor to offer employment to present or former employees as the result of a lawful collective bargaining contract, provided that the number of nonresident persons employed under this subparagraph (1c) shall not exceed 20 percent of the total number of employees employed by the contractor on the contract work, except as provided in subparagraph (4) below.
- 2. The contractor shall place a job order with the State Employment Service indicating (a) the classifications of the laborers, mechanics and other employees required to perform the contract work, (b) the number of employees required in each classification, (c) the date on which the participant estimates such employees will be required, and (d) any other pertinent information required by the State Employment Service to complete the job order form. The job order may be placed with the State Employment Service in writing or by telephone. If during the course of the contract work, the information submitted by the contractor in the original job order is substantially modified, the participant shall promptly notify the State Employment Service.
- 3. The contractor shall give full consideration to all qualified job applicants referred to him by the State Employment Service. The contractor is not required to grant employment to any job applicants who, in his opinion, are not qualified to perform the classification of work required.
- 4. If, within one week following the placing of a job order by the contractor with the State Employment Service, the State Employment Service is unable to refer any qualified job applicants to the contractor, or less than the number requested, the State Employment Service will forward a certificate to the contractor indicating the unavailability of applicants. Such certificate shall be made a part of the contractor's permanent project records. Upon receipt of this certificate, the contractor may employ persons who do not normally reside in the labor area to fill positions covered by the certificate, notwithstanding the provisions of subparagraph (1c) above
- 5. The provisions of 23 CFR 633.207(e) allow the contracting agency to provide a contractual preference for the use of mineral resource materials native to the Appalachian region
- 6. The contractor shall include the provisions of Sections 1 through 4 of this Attachment A in every subcontract for work which is, or reasonably may be, done as on-site work.

NON-DISCRIMINATION PROVISIONS

During the performance of this contract, the contractor, for itself, its assignees, and successors in interest (hereinafter referred to as the "contractor") agrees as follows:

- **1. Compliance with Regulations:** The contractor (hereinafter includes consultants) will comply with the Acts and the Regulations relative to Non-discrimination in Federally-assisted programs of the U.S. Department of Transportation, Federal Highway Administration, as they may be amended from time to time, which are herein incorporated by reference and made a part of this contract.
- **2. Non-discrimination:** The contractor, with regard to the work performed by it during the contract, will not discriminate on the grounds of race, color, or national origin in the selection and retention of subcontractors, including procurements of materials and leases of equipment. The contractor will not participate directly or indirectly in the discrimination prohibited by the Acts and the Regulations, including employment practices when the contract covers any activity, project, or program set forth in Appendix B of 49 CFR Part 21.
- **3. Solicitations for Subcontracts, Including Procurements of Materials and Equipment:** In all solicitations, either by competitive bidding, or negotiation made by the contractor for work to be performed under a subcontract, including procurements of materials, or leases of equipment, each potential subcontractor or supplier will be notified by the contractor of the contractor's obligations under this contract and the Acts and the Regulations relative to Non-discrimination on the grounds of race, color, or national origin.
- **4. Information and Reports:** The contractor will provide all information and reports required by the Acts, the Regulations, and directives issued pursuant thereto and will permit access to its books, records, accounts, other sources of information, and its facilities as may be determined by the Recipient or the Federal Highway Administration to be pertinent to ascertain compliance with such Acts, Regulations, and instructions. Where any information required of a contractor is in the exclusive possession of another who fails or refuses to furnish the information, the contractor will so certify to the Recipient or the Federal Highway Administration, as appropriate, and will set forth what efforts it has made to obtain the information.
- **5. Sanctions for Noncompliance:** In the event of a contractor's noncompliance with the Non-discrimination provisions of this contract, the Recipient will impose such contract sanctions as it or the Federal Highway Administration may determine to be appropriate, including, but not limited to:
 - a. Withholding payments to the contractor under the contract until the contractor complies; and/or
 - b. Cancelling, terminating, or suspending a contract, in whole or in part.
- **6. Incorporation of Provisions:** The contractor will include the provisions of paragraphs one through six in every subcontract, including procurements of materials and leases of equipment, unless exempt by the Acts, the Regulations and directives issued pursuant thereto. The contractor will take action with respect to any subcontract or procurement as the Recipient or the Federal Highway Administration may direct as a means of enforcing such provisions including sanctions for noncompliance. Provided, that if the contractor becomes involved in, or is threatened with litigation by a subcontractor, or supplier because of such direction, the contractor may request the Recipient to enter into any litigation to protect the interests of the Recipient. In addition, the contractor may request the United States to enter into the litigation to protect the interests of the United States.

During the performance of this contract, the contractor, for itself, its assignees, and successors in interest (hereinafter referred to as the "contractor") agrees to comply with the following non-discrimination statutes and authorities; including but not limited to:

Pertinent Non-Discrimination Authorities:

- Title VI of the Civil Rights Act of 1964 (42 U.S.C. § 2000d et seq., 78 stat. 252), (prohibits discrimination on the basis of race, color, national origin); and 49 CFR Part 21.
- The Uniform Relocation Assistance and Real Property Acquisition Policies Act of 1970, (42 U.S.C. § 4601), (prohibits unfair treatment of persons displaced or whose property has been acquired because of Federal or Federal-aid programs and projects);
- Federal-Aid Highway Act of 1973, (23 U.S.C. § 324 et seq.), (prohibits discrimination on the basis of sex);
- Section 504 of the Rehabilitation Act of 1973, (29 U.S.C. § 794 et seq.), as amended, (prohibits discrimination on the basis of disability); and 49 CFR Part 27;
- The Age Discrimination Act of 1975, as amended, (42 U.S.C. § 6101 et seq.), (prohibits discrimination on the basis of age);
- Airport and Airway Improvement Act of 1982, (49 USC § 471, Section 47123), as amended, (prohibits discrimination based on race, creed, color, national origin, or sex);
- The Civil Rights Restoration Act of 1987, (PL 100-209), (Broadened the scope, coverage and applicability of Title VI of the Civil Rights Act of 1964, The Age Discrimination Act of 1975 and Section 504 of the Rehabilitation Act of 1973, by expanding the definition of the terms "programs or activities" to include all of the programs or activities of the Federal-aid recipients, subrecipients and contractors, whether such programs or activities are Federally funded or not);
- Titles II and III of the Americans with Disabilities Act, which prohibit discrimination on the basis of disability in the operation of public entities, public and private transportation systems, places of public accommodation, and certain testing entities (42 U.S.C. §§ 12131-12189) as implemented by Department of Transportation regulations at 49 C.F.R. parts 37 and 38;
- The Federal Aviation Administration's Non-discrimination statute (49 U.S.C. § 47123) (prohibits discrimination on the basis of race, color, national origin, and sex);
- Executive Order 12898, Federal Actions to Address Environmental Justice in Minority Populations and Low-Income Populations, which ensures Non-discrimination against minority populations by discouraging programs, policies, and activities with disproportionately high and adverse human health or environmental effects on minority and low-income populations;
- Executive Order 13166, Improving Access to Services for Persons with Limited English
 Proficiency, and resulting agency guidance, national origin discrimination includes discrimination
 because of Limited English proficiency (LEP). To ensure compliance with Title VI, you must take
 reasonable steps to ensure that LEP persons have meaningful access to your programs (70 Fed.
 Reg. at 74087 to 74100);
- Title IX of the Education Amendments of 1972, as amended, which prohibits you from discriminating because of sex in education programs or activities (20 U.S.C. 1681 et seq).

NOTICE OF REQUIREMENT FOR AFFIRMATIVE ACTION TO ENSURE EQUAL EMPLOYMENT OPPORTUNITY (EXECUTIVE ORDER 11246)

- 1. The Offeror's or Bidder's attention is called to the "Employment Practices" and "Equal Opportunity Clause" set forth in the Required Contract Provisions, FHWA 1273.
- 2. The goals and timetables for minority and female participation expressed in percentage terms for the contractor's aggregate work force in each trade, on all construction work in the covered area, are as follows:

Goals for Minority Participation for Each Trade:

County	<u>%</u>	County	<u>%</u>	County	%
Adams	1.7	Iowa	1.7	Polk	2.2
Ashland	1.2	Iron	1.2	Portage	0.6
Barron	0.6	Jackson	0.6	Price	0.6
Bayfield	1.2	Jefferson	7.0	Racine	8.4
Brown	1.3	Juneau	0.6	Richland	1.7
Buffalo	0.6	Kenosha	3.0	Rock	3.1
Burnett	2.2	Kewaunee	1.0	Rusk	0.6
Calumet	0.9	La Crosse	0.9	St. Croix	2.9
Chippewa	0.5	Lafayette	0.5	Sauk	1.7
Clark	0.6	Langlade	0.6	Sawyer	0.6
Columbia	1.7	Lincoln	0.6	Shawano	1.0
Crawford	0.5	Manitowoc	1.0	Sheboygan	7.0
Dane	2.2	Marathon	0.6	Taylor	0.6
Dodge	7.0	Marinette	1.0	Trempealeau	0.6
Door	1.0	Marquette	1.7	Vernon	0.6
Douglas	1.0	Menominee	1.0	Vilas	0.6
Dunn	0.6	Milwaukee	8.0	Walworth	7.0
Eau Claire	0.5	Monroe	0.6	Washburn	0.6
Florence	1.0	Oconto	1.0	Washington	8.0
Fond du Lac	1.0	Oneida	0.6	Waukesha	8.0
Forest	1.0	Outagamie	0.9	Waupaca	1.0
Grant	0.5	Ozaukee	8.0	Waushara	1.0
Green	1.7	Pepin	0.6	Winnebago	0.9
Green Lake	1.0	Pierce	2.2	Wood	0.6

Goals for female participation for each trade: 6.9%

These goals are applicable to all the contractor's construction work, (whether or not it is federal or federally assisted), performed in the covered area. If the contractor performs construction work in the geographical area located outside of the covered area, it shall apply the goals established for such geographical area where the work is actually performed. With regard to this second area, the contractor also is subject to the goals for both its federally involved and nonfederally involved construction.

The contractor's compliance with the Executive Order and the Regulations in 41 CFR Part 60-4 shall be based on its implementation of the Equal Opportunity Clause, specific affirmative action obligations required by the specifications set forth in 41 CFR 60-4.3(a), and its efforts to meet the goals. The hours of minority and female employment and training must be substantially uniform throughout the length of the contract, and in each trade, and the contractor shall make a good faith effort to employ minorities and women evenly on each of its projects. The transfer of minority or female employees or trainees from contractor to contractor or from project to project for the sole purpose of meeting the contractor's goals shall be a violation of the contract, the Executive Order and the Regulations in 41 CFR Part 60-4. Compliance with the goals will be measured against the total work hours performed.

3. The contractor shall provide written notification to the Director of the Office of Federal Contract Compliance Programs within ten (10) working days of award of any construction subcontract in excess of \$10,000.00 at any tier for construction work under the contract resulting from this solicitation. The notification shall list the name, address and telephone number of the subcontractor, employer identification number of the subcontractor; estimated dollar amount of the subcontract; estimated starting and completion dates of the subcontract; and the geographical area in which the subcontract is to be performed.

As referred to in this section, the Director means:

Director
Office of Federal Contract Compliance Programs
Ruess Federal Plaza
310 W. Wisconsin Ave., Suite 1115
Milwaukee, WI 53202

The "Employer Identification Number" means the Federal Social Security number used on the Employer's Quarterly Federal Tax Return, U.S. Treasury Department Form 941.

4. As used in this notice, and in the contract resulting from solicitation, the "covered area" is the county(ies) in Wisconsin to which this proposal applies.

ADDITIONAL FEDERAL-AID PROVISIONS

NOTICE TO ALL BIDDERS

To report bid rigging activities call:

1-800-424-9071

The U.S. Department of Transportation (DOT) operates the above toll-free "hotline" Monday through Friday, 8:00 a.m. to 5:00 p.m., Eastern Time. Anyone with knowledge of possible bid rigging, bidding collusion, or other fraudulent activities should use the "hotline" to report such activities.

The "hotline" is part of the DOT's continuing effort to identify and investigate highway construction contract fraud and abuse and is operated under the direction of the DOT Inspector General. All information will be treated confidentially and caller anonymity will be respected.

BUY AMERICA PROVISION

Buy America (as documented in <u>88 FR 57750 (2 CFR part 184 and 200)</u> from the Office of Management and Budget: <u>Federal Register: Guidance for Grants and Agreements</u>) shall be domestic products and permanently incorporated in this project as classified in the following three categories, and as noted in the Construction and Materials Manual (CMM):

1. Iron and Steel

All iron and steel manufacturing and coating processes (from the initial melting stage through the application of coatings) must have occurred within the United States. Coating includes epoxy coating, galvanizing, painting and any other coating that protects or enhances the value of a material subject to the requirements of Buy America.

The exemption of the iron and steel manufacturing and coating processes Buy America requirement is the minimal use of foreign materials if the total cost of such material permanently incorporated in the product does not exceed one-tenth of one percent (1/10 of 1%) of the total contract cost or \$2,500.00, whichever is greater. For purposes of this paragraph, the cost is that shown to be the value of the subject products as they are delivered to the project.

2. Manufactured Product

All manufactured products (as defined in CMM 228.5) are covered under a previous waiver from 1983 and are currently exempt from Buy America.

3. Construction Material

All construction materials (as defined in <u>88 FR 57750 (2 CFR part 184 and 200)</u> and as referenced in CMM 228.5) must comply with Buy America. All manufacturing process of construction materials must occur in the United States.

<u>88 FR 55817 (DOT-OST-2022-0124)</u> allows a limited waiver of Buy America requirements for de minimis costs and small grants.

- The Total value of the non-compliant products is no more than the lesser of \$1,000,000 or 5% of total applicable costs for the project¹; or
- The total amount of Federal financial assistance applied to the project, through awards or subaward, is below \$500,000²

The contractor shall take actions and provide documentation conforming to CMM 228.5 to ensure compliance with this Buy America provision.

https://wisconsindot.gov/rdwy/cmm/cm-02-28.pdf

Upon completion of the project, certify to the engineer, in writing using department form DT4567 that all iron and steel, manufactured products, and construction materials conform to this Buy America provision.

Form DT4567 is available at: https://wisconsindot.gov/Documents/formdocs/dt4567.docx

Attach a list of iron or steel and construction material exemptions and their associated costs to the certification form.

¹ The de minimis public interest waiver does not apply to iron and steel subject to the requirements of 23 U.S.C. 313 on financial assistant administered by FHWA. The de minimis threshold in 23 CFR 635.410(b)(4) continues to apply for iron and steel. 2 The small grant portion of the waiver does not apply to iron, steel, and manufactured goods subject to the requirements of 49 U.S.C. 22905(a).

CARGO PREFERENCE ACT REQUIREMENT

All Federal-aid projects shall comply with 46 CFR 381.7 (a) – (b) as follows:

- (a) Agreement Clauses. "Use of United States-flag vessels:"
- (1) Pursuant to Pub. L. 664 (43 U.S.C. 1241(b)) at least 50 percent of any equipment, materials or commodities procured, contracted for or otherwise obtained with funds granted, guaranteed, loaned, or advanced by the U.S. Government under this agreement, and which may be transported by ocean vessel, shall be transported on privately owned United States-flag commercial vessels, if available.
- (2) Within 20 days following the date of loading for shipments originating within the United States or within 30 working days following the date of loading for shipments originating outside the United States, a legible copy of a rated, 'on-board' commercial ocean bill-of-lading in English for each shipment of cargo described in paragraph (a)(1) of this section shall be furnished to both the Contracting Officer (through the prime contractor in the case of subcontractor bills-of-lading) and to the Division of National Cargo, Office of Market Development, Maritime Administration, Washington, DC 20590."
- (b) Contractor and Subcontractor Clauses. "Use of United States-flag vessels: The contractor agrees—"
- (1) To utilize privately owned United States-flag commercial vessels to ship at least 50 percent of the gross tonnage (computed separately for dry bulk carriers, dry cargo liners, and tankers) involved, whenever shipping any equipment, material, or commodities pursuant to this contract, to the extent such vessels are available at fair and reasonable rates for United States-flag commercial vessels.
- (2) To furnish within 20 days following the date of loading for shipments originating within the United States or within 30 working days following the date of loading for shipments originating outside the United States, a legible copy of a rated, 'on-board' commercial ocean bill-of-lading in English for each shipment of cargo described in paragraph (b) (1) of this section to both the Contracting Officer (through the prime contractor in the case of subcontractor bills-of-lading) and to the Division of National Cargo, Office of Market Development, Maritime Administration, Washington, DC 20590.
- (3) To insert the substance of the provisions of this clause in all subcontracts issued pursuant to this contract.

WISCONSIN DEPARTMENT OF TRANSPORTATION DIVISION OF TRANSPORTATION AND SYSTEM DEVELOPMENT

SUPPLEMENTAL REQUIRED CONTRACT PROVISIONS FOR PROJECTS WITH FEDERAL AID

I. PREVAILING WAGE RATES

The attached U.S. Department of Labor (Davis-Bacon Minimum Wage Rates) furnishes the minimum prevailing wage rates pursuant to the Davis-Bacon and Related Acts. The wage rates shown are the minimum rates required by the contract to be paid during its life, however this is not a representation that labor can be obtained at these rates. It is the responsibility of bidders to inform themselves as to the local labor conditions and prospective changes or adjustments of wage rates. No increase in the contract price will be allowed or authorized on account of the payment of wage rates in excess of those listed herein.

II. COVERAGE OF TRUCK DRIVERS

Truck drivers are covered by Davis-Bacon Minimum Wage Rates in the following circumstances:

- Drivers of a contractor or subcontractor for time spent working on the site of the work.
- Drivers of a contractor or subcontractor for time spent loading and/or unloading materials and supplies on the site of the work, if such time is not de minimis. https://www.dol.gov/whd/FOH/FOH Ch15.pdf
- Truck drivers transporting materials or supplies between a facility that is deemed part of the site of the work and the actual construction site.
- Truck drivers transporting portions of the building or work between a site established specifically for the performance of the contract where a significant portion of such building or work is constructed and the physical place where the building or work called for in the contract will remain.

Truck drivers are not covered by Davis-Bacon Minimum Wage Rates in the following circumstances:

- Material delivery truck drivers while off the site of the work.
- Drivers of a contractor or subcontractor traveling between a Davis-Bacon job and a commercial supply facility while they are off the site of the work."
- Truck drivers whose time spent on the site of the work is de minimis, such as only a few
 minutes at a time merely to pick up or drop off materials or supplies.

Details are available online at:

https://www.dol.gov/whd/recovery/pwrb/Tab9.pdf

https://wisconsindot.gov/Pages/doing-bus/civil-rights/labornwage/trckng.aspx

III. POSTINGS AT THE SITE OF THE WORK

In addition to the required postings furnished by the department, the contractor shall post the following in at least one conspicuous and accessible place at the site of work:

a. A copy of the contractor's Equal Employment Opportunity Policy.

All required documents shall be posted by the first day of work and be accurate and complete. Postings must be readable, in an area where they will be noticed, and maintained until the last day of work.

IV. RESOURCES

Required information regarding compliance with federal provisions is found in the following resources:

- FHWA-1273 included in this contract
- U.S. Department of Labor Prevailing Wage Resource Book
- U.S. Department of Labor Field Operations Handbook
- U.S. Code of Federal Regulations
- Any applicable law, Act, or Executive Order enacted by the federal government at the time of the letting of this contract

"General Decision Number: WI20230010 10/13/2023

Superseded General Decision Number: WI20220010

State: Wisconsin

Construction Type: Highway

Counties: Wisconsin Statewide.

HIGHWAY, AIRPORT RUNWAY & TAXIWAY CONSTRUCTION PROJECTS (does not include bridges over navigable waters; tunnels; buildings in highway rest areas; and railroad construction)

Note: Contracts subject to the Davis-Bacon Act are generally required to pay at least the applicable minimum wage rate required under Executive Order 14026 or Executive Order 13658. Please note that these Executive Orders apply to covered contracts entered into by the federal government that are subject to the Davis-Bacon Act itself, but do not apply to contracts subject only to the Davis-Bacon Related Acts, including those set forth at 29 CFR 5.1(a)(2)-(60).

If the contract is entered into on or after January 30, 2022, or the contract is renewed or extended (e.g., an |. The contractor must pay option is exercised) on or after January 30, 2022:

- . Executive Order 14026 generally applies to the contract.
- all covered workers at least \$16.20 per hour (or the applicable wage rate listed on this wage determination, if it is higher) for all hours spent performing on the contract in 2023.

If the contract was awarded on . Executive Order 13658 or between January 1, 2015 and January 29, 2022, and the contract is not renewed or extended on or after January 30, 2022:

- generally applies to the contract.
- The contractor must pay all covered workers at least \$12.15 per hour (or the applicable wage rate listed on this wage determination, if it is higher) for all hours spent performing on that contract in 2023.

The applicable Executive Order minimum wage rate will be adjusted annually. If this contract is covered by one of the Executive Orders and a classification considered necessary for performance of work on the contract does not appear on this wage determination, the contractor must still submit a conformance request.

Additional information on contractor requirements and worker protections under the Executive Orders is available at http://www.dol.gov/whd/govcontracts.

1	01/13/2023
2	01/20/2023
3	03/31/2023
4	04/07/2023
5	05/26/2023
6	06/02/2023
7	06/16/2023
8	06/23/2023
9	07/07/2023
10	07/14/2023
11	07/28/2023
12	08/18/2023
13	09/01/2023
14	09/08/2023
15	10/13/2023

^{*} BRWI0001-002 06/01/2023

CRAWFORD, JACKSON, JUNEAU, LA CROSSE, MONROE, TREMPEALEAU, AND VERNON COUNTIES

	Rates	Fringes
BRICKLAYER	\$ 40.18	25.88
* BRWI0002-002 06/01/2023		
ASHLAND, BAYFIELD, DOUGLAS, AND	IRON COUNTIES	
	Rates	Fringes
BRICKLAYER	\$ 47.10	25.16

^{*} BRWI0002-005 06/01/2023

ADAMS, ASHLAND, BARRON, BROWN, BURNETT, CALUMET, CHIPPEWA, CLARK, COLUMBIA, DODGE, DOOR, DUNN, FLORENCE, FOND DU LAC, FOREST, GREEN LAKE, IRON, JEFFERSON, KEWAUNEE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, OCONTO, ONEIDA, OUTAGAMIE, POLK, PORTAGE, RUSK, ST CROIX, SAUK, SHAWANO, SHEBOYGAN, TAYLOR, VILAS, WALWORTH, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

	Rates	Fringes		
CEMENT MASON/CONCRETE FINISHER	.\$ 39.97	25.02		
* BRWI0003-002 06/01/2023				
BROWN, DOOR, FLORENCE, KEWAUNEE,	MARINETTE, ANI	O OCONTO COUNTIES		
	Rates	Fringes		
BRICKLAYER	.\$ 40.00	26.06		
* BRWI0004-002 06/01/2023				
KENOSHA, RACINE, AND WALWORTH COUNTIES				
	Rates	Fringes		

26.96

BRICKLAYER.....\$ 44.50

* BRWI0006-002 06/01/2023

ADAMS, CLARK, FOREST, LANGLADE, LINCOLN, MARATHON, MENOMINEE, ONEIDA, PORTAGE, PRICE, TAYLOR, VILAS AND WOOD COUNTIES

	Rates	Fringes			
BRICKLAYER	.\$ 40.08	25.98			
* BRWI0007-002 06/01/2023					
GREEN, LAFAYETTE, AND ROCK COUNTIES					
	Rates	Fringes			
BRICKLAYER	.\$ 40.95	26.80			
* BRWI0008-002 06/05/2023					
MILWAUKEE, OZAUKEE, WASHINGTON,	AND WAUKESH	A COUNTIES			
	Rates	Fringes			
BRICKLAYER	•	25.67			
* BRWI0011-002 06/01/2023					
CALUMET, FOND DU LAC, MANITOWOC, AND SHEBOYGAN COUNTIES					
	Rates	Fringes			
BRICKLAYER	.\$ 40.00	26.06			
* BRWI0019-002 06/01/2023					
BARRON, BUFFALO, BURNETT, CHIPPEWA, DUNN, EAU CLAIRE, PEPIN, PIERCE, POLK, RUSK, ST. CROIX, SAWYER AND WASHBURN COUNTIES					
	Rates	Fringes			
BRICKLAYER	.\$ 39.32	26.74			
* BRWI0034-002 06/01/2023					
COLUMBIA AND SAUK COUNTIES					
	Rates	Fringes			
BRICKLAYER					
CARP0068-011 05/02/2022					
BURNETT (W. of Hwy 48), PIERCE (W. of Hwy 29), POLK (W. of Hwys 35, 48 & 65), AND ST. CROIX (W. of Hwy 65) COUNTIES					
	Rates	Fringes			
Carpenter & Piledrivermen		27.05			
* CARP0264-003 06/05/2023					

	Rates	Fringes
CARPENTER		29.72
* CARP0310-002 06/05/2023		
Ashland, Bayfield, Forest, Iron, Oneida, Shawano, Taylor and Vila		ln, Marathon,
	Rates	Fringes
CARPENTERPiledriver	•	27.06 27.02
* CARP0314-001 06/05/2023		
Columbia, Dane, Dodge, Grant, Gr Lafayette, Richland, Rock, Sauk		erson,
	Rates	Fringes
CARPENTERPiledriver	.\$ 39.43	27.06 27.02
CARP0361-004 05/01/2018		
BAYFIELD (West of Hwy 63) AND DO	UGLAS COUNTIES	
	Rates	Fringes
CARPENTER	•	20.43
* CARP0731-002 06/05/2023		
Calumet (Eastern portion of the and Sheboygan	County), Fond Du	Lac, Manitowoc
	Rates	Fringes
CARPENTERPiledriver		27.06 27.02
* CARP0804-001 06/05/2023		
Adams, Juneau, Portage and Wood		
	Rates	Fringes
CARPENTERPiledriver		27.06 27.02
* CARP0955-002 06/05/2023		

Calumet (western portion of County), Fond Du Lac, Green Lake, Marquette, Outagamie and Winnebago

Rates Fringes

CARPENTER	·	27.06	
PILEDRIVER	.\$ 39.43 	27.02	
* CARP1056-002 06/01/2023			
	Rates	Fringes	
MILLWRIGHT		27.77	
* CARP1074-002 06/05/2023			
Barron, Burnett, Chippewa, Clark Pierce, Polk, Rusk, Sawyer, St. (
	Rates	Fringes	
CARPENTER		27.06 27.02	
* CARP1143-002 06/05/2023			
BUFFALO, CRAWFORD, JACKSON, LA CI VERNON COUNTIES	ROSSE, MONROE,	, TREMPEALEAU AND	
	Rates	Fringes	
CARPENTER	.\$ 39.43	27.06 27.02	
* CARP1146-002 06/05/2023			
Brown, Door, Florence, Kewaunee, Shawano	Marinette, Me	enominee and	
	Rates	Fringes	
CARPENTER		27.06 27.02	
* CARP2337-009 06/05/2023			
KENOSHA, MILWAUKEE, OZAUKEE, RAC	INE, WASHINGTO	DN, AND WAUKESHA	
	Rates	Fringes	
PILEDRIVERMAN	.\$ 39.22	34.01	
ELEC0014-002 12/25/2022			
ASHLAND, BARRON, BAYFIELD, BUFFALO, BURNETT, CHIPPEWA, CLARK (except Maryville, Colby, Unity, Sherman, Fremont, Lynn & Sherwood), CRAWFORD, DUNN, EAU CLAIRE, GRANT, IRON, JACKSON, LA CROSSE, MONROE, PEPIN, PIERCE, POLK, PRICE, RICHLAND, RUSK, ST CROIX, SAWYER, TAYLOR, TREMPEALEAU, VERNON, AND WASHBURN COUNTIES			
	Rates	Fringes	
Electricians:	.\$ 39.25	22.34	
ELEC0014-007 05/29/2022			

REMAINING COUNTIES		
	Rates	Fringes
Teledata System Installer Installer/Technician	.\$ 29.63	3%+16.18
Low voltage construction, instance removal of teledata facilities including outside plant, telephinterconnect, terminal equipmentiber optic cable and equipment bypass, CATV, WAN (wide area nemetworks), and ISDN (integrated	(voice, data, and data in the contral office, micro waves, etworks), LAN	and video) nside wire, ices, PABX, V-SAT, local area
ELEC0127-002 06/01/2023		
KENOSHA COUNTY		
	Rates	Fringes
Electricians:	.\$ 46.05	30%+13.15
ELEC0158-002 05/30/2021		
BROWN, DOOR, KEWAUNEE, MANITOWOC MARINETTE(Wausuakee and area Sout (East of a ine 6 miles West of the County), SHAWANO (Except Area Nor Hutchins) COUNTIES	th thereof), OCC ne West boundary	ONTO, MENOMINEE y of Oconto
	Rates	Fringes
ELECTRICIAN	.\$ 36.14 29	.75%+10.26
ELEC0159-003 05/30/2021		
COLUMBIA, DANE, DODGE (Area West Emmet Townships), GREEN, LAKE (ex Seneca, and St. Marie), IOWA, MAR Neshkoka, Crystal Lake, Newton, a COUNTIES	ccept Townships RQUETTE (except	of Berlin, Townships of
	Rates	Fringes
ELECTRICIAN		23.13
ELEC0219-004 06/01/2019		
FLORENCE COUNTY (Townships of Aur Florence and Homestead) AND MARIN Niagara)		
	Rates	Fringes
Electricians: Electrical contracts over \$180,000		21.80

Electrical contracts under

\$180,000.....\$ 31.75

21.73

ELEC0242-005 05/30/2021

DOUGLAS COUNTY

Rates Fringes

Electricians:......\$ 41.37 69.25%

* ELEC0388-002 06/01/2023

ADAMS, CLARK (Colby, Freemont, Lynn, Mayville, Sherman, Sherwood, Unity), FOREST, JUNEAU, LANGLADE, LINCOLN, MARATHON, MARINETTE (Beecher, Dunbar, Goodman & Pembine), MENOMINEE (Area West of a line 6 miles West of the West boundary of Oconto County), ONEIDA, PORTAGE, SHAWANO (Aniwa and Hutchins), VILAS AND WOOD COUNTIES

	Datas	Fuinas
	Rates	Fringes
Electricians:	.\$ 38.74	26%+11.76
ELEC0430-002 06/01/2023		
RACINE COUNTY (Except Burlington Township)		
	Rates	Fringes
Electricians:	.\$ 46.70	25.02

MILWAUKEE, OZAUKEE, WASHINGTON, AND WAUKESHA COUNTIES

ELEC0494-005 06/01/2022

	Rates	Fringes
Electricians:	\$ 46.38	25.86
ELEC0494-006 06/01/2021		

CALUMET (Township of New Holstein), DODGE (East of Hwy 26 including Chester Township), FOND DU LAC, MANITOWOC (Schleswig), and SHEBOYGAN COUNTIES

	Rates	Fringes	
Electricians:	\$ 37.91	22.74	
ELEC0494-013 05/29/2022			_

DODGE (East of Hwy 26 including Chester Twp, excluding Emmet Twp), FOND DU LAC (Except Waupuin), MILWAUKEE, OZAUKEE, MANITOWOC (Schleswig), WASHINGTON, AND WAUKESHA COUNTIES

	Rates	Fringes
Sound & Communications		
Installer\$	22.39	18.80
Technician\$	33.19	21.12

Installation, testing, maintenance, operation and servicing of all sound, intercom, telephone interconnect, closed

circuit TV systems, radio systems, background music systems, language laboratories, electronic carillion, antenna distribution systems, clock and program systems and low-voltage systems such as visual nurse call, audio/visual nurse call systems, doctors entrance register systems. Includes all wire and cable carrying audio, visual, data, light and radio frequency signals. Includes the installation of conduit, wiremold, or raceways in existing structures that have been occupied for six months or more where required for the protection of the wire or cable, but does not mean a complete conduit or raceway system. work covered does not include the installation of conduit, wiremold or any raceways in any new construction, or the installation of power supply outlets by means of which external electric power is supplied to any of the foregoing equipment or products

ELEC0577-003 06/01/2022

CALUMET (except Township of New Holstein), GREEN LAKE (N. part including Townships of Berlin, St Marie, and Seneca), MARQUETTE (N. part including Townships of Crystal Lake, Neshkoro, Newton, and Springfield), OUTAGAMIE, WAUPACA, WAUSHARA, AND WINNEBAGO COUNTIES

	Rates	Fringes
Electricians:	\$ 37.41	29.50%+10.00
ELEC0890-003 06/01/2022		

DODGE (Emmet Township only), GREEN, JEFFERSON, LAFAYETTE, RACINE (Burlington Township), ROCK AND WALWORTH COUNTIES

	Rates	Fringes	
Electricians:	\$ 40.70	25.95%+11.26	
ELEC0953-001 06/02/2019			
	Rates	Fringes	
Line Construction: (1) Lineman	\$ 42.78 \$ 38.02 \$ 33.27 \$ 30.89	21.43 19.80 18.40 16.88 16.11 14.60	
ENGT0139-005 06/01/2023			-

ENGI0139-005 06/01/2023

	Rates	Fringes
Power Equipment Operator		
Group 1	\$ 43.77	27.40
Group 2	\$ 43.27	27.40
Group 3	\$ 42.77	27.40
Group 4	\$ 42.51	27.40
Group 5	\$ 42.22	27.40
Group 6	\$ 36.32	27.40

HAZARDOUS WASTE PREMIUMS:

EPA Level ""A"" protection - \$3.00 per hour

EPA Level ""B"" protection - \$2.00 per hour

EPA Level ""C"" protection - \$1.00 per hour

POWER EQUIPMENT OPERATORS CLASSIFICATIONS

GROUP 1: Cranes, tower cranes, and derricks with or without attachments with a lifting capacity of over 100 tons; or cranes, tower cranes, and derricks with boom, leads and/or jib lengths measuring 176 feet or longer.

GROUP 2: Cranes, tower cranes and derricks with or without attachments with a lifting capacity of 100 tons or less; or cranes, tower cranes, and derricks with boom, leads, and/or jibs lengths measuring 175 feet or under and Backhoes (excavators) weighing 130,000 lbs and over; caisson rigs; pile driver; dredge operator; dredge engineer; Boat Pilot.

GROUP 3: Mechanic or welder - Heavy duty equipment; cranes with a lifting capacity of 25 tons or under; concrete breaker (manual or remote); vibratory/sonic concrete breaker; concrete laser screed; concrete slipform paver; concrete batch plant operator; concrete pvt. spreader heavy duty (rubber tired); concrete spreader & distributor; automatic subgrader (concrete); concrete grinder & planing machine; concrete slipform curb & gutter machine; slipform concrete placer; tube finisher; hydro blaster (10,000 psi & over); bridge paver; concrete conveyor system; concrete pump; Rotec type Conveyor; stabilizing mixer (self-propelled); shoulder widener; asphalt plant engineer; bituminious paver; bump cutter & grooving machine; milling machine; screed (bituminous paver); asphalt heater, planer & scarifier; Backhoes (excavators) weighing under 130,000 lbs; grader or motor patrol; tractor (scraper, dozer, pusher, loader); scraper - rubber tired (single or twin engine); endloader; hydraulic backhoe (tractor type); trenching machine; skid rigs; tractor, side boom (heavy); drilling or boring machine (mechanical heavy); roller over 5 tons; percussion or rotary drilling machine; air track; blaster; loading machine (conveyor); tugger; boatmen; winches & A-frames; post driver; material hoist.

GROUP 4: Greaser, roller steel (5 tons or less); roller (pneumatic tired) - self propelled; tractor (mounted or towed compactors & light equipment); shouldering machine; self- propelled chip spreader; concrete spreader; finishing machine; mechanical float; curing machine; power subgrader; joint sawer (multiple blade) belting machine; burlap machine; texturing machine; tractor endloader (rubber tired) - light; jeep digger; forklift; mulcher; launch operator; fireman, environmental burner

GROUP 5: Air compressor; power pack; vibrator hammer and extractor; heavy equipment, leadman; tank car heaters; stump chipper; curb machine operator; Concrete proportioning plants; generators; mudjack operator; rock breaker; crusher or screening plant; screed (milling machine); automatic belt conveyor and surge bin; pug mill operator; Oiler, pump (over 3 inches); Drilling Machine Tender, day light machine

GROUP 6: Off-road material hauler with or without ejector.

IRON0008-002 06/01/2023

BROWN, CALUMET, DOOR, FOND DU LAC, KEWAUNEE, MANITOWOC, MARINETTE, OCONTO, OUTAGAMI, SHAWANO, SHEBOYGAN, AND WINNEBAGO COUNTIES:

Rates Fringes

IRONWORKER.....\$ 43.40 30.67

Paid Holidays: New Year's Day, Memorial Day, July 4th, Labor Day, Thanksgiving Day & Christmas Day.

IRON0008-003 06/01/2023

KENOSHA, MILWAUKEE, OZAUKEE, RACINE, WALWORTH (N.E. 2/3), WASHINGTON, AND WAUKESHA COUNTIES

Rates Fringes

IRONWORKER......\$ 41.73 30.67

Paid Holidays: New Year's Day, Memorial Day, July 4th, Labor Day, Thanksgiving Day & Christmas Day.

IRON0383-001 06/01/2023

ADAMS, COLUMBIA, CRAWFORD, DANE, DODGE, FLORENCE, FOREST, GRANT, GREENE, (Excluding S.E. tip), GREEN LAKE, IOWA, JEFFERSON, JUNEAU, LA CROSSE, LAFAYETTE, LANGLADE, MARATHON, MARQUETTE, MENOMINEE, MONROE, PORTAGE, RICHLAND, ROCK (Northern area, vicinity of Edgerton and Milton), SAUK, VERNON, WAUPACA, WAUSHARA, AND WOOD COUNTIES

Rates Fringes

IRONWORKER.....\$ 41.00 30.13

* IRON0498-005 06/01/2023

GREEN (S.E. 1/3), ROCK (South of Edgerton and Milton), and WALWORTH (S.W. 1/3) COUNTIES:

Rates Fringes

IRONWORKER.....\$ 45.18 47.08

* IRON0512-008 04/30/2023

BARRON, BUFFALO, CHIPPEWA, CLARK, DUNN, EAU CLAIRE, JACKSON, PEPIN, PIERCE, POLK, RUSK, ST CROIX, TAYLOR, AND TREMPEALEAU COUNTIES

Rates Fringes
IRONWORKER.....\$ 43.00 34.11

ASHLAND, BAYFIELD, BURNETT, DOUGLAS, IRON, LINCOLN, ONEIDA, PRICE, SAWYER, VILAS AND WASHBURN COUNTIES

	Rates	Fringes
IRONWORKER	.\$ 39.14	34.00
LABO0113-002 06/01/2023		

MILWAUKEE AND WAUKESHA COUNTIES

	Rates	Fringes
LABORER		
Group 1	\$ 33.56	23.86
Group 2	\$ 33.71	23.86
Group 3	\$ 33.91	23.86
Group 4	\$ 34.06	23.86
Group 5		23.86
Group 6	\$ 30.05	23.86

LABORERS CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster and Powderman

GROUP 6: Flagperson; traffic control person

LAB00113-003 06/01/2023

OZAUKEE AND WASHINGTON COUNTIES

		Rates	Fringes
LABORER			
Group	1	\$ 32.81	23.86
Group	2	\$ 32.91	23.86
Group	3	\$ 32.96	23.86
Group	4	\$ 33.16	23.86
Group	5	\$ 33.01	23.86
Group	6	\$ 29.90	23.86

LABORERS CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated);

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster; powderman

GROUP 6: Flagperson and Traffic Control Person

.....

LABO0113-011 06/01/2023

KENOSHA AND RACINE COUNTIES

	F	Rates	Fringes
LABORER			
Group	1\$	32.62	23.86
Group	2\$	32.77	23.86
Group	3\$	32.97	23.86
Group	4\$	32.94	23.86
Group	5\$	33.27	23.86
Group	6\$	29.76	23.86

LABORERS CLASSIFICATIONS:

GROUP 1: General laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster and Powderman

GROUP 6: Flagman; traffic control person

LAB00140-002 06/01/2023

ADAMS, ASHLAND, BARRON, BAYFIELD, BROWN, BUFFALO, BURNETT, CALUMET, CHIPPEWA, CLARK, COLUMBIA, CRAWFORD, DODGE, DOOR,

DOUGLAS, DUNN, EAU CLAIRE, FLORENCE, FOND DU LAC, FOREST, GRANT, GREEN, GREEN LAKE, IRON, JACKSON, JUNEAU, IOWA, JEFFERSON, KEWAUNEE, LA CROSSE, LAFAYETTE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, MONROE, OCONTO, ONEIDA, OUTAGAMIE, PEPIN, PIERCE, POLK, PORTAGE, PRICE, RICHLAND, ROCK, RUSK, SAUK, SAWYER, SHAWANO, SHEBOYGAN, ST. CROIX, TAYLOR, TREMPEALEAU, VERNON, VILLAS, WALWORTH, WASHBURN, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

	Rates	Fringes
LABORER		
Group 1	\$ 37.57	19.25
Group 2	\$ 37.67	19.25
Group 3	\$ 37.72	19.25
Group 4	\$ 37.92	19.25
Group 5	\$ 37.77	19.25
Group 6		19.25

LABORER CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bitminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator, Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk and Pavement); Strike Off Man

GROUP 4: Line and Grade Secialist

GROUP 5: Blaster; powderman

GROUP 6: Flagperson; Traffic Control

LABO0464-003 06/01/2023

DANE COUNTY

	F	Rates	Fringes
LABORER			
Group	1\$	37.85	19.25
	2\$		19.25
Group	3\$	38.00	19.25
Group	4\$	38.20	19.25
Group	5\$	38.05	19.25
Group	6\$	34.20	19.25

LABORERS CLASSIFICATIONS:

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and

Utility Man); Batch Truck Dumper or Cement Handler; Bituminious Worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man GROUP 4: Line and Grade Specialist GROUP 5: Blaster; Powderman GROUP 6: Flagperson and Traffic Control Person PAIN0106-008 05/01/2023 ASHLAND, BAYFIELD, BURNETT, AND DOUGLAS COUNTIES Rates Fringes Painters: New: Brush, Roller.....\$ 34.59 24.84 Spray, Sandblast, Steel....\$ 35.19 24.84 Repaint: Brush, Roller.....\$ 33.09 24.84 Spray, Sandblast, Steel....\$ 33.69 PAIN0108-002 06/01/2023 RACINE COUNTY Rates Fringes Painters: Brush, Roller.....\$ 41.04 21.95 Spray & Sandblast.....\$ 42.04 21.95 PAIN0259-002 05/01/2008 BARRON, CHIPPEWA, DUNN, EAU CLAIRE, PEPIN, PIERCE, POLK, RUSK, SAWYER, ST. CROIX, AND WASHBURN COUNTIES Rates Fringes PAINTER.....\$ 24.11 12.15 ______ PAIN0259-004 05/01/2015 BUFFALO, CRAWFORD, JACKSON, LA CROSSE, MONROE, TREMPEALEAU, AND **VERNON COUNTIES** Rates Fringes PAINTER....\$ 22.03

PAIN0781-002 06/01/2023

JEFFERSON, MILWAUKEE, OZAUKEE, WASHINGTON, AND WAUKESHA COUNTIES

JETTERSON, MILWACKEE, OZACKEE, WA	SHINGTON, AND V	WAOKESHA COUNTIES
	Rates	Fringes
Painters: Bridge Brush Spray & Sandblast	\$ 39.09 \$ 39.84	24.86 24.86 24.86
PAIN0802-002 06/01/2023		
COLUMBIA, DANE, DODGE, GRANT, GRE ROCK, AND SAUK COUNTIES	EN, IOWA, LAFA\	YETTE, RICHLAND,
	Rates	Fringes
PAINTER Brush	\$ 35.00	20.62
PREMIUM PAY: Structural Steel, Spray, Bridge hour.		·
PAIN0802-003 06/01/2023		
ADAMS, BROWN, CALUMET, CLARK, DOO LAKE, IRON, JUNEAU, KEWAUNEE, LAN MARATHON, MARINETTE, MARQUETTE, M OUTAGAMIE, PORTAGE, PRICE, SHAWAN WAUSHARA, WAUPACA, WINNEBAGO, AND	GLADE, LINCOLN ENOMINEE, OCOM O, SHEBOYGAN,	, MANITOWOC, NTO, ONEIDA,
	Rates	Fringes
PAINTER	\$ 35.00	20.62
PAIN0934-001 06/01/2022		
KENOSHA AND WALWORTH COUNTIES		
	Rates	Fringes
Painters: Brush Spray Structural Steel	\$ 37.70	24.69 24.69 24.69
PAIN1011-002 06/06/2021		
FLORENCE COUNTY		
	Rates	Fringes
Painters:	•	14.38
PLAS0599-002 06/01/2023		
	Rates	Fringes
CEMENT MASON/CONCRETE FINISHER Area A	\$ 39.97	27.27 25.02 25.25

Area D\$ 41.16	24.49
Area E\$ 40.50	25.14
Area F\$ 36.98	28.67

AREA DESCRIPTIONS

AREA A: ASHLAND, BURNETT, BAYFIELD, DOUGLAS, IRON, PRICE, SAWYER, AND WASHBURN COUNTIES

AREA B: ADAMS, BARRON, BROWN, CALUMET, CHIPPEWA, CLARK, COLUMBIA, DODGE, DOOR, DUNN, FLORENCE, FOND DU LAC, FOREST, GREEN LAKE, JEFFERSON, KEWAUNEE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, OCONTO, ONEIDA, OUTAGAMIE, POLK, PORTAGE, RUSK, ST. CROIX, SAUK, SHAWANO, SHEBOYGAN, TAYLOR, VILAS, WALWORTH, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

AREA C: BUFFALO, CRAWFORD, EAU CLAIRE, JACKSON, JUNEAU, LA CROSSE, MONROE, PEPIN, PIERCE, RICHLAND, TREMPEALEAU, AND VERNON COUNTIES

AREA D: MILWAUKEE, OZAUKEE, WASHINGTON, AND WAUKESHA COUNTIES

AREA E: DANE, GRANT, GREEN, IOWA, LAFAYETTE, AND ROCK COUNTIES

AREA F: KENOSHA AND RACINE COUNTIES

TEAM0039-001 06/01/2023

	Rates	Fringes
TRUCK DRIVER 1 & 2 Axles 3 or more Axles; Euclids,	\$ 35.57	26.09
Dumptor & Articulated, Truck Mechanic	\$ 35.72	26.09

WELDERS - Receive rate prescribed for craft performing operation to which welding is incidental.

Note: Executive Order (EO) 13706, Establishing Paid Sick Leave for Federal Contractors applies to all contracts subject to the Davis-Bacon Act for which the contract is awarded (and any solicitation was issued) on or after January 1, 2017. If this contract is covered by the EO, the contractor must provide employees with 1 hour of paid sick leave for every 30 hours they work, up to 56 hours of paid sick leave each year. Employees must be permitted to use paid sick leave for their own illness, injury or other health-related needs, including preventive care; to assist a family member (or person who is like family to the employee) who is ill, injured, or has other health-related needs, including preventive care; or for reasons resulting from, or to assist a family member (or person who is like family to the employee) who is a victim of, domestic violence, sexual assault, or stalking. Additional information on contractor requirements and worker protections under the EO is available at

https://www.dol.gov/agencies/whd/government-contracts.

Unlisted classifications needed for work not included within

the scope of the classifications listed may be added after award only as provided in the labor standards contract clauses (29CFR 5.5 (a) (1) (ii)).

The body of each wage determination lists the classification and wage rates that have been found to be prevailing for the cited type(s) of construction in the area covered by the wage determination. The classifications are listed in alphabetical order of ""identifiers" that indicate whether the particular rate is a union rate (current union negotiated rate for local), a survey rate (weighted average rate) or a union average rate (weighted union average rate).

Union Rate Identifiers

A four letter classification abbreviation identifier enclosed in dotted lines beginning with characters other than ""SU"" or ""UAVG"" denotes that the union classification and rate were prevailing for that classification in the survey. Example: PLUM0198-005 07/01/2014. PLUM is an abbreviation identifier of the union which prevailed in the survey for this classification, which in this example would be Plumbers. 0198 indicates the local union number or district council number where applicable, i.e., Plumbers Local 0198. The next number, 005 in the example, is an internal number used in processing the wage determination. 07/01/2014 is the effective date of the most current negotiated rate, which in this example is July 1, 2014.

Union prevailing wage rates are updated to reflect all rate changes in the collective bargaining agreement (CBA) governing this classification and rate.

Survey Rate Identifiers

Classifications listed under the ""SU"" identifier indicate that no one rate prevailed for this classification in the survey and the published rate is derived by computing a weighted average rate based on all the rates reported in the survey for that classification. As this weighted average rate includes all rates reported in the survey, it may include both union and non-union rates. Example: SULA2012-007 5/13/2014. SU indicates the rates are survey rates based on a weighted average calculation of rates and are not majority rates. LA indicates the State of Louisiana. 2012 is the year of survey on which these classifications and rates are based. The next number, 007 in the example, is an internal number used in producing the wage determination. 5/13/2014 indicates the survey completion date for the classifications and rates under that identifier.

Survey wage rates are not updated and remain in effect until a new survey is conducted.

Union Average Rate Identifiers

Classification(s) listed under the UAVG identifier indicate that no single majority rate prevailed for those classifications; however, 100% of the data reported for the classifications was union data. EXAMPLE: UAVG-OH-0010 08/29/2014. UAVG indicates that the rate is a weighted union average rate. OH indicates the state. The next number, 0010 in

the example, is an internal number used in producing the wage determination. 08/29/2014 indicates the survey completion date for the classifications and rates under that identifier.

A UAVG rate will be updated once a year, usually in January of each year, to reflect a weighted average of the current negotiated/CBA rate of the union locals from which the rate is based.

WAGE DETERMINATION APPEALS PROCESS

- 1.) Has there been an initial decision in the matter? This can be:
- * an existing published wage determination
- * a survey underlying a wage determination
- * a Wage and Hour Division letter setting forth a position on a wage determination matter
- * a conformance (additional classification and rate) ruling

On survey related matters, initial contact, including requests for summaries of surveys, should be with the Wage and Hour National Office because National Office has responsibility for the Davis-Bacon survey program. If the response from this initial contact is not satisfactory, then the process described in 2.) and 3.) should be followed.

With regard to any other matter not yet ripe for the formal process described here, initial contact should be with the Branch of Construction Wage Determinations. Write to:

Branch of Construction Wage Determinations Wage and Hour Division U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

2.) If the answer to the question in 1.) is yes, then an interested party (those affected by the action) can request review and reconsideration from the Wage and Hour Administrator (See 29 CFR Part 1.8 and 29 CFR Part 7). Write to:

Wage and Hour Administrator U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

The request should be accompanied by a full statement of the interested party's position and by any information (wage payment data, project description, area practice material, etc.) that the requestor considers relevant to the issue.

3.) If the decision of the Administrator is not favorable, an interested party may appeal directly to the Administrative Review Board (formerly the Wage Appeals Board). Write to:

Administrative Review Board U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

4.)	A11	decisions	by -	the	Administrative	Review	Board	are	final.
		END OF	GENE	RAL	DECISION				
"									

NOTICE TO BIDDERS WAGE RATE DECISION

The wage rate decision of the Department of Labor which has been incorporated in these advertised specifications is incomplete in that the classifications may be omitted from the Department of Labor's decision.


Since the bidder is responsible, independently, for ascertaining area practice with respect to the necessity, or lack of necessity, for the use of these classifications in the prosecution of the work contemplated by this project, no inference may be drawn from the omission of these classifications concerning prevailing area practices relative to their use. Further, this omission will not, <u>per se</u>, be construed as establishing any governmental liability for increased labor cost if it is subsequently determined that such classifications are required.

There may be omissions and/or errors in the federal wage rates. The bidder is responsible for evaluating and determining the correct applicable rate.

If a project includes multiple types of construction (highway, bridge over navigable water, sanitary sewer and water main, building) and there is not a separate wage determination for this type of work included in the proposal, use the wage determination that is in the proposal.

If a project includes multiple types of construction, different wage rate determinations may be inserted into the contract (WI10/Highway = in all WisDOT highway contracts, WI15/Heavy = bridge over navigable water per USDOL and US Coast Guard designation, WI8/Heavy (Sewer & Water Line & Tunnel) = sanitary sewer and water main if the cost is more than 20% of the contract and/or at least \$1,000,000, and Building). If multiple wage rate determinations are inserted into the contract, use the classification in the wage determination for the work being done. Use WI15 wage rates when working on the bridge and/or structure from bank to bank. Use WI8 wage rates when working on any sanitary sewer or water main work. Use Building wage rates for all work done within the footprint of the building. Use WI10 wage rates for all other highway work in the contract and approaches to structures. For example, if a laborer is working within the footprint of a building, use the Laborer rate in the Building wage determination inserted in the contract. If a laborer is working on a bridge/structure within the banks, use the Laborer rate in the WI15/Heavy wage determination if inserted in the contract. If the laborer is working on the highway, use the Laborer rate in the WI10/Highway wage determination.







Page 1 of 17

Proposal ID: 20240109012 **Project(s):** 2310-13-70, 2310-13-71

Federal ID(s): WISC 2024117, WISC 2024118

SECTION: 0001 Roadway Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	203.0100 Removing Small Pipe Culverts	3.000 EACH		
0004	203.0220 Removing Structure (structure) 01. R-66-87	1.000 EACH		
0006	204.0110 Removing Asphaltic Surface	989.000 SY		
8000	204.0115 Removing Asphaltic Surface Butt Joints	1,588.000 SY	·	
0010	204.0120 Removing Asphaltic Surface Milling	42,858.000 SY		
0012	204.0150 Removing Curb & Gutter	1,989.000 LF		
0014	204.0155 Removing Concrete Sidewalk	1,318.000 SY		
0016	204.0190 Removing Surface Drains	1.000 EACH		
0018	204.0195 Removing Concrete Bases	36.000 EACH		
0020	204.0220 Removing Inlets	2.000 EACH		
0022	204.0245 Removing Storm Sewer (size) 01. 12-inch	113.000 LF	·	
0024	204.9060.S Removing (item description) 01. Traffic Signals STH 60 & CTH P	1.000 EACH		
0026	204.9060.S Removing (item description) 02. Traffic Signals STH 60 & Industrial Dr	1.000 EACH		·
0028	204.9060.S Removing (item description) 03. Traffic Signals STH 60 & Jackson Dr	1.000 EACH	·	·





Page 2 of 17

Proposal ID: 20240109012 **Project(s):** 2310-13-70, 2310-13-71

Federal ID(s): WISC 2024117, WISC 2024118

SECTION: 0001 Roadway Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0030	204.9060.S Removing (item description) 04. Loop Detector Wire & Lead In Cable STH 60 & CTH P	1.000 EACH	·	
0032	204.9060.S Removing (item description) 05. Loop Detector Wire & Lead In Cable STH 60 & Industrial Dr	1.000 EACH	·	
0034	204.9060.S Removing (item description) 06. Loop Detector Wire & Lead In Cable STH 60 & Jackson Dr	1.000 EACH	·	<u> </u>
0036	205.0100 Excavation Common	7,015.000 CY	·	
0038	205.0501.S Excavation, Hauling, and Disposal of Petroleum Contaminated Soil	432.000 TON		·
0040	211.0101 Prepare Foundation for Asphaltic Paving (project) 01. 2310-13-70	1.000 EACH	·	·
0042	211.0101 Prepare Foundation for Asphaltic Paving (project) 02. 2310-13-71	1.000 EACH	·	
0044	211.0400 Prepare Foundation for Asphaltic Shoulders	4.000 STA	·	
0046	213.0100 Finishing Roadway (project) 01. 2310-13-70	1.000 EACH		
0048	213.0100 Finishing Roadway (project) 02. 2310-13-71	1.000 EACH	·	
0050	305.0110 Base Aggregate Dense 3/4-Inch	270.000 TON		
0052	305.0120 Base Aggregate Dense 1 1/4-Inch	5,250.000 TON		
0054	310.0110 Base Aggregate Open-Graded	52.000 TON		





Page 3 of 17

Proposal ID: 20240109012 **Project(s):** 2310-13-70, 2310-13-71

Federal ID(s): WISC 2024117, WISC 2024118

SECTION: 0001 Roadway Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0056	312.0110 Select Crushed Material	5,425.000 TON		
0058	390.0405 Base Patching Concrete SHES	23.000 CY		
0060	405.0100 Coloring Concrete WisDOT Red	140.000 CY		
0062	415.2010 Concrete Truck Apron 12-inch	342.000 SY	·	
0064	455.0605 Tack Coat	6,518.000 GAL		
0066	460.2000 Incentive Density HMA Pavement	6,790.000 DOL	1.00000	6,790.00
0068	460.6223 HMA Pavement 3 MT 58-28 S	622.000 TON		
0070	460.6224 HMA Pavement 4 MT 58-28 S	9,241.000 TON		
0072	460.6424 HMA Pavement 4 MT 58-28 H	727.000 TON		
0074	465.0105 Asphaltic Surface	10.000 TON		
0076	465.0110 Asphaltic Surface Patching	35.000 TON		
0078	465.0315 Asphaltic Flumes	9.000 SY		·
0800	504.0900 Concrete Masonry Endwalls	4.000 CY		
0082	513.8011 Railing Steel Pedestrian Type C2	31.000 LF	·	
0084	520.8000 Concrete Collars for Pipe	4.000 EACH		
0086	522.0421 Culvert Pipe Reinforced Concrete Class IV 21-Inch	202.000 LF	<u>.</u>	·





Page 4 of 17


Proposal ID: 20240109012 **Project(s):** 2310-13-70, 2310-13-71

Federal ID(s): WISC 2024117, WISC 2024118

SECTION: 0001 Roadway Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0088	522.0448 Culvert Pipe Reinforced Concrete Class IV 48-Inch	436.000 LF		
0090	522.1012 Apron Endwalls for Culvert Pipe Reinforced Concrete 12-Inch	1.000 EACH		·
0092	522.1015 Apron Endwalls for Culvert Pipe Reinforced Concrete 15-Inch	2.000 EACH		
0094	522.1021 Apron Endwalls for Culvert Pipe Reinforced Concrete 21-Inch	2.000 EACH	·	
0096	522.1048 Apron Endwalls for Culvert Pipe Reinforced Concrete 48-Inch	2.000 EACH		
0098	601.0405 Concrete Curb & Gutter 18-Inch Type A	185.000 LF		
0100	601.0411 Concrete Curb & Gutter 30-Inch Type D	3,213.000 LF	·	·
0102	601.0551 Concrete Curb & Gutter 4-Inch Sloped 36-Inch Type A	242.000 LF		
0104	601.0557 Concrete Curb & Gutter 6-Inch Sloped 36-Inch Type D	50.000 LF	·	
0106	601.0580 Concrete Curb & Gutter 4-Inch Sloped 36-Inch Type R	273.000 LF		
0108	601.0600 Concrete Curb Pedestrian	167.000 LF		
0110	602.0405 Concrete Sidewalk 4-Inch	2,949.000 SF	·	
0112	602.0410 Concrete Sidewalk 5-Inch	20,082.000 SF	·	·
0114	602.0505 Curb Ramp Detectable Warning Field Yellow	562.000 SF	·	·







Page 5 of 17


Proposal ID: 20240109012 **Project(s):** 2310-13-70, 2310-13-71

Federal ID(s): WISC 2024117, WISC 2024118

SECTION: 0001 Roadway Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0116	602.0605 Curb Ramp Detectable Warning Field Radial Yellow	140.000 SF	·	
0118	602.0810 Concrete Driveway 6-Inch	93.000 SY		
0120	602.3010 Concrete Surface Drains	1.000 CY		
0122	606.0200 Riprap Medium	46.000 CY		<u> </u>
0124	608.0412 Storm Sewer Pipe Reinforced Concrete Class IV 12-Inch	424.000 LF		
0126	608.0415 Storm Sewer Pipe Reinforced Concrete Class IV 15-Inch	53.000 LF	·	·
0128	611.0530 Manhole Covers Type J	2.000 EACH		
0130	611.0612 Inlet Covers Type C	1.000 EACH		<u> </u>
0132	611.0636 Inlet Covers Type HM-S	2.000 EACH		
0134	611.0639 Inlet Covers Type H-S	11.000 EACH		
0136	611.0651 Inlet Covers Type S	2.000 EACH	·	
0138	611.0652 Inlet Covers Type T	3.000 EACH		
0140	611.2004 Manholes 4-FT Diameter	3.000 EACH		
0142	611.3004 Inlets 4-FT Diameter	6.000 EACH		
0144	611.3230 Inlets 2x3-FT	10.000 EACH	·	







Page 6 of 17


Proposal ID: 20240109012 **Project(s):** 2310-13-70, 2310-13-71

Federal ID(s): WISC 2024117, WISC 2024118

SECTION: 0001 Roadway Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0146	611.8110 Adjusting Manhole Covers	27.000 EACH		
0148	611.8115 Adjusting Inlet Covers	1.000 EACH		
0150	611.8120.S Cover Plates Temporary	27.000 EACH		
0152	611.9850.S Pipe Grates (size) 01. 48-Inch	2.000 EACH	·	
0154	612.0106 Pipe Underdrain 6-Inch	350.000 LF	·	
0156	612.0406 Pipe Underdrain Wrapped 6-Inch	35.000 LF	·	
0158	618.0100 Maintenance and Repair of Haul Roads (project) 01. 2310-13-70	1.000 EACH		<u> </u>
0160	618.0100 Maintenance and Repair of Haul Roads (project) 02. 2310-13-71	1.000 EACH		
0162	619.1000 Mobilization	1.000 EACH	·	
0164	620.0300 Concrete Median Sloped Nose	308.000 SF		
0166	624.0100 Water	140.000 MGAL	·	
0168	625.0100 Topsoil	7,885.000 SY	·	
0170	628.1504 Silt Fence	1,490.000 LF		
0172	628.1520 Silt Fence Maintenance	1,490.000 LF		
0174	628.1905 Mobilizations Erosion Control	8.000 EACH		
0176	628.1910 Mobilizations Emergency Erosion Control	10.000 EACH		







Page 7 of 17

Proposal ID: 20240109012 **Project(s):** 2310-13-70, 2310-13-71

Federal ID(s): WISC 2024117, WISC 2024118

SECTION: 0001 Roadway Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0178	628.7005 Inlet Protection Type A	39.000 EACH		
0180	628.7015 Inlet Protection Type C	38.000 EACH	<u></u> _	
0182	628.7020 Inlet Protection Type D	60.000 EACH		·
0184	628.7555 Culvert Pipe Checks	25.000 EACH		
0186	629.0210 Fertilizer Type B	4.000 CWT		
0188	630.0120 Seeding Mixture No. 20	9.000 LB		·
0190	630.0200 Seeding Temporary	9.000 LB		·
0192	630.0500 Seed Water	8.000 MGAL		·
0194	631.0300 Sod Water	130.000 MGAL		·
0196	631.1000 Sod Lawn	7,885.000 SY		
0198	633.5100 Markers ROW	5.000 EACH		·
0200	633.5200 Markers Culvert End	7.000 EACH		
0202	634.0618 Posts Wood 4x6-Inch X 18-FT	75.000 EACH		
0204	634.0622 Posts Wood 4x6-Inch X 22-FT	8.000 EACH		
0206	634.0814 Posts Tubular Steel 2x2-Inch X 14-FT	46.000 EACH		
0208	637.2210 Signs Type II Reflective H	867.610 SF		





Page 8 of 17

Proposal ID: 20240109012 **Project(s):** 2310-13-70, 2310-13-71

Federal ID(s): WISC 2024117, WISC 2024118

SECTION: 0001 Roadway Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0210	637.2215 Signs Type II Reflective H Folding	72.520 SF		
0212	637.2230 Signs Type II Reflective F	401.440 SF	·	
0214	638.2102 Moving Signs Type II	35.000 EACH		
0216	638.2602 Removing Signs Type II	74.000 EACH		
0218	638.3000 Removing Small Sign Supports	65.000 EACH		
0220	643.0300 Traffic Control Drums	50,390.000 DAY		
0222	643.0410 Traffic Control Barricades Type II	1,950.000 DAY	·	
0224	643.0420 Traffic Control Barricades Type III	3,460.000 DAY		
0226	643.0705 Traffic Control Warning Lights Type A	10,820.000 DAY		
0228	643.0715 Traffic Control Warning Lights Type C	2,085.000 DAY		
0230	643.0900 Traffic Control Signs	28,955.000 DAY		
0232	643.0910 Traffic Control Covering Signs Type I	16.000 EACH	·	
0234	643.1050 Traffic Control Signs PCMS	40.000 DAY		
0236	643.1070 Traffic Control Cones 42-Inch	12,100.000 DAY		
0238	643.3165 Temporary Marking Line Paint 6-Inch	32,085.000 LF	<u> </u>	
0240	643.3960 Temporary Marking Removable Mask Out Tape 6-Inch	41,020.000 LF		





Page 9 of 17

Proposal ID: 20240109012 **Project(s):** 2310-13-70, 2310-13-71

Federal ID(s): WISC 2024117, WISC 2024118

SECTION: 0001 Roadway Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0242	643.5000 Traffic Control	1.000 EACH		
0244	644.1410 Temporary Pedestrian Surface Asphalt	150.000 SF		
0246	644.1601 Temporary Pedestrian Curb Ramp	1,740.000 DAY	<u></u> _	
0248	644.1605 Temporary Pedestrian Detectable Warning Field	1,040.000 SF		
0250	644.1810 Temporary Pedestrian Barricade	2,080.000 LF		
0252	645.0111 Geotextile Type DF Schedule A	200.000 SY		
0254	645.0120 Geotextile Type HR	91.000 SY		
0256	646.2020 Marking Line Epoxy 6-Inch	41,629.000 LF		·
0258	646.4020 Marking Line Epoxy 10-Inch	1,758.000 LF		·
0260	646.5020 Marking Arrow Epoxy	27.000 EACH		·
0262	646.5120 Marking Word Epoxy	7.000 EACH		·
0264	646.5320 Marking Railroad Crossing Epoxy	2.000 EACH		·
0266	646.6120 Marking Stop Line Epoxy 18-Inch	399.000 LF		·
0268	646.7020 Marking Diagonal Epoxy 6-Inch	360.000 LF		
0270	646.7120 Marking Diagonal Epoxy 12-Inch	210.400 LF		
0272	646.7420 Marking Crosswalk Epoxy Transverse Line 6-Inch	1,502.000 LF	·	





Page 10 of 17

Proposal ID: 20240109012 **Project(s):** 2310-13-70, 2310-13-71

Federal ID(s): WISC 2024117, WISC 2024118

SECTION: 0001 Roadway Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0274	646.7520 Marking Crosswalk Epoxy Block Style 24-Inch	280.000 LF		
0276	646.8020 Marking Corrugated Median Epoxy	971.000 SF		<u>-</u>
0278	646.8120 Marking Curb Epoxy	255.000 LF		
0280	646.8220 Marking Island Nose Epoxy	12.000 EACH		
0282	646.9000 Marking Removal Line 4-Inch	8,935.000 LF		
0284	650.4000 Construction Staking Storm Sewer	1.000 EACH	<u> </u>	<u> </u>
0286	650.5500 Construction Staking Curb Gutter and Curb & Gutter	1,510.000 LF		
0288	650.6000 Construction Staking Pipe Culverts	4.000 EACH		<u>-</u>
0290	650.8000 Construction Staking Resurfacing Reference	9,150.000 LF		
0292	650.8501 Construction Staking Electrical Installations (project) 01. 2310-13-70	1.000 EACH		·
0294	650.8501 Construction Staking Electrical Installations (project) 02. 2310-13-71	1.000 EACH	.	·
0296	650.9000 Construction Staking Curb Ramps	38.000 EACH		
0298	650.9500 Construction Staking Sidewalk (project) 01. 2310-13-70	1.000 EACH		
0300	650.9911 Construction Staking Supplemental Control (project) 01. 2310-13-70	1.000 EACH		





Page 11 of 17

Proposal ID: 20240109012 **Project(s):** 2310-13-70, 2310-13-71

Federal ID(s): WISC 2024117, WISC 2024118

SECTION: 0001 Roadway Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0302	652.0225 Conduit Rigid Nonmetallic Schedule 40 2-Inch	2,505.000 LF	·	
0304	652.0325 Conduit Rigid Nonmetallic Schedule 80 2-Inch	1,885.000 LF	·	
0306	652.0605 Conduit Special 2-Inch	1,900.000 LF		
0308	652.0615 Conduit Special 3-Inch	1,635.000 LF		
0310	652.0800 Conduit Loop Detector	4,838.000 LF		<u> </u>
0312	653.0135 Pull Boxes Steel 24x36-Inch	10.000 EACH	·	
0314	653.0140 Pull Boxes Steel 24x42-Inch	45.000 EACH	·	
0316	653.0164 Pull Boxes Non-Conductive 24x42-Inch	6.000 EACH		
0318	653.0905 Removing Pull Boxes	40.000 EACH	<u>-</u>	
0320	654.0101 Concrete Bases Type 1	15.000 EACH	<u></u>	
0322	654.0102 Concrete Bases Type 2	3.000 EACH		
0324	654.0105 Concrete Bases Type 5	12.000 EACH		
0326	654.0110 Concrete Bases Type 10	7.000 EACH		
0328	654.0120 Concrete Bases Type 10-Special	5.000 EACH		
0330	654.0217 Concrete Control Cabinet Bases Type 9 Special	3.000 EACH		





Page 12 of 17

Proposal ID: 20240109012 **Project(s):** 2310-13-70, 2310-13-71

Federal ID(s): WISC 2024117, WISC 2024118

SECTION: 0001 Roadway Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0332	654.0224 Concrete Control Cabinet Bases Type L24	1.000 EACH		
0334	655.0230 Cable Traffic Signal 5-14 AWG	1,483.000 LF		
0336	655.0240 Cable Traffic Signal 7-14 AWG	1,991.000 LF		
0338	655.0260 Cable Traffic Signal 12-14 AWG	4,805.000 LF	<u></u>	
0340	655.0270 Cable Traffic Signal 15-14 AWG	450.000 LF		
0342	655.0305 Cable Type UF 2-12 AWG Grounded	2,255.000 LF		
0344	655.0515 Electrical Wire Traffic Signals 10 AWG	5,370.000 LF		
0346	655.0610 Electrical Wire Lighting 12 AWG	3,897.000 LF		
0348	655.0620 Electrical Wire Lighting 8 AWG	5,828.000 LF		
0350	655.0700 Loop Detector Lead In Cable	16,020.000 LF		·
0352	655.0800 Loop Detector Wire	15,893.000 LF		
0354	655.0900 Traffic Signal EVP Detector Cable	660.000 LF		
0356	656.0201 Electrical Service Meter Breaker Pedestal (location) 01. STH 60 & CTH P	1.000 EACH		
0358	656.0201 Electrical Service Meter Breaker Pedestal (location) 02. STH 60 & Industrial Dr	1.000 EACH	·	·





Page 13 of 17


Proposal ID: 20240109012 **Project(s):** 2310-13-70, 2310-13-71

Federal ID(s): WISC 2024117, WISC 2024118

SECTION: 0001 Roadway Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0360	656.0201 Electrical Service Meter Breaker Pedestal (location) 03. STH 60 & Jackson Dr	1.000 EACH		
0362	656.0201 Electrical Service Meter Breaker Pedestal (location) 04. Cabinet JA	1.000 EACH		<u> </u>
0364	657.0100 Pedestal Bases	15.000 EACH	·	
0366	657.0255 Transformer Bases Breakaway 11 1/2- Inch Bolt Circle	15.000 EACH	·	
0368	657.0310 Poles Type 3	3.000 EACH	·	
0370	657.0322 Poles Type 5-Aluminum	12.000 EACH	·	
0372	657.0420 Traffic Signal Standards Aluminum 13-FT	2.000 EACH		
0374	657.0425 Traffic Signal Standards Aluminum 15-FT	11.000 EACH		
0376	657.0430 Traffic Signal Standards Aluminum 10-FT	2.000 EACH		
0378	657.0609 Luminaire Arms Single Member 4-Inch Clamp 6-FT	5.000 EACH	·	
0380	657.0715 Luminaire Arms Truss Type 4 1/2-Inch Clamp 15-FT	12.000 EACH		
0382	658.0173 Traffic Signal Face 3S 12-Inch	36.000 EACH		
0384	658.0174 Traffic Signal Face 4S 12-Inch	24.000 EACH		
0386	658.0416 Pedestrian Signal Face 16-Inch	18.000 EACH	·	







Page 14 of 17

Proposal ID: 20240109012 **Project(s):** 2310-13-70, 2310-13-71

Federal ID(s): WISC 2024117, WISC 2024118

SECTION: 0001 Roadway Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0388	658.0500 Pedestrian Push Buttons	18.000 EACH		
0390	658.5070 Signal Mounting Hardware (location) 01. STH 60 & CTH P	1.000 EACH		
0392	658.5070 Signal Mounting Hardware (location) 02. STH 60 & Industrial Dr	1.000 EACH		
0394	658.5070 Signal Mounting Hardware (location) 03. STH 60 & Jackson Dr	1.000 EACH	·	
0396	659.1115 Luminaires Utility LED A	12.000 EACH	·	
0398	659.1125 Luminaires Utility LED C	16.000 EACH		
0400	659.2124 Lighting Control Cabinets 120/240 24- Inch	1.000 EACH		
0402	659.5000.S Lamp, Ballast, LED, Switch Disposal by Contractor	70.000 EACH	·	
0404	661.0201 Temporary Traffic Signals for Intersections (location) 01. STH 60 & CTH P	1.000 EACH	·	·
0406	661.0201 Temporary Traffic Signals for Intersections (location) 02. STH 60 & Industrial Dr	1.000 EACH	·	·
0408	661.0201 Temporary Traffic Signals for Intersections (location) 03. STH 60 & Jackson Dr	1.000 EACH	·	·
0410	690.0150 Sawing Asphalt	2,885.000 LF		
0412	690.0250 Sawing Concrete	491.000 LF		





Page 15 of 17

Proposal ID: 20240109012 **Project(s):** 2310-13-70, 2310-13-71

Federal ID(s): WISC 2024117, WISC 2024118

SECTION: 0001 Roadway Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0414	715.0720 Incentive Compressive Strength Concrete Pavement	500.000 DOL	1.00000	500.00
0416	740.0440 Incentive IRI Ride	7,540.000 DOL	1.00000	7,540.00
0418	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	1,500.000 HRS	5.00000	7,500.00
0420	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	1,800.000 HRS	5.00000	9,000.00
0422	SPV.0060 Special 01. Install Type 9 Pole	2.000 EACH		
0424	SPV.0060 Special 03. Install Type 10 Pole	5.000 EACH		
0426	SPV.0060 Special 04. Install Type 10 Special Pole	5.000 EACH		
0428	SPV.0060 Special 05. Install Monotube Arms 25-FT	3.000 EACH		
0430	SPV.0060 Special 06. Install Monotube Arms 30-FT	4.000 EACH		
0432	SPV.0060 Special 07. Install Monotube Arms 35-FT Special	4.000 EACH		·
0434	SPV.0060 Special 08. Install Monotube Arms 40-FT Special	1.000 EACH		·
0436	SPV.0060 Special 09. Install Luminaire Arms Steel 15-FT	11.000 EACH		
0438	SPV.0060 Special 10. Transport and Install State Furnished EVP Detector Heads STH 60 & CTH P	1.000 EACH	·	





Page 16 of 17

Proposal ID: 20240109012 **Project(s):** 2310-13-70, 2310-13-71

Federal ID(s): WISC 2024117, WISC 2024118

SECTION: 0001 Roadway Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0440	SPV.0060 Special 11. Transport and Install State Furnished EVP Detector Heads STH 60 & Industrial	1.000 EACH	·	·
0442	SPV.0060 Special 12. Transport and Install State Furnished EVP Detector Heads STH 60 & Jackson Dr	2.000 EACH	<u></u>	
0444	SPV.0060 Special 13. Transport and Install State Furnished Traffic Signal Cabinet STH 60 & CTH P	1.000 EACH	·	·
0446	SPV.0060 Special 14. Transport and Install State Furnished Signal Cabinet STH 60 & Industrial Dr	1.000 EACH	·	
0448	SPV.0060 Special 15. Transport and Install State Furnished Signal Cabinet STH 60 & Jackson Dr	1.000 EACH		·
0450	SPV.0060 Special 16. Temporary Infrared EVP System STH 60 & CTH P	1.000 EACH		
0452	SPV.0060 Special 17. Temporary Infrared EVP System STH 60 & Industrial Dr	1.000 EACH		·
0454	SPV.0060 Special 18. Temporary Infrared EVP System STH 60 & Jackson Dr	1.000 EACH		
0456	SPV.0060 Special 19. Transport Traffic Signal and Lighting Materials STH 60 & CTH P	1.000 EACH		
0458	SPV.0060 Special 20. Transport Traffic Signal and Lighting Materials STH 60 & Industrial Dr	1.000 EACH		
0460	SPV.0060 Special 21. Transport Traffic Signal and Lighting Materials STH 60 & Jackson Dr	1.000 EACH		
0462	SPV.0060 Special 22. Saddle Inlet	2.000 EACH		





Page 17 of 17

Proposal ID: 20240109012 **Project(s):** 2310-13-70, 2310-13-71

Federal ID(s): WISC 2024117, WISC 2024118

SECTION: 0001 Roadway Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0464	SPV.0060 Special 23. Construction Staking Roundabout	1.000 EACH		
0466	SPV.0060 Special 25. Section Corner Monuments	4.000 EACH		
0468	SPV.0060 Special 26. Pedestrian Shuttle Service	1.000 EACH		
0470	SPV.0060 Special 27. Utility Line Opening (ULO)	12.000 EACH		
0472	SPV.0165 Special 01. Wall Modular Block Mechanically Stabilized Earth (R-66-87)	106.000 SF		.
0474	SPV.0165 Special 02. Wall Modular Block Gravity Landscape	45.000 SF		<u>-</u>
0476	SPV.0195 Special 01. Asphalt Repair	315.000 TON		·

Section:	0001	Total:		
----------	------	--------	--	--

Total Bid: _____.___.

PLEASE ATTACH ADDENDA HERE



Wisconsin Department of Transportation

January 2, 2024

Division of Transportation Systems Development

Bureau of Project Development 4822 Madison Yards Way, 4th Floor South Madison, WI 53705

Telephone: (608) 266-1631 Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

ASP-6 Addendum #01

Letting of January 9, 2024

Attached is a copy of the revised ASP-6. This ASP-6 replaces ASP-6 in all proposals in the January 9, 2024 Letting.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractors.

Sincerely,

Mike Coleman

Proposal Development Specialist Proposal Management Section

Additional Special Provision 6 (ASP-6) Modifications to the standard specifications

Make the following revisions to the standard specifications:

108 Prosecution and Progress

108.10.2 Excusable, Non-Compensable Delays

108.10.2.1 General

Replace entire section with the following effective with the January 2024 letting:

- (1) Non-compensable delays, 108.10.2.1(3), are excusable delays not the contractor's or the department's fault. The engineer will not pay for the delay costs listed in 109.4.7 for non-compensable delays.
- (2) For non-compensable delays under calendar day and completion date contracts, the engineer will extend contract time if the conditions specified in 108.10.1 are met. The department will relieve the contractor from associated liquidated damages, as specified in 108.11, if the engineer extends time under 108.10.1.
- (3) The following are non-compensable delays:
 - 1. Delays due to earthquakes, other cataclysmic phenomena of nature the contractor cannot foresee and avoid, severe weather or job conditions caused by recent weather as specified in 108.10.2.2.
 - 2. Extraordinary delays in material deliveries the contractor or their suppliers cannot foresee and forestall resulting from strikes, lockouts, freight embargoes, industry-wide shortages, governmental acts, or sudden disasters.
 - 3. Delays due to acts of the government, a political subdivision other than the department, or the public enemy.
 - 4. Delays from fires or epidemics.
 - 5. Delays from strikes beyond the contractor's power to settle not caused by improper acts or omissions of the contractor, their subcontractors, or their suppliers.
 - 6. Altered quantities as specified in 109.3.

108.10.3 Excusable Compensable Delays

Replace entire section with the following effective with the January 2024 letting:

- (1) Compensable delays are excusable delays due to the department's actions or lack of actions. The engineer will grant a time extension for a compensable delay if the conditions specified in 108.10.1 are met.
- (2) The following are compensable delays:
 - 1. A contract change for revised work as specified for extra work under 104.2.2.1, for a differing site condition under 104.2.2.2, or for significant changes in the character of the work under 104.2.2.4.
 - 2. A contract change for an engineer-ordered suspension under 104.2.2.3.
 - 3. The unexpected discovery of human remains, an archaeological find, or historical find consistent with 107.25.
 - 4. The unexpected discovery of a hazardous substance consistent with 107.24.
 - 5. The non-completion of work that utilities or other third parties perform, if that work is not completed as specified in the contract.
- (3) For a compensable delay or a time extension, the department will relieve the contractor from associated liquidated damages under 108.11, and will pay the contractor for delay costs determined as follows:
 - 1. Adjust the contract price as specified in 109.4.2 through 109.4.5 for delays under item 1 of 108.10.3(2).
 - 2. Adjust the contract price as specified in 109.4.7 for delays under items 2 through 5 of 108.10.3(2).

108 Prosecution and Progress

Add subsection 108.9.4.1 effective with the November 2023 letting:

108.9.4.1 Winter Suspension for Completion Date Contracts

- (1) The contractor may request a winter suspension for a completion date contract. If the department determines weather conditions do not allow for the completion of the remaining work, the department may approve the contractor's request and determine the start date of the winter suspension. The end date of the winter suspension is March 31 or a date mutually agreed upon by both parties. For multi-year contracts, the department will only consider winter suspension for the final year of the contract.
- (2) During winter suspension, store all materials in a manner that does not obstruct vehicular and pedestrian traffic and protect the materials from damage. Install traffic control and other safety devices necessary to protect the traveling public and pedestrians. Provide suitable drainage and install temporary erosion control where necessary. If the winter suspension begins when liquidated damages are being assessed, or when the work has not progressed as scheduled and would not have been completed prior to the completion date, the cost of necessary pre-suspension work is incidental. If the winter suspension begins prior to the contract

- completion date, and the work has progressed as scheduled and would have been completed prior to the completion date, the cost of pre-suspension work will be paid as specified under 109.4.
- (3) For a winter suspension that begins prior to the contract completion date and the work has progressed as scheduled and would have been completed prior to the completion date, the engineer will extend contract time to correspond with the end of the winter suspension and liquidated damages will not be assessed during the winter suspension.
- (4) For a winter suspension that begins when liquidated damages are being assessed or when the work has not progressed as scheduled and would not have been completed prior to the completion date, the engineer will not extend contract time. Time will be suspended until the end of the winter suspension. Liquidated damages will not be assessed during the winter suspension and liquidated damages will resume at the end of the winter suspension.

310 Open Graded Base

310.2 Materials

Replace paragraph two with the following effective with the November 2023 letting:

(2) The contractor may substitute material conforming to the gradation requirements for crushed aggregate specified in Table 310-01 if that material conforms to the fracture requirements for open-graded crushed gravel specified in 301.2.4.5.

TABLE 310-01 COARSE AGGREGATE (% passing by weight)

AASHTO No. 67^[1]

	COARSE AGGREGATE (% PASSING by WEIGHT)
SEIVE	AASHTO No. 67
2-inch	-
1 1/2-inch	-
1-inch	100
3/4-inch	90 – 100
1/2-inch	-
3/8-inch	20 – 55
No. 4	0 – 10
No. 8	0 – 5
No. 16	-
No. 30	-
No. 50	-
No. 100	-
No. 200	<=1.5

^[1] Size according to AASHTO M43.

390 Base Patching

390.4 Measurement

Replace entire section with the following effective with the November 2023 letting:

- (1) The department will measure Removing Pavement for Base Patching by the cubic yard acceptably completed. Measure the depth from the bottom of the adjacent pavement to the top of the patch.
- (2) The department will measure Base Patching Asphaltic by the ton acceptably completed as specified for asphaltic pavement in 450.4.
- (3) The department will measure Base Patching Concrete HES and Base Patching Concrete SHES by the cubic yard acceptably completed. Measure the depth from the bottom of the adjacent pavement to the top of the patch.

390.5 Payment

Replace entire section with the following effective with the November 2023 letting:

(1) The department will pay for measured quantities at the contract unit price under the following bid items:

ITEM NUMBER	<u>DESCRIPTION</u>	<u>UNIT</u>
390.0100	Removing Pavement for Base Patching	CY
390.0201	Base Patching Asphaltic	TON
390.0305	Base Patching Concrete HES	CY
390.0405	Base Patching Concrete SHES	CY

- (2) Payment for Removing Pavement for Base Patching is full compensation for removing old pavement; for preparing the foundation and bringing up to grade. If the engineer orders the contractor to excavate yielding or unstable subgrade materials and backfill with suitable materials, the department will pay for that work with contract bid items or as agreed upon using 109.4.
- (3) Payment for Base Patching Asphaltic is full compensation for providing and compacting asphaltic mixture including asphaltic binder.
- (4) Payment for Base Patching Concrete HES and Base Patching Concrete SHES is full compensation for providing, curing, and protecting concrete. Payment also includes providing tie bars and dowel bars in unhardened concrete and steel within the patch. For tie bars and dowel bars provided in concrete not placed under the contract, the department will pay separately under the Drilled Tie Bars and Drilled Dowel Bars bid items as specified in 416.5.
- (5) Payment for Base Patching SHES also includes providing test data to the engineer as specified in 416.2.4.
- (6) The department will pay for sawing existing concrete pavement for removal under the Sawing Concrete bid item as specified in 690.5.

460 Hot Mix Asphalt Pavement

460.2.8.2.1.3.1 Contracts with 5000 Tons of Mixture or Greater

Replace paragraph four with the following effective with the November 2023 letting:

(4) Use the test methods identified below, or other methods the engineer approves, to perform the following tests at the frequency indicated:

Blended aggregate gradations:

Drum plants:

- Field extraction by ignition oven according to WTM T308, chemical extraction according to AASHTO T-164 method A or B; or automated extraction according to WTM D8159. Gradation of resulting aggregate sample determined according to WTM T30.
- Belt samples, optional for virgin mixtures, obtained from stopped belt or from the belt discharge using an engineer-approved sampling device and performed according to WTM T11 and T27.

Batch plants:

 Field extraction by ignition oven according to WTM T308, chemical extraction according to AASHTO T-164 method A or B; or automated extraction according to WTM D8159. Gradation of resulting aggregate sample determined according to WTM T30.

Asphalt content (AC) in percent:

Determine AC using one of the following methods:

- AC by ignition oven according to WTM T308.
- AC by chemical extraction according to AASHTO T-164 method A or B.
- AC by automated extraction according to WTM D8159.
- If the department is using an ignition oven to determine AC, conform to WTP H003.
- If the department is not using an ignition oven to determine AC, ignition oven correction factor (IOCF) must still be reverified for any of the reasons listed in WTP H003 Table 2 and conform to WTP H-003 sections 3 through 6.
- Gradation of resulting aggregate sample determined according to WTM T30.

Bulk specific gravity of the compacted mixture:

According to WTM T166.

Theoretical maximum specific gravity:

According to WTM T209.

Air voids (Va) by calculation according to WTM T269.

VMA by calculation according to WTM R35.

460.2.8.3.1.4 Department Verification Testing Requirements

Replace paragraph three with the following effective with the November 2023 letting:

(3) The department will perform testing conforming to the following standards:

Bulk specific gravity (G_{mb}) of the compacted mixture according to WTM T166.

Maximum specific gravity (Gmm) according to WTM T209.

Air voids (Va) by calculation according to WTM T269.

VMA by calculation according to WTM R35.

Asphalt content by ignition oven according to WTM T308, chemical extraction according to AASHTO T-164 method A or B, or automated extraction according to WTM D8159. If using an ignition oven to determine AC, conform to WTP H-003.

503 Prestressed Concrete Members

503.2.2 Concrete

Replace paragraph five with the following effective with the November 2023 letting:

(5) Furnish prestressed concrete members cast from air-entrained concrete, except I-type girders may use non-air-entrained concrete. Use type I, IL, IS, IP, IT, II, or III cement. The contractor may replace up to 30 percent of type I, IL, II, or III cement with an equal weight of fly ash, slag, or a combination of fly ash and slag. Ensure that fly ash conforms to 501.2.4.2.2 and slag conforms to 501.2.4.2.3. Use only one source and replacement rate for work under a single bid item. Use a department-approved air-entraining admixture conforming to 501.2.5.2 for air-entrained concrete. Use only coarse aggregate conforming to 310.2(2).

604 Slope Paving

604.2 Materials

Replace paragraph three with the following effective with the November 2023 letting:

(3) Under the Slope Paving Crushed Aggregate bid item, furnish crushed stone or crushed gravel conforming to the gradation in Table 604-01, but with the additional requirements that at least 75 percent of the particles, by count, have at least one fractured face. Determine fracture according to WTM D5821.

TABLE 604-01 COARSE AGGREGATE (% passing by weight)

AASHTO No. 4^[1]

SEIVE	COARSE AGGREGATE (% PASSING by WEIGHT) AASHTO No. 4
2-inch	100
1 1/2-inch	90 - 100
1-inch	20 - 55
3/4-inch	0 - 15
1/2-inch	-
3/8-inch	0 - 5
No. 4	-
No. 8	-
No. 16	-
No. 30	-
No. 50	-
No. 100	-
No. 200	<=1.5

[1] Size according to AASHTO M43.

612 Underdrains

612.3.9 Trench Underdrains

Replace paragraph one with the following effective with the November 2023 letting:

(1) Under the Underdrain Trench bid item, excavate and backfill underdrain trenches. Backfill with coarse aggregate gradation conforming to 604.2(3). Before backfilling place geotextile as the plans show.

614 Semi-rigid Barrier Systems and End Treatments

614.2.6 Sand Barrel Arrays

Replace paragraph one with the following effective with the November 2023 letting:

(1) Furnish sand barrels from the APL. Use fine aggregate conforming to gradation shown in Table 614-2 mixed with sodium chloride conforming to AASHTO M143. Apply an object marker to front-most barrel in the array.

TABLE 014-2 TIME AGGICGATE GRADATION		
SEIVE	FINE AGGREGATE (% PASSING by WEIGHT)	
3/8-inch	100	
No. 4	90 - 100	
No. 8	-	
No. 16	45 - 85	
No. 30	-	
No. 50	5 - 30	
No. 100	0 - 10	
No. 200	<=3.5	

TABLE 614-2 FINE AGGREGATE GRADATION

628 Erosion Control

628.2.13 Rock Bags

Replace paragraph two with the following effective with the November 2023 letting:

(2) Fill the bags with a clean, sound, hard, durable, engineer-approved coarse aggregate conforming by visual inspection to the gradation specified for coarse aggregate gradation in 604.2(3).

639 Drilling Wells

639.2.1 General

Replace paragraph two with the following effective with the November 2023 letting:

(2) For grout use fine aggregate conforming to 501.2.7.2; and gradation conforming to 614.2.6(1); and type I, IL, IS, IP, or IT cement.

652 Electrical Conduit

652.3.1.2 Installing Underground

Replace paragraph two with the following effective with the November 2023 letting:

(2) Excavate trenches true to line and grade to provide the conduit uniform bearing throughout its length. Do not backfill the trench before inspecting the conduit. Carefully tamp the backfill in place as specified for placing backfill in layers in 651.3. Place at least 0.7 cubic feet of coarse aggregate gradation conforming to 604.2(3) directly under each drainage hole.

ERRATA

390.3.4 Special High Early Strength Concrete Patching

Correct errata link in paragraph (1) by changing from 416.3.8 to 416.3.7.

- (1) Construct as specified for special high early strength repairs under 416.3.7 except as follows:
 - The contractor may delay removal for up to 14 calendar days after cutting the existing pavement.
 - Open to traffic as specified for concrete base in 320.3.



Wisconsin Department of Transportation

January 2, 2024

Division of Transportation Systems Development

Bureau of Project Development 4822 Madison Yards Way, 4th Floor South Madison, WI 53705

Telephone: (608) 266-1631 Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Federal Wage Rate Addendum #01

Letting of January 9, 2024

Attached is a copy of the revised WI 10 Highway Davis Bacon Prevailing Wage Rates that are included in proposals 01 – 020 and 22 – 28; and WI 15 Heavy Davis Bacon Prevailing Wage Rates that are included in proposal 27. These wage rates are effective for all proposals they are included in in the January 9, 2024 letting. The updated wage rates are dated December 22, 2023 and are effective on or after January 1, 2024.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractors.

Sincerely,

Mike Coleman

Proposal Development Specialist Proposal Management Section

"General Decision Number: WI20230010 12/22/2023

Superseded General Decision Number: WI20220010

State: Wisconsin

Construction Type: Highway

Counties: Wisconsin Statewide.

HIGHWAY, AIRPORT RUNWAY & TAXIWAY CONSTRUCTION PROJECTS (does not include bridges over navigable waters; tunnels; buildings in highway rest areas; and railroad construction)

Note: Contracts subject to the Davis-Bacon Act are generally required to pay at least the applicable minimum wage rate required under Executive Order 14026 or Executive Order 13658. Please note that these Executive Orders apply to covered contracts entered into by the federal government that are subject to the Davis-Bacon Act itself, but do not apply to contracts subject only to the Davis-Bacon Related Acts, including those set forth at 29 CFR 5.1(a)(2)-(60).

If the contract is entered into on or after January 30, 2022, or the contract is renewed or extended (e.g., an option is exercised) on or after January 30, 2022:

- l. Executive Order 14026 generally applies to the contract.
- 1. The contractor must pay all covered workers at least \$16.20 per hour (or the applicable wage rate listed on this wage determination, if it is higher) for all hours spent performing on the contract in 2023.

If the contract was awarded on |. Executive Order 13658 or between January 1, 2015 and January 29, 2022, and the contract is not renewed or extended on or after January 30, 2022:

- generally applies to the contract.
- |. The contractor must pay all covered workers at least \$12.15 per hour (or the applicable wage rate listed on this wage determination, if it is higher) for all hours spent performing on that contract in 2023.

The applicable Executive Order minimum wage rate will be adjusted annually. If this contract is covered by one of the Executive Orders and a classification considered necessary for performance of work on the contract does not appear on this wage determination, the contractor must still submit a conformance request.

Additional information on contractor requirements and worker protections under the Executive Orders is available at http://www.dol.gov/whd/govcontracts.

Modification Number

Publication Date 01/06/2023

1	01/13/2023
_	
2	01/20/2023
3	03/31/2023
4	04/07/2023
5	05/26/2023
6	06/02/2023
7	06/16/2023
8	06/23/2023
9	07/07/2023
10	07/14/2023
11	07/28/2023
12	08/18/2023
13	09/01/2023
14	09/08/2023
15	10/13/2023
16	12/15/2023
17	12/22/2023

BRWI0001-002 06/01/2023

CRAWFORD, JACKSON, JUNEAU, LA CROSSE, MONROE, TREMPEALEAU, AND VERNON COUNTIES

	Rates	Fringes
BRICKLAYER	\$ 40.18	25.88
BRWI0002-002 06/01/2023		

ASHLAND, BAYFIELD, DOUGLAS, AND IRON COUNTIES

	Rates	Fringes	
BRICKLAYER	\$ 47.10	25.16	
BRWI0002-005 06/01/2023			_

ADAMS, ASHLAND, BARRON, BROWN, BURNETT, CALUMET, CHIPPEWA, CLARK, COLUMBIA, DODGE, DOOR, DUNN, FLORENCE, FOND DU LAC, FOREST, GREEN LAKE, IRON, JEFFERSON, KEWAUNEE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, OCONTO, ONEIDA, OUTAGAMIE, POLK, PORTAGE, RUSK, ST CROIX, SAUK, SHAWANO, SHEBOYGAN, TAYLOR, VILAS, WALWORTH, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

	Rates	Fringes
CEMENT MASON/CONCRETE FINISHER	.\$ 39.97	25.02
BRWI0003-002 06/01/2023		
BROWN, DOOR, FLORENCE, KEWAUNEE,	MARINETTE, AND	OCONTO COUNTIES
	Rates	Fringes
BRICKLAYER	.\$ 40.00	26.06
BRWI0004-002 06/01/2023		

KENOSHA, RACINE, AND WALWORTH COUNTIES

Rates Fringes

BRICKLAYER.....\$ 44.50 26.96

BRWI0006-002 06/01/2023

ADAMS, CLARK, FOREST, LANGLADE, LINCOLN, MARATHON, MENOMINEE, ONEIDA, PORTAGE, PRICE, TAYLOR, VILAS AND WOOD COUNTIES

Rates Fringes

BRICKLAYER.....\$ 40.08 25.98

BRWI0007-002 06/01/2023

GREEN, LAFAYETTE, AND ROCK COUNTIES

Rates Fringes

BRICKLAYER.....\$ 40.95 26.80

.....

BRWI0008-002 06/05/2023

MILWAUKEE, OZAUKEE, WASHINGTON, AND WAUKESHA COUNTIES

Rates Fringes

BRICKLAYER.....\$ 44.96 25.67

DDUTO044 002 05 (04 (002)

BRWI0011-002 06/01/2023

CALUMET, FOND DU LAC, MANITOWOC, AND SHEBOYGAN COUNTIES

Rates Fringes

BRICKLAYER.....\$ 40.00 26.06

BRWI0019-002 06/01/2023

BARRON, BUFFALO, BURNETT, CHIPPEWA, DUNN, EAU CLAIRE, PEPIN, PIERCE, POLK, RUSK, ST. CROIX, SAWYER AND WASHBURN COUNTIES

Rates Fringes

BRICKLAYER.....\$ 39.32 26.74

BRWI0034-002 06/01/2023

COLUMBIA AND SAUK COUNTIES

Rates Fringes

BRICKLAYER...... \$ 41.56 26.19

CARP0068-011 05/02/2022

BURNETT (W. of Hwy 48), PIERCE (W. of Hwy 29), POLK (W. of Hwys 35, 48 & 65), AND ST. CROIX (W. of Hwy 65) COUNTIES

Rates Fringes

Carpenter & Piledrivermen......\$ 41.19 27.05

CARP0264-003 06/05/2023

KENOSHA, MILWAUKEE, OZAUKEE, RACINE, WAUKESHA, AND WASHINGTON COUNTIES

Ashland, Bayfield, Forest, Iron, Langlade, Lincoln, Marathon, Oneida, Shawano, Taylor and Vilas

Rates Fringes

CARPENTER.....\$ 38.86 27.06

Piledriver.....\$ 39.43 27.02

CARP0314-001 06/05/2023

Columbia, Dane, Dodge, Grant, Green, Iowa, Jefferson, Lafayette, Richland, Rock, Sauk and Walworth

Rates Fringes

CARPENTER......\$ 38.86 27.06
Piledriver.....\$ 39.43 27.02

CARP0361-004 05/01/2018

BAYFIELD (West of Hwy 63) AND DOUGLAS COUNTIES

Rates Fringes

CARPENTER.....\$ 36.15 20.43

CARP0731-002 06/05/2023

Calumet (Eastern portion of the County), Fond Du Lac, Manitowoc and Sheboygan

Rates Fringes

CARPENTER.....\$ 38.86 27.06

Piledriver.....\$ 39.43 27.02

CARP0804-001 06/05/2023

Adams, Juneau, Portage and Wood

CARP0955-002 06/05/2023

Calumet (western portion of County), Fond Du Lac, Green Lake, Marquette, Outagamie and Winnebago

1/2/24, 7:44 AM		SAM.gov
	Rates	Fringes
CARPENTER	·	27.06 27.02
CARP1056-002 06/01/2023		
	Rates	Fringes
MILLWRIGHT	\$ 40.00	27.77
CARP1074-002 06/05/2023		
Barron, Burnett, Chippewa, Clark, Pierce, Polk, Rusk, Sawyer, St. C		
	Rates	Fringes
CARPENTER		27.06 27.02
CARP1143-002 06/05/2023		
BUFFALO, CRAWFORD, JACKSON, LA CR VERNON COUNTIES	OSSE, MONROE, T	REMPEALEAU AND
	Rates	Fringes
CARPENTERPILEDRIVER		27.06 27.02
CARP1146-002 06/05/2023		
Brown, Door, Florence, Kewaunee, Shawano	Marinette, Meno	minee and
	Rates	Fringes
CARPENTER	\$ 39.43	
CARP2337-009 06/05/2023		
KENOSHA, MILWAUKEE, OZAUKEE, RACI	NE, WASHINGTON,	AND WAUKESHA
	Rates	Fringes
PILEDRIVERMAN		34.01
ELEC0014-002 12/25/2022		
ASHLAND, BARRON, BAYFIELD, BUFFAL (except Maryville, Colby, Unity, Sherwood), CRAWFORD, DUNN, EAU CL CROSSE, MONROE, PEPIN, PIERCE, PO CROIX, SAWYER, TAYLOR, TREMPEALEA	Sherman, Fremon AIRE, GRANT, IR LK, PRICE, RICH	t, Lynn & ON, JACKSON, LA LAND, RUSK, ST

CROIX, SAWYER, TAYLOR, TREMPEALEAU, VERNON, AND WASHBURN COUNTIES

Rates Fringes Electricians:.....\$ 39.25 22.34

ELEC0014-007 05/29/2022

REMAINING COUNTIES

Rates Fringes

Teledata System Installer

Installer/Technician......\$ 29.63 3%+16.18

Low voltage construction, installation, maintenance and removal of teledata facilities (voice, data, and video) including outside plant, telephone and data inside wire, interconnect, terminal equipment, central offices, PABX, fiber optic cable and equipment, micro waves, V-SAT, bypass, CATV, WAN (wide area networks), LAN (local area networks), and ISDN (integrated systems digital network).

ELEC0127-002 06/01/2023

KENOSHA COUNTY

Rates Fringes

Electricians:.....\$ 46.05 30%+13.15

.----

ELEC0158-002 05/30/2021

BROWN, DOOR, KEWAUNEE, MANITOWOC (except Schleswig), MARINETTE(Wausuakee and area South thereof), OCONTO, MENOMINEE (East of a ine 6 miles West of the West boundary of Oconto County), SHAWANO (Except Area North of Townships of Aniwa and Hutchins) COUNTIES

Rates Fringes

ELECTRICIAN.....\$ 36.14 29.75%+10.26

ELEC0159-003 05/30/2021

COLUMBIA, DANE, DODGE (Area West of Hwy 26, except Chester and Emmet Townships), GREEN, LAKE (except Townships of Berlin, Seneca, and St. Marie), IOWA, MARQUETTE (except Townships of Neshkoka, Crystal Lake, Newton, and Springfield), and SAUK COUNTIES

Rates Fringes

ELECTRICIAN.....\$ 43.38 23.13

ELEC0219-004 06/01/2019

FLORENCE COUNTY (Townships of Aurora, Commonwealth, Fern, Florence and Homestead) AND MARINETTE COUNTY (Township of Niagara)

Rates Fringes

Electricians:

Electrical contracts over

\$180,000.....\$ 33.94 21.80

1/2/24, 7:44 AM SAM.gov Electrical contracts under \$180,000.....\$ 31.75 21.73 ELEC0242-005 05/30/2021 DOUGLAS COUNTY Rates Fringes Electricians:.....\$ 41.37 69.25% ______ ELEC0388-002 06/01/2023 ADAMS, CLARK (Colby, Freemont, Lynn, Mayville, Sherman, Sherwood, Unity), FOREST, JUNEAU, LANGLADE, LINCOLN, MARATHON, MARINETTE (Beecher, Dunbar, Goodman & Pembine), MENOMINEE (Area West of a line 6 miles West of the West boundary of Oconto County), ONEIDA, PORTAGE, SHAWANO (Aniwa and Hutchins), VILAS AND WOOD COUNTIES Rates Fringes Electricians:.....\$ 38.74 26%+11.76 ELEC0430-002 06/01/2023 RACINE COUNTY (Except Burlington Township) Rates Fringes Electricians:.....\$ 46.70 * ELEC0494-005 05/28/2023 MILWAUKEE, OZAUKEE, WASHINGTON, AND WAUKESHA COUNTIES Rates Fringes Electricians:.....\$ 47.75 26.72 -----ELEC0494-006 06/01/2021 CALUMET (Township of New Holstein), DODGE (East of Hwy 26 including Chester Township), FOND DU LAC, MANITOWOC (Schleswig), and SHEBOYGAN COUNTIES Rates Fringes Electricians:.....\$ 37.91 * ELEC0494-013 05/28/2023 DODGE (East of Hwy 26 including Chester Twp, excluding Emmet Twp), FOND DU LAC (Except Waupuin), MILWAUKEE, OZAUKEE, MANITOWOC (Schleswig), WASHINGTON, AND WAUKESHA COUNTIES Rates **Fringes** Sound & Communications Installer.....\$ 34.65 18.36

Technician.....\$ 34.65

18.36

Installation, testing, maintenance, operation and servicing of all sound, intercom, telephone interconnect, closed circuit TV systems, radio systems, background music systems, language laboratories, electronic carillion, antenna distribution systems, clock and program systems and low-voltage systems such as visual nurse call, audio/visual nurse call systems, doctors entrance register systems. Includes all wire and cable carrying audio, visual, data, light and radio frequency signals. Includes the installation of conduit, wiremold, or raceways in existing structures that have been occupied for six months or more where required for the protection of the wire or cable, but does not mean a complete conduit or raceway system. work covered does not include the installation of conduit, wiremold or any raceways in any new construction, or the installation of power supply outlets by means of which external electric power is supplied to any of the foregoing equipment or products

.....

ELEC0577-003 06/01/2022

CALUMET (except Township of New Holstein), GREEN LAKE (N. part including Townships of Berlin, St Marie, and Seneca), MARQUETTE (N. part including Townships of Crystal Lake, Neshkoro, Newton, and Springfield), OUTAGAMIE, WAUPACA, WAUSHARA, AND WINNEBAGO COUNTIES

	Rates	Fringes
Electricians:	\$ 37.41	29.50%+10.00
ELEC0890-003 06/01/2022		

DODGE (Emmet Township only), GREEN, JEFFERSON, LAFAYETTE, RACINE (Burlington Township), ROCK AND WALWORTH COUNTIES

	Rates	Fringes
Electricians:	\$ 40.70	25.95%+11.26
ELEC0953-001 06/02/2019		

	Rates	Fringes
Line Construction: (1) Lineman	\$ 47.53	21.43
Operator	\$ 42.78	19.80
(3) Equipment Operator	\$ 38.02	18.40
(4) Heavy Groundman Driver	\$ 33.27	16.88
(5) Light Groundman Driver		16.11
(6) Groundsman	\$ 26.14	14.60

ENGI0139-005 06/01/2023

	Rates	Fringes
Power Equipment Operator		
Group 1	\$ 43.77	27.40
Group 2	\$ 43.27	27.40
Group 3	\$ 42.77	27.40
Group 4	\$ 42.51	27.40

Group 5......\$ 42.22 27.40 Group 6.....\$ 36.32 27.40

HAZARDOUS WASTE PREMIUMS:

EPA Level ""A"" protection - \$3.00 per hour EPA Level ""B"" protection - \$2.00 per hour EPA Level ""C"" protection - \$1.00 per hour

POWER EQUIPMENT OPERATORS CLASSIFICATIONS

GROUP 1: Cranes, tower cranes, and derricks with or without attachments with a lifting capacity of over 100 tons; or cranes, tower cranes, and derricks with boom, leads and/or jib lengths measuring 176 feet or longer.

GROUP 2: Cranes, tower cranes and derricks with or without attachments with a lifting capacity of 100 tons or less; or cranes, tower cranes, and derricks with boom, leads, and/or jibs lengths measuring 175 feet or under and Backhoes (excavators) weighing 130,000 lbs and over; caisson rigs; pile driver; dredge operator; dredge engineer; Boat Pilot.

GROUP 3: Mechanic or welder - Heavy duty equipment; cranes with a lifting capacity of 25 tons or under; concrete breaker (manual or remote); vibratory/sonic concrete breaker; concrete laser screed; concrete slipform paver; concrete batch plant operator; concrete pvt. spreader heavy duty (rubber tired); concrete spreader & distributor; automatic subgrader (concrete); concrete grinder & planing machine; concrete slipform curb & gutter machine; slipform concrete placer; tube finisher; hydro blaster (10,000 psi & over); bridge paver; concrete conveyor system; concrete pump; Rotec type Conveyor; stabilizing mixer (self-propelled); shoulder widener; asphalt plant engineer; bituminious paver; bump cutter & grooving machine; milling machine; screed (bituminous paver); asphalt heater, planer & scarifier; Backhoes (excavators) weighing under 130,000 lbs; grader or motor patrol; tractor (scraper, dozer, pusher, loader); scraper - rubber tired (single or twin engine); endloader; hydraulic backhoe (tractor type); trenching machine; skid rigs; tractor, side boom (heavy); drilling or boring machine (mechanical heavy); roller over 5 tons; percussion or rotary drilling machine; air track; blaster; loading machine (conveyor); tugger; boatmen; winches & A-frames; post driver; material hoist.

GROUP 4: Greaser, roller steel (5 tons or less); roller (pneumatic tired) - self propelled; tractor (mounted or towed compactors & light equipment); shouldering machine; self- propelled chip spreader; concrete spreader; finishing machine; mechanical float; curing machine; power subgrader; joint sawer (multiple blade) belting machine; burlap machine; texturing machine; tractor endloader (rubber tired) - light; jeep digger; forklift; mulcher; launch operator; fireman, environmental burner

GROUP 5: Air compressor; power pack; vibrator hammer and extractor; heavy equipment, leadman; tank car heaters; stump chipper; curb machine operator; Concrete proportioning plants; generators; mudjack operator; rock breaker; crusher or screening plant; screed (milling machine); automatic belt conveyor and surge bin; pug mill operator; Oiler, pump (over 3 inches); Drilling Machine Tender, day light machine

GROUP 6: Off-road material hauler with or without ejector.

IRON0008-002 06/01/2023

BROWN, CALUMET, DOOR, FOND DU LAC, KEWAUNEE, MANITOWOC, MARINETTE, OCONTO, OUTAGAMI, SHAWANO, SHEBOYGAN, AND WINNEBAGO COUNTIES:

Rates Fringes

IRONWORKER.....\$ 43.40 30.67

Paid Holidays: New Year's Day, Memorial Day, July 4th, Labor Day, Thanksgiving Day & Christmas Day.

IRON0008-003 06/01/2023

KENOSHA, MILWAUKEE, OZAUKEE, RACINE, WALWORTH (N.E. 2/3), WASHINGTON, AND WAUKESHA COUNTIES

Rates Fringes

IRONWORKER.....\$ 41.73 30.67

Paid Holidays: New Year's Day, Memorial Day, July 4th, Labor Day, Thanksgiving Day & Christmas Day.

IRON0383-001 06/01/2023

ADAMS, COLUMBIA, CRAWFORD, DANE, DODGE, FLORENCE, FOREST, GRANT, GREENE, (Excluding S.E. tip), GREEN LAKE, IOWA, JEFFERSON, JUNEAU, LA CROSSE, LAFAYETTE, LANGLADE, MARATHON, MARQUETTE, MENOMINEE, MONROE, PORTAGE, RICHLAND, ROCK (Northern area, vicinity of Edgerton and Milton), SAUK, VERNON, WAUPACA, WAUSHARA, AND WOOD COUNTIES

Rates Fringes

IRONWORKER.....\$ 41.00 30.13

IRON0498-005 06/01/2023

GREEN (S.E. 1/3), ROCK (South of Edgerton and Milton), and WALWORTH (S.W. 1/3) COUNTIES:

Rates Fringes

IRONWORKER.....\$ 45.18 47.08

IRON0512-008 04/30/2023

BARRON, BUFFALO, CHIPPEWA, CLARK, DUNN, EAU CLAIRE, JACKSON, PEPIN, PIERCE, POLK, RUSK, ST CROIX, TAYLOR, AND TREMPEALEAU COUNTIES

Rates Fringes

IRONWORKER.....\$ 43.00 34.11

IRON0512-021 04/30/2023

ASHLAND, BAYFIELD, BURNETT, DOUGLAS, IRON, LINCOLN, ONEIDA, PRICE, SAWYER, VILAS AND WASHBURN COUNTIES

	Rates	Fringes	
IRONWORKER	\$ 39.14	34.00	
			-

LAB00113-002 06/01/2023

MILWAUKEE AND WAUKESHA COUNTIES

	Ra	tes F	ringes
LABORER			
Group	1\$ 3	3.56	23.86
Group	2\$ 3	3.71	23.86
Group	3\$ 3	3.91	23.86
Group	4\$ 3	4.06	23.86
Group	5\$ 3	4.21	23.86
Group	6\$ 3	0.05	23.86

LABORERS CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster and Powderman

GROUP 6: Flagperson; traffic control person

LAB00113-003 06/01/2023

OZAUKEE AND WASHINGTON COUNTIES

		Rates	Fringes
LABORER			
Group	1	\$ 32.81	23.86
Group	2	\$ 32.91	23.86
Group	3	\$ 32.96	23.86
Group	4	\$ 33.16	23.86
Group	5	\$ 33.01	23.86
Group	6	\$ 29.90	23.86

LABORERS CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated);

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster; powderman

GROUP 6: Flagperson and Traffic Control Person

LABO0113-011 06/01/2023

KENOSHA AND RACINE COUNTIES

	Rates	Fringes
LABORER		
Group 1	\$ 32.62	23.86
Group 2	\$ 32.77	23.86
Group 3	\$ 32.97	23.86
Group 4	\$ 32.94	23.86
Group 5	\$ 33.27	23.86
Group 6	\$ 29.76	23.86

LABORERS CLASSIFICATIONS:

GROUP 1: General laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster and Powderman

GROUP 6: Flagman; traffic control person

LABO0140-002 06/01/2023

ADAMS, ASHLAND, BARRON, BAYFIELD, BROWN, BUFFALO, BURNETT, CALUMET, CHIPPEWA, CLARK, COLUMBIA, CRAWFORD, DODGE, DOOR, DOUGLAS, DUNN, EAU CLAIRE, FLORENCE, FOND DU LAC, FOREST, GRANT, GREEN, GREEN LAKE, IRON, JACKSON, JUNEAU, IOWA, JEFFERSON, KEWAUNEE, LA CROSSE, LAFAYETTE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, MONROE, OCONTO, ONEIDA, OUTAGAMIE, PEPIN, PIERCE, POLK, PORTAGE, PRICE, RICHLAND, ROCK, RUSK, SAUK, SAWYER, SHAWANO, SHEBOYGAN, ST. CROIX, TAYLOR, TREMPEALEAU, VERNON, VILLAS, WALWORTH, WASHBURN, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

		Rates	Fringes
LABORER			
Group	1	\$ 37.57	19.25
Group	2	\$ 37.67	19.25
Group	3	\$ 37.72	19.25
Group	4	\$ 37.92	19.25
Group	5	\$ 37.77	19.25
Group	6	\$ 34.20	19.25

LABORER CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bitminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator, Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk and Pavement); Strike Off Man

GROUP 4: Line and Grade Secialist

GROUP 5: Blaster; powderman

GROUP 6: Flagperson; Traffic Control

LAB00464-003 06/01/2023

DANE COUNTY

	Rates	Fringes
LABORER		
Group 1	\$ 37.85	19.25
Group 2	\$ 37.95	19.25
Group 3	\$ 38.00	19.25
Group 4	\$ 38.20	19.25
Group 5	\$ 38.05	19.25
Group 6	\$ 34.20	19.25

LABORERS CLASSIFICATIONS:

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and

Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminious Worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster; Powderman

GROUP 6: Flagperson and Traffic Control Person

PAIN0106-008 05/01/2023

ASHLAND, BAYFIELD, BURNETT, AND DOUGLAS COUNTIES

	Ī	Rates	Fringes
Painters:			
New:			
Brush,	Roller\$	34.59	24.84
Spray,	Sandblast, Steel\$	35.19	24.84
Repaint	•		
Brush,	Roller\$	33.09	24.84
Spray,	Sandblast, Steel\$	33.69	24.84

PAIN0108-002 06/01/2023

RACINE COUNTY

	Rates	Fringes	
Painters: Brush, Roller Spray & Sandblast	•	21.95 21.95	

PAIN0259-002 05/01/2008

BARRON, CHIPPEWA, DUNN, EAU CLAIRE, PEPIN, PIERCE, POLK, RUSK, SAWYER, ST. CROIX, AND WASHBURN COUNTIES

	Rates	Fringes
PAINTER	\$ 24.11	12.15
PATN0259-004 05/01/2015		

BUFFALO, CRAWFORD, JACKSON, LA CROSSE, MONROE, TREMPEALEAU, AND **VERNON COUNTIES**

	Rates	Fringes
PAINTER	\$ 22.03	12.45

PAIN0781-002 06/01/2023

JEFFERSON, MILWAUKEE, OZAUKEE, WASHINGTON, AND WAUKESHA COUNTIES

JEFFERSON, MILWAUKEE, OZAUKEE, WA	ASHINGTON, AND W	IAUKESHA COUNTIES
	Rates	Fringes
Painters: BridgeBrushSpray & Sandblast	\$ 39.09 \$ 39.84	24.86 24.86 24.86
PAIN0802-002 06/01/2023		
COLUMBIA, DANE, DODGE, GRANT, GRE ROCK, AND SAUK COUNTIES	EN, IOWA, LAFAY	ETTE, RICHLAND,
	Rates	Fringes
PAINTER Brush	\$ 35.00	20.62
PREMIUM PAY: Structural Steel, Spray, Bridge hour.		·
PAIN0802-003 06/01/2023		
ADAMS, BROWN, CALUMET, CLARK, DOC LAKE, IRON, JUNEAU, KEWAUNEE, LAN MARATHON, MARINETTE, MARQUETTE, M OUTAGAMIE, PORTAGE, PRICE, SHAWAN WAUSHARA, WAUPACA, WINNEBAGO, AND	IGLADE, LINCOLN, MENOMINEE, OCON IO, SHEBOYGAN,	MANITOWOC, ITO, ONEIDA,
	Rates	Fringes
PAINTER	•	20.62
PAIN0934-001 06/01/2022		
KENOSHA AND WALWORTH COUNTIES		
	Rates	Fringes
Painters: BrushSprayStructural Steel	\$ 37.70 \$ 36.85	24.69 24.69 24.69
PAIN1011-002 06/06/2021		
FLORENCE COUNTY		
	Rates	Fringes
Painters:	•	14.38
PLAS0599-002 06/01/2023		
	Rates	Fringes
CEMENT MASON/CONCRETE FINISHER Area A	\$ 45.17	27.27

Area	B\$	39.97	25.02
Area	C\$	40.40	25.25
Area	D\$	41.16	24.49
Area	E\$	40.50	25.14
Area	F\$	36.98	28.67

AREA DESCRIPTIONS

AREA A: ASHLAND, BURNETT, BAYFIELD, DOUGLAS, IRON, PRICE, SAWYER, AND WASHBURN COUNTIES

AREA B: ADAMS, BARRON, BROWN, CALUMET, CHIPPEWA, CLARK, COLUMBIA, DODGE, DOOR, DUNN, FLORENCE, FOND DU LAC, FOREST, GREEN LAKE, JEFFERSON, KEWAUNEE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, OCONTO, ONEIDA, OUTAGAMIE, POLK, PORTAGE, RUSK, ST. CROIX, SAUK, SHAWANO, SHEBOYGAN, TAYLOR, VILAS, WALWORTH, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

AREA C: BUFFALO, CRAWFORD, EAU CLAIRE, JACKSON, JUNEAU, LA CROSSE, MONROE, PEPIN, PIERCE, RICHLAND, TREMPEALEAU, AND VERNON COUNTIES

AREA D: MILWAUKEE, OZAUKEE, WASHINGTON, AND WAUKESHA COUNTIES

AREA E: DANE, GRANT, GREEN, IOWA, LAFAYETTE, AND ROCK COUNTIES

AREA F: KENOSHA AND RACINE COUNTIES

TEAM0039-001 06/01/2023

	Rates	Fringes
TRUCK DRIVER 1 & 2 Axles	\$ 35.57	26.09
3 or more Axles; Euclids,		
Dumptor & Articulated, Truck Mechanic	\$ 35.72	26.09

WELDERS - Receive rate prescribed for craft performing

operation to which welding is incidental.

Note: Executive Order (EO) 13706, Establishing Paid Sick Leave for Federal Contractors applies to all contracts subject to the Davis-Bacon Act for which the contract is awarded (and any solicitation was issued) on or after January 1, 2017. If this contract is covered by the EO, the contractor must provide employees with 1 hour of paid sick leave for every 30 hours they work, up to 56 hours of paid sick leave each year. Employees must be permitted to use paid sick leave for their own illness, injury or other health-related needs, including preventive care; to assist a family member (or person who is like family to the employee) who is ill, injured, or has other health-related needs, including preventive care; or for reasons resulting from, or to assist a family member (or person who is like family to the employee) who is a victim of, domestic violence, sexual assault, or stalking. Additional information on contractor requirements and worker protections under the EO is available at

https://www.dol.gov/agencies/whd/government-contracts.

Unlisted classifications needed for work not included within the scope of the classifications listed may be added after award only as provided in the labor standards contract clauses (29CFR 5.5 (a) (1) (ii)).

The body of each wage determination lists the classification and wage rates that have been found to be prevailing for the cited type(s) of construction in the area covered by the wage determination. The classifications are listed in alphabetical order of ""identifiers" that indicate whether the particular rate is a union rate (current union negotiated rate for local), a survey rate (weighted average rate) or a union average rate (weighted union average rate).

Union Rate Identifiers

A four letter classification abbreviation identifier enclosed in dotted lines beginning with characters other than ""SU"" or ""UAVG"" denotes that the union classification and rate were prevailing for that classification in the survey. Example: PLUM0198-005 07/01/2014. PLUM is an abbreviation identifier of the union which prevailed in the survey for this classification, which in this example would be Plumbers. 0198 indicates the local union number or district council number where applicable, i.e., Plumbers Local 0198. The next number, 005 in the example, is an internal number used in processing the wage determination. 07/01/2014 is the effective date of the most current negotiated rate, which in this example is July 1, 2014.

Union prevailing wage rates are updated to reflect all rate changes in the collective bargaining agreement (CBA) governing this classification and rate.

Survey Rate Identifiers

Classifications listed under the ""SU"" identifier indicate that no one rate prevailed for this classification in the survey and the published rate is derived by computing a weighted average rate based on all the rates reported in the survey for that classification. As this weighted average rate includes all rates reported in the survey, it may include both union and non-union rates. Example: SULA2012-007 5/13/2014. SU indicates the rates are survey rates based on a weighted average calculation of rates and are not majority rates. LA indicates the State of Louisiana. 2012 is the year of survey on which these classifications and rates are based. The next number, 007 in the example, is an internal number used in producing the wage determination. 5/13/2014 indicates the survey completion date for the classifications and rates under that identifier.

Survey wage rates are not updated and remain in effect until a new survey is conducted.

Union Average Rate Identifiers

Classification(s) listed under the UAVG identifier indicate that no single majority rate prevailed for those classifications; however, 100% of the data reported for the classifications was union data. EXAMPLE: UAVG-OH-0010

08/29/2014. UAVG indicates that the rate is a weighted union average rate. OH indicates the state. The next number, 0010 in the example, is an internal number used in producing the wage determination. 08/29/2014 indicates the survey completion date for the classifications and rates under that identifier.

A UAVG rate will be updated once a year, usually in January of each year, to reflect a weighted average of the current negotiated/CBA rate of the union locals from which the rate is based.

WAGE DETERMINATION APPEALS PROCESS

- 1.) Has there been an initial decision in the matter? This can be:
- * an existing published wage determination
- * a survey underlying a wage determination
- * a Wage and Hour Division letter setting forth a position on a wage determination matter
- * a conformance (additional classification and rate) ruling

On survey related matters, initial contact, including requests for summaries of surveys, should be with the Wage and Hour National Office because National Office has responsibility for the Davis-Bacon survey program. If the response from this initial contact is not satisfactory, then the process described in 2.) and 3.) should be followed.

With regard to any other matter not yet ripe for the formal process described here, initial contact should be with the Branch of Construction Wage Determinations. Write to:

Branch of Construction Wage Determinations Wage and Hour Division U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

2.) If the answer to the question in 1.) is yes, then an interested party (those affected by the action) can request review and reconsideration from the Wage and Hour Administrator (See 29 CFR Part 1.8 and 29 CFR Part 7). Write to:

Wage and Hour Administrator U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

The request should be accompanied by a full statement of the interested party's position and by any information (wage payment data, project description, area practice material, etc.) that the requestor considers relevant to the issue.

3.) If the decision of the Administrator is not favorable, an interested party may appeal directly to the Administrative Review Board (formerly the Wage Appeals Board). Write to:

Administrative Review Board U.S. Department of Labor 200 Constitution Avenue, N.W.

Washington, DC 20210

4.) All decisions by the Administrative Review Board are final.

END OF GENERAL DECISION

"General Decision Number: WI20230015 12/22/2023

Superseded General Decision Number: WI20220015

State: Wisconsin

Construction Type: Heavy

Counties: Wisconsin Statewide.

HEAVY CONSTRUCTION PROJECTS (Excluding Tunnel, Sewer, and Water

Lines).

Note: Contracts subject to the Davis-Bacon Act are generally required to pay at least the applicable minimum wage rate required under Executive Order 14026 or Executive Order 13658. Please note that these Executive Orders apply to covered contracts entered into by the federal government that are subject to the Davis-Bacon Act itself, but do not apply to contracts subject only to the Davis-Bacon Related Acts, including those set forth at 29 CFR 5.1(a)(2)-(60).

If the contract is entered into on or after January 30, 2022, or the contract is renewed or extended (e.g., an option is exercised) on or after January 30, 2022:

- l. Executive Order 14026 generally applies to the contract.
- 1. The contractor must pay all covered workers at least \$16.20 per hour (or the applicable wage rate listed on this wage determination, if it is higher) for all hours spent performing on the contract in 2023.

If the contract was awarded on |. Executive Order 13658 or between January 1, 2015 and January 29, 2022, and the contract is not renewed or extended on or after January 30, 2022:

- generally applies to the contract.
- |. The contractor must pay all covered workers at least \$12.15 per hour (or the applicable wage rate listed on this wage determination, if it is higher) for all hours spent performing on that contract in 2023.

The applicable Executive Order minimum wage rate will be adjusted annually. If this contract is covered by one of the Executive Orders and a classification considered necessary for performance of work on the contract does not appear on this wage determination, the contractor must still submit a conformance request.

Additional information on contractor requirements and worker protections under the Executive Orders is available at http://www.dol.gov/whd/govcontracts.

Modification Number

Publication Date

1

01/06/2023 01/13/2023

https://sam.gov/wage-determination/WI20230015/20

2	01/20/2023
3	03/31/2023
4	04/07/2023
5	05/26/2023
6	06/02/2023
7	06/09/2023
8	06/16/2023
9	06/23/2023
10	06/30/2023
11	07/07/2023
12	07/14/2023
13	07/28/2023
14	08/04/2023
15	08/18/2023
16	09/01/2023
17	09/08/2023
18	10/13/2023
19	12/15/2023
20	12/22/2023

BOIL0107-001 01/01/2021

	Rates	Fringes	
BOILERMAKER			
Boilermaker	\$ 39.52	31.50	
Small Boiler Repair (under			
25,000 lbs/hr)	\$ 26.91	16.00	
DDUTAGO			
BRWI0001-002 06/01/2023			

CRAWFORD, JACKSON, JUNEAU, LA CROSSE, MONROE, TREMPEALEAU, AND VERNON COUNTIES

	Rates	Fringes
BRICKLAYER	\$ 40.18	25.88

BRWI0002-002 06/01/2023

ASHLAND, BAYFIELD, DOUGLAS, AND IRON COUNTIES

	Rates	Fringes
BRICKLAYER	.\$ 47.10	25.16

BRWI0002-005 06/01/2023

ADAMS, ASHLAND, BARRON, BROWN, BURNETT, CALUMET, CHIPPEWA, CLARK, COLUMBIA, DODGE, DOOR, DUNN, FLORENCE, FOND DU LAC, FOREST, GREEN LAKE, IRON, JEFFERSON, KEWAUNEE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, OCONTO, ONEIDA, OUTAGAMIE, POLK, PORTAGE, RUSK, ST CROIX, SAUK, SHAWANO, SHEBOYGAN, TAYLOR, VILAS, WALWORTH, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

	Rates	Fringes	
CEMENT MASON/CONCRETE FINISHER.	\$ 39.97	25.02	
BRWI0003-002 06/01/2023			

BROWN, DOOR, FLORENCE, KEWAUNEE, MARINETTE, AND OCONTO COUNTIES

	Rates	Fringes
BRICKLAYER		26.06
BRWI0004-002 06/01/2023		
KENOSHA, RACINE, AND WALWORTH CO	OUNTIES	
	Rates	Fringes
BRICKLAYER		26.96
BRWI0006-002 06/01/2023		
ADAMS, CLARK, FOREST, LANGLADE, ONEIDA, PORTAGE, PRICE, TAYLOR,		
	Rates	Fringes
BRICKLAYER	\$ 40.08	25.98
BRWI0007-002 06/01/2023		
GREEN, LAFAYETTE, AND ROCK COUN	TIES	
	Rates	Fringes
BRICKLAYER		26.80
BRWI0008-002 06/05/2023		
, ,		
MILWAUKEE, OZAUKEE, WASHINGTON,	AND WAUKESHA	A COUNTIES
	AND WAUKESHA	A COUNTIES Fringes
	Rates	
MILWAUKEE, OZAUKEE, WASHINGTON,	Rates	Fringes
MILWAUKEE, OZAUKEE, WASHINGTON, BRICKLAYER	Rates \$ 44.96	Fringes 25.67
MILWAUKEE, OZAUKEE, WASHINGTON, BRICKLAYER BRWI0009-001 06/01/2023 GREEN LAKE, MARQUETTE, OUTAGAMI	Rates \$ 44.96	Fringes 25.67
MILWAUKEE, OZAUKEE, WASHINGTON, BRICKLAYER BRWI0009-001 06/01/2023 GREEN LAKE, MARQUETTE, OUTAGAMI AND WINNEBAGO COUNTIES BRICKLAYER	Rates\$ 44.96\$ SHAWANO, WARATES\$ 40.00	Fringes 25.67
MILWAUKEE, OZAUKEE, WASHINGTON, BRICKLAYER BRWI0009-001 06/01/2023 GREEN LAKE, MARQUETTE, OUTAGAMI AND WINNEBAGO COUNTIES	Rates\$ 44.96\$ SHAWANO, WARATES\$ 40.00	Fringes 25.67 NAUPACA, WASHARA, Fringes
MILWAUKEE, OZAUKEE, WASHINGTON, BRICKLAYER BRWI0009-001 06/01/2023 GREEN LAKE, MARQUETTE, OUTAGAMI AND WINNEBAGO COUNTIES BRICKLAYER	Rates\$ 44.96 E, SHAWANO, W Rates\$ 40.00	Fringes 25.67 NAUPACA, WASHARA, Fringes 26.06
MILWAUKEE, OZAUKEE, WASHINGTON, BRICKLAYER BRWI0009-001 06/01/2023 GREEN LAKE, MARQUETTE, OUTAGAMI AND WINNEBAGO COUNTIES BRICKLAYER BRWI0011-002 06/01/2023	Rates\$ 44.96 E, SHAWANO, W Rates\$ 40.00	Fringes 25.67 NAUPACA, WASHARA, Fringes 26.06 SAN COUNTIES
MILWAUKEE, OZAUKEE, WASHINGTON, BRICKLAYER BRWI0009-001 06/01/2023 GREEN LAKE, MARQUETTE, OUTAGAMI AND WINNEBAGO COUNTIES BRICKLAYER BRWI0011-002 06/01/2023	Rates \$ 44.96 E, SHAWANO, W Rates \$ 40.00 AND SHEBOYO	Fringes 25.67 NAUPACA, WASHARA, Fringes 26.06 GAN COUNTIES
MILWAUKEE, OZAUKEE, WASHINGTON, BRICKLAYER BRWI0009-001 06/01/2023 GREEN LAKE, MARQUETTE, OUTAGAMI AND WINNEBAGO COUNTIES BRICKLAYER BRWI0011-002 06/01/2023 CALUMET, FOND DU LAC, MANITOWOC	Rates \$ 44.96 E, SHAWANO, W Rates \$ 40.00 AND SHEBOYO	Fringes 25.67 NAUPACA, WASHARA, Fringes 26.06 SAN COUNTIES Fringes
MILWAUKEE, OZAUKEE, WASHINGTON, BRICKLAYER BRWI0009-001 06/01/2023 GREEN LAKE, MARQUETTE, OUTAGAMI AND WINNEBAGO COUNTIES BRICKLAYER BRWI0011-002 06/01/2023 CALUMET, FOND DU LAC, MANITOWOC BRICKLAYER	Rates\$ 44.96 E, SHAWANO, W Rates\$ 40.00 Rates\$ 40.00	Fringes 25.67 NAUPACA, WASHARA, Fringes 26.06 SAN COUNTIES Fringes
MILWAUKEE, OZAUKEE, WASHINGTON, BRICKLAYER BRWI0009-001 06/01/2023 GREEN LAKE, MARQUETTE, OUTAGAMI AND WINNEBAGO COUNTIES BRICKLAYER BRWI0011-002 06/01/2023 CALUMET, FOND DU LAC, MANITOWOC BRICKLAYER BRWI0013-002 06/01/2023	Rates\$ 44.96 E, SHAWANO, W Rates\$ 40.00 Rates\$ 40.00	Fringes 25.67 NAUPACA, WASHARA, Fringes 26.06 SAN COUNTIES Fringes

BRWI0019-002 06/01/2023

BARRON, BUFFALO, BURNETT, CHIPPEWA, DUNN, EAU CLAIRE, PEPIN, PIERCE, POLK, RUSK, ST. CROIX, SAWYER AND WASHBURN COUNTIES

Rates **Fringes** BRICKLAYER.....\$ 39.32 26.74 -----BRWI0021-002 06/01/2023 DODGE AND JEFFERSON COUNTIES Rates Fringes BRICKLAYER.....\$ 40.49 BRWI0034-002 06/01/2023 COLUMBIA AND SAUK COUNTIES Rates Fringes BRICKLAYER.....\$ 41.56 26.19 CARP0068-011 05/02/2022 BURNETT (W. of Hwy 48), PIERCE (W. of Hwy 29), POLK (W. of Hwys 35, 48 & 65), AND ST. CROIX (W. of Hwy 65) COUNTIES

KENOSHA, MILWAUKEE, OZAUKEE, RACINE, WAUKESHA, AND WASHINGTON COUNTIES

Ashland, Bayfield, Forest, Iron, Langlade, Lincoln, Marathon, Oneida, Shawano, Taylor and Vilas

Rates Fringes

CARPENTER......\$ 38.86 27.06
Piledriver......\$ 39.43 27.02

CARP0314-001 06/05/2023

Columbia, Dane, Dodge, Grant, Green, Iowa, Jefferson, Lafayette, Richland, Rock, Sauk and Walworth

Rates Fringes

CARPENTER.....\$ 38.86 27.06 Piledriver.....\$ 39.43

CARP0361-004 05/01/2018

BAYFIELD (West of Hwy 63) AND DOUGLAS COUNTIES

Rates Fringes CARPENTER.....\$ 36.15 20.43 -----

CARP0731-002 06/05/2023

Calumet (Eastern portion of the County), Fond Du Lac, Manitowoc and Sheboygan

Rates Fringes CARPENTER.....\$ 38.86 27.06 Piledriver.....\$ 39.43

CARP0804-001 06/05/2023

Adams, Juneau, Portage and Wood

Fringes Rates 27.06 CARPENTER.....\$ 38.86 Piledriver.....\$ 39.43 27.02

CARP0955-002 06/05/2023

Calumet (western portion of County), Fond Du Lac, Green Lake, Marquette, Outagamie and Winnebago

Fringes CARPENTER.....\$ 38.86 27.06 PILEDRIVER.....\$ 39.43 27.02

Rates

CARP1056-002 06/01/2023

Rates Fringes MILLWRIGHT.....\$ 40.00 27.77

CARP1074-002 06/05/2023

Barron, Burnett, Chippewa, Clark, Dunn, Eau Claire, Pepin, Pierce, Polk, Rusk, Sawyer, St. Croix and Washburn

Rates Fringes CARPENTER.....\$ 38.86 27.06 PILEDRIVER.....\$ 39.43 27.02

CARP1143-002 06/05/2023

BUFFALO, CRAWFORD, JACKSON, LA CROSSE, MONROE, TREMPEALEAU AND **VERNON COUNTIES**

CARP1146-002 06/05/2023

Brown, Door, Florence, Kewaunee, Marinette, Menominee and Shawano

	Rates	Fringes	
CARPENTER	\$ 38.86	27.06	
PILEDRIVER	\$ 39.43	27.02	
CARRA337 000 06/05/3033			

CARP2337-009 06/05/2023

KENOSHA, MILWAUKEE, OZAUKEE, RACINE, WASHINGTON, AND WAUKESHA

Rates Fringes
PILEDRIVERMAN.....\$ 39.22 34.01

CARP2337-010 06/01/2023

KENOSHA, MILWAUKEE, OZAUKEE, RACINE, WASHINGTON, AND WAUKESHA

ELEC0014-002 12/25/2022

ASHLAND, BARRON, BAYFIELD, BUFFALO, BURNETT, CHIPPEWA, CLARK (except Maryville, Colby, Unity, Sherman, Fremont, Lynn & Sherwood), CRAWFORD, DUNN, EAU CLAIRE, GRANT, IRON, JACKSON, LA CROSSE, MONROE, PEPIN, PIERCE, POLK, PRICE, RICHLAND, RUSK, ST CROIX, SAWYER, TAYLOR, TREMPEALEAU, VERNON, AND WASHBURN COUNTIES

Rates

Fringes

REMAINING COUNTIES

Teledata System Installer
Installer/Technician......\$ 29.63 3%+16.18

Low voltage construction, installation, maintenance and removal of teledata facilities (voice, data, and video) including outside plant, telephone and data inside wire, interconnect, terminal equipment, central offices, PABX, fiber optic cable and equipment, micro waves, V-SAT, bypass, CATV, WAN (wide area networks), LAN (local area networks), and ISDN (integrated systems digital network).

KENOSHA COUNTY

Rates Fringes

Electricians:.....\$ 46.05 30%+13.15

ELEC0158-002 05/30/2021

BROWN, DOOR, KEWAUNEE, MANITOWOC (except Schleswig), MARINETTE(Wausuakee and area South thereof), OCONTO, MENOMINEE (East of a ine 6 miles West of the West boundary of Oconto County), SHAWANO (Except Area North of Townships of Aniwa and Hutchins) COUNTIES

COLUMBIA, DANE, DODGE (Area West of Hwy 26, except Chester and Emmet Townships), GREEN, LAKE (except Townships of Berlin, Seneca, and St. Marie), IOWA, MARQUETTE (except Townships of Neshkoka, Crystal Lake, Newton, and Springfield), and SAUK COUNTIES

FLORENCE COUNTY (Townships of Aurora, Commonwealth, Fern, Florence and Homestead) AND MARINETTE COUNTY (Township of Niagara)

Rates Fringes

Electricians:
 Electrical contracts over
 \$180,000......\$ 33.94 21.80
 Electrical contracts under
 \$180,000......\$ 31.75 21.73

ELEC0242-005 05/30/2021

DOUGLAS COUNTY

ADAMS, CLARK (Colby, Freemont, Lynn, Mayville, Sherman, Sherwood, Unity), FOREST, JUNEAU, LANGLADE, LINCOLN, MARATHON, MARINETTE (Beecher, Dunbar, Goodman & Pembine), MENOMINEE (Area West of a line 6 miles West of the West boundary of Oconto County), ONEIDA, PORTAGE, SHAWANO (Aniwa and Hutchins), VILAS AND WOOD COUNTIES

Rates **Fringes** Electricians:.....\$ 38.74 26%+11.76 ELEC0430-002 06/01/2023 RACINE COUNTY (Except Burlington Township) Rates Fringes Electricians:.....\$ 46.70 25.02 -----* ELEC0494-005 05/28/2023 MILWAUKEE, OZAUKEE, WASHINGTON, AND WAUKESHA COUNTIES Rates **Fringes** Electricians:.....\$ 47.75 26.72 ELEC0494-006 06/01/2021

CALUMET (Township of New Holstein), DODGE (East of Hwy 26 including Chester Township), FOND DU LAC, MANITOWOC (Schleswig), and SHEBOYGAN COUNTIES

Rates Fringes

Electricians:.....\$ 37.91 22.74

DODGE (East of Hwy 26 including Chester Twp, excluding Emmet Twp), FOND DU LAC (Except Waupuin), MILWAUKEE, OZAUKEE, MANITOWOC (Schleswig), WASHINGTON, AND WAUKESHA COUNTIES

	Rates	Fringes
Sound & Communications		
Installer	\$ 34.65	18.36
Technician	\$ 34.65	18.36

Installation, testing, maintenance, operation and servicing of all sound, intercom, telephone interconnect, closed circuit TV systems, radio systems, background music systems, language laboratories, electronic carillion, antenna distribution systems, clock and program systems and low-voltage systems such as visual nurse call, audio/visual nurse call systems, doctors entrance register systems. Includes all wire and cable carrying audio, visual, data, light and radio frequency signals. Includes the installation of conduit, wiremold, or raceways in existing structures that have been occupied for six months or more where required for the protection of the wire or cable, but does not mean a complete conduit or raceway system. work covered does not include the installation of conduit, wiremold or any raceways in any new construction, or the installation of power supply outlets by means of which external electric power is supplied to any of the foregoing equipment or products

^{*} ELEC0494-013 05/28/2023

ELEC0577-003 06/01/2022

CALUMET (except Township of New Holstein), GREEN LAKE (N. part including Townships of Berlin, St Marie, and Seneca), MARQUETTE (N. part including Townships of Crystal Lake, Neshkoro, Newton, and Springfield), OUTAGAMIE, WAUPACA, WAUSHARA, AND WINNEBAGO COUNTIES

	Rates	Fringes	
Electricians:	\$ 37.41	29.50%+10.00	
ELEC0890-003 06/01/2022			

DODGE (Emmet Township only), GREEN, JEFFERSON, LAFAYETTE, RACINE (Burlington Township), ROCK AND WALWORTH COUNTIES

	Rates	Fringes	
Electricians:	\$ 40.70	25.95%+11.26	

ELEC0953-001 06/02/2019

	Rates	Fringes
Line Construction: (1) Lineman\$ (2) Heavy Equipment Operator\$ (3) Equipment Operator\$ (4) Heavy Groundman Driver\$ (5) Light Groundman Driver\$ (6) Groundsman\$	42.78 38.02 33.27 30.89	21.43 19.80 18.40 16.88 16.11 14.60

ENGI0139-001 06/01/2023

KENOSHA, MILWAUKEE, OZAUKEE, RACINE, WASHINGTON, AND WAUKESHA COUNTIES

	Rates	Fringes
Power Equipment Operator		
Group 1	\$ 50.21	24.05
Group 2	\$ 49.71	24.05
Group 3	\$ 49.21	24.05
Group 4	\$ 48.37	24.05
Group 5	\$ 44.39	24.05
Group 6	\$ 39.24	24.05

HAZARDOUS WASTE PREMIUMS:

EPA Level ""A"" Protection: \$3.00 per hour EPA Level ""B"" Protection: \$2.00 per hour EPA Level ""C"" Protection: \$1.00 per hour

POWER EQUIPMENT OPERATORS CLASSIFICATIONS

GROUP 1: Cranes, Tower Cranes, Pedestal Tower Cranes and Derricks with or w/o attachments with a lifting capacity of over 100 tons; or Cranes, Tower Cranes, Pedestal Tower Cranes and Derricks with boom, leads, and/or jib lengths measuring 176 feet or longer; Self-Erecting Tower Cranes over 4000 lbs lifting capacity; All Cranes with Boom

Dollies; Boring Machines (directional); Master Mechanic. \$0.50 additional per hour per 100 tons or 100 ft of boom over 200 ft or lifting capacity of crane over 200 tons to a maximum of 300 tons or 300 ft. Thereafter an increase of \$0.01 per ft or ton, whichever is greater.

- GROUP 2: Cranes, Tower Cranes, Pedestal Tower Cranes and Derricks with or without attachments with a lifting capacity of 100 tons or less; or Cranes, Tower Cranes Portable Tower Cranes, Pedestal Tower Cranes and Derricks with boom, leadsand/or jib lengths measuring 175 feet or less; Backhoes (excavators) 130,000 lbs and over; Caisson Rigs; Pile Drivers; Boring Machines (vertical or horizontal), Versi-Lift, Tri-Lift, Gantry 20,000 lbs & over.
- GROUP 3: Backhoe (excavator) under 130,000 lbs;Self-erecting Tower Crane 4000 lbs & under lifting capacity;Traveling Crane (bridge type); Skid Rigs; Dredge Operator; Mechanic; Concrete Paver (over 27E); Concrete Spreader and Distributor; Forklift/ Telehandler (machinery- moving / steel erection); Hydro Blaster, 10,000 psi and over
- GROUP 4: Material Hoists; Stack Hoists; Hydraulic Backhoe (tractor or truck mounted); Hydraulic Crane, 5 tons or under (tractor or truck mounted); Hoist (tuggers 5 tons & over); Hydro-Excavators/Daylighters; Concrete Pumps Rotec type Conveyors; Tractor/Bulldozer/End Loader (over 40 hp); Motor Patrol; Scraper Operator; Sideboom; Straddle Carrier; Welder; Bituminous Plant and Paver Operator; Roller over 5 tons; Rail Leveling Machine (Railroad); Tie Placer; Tie Extractor; Tie Tamper; Stone Leveler; Rotary Drill Operator and Blaster; Percussion Drill Operator; Air Track Drill and/or Hammers; Gantrys (under 20,000 lbs); Tencher (wheel type or chain type having 8 inch or larger bucket); Milling Machine; Off-Road Material Haulers.
- GROUP 5: Backfiller; Concrete Auto Breaker (large); Concrete Finishing Machines (road type); Rubber Tired Roller; Concrete Batch Hopper; Concrete Conveyor Systems; Grout Pumps; Concrete Mixers (14S or over); Screw Type Pumps and Gypsum Pumps; Tractor, Bulldozer, End Loader (under 40 hp); Trencher (chain type, bucket under 8 inch); Industrial Locomotives; Rollers under 5 tons; Stump Grinder/Chipper (Large); Timber Equipment; Firemen (pile drivers and derricks); Personnel Hoist, Telehandler over 8000 lbs; Robotic Tool Carrier with or without attachments
- GROUP 6: Tampers Compactors (riding type); Assistant Engineer; A-Frames and Winch Trucks; Concrete Auto Breaker; Hydrohammers (small); Brooms and Sweepers; Hoist (tuggers under 5 tons); Boats (Tug, Safety, Work Barges, Launch); Shouldering Machine Operator; Prestress Machines; Screed Operator; Stone Crushers and Screening Plants; Screed Operators (milling machine), Farm or Industrial Tractor Mounted Equipment; Post Hole Digger; Fireman (asphalt plants); Air Compressors over 400 CFM; Generators, over 150 KW; Augers (vertical and horizontal); Air, Electric, Hydraulic Jacks (slipform); Skid Steer Loaders (with or without attachments); Boiler Operators (temporary heat); Refrigeration Plant/Freeze Machines; Power Pack Vibratory/Ultra Sound Drivers and Extractors; Welding Machines; Heaters (mechanical); Pumps; Winches (small electric); Oiler and Greaser; Rotary Drill Tender; Conveyor; Forklifts/Telehandler 8000 lbs & under; Elevators: Automatic Hoists; Pumps (well points);

ENGI0139-003 06/05/2023

REMAINING COUNTIES

1/2/24, 7:45 AM

	Rates	Fringes
Power Equipment Operator		
Group 1	.\$ 47.53	25.89
Group 2	.\$ 46.28	25.89
Group 3	.\$ 43.23	25.89
Group 4	.\$ 42.70	25.89
Group 5	.\$ 40.63	25.89
Group 6	.\$ 39.10	25.89

HAZARDOUS WASTE PREMIUMS:

EPA Level ""A"" Protection: \$3.00 per hour EPA Level ""B"" Protection: \$2.00 per hour EPA Level ""C"" Protection: \$1.00 per hour

POWER EQUIPMENT OPERATORS CLASSIFICATIONS

GROUP 1: Cranes, Tower Cranes and Derricks with or without attachments with a lifting capacity of over 100 tons; Cranes, Tower Cranes, and Derricks with boom, leads and/or jib lengths 176 ft or longer.

GROUP 2: Backhoes (Excavators) weighing 130,00 lbs and over; Cranes, Tower Cranes and Derricks with or without attachments with a lifting capacity of 100 tons or less; Cranes, Tower Cranes, and Derricks with boom, leads, and/or jib lengths 175 ft or less; Caisson Rigs; Pile Driver

GROUP 3: Backhoes (Excavators) weighing under 130,000 lbs; Travelling Crane (bridge type); Milling Machine; Concrete Paver over 27 E; Concrete Spreader and Distributor; Concrete Laser Screed; Concrete Grinder and Planing Machine; Slipform Curb and Gutter Machine; Boring Machine (Directional); Dredge Operator; Skid Rigs; over 46 meter Concrete Pump.

GROUP 4: Hydraulic Backhoe (tractor or truck mounted); Hydraulic Crane, 10 tons or less; Tractor, Bulldozer, or End Loader (over 40 hp); Motor Patrol; Scraper Operator; Bituminous Plant and Paver Operator; Screed-Milling Machine; Roller over 5 tons; Concrete pumps 46 meter and under; Grout Pumps; Rotec type machine; Hydro Blaster, 10,000 psi and over; Rotary Drill Operator; Percussion Drilling Machine; Air Track Drill with or without integral hammer; Blaster; Boring Machine (vertical or horizontal); Side Boom; Trencher, wheel type or chain type having 8 inch or larger bucket; Rail Leveling Machine (Railroad); Tie Placer; Tie Extractor; Tie Tamper; Stone Leveler; Straddle Carrier; Material Hoists; Stack Hoist; Man Hoists; Mechanic and Welder; Off Road Material Haulers.

GROUP 5: Tractor, Bulldozer, or Endloader (under 40 hp); Tampers -Compactors, riding type; Stump Chipper, large; Roller, Rubber Tire; Backfiller; Trencher, chain type (bucket under 8 inch); Concrete Auto Breaker, large; Concrete Finishing Machine (road type); Concrete Batch Hopper; Concrete Conveyor Systems; Concrete Mixers, 14S or over; Pumps, Screw Type and Gypsum); Hydrohammers, small;

Brooms and Sweeeprs; Lift Slab Machine; Roller under 5 tons; Industrial Locomotives; Fireman (Pile Drivers and Derricks); Pumps (well points); Hoists, automatic; A-Frames and Winch Trucks; Hoists (tuggers); Boats (Tug, Safety, Work Barges and Launches); Assistant Engineer

GROUP 6: Shouldering Machine Operator; Farm or Industrial Tractor mounted equipment; Post Hole Digger; Auger (vertical and horizontal); Skid Steer Loader with or without attachments; Robotic Tool Carrier with or without attachments; Power Pack Vibratory/Ultra Sound Driver and Extractor; Fireman (Asphalt Plants); Screed Operator; Stone Crushers and Screening Plants; Air, Electric, Hydraulic Jacks (Slip Form); Prestress Machines; Air Compressor, 400 CFM or over; Refrigeration Plant/Freese Machine; Boiler Operators (temporary heat); Forklifts; Welding Machines; Generators; Pumps over 3""; Heaters, Mechanical; Combination small equipment operator; Winches, small electric; Oiler; Greaser; Rotary Drill Tender; Conveyor; Elevator Operator

.----

IRON0008-002 06/01/2023

BROWN, CALUMET, DOOR, FOND DU LAC, KEWAUNEE, MANITOWOC, MARINETTE, OCONTO, OUTAGAMI, SHAWANO, SHEBOYGAN, AND WINNEBAGO COUNTIES:

Rates Fringes

IRONWORKER.....\$ 43.40 30.67

Paid Holidays: New Year's Day, Memorial Day, July 4th, Labor Day, Thanksgiving Day & Christmas Day.

IRON0008-003 06/01/2023

KENOSHA, MILWAUKEE, OZAUKEE, RACINE, WALWORTH (N.E. 2/3), WASHINGTON, AND WAUKESHA COUNTIES

Rates Fringes

IRONWORKER.....\$ 41.73 30.67

Paid Holidays: New Year's Day, Memorial Day, July 4th, Labor Day, Thanksgiving Day & Christmas Day.

IRON0383-001 06/01/2023

ADAMS, COLUMBIA, CRAWFORD, DANE, DODGE, FLORENCE, FOREST, GRANT, GREENE, (Excluding S.E. tip), GREEN LAKE, IOWA, JEFFERSON, JUNEAU, LA CROSSE, LAFAYETTE, LANGLADE, MARATHON, MARQUETTE, MENOMINEE, MONROE, PORTAGE, RICHLAND, ROCK (Northern area, vicinity of Edgerton and Milton), SAUK, VERNON, WAUPACA, WAUSHARA, AND WOOD COUNTIES

Rates Fringes

IRONWORKER.....\$ 41.00 30.13

IRON0512-008 04/30/2023

BARRON, BUFFALO, CHIPPEWA, CLARK, DUNN, EAU CLAIRE, JACKSON, PEPIN, PIERCE, POLK, RUSK, ST CROIX, TAYLOR, AND TREMPEALEAU COUNTIES

	Rates	Fringes	
IRONWORKER	\$ 43.00	34.11	
IRON0512-021 04/30/2023			

ASHLAND, BAYFIELD, BURNETT, DOUGLAS, IRON, LINCOLN, ONEIDA, PRICE, SAWYER, VILAS AND WASHBURN COUNTIES

	Rates	Fringes	
IRONWORKER	\$ 39.14	34.00	
			-

LAB00113-002 06/01/2023

MILWAUKEE AND WAUKESHA COUNTIES

	Rates	Fringes
LABORER		
Group 1	\$ 33.56	23.86
Group 2	\$ 33.71	23.86
Group 3	\$ 33.91	23.86
Group 4	\$ 34.06	23.86
Group 5	\$ 34.21	23.86
Group 6	\$ 30.05	23.86

LABORERS CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster and Powderman

GROUP 6: Flagperson; traffic control person

LAB00113-003 06/01/2023

OZAUKEE AND WASHINGTON COUNTIES

Rates Fringes

LABORER

Group	1\$	32.81	23.86
-	2\$		23.86
•	3\$		23.86
•	4\$		23.86
	5\$		23.86
•	6\$		23.86

LABORERS CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated);

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster; powderman

GROUP 6: Flagperson and Traffic Control Person

LAB00113-011 06/01/2023

KENOSHA AND RACINE COUNTIES

	F	Rates	Fringes
			Ü
LABORER			
Group	1\$	32.62	23.86
Group	2\$	32.77	23.86
Group	3\$	32.97	23.86
Group	4\$	32.94	23.86
Group	5\$	33.27	23.86
Group	6\$	29.76	23.86

LABORERS CLASSIFICATIONS:

GROUP 1: General laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster and Powderman

GROUP 6: Flagman; traffic control person

LAB00140-002 06/01/2023

ADAMS, ASHLAND, BARRON, BAYFIELD, BROWN, BUFFALO, BURNETT, CALUMET, CHIPPEWA, CLARK, COLUMBIA, CRAWFORD, DODGE, DOOR, DOUGLAS, DUNN, EAU CLAIRE, FLORENCE, FOND DU LAC, FOREST, GRANT, GREEN, GREEN LAKE, IRON, JACKSON, JUNEAU, IOWA, JEFFERSON, KEWAUNEE, LA CROSSE, LAFAYETTE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, MONROE, OCONTO, ONEIDA, OUTAGAMIE, PEPIN, PIERCE, POLK, PORTAGE, PRICE, RICHLAND, ROCK, RUSK, SAUK, SAWYER, SHAWANO, SHEBOYGAN, ST. CROIX, TAYLOR, TREMPEALEAU, VERNON, VILLAS, WALWORTH, WASHBURN, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

	Ra	tes Fr	inges
LABORER			
Group	1\$ 3	7.57	19.25
Group	2\$ 3	7.67	19.25
Group	3\$ 3	7.72	19.25
Group	4\$ 3	7.92	19.25
Group	5\$ 3	7.77	19.25
Group	6\$ 3	4.20	19.25

LABORER CLASSIFICATIONS

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bitminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminous Worker (Dumper, Ironer, Smoother and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator, Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk and Pavement); Strike Off Man

GROUP 4: Line and Grade Secialist

GROUP 5: Blaster; powderman

GROUP 6: Flagperson; Traffic Control

LAB00464-003 06/01/2023

DANE COUNTY

		Rates	Fringes
LABORER			
Group	1	.\$ 37.85	19.25
Group	2	.\$ 37.95	19.25
Group	3	.\$ 38.00	19.25

Group 4\$	38.20	19.25
Group 5\$	38.05	19.25
Group 6\$	34.20	19.25

LABORERS CLASSIFICATIONS:

GROUP 1: General Laborer; Tree Trimmer; Conduit Layer; Demolition and Wrecking Laborer; Guard Rail, Fence, and Bridge Builder; Landscaper; Multiplate Culvert Assembler; Stone Handler; Bituminous Worker (Shoveler, Loader, and Utility Man); Batch Truck Dumper or Cement Handler; Bituminious Worker (Dumper, Ironer, Smoother, and Tamper); Concrete Handler

GROUP 2: Air Tool Operator; Joint Sawer and Filler (Pavement); Vibrator or Tamper Operator (Mechanical Hand Operated); Chain Saw Operator; Demolition Burning Torch Laborer

GROUP 3: Bituminous Worker (Raker and Luteman); Formsetter (Curb, Sidewalk, and Pavement); Strike Off Man

GROUP 4: Line and Grade Specialist

GROUP 5: Blaster; Powderman

GROUP 6: Flagperson and Traffic Control Person

PAIN0106-008 05/01/2023

ASHLAND, BAYFIELD, BURNETT, AND DOUGLAS COUNTIES

Rates Fringes

Painters:

New:

Brush, Roller............\$ 34.59 24.84

Spray, Sandblast, Steel....\$ 35.19 24.84

Repaint:

Brush, Roller............\$ 33.09 24.84

Spray, Sandblast, Steel....\$ 33.69 24.84

PAIN0108-002 06/01/2023

RACINE COUNTY

	Rates	Fringes	
Painters:			
Brush, Roller	\$ 41.04	21.95	
Spray & Sandblast	\$ 42.04	21.95	

PAIN0259-002 05/01/2008

BARRON, CHIPPEWA, DUNN, EAU CLAIRE, PEPIN, PIERCE, POLK, RUSK, SAWYER, ST. CROIX, AND WASHBURN COUNTIES

	Rates	Fringes	
PAINTER	\$ 24.11	12.15	
PAIN0259-004 05/01/2015			_

BUFFALO, CRAWFORD, JACKSON, LA CROSSE, MONROE, TREMPEALEAU, AND VERNON COUNTIES

	Rates	Fringes
PAINTER	.\$ 22.03	12.45
PAIN0781-002 06/01/2023		

JEFFERSON, MILWAUKEE, OZAUKEE, WASHINGTON, AND WAUKESHA COUNTIES

r	races	Fringes
Painters:		
Bridge\$	39.84	24.86
Brush\$	39.09	24.86
Spray & Sandblast\$	39.84	24.86

PAIN0802-002 06/01/2023

COLUMBIA, DANE, DODGE, GRANT, GREEN, IOWA, LAFAYETTE, RICHLAND, ROCK, AND SAUK COUNTIES

	Rates	Fringes
PAINTER Brush	35.00	20.62
PREMIUM PAY: Structural Steel, Spray, Bridges hour.	s = \$1.00 add:	itional per

PAIN0802-003 06/01/2023

ADAMS, BROWN, CALUMET, CLARK, DOOR, FOND DU LAC, FOREST, GREEN LAKE, IRON, JUNEAU, KEWAUNEE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, OCONTO, ONEIDA, OUTAGAMIE, PORTAGE, PRICE, SHAWANO, SHEBOYGAN, TAYLOR, VILAS, WAUSHARA, WAUPACA, WINNEBAGO, AND WOOD COUNTIES

	Rates	Fringes
PAINTER	.\$ 35.00	20.62
PAIN0934-001 06/01/2022		

KENOSHA AND WALWORTH COUNTIES

	Rates	Fringes
Painters:		
Brush	\$ 36.70	24.69
Spray	\$ 37.70	24.69
Structural Steel	\$ 36.85	24.69

PAIN1011-002 06/06/2021

FLORENCE COUNTY

Rates Fringes

Painters:.....\$ 26.71 14.38

PLAS0599-002 06/01/2023

AREA DESCRIPTIONS

AREA A: ASHLAND, BURNETT, BAYFIELD, DOUGLAS, IRON, PRICE, SAWYER, AND WASHBURN COUNTIES

AREA B: ADAMS, BARRON, BROWN, CALUMET, CHIPPEWA, CLARK, COLUMBIA, DODGE, DOOR, DUNN, FLORENCE, FOND DU LAC, FOREST, GREEN LAKE, JEFFERSON, KEWAUNEE, LANGLADE, LINCOLN, MANITOWOC, MARATHON, MARINETTE, MARQUETTE, MENOMINEE, OCONTO, ONEIDA, OUTAGAMIE, POLK, PORTAGE, RUSK, ST. CROIX, SAUK, SHAWANO, SHEBOYGAN, TAYLOR, VILAS, WALWORTH, WAUPACA, WAUSHARA, WINNEBAGO, AND WOOD COUNTIES

AREA C: BUFFALO, CRAWFORD, EAU CLAIRE, JACKSON, JUNEAU, LA CROSSE, MONROE, PEPIN, PIERCE, RICHLAND, TREMPEALEAU, AND VERNON COUNTIES

AREA D: MILWAUKEE, OZAUKEE, WASHINGTON, AND WAUKESHA COUNTIES

AREA E: DANE, GRANT, GREEN, IOWA, LAFAYETTE, AND ROCK COUNTIES

AREA F: KENOSHA AND RACINE COUNTIES

PLUM0011-003 05/01/2023

ASHLAND, BAYFIELD, BURNETT, DOUGLAS, IRON, SAWYER, AND WASHBURN COUNTIES

PLUM0075-002 06/01/2016

MILWAUKEE, OZAUKEE, WASHINGTON, AND WAUKESHA COUNTIES

PLUM0075-004 06/01/2016

DODGE (Watertown), GREEN, JEFFERSON, LAFAYETTE, AND ROCK COUNTIES

Rates Fringes
PLUMBER...... \$ 40.52 21.47

PLUM0075-009 06/01/2016

COLUMBIA, DANE, IOWA, MARQUETTE, RICHLAND AND SAUK COUNTIES

Rates

PLUMBER.....\$ 38.82

20.12

Fringes

PLUM0111-007 05/28/2018

MARINETTE COUNTY (Niagara only)

Rates

Fringes

PLUMBER/PIPEFITTER.....\$ 33.33

24.48

PLUM0118-002 06/01/2023

KENOSHA, RACINE, AND WALWORTH COUNTIES

Rates

Fringes

Plumber and Steamfitter..... \$ 50.50

25.47

PLUM0400-003 05/29/2023

ADAMS, BROWN, CALUMET, DODGE (except Watertown), DOOR, FOND DU LAC, GREEN LAKE, KEWAUNEE, MANITOWOC, MARINETTE (except Niagara), MENOMINEE, OCONTO, OUTAGAMIE, SHAWANO, SHEBOYGAN, WAUPACA, WAUSHARA, AND WINNEBAGO COUNTIES

Rates

Fringes

PLUMBER/PIPEFITTER.....\$ 49.85

PLUM0434-002 05/28/2023

BARON, BUFFALO, CHIPPEWA, CLARK, CRAWFORD, DUNN, EAU CLAIRE, FLORENCE, FOREST, GRANT, JACKSON, JUNEAU, LA CROSSE, LANGLADE, LINCOLN, MARATHON, MONROE, ONEIDA, PEPIN, PIERCE, POLK, PORTAGE, PRICE, RUSK, ST. CROIX, TAYLOR, TREMPEALEAU, VERNON, VILAS, AND WOOD COUNTIES

Rates

Fringes

PIPEFITTER.....\$ 46.89

PLUM0601-003 06/01/2022

DODGE (Watertown), GREEN, JEFFERSON, LAFAYETTE, MILWAUKEE, OZAUKEE, ROCK, WASHINGTON AND WAUKESHA COUNTIES

Rates

Fringes

PIPEFITTER....\$ 50.00

28.93

PLUM0601-009 06/01/2022

COLUMBIA, DANE, IOWA, MARQUETTE, RICHLAND AND SAUK COUNTIES

Rates

Fringes

PIPEFITTER..... \$ 52.06 TEAM0039-002 06/01/2023

	Rates	Fringes	
TRUCK DRIVER 1 & 2 Axle Trucks	\$ 35.57	26.09	
3 or more axles; Euclids or Dumptor, Articulated	33.37	20.03	
Truck, Mechanic	\$ 35.72	26.09	

SUWI2011-001 11/16/2011

	Rates	Fringes
WELL DRILLER	\$ 16.52	

WELDERS - Receive rate prescribed for craft performing operation to which welding is incidental.

Note: Executive Order (EO) 13706, Establishing Paid Sick Leave for Federal Contractors applies to all contracts subject to the Davis-Bacon Act for which the contract is awarded (and any solicitation was issued) on or after January 1, 2017. If this contract is covered by the EO, the contractor must provide employees with 1 hour of paid sick leave for every 30 hours they work, up to 56 hours of paid sick leave each year. Employees must be permitted to use paid sick leave for their own illness, injury or other health-related needs, including preventive care; to assist a family member (or person who is like family to the employee) who is ill, injured, or has other health-related needs, including preventive care; or for reasons resulting from, or to assist a family member (or person who is like family to the employee) who is a victim of, domestic violence, sexual assault, or stalking. Additional information on contractor requirements and worker protections under the EO is available at

https://www.dol.gov/agencies/whd/government-contracts.

Unlisted classifications needed for work not included within the scope of the classifications listed may be added after award only as provided in the labor standards contract clauses (29CFR 5.5 (a) (1) (ii)).

The body of each wage determination lists the classification and wage rates that have been found to be prevailing for the cited type(s) of construction in the area covered by the wage determination. The classifications are listed in alphabetical order of ""identifiers"" that indicate whether the particular rate is a union rate (current union negotiated rate for local), a survey rate (weighted average rate) or a union average rate (weighted union average rate).

Union Rate Identifiers

A four letter classification abbreviation identifier enclosed

in dotted lines beginning with characters other than ""SU"" or ""UAVG"" denotes that the union classification and rate were prevailing for that classification in the survey. Example: PLUM0198-005 07/01/2014. PLUM is an abbreviation identifier of the union which prevailed in the survey for this classification, which in this example would be Plumbers. 0198 indicates the local union number or district council number where applicable, i.e., Plumbers Local 0198. The next number, 005 in the example, is an internal number used in processing the wage determination. 07/01/2014 is the effective date of the most current negotiated rate, which in this example is July 1, 2014.

Union prevailing wage rates are updated to reflect all rate changes in the collective bargaining agreement (CBA) governing this classification and rate.

Survey Rate Identifiers

Classifications listed under the ""SU"" identifier indicate that no one rate prevailed for this classification in the survey and the published rate is derived by computing a weighted average rate based on all the rates reported in the survey for that classification. As this weighted average rate includes all rates reported in the survey, it may include both union and non-union rates. Example: SULA2012-007 5/13/2014. SU indicates the rates are survey rates based on a weighted average calculation of rates and are not majority rates. LA indicates the State of Louisiana. 2012 is the year of survey on which these classifications and rates are based. The next number, 007 in the example, is an internal number used in producing the wage determination. 5/13/2014 indicates the survey completion date for the classifications and rates under that identifier.

Survey wage rates are not updated and remain in effect until a new survey is conducted.

Union Average Rate Identifiers

Classification(s) listed under the UAVG identifier indicate that no single majority rate prevailed for those classifications; however, 100% of the data reported for the classifications was union data. EXAMPLE: UAVG-OH-0010 08/29/2014. UAVG indicates that the rate is a weighted union average rate. OH indicates the state. The next number, 0010 in the example, is an internal number used in producing the wage determination. 08/29/2014 indicates the survey completion date for the classifications and rates under that identifier.

A UAVG rate will be updated once a year, usually in January of each year, to reflect a weighted average of the current negotiated/CBA rate of the union locals from which the rate is based.

WAGE DETERMINATION APPEALS PROCESS

- 1.) Has there been an initial decision in the matter? This can be:
- * an existing published wage determination
- * a survey underlying a wage determination

* a Wage and Hour Division letter setting forth a position on a wage determination matter

* a conformance (additional classification and rate) ruling

On survey related matters, initial contact, including requests for summaries of surveys, should be with the Wage and Hour National Office because National Office has responsibility for the Davis-Bacon survey program. If the response from this initial contact is not satisfactory, then the process described in 2.) and 3.) should be followed.

With regard to any other matter not yet ripe for the formal process described here, initial contact should be with the Branch of Construction Wage Determinations. Write to:

Branch of Construction Wage Determinations Wage and Hour Division U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

2.) If the answer to the question in 1.) is yes, then an interested party (those affected by the action) can request review and reconsideration from the Wage and Hour Administrator (See 29 CFR Part 1.8 and 29 CFR Part 7). Write to:

Wage and Hour Administrator U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

The request should be accompanied by a full statement of the interested party's position and by any information (wage payment data, project description, area practice material, etc.) that the requestor considers relevant to the issue.

3.) If the decision of the Administrator is not favorable, an interested party may appeal directly to the Administrative Review Board (formerly the Wage Appeals Board). Write to:

Administrative Review Board U.S. Department of Labor 200 Constitution Avenue, N.W. Washington, DC 20210

4.) All decisions by the Administrative Review Board are final.

END OF GENERAL DECISION



Wisconsin Department of Transportation

January 3, 2024

Division of Transportation Systems Development

Bureau of Project Development 4822 Madison Yards Way, 4th Floor South Madison, WI 53705

Telephone: (608) 266-1631 Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #12: 2310-13-70, WISC 2024117

Main St, Village Jackson

CTH P to Eagle Dr

STH 60

Washington County

2310-13-71, WISC 2024118

V Jackson, Eagle Dr Intersection with STH 60

Local Street

Washington County

Letting of January 9, 2024

This is Addendum No. 01, which provides for the following:

Schedule of Items:

	Revised Bid Item	Quantitie	S						
			Proposal	Proposal	Proposal				
Bid Item	Itom Description	Unit	Total Prior	Quantity	Total After				
Did itelli	Item Description	Offic	to	Change (-)	Addendum				
			Addendum						
611.3230	Inlets 2x3-FT	Each	10	-1	9				

Plan Sheets:

	Revised Plan Sheets 2310-13-71
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
64	Miscellaneous Quantities (Quantity correction to the Storm Sewer Structures table)

	Added Plan Sheets 2310-13-71
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
12A	Soil Boring Logs (added information)
12B	Soil Boring Logs (added information)
12C	Soil Boring Logs (added information)
12D	Soil Boring Logs (added information)
12E	Soil Boring Logs (added information)

Schedule of Items

Attached, dated January 3, 2024, are the revised Schedule of Items Page 5.

Plan Sheets

The following $8\frac{1}{2}$ x 11-inch sheets are attached and made part of the plans for this proposal:

2310-13-71 Revised: 64. Added: 12A – 12E

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,


Mike Coleman

Proposal Development Specialist Proposal Management Section

END OF ADDENDUM



Addendum No. 01 ID 2310-13-71 Added Sheet 12B January 3, 2024



SHEET


SOIL BORING LOGS

COUNTY: WASHINGTON


HWY: EAGLE DRIVE

2310-13-71

PROJECT NO:



Addendum No. 01 ID 2310-13-71 Added Sheet 12C January 3, 2024



SHEET


SOIL BORING LOGS


COUNTY: WASHINGTON

HWY: EAGLE DRIVE

2310-13-71

PROJECT NO:





Laboratory Classification Criteria

UNIFIED SOIL CLASSIFICATION SYSTEM (ASTM D-2487)

Typical Names

Group

Major Divisions

Well-graded gravels, gravel-tures, little or no fines

βW

GP

More than half of course fraction is alreger than Mo. 4 slevee size)
Gravels with fines
Gravels with fines
Appreciable amount
(Little or no fines)
(Sines)

Above "A" line with P.I> between 4 and 7 are orderline cases requi

Atterberg limits below "A" ine or P.I. less than 4

use of dual symbols

Atterberg limits below "A' e with P.I. greater than

Not meeting all gradation requirements for GW

between 1 and 3

Himalayan Consultants, LLC Engineers and Hydrogeologists

Symbols and Terminology	
Symbols	
Drilling and Sampling Field and	Field and Laboratory Tests
HAS = Holiow Stem Auger	tons/sq. ft.
Terminology	
Grain Size Relati	Relative Proportion
Size Range Proportional Term	% by Weight
>12" Trace	0% - 5%
3"-12" Little	5% - 12%
Some	12% - 35%
3/4" – 3"	35% - 50%
#4 Sieve 3/4"	Plasticity
Term	Plasticity Index
#4 - #10 Sieve None to Slight	0-4
#10 - #40 Sieve Slight	5-7
#40 - #200 Sieve Medium	8 - 22
100% passing #200 Sieve & > 0.005 mm Medium to Very High	Over 22
100 % passing #200 Sieve & < 0.005 mm	
Relative Density C	Consistency
"N" Value	qest – tons/sq.ft.
0-4 Very Soft	0.00 - 0.25
4-10 Soft	0.25 - 0.50
10-30 Medium	0.50 - 1.00
30-50 Stiff	1.00 - 2.00
Over 50 Very Stiff	2.00 - 4.00
Hard	Over 4.00

zone with P.I. between 4 and 7 are borderline cases requiring use of dual

Atterberg limits above "A" line with P.I. greater than

ne or P.I. less than 4

meeting all gradation requirements for SW

 $\frac{(D_{30})^2}{D_n \times D_{20}}$ between 1 and 3

Determine percentages of sand and gravel from grain size curve
Depending to no percentage of tines (fraction smaller than No. 200 sieve size), course
soils are classified as follows:
GW, GP, SW, SP
Less than S percent
More than Ts percent
STO 37 Dercent

Well-graded sands, gravelly sands, little

SW

(Little or no fines)

gc

Course grained soils Annua Mo. 200 sleve size) (More than half of material is larger than No. 200 sleve size) ands (Gravelic Translet Are Translet A

no fines

SP

(More than half of course fraction is smaller than No. 4 sieve size)
Sands with fines
Sands with fines

Addendum No. 01 ID 2310-13-71 Added Sheet 12E January 3, 2024

a Division of GM and SM groups into subdivisions of d and u are for roads and arriedds only. Subdivision is based on Atterberg limits, suffix d used when LL is greater than 28 by the companies of so riess, the suffix u used when LL is greater than 28 by a Modelline classifications: used of rosile possessing characteristics of two groups; are designated by combinations of group symbols. For example: GW-GC, well-graded gravel-sand mixture with clay pinder

ರ

eous fine sandy or silty soils, elastic silts organic clays of high plasticity, fat clays

organic silts, micaceous or diatoma

Ξ

Fine grained soils

ᆼ Н Ħ

Silts and clays

Organic clays of medium to high plasticity

Peat and other highly organic soils

Highly organic soils

(%) XBUICITY INDEX (%)

plasticity, gravelly clays, sandy clays, silty Organic silts and organic silty clays of low

J Ы

Silts and clays

lays, lean clays

norganic clays of low to medium

inorganic silts and very fine sands, rock flour, silty or clayey fine sands or clayey silts with slight plasticity

₫

Clayey sands, sand-clay mixtures

SC

	HWY: EAGLE DRIVE	COUNTY: WASHINGTON	TON	SOIL BORING LOG
AR CORPORATION\DOCUMENTS-SE	RPORATION\DOCUMENTS-SE-DESIGN\2310-13-01 EAGLE DRIVE ROUNDABOUT\11 C3D\23101301\SHEE	ETSPLAN\021002-SB.DWG	PLOT DATE: 12/28/2023 12:02 PM	32 PM PLOT BY:

2310-13-71

PROJECT NO:

				_											IE R) lev	231 /ise	IO- ed	-13 Sh	-7 1ee	o. (1 et 6	4		628.1520	SILTFENCE	LF		170 85	90	615		165	0	200	200	086	
~~	~~~	~~~	~~	~	~	~	~	~	~	~	~	~	~~	~	~	~	~	~	~~	~~	~	 ~~~	}	628,1504	LO WILL H	LF LF		170 85	90	615		165		200	200	086	
		INVERT*** DEPTH **** ELEVATION FT			841.02 4.14			839.60				840.44 4.09		842.22 2.05					842.17 2.58				H			LOCATION		55	RT	STAGE 2 TOTAL		LT STAGE 3 TOTAL			UNDISTRIBUTED TOTAL	TOTAL 1000	
		RIM		i	846.40	845.74	846.00	844 99	845.11	845.44	845.47	845.53	i	845.27	845.72	845.45			845.75				SILTEENCE			NC		RWB'	RNB'				7		IOND		
	* 633.5200	MARKERS CULVERT END EACH		1	i	1 1	1	П	ii	1	i	i i	П	1 1	ı	1 1	e		1 1	0	е					TO STATION		3' - 302+22 'RWB' ' - 403+93 'RSB'				' 401+10 'RNB		!			
	611.3230	INLETS 2X3-FT EACH		!	-		1	! !	!!	1	1	!!	I	-	1		+ ∞		-	п	6					STATION		300+90 'RWB' 402+70 'RSB'	403+06 'RNB'	201000		400+00 'RNE		-			
	611.3004	INLETS 4-FT DIAMETER EACH		1	I	1 1	1	1	Ι =	1	-	- н	1	₽	1	: :	10		1 -	1	9					CATEGORY	STAGE 2	1000	1000		STAGE 3	1000	o o b	1000 1000			
	611.2004	MANHOLES 4-FT DIAMETER EACH		1	п	1 1	-	I -	4	1	I		ı		-	1 1	2		1 1	0	2							REMARKS					EXISTING CP				
ν a		INLET COVERS TYPE T EACH		ı	i	i i	-	1 1	i i	П	-		i		ı	: :	e		1 1	0	8					628.7555	CULVERT PIPE CHECKS			20	20		3 2 EXI	2	75	3	
STORM SEWER STRUCTURES	611.0639	INLET COVERS TYPE H-S EACH		!	-		1	1 1	!!	1	1		1				10		-	d	11			CULVERT PIPE CHECKS		29	COL	LOCATION		LI	STAGE 1 TOTAL		RT RT	STAGE 3 TOTAL	1000 IATO		
STORIN	611.0636	INLET COVERS TYPE H M-S EACH		!	!	i i	!	1 1		1	1	1 1	i	!	ı	! ;	1		- 1	п	2			CULVERT				STATION LOC		'RWB'	STAGE		303+60 'REB' 399+90 'RNB'		TOT		
	611.0530	MANHOLE COVERS TYPE J EACH		!	П	!!	1	-	- I	1	Į.		!	!!	1	: :	2		1 1	0	2							CATEGORY ST.	STAGE 1	1000 30221			1000 303+ 1000 399+				
	522.1015 APRON ENDWALLS FOR CULVETT PIPE REINFORCED	CONCRETE 15- INCH EACH		1	I	1 1	-	1	1 1	1	1	: ;	1	1 1	1	: :	2		1 1	0	2		HEIGHT	7				RIM	ELEVATION	Ī	846.15	l I	10				-
	~	CONCRETE 12- INCH EACH		1	!	!!	1	! !	!!	1	1	!!	!	!!	1	: :	1		1 1	0	П		** STATIONS AND OFFSETS ARE TO CENTER OF STRUCTURE *** THE INVERTELEVATION IS THE ELEVATION OF THE LOWEST PIPE FLOW LINE *** DEPTH = RIMELEV - INVERTELEV - COVER HEIGHT - 6 INCHADJUSTMENT RING HEIGHT	***************************************			SPV.0060.22	SPECIAL (22. SADDLE INLET) RI	- 1		1 846	2	2				!
	ш	OFFSET ***		39.7'LT	20.8'LT	1.5 RI	1.5'LT	18.1'RT 7.6'RT	1.0'RT	1.5'RT	1.5'LT	1.7'LT	31.1'RT	1.5'RT	1.5'RT	1.5'RT	STAGE 2 TOTAL		1.0'RT	STAGE 3 TOTAL	TOTAL 1000		TRUCTURE)F THE LOWEST PI HEIGHT - 6 I NCH A	***************************************													
		STATION		301+82 'RWB'	301+82 'RWB'	22+33 NW 303+14 'RWB'	303+19 'REB'	10+15 'NE'	10+71 'NE'	305+38 'RWB'	305+35 'REB'	10+39 'RAB'	11+86 'NE'	12+22 'NE' 403+07 'RNB'	403+08 'RSB'	20+81 'NW'			30+75'SW' 41+67'SE'			NOTES: * ADDITIONAL QUANTITIES LISTED ELSEWHERE	**STATIONS AND OFFSETS ARE TO CENTER OF STRUCTURE *** THE INVERT ELEVATION IS THE ELEVATION OF THE LOWEST PIPE FLOW LINE *** DEPTH = RIM ELEV-INVERT ELEY - COVER HEIGHT - 6 INCH ADJUSTMENT RI	*	ITEMS		611.0651	INLET COVERS TYPE S	EACH		1	AL 2	2				
		STRUCTURE		2.0	2.1	2.3	2.4	1.0	1.2	1.3	1.4	1.7	4.0	4.1	4.3	4.4			2.5			. QUANTITIES L	AND OFFSETS A RTELEVATION II RIMELEV - INV	3	SADDLE INLET ITEMS				OFFSET **		15.3'LT 7.2'IT	STAGE 2 TOTAL	TOTAL 1000		HB.	5	
•••		CATEGORY	STAGE 2	1000	1000	1000	1000	1000	1000	1000	1000	1000	1000	1000	1000	1000		STAGE3	1000		•	NOTES: * ADDITIONAL (** STATIONS A. *** THE INVERT **** DEPTH = R	The same of the sa	S	•			STRUCTURE STATION		S-C.1 - 10+83 'RAB' S-C.2 - 10+84 'RAB'				NOTES: ** STATIONS AND DEESETS ARE TO CENTER DESTRUCTURE		







Page 5 of 17

Proposal ID: 20240109012 **Project(s):** 2310-13-70, 2310-13-71

Federal ID(s): WISC 2024117, WISC 2024118

SECTION: 0001 Roadway Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0116	602.0605 Curb Ramp Detectable Warning Field Radial Yellow	140.000 SF		
0118	602.0810 Concrete Driveway 6-Inch	93.000 SY		
0120	602.3010 Concrete Surface Drains	1.000 CY	·	<u></u> _
0122	606.0200 Riprap Medium	46.000 CY		
0124	608.0412 Storm Sewer Pipe Reinforced Concrete Class IV 12-Inch	424.000 LF		
0126	608.0415 Storm Sewer Pipe Reinforced Concrete Class IV 15-Inch	53.000 LF		<u> </u>
0128	611.0530 Manhole Covers Type J	2.000 EACH		
0130	611.0612 Inlet Covers Type C	1.000 EACH		
0132	611.0636 Inlet Covers Type HM-S	2.000 EACH		
0134	611.0639 Inlet Covers Type H-S	11.000 EACH		
0136	611.0651 Inlet Covers Type S	2.000 EACH		
0138	611.0652 Inlet Covers Type T	3.000 EACH		
0140	611.2004 Manholes 4-FT Diameter	3.000 EACH		
0142	611.3004 Inlets 4-FT Diameter	6.000 EACH		
0144	611.3230 Inlets 2x3-FT	9.000 EACH		·



Wisconsin Department of Transportation

January 4, 2024

Division of Transportation Systems Development

Bureau of Project Development 4822 Madison Yards Way, 4th Floor South Madison, WI 53705

Telephone: (608) 266-1631 Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #12: 2310-13-70, WISC 2024117

Main St, Village Jackson

CTH P to Eagle Dr

STH 60

Washington County

2310-13-71, WISC 2024118

V Jackson, Eagle Dr Intersection with STH 60

Local Street

Washington County

Letting of January 9, 2024

This is Addendum No.02, which provides for the following:

Schedule of Items:

	Deleted Bid Item Quantities						
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Proposal Quantity Change (-)	Proposal Total After Addendum		
643.3960	Temporary Marking Removable Mask Out Tape 6-Inch	LF	41,020	-41,020	0		

Plan Sheets:

	Revised Plan Sheets 2310-13-70				
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)				
198	Miscellaneous Quantities (remove pay item 643.3960)				

Schedule of Items

Attached, dated January 4, 2024, are the revised Schedule of Items Page 1 - 17.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

2310-13-70 Revised: 198.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman


Proposal Development Specialist Proposal Management Section

END OF ADDENDUM

-	_
•	•

643.0300
TRAFFIC TRAFFIC CONTROL CONTROL DRUMS BARRICADES TYPE DAYS **EACH** DAY
45 650 29,250 30 45 15 650 9,750 31
184 10,120
09
TOTAL 0010 49,200
TRAFFIC CONTROL.
643.5000 TRAFFIC CONTROL PROJECT EACH
2310-13-70 0.95
TOTAL 0010 0.95
PROJECT NO: 2310-13-70 HWY: STH 60
www.zozou_mq.pptx







Page 1 of 17


Proposal ID: 20240109012 **Project(s):** 2310-13-70, 2310-13-71

Federal ID(s): WISC 2024117, WISC 2024118

SECTION: 0001 Roadway Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	203.0100 Removing Small Pipe Culverts	3.000 EACH		
0004	203.0220 Removing Structure (structure) 01. R-66-87	1.000 EACH	·	·
0006	204.0110 Removing Asphaltic Surface	989.000 SY		
8000	204.0115 Removing Asphaltic Surface Butt Joints	1,588.000 SY		
0010	204.0120 Removing Asphaltic Surface Milling	42,858.000 SY	·	
0012	204.0150 Removing Curb & Gutter	1,989.000 LF		
0014	204.0155 Removing Concrete Sidewalk	1,318.000 SY	·	
0016	204.0190 Removing Surface Drains	1.000 EACH	·	·
0018	204.0195 Removing Concrete Bases	36.000 EACH		
0020	204.0220 Removing Inlets	2.000 EACH		
0022	204.0245 Removing Storm Sewer (size) 01. 12-inch	113.000 LF	·	·
0024	204.9060.S Removing (item description) 01. Traffic Signals STH 60 & CTH P	1.000 EACH		·
0026	204.9060.S Removing (item description) 02. Traffic Signals STH 60 & Industrial Dr	1.000 EACH		
0028	204.9060.S Removing (item description) 03. Traffic Signals STH 60 & Jackson Dr	1.000 EACH		·







Page 2 of 17

Proposal ID: 20240109012 **Project(s):** 2310-13-70, 2310-13-71

Federal ID(s): WISC 2024117, WISC 2024118

SECTION: 0001 Roadway Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0030	204.9060.S Removing (item description) 04. Loop Detector Wire & Lead In Cable STH 60 & CTH P	1.000 EACH	·	·
0032	204.9060.S Removing (item description) 05. Loop Detector Wire & Lead In Cable STH 60 & Industrial Dr	1.000 EACH		·
0034	204.9060.S Removing (item description) 06. Loop Detector Wire & Lead In Cable STH 60 & Jackson Dr	1.000 EACH	·	·
0036	205.0100 Excavation Common	7,015.000 CY		
0038	205.0501.S Excavation, Hauling, and Disposal of Petroleum Contaminated Soil	432.000 TON	·	·
0040	211.0101 Prepare Foundation for Asphaltic Paving (project) 01. 2310-13-70	1.000 EACH	·	·
0042	211.0101 Prepare Foundation for Asphaltic Paving (project) 02. 2310-13-71	1.000 EACH	·	
0044	211.0400 Prepare Foundation for Asphaltic Shoulders	4.000 STA	·	
0046	213.0100 Finishing Roadway (project) 01. 2310-13-70	1.000 EACH	<u></u>	
0048	213.0100 Finishing Roadway (project) 02. 2310-13-71	1.000 EACH	·	
0050	305.0110 Base Aggregate Dense 3/4-Inch	270.000 TON		
0052	305.0120 Base Aggregate Dense 1 1/4-Inch	5,250.000 TON		
0054	310.0110 Base Aggregate Open-Graded	52.000 TON		







Page 3 of 17


Proposal ID: 20240109012 **Project(s):** 2310-13-70, 2310-13-71

Federal ID(s): WISC 2024117, WISC 2024118

SECTION: 0001 Roadway Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0056	312.0110 Select Crushed Material	5,425.000 TON		
0058	390.0405 Base Patching Concrete SHES	23.000 CY		
0060	405.0100 Coloring Concrete WisDOT Red	140.000 CY		
0062	415.2010 Concrete Truck Apron 12-inch	342.000 SY	·	
0064	455.0605 Tack Coat	6,518.000 GAL		
0066	460.2000 Incentive Density HMA Pavement	6,790.000 DOL	1.00000	6,790.00
0068	460.6223 HMA Pavement 3 MT 58-28 S	622.000 TON		
0070	460.6224 HMA Pavement 4 MT 58-28 S	9,241.000 TON		
0072	460.6424 HMA Pavement 4 MT 58-28 H	727.000 TON		
0074	465.0105 Asphaltic Surface	10.000 TON		
0076	465.0110 Asphaltic Surface Patching	35.000 TON		
0078	465.0315 Asphaltic Flumes	9.000 SY		·
0800	504.0900 Concrete Masonry Endwalls	4.000 CY		
0082	513.8011 Railing Steel Pedestrian Type C2	31.000 LF	·	
0084	520.8000 Concrete Collars for Pipe	4.000 EACH		
0086	522.0421 Culvert Pipe Reinforced Concrete Class IV 21-Inch	202.000 LF	<u>.</u>	·







Page 4 of 17


Proposal ID: 20240109012 **Project(s):** 2310-13-70, 2310-13-71

Federal ID(s): WISC 2024117, WISC 2024118

SECTION: 0001 Roadway Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0088	522.0448 Culvert Pipe Reinforced Concrete Class IV 48-Inch	436.000 LF		·
0090	522.1012 Apron Endwalls for Culvert Pipe Reinforced Concrete 12-Inch	1.000 EACH		·
0092	522.1015 Apron Endwalls for Culvert Pipe Reinforced Concrete 15-Inch	2.000 EACH		
0094	522.1021 Apron Endwalls for Culvert Pipe Reinforced Concrete 21-Inch	2.000 EACH		
0096	522.1048 Apron Endwalls for Culvert Pipe Reinforced Concrete 48-Inch	2.000 EACH		
0098	601.0405 Concrete Curb & Gutter 18-Inch Type A	185.000 LF		
0100	601.0411 Concrete Curb & Gutter 30-Inch Type D	3,213.000 LF		
0102	601.0551 Concrete Curb & Gutter 4-Inch Sloped 36-Inch Type A	242.000 LF		
0104	601.0557 Concrete Curb & Gutter 6-Inch Sloped 36-Inch Type D	50.000 LF		·
0106	601.0580 Concrete Curb & Gutter 4-Inch Sloped 36-Inch Type R	273.000 LF		
0108	601.0600 Concrete Curb Pedestrian	167.000 LF		
0110	602.0405 Concrete Sidewalk 4-Inch	2,949.000 SF		
0112	602.0410 Concrete Sidewalk 5-Inch	20,082.000 SF		
0114	602.0505 Curb Ramp Detectable Warning Field Yellow	562.000 SF		







Page 5 of 17


Proposal ID: 20240109012 **Project(s):** 2310-13-70, 2310-13-71

Federal ID(s): WISC 2024117, WISC 2024118

SECTION: 0001 Roadway Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0116	602.0605 Curb Ramp Detectable Warning Field Radial Yellow	140.000 SF		
0118	602.0810 Concrete Driveway 6-Inch	93.000 SY		
0120	602.3010 Concrete Surface Drains	1.000 CY	·	<u></u> _
0122	606.0200 Riprap Medium	46.000 CY		
0124	608.0412 Storm Sewer Pipe Reinforced Concrete Class IV 12-Inch	424.000 LF		
0126	608.0415 Storm Sewer Pipe Reinforced Concrete Class IV 15-Inch	53.000 LF		<u> </u>
0128	611.0530 Manhole Covers Type J	2.000 EACH		
0130	611.0612 Inlet Covers Type C	1.000 EACH		
0132	611.0636 Inlet Covers Type HM-S	2.000 EACH		
0134	611.0639 Inlet Covers Type H-S	11.000 EACH		
0136	611.0651 Inlet Covers Type S	2.000 EACH		
0138	611.0652 Inlet Covers Type T	3.000 EACH		
0140	611.2004 Manholes 4-FT Diameter	3.000 EACH		
0142	611.3004 Inlets 4-FT Diameter	6.000 EACH		
0144	611.3230 Inlets 2x3-FT	9.000 EACH		·







Page 6 of 17


Proposal ID: 20240109012 **Project(s):** 2310-13-70, 2310-13-71

Federal ID(s): WISC 2024117, WISC 2024118

SECTION: 0001 Roadway Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0146	611.8110 Adjusting Manhole Covers	27.000 EACH		
0148	611.8115 Adjusting Inlet Covers	1.000 EACH		
0150	611.8120.S Cover Plates Temporary	27.000 EACH		
0152	611.9850.S Pipe Grates (size) 01. 48-Inch	2.000 EACH	·	
0154	612.0106 Pipe Underdrain 6-Inch	350.000 LF	·	
0156	612.0406 Pipe Underdrain Wrapped 6-Inch	35.000 LF		
0158	618.0100 Maintenance and Repair of Haul Roads (project) 01. 2310-13-70	1.000 EACH	·	
0160	618.0100 Maintenance and Repair of Haul Roads (project) 02. 2310-13-71	1.000 EACH		
0162	619.1000 Mobilization	1.000 EACH	·	
0164	620.0300 Concrete Median Sloped Nose	308.000 SF		
0166	624.0100 Water	140.000 MGAL	·	
0168	625.0100 Topsoil	7,885.000 SY	·	
0170	628.1504 Silt Fence	1,490.000 LF		
0172	628.1520 Silt Fence Maintenance	1,490.000 LF		
0174	628.1905 Mobilizations Erosion Control	8.000 EACH		
0176	628.1910 Mobilizations Emergency Erosion Control	10.000 EACH		







Page 7 of 17


Proposal ID: 20240109012 **Project(s):** 2310-13-70, 2310-13-71

Federal ID(s): WISC 2024117, WISC 2024118

SECTION: 0001 Roadway Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0178	628.7005 Inlet Protection Type A	39.000 EACH		
0180	628.7015 Inlet Protection Type C	38.000 EACH	<u></u>	
0182	628.7020 Inlet Protection Type D	60.000 EACH	<u>-</u>	
0184	628.7555 Culvert Pipe Checks	25.000 EACH	·	·
0186	629.0210 Fertilizer Type B	4.000 CWT	·	
0188	630.0120 Seeding Mixture No. 20	9.000 LB		
0190	630.0200 Seeding Temporary	9.000 LB	·	
0192	630.0500 Seed Water	8.000 MGAL	·	·
0194	631.0300 Sod Water	130.000 MGAL	·	·
0196	631.1000 Sod Lawn	7,885.000 SY	·	
0198	633.5100 Markers ROW	5.000 EACH		
0200	633.5200 Markers Culvert End	7.000 EACH		
0202	634.0618 Posts Wood 4x6-Inch X 18-FT	75.000 EACH		
0204	634.0622 Posts Wood 4x6-Inch X 22-FT	8.000 EACH		
0206	634.0814 Posts Tubular Steel 2x2-Inch X 14-FT	46.000 EACH		
0208	637.2210 Signs Type II Reflective H	867.610 SF		







Page 8 of 17


Proposal ID: 20240109012 **Project(s):** 2310-13-70, 2310-13-71

Federal ID(s): WISC 2024117, WISC 2024118

SECTION: 0001 Roadway Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0210	637.2215 Signs Type II Reflective H Folding	72.520 SF		
0212	637.2230 Signs Type II Reflective F	401.440 SF		
0214	638.2102 Moving Signs Type II	35.000 EACH		
0216	638.2602 Removing Signs Type II	74.000 EACH		·
0218	638.3000 Removing Small Sign Supports	65.000 EACH		·
0220	643.0300 Traffic Control Drums	50,390.000 DAY		
0222	643.0410 Traffic Control Barricades Type II	1,950.000 DAY		
0224	643.0420 Traffic Control Barricades Type III	3,460.000 DAY		
0226	643.0705 Traffic Control Warning Lights Type A	10,820.000 DAY		·
0228	643.0715 Traffic Control Warning Lights Type C	2,085.000 DAY		
0230	643.0900 Traffic Control Signs	28,955.000 DAY		
0232	643.0910 Traffic Control Covering Signs Type I	16.000 EACH		
0234	643.1050 Traffic Control Signs PCMS	40.000 DAY		
0236	643.1070 Traffic Control Cones 42-Inch	12,100.000 DAY		
0238	643.3165 Temporary Marking Line Paint 6-Inch	32,085.000 LF		
0242	643.5000 Traffic Control	1.000 EACH		







Page 9 of 17


Proposal ID: 20240109012 **Project(s):** 2310-13-70, 2310-13-71

Federal ID(s): WISC 2024117, WISC 2024118

SECTION: 0001 Roadway Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0244	644.1410 Temporary Pedestrian Surface Asphalt	150.000 SF		
0246	644.1601 Temporary Pedestrian Curb Ramp	1,740.000 DAY		
0248	644.1605 Temporary Pedestrian Detectable Warning Field	1,040.000 SF		
0250	644.1810 Temporary Pedestrian Barricade	2,080.000 LF		
0252	645.0111 Geotextile Type DF Schedule A	200.000 SY		
0254	645.0120 Geotextile Type HR	91.000 SY	·	
0256	646.2020 Marking Line Epoxy 6-Inch	41,629.000 LF	·	
0258	646.4020 Marking Line Epoxy 10-Inch	1,758.000 LF		
0260	646.5020 Marking Arrow Epoxy	27.000 EACH		
0262	646.5120 Marking Word Epoxy	7.000 EACH		
0264	646.5320 Marking Railroad Crossing Epoxy	2.000 EACH		
0266	646.6120 Marking Stop Line Epoxy 18-Inch	399.000 LF		·
0268	646.7020 Marking Diagonal Epoxy 6-Inch	360.000 LF	·	
0270	646.7120 Marking Diagonal Epoxy 12-Inch	210.400 LF		
0272	646.7420 Marking Crosswalk Epoxy Transverse Line 6-Inch	1,502.000 LF		







Page 10 of 17


Proposal ID: 20240109012 **Project(s):** 2310-13-70, 2310-13-71

Federal ID(s): WISC 2024117, WISC 2024118

SECTION: 0001 Roadway Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0274	646.7520 Marking Crosswalk Epoxy Block Style 24-Inch	280.000 LF		·
0276	646.8020 Marking Corrugated Median Epoxy	971.000 SF		
0278	646.8120 Marking Curb Epoxy	255.000 LF		
0280	646.8220 Marking Island Nose Epoxy	12.000 EACH		
0282	646.9000 Marking Removal Line 4-Inch	8,935.000 LF		
0284	650.4000 Construction Staking Storm Sewer	1.000 EACH		·
0286	650.5500 Construction Staking Curb Gutter and Curb & Gutter	1,510.000 LF		·
0288	650.6000 Construction Staking Pipe Culverts	4.000 EACH		
0290	650.8000 Construction Staking Resurfacing Reference	9,150.000 LF		
0292	650.8501 Construction Staking Electrical Installations (project) 01. 2310-13-70	1.000 EACH		·
0294	650.8501 Construction Staking Electrical Installations (project) 02. 2310-13-71	1.000 EACH		
0296	650.9000 Construction Staking Curb Ramps	38.000 EACH	·	
0298	650.9500 Construction Staking Sidewalk (project) 01. 2310-13-70	1.000 EACH		
0300	650.9911 Construction Staking Supplemental Control (project) 01. 2310-13-70	1.000 EACH		







Page 11 of 17


Proposal ID: 20240109012 **Project(s):** 2310-13-70, 2310-13-71

Federal ID(s): WISC 2024117, WISC 2024118

SECTION: 0001 Roadway Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0302	652.0225 Conduit Rigid Nonmetallic Schedule 40 2-Inch	2,505.000 LF		
0304	652.0325 Conduit Rigid Nonmetallic Schedule 80 2-Inch	1,885.000 LF		·
0306	652.0605 Conduit Special 2-Inch	1,900.000 LF		
0308	652.0615 Conduit Special 3-Inch	1,635.000 LF		
0310	652.0800 Conduit Loop Detector	4,838.000 LF		
0312	653.0135 Pull Boxes Steel 24x36-Inch	10.000 EACH		
0314	653.0140 Pull Boxes Steel 24x42-Inch	45.000 EACH		
0316	653.0164 Pull Boxes Non-Conductive 24x42-Inch	6.000 EACH		
0318	653.0905 Removing Pull Boxes	40.000 EACH		
0320	654.0101 Concrete Bases Type 1	15.000 EACH		
0322	654.0102 Concrete Bases Type 2	3.000 EACH	<u> </u>	
0324	654.0105 Concrete Bases Type 5	12.000 EACH		
0326	654.0110 Concrete Bases Type 10	7.000 EACH		
0328	654.0120 Concrete Bases Type 10-Special	5.000 EACH		
0330	654.0217 Concrete Control Cabinet Bases Type 9 Special	3.000 EACH		·







Page 12 of 17


Proposal ID: 20240109012 **Project(s):** 2310-13-70, 2310-13-71

Federal ID(s): WISC 2024117, WISC 2024118

SECTION: 0001 Roadway Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0332	654.0224 Concrete Control Cabinet Bases Type L24	1.000 EACH	·	
0334	655.0230 Cable Traffic Signal 5-14 AWG	1,483.000 LF		
0336	655.0240 Cable Traffic Signal 7-14 AWG	1,991.000 LF		
0338	655.0260 Cable Traffic Signal 12-14 AWG	4,805.000 LF		
0340	655.0270 Cable Traffic Signal 15-14 AWG	450.000 LF		
0342	655.0305 Cable Type UF 2-12 AWG Grounded	2,255.000 LF		
0344	655.0515 Electrical Wire Traffic Signals 10 AWG	5,370.000 LF		
0346	655.0610 Electrical Wire Lighting 12 AWG	3,897.000 LF		
0348	655.0620 Electrical Wire Lighting 8 AWG	5,828.000 LF		
0350	655.0700 Loop Detector Lead In Cable	16,020.000 LF		
0352	655.0800 Loop Detector Wire	15,893.000 LF		
0354	655.0900 Traffic Signal EVP Detector Cable	660.000 LF		
0356	656.0201 Electrical Service Meter Breaker Pedestal (location) 01. STH 60 & CTH P	1.000 EACH		
0358	656.0201 Electrical Service Meter Breaker Pedestal (location) 02. STH 60 & Industrial Dr	1.000 EACH		







Page 13 of 17


Proposal ID: 20240109012 **Project(s):** 2310-13-70, 2310-13-71

Federal ID(s): WISC 2024117, WISC 2024118

SECTION: 0001 Roadway Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0360	656.0201 Electrical Service Meter Breaker Pedestal (location) 03. STH 60 & Jackson Dr	1.000 EACH		
0362	656.0201 Electrical Service Meter Breaker Pedestal (location) 04. Cabinet JA	1.000 EACH	·	
0364	657.0100 Pedestal Bases	15.000 EACH		
0366	657.0255 Transformer Bases Breakaway 11 1/2- Inch Bolt Circle	15.000 EACH		
0368	657.0310 Poles Type 3	3.000 EACH	·	
0370	657.0322 Poles Type 5-Aluminum	12.000 EACH		
0372	657.0420 Traffic Signal Standards Aluminum 13-FT	2.000 EACH		
0374	657.0425 Traffic Signal Standards Aluminum 15-FT	11.000 EACH		
0376	657.0430 Traffic Signal Standards Aluminum 10-FT	2.000 EACH	·	
0378	657.0609 Luminaire Arms Single Member 4-Inch Clamp 6-FT	5.000 EACH		·
0380	657.0715 Luminaire Arms Truss Type 4 1/2-Inch Clamp 15-FT	12.000 EACH		
0382	658.0173 Traffic Signal Face 3S 12-Inch	36.000 EACH		
0384	658.0174 Traffic Signal Face 4S 12-Inch	24.000 EACH		
0386	658.0416 Pedestrian Signal Face 16-Inch	18.000 EACH		







Page 14 of 17


Proposal ID: 20240109012 **Project(s):** 2310-13-70, 2310-13-71

Federal ID(s): WISC 2024117, WISC 2024118

SECTION: 0001 Roadway Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0388	658.0500 Pedestrian Push Buttons	18.000 EACH		
0390	658.5070 Signal Mounting Hardware (location) 01. STH 60 & CTH P	1.000 EACH		
0392	658.5070 Signal Mounting Hardware (location) 02. STH 60 & Industrial Dr	1.000 EACH	·	
0394	658.5070 Signal Mounting Hardware (location) 03. STH 60 & Jackson Dr	1.000 EACH	·	
0396	659.1115 Luminaires Utility LED A	12.000 EACH		
0398	659.1125 Luminaires Utility LED C	16.000 EACH	·	
0400	659.2124 Lighting Control Cabinets 120/240 24- Inch	1.000 EACH		·
0402	659.5000.S Lamp, Ballast, LED, Switch Disposal by Contractor	70.000 EACH		
0404	661.0201 Temporary Traffic Signals for Intersections (location) 01. STH 60 & CTH P	1.000 EACH		
0406	661.0201 Temporary Traffic Signals for Intersections (location) 02. STH 60 & Industrial Dr	1.000 EACH	·	
0408	661.0201 Temporary Traffic Signals for Intersections (location) 03. STH 60 & Jackson Dr	1.000 EACH		
0410	690.0150 Sawing Asphalt	2,885.000 LF		
0412	690.0250 Sawing Concrete	491.000 LF		







Page 15 of 17


Proposal ID: 20240109012 **Project(s):** 2310-13-70, 2310-13-71

Federal ID(s): WISC 2024117, WISC 2024118

SECTION: 0001 Roadway Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0414	715.0720 Incentive Compressive Strength Concrete Pavement	500.000 DOL	1.00000	500.00
0416	740.0440 Incentive IRI Ride	7,540.000 DOL	1.00000	7,540.00
0418	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	1,500.000 HRS	5.00000	7,500.00
0420	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	1,800.000 HRS	5.00000	9,000.00
0422	SPV.0060 Special 01. Install Type 9 Pole	2.000 EACH	·	
0424	SPV.0060 Special 03. Install Type 10 Pole	5.000 EACH	·	<u>.</u>
0426	SPV.0060 Special 04. Install Type 10 Special Pole	5.000 EACH	·	
0428	SPV.0060 Special 05. Install Monotube Arms 25-FT	3.000 EACH	·	
0430	SPV.0060 Special 06. Install Monotube Arms 30-FT	4.000 EACH	·	
0432	SPV.0060 Special 07. Install Monotube Arms 35-FT Special	4.000 EACH		·
0434	SPV.0060 Special 08. Install Monotube Arms 40-FT Special	1.000 EACH		·
0436	SPV.0060 Special 09. Install Luminaire Arms Steel 15-FT	11.000 EACH		
0438	SPV.0060 Special 10. Transport and Install State Furnished EVP Detector Heads STH 60 & CTH P	1.000 EACH		







Page 16 of 17


Proposal ID: 20240109012 **Project(s):** 2310-13-70, 2310-13-71

Federal ID(s): WISC 2024117, WISC 2024118

SECTION: 0001 Roadway Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0440	SPV.0060 Special 11. Transport and Install State Furnished EVP Detector Heads STH 60 & Industrial	1.000 EACH	·	
0442	SPV.0060 Special 12. Transport and Install State Furnished EVP Detector Heads STH 60 & Jackson Dr	2.000 EACH	·	
0444	SPV.0060 Special 13. Transport and Install State Furnished Traffic Signal Cabinet STH 60 & CTH P	1.000 EACH	·	
0446	SPV.0060 Special 14. Transport and Install State Furnished Signal Cabinet STH 60 & Industrial Dr	1.000 EACH	·	·
0448	SPV.0060 Special 15. Transport and Install State Furnished Signal Cabinet STH 60 & Jackson Dr	1.000 EACH	·	
0450	SPV.0060 Special 16. Temporary Infrared EVP System STH 60 & CTH P	1.000 EACH		
0452	SPV.0060 Special 17. Temporary Infrared EVP System STH 60 & Industrial Dr	1.000 EACH		
0454	SPV.0060 Special 18. Temporary Infrared EVP System STH 60 & Jackson Dr	1.000 EACH		
0456	SPV.0060 Special 19. Transport Traffic Signal and Lighting Materials STH 60 & CTH P	1.000 EACH		
0458	SPV.0060 Special 20. Transport Traffic Signal and Lighting Materials STH 60 & Industrial Dr	1.000 EACH		
0460	SPV.0060 Special 21. Transport Traffic Signal and Lighting Materials STH 60 & Jackson Dr	1.000 EACH		·
0462	SPV.0060 Special 22. Saddle Inlet	2.000 EACH		







Page 17 of 17

Proposal ID: 20240109012 **Project(s):** 2310-13-70, 2310-13-71

Federal ID(s): WISC 2024117, WISC 2024118

SECTION: 0001 Roadway Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0464	SPV.0060	1.000		
	Special 23. Construction Staking Roundabout	EACH	·	·
0466	SPV.0060	4.000		
	Special 25. Section Corner Monuments	EACH	·	·
0468	SPV.0060	1.000		
	Special 26. Pedestrian Shuttle Service	EACH	·	·
0470	SPV.0060	12.000		
	Special 27. Utility Line Opening (ULO)	EACH	·	·
0472	SPV.0165	106.000		
	Special 01. Wall Modular Block Mechanically Stabilized Earth (R-66-87)	SF	·	·
0474	SPV.0165	45.000		
	Special 02. Wall Modular Block Gravity Landscape	SF	·	·
0476	SPV.0195	315.000		
	Special 01. Asphalt Repair	TON	<u>-</u>	·
	Section: 00	01	Total:	·

Total Bid:



Wisconsin Department of Transportation

January 4, 2024

Division of Transportation Systems Development

Bureau of Project Development 4822 Madison Yards Way, 4th Floor South Madison, WI 53705

Telephone: (608) 266-1631 Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #12: 2310-13-70, WISC 2024117

Main St, Village Jackson

CTH P to Eagle Dr

STH 60

Washington County

2310-13-71, WISC 2024118

V Jackson, Eagle Dr Intersection with STH 60

Local Street

Washington County

Letting of January 9, 2024

This is Addendum No. 03, which provides for the following:

Schedule of Items:

Added Bid Item Quantities						
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Quantity Added	Proposal Total After Addendum	
204.0100	Removing Concrete Pavement	SY	0	1,565	1,565	

Plan Sheets:

Revised Plan Sheets 2310-13-70				
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)			
61	Miscellaneous Quantities (add pay item 204.0100)			

Schedule of Items

Attached, dated January 4, 2024, are the revised Schedule of Items Page 17.

Plan Sheets

The following $8\frac{1}{2}$ x 11-inch sheets are attached and made part of the plans for this proposal:

2310-13-71 Revised: 61

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist Proposal Management Section


END OF ADDENDUM

က Addendum No. 03 61 ID 2310-13-71 COMMENT **Revised Sheet 61** SHEET: January 4, 2024 WASTE PLOT SCALE: 1:1 00000 00000 MASS ORDINATE +/-(14) THE MASS ORDINATE + OR - QTY CALCULATED FOR THE DIVISION. PLUS QUANTITY INDICATES AN EXCESS OF MATERIAL WITHIN THE DIVISION.

(15) FACTORS USED TO COMPUTE ANTICIPATED WASTE AND THE COMPUTED WASTE VOLUME! DENTIFIED ARE FOR GENERAL INFORMATION ONLY.

UNDISTRIBUTED QUANTITY FOR REMOVING CONCRETE PAVEMBIT WAS NOT FACTORED INTO THE EARTH WORK TABLE. 2,093 366 533 462 147 -35 789 403 345 221 335 PLOT NAME **EXPANDED FILL** FACTOR 1.25 444 330 31 6 641 1,453 104 3 10 56 56 MISCELLANEOUS QUANTITIES (1) COMMON EXCANATION IS THE SUM OF THE CUTAND EBS EXCAVATION COLUMNS. ITEM NUMBER 205, 0.100 (2) SALVAGED/UNSUABLE PAVEMENT MATERIAL IS INCLUDED IN CUT. (3) EBS VOLUME ASSUMED TO BE 5% OF CUTVOLUME. EBS EXCAVATION TO BE BACKFILLED WITH SELECT CRUSH MATERIAL. EBS MATERIAL IS ASSUMED TO BE UNUSABLE IN FILLS. UNEXPANDED PLOT BY: MSA 355 264 25 5 5 513 1,162 표 83 2 8 8 45 REMOVING CONCRETE PAVEMENT 204.0100 1,565 1,565 AVAILABLE MATERIAL TOTAL 1000 LOCATION 793 507 347 231 391 2,269 810 863 493 153 606 (2) REMOVING CONCRETE PAVEMENT PLOT DATE: January 4, 2024 STATION TO STATION SALVAGED/UNUSABLE PAVEMENT MATERIAL **UNDISTRIBUTED** COUNTY: WASHINGTON 186 106 76 39 132 539 98 147 96 29 270 270 640 ROADWAY PROJECT **EBS EXCAVATION** (4) SALVAGED/UNUSABLE PAVEMENT MATERIAL INCLUDES EXISTING APSHALTIC PAVEMENT (13) EXPANDED FILL FACTOR = 1.25. EXPANDED FILL = (UNEXPANDED FILL)*FILL FACTOR 205.0100 COMMON EXCAVATION 45 51 30 10 44 180 50 31 21 15 30 CATEGORY 1000 5) AVAILABLE MATERIAL = CUT - SALVAGED/UNUSUABLE PAVEMENT MATERIAL 908 1,010 589 182 876 876 8,565 CUT (2) 979 613 423 270 523 2,808 HWY: EAGLE DRIVE LOCATION LT/RT LT/RT LT/RT LT/RT LT/RT RT LT/RT LT LT LT/RT 301+04.26/303+60.30 304+86.54/306+93.45 400+00.00/401+32.77 400+10.26/401+35.28 11+82.35/12+80.93 402+61.69/403+87.00 402+63.87/403+22.95 301+06.49/303+63.08 304+91.72/306+96.16 FROM/TO STATION PROJECT NO: 2310-13-71 FILE NAME: N:\PDS\...\030200_mq.pptx STAGE 3 SUBTOTAL STAGE 2 - RNB NORTH LEG STAGE 2 - RSB NORTH LEG STAGE 2 - RAB STAGE 2 SUBTOTAL STAGE 3 - RNB SOUTH LEG STAGE 3 - RSB SOUTH LEG STAGE 3 - RAB DIVISION **IAGE 2 - RWB WEST LEG** TAGE 2 - RWB EAST LEG STAGE 3 - REB WEST LEG STAGE 3 - REB EAST LEG







Page 17 of 17

Federal ID(s): WISC 2024117, WISC 2024118

SECTION: 0001 Roadway Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0464	SPV.0060 Special 23. Construction Staking Roundabout	1.000 EACH		·
0466	SPV.0060 Special 25. Section Corner Monuments	4.000 EACH		
0468	SPV.0060 Special 26. Pedestrian Shuttle Service	1.000 EACH		
0470	SPV.0060 Special 27. Utility Line Opening (ULO)	12.000 EACH		
0472	SPV.0165 Special 01. Wall Modular Block Mechanically Stabilized Earth (R-66-87)	106.000 SF		
0474	SPV.0165 Special 02. Wall Modular Block Gravity Landscape	45.000 SF		·
0476	SPV.0195 Special 01. Asphalt Repair	315.000 TON		
0478	204.0100 Removing Concrete Pavement	1,565.000 SY		

Section: 0001

_ ._..

Total:

Total Bid: _____.___.