



Wisconsin Department of Transportation

February 5, 2024

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #31: 6999-09-72, WISC 2024256
C Wausau, Stewart Avenue
S 72nd Avenue to S 48th Avenue
Loc Str
Marathon County

Letting of February 13, 2024

This is Addendum No. 01, which provides for the following:

Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Proposal Quantity Change (-)	Proposal Total After Addendum
SPV.0060.10	Manholes Sanitary 5-FT Diameter	EA	14	1	15
SPV.0060.11	Manholes Sanitary 6-FT Diameter	EA	3	-1	2

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
19	Corrected error in dimensions between all views
207	Corrected summation error in HMA Pavement 4 LT 58-28 S in Stage 3 (no proposal change required)
223	Corrected manhole size on Structure 30 to match the plans

Schedule of Items

Attached, dated February 5, 2024, are the revised Schedule of Items Pages 16 and 17.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 19, 207, and 223.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

END OF ADDENDUM

Addendum No. 01
 ID 6999-09-72
 Revised Sheet 207
 February 5, 2024

3

BASE AGGREGATE ITEMS											
211.0500	305.0110*	305.0120*	PREPARE		FOUNDATION FOR		COMMENTS				
STA	TON	TON	STATION	TO	STATION	TO	OFFSET	OFFSET	COMMENTS		
0010	1	100+42 - 101+34	LT	77-50	-	80+00	LT & RT	3	10	470	WIDENING S 48TH AVE
SUBTOTALS STAGE 1											
0010	2	96+75 - 100+42	LT & RT	27	27	17+55	LT & RT	20	20	9,470	S 72ND AVE
0010	3	17+57 - 23+61	LT	15	15	58+80	LT & RT	3	3	700	S 56TH AVE
SUBTOTALS STAGE 2											
0010	3	100+42 - 152+42	LT & RT	50	50	15+82	RT	10	10	435	S 72ND AVE
0010	4	15+82 - 18+67	RT	1	1	40+16	LT & RT	1	1	310	S 68TH AVE
SUBTOTALS STAGE 3											
0010	4	100+42 - 119+00	LT	19+17	-	23+61	RT	2	2	930	MULTI-USE TRAIL S 72ND AVE
SUBTOTALS STAGE 4											
0010	4	102+78 - 103+01	LT	84	84			1	1	3,510	
CATEGORY 0010 TOTALS											
NOTE: *ADDITIONAL QUANTITIES SHOWN ELSEWHERE											

NOTE: *ADDITIONAL QUANTITIES SHOWN ELSEWHERE

EXCAVATION FOR STRUCTURES CULVERTS										
206.2001.01	206.2001.01	206.2001.01	PREPARE		FOUNDATION FOR		COMMENTS			
STA	TON	TON	STATION	TO	STATION	TO	OFFSET	OFFSET	COMMENTS	
0010	2	102+78 - 103+01	LT	1	1			1	1	
CATEGORY 0010 TOTAL										

PRECAST CONCRETE BOX CULVERT										
SPV.0090.04	SPV.0090.04	SPV.0090.04	PREPARE		FOUNDATION FOR		COMMENTS			
STA	TON	TON	STATION	TO	STATION	TO	OFFSET	OFFSET	COMMENTS	
0010	2	102+78 - 103+01	LT	30	30			30	30	
CATEGORY 0010 TOTAL										

DRIVEWAYS										
305.0110*	305.0120*	305.0120*	PREPARE		FOUNDATION FOR		COMMENTS			
STA	TON	TON	STATION	TO	STATION	TO	OFFSET	OFFSET	COMMENTS	
0010	1	77+55 - 78+45	LT	80	80			80	80	S 48TH AVE
SUBTOTALS STAGE 1										
0010	2	150+25 - 176+55	LT & RT	112	112	833	410	410	410	262
0010	3	58+80 - 61+00	LT & RT	15	15					5
SUBTOTALS STAGE 2										
0010	3	97+25 - 100+42	RT	85	85					32
0010	4	100+42 - 150+25	LT & RT	108	108	740	75	75	75	270
SUBTOTALS STAGE 3										
0010	4	107+50 - 118+10	LT	113	113					11
0010	5	14+60 - 23+61	LT & RT	34	34					10
SUBTOTALS STAGE 4										
0010	5	147 - 147	LT	175	175					21
CATEGORY 0010 TOTALS										
NOTE: BASE AGGREGATE DENSE 3/4-INCH IS TO BE USED ON ALL UNPAVED DRIVEWAYS.										

NOTE: BASE AGGREGATE DENSE 3/4-INCH IS TO BE USED ON ALL UNPAVED DRIVEWAYS.

ASPHALTIC ITEMS										
211.0400	450.4000	455.0605	PREPARE		FOUNDATION FOR		COMMENTS			
STA	TON	TON	STATION	TO	STATION	TO	OFFSET	OFFSET	COMMENTS	
0010	45	94+50 - 150+25	LT & RT	45	45					2
0010	1	14+60 - 23+61	LT & RT	23	23	89	44	44	44	2
0010	2	17+90 - 22+23	LT	53	53					2
0010	3	152+42 - 176+55	LT & RT	1,911	1,911					6
0010	4	153+22 - 176+29	LT	435	435					6
0010	5	58+80 - 61+00	LT & RT	57	57					6
SUBTOTALS STAGE 1										
0010	5	17+90 - 22+23	LT	53	53					6
0010	6	152+42 - 176+55	LT & RT	1,911	1,911					6
0010	7	153+22 - 176+29	LT	435	435					6
0010	8	58+80 - 61+00	LT & RT	57	57					6
SUBTOTALS STAGE 2										
0010	3	100+42 - 152+42	LT & RT	3,026	3,026					6
0010	4	119+47 - 152+42	LT	616	616					6
0010	5	18+62 - 18+82	LT & RT	67	67					6
0010	6	40+16 - 41+00	LT & RT	67	67					6
SUBTOTALS STAGE 3										
0010	4	100+42 - 152+42	LT & RT	3,094	3,094					6
0010	5	100+42 - 118+11	LT	331	331					6
SUBTOTALS STAGE 4										
0010	5	100+42 - 118+37	LT	1,800	1,800					6
0010	6	40+16 - 41+00	LT & RT	34	34					6
0010	7	40+16 - 41+00	LT & RT	34	34					6
SUBTOTALS STAGE 5										
0010	8	100+42 - 118+37	LT	1,800	1,800					6
0010	9	40+16 - 41+00	LT & RT	34	34					6
0010	10	40+16 - 41+00	LT & RT	34	34					6
CATEGORY 0010 TOTALS										

MISCELLANEOUS QUANTITIES										
211.0400	450.4000	455.0605	PREPARE		FOUNDATION FOR		COMMENTS			
STA	TON	TON	STATION	TO	STATION	TO	OFFSET	OFFSET	COMMENTS	
0010	45	94+50 - 150+25	LT & RT	45	45					2
0010	1	14+60 - 23+61	LT & RT	23	23	89	44	44	44	2
0010	2	17+90 - 22+23	LT	53	53					2
0010	3	152+42 - 176+55	LT & RT	1,911	1,911					6
0010	4	153+22 - 176+29	LT	435	435					6
0010	5	58+80 - 61+00	LT & RT	57	57					6
SUBTOTALS STAGE 1										
0010	6	17+90 - 22+23	LT	53	53					6
0010	7	152+42 - 176+55	LT & RT	1,911	1,911					6
0010	8	153+22 - 176+29	LT	435	435					6
0010	9	58+80 - 61+00	LT & RT	57	57					6
SUBTOTALS STAGE 2										
0010	3	100+42 - 152+42	LT & RT	3,026	3,026					6
0010	4	119+47 - 152+42	LT	616	616					6
0010	5	18+62 - 18+82	LT & RT	67	67					6
0010	6	40+16 - 41+00	LT & RT	67	67					6
SUBTOTALS STAGE 3										
0010	4	100+42 - 152+42	LT & RT	3,094	3,094					6
0010	5	100+42 - 118+11	LT	331	331					6
SUBTOTALS STAGE 4										
0010	5	100+42 - 118+37	LT	1,800	1,800					6
0010	6	40+16 - 41+00	LT & RT	34	34					6
0010	7	40+16 - 41+00	LT & RT	34	34					6
SUBTOTALS STAGE 5										
0010	8	100+42 - 118+37	LT	1,800	1,800					6
0010	9	40+16 - 41+00	LT & RT	34	34					6
0010	10	40+16 - 41+00	LT & RT	34	34					6
CATEGORY 0010 TOTALS										

Addendum No. 01
ID 6999-09-72
Revised Sheet 223
February 5, 2024

ABANDONING SANITARY SEWER

CATEGORY	STAGE	LOCATION	FROM	TO	SPV.0035.02 CY
0020	2	STEWART AVE	MH AT STA. 176+84	EXISTING MH AT STA. 177+40	3
SUBTOTAL STAGE 2					3
0020	3		EXISTING MH AT STA. 100+28	SAN MH (46) STA. 119+10	26
SUBTOTAL STAGE 3					26
CATEGORY 0020 TOTAL					29

TEMPORARY WATER SERVICE

CATEGORY	LOCATION	SPV.0060.07 EACH
0020	PROJECT	1
CATEGORY 0020 TOTAL		

ABANDONING SANITARY STRUCTURE

CATEGORY	STAGE	STATION	OFFSET	SPV.0060.08 EACH
0020	3	104+03	RT	1
		107+22	RT	1
		111+24	RT	1
		114+73	RT	1
		117+14	RT	1
		119+12	RT	1
SUBTOTAL STAGE 3				
CATEGORY 0020 TOTAL				

CONNECTING SANITARY SEWER

CATEGORY	STAGE	STRUCTURE	STATION	OFFSET	NO. OF EXISTING PIPES TO BE CONNECTED	SPV.0060.09 EACH	COMMENTS
0020	1	SAN MH (76)	79+16.0	30.4 RT	2	1	
SUBTOTAL STAGE 1							
0020	2	SAN MH (68)	170+36.0	11.8 RT	1	1	
SUBTOTAL STAGE 2							
0020	3	SAN MH (30)	100+27.8	27.5 RT	1	1	3 EXISTING PIPES, 1 TO BE ABANDONED
		SAN MH (34)	104+08.0	49.0 RT	1	1	2 EXISTING PIPES, 1 TO BE ABANDONED
		EX. SAN FM TEE	104+00.3	98.2 RT	1	1	EXISTING SANITARY FORCE MAIN TEE
		SAN MH (46)	119+10.0	0.0'	1	1	
SUBTOTAL STAGE 3							
CATEGORY 0020 TOTAL							

SANITARY SEWER MANHOLES AND COVERS

CATEGORY	STAGE	STATION	OFFSET	STRUCTURE	611.0230.5* TEMPORARY PLATES EACH	SPV.0060.34 SANITARY 6-FT DIAMETER EACH	SPV.0060.10 SANITARY 5-FT DIAMETER EACH	SPV.0060.11 SANITARY 6-FT COVERS EACH	SPV.0060.12 SPECIAL MANHOLE COVERS EACH
0020	1	176+83.9	13.4 RT	72	1	--	1	--	1
		078+54.4	38.6 RT	74	1	--	1	--	1
		26+00.0	26.0 RT	76	1	--	1	--	1
		101+00.4	46.4 RT	32	1	--	1	--	1
SUBTOTAL STAGE 1									
0020	2	149+08.3	12.0 RT	58	1	--	1	--	1
		155+08.3	12.0 RT	60	1	--	1	--	1
		161+07.3	12.0 RT	62	1	--	1	--	1
		167+07.3	12.0 RT	64	1	--	1	--	1
		168+35.5	12.0 RT	66	1	--	1	--	1
		170+35.8	12.0 RT	68	1	--	1	--	1
		173+91.9	12.0 RT	70	1	--	1	--	1
SUBTOTAL STAGE 2									
0020	3	100+27.8	27.6 RT	30	1	--	1	--	1
		104+05.7	90.17 RT	32	1	--	1	--	1
		104+51.0	0.0'	34	1	--	1	--	1
		104+51.0	0.0'	36	1	--	1	--	1
		108+50.0	0.0'	38	1	--	1	--	1
		111+47.4	0.0'	40	1	--	1	--	1
		115+00.0	0.0'	42	1	--	1	--	1
		118+00.0	0.0'	44	1	--	1	--	1
		119+08.3	0.0'	46	1	--	1	--	1
		129+01.7	0.0'	48	1	--	1	--	1
		132+91.1	0.0'	50	1	--	1	--	1
		137+08.5	0.0'	52	1	--	1	--	1
		143+08.3	0.0'	54	1	--	1	--	1
SUBTOTAL STAGE 3									
CATEGORY 0020 TOTALS									

NOTE:
ADDITIONAL QUANTITIES SHOWN ELSEWHERE



Proposal Schedule of Items

Proposal ID: 20240213031 Project(s): 6999-09-72

Federal ID(s): WISC 2024256

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0452	SPV.0030 Special 01. Fertilizer for Lawn Type Turf	15.000 CWT	_____.	_____.
0454	SPV.0035 Special 01. Utility Trench Rock Excavation	40.000 CY	_____.	_____.
0456	SPV.0035 Special 02. Abandoning Sanitary Sewer	29.000 CY	_____.	_____.
0458	SPV.0060 Special 01. Research and Locate Existing Land Parcel Monuments	97.000 EACH	_____.	_____.
0460	SPV.0060 Special 02. Verify and Replace Existing Land Parcel Monuments	97.000 EACH	_____.	_____.
0462	SPV.0060 Special 03. Inlet Covers Type H-D	2.000 EACH	_____.	_____.
0464	SPV.0060 Special 04. Remove and Reinstall Street Lighting Assembly	1.000 EACH	_____.	_____.
0466	SPV.0060 Special 05. Salvage Traffic Signal and Lighting System (Stewart Avenue & S 72nd Avenue)	1.000 EACH	_____.	_____.
0468	SPV.0060 Special 06. Transport and Install City Furnished EVP (Stewart Avenue & S 72nd Avenue)	1.000 EACH	_____.	_____.
0470	SPV.0060 Special 07. Temporary Water Service	1.000 EACH	_____.	_____.
0472	SPV.0060 Special 08. Abandoning Sanitary Structure	6.000 EACH	_____.	_____.
0474	SPV.0060 Special 09. Connecting Sanitary Sewer	6.000 EACH	_____.	_____.
0476	SPV.0060 Special 10. Manholes Sanitary 5-FT Diameter	15.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20240213031 Project(s): 6999-09-72

Federal ID(s): WISC 2024256

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0478	SPV.0060 Special 11. Manholes Sanitary 6-FT Diameter	2.000 EACH	_____.	_____.
0480	SPV.0060 Special 12. Sanitary Manhole Covers Type J-Special	23.000 EACH	_____.	_____.
0482	SPV.0060 Special 13. Sanitary Sewer PVC Wyes	23.000 EACH	_____.	_____.
0484	SPV.0060 Special 14. Sanitary Sewer Force Main Cleanout	1.000 EACH	_____.	_____.
0486	SPV.0060 Special 15. Connecting Water Main	14.000 EACH	_____.	_____.
0488	SPV.0060 Special 16. 10x10x10-Inch Tee	1.000 EACH	_____.	_____.
0490	SPV.0060 Special 17. 12x12x8-Inch Tee	3.000 EACH	_____.	_____.
0492	SPV.0060 Special 18. 14x14x8-Inch Tee	6.000 EACH	_____.	_____.
0494	SPV.0060 Special 19. 14x14x12-Inch Tee	1.000 EACH	_____.	_____.
0496	SPV.0060 Special 20. 12-Inch 11.25 Degree Bend	4.000 EACH	_____.	_____.
0498	SPV.0060 Special 21. 12-Inch 45 Degree Bend	4.000 EACH	_____.	_____.
0500	SPV.0060 Special 22. 8x6-Inch Reducer	8.000 EACH	_____.	_____.
0502	SPV.0060 Special 23. 12x10-Inch Reducer	1.000 EACH	_____.	_____.
0504	SPV.0060 Special 24. 8-Inch Valve & Valve Box	9.000 EACH	_____.	_____.
0506	SPV.0060 Special 25. 12-Inch Valve & Valve Box	6.000 EACH	_____.	_____.

