



Wisconsin Department of Transportation

March 20, 2024

**Division of Transportation Systems
Development**

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

**Proposal #01: 1010-10-82, WISC 2024324
Madison – Portage
Wisconsin River Bridges
IH 39
Columbia County**

Letting of April 9, 2024

This is Addendum No. 01, which provides for the following:

The Schedule of Items shown in the proposal was outdated. This addendum replaces the SOI to the latest version.

Schedule of Items

Attached, dated March 20, 2024, are the revised Schedule of Items Pages 1 – 30.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

END OF ADDENDUM



Proposal Schedule of Items

Proposal ID: 20240409001 Project(s): 1010-10-82

Federal ID(s): WISC 2024324

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	108.4400 CPM Progress Schedule	1.000 EACH	_____.	_____.
0004	201.0105 Clearing	6.000 STA	_____.	_____.
0006	201.0205 Grubbing	134.000 STA	_____.	_____.
0008	201.0220 Grubbing	24.000 ID	_____.	_____.
0010	203.0100 Removing Small Pipe Culverts	6.000 EACH	_____.	_____.
0012	203.0220 Removing Structure (structure) 01. Box Culvert	1.000 EACH	_____.	_____.
0014	203.0220 Removing Structure (structure) 02. Culvert with Headwalls	1.000 EACH	_____.	_____.
0016	203.0220 Removing Structure (structure) 03. B-11-37	1.000 EACH	_____.	_____.
0018	203.0220 Removing Structure (structure) 04. B-11-35	1.000 EACH	_____.	_____.
0020	203.0220 Removing Structure (structure) 05. C-11-11	1.000 EACH	_____.	_____.
0022	203.0260 Removing Structure Over Waterway Minimal Debris (structure) 01. B-11-22	1.000 EACH	_____.	_____.
0024	203.0260 Removing Structure Over Waterway Minimal Debris (structure) 02. B-11-23	1.000 EACH	_____.	_____.
0026	203.0330 Debris Containment (structure) 01. B-11-37	1.000 EACH	_____.	_____.
0028	203.0330 Debris Containment (structure) 02. B-11-35	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20240409001 Project(s): 1010-10-82

Federal ID(s): WISC 2024324

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0030	204.0100 Removing Concrete Pavement	91,507.000 SY	_____.	_____.
0032	204.0110 Removing Asphaltic Surface	67.000 SY	_____.	_____.
0034	204.0115 Removing Asphaltic Surface Butt Joints	920.000 SY	_____.	_____.
0036	204.0120 Removing Asphaltic Surface Milling	62,480.000 SY	_____.	_____.
0038	204.0150 Removing Curb & Gutter	180.000 LF	_____.	_____.
0040	204.0157 Removing Concrete Barrier	2,449.000 LF	_____.	_____.
0042	204.0165 Removing Guardrail	9,353.000 LF	_____.	_____.
0044	204.0170 Removing Fence	17,761.000 LF	_____.	_____.
0046	204.0180 Removing Delineators and Markers	428.000 EACH	_____.	_____.
0048	204.0195 Removing Concrete Bases	10.000 EACH	_____.	_____.
0050	204.0220 Removing Inlets	18.000 EACH	_____.	_____.
0052	204.0245 Removing Storm Sewer (size) 01. 18-Inch	714.000 LF	_____.	_____.
0054	204.0245 Removing Storm Sewer (size) 02. 24-Inch	1,140.000 LF	_____.	_____.
0056	204.0245 Removing Storm Sewer (size) 03. 30-Inch	154.000 LF	_____.	_____.
0058	204.0245 Removing Storm Sewer (size) 04. 42-Inch	170.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20240409001 **Project(s):** 1010-10-82
Federal ID(s): WISC 2024324
SECTION: 0001 Contract Items
Alt Set ID: **Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0060	204.0291.S Abandoning Sewer	47.000 CY	_____.	_____.
0062	204.9060.S Removing (item description) 01. Apron Endwall	5.000 EACH	_____.	_____.
0064	204.9060.S Removing (item description) 02. Gate	2.000 EACH	_____.	_____.
0066	204.9060.S Removing (item description) 03. Pole	1.000 EACH	_____.	_____.
0068	205.0100 Excavation Common	307,341.000 CY	_____.	_____.
0070	205.0200 Excavation Rock	13,095.000 CY	_____.	_____.
0072	205.0400 Excavation Marsh	14,500.000 CY	_____.	_____.
0074	206.1001 Excavation for Structures Bridges (structure) 01. B-11-184	1.000 EACH	_____.	_____.
0076	206.1001 Excavation for Structures Bridges (structure) 02. B-11-183	1.000 EACH	_____.	_____.
0078	206.1001 Excavation for Structures Bridges (structure) 03. B-11-182	1.000 EACH	_____.	_____.
0080	206.1001 Excavation for Structures Bridges (structure) 04. B-11-185	1.000 EACH	_____.	_____.
0082	206.1050.S Underwater Foundation Inspection (location) 01. B-11-184 Pier 12	1.000 EACH	_____.	_____.
0084	206.1050.S Underwater Foundation Inspection (location) 02. B-11-183 Pier 12	1.000 EACH	_____.	_____.
0086	206.2001 Excavation for Structures Culverts (structure) 01. C-11-11	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20240409001 Project(s): 1010-10-82

Federal ID(s): WISC 2024324

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0088	206.3001 Excavation for Structures Retaining Walls (structure) 01. R-11-48	1.000 EACH	_____.	_____.
0090	206.5001 Cofferdams (structure) 01. B-11-184	1.000 EACH	_____.	_____.
0092	206.5001 Cofferdams (structure) 02. B-11-183	1.000 EACH	_____.	_____.
0094	206.5001 Cofferdams (structure) 03. C-11-11	1.000 EACH	_____.	_____.
0096	209.2500 Backfill Granular Grade 2	160.000 TON	_____.	_____.
0098	210.1500 Backfill Structure Type A	5,062.000 TON	_____.	_____.
0100	210.2500 Backfill Structure Type B	416.000 TON	_____.	_____.
0102	211.0400 Prepare Foundation for Asphaltic Shoulders	11.000 STA	_____.	_____.
0104	213.0100 Finishing Roadway (project) 01. 1010-10-82	1.000 EACH	_____.	_____.
0106	214.0100 Obliterating Old Road	3.300 STA	_____.	_____.
0108	305.0110 Base Aggregate Dense 3/4-Inch	7,474.000 TON	_____.	_____.
0110	305.0120 Base Aggregate Dense 1 1/4-Inch	92,994.000 TON	_____.	_____.
0112	310.0110 Base Aggregate Open-Graded	705.000 TON	_____.	_____.
0114	312.0110 Select Crushed Material	240,438.000 TON	_____.	_____.
0116	415.0210 Concrete Pavement Gaps	3.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20240409001 Project(s): 1010-10-82

Federal ID(s): WISC 2024324

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0118	415.0410 Concrete Pavement Approach Slab	580.000 SY	_____.	_____.
0120	416.0610 Drilled Tie Bars	260.000 EACH	_____.	_____.
0122	450.4000 HMA Cold Weather Paving	890.000 TON	_____.	_____.
0124	455.0605 Tack Coat	7,598.000 GAL	_____.	_____.
0126	460.2000 Incentive Density HMA Pavement	7,780.000 DOL	1.00000	7,780.00
0128	460.5223 HMA Pavement 3 LT 58-28 S	2,069.000 TON	_____.	_____.
0130	460.5224 HMA Pavement 4 LT 58-28 S	1,773.000 TON	_____.	_____.
0132	460.7223 HMA Pavement 3 HT 58-28 S	7,500.000 TON	_____.	_____.
0134	460.7224 HMA Pavement 4 HT 58-28 S	4,175.000 TON	_____.	_____.
0136	460.7424 HMA Pavement 4 HT 58-28 H	6,130.000 TON	_____.	_____.
0138	465.0105 Asphaltic Surface	50.000 TON	_____.	_____.
0140	465.0120 Asphaltic Surface Driveways and Field Entrances	46.000 TON	_____.	_____.
0142	465.0125 Asphaltic Surface Temporary	1,665.000 TON	_____.	_____.
0144	465.0315 Asphaltic Flumes	55.000 SY	_____.	_____.
0146	501.1000.S Ice Hot Weather Concreting	216,895.000 LB	_____.	_____.
0148	502.0100 Concrete Masonry Bridges	15,085.000 CY	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20240409001 Project(s): 1010-10-82

Federal ID(s): WISC 2024324

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0150	502.1100 Concrete Masonry Seal	5,998.000 CY	_____.	_____.
0152	502.3101 Expansion Device	172.000 LF	_____.	_____.
0154	502.3111.S Expansion Device Modular	688.000 LF	_____.	_____.
0156	502.3200 Protective Surface Treatment	18,604.000 SY	_____.	_____.
0158	502.3210 Pigmented Surface Sealer	4,201.000 SY	_____.	_____.
0160	502.4205 Adhesive Anchors No. 5 Bar	679.000 EACH	_____.	_____.
0162	502.9000.S Underwater Substructure Inspection (structure) 01. B-11-184	1.000 EACH	_____.	_____.
0164	502.9000.S Underwater Substructure Inspection (structure) 02. B-11-183	1.000 EACH	_____.	_____.
0166	503.0146 Prestressed Girder Type I 45W-Inch	851.000 LF	_____.	_____.
0168	503.0155 Prestressed Girder Type I 54W-Inch	963.000 LF	_____.	_____.
0170	503.0172 Prestressed Girder Type I 72W-Inch	32,660.000 LF	_____.	_____.
0172	504.0100 Concrete Masonry Culverts	64.000 CY	_____.	_____.
0174	504.0500 Concrete Masonry Retaining Walls	720.000 CY	_____.	_____.
0176	505.0400 Bar Steel Reinforcement HS Structures	3,447,610.000 LB	_____.	_____.
0178	505.0600 Bar Steel Reinforcement HS Coated Structures	3,590,595.000 LB	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20240409001 **Project(s):** 1010-10-82
Federal ID(s): WISC 2024324
SECTION: 0001 Contract Items
Alt Set ID: **Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0180	505.0800.S Bar Steel Reinforcement HS Stainless Structures	5,580.000 LB	_____.	_____.
0182	506.0605 Structural Steel HS	518,030.000 LB	_____.	_____.
0184	506.2605 Bearing Pads Elastomeric Non-Laminated	356.000 EACH	_____.	_____.
0186	506.2610 Bearing Pads Elastomeric Laminated	144.000 EACH	_____.	_____.
0188	506.3015 Welded Stud Shear Connectors 7/8x6-Inch	2,190.000 EACH	_____.	_____.
0190	506.4000 Steel Diaphragms (structure) 01. B-11-184	208.000 EACH	_____.	_____.
0192	506.4000 Steel Diaphragms (structure) 02. B-11-183	208.000 EACH	_____.	_____.
0194	506.4000 Steel Diaphragms (structure) 03. B-11-182	12.000 EACH	_____.	_____.
0196	506.4000 Steel Diaphragms (structure) 04. B-11-185	12.000 EACH	_____.	_____.
0198	509.5100.S Polymer Overlay	32,370.000 SY	_____.	_____.
0200	511.1100 Temporary Shoring	300.000 SF	_____.	_____.
0202	511.1200 Temporary Shoring (structure) 01. B-11-183	4,000.000 SF	_____.	_____.
0204	511.1200 Temporary Shoring (structure) 02. R-11-44	490.000 SF	_____.	_____.
0206	511.1200 Temporary Shoring (structure) 03. R-11-45	540.000 SF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20240409001 Project(s): 1010-10-82

Federal ID(s): WISC 2024324

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0208	511.1200 Temporary Shoring (structure) 04. C-11-11	347.000 SF	_____.	_____.
0210	513.2001 Railing Pipe	580.000 LF	_____.	_____.
0212	514.0450 Floor Drains Type WF	18.000 EACH	_____.	_____.
0214	516.0500 Rubberized Membrane Waterproofing	170.000 SY	_____.	_____.
0216	517.0601 Painting Epoxy System (structure) 01. R-11-48	1.000 EACH	_____.	_____.
0218	520.3318 Culvert Pipe Class III-A 18-Inch	118.000 LF	_____.	_____.
0220	520.3324 Culvert Pipe Class III-A 24-Inch	142.000 LF	_____.	_____.
0222	520.8000 Concrete Collars for Pipe	7.000 EACH	_____.	_____.
0224	521.0549 Apron Endwalls for Pipe Arch Sloped Cross Drains Steel 49x33-Inch 4 to 1	1.000 EACH	_____.	_____.
0226	521.0649 Apron Endwalls for Pipe Arch Sloped Cross Drains Steel 49x33-Inch 6 to 1	1.000 EACH	_____.	_____.
0228	521.1012 Apron Endwalls for Culvert Pipe Steel 12-Inch	4.000 EACH	_____.	_____.
0230	521.1018 Apron Endwalls for Culvert Pipe Steel 18-Inch	2.000 EACH	_____.	_____.
0232	521.1030 Apron Endwalls for Culvert Pipe Steel 30-Inch	1.000 EACH	_____.	_____.
0234	521.1505 Apron Endwalls for Culvert Pipe Sloped Side Drains Steel 24-Inch 4 to 1	2.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20240409001 Project(s): 1010-10-82

Federal ID(s): WISC 2024324

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0236	521.1518 Apron Endwalls for Culvert Pipe Sloped Side Drains Steel 18-Inch 6 to 1	4.000 EACH	_____.	_____.
0238	521.1524 Apron Endwalls for Culvert Pipe Sloped Side Drains Steel 24-Inch 6 to 1	4.000 EACH	_____.	_____.
0240	521.2005.S Surface Drain Pipe Corrugated Metal Slotted (inch) 01. 18-Inch	1,025.000 LF	_____.	_____.
0242	521.3118 Culvert Pipe Corrugated Steel 18-Inch	110.000 LF	_____.	_____.
0244	522.0424 Culvert Pipe Reinforced Concrete Class IV 24-Inch	220.000 LF	_____.	_____.
0246	522.0442 Culvert Pipe Reinforced Concrete Class IV 42-Inch	42.000 LF	_____.	_____.
0248	522.0530 Culvert Pipe Reinforced Concrete Class V 30-Inch	186.000 LF	_____.	_____.
0250	522.0548 Culvert Pipe Reinforced Concrete Class V 48-Inch	180.000 LF	_____.	_____.
0252	522.1015 Apron Endwalls for Culvert Pipe Reinforced Concrete 15-Inch	1.000 EACH	_____.	_____.
0254	522.1018 Apron Endwalls for Culvert Pipe Reinforced Concrete 18-Inch	2.000 EACH	_____.	_____.
0256	522.1024 Apron Endwalls for Culvert Pipe Reinforced Concrete 24-Inch	17.000 EACH	_____.	_____.
0258	522.1030 Apron Endwalls for Culvert Pipe Reinforced Concrete 30-Inch	2.000 EACH	_____.	_____.
0260	522.1036 Apron Endwalls for Culvert Pipe Reinforced Concrete 36-Inch	2.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20240409001 Project(s): 1010-10-82

Federal ID(s): WISC 2024324

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0262	522.1042 Apron Endwalls for Culvert Pipe Reinforced Concrete 42-Inch	5.000 EACH	_____.	_____.
0264	522.1048 Apron Endwalls for Culvert Pipe Reinforced Concrete 48-Inch	2.000 EACH	_____.	_____.
0266	522.2434 Culvert Pipe Reinforced Concrete Horizontal Elliptical Class HE-IV 34x53-Inch	44.000 LF	_____.	_____.
0268	530.0112 Culvert Pipe Corrugated Polyethylene 12-Inch	289.000 LF	_____.	_____.
0270	530.0118 Culvert Pipe Corrugated Polyethylene 18-Inch	17.000 LF	_____.	_____.
0272	530.0130 Culvert Pipe Corrugated Polyethylene 30-Inch	30.000 LF	_____.	_____.
0274	531.1100 Concrete Masonry Ancillary Structures Type NS	9.600 CY	_____.	_____.
0276	531.1140 Steel Reinforcement HS Ancillary Structures Type NS	906.000 LB	_____.	_____.
0278	531.2024 Drilling Shaft 24-Inch	30.000 LF	_____.	_____.
0280	531.2036 Drilling Shaft 36-Inch	10.000 LF	_____.	_____.
0282	531.4050 Foundation Camera Pole 50-FT	1.000 EACH	_____.	_____.
0284	550.0020 Pre-Boring Rock or Consolidated Materials	2,176.000 LF	_____.	_____.
0286	550.0500 Pile Points	128.000 EACH	_____.	_____.
0288	550.2128 Piling CIP Concrete 12 3/4 X 0.50-Inch	6,710.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20240409001 Project(s): 1010-10-82

Federal ID(s): WISC 2024324

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0290	601.0553 Concrete Curb & Gutter 4-Inch Sloped 36-Inch Type D	352.000 LF	_____.	_____.
0292	601.0557 Concrete Curb & Gutter 6-Inch Sloped 36-Inch Type D	345.000 LF	_____.	_____.
0294	601.0588 Concrete Curb & Gutter 4-Inch Sloped 36-Inch Type TBT	301.000 LF	_____.	_____.
0296	601.0590 Concrete Curb & Gutter 4-Inch Sloped 36-Inch Type TBTT	199.000 LF	_____.	_____.
0298	602.0815 Concrete Driveway 7-Inch	29.000 SY	_____.	_____.
0300	602.3010 Concrete Surface Drains	10.000 CY	_____.	_____.
0302	602.3220 Concrete Rumble Strips, Shoulder	26,290.000 LF	_____.	_____.
0304	603.1142 Concrete Barrier Type S42	6,434.000 LF	_____.	_____.
0306	603.1456 Concrete Barrier Type S56C	390.000 LF	_____.	_____.
0308	603.8000 Concrete Barrier Temporary Precast Delivered	54,038.000 LF	_____.	_____.
0310	603.8125 Concrete Barrier Temporary Precast Installed	67,275.000 LF	_____.	_____.
0312	603.8500 Anchoring Concrete Barrier Temporary Precast	4,725.000 LF	_____.	_____.
0314	604.0400 Slope Paving Concrete	88.000 SY	_____.	_____.
0316	604.0500 Slope Paving Crushed Aggregate	2,645.000 SY	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20240409001 Project(s): 1010-10-82

Federal ID(s): WISC 2024324

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0318	606.0200 Riprap Medium	248.000 CY	_____.	_____.
0320	606.0300 Riprap Heavy	1,571.000 CY	_____.	_____.
0322	608.0412 Storm Sewer Pipe Reinforced Concrete Class IV 12-Inch	58.000 LF	_____.	_____.
0324	608.0415 Storm Sewer Pipe Reinforced Concrete Class IV 15-Inch	99.000 LF	_____.	_____.
0326	608.0418 Storm Sewer Pipe Reinforced Concrete Class IV 18-Inch	43.000 LF	_____.	_____.
0328	608.0424 Storm Sewer Pipe Reinforced Concrete Class IV 24-Inch	2,566.000 LF	_____.	_____.
0330	608.0436 Storm Sewer Pipe Reinforced Concrete Class IV 36-Inch	309.000 LF	_____.	_____.
0332	608.0442 Storm Sewer Pipe Reinforced Concrete Class IV 42-Inch	412.000 LF	_____.	_____.
0334	611.0535 Manhole Covers Type J-Special	8.000 EACH	_____.	_____.
0336	611.0606 Inlet Covers Type B	2.000 EACH	_____.	_____.
0338	611.0624 Inlet Covers Type H	13.000 EACH	_____.	_____.
0340	611.0642 Inlet Covers Type MS	31.000 EACH	_____.	_____.
0342	611.0651 Inlet Covers Type S	4.000 EACH	_____.	_____.
0344	611.0654 Inlet Covers Type V	6.000 EACH	_____.	_____.
0346	611.2004 Manholes 4-FT Diameter	5.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20240409001 Project(s): 1010-10-82

Federal ID(s): WISC 2024324

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0348	611.2005 Manholes 5-FT Diameter	2.000 EACH	_____.	_____.
0350	611.2006 Manholes 6-FT Diameter	1.000 EACH	_____.	_____.
0352	611.3004 Inlets 4-FT Diameter	5.000 EACH	_____.	_____.
0354	611.3220 Inlets 2x2-FT	6.000 EACH	_____.	_____.
0356	611.3230 Inlets 2x3-FT	13.000 EACH	_____.	_____.
0358	611.3901 Inlets Median 1 Grate	4.000 EACH	_____.	_____.
0360	611.3902 Inlets Median 2 Grate	14.000 EACH	_____.	_____.
0362	611.8120.S Cover Plates Temporary	2.000 EACH	_____.	_____.
0364	612.0206 Pipe Underdrain Unperforated 6-Inch	300.000 LF	_____.	_____.
0366	612.0406 Pipe Underdrain Wrapped 6-Inch	10,130.000 LF	_____.	_____.
0368	612.0806 Apron Endwalls for Underdrain Reinforced Concrete 6-Inch	12.000 EACH	_____.	_____.
0370	614.0150 Anchor Assemblies for Steel Plate Beam Guard	15.000 EACH	_____.	_____.
0372	614.0220 Steel Thrie Beam Bullnose Terminal	4.000 EACH	_____.	_____.
0374	614.0230 Steel Thrie Beam	154.000 LF	_____.	_____.
0376	614.0397 Guardrail Mow Strip Emulsified Asphalt	3,415.000 SY	_____.	_____.
0378	614.0905 Crash Cushions Temporary	24.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20240409001 Project(s): 1010-10-82

Federal ID(s): WISC 2024324

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0380	614.0920 Salvaged Rail	2,303.000 LF	_____.	_____.
0382	614.0925 Salvaged Guardrail End Treatments	8.000 EACH	_____.	_____.
0384	614.2300 MGS Guardrail 3	4,779.000 LF	_____.	_____.
0386	614.2330 MGS Guardrail 3 K	75.000 LF	_____.	_____.
0388	614.2500 MGS Thrie Beam Transition	1,080.000 LF	_____.	_____.
0390	614.2610 MGS Guardrail Terminal EAT	19.000 EACH	_____.	_____.
0392	614.2620 MGS Guardrail Terminal Type 2	7.000 EACH	_____.	_____.
0394	616.0100 Fence Woven Wire (height) 01. 4-ft	17,340.000 LF	_____.	_____.
0396	616.0206 Fence Chain Link 6-FT	881.000 LF	_____.	_____.
0398	616.0700.S Fence Safety	17,820.000 LF	_____.	_____.
0400	618.0100 Maintenance and Repair of Haul Roads (project) 01. 1010-10-82	1.000 EACH	_____.	_____.
0402	619.1000 Mobilization	1.000 EACH	_____.	_____.
0404	623.0200 Dust Control Surface Treatment	143,890.000 SY	_____.	_____.
0406	624.0100 Water	1,488.000 MGAL	_____.	_____.
0408	625.0100 Topsoil	73,393.000 SY	_____.	_____.
0410	625.0500 Salvaged Topsoil	163,062.000 SY	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20240409001 Project(s): 1010-10-82

Federal ID(s): WISC 2024324

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0412	627.0200 Mulching	29,269.000 SY	_____.	_____.
0414	628.1504 Silt Fence	17,845.000 LF	_____.	_____.
0416	628.1520 Silt Fence Maintenance	42,564.000 LF	_____.	_____.
0418	628.1530.S Silt Fence Heavy Duty	8,433.000 LF	_____.	_____.
0420	628.1535.S Silt Fence Heavy Duty Maintenance	22,230.000 LF	_____.	_____.
0422	628.1905 Mobilizations Erosion Control	57.000 EACH	_____.	_____.
0424	628.1910 Mobilizations Emergency Erosion Control	30.000 EACH	_____.	_____.
0426	628.2002 Erosion Mat Class I Type A	113,465.000 SY	_____.	_____.
0428	628.2004 Erosion Mat Class I Type B	81,771.000 SY	_____.	_____.
0430	628.2008 Erosion Mat Urban Class I Type B	12,782.000 SY	_____.	_____.
0432	628.5505 Polyethylene Sheeting	310.000 SY	_____.	_____.
0434	628.6510 Soil Stabilizer Type B	2.000 ACRE	_____.	_____.
0436	628.7005 Inlet Protection Type A	69.000 EACH	_____.	_____.
0438	628.7010 Inlet Protection Type B	124.000 EACH	_____.	_____.
0440	628.7015 Inlet Protection Type C	33.000 EACH	_____.	_____.
0442	628.7504 Temporary Ditch Checks	2,490.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20240409001 Project(s): 1010-10-82

Federal ID(s): WISC 2024324

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0444	628.7555 Culvert Pipe Checks	118.000 EACH	_____.	_____.
0446	628.7560 Tracking Pads	8.000 EACH	_____.	_____.
0448	628.7570 Rock Bags	1,126.000 EACH	_____.	_____.
0450	629.0210 Fertilizer Type B	163.000 CWT	_____.	_____.
0452	630.0130 Seeding Mixture No. 30	3,207.000 LB	_____.	_____.
0454	630.0180 Seeding Mixture No. 80	13.000 LB	_____.	_____.
0456	630.0200 Seeding Temporary	6,113.000 LB	_____.	_____.
0458	630.0300 Seeding Borrow Pit	470.000 LB	_____.	_____.
0460	630.0500 Seed Water	4,084.000 MGAL	_____.	_____.
0462	632.0201 Shrubs (species, root, size) 01. Species 1, Bare Root Stock (BR), 12" - 18"	3,138.000 EACH	_____.	_____.
0464	632.9101 Landscape Planting Surveillance and Care Cycles	30.000 EACH	_____.	_____.
0466	633.0100 Delineator Posts Steel	50.000 EACH	_____.	_____.
0468	633.0200 Delineators Flexible	225.000 EACH	_____.	_____.
0470	633.0500 Delineator Reflectors	66.000 EACH	_____.	_____.
0472	633.1000 Delineators Barrier Wall	133.000 EACH	_____.	_____.
0474	633.5100 Markers ROW	27.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20240409001 Project(s): 1010-10-82

Federal ID(s): WISC 2024324

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0476	633.5200 Markers Culvert End	13.000 EACH	_____.	_____.
0478	634.0616 Posts Wood 4x6-Inch X 16-FT	49.000 EACH	_____.	_____.
0480	634.0618 Posts Wood 4x6-Inch X 18-FT	17.000 EACH	_____.	_____.
0482	634.0620 Posts Wood 4x6-Inch X 20-FT	9.000 EACH	_____.	_____.
0484	635.0200 Sign Supports Structural Steel HS	1,635.000 LB	_____.	_____.
0486	636.0050.S Foundation Drilling (diameter) 01. 36-Inch Diameter	5,010.000 LF	_____.	_____.
0488	637.2210 Signs Type II Reflective H	571.000 SF	_____.	_____.
0490	637.2230 Signs Type II Reflective F	181.000 SF	_____.	_____.
0492	638.2101 Moving Signs Type I	5.000 EACH	_____.	_____.
0494	638.2102 Moving Signs Type II	95.000 EACH	_____.	_____.
0496	638.2602 Removing Signs Type II	61.000 EACH	_____.	_____.
0498	638.3000 Removing Small Sign Supports	65.000 EACH	_____.	_____.
0500	638.3100 Removing Structural Steel Sign Supports	6.000 EACH	_____.	_____.
0502	638.4000 Moving Small Sign Supports	101.000 EACH	_____.	_____.
0504	638.4100 Moving Structural Steel Sign Supports	2.000 EACH	_____.	_____.
0506	643.0300 Traffic Control Drums	577,529.000 DAY	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20240409001 Project(s): 1010-10-82

Federal ID(s): WISC 2024324

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0508	643.0420 Traffic Control Barricades Type III	15,470.000 DAY	_____.	_____.
0510	643.0500 Traffic Control Flexible Tubular Marker Posts	70.000 EACH	_____.	_____.
0512	643.0600 Traffic Control Flexible Tubular Marker Bases	70.000 EACH	_____.	_____.
0514	643.0705 Traffic Control Warning Lights Type A	30,940.000 DAY	_____.	_____.
0516	643.0715 Traffic Control Warning Lights Type C	80,739.000 DAY	_____.	_____.
0518	643.0800 Traffic Control Arrow Boards	685.000 DAY	_____.	_____.
0520	643.0900 Traffic Control Signs	82,785.000 DAY	_____.	_____.
0522	643.0920 Traffic Control Covering Signs Type II	50.000 EACH	_____.	_____.
0524	643.1000 Traffic Control Signs Fixed Message	263.250 SF	_____.	_____.
0526	643.1050 Traffic Control Signs PCMS	280.000 DAY	_____.	_____.
0528	643.1051 Traffic Control Signs PCMS with Cellular Communications	2,500.000 DAY	_____.	_____.
0530	643.1055.S Truck or Trailer Mounted Attenuator	100.000 DAY	_____.	_____.
0532	643.1200.S Portable Automated Real-Time Traffic Queue Warning System	2,500.000 DAY	_____.	_____.
0534	643.3165 Temporary Marking Line Paint 6-Inch	35,850.000 LF	_____.	_____.
0536	643.3170 Temporary Marking Line Epoxy 6-Inch	209,020.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20240409001 Project(s): 1010-10-82

Federal ID(s): WISC 2024324

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0538	643.3180 Temporary Marking Line Removable Tape 6-Inch	10,000.000 LF	_____.	_____.
0540	643.3760 Temporary Marking Raised Pavement Marker Type I	2,000.000 EACH	_____.	_____.
0542	643.4100 Traffic Control Interim Lane Closure	98.000 EACH	_____.	_____.
0544	643.5000 Traffic Control	1.000 EACH	_____.	_____.
0546	645.0111 Geotextile Type DF Schedule A	4,792.000 SY	_____.	_____.
0548	645.0120 Geotextile Type HR	3,233.000 SY	_____.	_____.
0550	645.0220 Geogrid Type SR	6,330.000 SY	_____.	_____.
0552	646.1020 Marking Line Epoxy 4-Inch	18,380.000 LF	_____.	_____.
0554	646.2020 Marking Line Epoxy 6-Inch	9,360.000 LF	_____.	_____.
0556	646.2025 Marking Line Grooved Black Epoxy 6-Inch	11,370.000 LF	_____.	_____.
0558	646.2040 Marking Line Grooved Wet Ref Epoxy 6-Inch	45,450.000 LF	_____.	_____.
0560	646.2050 Marking Line Grooved Permanent Tape 6-Inch	11,370.000 LF	_____.	_____.
0562	646.5520 Marking Outfall Epoxy	12.000 EACH	_____.	_____.
0564	646.6120 Marking Stop Line Epoxy 18-Inch	66.000 LF	_____.	_____.
0566	646.9000 Marking Removal Line 4-Inch	52,110.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20240409001 Project(s): 1010-10-82

Federal ID(s): WISC 2024324

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0568	646.9010 Marking Removal Line Water Blasting 4-Inch	8,460.000 LF	_____.	_____.
0570	646.9050 Marking Removal Line Grooved Permanent Tape 4-Inch	4,980.000 LF	_____.	_____.
0572	650.4000 Construction Staking Storm Sewer	78.000 EACH	_____.	_____.
0574	650.4500 Construction Staking Subgrade	37,303.000 LF	_____.	_____.
0576	650.5000 Construction Staking Base	22,770.000 LF	_____.	_____.
0578	650.5500 Construction Staking Curb Gutter and Curb & Gutter	998.000 LF	_____.	_____.
0580	650.6000 Construction Staking Pipe Culverts	11.000 EACH	_____.	_____.
0582	650.6501 Construction Staking Structure Layout (structure) 01. B-11-184	1.000 EACH	_____.	_____.
0584	650.6501 Construction Staking Structure Layout (structure) 02. B-11-183	1.000 EACH	_____.	_____.
0586	650.6501 Construction Staking Structure Layout (structure) 03. B-11-182	1.000 EACH	_____.	_____.
0588	650.6501 Construction Staking Structure Layout (structure) 04. R-11-44	1.000 EACH	_____.	_____.
0590	650.6501 Construction Staking Structure Layout (structure) 05. R-11-45	1.000 EACH	_____.	_____.
0592	650.6501 Construction Staking Structure Layout (structure) 06. B-11-185	1.000 EACH	_____.	_____.
0594	650.6501 Construction Staking Structure Layout (structure) 07. R-11-46	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20240409001 Project(s): 1010-10-82

Federal ID(s): WISC 2024324

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0596	650.6501 Construction Staking Structure Layout (structure) 08. R-11-47	1.000 EACH	_____.	_____.
0598	650.6501 Construction Staking Structure Layout (structure) 09. R-11-48	1.000 EACH	_____.	_____.
0600	650.6501 Construction Staking Structure Layout (structure) 10. C-11-11	1.000 EACH	_____.	_____.
0602	650.7000 Construction Staking Concrete Pavement	14,933.000 LF	_____.	_____.
0604	650.7500 Construction Staking Concrete Barrier	332.000 LF	_____.	_____.
0606	650.8000 Construction Staking Resurfacing Reference	9,567.000 LF	_____.	_____.
0608	650.9911 Construction Staking Supplemental Control (project) 01. 1010-10-82	1.000 EACH	_____.	_____.
0610	650.9920 Construction Staking Slope Stakes	37,303.000 LF	_____.	_____.
0612	652.0125 Conduit Rigid Metallic 2-Inch	90.000 LF	_____.	_____.
0614	652.0225 Conduit Rigid Nonmetallic Schedule 40 2-Inch	1,530.000 LF	_____.	_____.
0616	652.0605 Conduit Special 2-Inch	490.000 LF	_____.	_____.
0618	652.0700.S Install Conduit into Existing Item	1.000 EACH	_____.	_____.
0620	653.0140 Pull Boxes Steel 24x42-Inch	7.000 EACH	_____.	_____.
0622	653.0905 Removing Pull Boxes	10.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20240409001 Project(s): 1010-10-82

Federal ID(s): WISC 2024324

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0624	654.0105 Concrete Bases Type 5	1.000 EACH	_____.	_____.
0626	655.0515 Electrical Wire Traffic Signals 10 AWG	135.000 LF	_____.	_____.
0628	655.0625 Electrical Wire Lighting 6 AWG	1,635.000 LF	_____.	_____.
0630	655.0635 Electrical Wire Lighting 2 AWG	4,720.000 LF	_____.	_____.
0632	656.0201 Electrical Service Meter Breaker Pedestal (location) 50. MBDMS110060	1.000 EACH	_____.	_____.
0634	656.0201 Electrical Service Meter Breaker Pedestal (location) 51. MBCCTV110024	1.000 EACH	_____.	_____.
0636	656.0201 Electrical Service Meter Breaker Pedestal (location) 52. MBDMS110057	1.000 EACH	_____.	_____.
0638	670.0101 Field System Integrator	1.000 EACH	_____.	_____.
0640	670.0201 ITS Documentation	1.000 EACH	_____.	_____.
0642	673.1225.S Install Pole Mounted Cabinet	3.000 EACH	_____.	_____.
0644	674.0300 Remove Cable	1,605.000 LF	_____.	_____.
0646	674.0400 Reinstall Cable	145.000 LF	_____.	_____.
0648	677.0150 Install Camera Pole 50-FT	1.000 EACH	_____.	_____.
0650	677.0200 Install Camera Assembly	1.000 EACH	_____.	_____.
0652	677.9051.S Removing 50-FT Camera Pole	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20240409001 Project(s): 1010-10-82

Federal ID(s): WISC 2024324

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0654	677.9200.S Removing CCTV Camera	1.000 EACH	_____.	_____.
0656	678.0006 Install Fiber Optic Cable Outdoor Plant 6-CT	135.000 LF	_____.	_____.
0658	678.0200 Fiber Optic Splice Enclosure	1.000 EACH	_____.	_____.
0660	678.0300 Fiber Optic Splice	4.000 EACH	_____.	_____.
0662	678.0400 Fiber Optic Termination	6.000 EACH	_____.	_____.
0664	678.0501 Communication System Testing	1.000 EACH	_____.	_____.
0666	678.0600 Install Ethernet Switches	2.000 EACH	_____.	_____.
0668	690.0150 Sawing Asphalt	14,411.000 LF	_____.	_____.
0670	690.0250 Sawing Concrete	9,594.000 LF	_____.	_____.
0672	715.0502 Incentive Strength Concrete Structures	174,548.000 DOL	1.00000	174,548.00
0674	715.0603 Incentive Strength Concrete Barrier	3,412.000 DOL	1.00000	3,412.00
0676	715.0715 Incentive Flexural Strength Concrete Pavement	35,622.000 DOL	1.00000	35,622.00
0678	740.0440 Incentive IRI Ride	33,240.000 DOL	1.00000	33,240.00
0680	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	4,000.000 HRS	5.00000	20,000.00
0682	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	2,750.000 HRS	5.00000	13,750.00



Proposal Schedule of Items

Proposal ID: 20240409001 Project(s): 1010-10-82

Federal ID(s): WISC 2024324

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0684	SPV.0035 Special 01. High Performance Concrete (HPC) Masonry Structures	13,044.000 CY	_____.	_____.
0686	SPV.0035 Special 02. Concrete Masonry Soldier Pile Footings	780.000 CY	_____.	_____.
0688	SPV.0045 Special 01. Digital Speed Reduction System (DSRS)	2,500.000 DAY	_____.	_____.
0690	SPV.0060 Special 01. Temporary Concrete Barrier Gate	5.000 EACH	_____.	_____.
0692	SPV.0060 Special 02. Pile Dynamic Analyzer (PDA) Testing	8.000 EACH	_____.	_____.
0694	SPV.0060 Special 03. Pile Dynamic Analyzer (PDA) Restrikes	8.000 EACH	_____.	_____.
0696	SPV.0060 Special 04. Case Pile Wave Analysis Program (CAPWAP) Evaluation	4.000 EACH	_____.	_____.
0698	SPV.0060 Special 05. Utility Line Opening (ULO)	25.000 EACH	_____.	_____.
0700	SPV.0060 Special 06. Access Gate 6-Foot	9.000 EACH	_____.	_____.
0702	SPV.0060 Special 07. Tieback Anchors	184.000 EACH	_____.	_____.
0704	SPV.0060 Special 08. Tieback Anchor Performance Tests	10.000 EACH	_____.	_____.
0706	SPV.0060 Special 09. Crosshole Sonic Log (CSL) Testing, Wall Secant Pile 59.06-Inch	11.000 EACH	_____.	_____.
0708	SPV.0060 Special 10. Crosshole Sonic Log (CSL) Testing, Drilled Shaft Foundation 59.06-Inch	124.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20240409001 Project(s): 1010-10-82

Federal ID(s): WISC 2024324

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0710	SPV.0060 Special 11. Thermal Integrity Profiler (TIP) Testing, Wall Secant Pile 59.06-Inch	11.000 EACH	_____.	_____.
0712	SPV.0060 Special 12. Thermal Integrity Profiler (TIP) Testing, Drilled Shaft 59.06-Inch	124.000 EACH	_____.	_____.
0714	SPV.0060 Special 13. Bar Couplers No. 18	159.000 EACH	_____.	_____.
0716	SPV.0060 Special 14. Pipe Connection to Existing Structure	4.000 EACH	_____.	_____.
0718	SPV.0060 Special 15. Remove, Salvage, and Reinstall Barricade Rack	1.000 EACH	_____.	_____.
0720	SPV.0060 Special 16. Emergency Response to Pavement Repairs	15.000 EACH	_____.	_____.
0722	SPV.0060 Special 17. Emergency Response to Traffic Incident Involving Concrete Barrier Temporary	15.000 EACH	_____.	_____.
0724	SPV.0060 Special 18. Emergency Response to Traffic Incident Involving Crash Cushion	8.000 EACH	_____.	_____.
0726	SPV.0060 Special 19. Emergency Response to Traffic Incident Involving Guardrail or EAT	10.000 EACH	_____.	_____.
0728	SPV.0060 Special 20. Repair State Owned Energy Absorbing Terminal (EAT)	5.000 EACH	_____.	_____.
0730	SPV.0060 Special 21. Research and Locate Existing Land Parcel Monuments	10.000 EACH	_____.	_____.
0732	SPV.0060 Special 22. Verify and Replace Existing Land Parcel Monuments	10.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20240409001 Project(s): 1010-10-82

Federal ID(s): WISC 2024324

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0734	SPV.0060 Special 23. Winter Shoulder Maintenance	10.000 EACH	_____.	_____.
0736	SPV.0060 Special 24. Cofferdams B-11-184 Pier 12	1.000 EACH	_____.	_____.
0738	SPV.0060 Special 25. Underwater Scour Monitoring	10.000 EACH	_____.	_____.
0740	SPV.0060 Special 26. Shaft Inspection Device (SID) Testing, Trial Drilled Shaft 59.06-Inch	4.000 EACH	_____.	_____.
0742	SPV.0060 Special 27. Shaft Inspection Device (SID) Testing, Drilled Shaft 59.06-Inch	120.000 EACH	_____.	_____.
0744	SPV.0060 Special 28. Geotechnical Borings, Equipment Mobilization	2.000 EACH	_____.	_____.
0746	SPV.0060 Special 29. Rock Unconfined Compressive Strength Testing	80.000 EACH	_____.	_____.
0748	SPV.0060 Special 30. Trial Drilled Shaft Foundation 59.06-Inch	4.000 EACH	_____.	_____.
0750	SPV.0060 Special 31. Temporary Sediment Traps	20.000 EACH	_____.	_____.
0752	SPV.0060 Special 32. Temporary Access for Wisconsin River Structure Construction and Demolition	1.000 EACH	_____.	_____.
0754	SPV.0060 Special 51. Removing Controller Cabinet	1.000 EACH	_____.	_____.
0756	SPV.0060 Special 52. Removing Controller Cabinet Base	1.000 EACH	_____.	_____.
0758	SPV.0060 Special 53. Removing Electrical Service Meter Breaker Pedestal	3.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20240409001 Project(s): 1010-10-82

Federal ID(s): WISC 2024324

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0760	SPV.0060 Special 54. Salvage Structural Steel Sign Support Stubs	2.000 EACH	_____.	_____.
0762	SPV.0060 Special 55. Salvage Hybrid DMS Assembly	1.000 EACH	_____.	_____.
0764	SPV.0060 Special 56. Ground Rod	3.000 EACH	_____.	_____.
0766	SPV.0060 Special 57. Install Salvaged Pole	1.000 EACH	_____.	_____.
0768	SPV.0060 Special 58. Install Salvaged Steel Sign Support Stub	2.000 EACH	_____.	_____.
0770	SPV.0060 Special 59. Install Ethernet Radio	2.000 EACH	_____.	_____.
0772	SPV.0060 Special 60. Temporary Poles Wood 40-Foot	1.000 EACH	_____.	_____.
0774	SPV.0060 Special 61. Install Solar Power System Assembly	1.000 EACH	_____.	_____.
0776	SPV.0060 Special 62. Install Hybrid Dynamic Message Sign	2.000 EACH	_____.	_____.
0778	SPV.0075 Special 01. Obstructions Wall Secant Pile	6.000 HRS	_____.	_____.
0780	SPV.0075 Special 02. Obstructions Foundation Drilling	56.000 HRS	_____.	_____.
0782	SPV.0075 Special 03. Obstructions Drilled Shaft Foundation	60.000 HRS	_____.	_____.
0784	SPV.0075 Special 04. Obstructions Rigid Inclusion System	5.000 HRS	_____.	_____.
0786	SPV.0085 Special 01. Seeding Mixture Wetland	382.000 LB	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20240409001 Project(s): 1010-10-82

Federal ID(s): WISC 2024324

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0788	SPV.0090 Special 01. Removing Asphaltic Rumble Strips	33,090.000 LF	_____.	_____.
0790	SPV.0090 Special 02. Removing Concrete Rumble Strips	4,055.000 LF	_____.	_____.
0792	SPV.0090 Special 03. Traffic Control Gawk Screen Furnished	21,813.000 LF	_____.	_____.
0794	SPV.0090 Special 04. Traffic Control Gawk Screen Installed	28,175.000 LF	_____.	_____.
0796	SPV.0090 Special 05. Traffic Control Glare Screen Furnished	15,305.000 LF	_____.	_____.
0798	SPV.0090 Special 06. Traffic Control Glare Screen Installed	15,305.000 LF	_____.	_____.
0800	SPV.0090 Special 07. Wall Secant Pile 59.06-Inch	693.000 LF	_____.	_____.
0802	SPV.0090 Special 08. Piling Steel HP 14-Inch X 89 Lb	4,960.000 LF	_____.	_____.
0804	SPV.0090 Special 09. Temporary Snow Fence	4,181.000 LF	_____.	_____.
0806	SPV.0090 Special 10. Bore and Jack Culvert Pipe Reinforced Concrete Class IV 42-Inch	76.000 LF	_____.	_____.
0808	SPV.0090 Special 11. Repair State Owned Guardrail	125.000 LF	_____.	_____.
0810	SPV.0090 Special 12. Drilled Shaft Foundation 59.06-Inch	13,200.000 LF	_____.	_____.
0812	SPV.0090 Special 13. Geotechnical Boring, Soil Drilling 0-50 feet	980.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20240409001 Project(s): 1010-10-82

Federal ID(s): WISC 2024324

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0814	SPV.0090 Special 14. Geotechnical Boring, Soil Drilling 51-100 feet	460.000 LF	_____.	_____.
0816	SPV.0090 Special 15. Geotechnical Boring, Soil Drilling 101-150 feet	160.000 LF	_____.	_____.
0818	SPV.0090 Special 16. Geotechnical Boring, Rock Coring 0-50 feet	20.000 LF	_____.	_____.
0820	SPV.0090 Special 17. Geotechnical Boring, Rock Coring 51-100 feet	520.000 LF	_____.	_____.
0822	SPV.0090 Special 18. Geotechnical Boring, Rock Coring 101-150 feet	300.000 LF	_____.	_____.
0824	SPV.0090 Special 19. Geotechnical Boring, Rock Coring 151-200 feet	160.000 LF	_____.	_____.
0826	SPV.0110 Special 01. Timber Lagging	93.000 MBM	_____.	_____.
0828	SPV.0135 Special 01. Field Office Special	45.000 MON	_____.	_____.
0830	SPV.0165 Special 01. Longitudinal Grooving Bridge Deck	162,846.000 SF	_____.	_____.
0832	SPV.0165 Special 02. Wall Concrete Panel Mechanically Stabilized Earth R-11-44	1,386.000 SF	_____.	_____.
0834	SPV.0165 Special 03. Wall Concrete Panel Mechanically Stabilized Earth R-11-45	1,473.000 SF	_____.	_____.
0836	SPV.0165 Special 04. Wall Concrete Panel Mechanically Stabilized Earth R-11-46	2,067.000 SF	_____.	_____.
0838	SPV.0165 Special 05. Wall Concrete Panel Mechanically Stabilized Earth R-11-47	2,059.000 SF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20240409001 Project(s): 1010-10-82

Federal ID(s): WISC 2024324

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0840	SPV.0165 Special 06. Temporary Wall Wire Faced Mechanically Stabilized Earth	1,250.000 SF	_____.	_____.
0842	SPV.0165 Special 07. Geocomposite Drain Board	13,540.000 SF	_____.	_____.
0844	SPV.0165 Special 08. Geocomposite Wall Drain	210.000 SF	_____.	_____.
0846	SPV.0165 Special 09. Ground Improvement Rigid Inclusion System	61,305.000 SF	_____.	_____.
0848	SPV.0180 Special 01. Concrete Pavement 12-Inch Special	118,740.000 SY	_____.	_____.
Section: 0001			Total:	_____.
			Total Bid:	_____.

