



## Wisconsin Department of Transportation

---

April 24, 2024

**Division of Transportation Systems  
Development**

Bureau of Project Development  
4802 Sheboygan Avenue, Rm 601  
P O Box 7916  
Madison, WI 53707-7916

Telephone: (608) 266-1631  
Facsimile (FAX): (608) 266-8459

### NOTICE TO ALL CONTRACTORS:

**Proposal #16: 1146-75-81**  
**STH 76 - New London**  
**CTH JJ - CTH T/Givens Rd**  
**STH 15**  
**Outagamie County**

### Letting of May 14, 2024

This is Addendum No. 01, which provides for the following:

#### Special Provisions:

Revised Special Provisions	
Article No.	Description
14	Engineered Soils, Item SPV.0035.01
15	Salt Storage Facility, Item SPV.0060.01

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

*Mike Coleman*

Proposal Development Specialist  
Proposal Management Section

**ADDENDUM NO. 01**

**1146-75-81**

**April 24, 2024**

**Special Provisions**

**14. Engineered Soils, Item SPV.0035.01.**

*Replace (2) under section titled **B Materials** with the following:*

- (2) Provide sand meeting the gradation requirements of USDA Coarse sand (0.02-0.04 inches) or ASTM C33 (fine aggregate concrete sand). Provide sand consisting of mineral sand that is at least 97% SiO<sub>2</sub>. Substitutions, such as calcium carbonated sand or dolomitic sand may also be used. Manufactured sand or stone dust will not be allowed. Wash the sand to remove clay and silt particles, and well drain prior to mixing.

**15. Salt Storage Facility, Item SPV.0060.01.**

*Replace paragraph e. under subsection titled G. Building Walls under section titled **PART 3 – DESIGN CRITERIA & PRODUCTS** with the following:*

- e. Design the walls to resist a salt and sand load of 80 pounds per cubic foot and to resist a horizontal impact load from a loader.

END OF ADDENDUM