



Wisconsin Department of Transportation

January 6, 2025

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631

Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #01: 1204-08-73, WISC 2025145
Mount Horeb - Madison
CTH G to West Verona Ave/Epic Ln
USH 18
Dane County

1204-08-74, WISC 2025146
Mount Horeb - Madison
West Verona Ave/Epic Ln to STH 69
USH 18
Dane County

Letting of January 14, 2025

This is Addendum No. 01, which provides for the following:

Special Provisions:

Added Special Provisions	
Article No.	Description
55	Removing Polymer Overlay B-13-0052, Item 509.9015.S.01
56	Removing Polymer Overlay B-13-0383, Item 509.9015.S.02

Schedule of Items:

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Quantity Added	Proposal Total After Addendum
509.9015.S	Removing Polymer Overlay B-13-0052	SY	0	930	930
509.9015.S	Removing Polymer Overlay B-13-0383	SY	0	880	880

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
571	Revised page to add bid item 509.9015.S for B-13-0052.
596	Revised page to add bid item 509.9015.S for B-13-0383.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01
1204-08-73, 1204-08-74
January 6, 2025

Special Provisions

55. Removing Polymer Overlay B-13-0052, Item 509.9015.S.01.

A Description

This special provision describes removing the polymer overlay. Perform work conforming to standard spec 204.

B (Vacant)

C Construction

Remove the overlay by scraping, grinding, milling, or other approved method without damaging the underlying concrete. Submit removal procedures to the engineer for approval before beginning. Do not remove more than 1/4" of the existing concrete surface. Leave a uniform textured finish over the entire concrete surface.

D Measurement

The department will measure Removing Polymer Overlay B-13-0052 by the square yard, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
509.9015.S	Removing Polymer Overlay B-13-0052	SY

Payment for is full compensation for removing the polymer; and for properly disposing of all materials.
stp-509-015 (20210113)

56. Removing Polymer Overlay B-13-0383, Item 509.9015.S.02.

A Description

This special provision describes removing the polymer overlay. Perform work conforming to standard spec 204.

B (Vacant)

C Construction

Remove the overlay by scraping, grinding, milling, or other approved method without damaging the underlying concrete. Submit removal procedures to the engineer for approval before beginning. Do not remove more than 1/4" of the existing concrete surface. Leave a uniform textured finish over the entire concrete surface.

D Measurement

The department will measure Removing Polymer Overlay B-13-0383 by the square yard, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
509.9015.S	Removing Polymer Overlay B-13-0383	SY
Payment for is full compensation for removing the polymer; and for properly disposing of all materials. stp-509-015 (20210113)		

Schedule of Items

Attached, dated January 6, 2025, are the revised Schedule of Items Page 24.

Plan Sheets


The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:
Revised: 571 and 596.

END OF ADDENDUM

TOTAL ESTIMATED QUANTITIES


BID ITEM NUMBER	BID ITEM DESCRIPTION	UNIT	WEST ABUTMENT	PIER 1	PIER 2	EAST ABUTMENT	SUPER	TOTALS
203.0200	REMOVING STRUCTURE OVER WATERWAY MINIMAL DEBRIS B-13-0052	EACH	—	—	—	—	—	1
206.0001	EXCAVATION FOR STRUCTURES BRIDGES B-13-0052	EACH	—	—	—	—	—	1
206.0001	COFFERDAMS B-13-0052	EACH	—	—	—	—	—	1
210.1500	BACKFILL STRUCTURE TYPE A	TON	64	117	117	65	—	363
502.0100	CONCRETE MASONRY BRIDGES	CY	25	20	20	25	89	178
502.0100	CONCRETE MASONRY SEAL	CY	—	—	—	—	—	50
502.3101	EXPANSION DEVICE	LF	18	—	—	18	—	36
502.3200	PROTECTIVE SURFACE TREATMENT	SY	—	—	—	—	310	310
502.3205	PIGMENTED SURFACE SEALER RESEAL	SY	5	—	—	5	64	74
502.3210	PIGMENTED SURFACE SEALER	SY	6	—	—	6	79	91
502.4204	ADHESIVE ANCHORS NO. 4 BAR	EACH	—	—	—	—	—	8
502.4205	ADHESIVE ANCHORS NO. 5 BAR	EACH	—	—	—	—	—	12
502.4206	ADHESIVE ANCHORS NO. 6 BAR	EACH	—	—	—	—	—	28
505.0400	BAR STEEL REINFORCEMENT HS STRUCTURES	LB	850	835	835	850	—	3,370
505.0400	BAR STEEL REINFORCEMENT HS COATED STRUCTURES	LB	1,100	1,895	1,895	1,090	25,210	31,190
506.0105	STRUCTURAL STEEL CARBON	LB	—	—	—	—	5,670	5,670
506.0605	STRUCTURAL STEEL HS	LB	—	—	—	—	37,520	37,520
506.0915	WELDED STUD SHEAR CONNECTORS 7/8X6 INCH	EACH	—	—	—	—	—	1,422
506.5000	BEARING ASSEMBLIES FIXED B-13-0052	EACH	—	—	—	—	—	2
506.5000	BEARING ASSEMBLIES EXPANSION B-13-0052	EACH	—	—	—	—	—	6
509.1500	CONCRETE SURFACE REPAIR	SF	7	—	—	—	—	7
509.5100 S	POLYMER OVERLAY	SY	—	—	—	—	930	930
509.5100 S	REMOVING POLYMER OVERLAY B-13-0052	SY	—	—	—	—	930	930
511.1200	TEMPORARY SHORING B-13-0052	SF	117	—	—	117	—	234
516.6000	RUBBERIZED MEMBRANE WATERPROOFING	SY	5	—	—	5	—	10
517.6001	PAINTING EPOXY SYSTEM B-13-0052	EACH	—	—	—	—	—	1
517.6001 S.001	PREPARATIONS AND COATING OF TOP FLANGES B-13-0052	EACH	—	—	—	—	—	900
530.1100	PAINTING STEEL HP 10X10X42 LB	LF	450	—	—	450	—	900
530.1140	PAINTING STEEL HP 14X10X43 LB	CY	110	485	485	—	—	980
600.0000	REPAIR REPAIR	LF	29	80	90	29	—	380
612.0405	PPE UNDERDRUM WRAPPED GINCH	LF	—	—	—	—	—	58
614.0150	ANCHOR ASSEMBLIES FOR STEEL PLATE BEAM GUARD	EACH	9	—	—	—	—	2
645.0111	GEOTEXTILE TYPE DP SCHEDULE A	SY	—	—	—	—	—	18
645.0120	GEOTEXTILE TYPE HR	SY	170	130	130	160	—	590
SPV.0000.302	CLEANING AND PAINTING BEARINGS	EACH	—	—	—	—	—	12
SPV.0000.303	TEMPORARY SUPPORT B-13-0052	EACH	—	—	—	—	—	1
SPV.0000.301	STRIP SEAL GLAND REPLACEMENT	LF	35	—	—	35	—	70
FILLER	NON-BID ITEMS	SIZE	—	—	—	—	—	1/2"

* CLEAN AND PAINT GIRDER BEARINGS AT ABUTMENTS AND PIERS AS DIRECTED BY FIELD ENGINEER.



SECTION THRU ABUTMENT
TRANSITIONAL AREA ON DECK
AT EXPANSION JOINT
(REMOVAL AND OVERLAY THICKNESS NOT TO SCALE)

01/02/25



Addendum No. 01
ID 1204-08-73
Revised Sheet 571
January 6, 2023

12/31/24	ADDED BID ITEM	MES
NO.	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION		
STRUCTURE B-13-52		
DESIGNED BY	DRAWN BY	SRA
SHEET 3 OF 25		
QUANTITIES		
571		

SCALE =


STATE PROJECT NUMBER

1204-08-73


TOTAL ESTIMATED QUANTITIES

BID ITEM NUMBER	BID ITEM	UNIT	WEST ABUTMENT	PIER 1	PIER 2	EAST ABUTMENT	SUPER	TOTALS
203.0200	REMOVING STRUCTURE OVER WATERWAY MINIMAL DEBRIS B-13-0383	EACH	---	---	---	---	---	1
206.1001	EXCAVATION FOR STRUCTURES BRIDGES B-13-0383	EACH	---	---	---	---	---	1
206.5001	COFFERDAMS B-13-0383	EACH	---	---	---	---	---	1
210.1500	BACKFILL STRUCTURE TYPE A	TON	75	117	117	70	---	379
502.0100	CONCRETE MASONRY BRIDGES	CY	19	21	21	19	97	177
502.1100	CONCRETE MASONRY SEAL	CY	---	25	25	---	---	50
502.3200	PROTECTIVE SURFACE TREATMENT	SY	---	---	---	---	280	280
502.3205	PIGMENTED SURFACE SEALER RESEAL	SY	4	---	---	---	61	65
502.3210	PIGMENTED SURFACE SEALER	SY	6	---	---	6	75	87
502.4208	ADHESIVE ANCHORS NO. 8 BAR	EACH	---	---	---	---	---	46
505.0000	BAR STEEL REINFORCEMENT HS STRUCTURES	LB	930	835	835	930	---	3,530
505.0000	BAR STEEL REINFORCEMENT HS COATED STRUCTURES	LB	1,100	1,895	1,895	1,170	20,620	26,770
506.0105	STRUCTURAL STEEL CARBON	LB	---	---	---	---	3,470	3,470
506.0905	STRUCTURAL STEEL HS	LB	---	---	---	---	44,970	44,970
506.2005	BEARING PAUS ELASTOMERIC NON LAMINATED	EACH	---	---	---	---	---	1
506.3015	WELDED STUD SHEAR CONNECTORS 1/8"X1/4"	EACH	---	---	---	---	---	1,422
506.3000	BEARING ASSEMBLIES FIXED B-13-0383	EACH	---	---	---	---	---	4
508.1000	CONCRETE SURFACE REPAIR	SF	---	2	---	---	---	2
509.5100 S	POLYMER OVERLAY	SF	---	---	---	---	890	890
509.9015 S	REMOVING POLYMER OVERLAY B-13-0383	SF	---	---	---	---	890	890
511.1200	TEMPORARY SHORING B-13-0383	SF	180	---	---	330	---	510
517.0000	RUBBERIZED MEMBRANE WATERPROOFING	SF	7	---	---	7	---	14
550.0001 S.002	PREPARATIONS AND COATING OF TOP FLANGES B-13-0383	EACH	---	---	---	---	---	1
550.1100	PILING STEEL HP 10"X14 X 42 LB	LF	210	---	---	210	---	420
550.1140	PILING STEEL HP 14"X14 X 73 LB	LF	---	495	495	---	---	990
600.0300	RFRAP HEAVY	CY	120	100	100	90	---	410
612.0000	PIPE UNDERGRAN WRAPPED 6"X12"	LF	29	---	---	29	---	58
614.0150	ANCHOR ASSEMBLIES FOR STEEL PLATE BEAM GUARD	EACH	---	---	---	---	---	2
646.0111	GEOTEXTILE TYPE OF SCHEDULE A	SY	22	---	---	22	---	44
646.0120	GEOTEXTILE TYPE HR	SY	180	170	170	140	---	660
SPV.0000.504	TEMPORARY SUPPORT B-13-0383	EACH	---	---	---	---	---	1
	NON-BID ITEMS	SIZE	---	---	---	---	---	12'
	FILLER	---	---	---	---	---	---	---

01/02/25



Addendum No. 01
ID 1204-08-73
Revised Sheet 596
January 6, 2023



SECTION THRU ABUTMENT
TRANSITIONAL AREA ON DECK AT
SEMI-EXPANSION OR FIXED JOINT
(REMOVAL AND OVERLAY THICKNESS NOT TO SCALE)

NOTE: TRANSITIONAL AREA REQUIRED WHEN APPROACH PAVEMENT
HAS BEEN PLACED PRIOR TO OVERLAY PLACEMENT.

12/31/24	ADD'D BID ITEM	MES
NO.	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION		
STRUCTURE B-13-383		
DESIGNED BY	DRAWN BY	SRA
SHEET 3 OF 23		
QUANTITIES		596



Proposal Schedule of Items

Page 24 of 24

Proposal ID: 20250114001 Project(s): 1204-08-73, 1204-08-74

Federal ID(s): WISC 2025145, WISC 2025146

SECTION: 0001 Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0668	SPV.0090 Special 101. Salvage and Reinstall Cable Guard	4,772.000 LF	_____.	_____.
0670	SPV.0090 Special 350. Transport and Install State Furnished CAT-5E Cable	240.000 LF	_____.	_____.
0672	SPV.0090 Special 501. Strip Seal Gland Replacement	130.000 LF	_____.	_____.
0674	SPV.0090 Special 502. Grout Drilling	1,136.000 LF	_____.	_____.
0676	SPV.0195 Special 101. Limestone Screenings Path	4.000 TON	_____.	_____.
0678	509.9015.S Removing Polymer Overlay (structure) 01. B-13-0052	930.000 SY	_____.	_____.
0680	509.9015.S Removing Polymer Overlay (structure) 02. B-13-0383	880.000 SY	_____.	_____.
Section: 0001			Total:	_____.
			Total Bid:	_____.

