

Wisconsin Department of Transportation

August 28, 2025

Division of Transportation Systems Development

Bureau of Project Development 4822 Madison Yards Way, 4th Floor South Madison, WI 53705

Telephone: (608) 266-1631 Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #07: 1060-27-74, WISC 2025597

I-94 East West, Early East Leg

30th Street to 25th Street

IH 94

Milwaukee County

Letting of September 9, 2025

This is Addendum No. 02, which provides for the following:

Special Provisions:

	Revised Special Provisions
Article No.	Description
4	Prosecution and Progress.
6	Traffic.
8	Utilities.
10	Work by Others.
18	Notice to Contractor – Coordination of Electric Outages with American Transmission Company (ATC).
33	Contract Award and Execution.
208	Remove Existing Steel Piling, Item SPV.0090.4300.
216	Timber Lagging, SPV.0110.4000.
222	Temporary Wall Wire Faced Mechanically Stabilized Earth LFCF R-40-767, Item SPV.0165.4100.
223	Wall Concrete Panel Mechanically Stabilized Earth LFCF R-40-761, Item SPV.0165.4761; Wall Concrete Panel Mechanically Stabilized Earth LFCF R-40-767, Item SPV.0165.4767.

	Added Special Provisions
Article	Description
No.	Description
232	Removing Bollard, Item 204.9060.S.0002.

Schedule of Items:

	Revised Bid Item	Quantitie	S		
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Proposal Quantity Change (-)	Proposal Total After Addendum
204.0100	Removing Concrete Pavement	SY	18,770	1,000	19,770
655.0144	Cable in Duct 4-4 AWG	LF	606	176	782
SPV.0060.5201	Manholes Type TES Doghouse 4-Ft Diameter	Each	1	1	2
SPV.0060.5204	Removing CUC Manholes	Each	1	1	2
SPV.0060.5212	Adjusting TES Manhole	Each	2	-1	1
SPV.0090.1013	Cable Aerial Alum 4AWG Quadruplex Left In Place	LF	2,110	-176	1,934
SPV.0090.5001	Ductile Iron (DI) AWWA C-151 Class 55 Water Main 12-Inch	LF	34	13	47
SPV.0110.4000	Timber Lagging	MBM	10	109	119

	Added Bid Item (Quantities			
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Quantity Added	Proposal Total After Addendum
204.9060.S.0002	Removing Bollard	Each	0	2	2

Plan Sheets:

	Revised Plan Sheets
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
4	General Notes – updated utility contact information
70	Removal Plan – Added callout for Removing Bollard bid item
124	N. 27th Street Watermain – Updated location for proposed 12" water main connection and the 12"water main length, and fittings; updated the MWW Project Number.
125	W. St. Paul Avenue Watermain – Updated the hydrant fitting, MWW Project Number and Plan File Number.
204-205	Lighting Plan – Shifted Pole T-DPH1 east (station/offset updated) and updated conduit type between T-CPH1 and T-DPH2 from overhead to cable-in-duct
217	City Underground Conduit – CUC plan detail with updated construction note and updated a manhole from being adjusted to removed and replaced.
218	City Underground Conduit – CUC plan detail with revised construction notes.
367	Miscellaneous Quantity – Revised Removing Concrete Pavement quantity
369	Miscellaneous Quantity – Added table for Removing Bollard
413	Miscellaneous Quantities – Revised Temporary Left-In-Place Lighting Conduit and Cable table and STA/OFF of pole T-DPH1.
424	Miscellaneous Quantities – Revised 12" Water main quantity.
425	Miscellaneous Quantities – Revised CUC MQ sheet.
829	Structures Plan (R-40-761) – Revised Timber Lagging quantity.
846	Structures Plan (R-40-761) – Added optional construction joint note.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist Proposal Management Section

ADDENDUM NO. 02 1060-27-74 August 28, 2025

Special Provisions

4. Prosecution and Progress.

Replace paragraph 13 with the following:

Do not shift traffic into the Stage 3A configuration prior to July 6, 2026, unless approved by the engineer. The Contractor may transition westbound traffic directly from the Stage 2 configuration to the Stage 3B configuration following the completion of Stage 2 if approved by the engineer, provided that a minimum of three westbound lanes are maintained.

Replace the table under section titled **Demolition Contracts (By Others)** with the following:

Plat I.D.	Parcel Number	Site Address	Anticipated Completion Date
1060-27-21	3 & 7	2640 W. Greves Street	November 3, 2025
1060-27-21	N/A	2401 W. St. Paul Avenue	December 1, 2025
1060-27-21	2	2620 W. St. Paul Avenue	June 7, 2026

6. Traffic.

Replace paragraph 3 under section titled Freeway Lane Restrictions with the following:

Do not begin construction B-40-1083 north abutment until temporary median pavement is complete and traffic is switched as shown in stage 3 of the plans, or as approved by the engineer. Prior to implementing the lane closure shown in Stage 3A, the Contractor may proceed directly from Stage 2 configuration to Stage 3B – maintaining three lanes of IH 94 westbound traffic – to complete preparatory work necessary to support the Stage 3A lane reduction.

8. Utilities.

Replace the entire article with the following:

This contract comes under the provision of Administrative Rule Trans 220.

The utility work plan includes additional detailed information regarding the location of known discontinued, relocated, or removed utility facilities. These can be requested from the department during the bid preparation process, or from the project engineer after the contract has been awarded and executed.

Some of the utility work described below is dependent on prior work being performed by the contractor at a specific site. In such situations, provide the engineer and the affected utility a good faith notice of when the utility is to start work at the site. Provide this notice 14 to 16 calendar days in advance of when the prior work will be completed, and the site will be available to the utility owner. Follow-up with a confirmation notice to the engineer and the utility owner not less than 3 working days before the site will be ready for the utility owner to begin its work.

stp-107-065 (20240703)

Any utility facility locations (stations, offsets, elevations, depths) listed in this article are approximate. The following utilities will require work during construction:

AT&T Wisconsin has facilities located within the project limits. As part of this project, AT&T Wisconsin will relocate its existing fiber optic infrastructure using both aerial and underground methods, implemented in phases to maintain service continuity. Work will be performed in coordination with We Energies and may overlap with other utility relocation efforts.

• TEMPORARY FACILITIES

- Install new fiber optic cable from existing manhole near Evergreen Lane and S. Layton Blvd (WIS 57) to the south side of Pier 16 on existing Structure B-40-513_5 at approximately Station 20+00 KS north of Greves Street.
- Install lateral riser on north side of Pier 16 to a 4'x4'x6' manhole placed 10' north of existing Pier 16.
- Open cut and install conduit from proposed manhole to existing power pole on south side of Greves Street.
- Continue by placing aerial fiber optic cable along existing telecom poles on the south side of Greves Street easterly to N. 25th Street.
- Continue aerial fiber optic cable along existing power poles northerly on west side of N. 25th Street.
- Continue aerial fiber optic cable on existing power poles heading northwest from the intersection of W. St. Paul Avenue and N. 25th Street across IH 94 to N. 26th Street (approximately 175' north of W. St. Paul Avenue and N. 26th Street intersection).
- Continue aerial fiber optic cable on existing power poles on the east side of N. 26th Street to pole in the southwest corner of N. 26th Street and W. Clybourn Street intersection.
- Place a lateral on the last pole and enter manhole within the N. 26th Street and W. Clybourn Street intersection.
- o Splice cables.
- AT&T WI will remove existing cables from the conduits between Pier 16 and their existing manhole at the St. Paul Ave and N 27th St intersection (MH 3D61). The existing conduits underhanging the bridge will be removed by the WisDOT contractor. Conduits between the north abutment and the St. Paul Ave intersection along 27th St will be discontinued in place.
- Construction of temporary facilities is anticipated to take approximately 60 working days.
 Anticipated Start Date for Temporary Relocation: September 1, 2025.

PERMANENT FACILITIES

- Construct and remove AT&T Wisconsin facilities as shown in the plans and in the bid items for this project. Notify AT&T Wisconsin in advance of this work.
- During construction, AT&T Wisconsin to install (3) 4" conduits from 5' North of Abutment wall of Structure B-40-1083 under northbound N. 27th Street to the existing AT&T Wisconsin manhole MH 3D61 in the intersection of N. 27th Street and W. St. Paul Avenue. Elevation of conduit, 5' North of abutment, to be provided by Road Contractor. Conduit installation in roadway is anticipated to take approximately 10 working days. Notify AT&T Wisconsin when the three 4-inch conduits attached to structure B-40-1083 installation is complete and the roadway is ready for the utility to commence work.
- During construction, AT&T Wisconsin to open cut and install three 4" conduits from new manhole north of Pier 16 to a new manhole to be installed north of proposed Pier 1 of structure B-40-1083. Work is anticipated to take approximately 30 working days. Notify AT&T Wisconsin when proposed Pier 1 of structure B-40-1083 is complete and site is ready for them to begin this work.

- Prior to and during construction, AT&T Wisconsin will relocate from existing power poles in the We Energies corridor west of Greves Street into a joint trench with We Energies – Electric. Work is expected to begin in mid-October 2025 and is anticipated to take 30 working days.
- During construction, AT&T Wisconsin will adjust manholes at approximately Station 17+86 SP, 0' RT and Station 18+03 SP, 12' RT, to final grades as provided by the contractor. Each adjustment is anticipated to take 1 working day. Notify AT&T Wisconsin when the site is ready for each adjustment needed.
- After Early East Leg construction is complete, AT&T Wisconsin will pull permanent fiber through the new conduits and remove the temporary aerial facilities.

ATC Management, Inc. (ATC) has facilities within the project limits.

ATC will be performing work within the construction limits of this project concurrently and in coordination with this project to relocate existing electric transmission facilities from Zablocki Drive to the 28th Street Substation. A temporary transmission line structure will be installed south of IH 94 in overhead spans to the west of the crossing to the 28th Street substation as part of the relocation work. The location of this structure will be determined in the detailed design and will be coordinated with We Energies' facility relocations.

ATC will require a representative on-site during the installation of the retaining walls R-40-761 and R-40-767. Contact ATC to coordinate oversight. To facilitate WisDOT's construction of walls R-40-761 and R-40-767 in the Early East Leg contract, ATC's two existing 138kV lines into We Energies Greves Substation will be temporarily removed and require reinstallation. ATC requires a two-month notice and uninterrupted and unimpeded access to the work area surrounding these lines, for a week to remove the lines and another week to restore these lines. ATC retains the right to deny any outage request based on real-time system conditions, operational constraints, or load demands. The availability of any outage is not guaranteed. Single- or double-circuit outages may be requested year-round, but full triple-circuit outages are only permitted from October 1 through December 31 unless specifically approved in writing by ATC. No full circuit outages are allowed between January 1 and September 30 unless prior written approval is granted by ATC. This work affects We Energies facilities and will require joint ATC, WisDOT and We Energies coordination.

For any additional outage requests, see the "Notice to Contractor - Coordination of Electric Outages with American Transmission Company (ATC)" section of the Special Provisions for information.

During construction, ATC will adjust manhole covers to the proposed final grade within construction limits at the following locations.

- Station 11+04 J, 14' LT
- Station 11+18 J, 14' LT

Contact Jeff Vanderwerff at 262-206-4966 in advance of needing manhole adjustments.

ATC will install flowable thermal backfill and steel plates over their electric duct package crossing St. Paul Avenue at approximately Station 14+00 SP. Provide ATC's Jeff Vanderwerff at 262-206-4966 with advance notice of when the subgrade will be exposed, and the site will be available to the ATC. ATC requires 3 working days to complete this work.

ATC underground transmission facilities are located in the vicinity of storm sewer runs 200–205 and 220–215–210. Installation of these sewer runs will result in the exposure of ATC facilities. Notify Jeff Vanderwerff of ATC at (262) 206-4966 to coordinate ATC field representation during construction. ATC will support the pipe and furnish/install thermal backfill at these locations. ATC requires 10 days to procure thermal back fill and 5 days to install. Contact Jeff Vanderwerff (262) 2026-4966 in the event of or before a known disturbance.

Provide ATC a vibration mitigation plan 30 working days in advance of using vibratory or impact equipment (e.g., pile hammers, drop hammers, hydraulic breakers).

City of Milwaukee - Communications has facilities within the project limits. City forces will remove existing fiber optic cabling along the 27th Street viaduct south of the project limits and east along W. St. Paul Avenue prior to the start of construction. Anticipated Start Date: August 18, 2025. Estimated Duration for Removal Work: 10 working days

Install City of Milwaukee – Communication facilities as shown in the plans and in the bid items for this project. Upon completion of the project, the City will perform all required fiber splicing operations.

City of Milwaukee - Conduit has facilities within the project limits. Construct, remove, and adjust CUC facilities as shown in the plans and in the bid items for this project.

City of Milwaukee – Sewer has facilities within the project limits. Adjust, remove and discontinue City of Milwaukee – Sewer facilities as shown in the plans and in the bid items for this project.

City of Milwaukee – Water has facilities within the project limits. Install, remove, adjust and connect City of Milwaukee – Water facilities as shown in the plans and in the bid items for this project.

Midwest Fiber Networks LLC (MWFN) has facilities within the project limits.

Prior to construction, MWFN will relocate one pole on the south side of W. St. Paul Avenue. The south pole at Station 15+61 SP, 33' RT will be relocated 2 feet north to avoid conflict with the proposed sidewalk, and the existing guy at Station 15+61 SP, 43' RT will be replaced with a sidewalk guy. Additionally, approximately 12 feet of conduit extending from the pole to the MWFN handhole at Station 15+54 SP, 43' RT (along the fence line of the substation) will be lowered to a minimum depth of 36 inches. The handhole will be adjusted in place and downsized as needed.

During construction, MWFN will bore two (2) 1.25-inch ducts outside the project limits to tie into existing fiber and complete the gap in the I-94 FTMS system within the project limits. MWFN cannot take an outage for their facilities located within the existing FTMS ducts in the project limits. This gap work is anticipated to begin on October 1, 2025, and is scheduled to take 45 working days.

Verizon Business (MCI) has underground communications facilities within the project limits. Verizon Business (MCI) will relocate its fiber optic facilities outside the project limits during construction. The new facility route begins and terminates beyond the project limits. MCI's contractor will remove all discontinued inplace fiber from ducts once cutover to the new route is complete. Anticipated start date for MCI's relocation is October 1, 2025, and an estimated duration of 90 working days.

We Energies – Electricity has existing overhead and underground electric facilities within the project limits. We Energies will perform substantial underground conduit and manhole installation work, remove poles, and adjust manholes during construction. We Energies will also discontinue conduits and manholes during construction.

During construction, there will be relocation work, which involves converting overhead feeders (3 circuits) from the 28th Street Substation to underground facilities extending from 28th Street to the Greves Substation. The route generally follows N. 29th Street, W. Mount Vernon Avenue, N. 32nd Street, W. Park Hill Avenue, and W. Canal Street. Three VFI (Vacuum Fault Interrupter) units and riser poles will be installed at the northwest corner of N. 32nd Street and W. Canal Street. The construction schedule includes:

- Conduit and Manhole Work: 140 working days, starting no later than 10/31/2025.
- Cable Construction: 60 working days, starting no later than 3/1/2026.
- Overhead/Direct Bury Work: 100 working days, starting no later than 4/1/2026.

Work will overlap among the above three types and is scheduled to be completed by 9/1/2026. The poles, along with both We Energies and AT&T overhead lines, are anticipated to be removed by January 1st, 2027.

During construction, We Energies will adjust 17 existing manholes between Station 10+77 SP and Station 219+49 SP as described below. We Energies requires a minimum of 1 business day per adjustment. Provide advance notice of when the subgrade will be exposed, and the site will be available to We Energies to make the adjustments.

Prior to construction, steel plating (10ga, 18"–24" wide) will be installed in two locations (conduits running south from both MH 88-8011 and MH 88-8021) to protect the existing conduit found within the proposed subgrade. Installation of the steel plating is expected to take 1 (one) week per location.

Below is a summary of the locations with proposed work for We Energies' facilities.

Station No.	Pole No.	Work Proposed
409+24 EW, 129'RT	04-13288	Remove Pole
411+4 EW, 147'RT	66-1029	Remove Pole
412+11 EW, 153'RT	17-03077	Remove Pole
413+30 EW, 143'RT	15-03105	Remove Pole
413+26 EW, 127'RT	15-14054	Remove Pole
413+65 EW, 119'RT	15-14055	Remove Pole
414+12 EW, 112'RT	15-14056	Remove Pole
414+13 EW, 142'RT	78-6601	Remove Pole
414+25 EW, 235'RT	78-6602	Remove Pole
414+54 EW, 107'RT	15-14057	Remove Pole
414+96 EW, 104'RT	15-14058	Remove Pole
415+00 EW, 131'RT	15-03104	Remove Pole
415+54 EW, 127'RT	79-08139	Remove Pole
417+33 EW, 96'RT	99-05639	Remove Pole
418+70 EW, 61'RT	57-2904	Remove Pole
418+93 EW 73'RT	57-2949	Remove Pole
419+52 EW, 49'RT	57-2892	Remove Pole
419+55 EW, 66'RT	57-2891	Remove Pole
420+7 EW, 44'RT	69-2612	Remove Guy Stub Pole
10+56 SP, 36'RT		MH88-8002, Cover adjustment
10+68 SP, 23'LT		MH88-8003, Cover adjustment
10+88 SP, 14'RT		MH88-8004, Cover adjustment
11+84 SP, 13'RT		MH88-8006, Roof will be 4" into base
40+20 CD 45'DT		aggregate, cover adjustment MH88-8007, Roof will be 4" into base
12+28 SP, 15'RT		aggregate, cover adjustment
12+28 SP, 15'RT To 102+80 TJD, 38'RT		New Conduit from MH88-8007 to MH88-8009
102+78 TJD, 24'RT		MH88-8008 to be Discontinued (roof removed,
		top of wall removed, floor broken up, backfill
12+28 SP, 15'RT To 102+78 TJD, 24'RT		slurry) Conduit from MH88-8007 to MH88-8008 to be
12+20 3F, 13 K1 10 102+76 13D, 24 K1		discontinued in place
102+78 TJD, 24'RT To 102+10 TJD, 40'RT		Conduit from MH88-8008 into the Substation to
400 - 00 T ID - 00 IDT T - 400 - 40 T ID - 40 IDT		be discontinued in place
102+80 TJD, 38'RT To 102+10 TJD, 40'RT		New Conduit from new MH88-8009 into Substation
12+53 SP, 21'LT		MH88-8011, Cover adjustment
12+53 SP, 21'LT To 102+80 TJD, 38'RT		Steel plate over existing conduit from MH88-
		8011 to MH88-8009
102+80 TJD, 38'RT		MH88-8009 to remain
102+73 TJD 112'LT to 102+73 TJD, 50'RT		New Conduit crossing ramp between MH88- 8005 and MH88- 8022 (into SS)

102+70 TJD, 112'LT to 102+70 TJD, 50'RT	Existing conduit to be discontinued in place
13+18 SP, 19'LT	MH88-8019, Roof to be lowered. Cover to
,	move 2'N to avoid the proposed curb
13+31 SP, 20'RT	MH88-8020, Cover adjustment
12+66 SP, 51'RT	MH88-8012, Cover adjustment
12+66 SP, 51'RT To 15+65 SP 42'RT	Conduit replaced from MH88-8012 to MH88-
	8026, in the same location.
13+88 SP, 23'LT	MH88-8021, Cover adjustment
13+88 SP, 23'LT To 13+81 SP, 36'RT	Steel Plate over existing conduit from MH88- 8021 to SS entrance
13+90 SP, 44'LT	MH88-8023, Cover adjustment
15+65 SP, 42'RT	MH88-8026, Possible Relocation, further investigation needed
16+92 SP, 7'RT	MH8322, Roof needs to be replaced, Cover adjustment
17+57 SP, 22'LT	MH88-8030, Cover adjustment
17+50 SP, 22'RT	MH88-8028, Cover adjustment
25+78 KS, 22'LT	MH88-8029, Cover adjustment
16+92 SP, 7'RT To 219TSP+03 11'RT	New Conduit from MH8322 to MH6384 in place of the existing conduit to be discontinued
219+03 TSP, 11'RT	MH6384, Cover adjustment
11+29 J, 44'LT	MH94-8006, Cover adjustment
11+14 SP, 59'RT to 12+61 SP, 54'RT	New Conduit Span from MH88-8012 to N 29th ST
N 29th ST From W ST Paul to W MT Vernon Ave 2' to 5' E of ELL	New Conduit Span on N 29th ST
New MH in N 29th ST	5' E OF ELL N 29TH ST, 5' S OF SLL W MT VERNON
W MT Vernon Ave from N 29th ST to N 32nd ST 30' N of SLL	New Conduit Span on W MT Vernon Ave
New MH in MT Vernon Ave	86' W OF WLL N 30TH ST, 30' N OF SLL W MT VERNON
New MH in MT Vernon Ave	78' E OF ELL N 32ND ST, 30' N OF SLL W MT VERNON
N 32nd ST From W MT Vernon to W Park Hill Ave 23' W of ELL To W Canal ST Varies East Side	New Conduit Span on N 32nd ST
New MH in N 32nd ST	New MH in Intersection of N 32nd ST and W Park Hill Ave
W Park Hill Ave from N 32nd ST To Alley N 31st St 25' S of NLL	New Conduit Span on W Park Hill ave for New Riser
New MH in N 32nd ST	New MH in Intersection of N 32nd ST and W Canal ST, North Side
W Canal ST from N 32nd ST To Greves SS Varies North Side	New Conduit Span North of W Canal St to Greves SS
NW Corner of W Canal ST and N 32nd ST	3 VFI Units and 3 Riser Poles (Gazebo Needs to be relocated)

Poles and guy wires/anchors not listed above will remain in the project area during the project. These remaining poles and their associated circuits, which will not be relocated until after this contract work is complete, will be energized during the project.

We Energies requires that grading north and east of the existing Greves Substation, including the entire area between Greves Substation and the new ATC Ballpark Substation, be near final grade and ready for substation construction. We Energies is planning to begin substation modifications from April 1, 2028, through December 31, 2028, concurrent with extensive other relocation efforts in this area.

Work on structure R-40-761 between approximately Station 2003+00 and Station 2004+20 will require a substation outage of up to 75 calendar days, anticipated between October and December 2027. Provide We Energies a minimum of 60 days' notice prior to starting work in this area to allow for outage planning. The 75-day period will begin upon written confirmation from ATC or We Energies to WisDOT and the WisDOT contractor that the overhead lines in the outage area have been removed. This duration does not include the time needed by ATC and We Energies to remove and restore the lines. Coordinate with We Energies and ATC on outages required to perform as noted in the "Prosecution and Progress" and "Notice to Contractor - Coordination of Electric Outages with American Transmission Company (ATC)" articles.

We Energies - Gas has facilities within the project limits.

Prior to construction, gas services at the following addresses will be replaced from the existing main:

- 2734 W. St. Paul Avenue
- 2818 W. St. Paul Avenue
- 402 N. 28th Street
- 412 N. 28th Street

Additionally, the gas service stub at 2724 W. St. Paul Avenue will be discontinued.

Anticipated Start Date: July 15, 2025. Anticipated duration of work: 25 working days.

Valve box adjustments will be required at the following locations:

- Station 10+36 SP, 15' RT
- Station 16+82 SP, 33' LT

Notify We Energies to coordinate gas valve box adjustments. We Energies requires a minimum of 1 business day per valve box adjustment.

The following utilities have facilities within the construction limits; however, no adjustments are anticipated:

AT&T Legacy

Level 3 Communications LLC

Milwaukee Metropolitan Sewerage District

Spectrum

Windstream KDL, LLC

10. Work by Others.

Replace paragraph one under section titled City of Milwaukee – Street Lighting with the following:

City of Milwaukee – Street Lighting has facilities within the project limits. Construct, install, remove, and discontinue City of Milwaukee – Street Lighting facilities as shown in the plans and in the bid items for this project.

Replace paragraph one under section titled City of Milwaukee – Signals with the following:

City of Milwaukee – Signals has facilities within the project limits at the intersection of S. 27th Street and W. St. Paul Avenue. Construct, install, remove, and discontinue City of Milwaukee – Signals facilities as shown in the plans and in the bid items for this project.

18. Notice to Contractor – Coordination of Electric Outages with American Transmission Company (ATC).

Replace the entire article with the following:

American Transmission Company (ATC) has 138 kV overhead transmission lines located along the south side of IH 94 within the project limits, which will remain energized throughout the duration of construction. The contractor is required to maintain OSHA-specified Minimum Approach Distances (MADs) from these energized lines at all times. It is the contractor's responsibility to determine the appropriate clearance for the equipment being used and to ensure that these minimum distances are strictly adhered to during all operations near ATC facilities.

Contractors are not permitted to enter any ATC switchyard without prior coordination and approval. Any work planned inside an ATC switchyard must first be coordinated with and approved by ATC. All work in the vicinity of ATC transmission facilities must be conducted with extreme caution. Transmission structures may include multiple ground rods that could extend significant distances from the base of the structure. These rods are connected via ground wires and may be buried up to 18 inches or deeper. If ground rods or any other ATC facilities are disturbed during construction, their locations must be documented and promptly reported to ATC. ATC has two (2) structures within the project limits i.e., lattice towers at approximately Station 421EW+45, 16'RT and Station 417EW+27, 56'RT. No excavation within 50 feet of any ATC structure is allowed without ATC approval. Contact Jeff Vanderwerff, (262) 206-4966 to coordinate review and approval.

No temporary or permanent stockpiling or staging of equipment, materials, or earthwork is allowed within the ATC wire zone or easements at any time. Unobstructed access to ATC facilities must be maintained throughout the project, including access points such as the ATC's 28th St substation driveway at St Paul Avenue. Blocking or restricting access is not permitted unless coordinated and approved by ATC in advance. If thermal sand around an ATC underground cable is disturbed during construction, it must be replaced in accordance with ATC's specifications.

For construction activities expected to cause excessive vibration—such as blasting, pile driving, vibratory hammers, hydraulic breakers, or drop hammers—the contractor must notify ATC at least thirty (30) working days in advance. A vibration mitigation plan must be provided for ATC's review, including the anticipated peak particle velocity (PPV) and frequencies at ATC structures, substations, and underground facilities.

Outage requests not already addressed in the Utilities article under the ATC Management, Inc. section must be submitted to ATC with at least 150 calendar days' notice and must include sufficient justification. ATC retains the right to deny any outage request based on real-time system conditions, operational constraints, or load demands. The availability of any outage is not guaranteed. Single- or double-circuit outages may be requested year-round, but full triple-circuit outages are only permitted from October 1 through December 31 unless specifically approved in writing by ATC. No full circuit outages are allowed between January 1 and September 30 unless prior written approval is granted by ATC. The contractor must contact ATC Construction Manager Dale Hartung at (262) 212-9449 to initiate the outage agreement process. An executed outage agreement is required for any planned outages. All costs associated with ATC outages requested for WisDOT project work will be the responsibility of WisDOT.

Electric fields under transmission lines can cause induced voltages on ungrounded equipment and vehicles working near transmission lines. It is the contractor's responsibility to ensure that all equipment used in proximity to ATC lines is properly grounded to mitigate the risks associated with induced voltages.

33. Contract Award and Execution.

Replace paragraph 7 under section titled 103.9 Bid Escrow Documentation with the following:

The low bidder shall present authentic copies of their BED at the department's office, located at WisDOT Southeast Region Office, 141 NW Barstow Street, Waukesha WI, 53188, on Monday, September 15th, at 1:30 PM.

208. Remove Existing Steel Piling, Item SPV.0090.4300.

Replace entire section titled A Description with the following:

This special provision describes removing existing steel piles that conflict with proposed new drilled shafts for substructures as shown in the plans.

Replace entire section titled C Construction with the following:

C Construction

Remove any existing steel piling that conflicts with proposed drilled shaft locations and as shown on the contract plans. An existing steel pile conflicts with a proposed drilled shaft if it is in direct conflict or otherwise prohibits installation of the proposed-drilled shaft temporary steel casing.

One of the following methods of removing shall be used:

- a. Direct Pull: Remove the piling from the soil by pulling directly upward.
- Vibratory Excavation: Remove the piling by vibrating the piling loose and pulling the piling directly upward
- c. Contractor Proposed: If the contractor chooses to use an alternate method to remove the existing steel piling, the contractor shall provide the engineer with a written methodology for review and acceptance.

When an existing steel piling is found to conflict with the proposed location of a new drilled shaft, the contractor shall notify the engineer and receive written acceptance on the method of removal that was chosen prior to beginning any work to remove the steel piling.

After pile removal and prior to drilled shaft construction, backfill any excavated areas holes left by pile removal with flowable backfill, consisting of aggregates that conform to standard spec 501 for Grade A Concrete and do not add any cementitous material; cement or fly ash, to the flowable fill mix. Weigh aggregates at a batch plant suitable for batching concrete masonry. Mix and deliver to the project site using a truck mixer. Add enough water to enable the mixture to flow readily.

Replace **E Payment**, paragraph 2, sentence 1 with the following:

Payment for Remove Existing Steel Piling is full compensation for removing existing steel piling, providing and backfilling with flowable backfill, and for disposing of all material removed.

216. Timber Lagging, Item SPV.0110.4000.

Replace entire section titled B Materials with the following:

Use materials that conform to lumber as specified in standard spec 507 except that preservative treatments according to standard spec 507.2.2.6 are not required and untreated lumber may be used. Use Douglas fir or Southern pine construction grade rough-cut lumber with a minimum thickness of 4-inches.

222. Temporary Wall Wire Faced Mechanically Stabilized Earth LFCF R-40-767, Item SPV.0165.4100.

Replace paragraph 9 under section titled B.2 Design Requirements with the following:

The wall facings shall be designed according to AASHTO 11.10.2.3. A geotextile shall be used at the front face of the wall.

Replace entire section titled **B.3.1 Steel Components** with the following:

B.3.1 Steel Components

Provide steel reinforcement that meets the following requirements:

1. Welded Wire Fabric Soil Reinforcement

Provide shop fabricated welded wire reinforcement from cold drawn steel wire that has a yield stress of 65,000 psi and conforming to the minimum requirements of ASTM A1064 and be welded into the finished configuration according to ASTM A1064. Replace welded wire fabric that has been damaged during handling, placing or backfilling at the direction of the engineer, at no expense to the department.

Steel Reinforcing Strips and Tie Strips

As an alternate to welded wire reinforcing mesh, provide steel reinforcing strips or ladder reinforcing strips or equal, hot-rolled from bars, to the required shape and dimensions meeting the requirements of ASTM A572 Grade 65 minimum. Tie strips shall be shop fabricated of hot-rolled steel meeting the requirements of ASTM A1011 Grade 50.

3. Welded Wire Fabric Facing Panels

Provide welded wire fabric that is used to fabricate the facings of the wire-faced wall that has a yield stress of 65,000 psi. All steel shall be shop fabricated of cold drawn steel wire conforming to the minimum requirements of ASTM A1064 and be welded into the finished configuration according to ASTM A1064. Replace welded wire fabric that has been damaged during handling, placing or backfilling at the direction of the engineer, at no expense to the department.

4. Fasteners

High strength bolts meeting the requirements of AASHTO M164 or equivalent.

5. Connector Pins and Mat Bars

Connector pins and mat bars fabricated from cold drawn steel wire meeting the requirements of ASTM A82.

Replace entire section titled **B.3.2 Geotextile** with the following:

B.3.2 Geotextile

Use geotextile as recommended by the wall manufacturer. If none is recommended, use Type DF (schedule B) as shown in standard spec 645 or as specified on the contract plans. Deliver in a protective wrap and keep protected from ultraviolet light until incorporated into the work.

223. Wall Concrete Panel Mechanically Stabilized Earth LFCF R-40-761, Item SPV.0165.4761; Wall Concrete Panel Mechanically Stabilized Earth LFCF R-40-767, Item SPV.0165.4767.

Replace paragraph one under section titled A Description with the following:

This special provision describes designing, furnishing materials and erecting a permanent earth retention system in accordance to the lines, dimension, elevations and details as shown on the plans and provided in the contract. The design life of the mechanically stabilized earth (MSE) wall and all wall components shall be 100 years minimum.

Replace paragraph 6 under section titled B.2 Design Requirements with the following:

Use LFCF as MSE backfill within the limits shown on the plans. The design of the wall and reinforced backfill zone behind this wall is to be based on an equivalent backfill area of assumed granular backfill with a maximum angle of internal friction of 30 degrees and unit weight density equal to the unit weight density of the LFCF backfill. The design of the wall and reinforced backfill zone behind this wall is to be based on an equivalent backfill area of assumed granular backfill with a maximum angle of internal friction of 40 degrees and a unit weight density equal to the unit weight density of the LFCF backfill.

232. Removing Bollard, Item 204.9060.S.0002.

A Description

This special provision describes removing steel encased concrete bollards conforming to standard spec 204.

- B (Vacant)
- C (Vacant)
- **D** Measurement

The department will measure Removing Bollard as each individually unit, acceptably completed.

E Payment

Add the following to standard spec 204.5:

ITEM NUMBERDESCRIPTIONUNIT204.9060.S.0002Removing BollardEACH.

stp-204-025 (20230113)


Schedule of Items


Attached, dated August 28, 2025, are the revised Schedule of Items Pages 1, 18, 26, 27, and 29 - 31.


Plan Sheets


The following $8\frac{1}{2}$ x 11-inch sheets are attached and made part of the plans for this proposal: Revised: 4, 70, 124-125, 204-205, 217-218, 367, 369, 369, 413, 424-425, 829, 846.


END OF ADDENDUM

















TOTAL TOTA	. 02 GD	CATEGORY 1000 UNLESS OTHERWISE NOTED
REMOVING ASPHALT 204 0110 204 0120* REMOVING STATION TO STATION OFFSET SYR 4,260 - SWEACE SUBFACE MILLING STATION	202	
NAMINING STATION TO STATION OFFSET SY	ust 28	
REMOVING ASPHALI 204.0110 204.0120* REMOVING ASPHALIC AS	Aug	
REMOVING ASPHALI 204,0110 REMOVING ASPHALI 204,0110 REMOVING ASPHALIC SUBRACE SVIRAGE SVIR	16	-
REMOVING ASPHALI 204,0110 REMOVING ASPHALI 204,0110 REMOVING ASPHALIC 204,0110 REMOVING ASPHALIC 204,0110		92,290
REMOVING ASPHALT 204.0110 REMOVING ASPHALT 204.0110 REMOVING ASPHALT 204.0110 ASPHALT 204.0110 ASPHALT 204.0110 ASPHALT 204.0110 20.000 2		670
REMOVING ASPHALT 204,0110 REMOVING ASPHALT 204,0110 REMOVING ASPHAITC SUBRACE SYRAGE S		50
REMOVING ASPHALI 204 0110 REMOVING ASPHALI 204 0110 REMOVING ASPHALIC STATION TO STATION OFFSET SY SUBTRACE SY SUBTOTAL 4,260 SUBTOTAL 4,260 MAINLINE H54		I
REMOVING ASPHALT 204,0110 REMOVING ASPHALT 204,0110 REMOVING ASPHALTIC SUBFACE SUBFACE SY 4,260 SUBTOTAL 1,71E9+00 231E8+03 RT 4,260 MAINLINE 1194 177E9+00 231E8+06 LT - - - - - - - - -		620
REMOVING ASPHALT 204 0110 REMOVING ASPHALT 204 0110 REMOVING ASPHALT 204 0110 REMOVING ASPHALTC STATION TO STATION OFFSET SY SUBTOTAL STATION OFFSET SY SY STATION OFFSET SY STATION		1,760
REMOVING ASPHALT 204 0110 2		1,760
REMOVING ASPHALT 204.0110 204.0110 ERMOVING REMOVING STATION TO STATION OFFSET SY WAINLINE 119.94 1,250 131E9.43 RT 4,250 141.24 1,250 141.24 1,250 141.24 1,250 141.24 1,250 141.24 1,250 141.24 1,250 141.24 1,250 141.24 1,250 141.24 1,250	1	:
REMOVING ASPHALT 204 0110 REMOVING REMOVING REMOVING ASPHALTIC SURFACE SURFACE SURFACE SURFACE		ı
204.0110 REMOVING		
REMOVING ASPHALT		

က

			R	0 106 evise ugus	ed S	Sheet 3 5, 2025	69									JERWAISE MOTER
	00002 Vie					204.9165.S.0002 REMOVING LANDSCAPE ROCK SF		1,360	204.0165 REMOVING			757	418	1,400		CATEGORY 1000 LINI ESS OTHERWISE NOTED
	204.9060.5.0002 REMOVING BOLLARD EACH	2 2			⊻I	OFFSET		눖		OFFSET		RT/LT	LT/RT LT			, VACCATA
OLLARD	N OFFSET	08 60'RT			REMOVING LANDSCAPE ROCK	STATION		16SP+60	REMOVING GUARDRAIL	STATION		15TEB+51 25TEB+12	25TLC+49 25TLC+59			L
REMOVING BOLLARD	STATION	E 20TLC+08			VING LAND	STATION TO		14SP+05	REMOVING	ION TO		V+29 - 3+40 -	C+37 - C+15			
8	ROADWAY	LOCAL ROADS W ST PAUL AVENUE TOTALS			REMO		9			Y STATION		415EW+29 21TEB+40	21TLC+37 24TLC+15			
	STAGE	1 LOC				ROADWAY	LOCAL ROADS	TOTALS		ROADWAY	MAINLINE IH 94		RAMP LC	TOTAL		
						STAGE				STAGE	Н					
					1	H ST	ĺ									
	REMARKS					2.UDES N. 27TH ST			.0060.0122 SAWING CONCRETE BARRIER EACH		1		ਦਾਦਾ	l e e	2	
						INCLUDES N. 27TH ST			SPV							
	204.9060.S.0001 REMOVING STEPS RAUING EACH REMARKS	2	1	1	2	- INCLUDES N. 27TH ST	1	2	204.0157 REMOVING CONCRETE BARRIER LF		145 145		277 277 205	703 373 248	2,170 5	
<u>WAIK</u>	204.9060.5.0001 REMOVING STEPS RAILING EACH					ı			204.0157 REMOVING CONCRETE BARRIER OFFSET LF		18.1'RT 145 41.3'RT 145		4.2'RT 277 8.4'RT 277 6.3'RT 277	6.3 KI 703 8.4 RT 373 4.2 RT 248		
CRETE SIDEWALK	204.0155 204.9060.5.0001 REMOVING REMOVING CONCRETE SIDEWALK STEPS RALING SY EACH	672	336	177	1,185 2		375	1,560 2	204.0157 REMOVING CONCRETE BARRIER STATION OFFSET LE		21TEB+39 18.1'RT 145 25TEB+12 41.3'RT 145		113TWB+74 4.2'RT 277 113TWB+74 8.4'RT 277	703 373 248		
DVING CONCRETE SIDEWAIK	204.0155 204.9060.5.0001 REMOVING REMOVING CONCRETESIDEWALK STEPS RALING OFFSET SY EACH	LT/RT 672	LT/RT 336	LT/RT 177		- 375 -			204.0157 REMOVING CONCRETE BARRIER TO STATION OFFSET LF		- 21TEB+39 18.1'RT 145 - 25TEB+12 41.3'RT 145		- 113TWB+74 4.2'RT 277 - 113TWB+74 8.4'RT 277	- 124TW8+49 8.4'RT 373 - 124TW8+49 4.2'RT 248		
REMOVING CONCRETE SIDEWALK	204.0155 204.9060.5.0001 REMOVING REMOVING CONCRETE SIDEWALK STEPS RALING SY EACH	672	336	177		375			204.0157 REMOVING CONCRETE BARRIER OFFSET TO STATION OFFSET LF		10.7'LT - 21TEB+39 18.1'RT 145 20.9'RT - 25TEB+12 41.3'RT 145		4.2'RT - 113TW8+74 4.2'RT 277 8.4'RT - 113TW8+74 8.4'RT 277 6.3'DT - 120TW8-78 6.3'DT 205	6.5 KI - 124TWB449 8.4 KT 373 4.2 KT - 124TWB449 4.2 KT 248		
REMOVING CONCRETE SIDEWALK	204.0155 204.9060.5.0001 REMOVING REMOVING CONCRETE SIDEWALK STEPS AALING STATION OFFSET SY EACH	19SP+49 LT/RT 672	13J+05 LT/RT 336	26KS+32 LT/RT 177		195P+49 LT 375 -			204.0157 REMOVING CONCRETE BARRIER STATION OFFSET TO STATION OFFSET LF	NE .	19TEB+98 10.7'LT - 21TEB+39 18.1'RT 145 23TEB+66 20.9'RT - 25TEB+12 41.3'RT 145	EN E	4.2'RT - 113TW8+74 4.2'RT 277 8.4'RT - 113TW8+74 8.4'RT 277 6.3'DT - 120TW8-78 6.3'DT 205	- 124TW8+49 8.4'RT 373 - 124TW8+49 4.2'RT 248		
REMOVING CONCRETE SIDEWALK	204.0155 204.9060.S.0001 REMOVING REMOVING CONCRETESIDEMALK STEPS RALING STATION TO STATION OFFSET SY EACH	<u>UE</u> 10SP+25 - 19SP+49 LT/RT 672	10H39 - 13J+05 LT/RT 336	24KS+96 - 26KS+32 LT/RT 177	1,185	<u>JL</u> 16SP+13 . 19SP+49 LT 375 –	375		204-0157 REMOVING CONCRETE BARRIER ROADWAY STATION OFFSET LF	MAININE	19TEB+98 10.7'LT - 21TEB+39 18.1'RT 145 23TEB+66 20.9'RT - 25TEB+12 41.3'RT 145	MAINLINE H94	110TWB+98 4.2 KT - 113TWB+74 4.2 KT 277 110TWB+98 4.4 KT - 113TWB+74 4.4 KT 277 111TWB+74 6.9 PT 177TWB+72 6.9 PT 705	6.5 KI - 124TWB449 8.4 KT 373 4.2 KT - 124TWB449 4.2 KT 248		
REMOVING CONCRETE SIDEWALK	204.0155 204.9060.5.0001 REMOVING REMOVING CONCRETESIDEWALK STREPS RAULING ROADWAY STATION TO STATION OFFSET SY EACH	- 19SP+49 LT/RT 672	- 13J+05 LT/RT 336	- 26KS+32 LT/RT 177		- 198P+49 LT 375 -			204.0157 REMOVING CONCRETE BARRIER STATION OFFSET TO STATION OFFSET LF	1 MAINLINE	19TEB+98 10.7'LT - 21TEB+39 18.1'RT 145 23TEB+66 20.9'RT - 25TEB+12 41.3'RT 145	2 MAINLINE IH94	110TWB+98 4.2 KT - 113TWB+74 4.2 KT 277 110TWB+98 4.4 KT - 113TWB+74 4.4 KT 277 111TWB+74 6.9 PT 177TWB+72 6.9 PT 705	6.5 KI - 124TWB449 8.4 KT 373 4.2 KT - 124TWB449 4.2 KT 248	2,170	
REMOVING CONCRETE SIDEWALK	204.0155 204.9060.S.0001 REMOVING REMOVING CONCRETESIDEMALK STEPS RALING STATION TO STATION OFFSET SY EACH	<u>UE</u> 10SP+25 - 19SP+49 LT/RT 672	10H39 - 13J+05 LT/RT 336	24KS+96 - 26KS+32 LT/RT 177	1,185	<u>JL</u> 16SP+13 . 19SP+49 LT 375 –	375	1,560	204-0157 REMOVING CONCRETE BARRIER ROADWAY STATION OFFSET LF		19TEB+98 10.7'LT - 21TEB+39 18.1'RT 145 23TEB+66 20.9'RT - 25TEB+12 41.3'RT 145		110TWB+98 4.2 KT - 113TWB+74 4.2 KT 277 110TWB+98 4.4 KT - 113TWB+74 4.4 KT 277 111TWB+74 6.9 PT 177TWB+72 6.9 PT 705	6.5 KI - 124TWB449 8.4 KT 373 4.2 KT - 124TWB449 4.2 KT 248	2,170	

		က								
										Addendum No. 02 ID 1060-27-74 Revised Sheet 424 August 28, 2025
SPV.0090.5002 DUCTILE	RON HYDRANT BRANCH	6-INCH LF		1 1	13	ı	1	1	13	
_ 🙃	AWWA C-151 CLASS 55 WATER MAIN	12-NCH LF		1 1	1	1	47	1	47	
- - =	AWWA C-151 CLASS 55 WATER MAIN	6-NCH LF	°	0 1	9	ı	ı	1	34	
40	ORIGINAL SERVICE (C.O.S.)	ЕАСН		ı -	ı	ı	ı	1	-	
SPV.0060.5003 ADJUSTING	WATER VALVE BOXES	EACH			ı	ı	ı	24	24	
SPV.0060.5002	INSTALLING HYDRANT - ALTERATION	ЕАСН			ı	ı	ı	-	-	
.0060.5000 SPV.0060.5001 SPV.0	REMOVING HYDRANT/MAJOR	ЕАСН			ŀ	-	1	:	-	
SPV.0060.5000	INSTALLING	EACH			-	1	ı		-	
		TO STATION OFFSET	T 100 00 00 11 11 11 11 11 11 11 11 11 11				27KN+49.0 20.0'LT	UNDISTRBUTED	TOTALS	
		STATION OFFSET TO	VE. 4150+26.20 40.48.T				27KN+20.3 20'0'LT	SIGNO		
		STAGE ROADWAY	W. ST PAUL AVE.				N.27THST.			
		≿	7000							

CUC MANHOLES			LOCATION		* 5 &	SS SETER	201 E 38 201 E 38 201	3202 33 31 31 31	3204 JG ES	SPV. 0060.5210 INSTALL CEMENT ENCASED CONDUIT INTO EXISTING MANHOLE	SPV.0060.5212 ADJUSTNG TES MANHOLE	
RO	ROADWAY	MANHOLEID	STATION	OFFSET	EACH	EACH	EACH	EACH	EACH	EACH	EACH	
F2 W.	L) V = 1 V C	ACCES LIMA	0000	F				*				
.isw	W ST. PAUL AVE	MH 3592	13+66SP	36 9' PT	¦ -	: :	: :	- :	: :	: :	: :	
TS M	W ST. PAUL AVE	EXMH 3590	13+02SP	41.2" LT	- :	: :	: :		۱ :	: :	۱ +	
WST	W ST. PAUL AVE	EXMH 3591	13+65SP	41.6' LT	1	ı	-	ı	-	1	:	
WST	W ST. PAUL AVE	MH 3593A	16+61SP	20.2' RT	1	τ-	1	;	1	i	1	
W ST.	W ST. PAUL AVE	EXMH 3593	17+33SP	36.1' RT	1	-	:	-	-	:	:	
TSW WST	PAUL AVE	EXMH 3594	17+59SP	37.2' RT	1	1	τ-	1	-	1	1	
TSM	W ST. PAUL AVE	EXMH 3527A	18+07SP	31.1'RT	- -	;	1	;	1	:	1	
WSI.	W ST. PAUL AVE	EXMH 3527B	18+48SP	23.0' LT	1	; •	1	+	1	:	:	
WST.	W ST. PAUL AVE	MH 3527C	18+40SP	16.5' RT	1	-	1	1	1	;	1	
ZZ	N 27TH ST	MH 3594A EXMH 3596	25+72KS 25+24KS	38.5' LT	-	~	:		!	:	1	
	10 0	CORP CORP	23+2+V3	13 6.00	_	ŀ	l	ŀ	!	ŀ	l	
* ADDITIONAL QUANTITIES SHOWN ELSEWHERE	TES SHOWN ELSEWHE	æ		TOTAL	2	ю	2 2	-	$\begin{pmatrix} 2 \\ 2 \end{pmatrix}$	-	1	
	CONDUIT											
				SPV.0090.5200 2-DUCT CONDUIT		SPV.0090.5201 4-DUCT CONDUIT		SPV 0090-5202 6-DUCT CONDUIT	SPV.0090.5203 2-DUCT CONDUIT	30.5203 XONDUIT		
				4-INCH CONDUIT		4-INCH CONDUIT		4-INCH CONDUIT	3-INCH CONDUIT	ONDUIT		
				DB-60		DB-60		DB-60	DB-60	09		
	ROADWAY	FROM	10	片		4		4	4			
	W ST. PAUL AVE		MH 3592A	17		:		1	1			
	W ST. PAUL AVE		MH 3592A	ŀ		71		ı	1			II F
	W ST. PAUL AVE	MH 3593A	STUB	; ∞				: :				D Re¹
	W ST PAUL AVE		EXMH 3594	1		102		1	1			10
	W ST. PAUL AVE	EXMH 3594	MH 3527C	1 8		;		79	1			60 sec
	WST.PAULAVE	MH 3527C	STUB FOR CB1	94					1 1)-2 d 8
	W ST PAUL AVE		STUB	4		٠ ;		: :				27. Sh
	N 27TH ST	EXMH 3594	MH 3594A	:		:		54	1			-7 e
	N 27TH ST		STUB	12		1		;	1			4 et
	N 27TH ST	MH 3594A STR	STRUCTURE B40-1083	i		1		1	83	3		02 42 5
			TOTALS	105		445		133	83	3		
ALL ITEMS CATEGORY 7010 UNLESS NOTED OTHERWISE												PAGE 1 OF 2
			_			-						
DDO 150T NO: 4060 27 74												

ID 1060-27-74 **Revised Sheet 829** August 28, 2025

GENERAL NOTES

BEVEL EXPOSED EDGES OF CONCRETE 3/4", UNLESS NOTED OTHERWISE. REFER TO SPECIAL PROVISIONS FOR INTERIM COMPLETION DATES. COORDINATES ON THIS PLAN ARE REFERENCED TO THE WISCONSIN COUNTY COORDINATE SYSTEM (WCCS), MIWANDINGS COUNTY OCORDINATE SYSTEM (WCCS), MIWANDINGS ARE INFEET. ELEVATIONS ARE IREFERENCED TO THE NORTH AMERICAN VERTICAL, DATUM NAVD 88 (2007).

ALL DIMENSIONS ARE ALONG THE FRONT FACE OF WALL, UNLESS SHOWN OTHERWISE.

ALL BAR STEEL REINFORCEMENTIS TO BE EPOXY COATED. BAR STEEL REINFORCEMENT SHALL HAVE 2". CLEAR COVER, UNLESS SHOWN OTHERWISE.

THE CONTRACTOR MUST COORDINATE THE REMOVAL OF EXISTING STRUCTURE B-40-513_5 AND CONSTRUCTION OF THE SINGLOGE B-40-513_5 AND AND CONSTRUCTION OF THE SINGLOGE B-40-513_5 IS A FOUN-SPAN STEEP PALIF GINDER BRIDGE. THE EXISTING GROUND LINE SHALL BE THE UPPER LIMITS OF "EXCAVATION FOR STRUCTURES RETAINING WALLS (R-40-761)".

THE LTILLY IN FORMATION SCHOWN, OF THESE DRAWINGS CONCERNING THE AND LOCATION OF UNDERSCHOULD UNITIEST IS NOT GLARANTED TO BE ACCURATE OR ALL INCLUSIVE. THE CONTRACTION IS RESPONSIBLE FOR MARKING THEIR OWN DETERMINATIONS AS TO THE TYPE AND LOCATION OF UNDERSCHOOM OIL ILLIFES SAME AND REDESSANT TO AND DAMAGE. UNITIEST WHERE DAS SPROPOSED MAY BE INSTALLED BY OTHER PRIOR TO THE CONTRACT.

NAME PLATE SHALL BE CONSIDERED INCIDENTAL TO ITEM 504.0500 "CONGRETE MASONRY RETAINING WALLS". FABRICATE IN ACCORDANCE TO SDD.12 A 3-10.

HAZIMAT CONTAMINATED SOIL EXIST FROM APPROXIMATELY STA 2008+70 TO STA 2013+25.
HAULING AND DISPOSAL OF HET TOP 25: 100 TO A DEPTH DIRECTED BY THEWRODOD TEST
HAULING AND DISPOSALO, THE TOP 25: 100 TO A DEPTH DIRECTED BY THEWRODOD STEST
HEREOL CHACHOSTS, "EXCAVATION FOR STRUCTURES RETAINING WALKE (84-2-56)" AND
"EXCAVATION, HAULING AND PRESSED STEEP STRUCTURE DIRECTED FOR THE CONTAMINATED SOIL", HAULING
TEXCAVATION, HAULING AND RESS OF 100 THE STRUCTURED IN
"EXCAVATION, HAULING, AND ESPOSAL OF PETFOLEIM CONTAMINATED SOIL", "MANAGEMENT OF
SOID WASTE CREPTES ST, MEST OF 2771 FT OF STRUCTURED IN
"EXCAVATION, HAULING, AND ESPOSAL OF PETFOLEIM CONTAMINATED SOIL", "MANAGEMENT OF
SOID WASTE CREPTES ST, MEST OF 2771 FT OF STRUCTURED IN
"TOTAL OF SOIL OF STRUCTURED IN MANAGEMENT OF SOIL OWNSTE CREPTES ST,

ESTIMATE OF QUANTITIES

27,490 27,490 27,490 28,290 29,290 29,290 29,290 29,290 29,290 29,290 29,290 29,290 29,290 29,290 20		
61 64 64 64 64 64 64 64 64 64 64 64 64 64		68 68 68 68 68 68 68 68 68 68 68 68 68 6
1,615 175,250 7,952 500 1,230 1,230 1,230 3,80 3,80 3,80 3,80 1,230 1,230 1,230 1,230 1,230 1,230 1,230 1,230 1,230 1,230 1,230	1,615 175,250 7,952 500 1,230 380 380 380 380 10 10 10 10 10 10 10 10 10 10 10 10 10	1,615 115,250 7,592 500 1,230 1,230 1,230 1,230 1,66,134 1,466,134 1,466,134 1,230
SF S	EACH	3218 3218 3218 3218 3218 3218 3218 3218
BAR STELL REIL PORCEMENT IN COATED STRUCTURES TEMPORARY SHORING FA 40-761 THE AND THE TEMPORARY SHORING FA 40-761 THE AND THE TEMPORARY SHORING FA 40-761 THE AND THE SHORING FA 40-761 TOWN THE SHORING FA 40-761 THE AND THE AND THE SHORING FA 40-761 THE AND THE AND THE SHORING FA 40-761	WELDED STUD SHEAR CONNECTOR STRUCTURES WELDED STUD SHEAR CONNECTORS 7/8 X 10-INCH HEMODARY SHORING FAQ P./61 TEMPODARY SHORING FAQ P./61 TEMPODARY SHORING SAQ P./61 TEMPODARY SYSTEM THE SACK ANCHORS THE SACK ANCHORS THE SACK ANCHORS THE SACK ANCHORS THE SAD SHORING STRUCK SAD SET SAG SAC	MANDED STUD SHEAR CONNECTOR STRUCTURES TEMPORARY SHOUNES HEAD-SEL TEMPORARY SHORING R-40-761 TEMPORARY SHORING R-40-761 TEMPORARY SHORING R-40-761 ARAURE DIE R-50-761
25 SY	87. EACH 1.	328 (2014) 328 (3014)
1 В В В В В В В В В В В В В В В В В В В	87. 87. 87. 87. 87. 87. 87. 87. 87. 87.	3ZS S S S S S S S S S S S S S S S S S S
SY EACH EA	328 328 328 328 328 328 328 328 328 328	3288 3288 3288 3288 3288 3288 3288 3288
EACH	3ZS 3ZS 3ZS 4Z	328 328 8 8 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9
ЕАСН ЕАСН ЕАСН ЕАСН ЕАСН ЕАСН НВ 1.8 1.8 1.8 1.8 1.8 1.8 1.8 1.8	EACH	328 HD74 S 18 S 28
LF LB LB LB LB LB LB LB	10 EACH 10 EACH 10 EACH 11 EACH 12 EACH 13 EACH 14 EACH 15 EACH 16 EACH 17 EACH 18 EACH 18 EACH 18 EACH 18 EACH 18 EACH 19 EACH 10 EACH 10 EACH 11 EACH 11 EACH 12 EACH 13 EACH 14 EACH 15 EACH 16 EACH 16 EACH 17 EACH 18 EAC	3ZS
EACH EACH EACH EACH HRS LB LB LF LF LF RS NBM MBM	1278 3278 3278 3278 3278 3278 3279 3279 3279 3279 3279 3279 3279 3279	3288 S2E EACH HOVE SEAL BANK SALE EACH HOVE SALE EA
EACH EACH HRS HRS LB LF LF LF RMBM MBM	EACH	3ZS H2V4 S S S S S S S S S S S S S S S S S S S
EACH 25 EACH 25 EACH 21 EACH 21 EACH 21 EB 1,615,134 EB 1,615,134 EF 12,339 EF 12,339 EF 35,333	EACH 25	EACH 25
В БАСН 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	EACH 1 HIS 1200 HIS 1,515,194 LE 1,230 LF 1,230 LF 1,230 KIR 1,19 SF 5,533 SF 5,533 	HG 10 10 10 10 10 10 10 10 10 10 10 10 10
HFS 120 18 1,616,194 18 1,460,116 1F 1,230 1F 12,39 MRM 119 SF 50,533 SF 50,533	HRS 120 18 1,660,194 18 1,660,116 19 1,600,116 19 1,2300 10 1,2300 10 1,2300 11 1,2300 12 1,2300 13 1,2300 14 1,2300 15 1,2300 16 1,2300 17 1,2300 18 2	HRS 120 HRS 120 HR 1,0534
LB 1,616,194 LB 1,460,116 LF 1,230 LF 1,230 LF 1,2350 LF 1,2350 LF 1,2350 SF 30,533	18 1,616,134	16 1,615,134 1
LF 1,460,116 LF 1,230 LF 12,350 MBM 119 SF 30,533	18 1,460,116 19 1,460,116 19 1,460,116 19 1,500	19 1,460,116
LF 1,230 LF 12,350 MBM 119 SF 30,533	LF 1230 WBM 1239 KB 76,233 SF SF SF SIZE EACH	1,230 1,23
MBM 119 SF 30,533	11.0 2.0 2.0 EACH 1.0 2.0 2.0 EACH 1.0 2.0 2.0 EACH 1.0 EACH 1.	378 378 378 378 378 378 378 378 378 378
MBM 119 SF 30,533	SF 30,533 SF SF SIZE SIZE EACH	32/8 H
SF 30,533	SF 30,533 SF SIZE SIZE EACH	SF
SF	SF SIZE SIZE EACH	SIZE SIZE EACH SIZE
ON-BID ITEMS		DIVSTYRENE
		DLYSTYRENE
NON-BID ITEMS SIZE SIZE SIZE SIZE SIZE SIZE SIZE SIZ		

SOLDIER PILE WALL NOTES Addendum No. 02

FLOWABLE BACKFILL AND CLSM ARE INCLUDED IN THE BID ITEM "EXCANATION FOR STRUCTURES RETAINING WALLS (R-40-761)". SEE SPECIAL PROVISIONS FOR DESCRIPTION OF FLOWABLE BACKFILL AND CLSM.

TIMBER LAGGING DESIGN ASSUMES NO R-40-767 CONSTRUCTION AND NO LIVE LOAD PRESENT ON TOP OF WALL HOOR FOR CAST IN PLACE CONVERTE FACING BEING INSTALLED AND REACHING DESIGN STRENGTH. IF THESE ASSUMPTIONS ARE NOT MET THE CONTRACTOR WILL BE RESPONSIBLE FOR THE DESIGN AND THE COST OF MODIFICATIONS TO THE TIMBER LAGGING.

SURFACE PREP AND PAINT SOLDIER PILES FROM TOP OF PILE TO 1'-0" BELOW TOP OF FOOTING WITH ONE COAT OF TAXIVE ACHD PRIMER AS SPECHED IN SECTION SLY OF THE STANDARD SPECHEGATIONS. WE RELOSE THIS SHARED PAINTING OF PILES IS MEESINED AND PAINTING OF PILES IS MEASURED AND PAID FOR AS BIO ITEM NUMBER 517.0600, PAINTING EPOXY SYSTEM R-40-761.

THE EARTHWORK REQUIRED TO INSTALL THE SOLD ER PILES, FOOTINGS, TIEBACK ANCHORS, AND MALL EACHERS INCLUDED IN THE BIO TEAT STRUCTURES RESTRUCTURES RESTRUING WALLS WALL EARTHWORK IN THE BIO TEAT STRUCTURES RESTRUCTURES RESTRUINGS WALLS BETTAKEN THE REPUBLIES INCLUDED IN THE ROADWAY BID TITEM "COMMON EXCAMATION" SEE EXCAMATION THE RELAGINES ON SHEET 6 AND ROADWAY PLANS FOR RECAMATION UNITS.

"STRUCTURAL STEEL HS SOLDIER PILES DELIVERED" ESTIMATED QUANTITY IS BASED ON MAXIMUM PILE LENGTH REQUIRED IF BEDROCK IS NOT ENCOUNTERED.

"STRUCTURAL STEEL BS SOLDER PLIE INSTALLED", "FOUNDATION DISLUMS" AND "CONGETET MANDEN SOLDER PLE INSTALLED STEEL STRUCTURE STEEL BS SOLDER PLE FOOTINGS" QUANTITY ESTIMATES ARE BASED ON THE ASSUMPTION BEDROCK IS OLD UNTERED AT ESTIMATED ELEVATIONS AND ARE TO BE PAID BASED UPON QUANTITY BEDROCK STALLED.

MASE RETAINING WALL SOIL REINFORCEMENT MAY BE PLACED UP TO A MAXIMUM OF 15' FROM PERRENDICUMR IN RECESSARY TO AVOID INTERFERENCEMIT HERMS BEHIND THE WALL ANGLES GREATER HAN 15' REQUIRE APPROVAL, FROM THE BURBAU OF STRUCTURED SEISION SECTION. **MSE WALL NOTES**

THE CONTRACTOR SHALL PROVINE COMPLETE DESIGN PLANS DETAILS, SPECIFICATIONS, AND SHOD DRAWINGS FOR THE MSE RETAINING WALL IN ACCORDANCE WITH THE SPECIAL PROVISIONS. THE MSE RETAINING WALL INANUFFICTURER SHALL PROVIDE TECHNICAL ASSISTANCE TO THE CONTRACTOR DOUNING CONSTRUCTION. THE CONTRACTOR DETAILS SHALL DROVING TECHNICAL SHALL SHALL

THE COST OF FURNISHING AND PLACING THE UNREINFORCED CONCRETE LEVELING PAD UNDER THE WAS PRECAST WALL BY WANTES IS INCLUDED IN THE BID ITEM "WALL CONCRETE PANEL MECHANICALLY STABILIZED EARTH LEFT (R-40-761)".

WALL EXTERNAL STABILITY EVALUATION

THE VOLUME OF EARTHWORK REQUIRED TO INSTALL THE UNREINFORCED CONCRETE LEVELING PAD, BACKFILL, ANCHORS AND REINFORCING STRIPS IS INCLUDED IN THE BID TEM "EXCANATION FOR STRUCTURES RETAINING WALLS (R-40-761)". SEE WALL EXCAVATION LIMITS DIAGRAM ON SHEET 6.

THE PLANQUARTITY FOR THE THE "WALL COVERTE PAREL MICHARICALYSTABILESE DATA HET (16-40 761) "IS BASED ON A WALL HEGHT MEKSURED FROM THE TOP OF THE LEVELING PAD TOTHE (16-40 761)" IS BASED ON A WALL HEGHT WENSURED FROM THE TOP OF THE LEVELING PAD TOTHE (16-40 761)" IS BASED ON THE PLANS. "THE TOP OF LEVELING PAD IS ASSUMED TO BE A MINIMUM OUTSIDE THESE UMITS WILL NOT BE MISSINED FOR PARMENT.

DESIGN SPECIFICATION: AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, 9TH EDITION, 2020

AASHT LIVE LOAD:

DESIGN DATA

1060-27-74

PIANS, ELEVATIONS, AND DETAILS SHOWN ON THESE DRAWINGS ARE INTENDED TO INDICATE MSE WALLLOCATIONS, LENGTHS, HEIGHTS, AND DETAILS COMMON TO THE MSE WALL SYSTEM SELECTED. THE CONTRACTOR SHALL VERPIT THAT THE WALL SYSTEM SELECTED WILL COMPORM TO THE REQUIRED ALLIGNMENTS AND DETAILS.

PLAN DIMENSIONS, QUANTITIES AND REINFORCEMENT DETAILS FOR THE MSE RETAINING WALL ARE BASED ON AN ASSAIMED MAXIMAMIO CONCERTE WALL PANEL INTENCESS OF GINCHES. FOR PANEL THICKNESS OF PICKNESS DIFFERENT THAN GINCHES, THE CONTRACTOR SHALL VERIFY REINFORCEMENT BAR DETAILS AND QUANTITIES AND QUANTITIES AND QUANTITIES AND QUANTITIES AND QUANTITIES AND QUANTITIES.

.fy = 60,000 PSI _fy = 50,000 PS

CONCRETE MASONRY RETAINING WALL
PREGAST CONCRETE WALL PANELS
CONCRETE MASONRY SOLDIER PILE FOOTINGS.
BAR STEEL REINFORCEMENT:

* TIMBER LAGGING

LIVE LOAD SURCHARGE (ROADWAY)
LIVE LOAD SURCHARGE (NON-ROADWAY)
LIVE LOAD SURCHARGE (CONSTRUCTION)
MATERIAL PROPERTIES:
CONGRETE MASONRY:

ONLY WALL CONCRETE PANEL MSE WALL SYSTEMS THAT USE STRIP TYPE SOIL REINFORCEMENTTHAT ARE HINGED AT THE PANEL CONNECTION CAN BE USED FOR THIS PROJECT. THE STANDARD PANEL SIZE SHALL BE 5' HIGH x 10' WIDE. 5' HIGH x 5' WIDE PANELS WILL NOT BE ALLOWED.

THE QUANTITIES OF CONCRETE MASONRY AND BAR STEEL REINFORCEMENT FOR THE UNIT 2 CAST-IN-PLACE COPING ARE INCIDENTAL TO BIO ITEM "WALL CONCRETE PAINEL MECHANICALLY STABALIZED BATH, LFG".

DESIGN UNIT 2 MSE WALL FOR A HORIZONTAL BACKSLOPE BEHIND THE WALL AND A LIVE LOAD VERTICAL SURCHARGE OF 240 PSF.

* MATERIAL VALUES BASED ON DOUGLAS FIR-LARCH NO.1, >2" WIDE, REFERENCE AASHTO LRFD SPECIFICATION TABLE 8.4.1.1.4-1

THE COST OF FURNISHING AND PLACING LIGHTWREIGHT FOAMED CONCRETE FILL (LFCF) WITHIN THE METHWREED SOLY LONE IS TO BE INCLUDED IN THE BOT ITEN "WALL CONCRETE PANEL METHWREIGHT STABLIZED EARTH LFCF". SEE ROADWAR PLANS FOR THE QUANTITY OF LIGHTWREIGHT FOAMED CONCRETE FILL OUTSIDE OF THE REINFORCED SOLL ZONE.

LIGHTWEIGHT FOAMED CONCRETE FILL (LFCF) SHALL BE PLACED IN LIFTS NOT EXCEEDING 4 FEET IN DEPTH. EACH SUCCESSIVE LIFT WILL BE PLACED AFTER A MINIMUM OF 24 HOURS.

THE CONTRACTOR SHALL PROVIDE SUITABLE S FACING PANELS DURING PLACEMENT OF LIGHT

HORIZONTAL CURVE DATA

00

THIS WALL IS PART OF A SUPERIMPOSED (TRERED) MSE WALL AND SHOULD BE DESIGNED AS ONE TREED WALL.
THE DESIGN WALH HEIGHT (H) FOR THE LOWER WALL EQUALS THE UPPER + LOWER WALL.

HEIGHT. THE CDR VALUES SHOWN ARE THE MINIMUM BETWEEN THE UNDRAINED AND DRAINED

ANALYSIS. NP: NOT PERFORMED. GLOBAL STABILITY WAS NOT PERFORMED AT THIS SECTION. PREVIOUS SECTION IS MORE CRITICAL.

0	ŏ.							1
D ST PAUL AVE ACT 1060-27-72								
IH-94 EB EXIT RAMP TO 26TH STAND ST PAUL AVE AT CONCLUSION OF FUTURE CONTRACT 1060-27-72 (3)8		COHESION (PSF)	:	50	0	0	0	0
IH-94 EB EXIT RAI AT CONCLUSION C	DRAINED	FRICTION ANGLE (DEGREES)	32	30	28	20	29	35
	GD.	COHESION (PSF)	-	1250 - 2000	750 - 1000	200	1	3500
	UNDRAINED	FRICTION ANGLE (DEGREES)	i	1	1	ı	1	
		(PCF)	125	125	125	06	120	135
SOIL PARAMETERS		SOIL DESCRIPTION	NEW GRANULAR FILL	EXISTING BACKFILL	SOFT-MEDIUM STIFF CLAY	PEAT AND ORGANIC	LOOSE TO MEDIUM DENSE SAND	GLACIAL TILL

SHEET 5 OF 38

GENERAL NOTES, **QUANTITIES &** PROFILE GRADE LINES

STRUCTURE R-40-761

SUPPORTS FOR THE MSE REINFORCING STRIPS AND ITWEIGHT FOAMED CONCRETE FILL.	PS AND WALL CURVE 1	WALL CURVE 2	WALL CURVE 3
12. EE + 2) ES C T S O Y O Y O Y O Y O Y O Y O Y O Y O Y O	N = 570, 2005+13.76 N = 570, 2005+13.76 N = 2075-13.57 N = 2075-13.47 N = 2076-13.47 N = 2076-13.47 N = 2076-13.47 N = 2071-13.47 N = 2071-13.47 N = 2071-13.17 N = 5071-13.17 N = 5071-13.17 N = 5073-13.17 N = 5073-13.17 N = 5073-13.17	P. I. STA 2012-83.88 Y. \$59564.34 V. \$79562.40 D. 3757.52.21 D. 3757.52.21 T. \$14.62.72 F. \$15.72.72 F. \$15.72.72 P. \$15.72.72 P. \$15.72.72 P. \$15.72.72 P. \$15.72.72 V. \$29558.03 V. \$29559.03 V. \$29576.03 V. \$29576.03	P. I. S. A.
.2.61%			1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1
APC STA 235LC+40.38	NPI STA 328LC+65.38	PROFE EZ TEB 13 LIA/IIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIIII	PAUL R. KRUM E-43964-6 WAUKESHA
PROFILE GRADE LINE - LC H-94 EBEXITRAMP TO 26TH ST AND ST PAUL AVE	DE LINE - LC THSTAND ST PAUL AVE	Silili	III ON A L

2015+00 TO 2016+15

2012+30 TO 2015+00

0.60H

REINFORCEMENT RATIO

WALL STATION BORING USED SLIDING 3 BEARING

REFER TO GEOTECHNICAL REPORT

1.41 >3.00

>3.00

GLOBAL STABILITY ECCENTRICITY 3


0.60H²

34.0


STA 2012+50 WALL DIMENSIONS

R/L RETAINING WALL STATION

ALL ITEMS ARE CATEGORY 3000










Page 1 of 31

Federal ID(s): WISC 2025597

SECTION: 0001 Contract Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	201.0105 Clearing	23.000 STA	<u> </u>	
0004	201.0120 Clearing	140.000 ID	·	
0006	201.0205 Grubbing	23.000 STA		·
8000	201.0220 Grubbing	140.000 ID	·	
0010	203.0220 Removing Structure (structure) 0010. R-40-10	1.000 EACH	·	
0012	203.0220 Removing Structure (structure) 0033. R-40-33	1.000 EACH	·	
0014	203.0220 Removing Structure (structure) 0043. B-40-43	1.000 EACH		·
0016	203.0220 Removing Structure (structure) 0057. B-40-57	1.000 EACH		
0018	203.0220 Removing Structure (structure) 0513. B-40-513	1.000 EACH		
0020	203.0220 Removing Structure (structure) 1000. CIP Concrete Retaining Wall 415EW+60 - 416EW+83	1.000 EACH		
0022	204.0100 Removing Concrete Pavement	19,770.000 SY		·
0024	204.0110 Removing Asphaltic Surface	4,290.000 SY		
0026	204.0115 Removing Asphaltic Surface Butt Joints	170.000 SY		
0028	204.0120 Removing Asphaltic Surface Milling	95,720.000 SY		<u></u>







Page 18 of 31


Proposal ID: 20250909007 **Project(s)**: 1060-27-74

Federal ID(s): WISC 2025597

SECTION: 0001 Contract Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0504	652.0225 Conduit Rigid Nonmetallic Schedule 40 2-Inch	2,450.000 LF	·	·
0506	652.0235 Conduit Rigid Nonmetallic Schedule 40 3-Inch	4,178.000 LF	·	<u> </u>
0508	652.0335 Conduit Rigid Nonmetallic Schedule 80 3-Inch	206.000 LF	·	·
0510	652.0615 Conduit Special 3-Inch	39.000 LF		·
0512	652.0700.S Install Conduit into Existing Item	8.000 EACH		·
0514	653.0140 Pull Boxes Steel 24x42-Inch	3.000 EACH		
0516	653.0222 Junction Boxes 18x12x6-Inch	11.000 EACH		·
0518	653.0905 Removing Pull Boxes	12.000 EACH		
0520	654.0102 Concrete Bases Type 2	2.000 EACH		
0522	654.0105 Concrete Bases Type 5	18.000 EACH	<u> </u>	·
0524	654.0120 Concrete Bases Type 10-Special	2.000 EACH		
0526	655.0144 Cable In Duct 4-4 AWG	782.000 LF		
0528	655.0305 Cable Type UF 2-12 AWG Grounded	800.000 LF	<u> </u>	<u></u>
0530	655.0320 Cable Type UF 2-10 AWG Grounded	30.000 LF	·	
0532	655.0510 Electrical Wire Traffic Signals 12 AWG	407.000 LF		<u></u>








Page 26 of 31

Federal ID(s): WISC 2025597

SECTION: 0001 Contract Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0716	SPV.0060 Special 4410. Tieback Anchors Performance Tests	31.000 EACH	·	·
0718	SPV.0060 Special 4600. Trial Drilled Foundation Shaft 34.65-Inch	1.000 EACH	·	<u> </u>
0720	SPV.0060 Special 4700. Underdeck Utility Structure B-40-1083	1.000 EACH	·	
0722	SPV.0060 Special 4800. Retaining Wall Instrumentation R-40-761	1.000 EACH		
0724	SPV.0060 Special 4810. Retaining Wall Instrumentation R-40-767	1.000 EACH	·	·
0726	SPV.0060 Special 4900. Embedded Galvanic Anodes	136.000 EACH	·	·
0728	SPV.0060 Special 5000. Installing Hydrant	1.000 EACH	·	
0730	SPV.0060 Special 5001. Removing Hydrant/Major	1.000 EACH		
0732	SPV.0060 Special 5002. Installing Hydrant - Alteration	1.000 EACH	·	·
0734	SPV.0060 Special 5003. Adjusting Water Valve Boxes	24.000 EACH	·	
0736	SPV.0060 Special 5004. Connect Original Service (C.O.S.)	1.000 EACH		
0738	SPV.0060 Special 5200. Manholes Type TES 4-FT Diameter	3.000 EACH	·	
0740	SPV.0060 Special 5201. Manholes Type TES Doghouse 4-FT Diameter	2.000 EACH	·	








Page 27 of 31

Federal ID(s): WISC 2025597

SECTION: 0001 Contract Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0742	SPV.0060 Special 5202. Manholes Type TES 5-FT Diameter	1.000 EACH	·	·
0744	SPV.0060 Special 5204. Removing CUC Manholes	2.000 EACH	<u></u> ,	
0746	SPV.0060 Special 5210. Install Cement Encased Conduit Into Existing Manhole	1.000 EACH	·	
0748	SPV.0060 Special 5212. Adjusting TES Manhole	1.000 EACH		·
0750	SPV.0060 Special 8003. Reconnect Storm Sewer	47.000 EACH	·	·
0752	SPV.0060 Special 8005. Sealing Storm Structure	14.000 EACH	,	
0754	SPV.0060 Special 8007. Cover Plates Left in Place	20.000 EACH	,	
0756	SPV.0060 Special 8009. Manhole Cover Type MS 58A	5.000 EACH		
0758	SPV.0060 Special 8010. Inlet Cover Type MS 57	34.000 EACH		
0760	SPV.0060 Special 8100. Cover Plates Left In Place In Pavement	12.000 EACH		·
0762	SPV.0075 Special 0203. Pavement Cleanup Project (1060-27-74)	1,500.000 HRS		
0764	SPV.0075 Special 4000. Obstructions, Drilled Foundation Shaft	40.000 HRS		
0766	SPV.0075 Special 4010. Obstructions Foundation Drilling	120.000 HRS	·	·
0768	SPV.0085 Special 4000. Structural Steel HS Soldier Piles Delivered	1,616,194.000 LB	·	







Page 29 of 31

Federal ID(s): WISC 2025597

SECTION: 0001 Contract Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0796	SPV.0090 Special 0705. Glare Screens Temporary Left In Place	1,652.000 LF		<u></u>
0798	SPV.0090 Special 1005. Liquidtight Flexible Nonmetallic 1 1/2 inch Conduit	5.000 LF		
0800	SPV.0090 Special 1012. Electrical Cable Type 4#2/1#8 XLP	3,872.000 LF		·
0802	SPV.0090 Special 1013. Cable Aerial Aluminum 4 AWG Quadruplex Left In Place	1,934.000 LF	·	·
0804	SPV.0090 Special 4100. Drilled Foundation Shaft 34.65-Inch	800.000 LF	·	·
0806	SPV.0090 Special 4110. Drilled Foundation Shaft 59.06-Inch	415.000 LF	·	·
0808	SPV.0090 Special 4200. Foundation Drilling	12,350.000 LF		
0810	SPV.0090 Special 4300. Remove Existing Steel Piling	40.000 LF		
0812	SPV.0090 Special 5000. Ductile Iron (DI) AWWA C- 151 Class 55 Watermain 6-Inch	34.000 LF		
0814	SPV.0090 Special 5001. Ductile Iron (DI) AWWA C- 151 Class 55 Watermain 12-Inch	47.000 LF	·	·
0816	SPV.0090 Special 5002. Ductile Iron Hydrant Branch 6-Inch	13.000 LF		·
0818	SPV.0090 Special 5200. 2-Duct Conduit Cement Encased 4-Inch Conduit DB-60	105.000 LF	·	
0820	SPV.0090 Special 5201. 4-Duct Conduit Cement Encased 4-Inch Conduit DB-60	445.000 LF	·	





Page 30 of 31

Federal ID(s): WISC 2025597

SECTION: 0001 Contract Items

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0822	SPV.0090 Special 5202. 6-Duct Conduit Cement Encased 4-Inch Conduit DB-60	133.000 LF	·	·
0824	SPV.0090 Special 5203. 2-Duct Conduit Cement Encased 3-Inch Conduit DB-60	83.000 LF	·	·
0826	SPV.0090 Special 5210. Conduit Subduct 1-Inch	606.000 LF		<u> </u>
0828	SPV.0090 Special 5215. Furnish Municipal Fiber Optic Cable 288 Count	786.000 LF		·
0830	SPV.0090 Special 5216. Install Fiber Optic Cable Outdoor Plant 288-Ct	1,465.000 LF	·	·
0832	SPV.0090 Special 5217. Removing Service Cable	706.000 LF	·	·
0834	SPV.0090 Special 8002. Drain Slotted Vane Permanent	1,793.000 LF	·	·
0836	SPV.0110 Special 4000. Timber Lagging	119.000 MBM		<u> </u>
0838	SPV.0135 Special 0301. Vibration Monitoring	24.000 MON	·	<u> </u>
0840	SPV.0165 Special 0400. Tactile Directional Indicator	600.000 SF		·
0842	SPV.0165 Special 0401. High Friction Traffic Marking Green Bike Lane Panel	70.000 SF		·
0844	SPV.0165 Special 0410. Wall Modular Block Gravity Landscape	762.000 SF		·
0846	SPV.0165 Special 4000. Geocomposite Drain Board	30,533.000 SF		



Page 31 of 31

Federal ID(s): WISC 2025597

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0848	SPV.0165 Special 4100. Temporary Wall Wire Faced Mechanically Stabilized Earth LFCF R-40-767	1,895.000 SF	·	<u></u>
0850	SPV.0165 Special 4761. Wall Concrete Panel Mechanically Stabilized Earth LFCF R- 40-761	4,726.000 SF		<u> </u>
0852	SPV.0165 Special 4767. Wall Concrete Panel Mechanically Stabilized Earth LFCF R- 40-767	21,190.000 SF		·
0854	SPV.0180 Special 0421. HPC Pavement 9-Inch	6,280.000 SY		
0856	SPV.0195 Special 0443. HMA Longitudinal Joint Repair	50.000 TON		:
0858	SPV.0195 Special 0444. HMA Transverse Joint Repair	25.000 TON		
0860	SPV.0195 Special 0446. Management of Solid Waste - St Paul Ave / 27th St	930.000 TON		<u> </u>
0862	SPV.0195 Special 0447. Management of Solid Waste - Greves St, East of 27th St	975.000 TON		
0864	SPV.0195 Special 0448. Management of Solid Waste - Greves St, West of 27th St	510.000 TON		·
0866	204.9060.S Removing (item description) 0002. Removing Bollard	2.000 EACH	·	
	Section: 00	001	Total:	<u> </u>

Total Bid: ______