



Wisconsin Department of Transportation

November 6, 2025

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #15: 1140-00-77, WISC 2026056
New London - Clintonville
Givens Road to Church Road
USH 45
Outagamie & Waupaca Counties

6220-04-76, WISC 2026057
New London – Black Creek
W Jeanne Street to CTH S
STH 54
Waupaca & Outagamie Counties

Letting of November 11, 2025

This is Addendum No. 02, which provides for the following:

Schedule of Items:

Revised Bid Item Quantities – ID 1140-00-77					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Proposal Quantity Change (-)	Proposal Total After Addendum
705.2010	Incentive Air Voids HMA Pavement	DOL	83,750	-4,000	79,750

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
134	1140-00-77 Question #9 (1 page) – Update HMA Mixture Table

Schedule of Items

Attached, dated November 6, 2025, are the revised Schedule of Items Page 18.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:
ID 1140-00-77 Revised: 134.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

END OF ADDENDUM

LOCATION	ROADWAY	STATION	MIXTURE USE:	UNDERLYING SURFACE	BID ITEM	TONS	THICKNESS	QUALITY MANAGEMENT PROGRAM TO BE USED FOR:	
								MIXTURE ACCEPTANCE	DENSITY ACCEPTANCE
DRIVING LANES 12-FOOT	USH 45 NB/SB MAINLINE	802+50 to 1074+03	LOWER LAYER	BASE AGGREGATE	HMA PAVEMENT 3 MT 58-28 S	15980	3.5"	PWL	PWL CORES
DRIVING LANES 12-FOOT	USH 45 NB/SB MAINLINE	1074+03 to 1209+21	LOWER LAYER	BASE AGGREGATE	HMA PAVEMENT 3 MT 58-28 S	5920	3.0"	PWL	PWL CORES
DRIVING LANES 12-FOOT	USH 45 NB/SB MAINLINE	802+50 to 1209+21	LOWER LAYER	HMA PAVEMENT 3 MT 58-28 S	HMA PAVEMENT 3 MT 58-28 S	12390	2.25"	PWL	PWL CORES
DRIVING LANES 12-FOOT	USH 45 NB/SB MAINLINE	802+50 to 1209+21	UPPER LAYER	HMA PAVEMENT 3 MT 58-28 S	HMA PAVEMENT 4 MT 58-28 S	9290	1.75"	PWL	PWL CORES
3-FOOT SHOULDERS	USH 45 NB/SB MAINLINE	802+50 to 1209+21	LOWER LAYER	HMA PAVEMENT 3 MT 58-28 S	HMA PAVEMENT 3 MT 58-28 S	1700	2.25"	PWL	DEPARTMENT ACCEPTANCE CORES
3-FOOT SHOULDERS	USH 45 NB/SB MAINLINE	802+50 to 1209+21	UPPER LAYER	HMA PAVEMENT 3 MT 58-28 S	HMA PAVEMENT 4 MT 58-28 S	1320	1.75"	PWL	DEPARTMENT ACCEPTANCE CORES
INTERSECTIONS	USH 45 NB/SB MAINLINE	802+50 to 1209+21	LOWER LAYER	BASE AGGREGATE	HMA PAVEMENT 3 MT 58-28 S	5720	3.5"	PWL	DEPARTMENT ACCEPTANCE CORES
INTERSECTIONS	USH 45 NB/SB MAINLINE	802+50 to 1209+21	LOWER LAYER	HMA PAVEMENT 3 MT 58-28 S	HMA PAVEMENT 3 MT 58-28 S	3680	2.25"	PWL	DEPARTMENT ACCEPTANCE CORES
INTERSECTIONS	USH 45 NB/SB MAINLINE	802+50 to 1209+21	UPPER LAYER	HMA PAVEMENT 3 MT 58-28 S	HMA PAVEMENT 4 MT 58-28 S	2860	1.75"	PWL	DEPARTMENT ACCEPTANCE CORES
RAB	USH 45 NB/SB MAINLINE	1124+31 to 1138+58	LOWER LAYER	BASE AGGREGATE	HMA PAVEMENT 3 HT 58-28 S	1500	3.0"	DEPARTMENT ACCEPTANCE	DEPARTMENT ACCEPTANCE CORES
RAB	USH 45 NB/SB MAINLINE	1124+31 to 1138+58	LOWER LAYER	HMA PAVEMENT 3 HT 58-28 S	HMA PAVEMENT 3 HT 58-28 S	1390	2.75"	DEPARTMENT ACCEPTANCE	DEPARTMENT ACCEPTANCE CORES
RAB	USH 45 NB/SB MAINLINE	1124+31 to 1138+58	UPPER LAYER	HMA PAVEMENT 3 HT 58-28 S	HMA PAVEMENT 4 HT 58-28 V	1110	2"	DEPARTMENT ACCEPTANCE	DEPARTMENT ACCEPTANCE CORES
RAMP R1	USH 45/STH 54 RAMP	1027+41 to 1043+17	LOWER LAYER	BASE AGGREGATE	HMA PAVEMENT 3 MT 58-28 S	680	3.5"	PWL	DEPARTMENT ACCEPTANCE CORES
RAMP R1	USH 45/STH 54 RAMP	1027+41 to 1043+18	LOWER LAYER	HMA PAVEMENT 3 MT 58-28 S	HMA PAVEMENT 3 MT 58-28 S	440	2.25"	PWL	DEPARTMENT ACCEPTANCE CORES
RAMP R1	USH 45/STH 54 RAMP	1027+41 to 1043+19	UPPER LAYER	HMA PAVEMENT 3 MT 58-28 S	HMA PAVEMENT 4 MT 58-28 S	450	1.75"	PWL	DEPARTMENT ACCEPTANCE CORES
RAMP R2	USH 45/STH 54 RAMP	1033+34 to 1042+45	LOWER LAYER	BASE AGGREGATE	HMA PAVEMENT 3 MT 58-28 S	400	3.5"	PWL	DEPARTMENT ACCEPTANCE CORES
RAMP R2	USH 45/STH 54 RAMP	1033+34 to 1042+46	LOWER LAYER	HMA PAVEMENT 3 MT 58-28 S	HMA PAVEMENT 3 MT 58-28 S	250	2.25"	PWL	DEPARTMENT ACCEPTANCE CORES
RAMP R2	USH 45/STH 54 RAMP	1033+34 to 1042+47	UPPER LAYER	HMA PAVEMENT 3 MT 58-28 S	HMA PAVEMENT 4 MT 58-28 S	230	1.75"	PWL	DEPARTMENT ACCEPTANCE CORES
RAMP R3	USH 45/STH 54 RAMP	1052+12 to 1067+84	LOWER LAYER	BASE AGGREGATE	HMA PAVEMENT 3 MT 58-28 S	670	3.5"	PWL	DEPARTMENT ACCEPTANCE CORES
RAMP R3	USH 45/STH 54 RAMP	1052+12 to 1067+85	LOWER LAYER	HMA PAVEMENT 3 MT 58-28 S	HMA PAVEMENT 3 MT 58-28 S	430	2.25"	PWL	DEPARTMENT ACCEPTANCE CORES
RAMP R3	USH 45/STH 54 RAMP	1052+12 to 1067+86	UPPER LAYER	HMA PAVEMENT 3 MT 58-28 S	HMA PAVEMENT 4 MT 58-28 S	410	1.75"	PWL	DEPARTMENT ACCEPTANCE CORES
RAMP R4	USH 45/STH 54 RAMP	1047+53 to 1069+65	LOWER LAYER	BASE AGGREGATE	HMA PAVEMENT 3 MT 58-28 S	970	3.5"	PWL	DEPARTMENT ACCEPTANCE CORES
RAMP R4	USH 45/STH 54 RAMP	1047+53 to 1069+66	LOWER LAYER	HMA PAVEMENT 3 MT 58-28 S	HMA PAVEMENT 3 MT 58-28 S	620	2.25"	PWL	DEPARTMENT ACCEPTANCE CORES
RAMP R4	USH 45/STH 54 RAMP	1047+53 to 1069+67	UPPER LAYER	HMA PAVEMENT 3 MT 58-28 S	HMA PAVEMENT 4 MT 58-28 S	600	1.75"	PWL	DEPARTMENT ACCEPTANCE CORES

NOTE: DEPARTMENT ACCEPTANCE CORES ARE CUT AND TESTED BY THE CONTRACTOR UNDER THE SUPERVISION OF THE ENGINEER. THE DEPARTMENT WILL MAINTAIN CUSTODY OF THE CORES.



Proposal Schedule of Items

Page 18 of 20

Proposal ID: 20251111015 Project(s): 1140-00-77, 6220-04-76

Federal ID(s): WISC 2026056, WISC 2026057

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0504	658.0500 Pedestrian Push Buttons	8.000 EACH	_____.	_____.
0506	658.5070 Signal Mounting Hardware (location) 01. STH 54 and CTH D	1.000 EACH	_____.	_____.
0508	659.1115 Luminaires Utility LED A	24.000 EACH	_____.	_____.
0510	659.1125 Luminaires Utility LED C	12.000 EACH	_____.	_____.
0512	659.2130 Lighting Control Cabinets 120/240 30- Inch	1.000 EACH	_____.	_____.
0514	661.0201 Temporary Traffic Signals for Intersections (location) 01. STH 54 and CTH D	1.000 EACH	_____.	_____.
0516	690.0150 Sawing Asphalt	27,330.000 LF	_____.	_____.
0518	690.0250 Sawing Concrete	1,325.000 LF	_____.	_____.
0520	705.0105 HMA Percent Within Limits (PWL) Test Strip Volumetrics	2.000 EACH	_____.	_____.
0522	705.2005 Incentive Density PWL HMA Pavement	49,970.000 DOL	1.00000	49,970.00
0524	705.2007 Incentive Density HMA Pavement Longitudinal Joints	16,680.000 DOL	1.00000	16,680.00
0526	705.2010 Incentive Air Voids HMA Pavement	79,750.000 DOL	1.00000	79,750.00
0528	729.0440 Incentive IRI Ride	35,040.000 DOL	1.00000	35,040.00
0530	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	4,500.000 HRS	5.00000	22,500.00

