



Wisconsin Department of Transportation

December 3, 2025

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #03: 1640-03-73, WISC 2026095
Richland Center – Spring Green
Bohmann Drive to CTH O
USH 14
Richland County

1640-03-78, WISC 2026096
C Richland Center, USH 14
STH 80 to Bohmann Drive
USH 14
Richland County

Letting of December 9, 2025

This is Addendum No. 02, which provides for the following:

Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Proposal Quantity Change (-)	Proposal Total After Addendum
205.0100	Common Excavation	CY	63,912	5,319	69,231

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
152	Earthwork Summary table updated to reflect new calculations
350 - 353	Earthwork Data table updated to reflect new calculations

Added Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of why sheet was added)
353A – 353H	Earthwork Data table updated to reflect new calculations

Schedule of Items

Attached, dated December 3, 2025, are the revised Schedule of Items Page 1.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 152 and 350 – 353,

Added: 353A – 353H

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

END OF ADDENDUM

DIVISION	FROM/TO STATION	LOCATION	205.0100 EXCAVATION COMMON		SALVAGED/UNUSABLE PAVEMENT MATERIAL (4)	AVAILABLE MATERIAL (5)	UNEXPANDED FILL	EXPANDED FILL		MASS ORDNATE +/- (7)	WASTE	COMMENT
			CUT (2)	EBS EXCAVATION (3)				(6)	FACTOR 1.25			
DIVISION 1												
STAGE 1	64+58.63/147+51.54		11,700	384	2,361	9,339	0	0		11,651		
DIVISION 1 SUBTOTAL												
			11,700	384	2,361	9,339	0	0		11,651		11,651
DIVISION 2												
STAGE 2	64+59.33/147+41.44		25,400	837	6,265	19,135	210	260		25,103		
DIVISION 2 SUBTOTAL												
			25,400	837	6,265	19,135	210	260		25,103		25,103
DIVISION 3												
STAGE 3	64+60.15/147+63.68		29,800	981	8,557	21,243	570	720		29,026		
DIVISION 3 SUBTOTAL												
			29,800	981	8,557	21,243	570	720		29,026		29,026
GRAND TOTAL			66,900	2,202	17,183	49,717	780	980		65,780		65,780
TOTAL COMMON EXC			69,102									

NOTES:

- (1) COMMON EXCAVATION IS THE SUM OF THE CUT AND EBS EXCAVATION COLUMNS. ITEM NUMBER 205.0100
(2) SALVAGED/UNUSABLE PAVEMENT MATERIAL IS INCLUDED IN CUT.
(3) EBS EXCAVATION TO BE BACKFILLED WITH SELECT BORROW MATERIAL. NOTE: THIS IS DESIGNERS CHOICE, CAN BE BACKFILLED WITH BORROW, OR CUT AS WELL.
(4) SALVAGED/UNUSABLE PAVEMENT MATERIAL
(5) AVAILABLE MATERIAL = CUT - SALVAGED/UNUSABLE PAVEMENT MATERIAL
(6) MARSH EXCAVATION - TO BE BACK FILLED WITH SELECT BORROW MATERIAL. NOTE: THIS IS DESIGNERS CHOICE, CAN BE BACKFILLED WITH BORROW, OR CUT AS WELL. ITEM NUMBER 205.0500
(6) EXPANDED FILL FACTOR = 1.25
DEPENDENT ON SELECTIONS:
OR
OR
OR
(7) THE MASS ORDNATE + OR - QTY CALCULATED FOR THE DIVISION. PLUS QUANTITY INDICATES AN EXCESS OF MATERIAL WITHIN THE DIVISION. MINUS INDICATES A SHORTAGE OF MATERIAL WITHIN THE DIVISION.

EXPANDED FILL = (UNEXPANDED FILL - EXPANDED ROCK - REDUCED MARSH - REDUCED EBS) * FILL FACTOR

EXPANDED FILL = (UNEXPANDED FILL - EXPANDED ROCK - REDUCED EBS) * FILL FACTOR

EXPANDED FILL = (UNEXPANDED FILL - EXPANDED ROCK - REDUCED MARSH) * FILL FACTOR

EXPANDED FILL = (UNEXPANDED FILL - EXPANDED ROCK) * FILL FACTOR

Addendum No. 02
ID 1640-03-73
Revised Sheet 152
December 3, 2025

STAGE 1

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)		CUMULATIVE VOL (CY)		
			CUT	FILL	CUT	FILL	CUT 1.00 NOTE 1	EXPANDED FILL 1.25	MASS ORDNATE
64+58.63	6458.63	0.00	39.91	0.00	0	0	0	0	0
65+00.00	6500.00	41.37	38.12	0.00	60	0	60	0	60
65+50.00	6550.00	50.00	39.68	0.00	72	0	132	0	132
66+00.00	6600.00	50.00	41.12	0.00	75	0	207	0	207
66+50.00	6650.00	50.00	35.57	0.00	71	0	278	0	278
67+00.00	6700.00	50.00	39.61	0.00	70	0	348	0	348
67+50.00	6750.00	50.00	41.51	0.00	75	0	423	0	423
68+00.00	6800.00	50.00	41.56	0.00	77	0	500	0	500
68+50.00	6850.00	50.00	39.27	0.00	75	0	575	0	575
69+00.00	6900.00	50.00	36.87	0.00	70	0	645	0	645
69+50.00	6950.00	50.00	36.22	0.00	68	0	713	0	713
70+00.00	7000.00	50.00	37.96	0.00	69	0	782	0	782
70+50.00	7050.00	50.00	41.58	0.00	74	0	856	0	856
71+00.00	7100.00	50.00	42.48	0.00	78	0	934	0	934
71+50.00	7150.00	50.00	40.46	0.00	77	0	1011	0	1011
72+00.00	7200.00	50.00	37.20	0.00	72	0	1083	0	1083
72+50.00	7250.00	50.00	37.19	0.00	69	0	1152	0	1152
73+00.00	7300.00	50.00	36.80	0.00	69	0	1221	0	1221
73+50.00	7350.00	50.00	36.60	0.00	68	0	1289	0	1289
74+00.00	7400.00	50.00	35.80	0.00	67	0	1356	0	1356
74+50.00	7450.00	50.00	34.76	0.00	65	0	1421	0	1421
75+00.00	7500.00	50.00	33.31	0.00	63	0	1484	0	1484
75+50.00	7550.00	50.00	32.15	0.00	61	0	1545	0	1545
76+00.00	7600.00	50.00	31.00	0.00	58	0	1603	0	1603
76+50.00	7650.00	50.00	30.38	0.00	57	0	1660	0	1660
77+00.00	7700.00	50.00	34.67	0.00	60	0	1720	0	1720
77+50.00	7750.00	50.00	37.22	0.00	67	0	1787	0	1787
78+00.00	7800.00	50.00	38.21	0.00	70	0	1857	0	1857
78+50.00	7850.00	50.00	39.36	0.00	72	0	1929	0	1929
79+00.00	7900.00	50.00	37.48	0.00	71	0	2000	0	2000
79+50.00	7950.00	50.00	35.43	0.00	68	0	2068	0	2068
80+00.00	8000.00	50.00	34.45	0.00	65	0	2133	0	2133
80+50.00	8050.00	50.00	35.97	0.00	65	0	2198	0	2198
81+00.00	8100.00	50.00	37.08	0.00	68	0	2266	0	2266
81+50.00	8150.00	50.00	38.16	0.00	70	0	2336	0	2336
82+00.00	8200.00	50.00	38.46	0.00	71	0	2407	0	2407
82+50.00	8250.00	50.00	38.99	0.00	72	0	2479	0	2479
83+00.00	8300.00	50.00	39.10	0.00	72	0	2551	0	2551
83+50.00	8350.00	50.00	38.95	0.00	72	0	2623	0	2623
84+00.00	8400.00	50.00	42.75	0.00	76	0	2699	0	2699
84+50.00	8450.00	50.00	43.43	0.00	80	0	2779	0	2779
85+00.00	8500.00	50.00	41.19	0.00	78	0	2857	0	2857
85+50.00	8550.00	50.00	40.30	0.00	75	0	2932	0	2932
86+00.00	8600.00	50.00	40.27	0.00	75	0	3007	0	3007
86+50.00	8650.00	50.00	37.55	0.00	72	0	3079	0	3079

NOTES:	
1 - CUT	CUT INCLUDES SALVAGED/UNUSABLE PAVEMENT MATERIAL
2 - FILL	DOES NOT INCLUDE UNUSABLE PAVEMENT EXC. VOLUME

Addendum No. 02
ID 1640-03-73
Revised Sheet 350
December 3, 2025

STAGE 1

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL. (CY) (UNADJUSTED)		CUMULATIVE VOL. (CY)		
			CUT	FILL	CUT	FILL	CUT 1.00 NOTE 1	EXPANDED FILL 1.25	MASS ORDNATE
87+00.00	8700.00	50.00	38.25	0.00	70	0	3149	0	3149
87+50.00	8750.00	50.00	43.40	0.00	76	0	3225	0	3225
88+00.00	8800.00	50.00	43.20	0.00	80	0	3305	0	3305
88+50.00	8850.00	50.00	43.08	0.00	80	0	3385	0	3385
89+00.00	8900.00	50.00	42.79	0.00	80	0	3465	0	3465
89+50.00	8950.00	50.00	37.06	0.00	74	0	3539	0	3539
90+00.00	9000.00	50.00	36.07	0.00	68	0	3607	0	3607
90+50.00	9050.00	50.00	38.68	0.00	69	0	3676	0	3676
91+00.00	9100.00	50.00	38.85	0.00	72	0	3748	0	3748
91+50.00	9150.00	50.00	39.61	0.00	73	0	3821	0	3821
92+00.00	9200.00	50.00	40.64	0.00	74	0	3895	0	3895
92+50.00	9250.00	50.00	40.30	0.00	75	0	3970	0	3970
93+00.00	9300.00	50.00	34.51	0.00	69	0	4039	0	4039
93+50.00	9350.00	50.00	35.18	0.00	65	0	4104	0	4104
94+00.00	9400.00	50.00	37.47	0.00	67	0	4171	0	4171
94+50.00	9450.00	50.00	39.31	0.00	71	0	4242	0	4242
95+00.00	9500.00	50.00	39.81	0.00	73	0	4315	0	4315
95+50.00	9550.00	50.00	38.28	0.00	72	0	4387	0	4387
96+00.00	9600.00	50.00	37.57	0.00	70	0	4457	0	4457
96+50.00	9650.00	50.00	37.69	0.00	70	0	4527	0	4527
97+00.00	9700.00	50.00	38.13	0.00	70	0	4597	0	4597
97+50.00	9750.00	50.00	38.80	0.00	71	0	4668	0	4668
98+00.00	9800.00	50.00	39.26	0.00	72	0	4740	0	4740
98+50.00	9850.00	50.00	39.09	0.00	73	0	4813	0	4813
99+00.00	9900.00	50.00	38.49	0.00	72	0	4885	0	4885
99+50.00	9950.00	50.00	38.52	0.00	71	0	4956	0	4956
100+00.00	10000.00	50.00	38.42	0.00	71	0	5027	0	5027
100+50.00	10050.00	50.00	38.26	0.00	71	0	5098	0	5098
101+00.00	10100.00	50.00	38.56	0.00	71	0	5169	0	5169
101+50.00	10150.00	50.00	38.58	0.00	71	0	5240	0	5240
102+00.00	10200.00	50.00	38.59	0.00	71	0	5311	0	5311
102+50.00	10250.00	50.00	38.34	0.00	71	0	5382	0	5382
103+00.00	10300.00	50.00	38.12	0.00	71	0	5453	0	5453
103+50.00	10350.00	50.00	37.99	0.00	70	0	5523	0	5523
104+00.00	10400.00	50.00	37.61	0.00	70	0	5593	0	5593
104+50.00	10450.00	50.00	37.65	0.00	70	0	5663	0	5663
105+00.00	10500.00	50.00	38.32	0.00	70	0	5733	0	5733
105+50.00	10550.00	50.00	38.60	0.00	71	0	5804	0	5804
106+00.00	10600.00	50.00	38.75	0.00	72	0	5876	0	5876
106+50.00	10650.00	50.00	38.65	0.00	72	0	5948	0	5948
107+00.00	10700.00	50.00	37.96	0.00	71	0	6019	0	6019
107+50.00	10750.00	50.00	38.35	0.00	71	0	6090	0	6090
108+00.00	10800.00	50.00	38.34	0.00	71	0	6161	0	6161
108+50.00	10850.00	50.00	38.41	0.00	71	0	6232	0	6232
109+00.00	10900.00	50.00	38.53	0.00	71	0	6303	0	6303
			NOTES:						
			1 - CUT		CUT INCLUDES SALVAGED/UNUSABLE PAVEMENT MATERIAL				
			2- FILL		DOES NOT INCLUDE UNUSABLE PAVEMENT EXC. VOLUME				

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)		CUMULATIVE VOL (CY)		
			CUT	FILL	CUT	FILL	CUT	EXPANDED FILL	
									1.00 NOTE 1
109+50.00	10950.00	50.00	38.39	0.00	71	0	6374	0	6374
110+00.00	11000.00	50.00	37.93	0.00	71	0	6445	0	6445
110+50.00	11050.00	50.00	37.76	0.00	70	0	6515	0	6515
111+00.00	11100.00	50.00	37.31	0.00	70	0	6585	0	6585
111+50.00	11150.00	50.00	37.46	0.00	69	0	6654	0	6654
112+00.00	11200.00	50.00	37.77	0.00	70	0	6724	0	6724
112+50.00	11250.00	50.00	37.81	0.00	70	0	6794	0	6794
113+00.00	11300.00	50.00	37.74	0.00	70	0	6864	0	6864
113+50.00	11350.00	50.00	38.08	0.00	70	0	6934	0	6934
114+00.00	11400.00	50.00	38.09	0.00	71	0	7005	0	7005
114+50.00	11450.00	50.00	38.08	0.00	71	0	7076	0	7076
115+00.00	11500.00	50.00	37.01	0.00	70	0	7146	0	7146
115+50.00	11550.00	50.00	40.77	0.00	72	0	7218	0	7218
116+00.00	11600.00	50.00	42.96	0.00	78	0	7296	0	7296
116+50.00	11650.00	50.00	41.56	0.00	78	0	7374	0	7374
117+00.00	11700.00	50.00	40.42	0.00	76	0	7450	0	7450
117+50.00	11750.00	50.00	39.80	0.00	74	0	7524	0	7524
118+00.00	11800.00	50.00	38.78	0.00	73	0	7597	0	7597
118+50.00	11850.00	50.00	36.60	0.00	70	0	7667	0	7667
119+00.00	11900.00	50.00	37.53	0.00	69	0	7736	0	7736
119+50.00	11950.00	50.00	39.63	0.00	71	0	7807	0	7807
120+00.00	12000.00	50.00	41.38	0.00	75	0	7882	0	7882
120+50.00	12050.00	50.00	41.23	0.00	76	0	7958	0	7958
121+00.00	12100.00	50.00	41.00	0.00	76	0	8034	0	8034
121+50.00	12150.00	50.00	40.24	0.00	75	0	8109	0	8109
122+00.00	12200.00	50.00	39.61	0.00	74	0	8183	0	8183
122+50.00	12250.00	50.00	39.41	0.00	73	0	8256	0	8256
123+00.00	12300.00	50.00	39.90	0.00	73	0	8329	0	8329
123+50.00	12350.00	50.00	39.23	0.00	73	0	8402	0	8402
124+00.00	12400.00	50.00	39.48	0.00	73	0	8475	0	8475
124+50.00	12450.00	50.00	39.64	0.00	73	0	8548	0	8548
125+00.00	12500.00	50.00	39.72	0.00	73	0	8621	0	8621
125+50.00	12550.00	50.00	39.73	0.00	74	0	8695	0	8695
126+00.00	12600.00	50.00	39.69	0.00	74	0	8769	0	8769
126+50.00	12650.00	50.00	39.34	0.00	73	0	8842	0	8842
127+00.00	12700.00	50.00	39.65	0.00	73	0	8915	0	8915
127+50.00	12750.00	50.00	39.67	0.00	73	0	8988	0	8988
128+00.00	12800.00	50.00	39.22	0.00	73	0	9061	0	9061
128+50.00	12850.00	50.00	39.70	0.00	73	0	9134	0	9134
129+00.00	12900.00	50.00	39.71	0.00	74	0	9208	0	9208
129+50.00	12950.00	50.00	39.26	0.00	73	0	9281	0	9281
130+00.00	13000.00	50.00	35.77	0.00	69	0	9350	0	9350
130+50.00	13050.00	50.00	35.24	0.00	66	0	9416	0	9416
131+00.00	13100.00	50.00	35.60	0.00	66	0	9482	0	9482
131+50.00	13150.00	50.00	36.05	0.00	66	0	9548	0	9548

NOTES:	
1 - CUT	CUT INCLUDES SALVAGED/UNUSABLE PAVEMENT MATERIAL
2 - FILL	DOES NOT INCLUDE UNUSABLE PAVEMENT EXC. VOLUME

Addendum No. 02
ID 1640-03-73
Revised Sheet 352
December 3, 2025

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)		CUMULATIVE VOL (CY)		
			CUT	FILL	CUT	FILL	CUT	EXPANDED FILL 1.25	MASS ORDNATE
132+00.00	13200.00	50.00	35.93	0.00	67	0	9615	0	9615
132+50.00	13250.00	50.00	35.65	0.00	66	0	9681	0	9681
133+00.00	13300.00	50.00	35.25	0.00	66	0	9747	0	9747
133+50.00	13350.00	50.00	35.71	0.00	66	0	9813	0	9813
134+00.00	13400.00	50.00	35.32	0.00	66	0	9879	0	9879
134+50.00	13450.00	50.00	35.67	0.00	66	0	9945	0	9945
135+00.00	13500.00	50.00	35.85	0.00	66	0	10011	0	10011
135+50.00	13550.00	50.00	36.05	0.00	67	0	10078	0	10078
136+00.00	13600.00	50.00	35.95	0.00	67	0	10145	0	10145
136+50.00	13650.00	50.00	34.45	0.00	65	0	10210	0	10210
137+00.00	13700.00	50.00	34.59	0.00	64	0	10274	0	10274
137+50.00	13750.00	50.00	35.63	0.00	65	0	10339	0	10339
138+00.00	13800.00	50.00	36.11	0.00	66	0	10405	0	10405
138+50.00	13850.00	50.00	36.27	0.00	67	0	10472	0	10472
139+00.00	13900.00	50.00	36.31	0.00	67	0	10539	0	10539
139+50.00	13950.00	50.00	35.73	0.00	67	0	10606	0	10606
140+00.00	14000.00	50.00	35.48	0.00	66	0	10672	0	10672
140+50.00	14050.00	50.00	35.43	0.00	66	0	10738	0	10738
141+00.00	14100.00	50.00	35.55	0.00	66	0	10804	0	10804
141+50.00	14150.00	50.00	35.54	0.00	66	0	10870	0	10870
142+00.00	14200.00	50.00	35.72	0.00	66	0	10936	0	10936
142+50.00	14250.00	50.00	36.02	0.00	66	0	11002	0	11002
143+00.00	14300.00	50.00	36.05	0.00	67	0	11069	0	11069
143+50.00	14350.00	50.00	36.39	0.00	67	0	11136	0	11136
144+00.00	14400.00	50.00	35.15	0.00	66	0	11202	0	11202
144+50.00	14450.00	50.00	33.99	0.00	64	0	11266	0	11266
145+00.00	14500.00	50.00	33.52	0.00	63	0	11329	0	11329
145+50.00	14550.00	50.00	36.87	0.00	65	0	11394	0	11394
146+00.00	14600.00	50.00	36.93	0.00	68	0	11462	0	11462
146+50.00	14650.00	50.00	32.82	0.00	65	0	11527	0	11527
147+00.00	14700.00	50.00	33.31	0.00	61	0	11588	0	11588
147+50.00	14750.00	50.00	32.31	0.00	61	0	11649	0	11649
147+51.54	14751.54	1.54	32.25	0.00	2	0	11651	0	11651

NOTES:	
1 - CUT	CUT INCLUDES SALVAGED/UNUSABLE PAVEMENT MATERIAL DOES NOT INCLUDE UNUSABLE PAVEMENT EXC VOLUME
2 - FILL	

Addendum No. 02
ID 1640-03-73
Revised Sheet 353
December 3, 2025

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)		CUMULATIVE VOL (CY)		
			CUT	FILL	CUT	FILL	CUT 1.00 NOTE 1	EXPANDED FILL 1.25	MASS ORDINATE
64+59.33	6459.33	0.00	73.95	0.00	0	0	0	0	0
65+00.00	6500.00	40.67	69.64	0.05	108	0	108	0	108
65+50.00	6550.00	50.00	70.44	0.03	130	0	238	0	238
66+00.00	6600.00	50.00	73.81	0.00	134	0	372	0	372
66+50.00	6650.00	50.00	81.06	0.23	143	0	515	0	515
67+00.00	6700.00	50.00	85.10	0.99	154	1	669	1	668
67+50.00	6750.00	50.00	85.15	0.00	158	1	827	3	825
68+00.00	6800.00	50.00	84.86	0.00	157	0	984	3	982
68+50.00	6850.00	50.00	82.28	0.00	155	0	1139	3	1137
69+00.00	6900.00	50.00	74.21	0.00	145	0	1284	3	1282
69+50.00	6950.00	50.00	72.77	0.00	136	0	1420	3	1418
70+00.00	7000.00	50.00	72.85	0.00	135	0	1555	3	1553
70+50.00	7050.00	50.00	75.56	0.00	137	0	1692	3	1690
71+00.00	7100.00	50.00	76.82	0.00	141	0	1833	3	1831
71+50.00	7150.00	50.00	76.29	0.00	142	0	1975	3	1973
72+00.00	7200.00	50.00	79.91	0.00	145	0	2120	3	2118
72+50.00	7250.00	50.00	80.66	0.00	149	0	2269	3	2267
73+00.00	7300.00	50.00	79.85	0.00	149	0	2418	3	2416
73+50.00	7350.00	50.00	79.93	0.00	148	0	2566	3	2564
74+00.00	7400.00	50.00	77.77	0.00	146	0	2712	3	2710
74+50.00	7450.00	50.00	75.47	0.00	142	0	2854	3	2852
75+00.00	7500.00	50.00	72.81	0.00	137	0	2991	3	2989
75+50.00	7550.00	50.00	71.61	0.00	134	0	3125	3	3123
76+00.00	7600.00	50.00	69.51	0.00	131	0	3256	3	3254
76+50.00	7650.00	50.00	71.60	0.00	131	0	3387	3	3385
77+00.00	7700.00	50.00	75.53	0.00	136	0	3523	3	3521
77+50.00	7750.00	50.00	79.90	0.00	144	0	3667	3	3665
78+00.00	7800.00	50.00	78.69	0.00	147	0	3814	3	3812
78+50.00	7850.00	50.00	77.97	0.00	145	0	3959	3	3957
79+00.00	7900.00	50.00	76.31	0.00	143	0	4102	3	4100
79+50.00	7950.00	50.00	72.97	0.00	138	0	4240	3	4238
80+00.00	8000.00	50.00	71.61	0.03	134	0	4374	3	4372
80+50.00	8050.00	50.00	71.03	0.01	132	0	4506	3	4504
81+00.00	8100.00	50.00	70.33	0.01	131	0	4637	3	4635
81+50.00	8150.00	50.00	69.00	0.02	129	0	4766	3	4764
82+00.00	8200.00	50.00	68.46	0.01	127	0	4893	3	4891
82+50.00	8250.00	50.00	70.12	0.07	128	0	5021	3	5019
83+00.00	8300.00	50.00	72.04	0.00	132	0	5153	3	5151
83+50.00	8350.00	50.00	71.58	0.00	133	0	5286	3	5284
84+00.00	8400.00	50.00	82.45	0.00	143	0	5429	3	5427
84+50.00	8450.00	50.00	91.59	0.00	161	0	5590	3	5588
85+00.00	8500.00	50.00	98.12	0.00	176	0	5766	3	5764
85+50.00	8550.00	50.00	98.90	0.00	182	0	5948	3	5946
86+00.00	8600.00	50.00	79.83	0.00	165	0	6113	3	6111
86+50.00	8650.00	50.00	78.79	0.00	147	0	6260	3	6258

NOTES:	
1- CUT	CUT INCLUDES SALVAGED/UNUSABLE PAVEMENT MATERIAL
2- FILL	DOES NOT INCLUDE UNUSABLE PAVEMENT EXC. VOLUME

Addendum No. 02
ID 1640-03-73
Added Sheet 353A
December 3, 2025

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)		CUMULATIVE VOL (CY)		
			CUT	FILL	CUT	FILL	CUT	EXPANDED FILL	MASS ORDNATE
					NOTE 1	NOTE 2	NOTE 1	1.25	
87+00.00	8700.00	50.00	78.30	0.00	145	0	6405	3	6403
87+50.00	8750.00	50.00	110.98	0.00	175	0	6580	3	6578
88+00.00	8800.00	50.00	103.20	0.00	198	0	6778	3	6776
88+50.00	8850.00	50.00	98.25	0.00	187	0	6965	3	6963
89+00.00	8900.00	50.00	100.61	0.00	184	0	7149	3	7147
89+50.00	8950.00	50.00	101.79	0.00	187	0	7336	3	7334
90+00.00	9000.00	50.00	99.74	0.00	187	0	7523	3	7521
90+50.00	9050.00	50.00	97.54	0.00	183	0	7706	3	7704
91+00.00	9100.00	50.00	92.70	0.00	176	0	7882	3	7880
91+50.00	9150.00	50.00	86.85	0.00	166	0	8048	3	8046
92+00.00	9200.00	50.00	83.09	1.01	157	1	8205	4	8201
92+50.00	9250.00	50.00	83.18	0.02	154	1	8359	5	8354
93+00.00	9300.00	50.00	79.29	19.95	150	18	8509	28	8482
93+50.00	9350.00	50.00	83.54	1.93	151	20	8660	53	8608
94+00.00	9400.00	50.00	89.25	2.38	160	4	8820	58	8763
94+50.00	9450.00	50.00	95.84	1.09	171	3	8991	61	8930
95+00.00	9500.00	50.00	98.17	0.00	180	1	9171	63	9109
95+50.00	9550.00	50.00	95.97	0.00	180	0	9351	63	9289
96+00.00	9600.00	50.00	97.55	0.00	179	0	9530	63	9468
96+50.00	9650.00	50.00	97.12	0.00	180	0	9710	63	9648
97+00.00	9700.00	50.00	99.16	0.00	182	0	9892	63	9830
97+50.00	9750.00	50.00	100.33	0.00	185	0	10077	63	10015
98+00.00	9800.00	50.00	100.63	0.00	186	0	10263	63	10201
98+50.00	9850.00	50.00	99.51	0.00	185	0	10448	63	10386
99+00.00	9900.00	50.00	96.89	0.00	182	0	10630	63	10568
99+50.00	9950.00	50.00	97.75	0.00	180	0	10810	63	10748
100+00.00	10000.00	50.00	98.38	0.00	182	0	10992	63	10930
100+50.00	10050.00	50.00	99.03	0.00	183	0	11175	63	11113
101+00.00	10100.00	50.00	98.02	0.00	182	0	11357	63	11295
101+50.00	10150.00	50.00	96.22	0.00	180	0	11537	63	11475
102+00.00	10200.00	50.00	99.85	0.00	182	0	11719	63	11657
102+50.00	10250.00	50.00	103.27	0.00	188	0	11907	63	11845
103+00.00	10300.00	50.00	102.05	0.00	190	0	12097	63	12035
103+50.00	10350.00	50.00	103.35	0.00	190	0	12287	63	12225
104+00.00	10400.00	50.00	70.57	0.00	161	0	12448	63	12386
104+50.00	10450.00	50.00	67.31	0.00	128	0	12576	63	12514
105+00.00	10500.00	50.00	71.31	0.01	128	0	12704	63	12642
105+50.00	10550.00	50.00	72.93	0.00	134	0	12838	63	12776
106+00.00	10600.00	50.00	73.17	0.00	135	0	12973	63	12911
106+50.00	10650.00	50.00	72.71	0.01	135	0	13108	63	13046
107+00.00	10700.00	50.00	72.11	0.01	134	0	13242	63	13180
107+50.00	10750.00	50.00	73.07	0.00	134	0	13376	63	13314
108+00.00	10800.00	50.00	72.21	0.01	135	0	13511	63	13449
108+50.00	10850.00	50.00	72.53	0.01	134	0	13645	63	13583
109+00.00	10900.00	50.00	72.87	0.00	135	0	13780	63	13718

NOTES:	
1 - CUT	CUT INCLUDES SALVAGED/UNUSABLE PAVEMENT MATERIAL
2 - FILL	DOES NOT INCLUDE UNUSABLE PAVEMENT EXC. VOLUME

Addendum No. 02
ID 1640-03-73
Added Sheet 353B
December 3, 2025

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)				CUMULATIVE VOL (CY)	
			CUT	FILL	CUT	FILL	CUT	EXPANDED FILL		
									NOTE 1	NOTE 2
109+50.00	10950.00	50.00	70.98	0.00	133	0	13913	63	13851	
110+00.00	11000.00	50.00	69.73	0.02	130	0	14043	63	13981	
110+50.00	11050.00	50.00	71.13	0.01	130	0	14173	63	14111	
111+00.00	11100.00	50.00	71.50	0.01	132	0	14305	63	14243	
111+50.00	11150.00	50.00	70.42	0.02	131	0	14436	63	14374	
112+00.00	11200.00	50.00	71.16	0.00	131	0	14567	63	14505	
112+50.00	11250.00	50.00	70.61	0.02	131	0	14698	63	14636	
113+00.00	11300.00	50.00	70.37	0.02	131	0	14829	63	14767	
113+50.00	11350.00	50.00	71.22	0.02	131	0	14960	63	14898	
114+00.00	11400.00	50.00	70.50	0.00	131	0	15091	63	15029	
114+50.00	11450.00	50.00	71.19	0.01	131	0	15222	63	15160	
115+00.00	11500.00	50.00	70.62	0.02	131	0	15353	63	15291	
115+50.00	11550.00	50.00	70.95	0.01	131	0	15484	63	15422	
116+00.00	11600.00	50.00	70.81	0.00	131	0	15615	63	15553	
116+50.00	11650.00	50.00	71.10	0.02	131	0	15746	63	15684	
117+00.00	11700.00	50.00	71.15	0.00	132	0	15878	63	15816	
117+50.00	11750.00	50.00	73.78	0.00	134	0	16012	63	15950	
118+00.00	11800.00	50.00	62.08	0.00	126	0	16138	63	16076	
118+50.00	11850.00	50.00	59.98	0.00	113	0	16251	63	16189	
119+00.00	11900.00	50.00	60.18	0.00	111	0	16362	63	16300	
119+50.00	11950.00	50.00	72.68	0.00	123	0	16485	63	16423	
120+00.00	12000.00	50.00	72.99	0.01	135	0	16620	63	16558	
120+50.00	12050.00	50.00	70.52	0.00	133	0	16753	63	16691	
121+00.00	12100.00	50.00	67.67	0.02	128	0	16881	63	16819	
121+50.00	12150.00	50.00	70.38	0.00	128	0	17009	63	16947	
122+00.00	12200.00	50.00	72.89	0.04	133	0	17142	63	17080	
122+50.00	12250.00	50.00	72.65	0.02	135	0	17277	63	17215	
123+00.00	12300.00	50.00	72.24	0.01	134	0	17411	63	17349	
123+50.00	12350.00	50.00	71.40	0.03	133	0	17544	63	17482	
124+00.00	12400.00	50.00	74.24	0.01	135	0	17679	63	17617	
124+50.00	12450.00	50.00	76.72	0.00	140	0	17819	63	17757	
125+00.00	12500.00	50.00	77.18	0.00	142	0	17961	63	17899	
125+50.00	12550.00	50.00	76.05	0.03	142	0	18103	63	18041	
126+00.00	12600.00	50.00	79.83	0.00	144	0	18247	63	18185	
126+50.00	12650.00	50.00	80.60	0.00	149	0	18396	63	18334	
127+00.00	12700.00	50.00	78.95	0.00	148	0	18544	63	18482	
127+50.00	12750.00	50.00	76.20	0.06	144	0	18688	63	18626	
128+00.00	12800.00	50.00	75.62	0.00	141	0	18829	63	18767	
128+50.00	12850.00	50.00	75.92	0.00	140	0	18969	63	18907	
129+00.00	12900.00	50.00	74.38	0.04	139	0	19108	63	19046	
129+50.00	12950.00	50.00	71.63	0.03	135	0	19243	63	19181	
130+00.00	13000.00	50.00	90.48	0.00	150	0	19393	63	19331	
130+50.00	13050.00	50.00	95.88	0.00	173	0	19566	63	19504	
131+00.00	13100.00	50.00	98.51	0.00	180	0	19746	63	19684	
131+50.00	13150.00	50.00	98.03	0.00	182	0	19928	63	19866	

NOTES:	
1 - CUT	CUT INCLUDES SALVAGED/UNUSABLE PAVEMENT MATERIAL
2 - FILL	DOES NOT INCLUDE UNUSABLE PAVEMENT EXC. VOLUME

Addendum No. 02
ID 1640-03-73
Added Sheet 353C
December 3, 2025

STAGE 2

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)		CUMULATIVE VOL (CY)		
			CUT	FILL	CUT	FILL	CUT	EXPANDED FILL	MASS ORDNATE
132+00.00	13200.00	50.00	96.41	0.00	180	0	20108	63	20046
132+50.00	13250.00	50.00	96.21	0.00	178	0	20286	63	20224
133+00.00	13300.00	50.00	96.16	0.00	178	0	20464	63	20402
133+50.00	13350.00	50.00	94.68	0.00	177	0	20641	63	20579
134+00.00	13400.00	50.00	94.03	4.38	175	4	20816	68	20749
134+50.00	13450.00	50.00	94.34	3.59	174	7	20990	76	20914
135+00.00	13500.00	50.00	96.45	0.00	177	3	21167	80	21087
135+50.00	13550.00	50.00	97.41	0.00	180	0	21347	80	21267
136+00.00	13600.00	50.00	93.27	1.30	177	1	21524	81	21443
136+50.00	13650.00	50.00	88.87	31.33	169	30	21693	119	21574
137+00.00	13700.00	50.00	90.59	19.51	166	47	21859	178	21682
137+50.00	13750.00	50.00	84.46	0.00	162	18	22021	200	21821
138+00.00	13800.00	50.00	94.59	4.42	166	4	22187	205	21982
138+50.00	13850.00	50.00	95.74	6.90	176	10	22363	218	22146
139+00.00	13900.00	50.00	95.53	3.66	177	10	22540	230	22310
139+50.00	13950.00	50.00	95.03	4.42	176	7	22716	239	22477
140+00.00	14000.00	50.00	95.01	1.30	176	5	22892	245	22647
140+50.00	14050.00	50.00	96.72	0.00	178	1	23070	246	22824
141+00.00	14100.00	50.00	101.69	0.00	184	0	23254	246	23008
141+50.00	14150.00	50.00	96.09	0.00	183	0	23437	246	23191
142+00.00	14200.00	50.00	95.85	0.00	178	0	23615	246	23369
142+50.00	14250.00	50.00	97.74	0.00	179	0	23794	246	23548
143+00.00	14300.00	50.00	79.81	0.00	164	0	23958	246	23712
143+50.00	14350.00	50.00	96.83	3.63	164	3	24122	250	23872
144+00.00	14400.00	50.00	96.26	0.00	179	3	24301	254	24047
144+50.00	14450.00	50.00	94.69	0.00	177	0	24478	254	24224
145+00.00	14500.00	50.00	97.38	0.00	178	0	24656	254	24402
145+50.00	14550.00	50.00	102.21	0.00	185	0	24841	254	24587
146+00.00	14600.00	50.00	87.70	0.00	176	0	25017	254	24763
146+50.00	14650.00	50.00	60.61	0.00	137	0	25154	254	24900
147+00.00	14700.00	50.00	59.46	0.00	111	0	25265	254	25011
147+41.44	14741.44	41.44	60.09	0.00	92	0	25357	254	25103

NOTES:	
1- CUT	CUT INCLUDES SALVAGED/UNUSABLE PAVEMENT MATERIAL
2- FILL	DOES NOT INCLUDE UNUSABLE PAVEMENT EXC. VOLUME

Addendum No. 02
ID 1640-03-73
Added Sheet 353D
December 3, 2025

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)		CUMULATIVE VOL (CY)		
			CUT	FILL	CUT	FILL	CUT 1.00 NOTE 1	EXPANDED FILL 1.25	MASS ORDNATE
64+60.15	6460.15	0.00	99.67	0.07	0	0	0	0	0
65+00.00	6500.00	39.85	97.74	0.10	146	0	146	0	146
65+50.00	6550.00	50.00	99.58	0.09	183	0	329	0	329
66+00.00	6600.00	50.00	105.97	0.00	190	0	519	0	519
66+50.00	6650.00	50.00	59.53	0.00	153	0	672	0	672
67+00.00	6700.00	50.00	62.43	0.00	113	0	785	0	785
67+50.00	6750.00	50.00	61.73	0.00	115	0	900	0	900
68+00.00	6800.00	50.00	101.10	0.00	151	0	1051	0	1051
68+50.00	6850.00	50.00	87.18	0.03	174	0	1225	0	1225
69+00.00	6900.00	50.00	83.68	0.00	158	0	1383	0	1383
69+50.00	6950.00	50.00	81.65	0.00	153	0	1536	0	1536
70+00.00	7000.00	50.00	80.49	0.00	150	0	1686	0	1686
70+50.00	7050.00	50.00	87.86	0.00	156	0	1842	0	1842
71+00.00	7100.00	50.00	90.77	0.00	165	0	2007	0	2007
71+50.00	7150.00	50.00	93.77	0.00	171	0	2178	0	2178
72+00.00	7200.00	50.00	95.32	0.00	175	0	2353	0	2353
72+50.00	7250.00	50.00	93.64	0.13	175	0	2528	0	2528
73+00.00	7300.00	50.00	92.80	0.00	173	0	2701	0	2701
73+50.00	7350.00	50.00	91.35	0.07	171	0	2872	0	2872
74+00.00	7400.00	50.00	89.37	1.85	167	2	3039	3	3037
74+50.00	7450.00	50.00	87.49	0.62	164	2	3203	5	3198
75+00.00	7500.00	50.00	84.26	1.75	159	2	3362	8	3355
75+50.00	7550.00	50.00	80.81	0.18	153	2	3515	10	3505
76+00.00	7600.00	50.00	77.16	1.39	146	1	3661	11	3650
76+50.00	7650.00	50.00	73.54	1.09	140	2	3801	14	3787
77+00.00	7700.00	50.00	66.35	0.00	130	1	3931	15	3916
77+50.00	7750.00	50.00	115.87	0.00	169	0	4100	15	4085
78+00.00	7800.00	50.00	119.20	0.00	218	0	4318	15	4303
78+50.00	7850.00	50.00	136.84	0.00	237	0	4555	15	4540
79+00.00	7900.00	50.00	95.40	0.00	215	0	4770	15	4755
79+50.00	7950.00	50.00	109.46	0.07	190	0	4960	15	4945
80+00.00	8000.00	50.00	77.72	0.00	173	0	5133	15	5118
80+50.00	8050.00	50.00	81.95	0.15	148	0	5281	15	5266
81+00.00	8100.00	50.00	92.32	0.00	161	0	5442	15	5427
81+50.00	8150.00	50.00	100.63	0.00	179	0	5621	15	5606
82+00.00	8200.00	50.00	101.21	0.00	187	0	5808	15	5793
82+50.00	8250.00	50.00	103.23	0.00	189	0	5997	15	5982
83+00.00	8300.00	50.00	96.63	0.00	185	0	6182	15	6167
83+50.00	8350.00	50.00	103.56	0.00	185	0	6367	15	6352
84+00.00	8400.00	50.00	106.86	0.00	195	0	6562	15	6547
84+50.00	8450.00	50.00	108.51	0.00	199	0	6761	15	6746
85+00.00	8500.00	50.00	107.41	0.00	200	0	6961	15	6946
85+50.00	8550.00	50.00	103.62	0.01	195	0	7156	15	7141
86+00.00	8600.00	50.00	104.96	0.00	193	0	7349	15	7334
86+50.00	8650.00	50.00	105.66	0.00	195	0	7544	15	7529

NOTES:	
1 - CUT	CUT INCLUDES SALVAGED/UNUSABLE PAVEMENT MATERIAL
2 - FILL	DOES NOT INCLUDE UNUSABLE PAVEMENT EXC. VOLUME

Addendum No. 02
ID 1640-03-73
Added Sheet 353E
December 3, 2025

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)				CUMULATIVE VOL (CY)	
			CUT	FILL	CUT	FILL	CUT 1.00 NOTE 1	EXPANDED FILL 1.25	MASS ORDNATE	
87+00.00	8700.00	50.00	79.57	0.00	172	0	7716	15	7701	
87+50.00	8750.00	50.00	100.42	0.02	167	0	7883	15	7868	
88+00.00	8800.00	50.00	99.62	0.65	185	1	8068	16	8052	
88+50.00	8850.00	50.00	99.22	1.07	184	2	8252	19	8233	
89+00.00	8900.00	50.00	91.07	1.01	176	2	8428	21	8407	
89+50.00	8950.00	50.00	79.93	0.00	158	1	8586	23	8564	
90+00.00	9000.00	50.00	78.52	0.00	147	0	8733	23	8711	
90+50.00	9050.00	50.00	101.59	0.16	167	0	8900	23	8878	
91+00.00	9100.00	50.00	100.70	0.00	187	0	9087	23	9065	
91+50.00	9150.00	50.00	98.92	0.22	185	0	9272	23	9250	
92+00.00	9200.00	50.00	96.50	1.52	181	2	9453	25	9428	
92+50.00	9250.00	50.00	94.75	3.51	177	5	9630	31	9599	
93+00.00	9300.00	50.00	78.93	3.32	161	6	9791	39	9752	
93+50.00	9350.00	50.00	71.01	0.00	139	3	9930	43	9888	
94+00.00	9400.00	50.00	96.77	0.59	155	1	10085	44	10041	
94+50.00	9450.00	50.00	79.40	0.00	163	1	10248	45	10203	
95+00.00	9500.00	50.00	108.14	1.79	174	2	10422	48	10375	
95+50.00	9550.00	50.00	84.00	0.00	178	2	10600	50	10550	
96+00.00	9600.00	50.00	94.67	0.28	165	0	10765	50	10715	
96+50.00	9650.00	50.00	102.61	0.01	183	0	10948	50	10898	
97+00.00	9700.00	50.00	80.66	0.00	170	0	11118	50	11068	
97+50.00	9750.00	50.00	101.98	3.74	169	3	11287	54	11233	
98+00.00	9800.00	50.00	99.82	0.21	187	4	11474	59	11415	
98+50.00	9850.00	50.00	87.78	0.51	174	1	11648	60	11588	
99+00.00	9900.00	50.00	80.51	0.00	156	0	11804	60	11744	
99+50.00	9950.00	50.00	102.28	1.33	169	1	11973	61	11912	
100+00.00	10000.00	50.00	101.71	4.17	189	5	12162	68	12095	
100+50.00	10050.00	50.00	101.28	5.50	188	9	12350	79	12271	
101+00.00	10100.00	50.00	80.62	0.00	168	5	12518	85	12433	
101+50.00	10150.00	50.00	85.72	0.89	154	1	12672	86	12586	
102+00.00	10200.00	50.00	98.38	0.00	170	1	12842	88	12755	
102+50.00	10250.00	50.00	98.31	1.53	182	1	13024	89	12935	
103+00.00	10300.00	50.00	98.00	0.02	182	1	13206	90	13116	
103+50.00	10350.00	50.00	96.18	4.38	180	4	13386	95	13291	
104+00.00	10400.00	50.00	97.51	0.00	179	4	13565	100	13465	
104+50.00	10450.00	50.00	98.26	0.00	181	0	13746	100	13646	
105+00.00	10500.00	50.00	105.03	0.00	188	0	13934	100	13834	
105+50.00	10550.00	50.00	104.37	0.32	194	0	14128	100	14028	
106+00.00	10600.00	50.00	103.24	0.00	192	0	14320	100	14220	
106+50.00	10650.00	50.00	102.30	0.00	190	0	14510	100	14410	
107+00.00	10700.00	50.00	103.24	0.00	190	0	14700	100	14600	
107+50.00	10750.00	50.00	106.69	0.00	194	0	14894	100	14794	
108+00.00	10800.00	50.00	95.70	0.00	187	0	15081	100	14981	
108+50.00	10850.00	50.00	104.00	0.00	185	0	15266	100	15166	
109+00.00	10900.00	50.00	106.54	0.00	195	0	15461	100	15361	

NOTES:	
1 - CUT	CUT INCLUDES SALVAGED/UNUSABLE PAVEMENT MATERIAL
2 - FILL	DOES NOT INCLUDE UNUSABLE PAVEMENT EXC. VOLUME

Addendum No. 02
ID 1640-03-73
Added Sheet 353F
December 3, 2025

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)		CUMULATIVE VOL (CY)		
			CUT	FILL	CUT	FILL	CUT 1.00 NOTE 1	EXPANDED FILL 1.25	MASS ORDINATE
109+50.00	10950.00	50.00	110.86	0.00	201	0	15662	100	15562
110+00.00	11000.00	50.00	99.78	0.00	195	0	15857	100	15757
110+50.00	11050.00	50.00	109.83	0.00	194	0	16051	100	15951
111+00.00	11100.00	50.00	110.51	0.00	204	0	16255	100	16155
111+50.00	11150.00	50.00	97.19	0.00	192	0	16447	100	16347
112+00.00	11200.00	50.00	108.09	0.00	190	0	16637	100	16537
112+50.00	11250.00	50.00	103.55	8.82	196	8	16833	110	16723
113+00.00	11300.00	50.00	102.92	11.48	191	19	17024	134	16890
113+50.00	11350.00	50.00	102.15	11.00	190	21	17214	160	17054
114+00.00	11400.00	50.00	101.98	9.70	189	19	17403	184	17219
114+50.00	11450.00	50.00	102.95	7.10	190	16	17593	204	17389
115+00.00	11500.00	50.00	103.10	11.84	191	18	17784	226	17558
115+50.00	11550.00	50.00	105.65	10.25	193	20	17977	251	17726
116+00.00	11600.00	50.00	107.86	2.49	198	12	18175	266	17909
116+50.00	11650.00	50.00	109.33	4.06	201	6	18376	274	18102
117+00.00	11700.00	50.00	108.60	3.91	202	7	18578	283	18296
117+50.00	11750.00	50.00	108.44	5.44	201	9	18779	294	18485
118+00.00	11800.00	50.00	114.88	0.00	207	5	18986	300	18686
118+50.00	11850.00	50.00	75.81	0.00	177	0	19163	300	18863
119+00.00	11900.00	50.00	92.63	0.54	156	1	19319	301	19018
119+50.00	11950.00	50.00	104.09	0.32	182	1	19501	303	19199
120+00.00	12000.00	50.00	101.42	5.91	190	6	19691	310	19381
120+50.00	12050.00	50.00	101.05	14.08	187	19	19878	334	19544
121+00.00	12100.00	50.00	98.11	11.49	184	24	20062	364	19698
121+50.00	12150.00	50.00	95.12	4.37	179	15	20241	383	19859
122+00.00	12200.00	50.00	104.60	9.75	185	13	20426	399	20027
122+50.00	12250.00	50.00	110.82	0.00	199	9	20625	410	20215
123+00.00	12300.00	50.00	110.32	0.00	205	0	20830	410	20420
123+50.00	12350.00	50.00	109.07	0.00	203	0	21033	410	20623
124+00.00	12400.00	50.00	112.43	0.00	205	0	21238	410	20828
124+50.00	12450.00	50.00	112.70	0.00	208	0	21446	410	21036
125+00.00	12500.00	50.00	114.79	0.00	211	0	21657	410	21247
125+50.00	12550.00	50.00	118.82	0.00	216	0	21873	410	21463
126+00.00	12600.00	50.00	119.09	0.00	220	0	22093	410	21683
126+50.00	12650.00	50.00	117.60	0.00	219	0	22312	410	21902
127+00.00	12700.00	50.00	114.27	0.00	215	0	22527	410	22117
127+50.00	12750.00	50.00	101.24	0.00	200	0	22727	410	22317
128+00.00	12800.00	50.00	106.09	0.00	192	0	22919	410	22509
128+50.00	12850.00	50.00	108.03	0.00	198	0	23117	410	22707
129+00.00	12900.00	50.00	108.29	0.00	200	0	23317	410	22907
129+50.00	12950.00	50.00	106.84	0.00	199	0	23516	410	23106
130+00.00	13000.00	50.00	92.64	12.97	185	12	23701	425	23276
130+50.00	13050.00	50.00	92.46	4.17	171	16	23872	445	23427
131+00.00	13100.00	50.00	92.25	0.01	171	4	24043	450	23593
131+50.00	13150.00	50.00	91.84	0.06	170	0	24213	450	23763

NOTES:	
1 - CUT	CUT INCLUDES SALVAGED/UNUSABLE PAVEMENT MATERIAL
2 - FILL	DOES NOT INCLUDE UNUSABLE PAVEMENT EXC. VOLUME

Addendum No. 02
ID 1640-03-73
Added Sheet 353G
December 3, 2025

STAGE 3

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)		CUMULATIVE VOL (CY)		
			CUT	FILL	CUT	FILL	CUT	EXPANDED FILL	MASS ORDNATE
132+00.00	13200.00	50.00	93.03	0.48	171	0	24384	450	23934
132+50.00	13250.00	50.00	91.72	3.89	171	4	24555	455	24100
133+00.00	13300.00	50.00	91.39	6.40	170	10	24725	468	24258
133+50.00	13350.00	50.00	90.51	4.11	168	10	24893	480	24413
134+00.00	13400.00	50.00	90.85	0.02	168	4	25061	485	24576
134+50.00	13450.00	50.00	90.87	0.00	168	0	25229	485	24744
135+00.00	13500.00	50.00	89.49	4.37	167	4	25396	490	24906
135+50.00	13550.00	50.00	87.70	18.24	164	21	25560	516	25044
136+00.00	13600.00	50.00	86.90	25.42	162	40	25722	566	25156
136+50.00	13650.00	50.00	86.63	14.53	161	37	25883	613	25271
137+00.00	13700.00	50.00	87.05	20.89	161	33	26044	654	25390
137+50.00	13750.00	50.00	90.00	0.00	164	19	26208	678	25531
138+00.00	13800.00	50.00	92.38	11.10	169	10	26377	690	25687
138+50.00	13850.00	50.00	91.40	1.43	170	12	26547	705	25842
139+00.00	13900.00	50.00	91.21	0.03	169	1	26716	706	26010
139+50.00	13950.00	50.00	90.25	1.98	168	2	26884	709	26175
140+00.00	14000.00	50.00	89.74	0.00	167	2	27051	711	26340
140+50.00	14050.00	50.00	90.10	0.00	167	0	27218	711	26507
141+00.00	14100.00	50.00	91.42	0.00	168	0	27386	711	26675
141+50.00	14150.00	50.00	93.28	0.00	171	0	27557	711	26846
142+00.00	14200.00	50.00	95.21	0.00	175	0	27732	711	27021
142+50.00	14250.00	50.00	103.42	0.00	184	0	27916	711	27205
143+00.00	14300.00	50.00	97.94	0.00	186	0	28102	711	27391
143+50.00	14350.00	50.00	95.09	0.00	179	0	28281	711	27570
144+00.00	14400.00	50.00	104.58	0.00	185	0	28466	711	27755
144+50.00	14450.00	50.00	104.93	0.00	194	0	28660	711	27949
145+00.00	14500.00	50.00	111.09	0.00	200	0	28860	711	28149
145+50.00	14550.00	50.00	105.88	0.00	201	0	29061	711	28350
146+00.00	14600.00	50.00	106.75	0.00	197	0	29258	711	28547
146+50.00	14650.00	50.00	102.02	0.00	193	0	29451	711	28740
147+00.00	14700.00	50.00	62.22	0.00	152	0	29603	711	28892
147+50.00	14750.00	50.00	58.55	0.00	112	0	29715	711	29004
147+63.68	14763.68	13.68	29.29	0.00	22	0	29737	711	29026

NOTES:	
1 - CUT	CUT INCLUDES SALVAGED/UNUSABLE PAVEMENT MATERIAL
2 - FILL	DOES NOT INCLUDE UNUSABLE PAVEMENT EXC VOLUME

Addendum No. 02
ID 1640-03-73
Added Sheet 353H
December 3, 2025



Proposal Schedule of Items

Page 1 of 17

Proposal ID: 20251209003 Project(s): 1640-03-73, 1640-03-78

Federal ID(s): WISC 2026095, WISC 2026096

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	203.0100 Removing Small Pipe Culverts	1.000 EACH	_____.	_____.
0004	204.0100 Removing Concrete Pavement	68,814.000 SY	_____.	_____.
0006	204.0110 Removing Asphaltic Surface	640.000 SY	_____.	_____.
0008	204.0150 Removing Curb & Gutter	1,748.000 LF	_____.	_____.
0010	204.0155 Removing Concrete Sidewalk	1,471.000 SY	_____.	_____.
0012	204.0165 Removing Guardrail	614.000 LF	_____.	_____.
0014	204.0195 Removing Concrete Bases	54.000 EACH	_____.	_____.
0016	204.9060.S Removing (item description) 02. Traffic Signals	52.000 EACH	_____.	_____.
0018	205.0100 Excavation Common	69,231.000 CY	_____.	_____.
0020	209.2500 Backfill Granular Grade 2	820.000 TON	_____.	_____.
0022	213.0100 Finishing Roadway (project) 01. 1640-03-73	1.000 EACH	_____.	_____.
0024	213.0100 Finishing Roadway (project) 02. 1640-03-78	1.000 EACH	_____.	_____.
0026	305.0110 Base Aggregate Dense 3/4-Inch	140.000 TON	_____.	_____.
0028	305.0120 Base Aggregate Dense 1 1/4-Inch	27,281.000 TON	_____.	_____.
0030	312.0110 Select Crushed Material	69,076.000 TON	_____.	_____.