



Wisconsin Department of Transportation

July 2, 2026

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #04: 2030-10-71, WISC 2026378
N Mayfair Rd/N Lovers Ln
W Burleigh St to W Silver Spring Dr
STH 100
Milwaukee County

Letting of July 14, 2026

This is Addendum No. 01, which provides for the following:

Special Provisions:

Revised Special Provisions	
Article No.	Description
3	Prosecution and Progress.
7	Utilities.
9	Other Contracts.
70	Temporary Causeway, Item SPV.0060.13.

Added Special Provisions	
Article No.	Description
94	Coordination with Businesses and Residents.

Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Proposal Quantity Change (-)	Proposal Total After Addendum
416.0620	Drilled Dowel Bars	EACH	6,408	8,300	14,708
690.0250	Sawing Concrete	LF	8,638	23,958	32,596

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
23	Construction Detail – Causeway: Included underground utilities within the area of the temporary causeway along with the approximate location of the temporary utility poles and line along the west side of STH 100 that will be installed prior to construction.
225	Utility Plan: Adjusted approximate location of and included an additional existing We Energies gas main and added labels for clarity. Referenced new structures.
226	Utility Plan: Adjusted approximate location of and included an additional existing We Energies gas main and added labels for clarity. Referenced new structures.
510	Miscellaneous Quantities: Revised quantity for Item 416.0620 Drilled Dowel Bars.
524	Miscellaneous Quantities: Revised quantity for Item 690.0250 Sawing Concrete.
778	General Plan (B-40-1029): Adjusted approximate location of and included an additional existing We Energies gas main and added labels for clarity.
819	General Plan (R-40-730): Adjusted approximate location of existing We Energies gas main and added labels for clarity.
836	General Layout S-40-3107: Adjusted approximate location of existing We Energies gas line and added labels for clarity.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01

2030-10-71

July 2, 2026

Special Provisions

3. Prosecution and Progress.

*Replace entire subsection titled Stage 1 Construction under section titled **Schedule of Operations** with the following:*

Stage 1 Construction:

- Install erosion control devices as shown on the plan or as directed by the engineer prior to ground disturbing activity
- Perform grubbing as shown on the plans and in accordance with these special provisions
- Complete all in-stream construction activities in accordance with these special provisions. In-stream work includes work that causes disturbance to bed or the banks of the waterway.
- Begin construction on the STH 100 bridge(s) over the Menomonee River between Currie Park entrance and Menomonee River Parkway
- Construct temporary access to 3800 N. Mayfair Road
- Complete construction of median opening closure on Burleigh Street
- Complete all instream work in accordance with these special provisions
- Install detour signing for STH 100 between Burleigh Street and Capitol Drive

7. Utilities.

Replace entire article language with the following:

This contract comes under the provision of Administrative Rule Trans 220.

The utility work plan includes additional detailed information regarding the location of known discontinued, relocated, or removed utility facilities. These can be requested from the department during the bid preparation process, or from the project engineer after the contract has been awarded and executed.

Some of the utility work described below is dependent on prior work being performed by the contractor at a specific site. In such situations, provide the engineer and the affected utility a good faith notice of when the utility is to start work at the site. Provide this notice 14 to 16 calendar days in advance of when the prior work will be completed and the site will be available to the utility. Follow-up with a confirmation notice to the engineer and the utility not less than 3 working days before the site will be ready for the utility to begin its work.

stp-107-065 (20240703)

Any utility facility locations (stations, offsets, elevations, depths) listed in this article are approximate.

The following utility owners have facilities in the project area:

AT&T Wisconsin owns aerial and underground communications facilities within the project area.

AT&T Wisconsin plans the following work that will occur during construction:

Approximate Location	Planned Work	Estimated Construction Time
Station 43+77, 61' RT	Removal of existing pedestal.	½ of a working day.
Station 144+57, 31' RT	Manhole casting removal, plating, reinstallation, and adjustment.	Casting removal and plating: 6 hours per manhole. Casting reinstallation and adjustment: 6 hours per manhole.
Station 202+40, 20' RT	Manhole casting removal, plating, reinstallation, and adjustment.	
Station 45+56, 8' RT	Manhole adjustment.	6 hours.
Station 45+60 – Station 45+85, 7' – 9' RT	Excavate to expose and shift 6 MCD conduit to the south to avoid catch basin.	2 working days.

Contact AT&T Wisconsin prior to any work operation that they will be performing during construction. Provide advance notice after the final lower layer of asphalt is placed but prior to placement of the upper layer of asphalt, and the site will be available to the utility owner for casting reinstallation and adjustment. Provide advance notice after staking the location of the storm sewer inlet along the Burleigh Street eastbound inside lane (Storm Sewer Structure 10), and the site will be available to the utility owner for shifting the 6 MCD conduit.

City of Milwaukee - Sewer owns underground sanitary sewer facilities within the project area.

Adjust sanitary sewer manholes and install sanitary sewer manhole internal seals as shown in the plans and in the bid items for this project.

City of Milwaukee – Water (Milwaukee Water Works) owns underground water facilities within the project area.

Contact Milwaukee Water Works prior to the start of construction. Milwaukee Water Works will locate, mark, inspect and repair all water service boxes, water valve boxes and water manhole frames and lids within the limits of the project prior to commencement of work on the project. This work is estimated to take 5 working days.

Adjust water valve boxes as shown in the plans and in the bid item for this project.

An existing hydrant located at Station 201+78, 81' RT will be within 18" of grading for a curb ramp.

City of Wauwatosa (COMLN) owns underground communication facilities within the project area.

The City of Wauwatosa (COMLN) plans the following work that will occur during construction:

Approximate Location	Planned Work
Station 120+30 – Station 132+20	Relocation of fiber conduit. Pulling fiber and splicing.
Station 120+45	Handhole adjustment.
Station 132+20	Handhole adjustment.

Work during construction is estimated to take 15 working days for the relocation of the fiber conduit and handhole adjustments and 3 working days for pulling fiber and splicing. The relocation of the fiber conduit requires the fill along the bridge approaches to be in place prior to the city performing their relocation.

Provide the City of Wauwatosa (COMLN) a 30-working day initial notice then advanced notice prior to each onsite mobilization.

The city will leave in place and discontinue the existing underground fiber conduit between Station 120+30 and Station 132+20. No conflicts are anticipated with the existing fiber conduit. Cut and remove the existing fiber conduit, as necessary.

City of Wauwatosa – Sewer owns underground sanitary sewer facilities within the project area.

Adjust sanitary sewer manholes as shown in the plans and in the bid items for this project.

City of Wauwatosa – Water (Wauwatosa Water Utility) owns underground water facilities within the project area.

Adjust water valve boxes, perform hydrant and water valve vault extensions, and replace water valve vaults with water valve boxes as shown in the plans and in the bid items for this project.

The following water valve boxes are anticipated to require extensions:

Location
Station 121+69, 46' RT
Station 121+72, 48' RT
Station 121+77, 44' RT
Station 123+90, 57' RT
Station 128+08, 74' RT
Station 130+36, 65' RT
Station 130+40, 65' RT
Station 132+36, 64' RT

Midwest Fiber Networks LLC owns underground communications facilities within the project area.

Prior to construction, Midwest Fiber Networks LLC plans the following work:

Approximate Location	Planned Work
Station 117+40, 2' RT	Installation of a new handhole.
Station 122+35 LT (within the median)	Adjustment of existing handhole.
Station 117+40, 2' RT – Station 122+35 LT	Installation of new 1.25-inch HDPE between the new handhole and existing handhole.
Station 140+44, 71' RT – Station 141+76, 58' RT	Installation of new 1.25-inch duct path will be placed at approximately a 48 to 60-inch minimum depth.
Station 117+34 – Station 141+82	Removal of 432ct fiber from the WisDOT duct.

Work prior to construction is anticipated to be completed by July 14, 2026.

For the following coordination items taking place during construction, contact Patty Finn at (414) 459-3551.

Midwest Fiber Networks LLC will adjust the handhole located at Station 122+35 LT. Contact Midwest Fiber Networks LLC prior to placing fill around the handhole. Handhole adjustment is anticipated to take 1 working day. Work around handhole prior to and after adjustment.

Contact Midwest Fiber Networks LLC prior to the WisDOT conduit between Station 117+34 and Station 141+82 being available to pull new 432ct fiber. Pulling fiber and splicing is anticipated to take 3 working days.

Contact Cory Schmuki at (414) 459-3561 prior to constructing the storm sewer median inlet (Storm Sewer Structure 9C) and pipe connection at Station 119+50 so that they can have a watchdog present.

Milwaukee Metropolitan Sewerage District (MMSD) owns underground sanitary sewer facilities within the project area.

MMSD will remove manhole castings, plate manhole openings, and reinstall and adjust manhole castings during construction at the following locations:

Structure	Location
Manhole 19004	Station 191+27, 26' RT
Manhole 19005	Station 196+77, 26' RT
Manhole 19006	Station 203+06, 27' RT
Conveyance Structure 20101	Station 209+00, 37' RT
Conveyance Structure 20102A	Station 213+89.2, 43.6' RT
Manhole 20102	Station 215+20, 39.2' RT
Conveyance Structure 20103	Station 220+16.8, 41.6' LT

MMSD estimates 1 working day for removing casting and plating manhole opening per manhole and 1 working day for reinstalling and adjusting casting per manhole. Contact MMSD in advance of construction prior to casting removal and plating. Provide advance notice after the final lower layer of asphalt is placed but prior to placement of the upper layer of asphalt, and the site will be available to the utility owner for casting reinstallation and adjustment.

Spectrum owns aerial and underground communications facilities within the project area.

Prior to construction, Spectrum completed the following work:

Approximate Location	Planned Work
Station 115+26 LT – Station 123+87 LT	Relocation of underground communications facilities by installing a 2-inch duct approximately 3.5 feet to 5.5 feet LT of the proposed right-of-way line. The new conduit will be installed to a depth that varies between 38 inches and 84 inches. Installation of a new vault located at Station 115+26. Removal of existing pedestals located at Station 120+51 and Station 122+31.
Station 127+07 LT – Station 135+67 LT	Relocation of underground communications facilities by installing a 2-inch duct approximately 1 foot to 2 feet LT of the proposed right-of-way line. The new conduit will be installed to a depth that varies between 32 inches and 42 inches. Installation of new vaults located at Station 127+07 and Station 129+46.
Station 142+40 LT – Station 142+57 LT	Removal of existing cable tv pole located at Station 142+41, 61' LT and installation of a new cable tv pole located at Station 142+41, 56.5' LT. Removal of existing vault located at Station 142+46, 61' LT and installation of a new vault located at Station 142+54, 56.5' LT. Removal of an existing pedestal located at Station 142+35, 70' LT.

Spectrum has identified the following existing underground communications facilities that will be left in place and discontinued:

Approximate Location	Type and Size of Facility
Station 115+26 LT – Station 123+87 LT	2-inch duct
Station 127+07 LT – Station 135+67 LT	2-inch duct

For coordination during construction, contact Lois Rosado at (414) 335-6994.

Contact Spectrum prior to streetlight installation at the following locations so that they can have a watchdog present: Station 136+15.7 LT, Station 137+85.7 LT, and Station 139+56.1 LT.

Prior to placing the temporary causeway, Spectrum will plate the new vault installed at Station 127+07, 83' LT. Contact Spectrum in advance for plate placement. Spectrum will place plate within 10 calendar days after being notified. Plating is estimated to take 2 working days. After the temporary causeway has been removed and rough grading of the area around the vault has been completed, but prior to the placement of topsoil, contact Spectrum in advance for plate removal and vault adjustment. Spectrum will remove the plate and adjust the vault, within 20 calendar days of being notified that they have access to the vault. Vault adjustment is estimated to take 2 working days.

Verizon owns underground communications facilities within the project area.

Prior to construction, Verizon plans the following work:

Approximate Location	Planned Work
Station 111+40, 56.47' LT	Handhole to be relocated 3' easterly.
Station 117+52.33, 5.5' LT – Station 132+83.92, 67.3' LT	Temporarily relocating their facilities overhead to poles being installed by Wisconsin Independent Network, LLC.
Station 117+52.33, 5.5' LT – Station 120+45	Place temporary fiber underground between existing hand hole at Station 120+45 and temporary pole at Station 117+52.33, 5.5' LT.
Station 132+25, 48.71' LT – Station 132+83.92, 67.3' LT	Place temporary fiber underground between existing hand hole at Station 132+25, 48.71' LT and temporary pole at Station 132+83.92, 67.3' LT.
Station 123+70	Expose existing conduit, install temporary hand hole and protect by burying below grade.
Station 127+85	Expose existing conduit, install temporary hand hole and protect by burying below grade.

Work prior to construction is anticipated to begin in May of 2026 and is estimated to take 30 working days.

Verizon plans the following work that will occur during construction:

Approximate Location	Planned Work
Station 123+70	Expose and remove temporary hand hole.
Station 123+70 – Bridge	Swing existing duct to vault constructed as part of this project located at Station 124+59 and connect to conduit reserved for Verizon in the bridge structure.
Bridge – Station 127+85	Connect conduit reserved for Verizon in the bridge structure to vault constructed as part of this project located at Station 127+65 and swing existing duct to Station 127+85.
Station 127+85	Expose and remove temporary hand hole.
Station 120+23 – Station 132+25	Pulling fiber and splicing.
Station 120+45	Handhole adjustment.
Station 132+10	Handhole adjustment.
Station 132+25, 52' LT	Handhole adjustment.
Station 132+25, 8' LT	Handhole to be relocated 10' easterly and adjusted.

Station 117+52.33, 5.5' LT – Station 132+83.92, 67.3' LT	Removal of temporary facilities.
---	----------------------------------

Work during construction is estimated to take 10 working days to complete the permanent installations and adjustments and 10 working days for the removal of the temporary facilities.

Provide notice prior to Verizon having availability to occupy the site.

Verizon Wireless owns underground communications facilities within the project area.

Prior to construction, Verizon Wireless plans to relocate their existing meter pedestal located at Station 111+36, 56' LT to Station 0+84, 22' LT within the northeast quadrant of the West Townsend Street intersection. This work has been completed.

We Energies (Electric) owns aerial and underground electric facilities within the project area.

Prior to construction, We Energies (Electric) plans to relocate their existing pad-mounted transformer located at Station 110+70, 58' LT to the north side of West Townsend Street outside of the construction limits.

For the following coordination items taking place during construction, contact Tara Blecha at (414) 540-5784.

We Energies (Electric) will adjust the following manhole castings during construction:

Structure	Location
Manhole 9292	Station 197+62, 41' LT
Manhole 9288	Station 202+21, 52' LT
Manhole 9291	Station 207+07, 45' LT

We Energies estimates 1½ working days for removing casting and plating manhole opening per manhole and 1 working day for reinstalling and adjusting casting per manhole. We Energies requires notice prior to each location requiring adjustment and prior to the site being available for their work.

We Energies (Gas) owns underground gas facilities within the project area.

Prior to construction, We Energies (Gas) completed the following work:

Approximate Location	Planned Work
Station 93+26, 44' RT – Station 116+51, 46' RT	Installation of a new 4-inch PE gas line.
Station 107+61	Installation of a new 4-inch PE gas line crossing STH 100.
Station 121+01, 66' LT – Station 130+75, 54' LT	Installation of a new 24-inch steel pipe gas main bored underneath the Menomonee River. Installation of new service to Currie Park Golf Course and curb valve beginning at Station 121+25, LT.

We Energies (Gas) plans the following work that will occur during construction:

Approximate Location	Planned Work
Station 121+00	Installation of a new 24-inch steel pipe crossing to tie-in to 24-inch steel gas main south of Currie Golf Course driveway entrance.
Station 130+52, 71' LT – Station 130+80, 54' LT	Installation of a new 24-inch steel pipe crossing to tie-in to 24-inch steel gas main north of Menomonee River Parkway.
Proposed bridge wing walls	Removal of sections of the discontinued steel pipe located under the proposed bridge wing walls/retaining walls after removal of existing bridge B-40-340 (STH 100 SB-Mayfair Rd over Menomonee River).
Station 107+61, 42' RT	Gas valve adjustment.
Station 121+10, 71' LT	Gas valve adjustment.
Station 143+55, 109.5' LT	Gas valve adjustment.

Installation of the two new crossings is estimated to take 40 working days with an estimated start date in the second week of August 2026. Removal of sections of the discontinued steel pipe located under the proposed bridge wing walls are anticipated to take 10 working days during construction. Gas valve adjustments are anticipated to take 1 working day per adjustment. Contact We Energies (Gas) in advance of discontinued steel pipe removals or any gas valve adjustment.

For coordination during construction, contact We Energies Gas Dispatch at 1-800-261-5325.

We Energies (Gas) has identified the following existing underground communications facility that will be left in place and discontinued:

Approximate Location	Type and Size of Facility
Station 121+01 RT – Station 130+48 LT	22-inch steel pipe ¹
Station 124+90 LT – Station 127+15 LT	24-inch steel pipe

¹There is potential for encountering a discontinued 22-inch gas main within the cofferdam installation west of the existing structure, location and existence is unverified. This line was discontinued and potentially removed for the 1968 bridge construction. If this main is encountered during construction, contact We Energies to coordinate removal as needed.

Wisconsin Independent Network, LLC owns underground communications facilities within the project area.

Prior to construction, Wisconsin Independent Network, LLC plans the following work:

Approximate Location	Planned Work
Pole TP1: Station 117+52.33, 5.5' LT Pole TP2: Station 118+74.50, 69.9' LT Pole TP3: Station 121+74.50, 67.8' LT	Temporarily relocating their facilities overhead to poles.

Pole TP4: Station 124+74.83, 113.8' LT	
Pole TP5: Station 127+39.83, 112.8' LT	
Pole TP6: Station 130+11.92, 78.7' LT	
Pole TP7: Station 132+83.92, 67.3' LT	
Pole TP8: Station 134+47.50, 11.8' LT	

Work prior to construction is anticipated to begin in June of 2026 and is estimated to take 30 working days.

Wisconsin Independent Network, LLC plans the following work that will occur during construction:

Approximate Location	Planned Work
Station 117+43.33	Installing new hand hole and connecting to existing WisDOT vault located at approximately Station 117+33, 5' RT.
Station 134+47.50	Installing new hand hole and connecting to existing WisDOT vault located at approximately Station 134+45, 10' RT.
Station 117+43.33 – Station 134+47.50	Pulling fiber and splicing.
Station 117+52.33, 5.5' LT – Station 134+47.50, 11.8' LT	Removal of temporary facilities.

Work during construction is estimated to take 10 working days to complete the permanent installations and 10 working days for the removal of the temporary facilities.

Provide a 21-calendar day notice prior to Wisconsin Independent Network, LLC having the ability to remove the temporary facilities.

The following utility owners have facilities within the project area; however, no adjustments are anticipated:

- **Level 3 Communications**
- **Milwaukee County Department of Public Works (WISGN)**
-

9. Other Contracts.

Add the following:

Project 1100-20-70
 IH 41 Zoo Freeway
 Burleigh Street to Capitol Drive
 WisDOT Contact: Steve Kuhl, 414-531-6932
steve.kuhl@dot.wi.gov

Project 1100-20-71
 IH 41 Zoo Freeway
 Capitol Drive to Silver Spring Drive
 WisDOT Contact: Steve Kuhl, 414-531-6932
steve.kuhl@dot.wi.gov

70. Temporary Causeway, Item SPV.0060.13.

Add the following:

After determining the location of existing gas main by Utility Line Opening (ULO), provide access to We Energies for removal.

94. Coordination with Businesses and Residents.

The department will arrange and conduct a meeting between the contractor, the department, affected residents, local officials and business people to discuss the project schedule of operations including vehicular and pedestrian access during construction operations. Hold the first meeting at least one week before the start of work under this contract and no further meetings will be required unless directed by the engineer. The department will arrange for a suitable location for meetings that provides reasonable accommodation for public involvement. The department will prepare and coordinate publication of the meeting notices and mailings for meetings. The contractor shall schedule meetings with at least 2 weeks' prior notice to the engineer to allow for these notifications.

stp-108-060 (20141107)

Schedule of Items



Attached, dated July 2, 2026, are the revised Schedule of Items Pages 5 and 20.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:


Revised: 23, 225, 226, 510, 524, 778, 819, and 836.


END OF ADDENDUM



- NOTES:
1. PROVIDE WATERWAY MARKERS IN ACCORDANCE WITH WISCONSIN DEPARTMENT OF NATURAL RESOURCES WATERWAY MARKER PERMIT
 2. PROPER ANCHORING OF WATERWAY MARKERS IS INCIDENTAL TO MAINTENANCE OF WATERWAY MARKERS.
 3. WATERWAY MARKERS TO BE PLACED PRIOR TO BEGINNING CONSTRUCTION IN MEMONONIE RIVER
 4. SEE STRUCTURE PLANS FOR INFORMATION ON COFFERDAM PLACEMENT
 5. BUOYS TO REMAIN IN THE WATER AT ALL TIMES DURING BRIDGE REMOVAL AND BRIDGE CONSTRUCTION.
 6. REMOVE AND STOCKPILE ORGANIC MATERIAL TO PROVIDE FOR A MINIMUM OF 6-INCHES OF SALVAGED WATERWALL AS SHOWN ON THE PERMANENT CAUSEWAY TO REMAIN PLAN DETAIL

Addendum No. 01
ID 2030-10-71
Revised Sheet 23
July 2, 2026





Addendum No. 01
ID 2030-10-71
Revised Sheet 226
July 2, 2026

- LEGEND**
- XXX ADJUST SANITARY SEWER MANHOLE
 - XXX ADJUST PULL BOXES
 - XXX ADJUSTING WATER VALVE BOXES/MANHOLE
 - XXX ADJUSTING HYDRANT
 - XXX REPLACE VALVE VAULT WITH BOX

PROJECT NO: 2030-10-71		COUNTY: MILWAUKEE	UTILITY PLAN	SHEET 226 E
FILE NAME: X:\M\2021\20210100\DESIGN\TRANSPORTATION\SHEETSP\AM023001_LUP.DWG		PLOT DATE: 6/26/2026 1:19 PM		PLOT NAME: 1 IN=40 FT
LAYOUT NAME: 023008_LUP		PLOT BY: ENGLISH, BRIAN		WISDOT/CADD 9 SHEET 42

et 510

CONCRETE BASE 320.0145 8-INCH SY <table><tr><th>STATION TO STATION</th><th>SY</th></tr><tr><td>90+00 - 119+00</td><td>-</td></tr><tr><td>119+00 - 133+76</td><td>-</td></tr><tr><td>133+76 - 147+00</td><td>-</td></tr><tr><td>147+00 - 204+25</td><td>-</td></tr><tr><td>204+25 - 249+46</td><td>-</td></tr><tr><td>UNDISTRIBUITED</td><td>243</td></tr><tr><td>TOTALS</td><td>243</td></tr></table>				STATION TO STATION	SY	90+00 - 119+00	-	119+00 - 133+76	-	133+76 - 147+00	-	147+00 - 204+25	-	204+25 - 249+46	-	UNDISTRIBUITED	243	TOTALS	243	CONCRETE PAVEMENT 415.0080 8-INCH SY <table><tr><th>STATION TO STATION</th><th>SY</th></tr><tr><td>90+00 - 119+00</td><td>-</td></tr><tr><td>119+00 - 133+76</td><td>9,658</td></tr><tr><td>133+76 - 147+00</td><td>-</td></tr><tr><td>147+00 - 204+25</td><td>-</td></tr><tr><td>204+25 - 249+46</td><td>-</td></tr><tr><td>TOTALS</td><td>9,658</td></tr></table>				STATION TO STATION	SY	90+00 - 119+00	-	119+00 - 133+76	9,658	133+76 - 147+00	-	147+00 - 204+25	-	204+25 - 249+46	-	TOTALS	9,658	CONCRETE PAVEMENT 416.1720 REPLACEMENT HES 8-INCH SY <table><tr><th>STATION TO STATION</th><th>SY</th></tr><tr><td>90+00 - 119+00</td><td>-</td></tr><tr><td>119+00 - 133+76</td><td>-</td></tr><tr><td>133+76 - 147+00</td><td>178</td></tr><tr><td>147+00 - 204+25</td><td>356</td></tr><tr><td>204+25 - 249+46</td><td>-</td></tr><tr><td>TOTALS</td><td>534</td></tr></table>				STATION TO STATION	SY	90+00 - 119+00	-	119+00 - 133+76	-	133+76 - 147+00	178	147+00 - 204+25	356	204+25 - 249+46	-	TOTALS	534	CONCRETE PAVEMENT 415.1080 HES 8-INCH SY <table><tr><th>STATION TO STATION</th><th>SY</th></tr><tr><td>90+00 - 119+00</td><td>-</td></tr><tr><td>119+00 - 133+76</td><td>-</td></tr><tr><td>133+76 - 147+00</td><td>-</td></tr><tr><td>147+00 - 204+25</td><td>-</td></tr><tr><td>204+25 - 249+46</td><td>-</td></tr><tr><td>TOTALS</td><td>1,160</td></tr></table>				STATION TO STATION	SY	90+00 - 119+00	-	119+00 - 133+76	-	133+76 - 147+00	-	147+00 - 204+25	-	204+25 - 249+46	-	TOTALS	1,160																																																																																														
STATION TO STATION	SY																																																																																																																																																																						
90+00 - 119+00	-																																																																																																																																																																						
119+00 - 133+76	-																																																																																																																																																																						
133+76 - 147+00	-																																																																																																																																																																						
147+00 - 204+25	-																																																																																																																																																																						
204+25 - 249+46	-																																																																																																																																																																						
UNDISTRIBUITED	243																																																																																																																																																																						
TOTALS	243																																																																																																																																																																						
STATION TO STATION	SY																																																																																																																																																																						
90+00 - 119+00	-																																																																																																																																																																						
119+00 - 133+76	9,658																																																																																																																																																																						
133+76 - 147+00	-																																																																																																																																																																						
147+00 - 204+25	-																																																																																																																																																																						
204+25 - 249+46	-																																																																																																																																																																						
TOTALS	9,658																																																																																																																																																																						
STATION TO STATION	SY																																																																																																																																																																						
90+00 - 119+00	-																																																																																																																																																																						
119+00 - 133+76	-																																																																																																																																																																						
133+76 - 147+00	178																																																																																																																																																																						
147+00 - 204+25	356																																																																																																																																																																						
204+25 - 249+46	-																																																																																																																																																																						
TOTALS	534																																																																																																																																																																						
STATION TO STATION	SY																																																																																																																																																																						
90+00 - 119+00	-																																																																																																																																																																						
119+00 - 133+76	-																																																																																																																																																																						
133+76 - 147+00	-																																																																																																																																																																						
147+00 - 204+25	-																																																																																																																																																																						
204+25 - 249+46	-																																																																																																																																																																						
TOTALS	1,160																																																																																																																																																																						
CONCRETE PAVEMENT APPROACH SLAB 415.0410 CONCRETE PAVEMENT APPROACH SLAB SY <table><tr><th>STATION TO STATION</th><th>SY</th></tr><tr><td>90+00 - 119+00</td><td>-</td></tr><tr><td>119+00 - 133+76</td><td>238</td></tr><tr><td>133+76 - 147+00</td><td>-</td></tr><tr><td>147+00 - 204+25</td><td>-</td></tr><tr><td>204+25 - 249+46</td><td>-</td></tr><tr><td>TOTALS</td><td>238</td></tr></table>				STATION TO STATION	SY	90+00 - 119+00	-	119+00 - 133+76	238	133+76 - 147+00	-	147+00 - 204+25	-	204+25 - 249+46	-	TOTALS	238	DRILLED TIE BARS 416.0610 DRILLED TIE BARS EACH <table><tr><th>STATION TO STATION</th><th>EACH</th></tr><tr><td>90+00 - 119+00</td><td>315</td></tr><tr><td>119+00 - 133+76</td><td>30</td></tr><tr><td>133+76 - 147+00</td><td>531</td></tr><tr><td>147+00 - 204+25</td><td>827</td></tr><tr><td>204+25 - 249+46</td><td>203</td></tr><tr><td>UNDISTRIBUTED</td><td>2,786</td></tr><tr><td>TOTALS</td><td>4,692</td></tr></table>				STATION TO STATION	EACH	90+00 - 119+00	315	119+00 - 133+76	30	133+76 - 147+00	531	147+00 - 204+25	827	204+25 - 249+46	203	UNDISTRIBUTED	2,786	TOTALS	4,692	DRILLED DOWEL BARS 416.0620 DRILLED DOWEL BARS EACH <table><tr><th>STATION TO STATION</th><th>EACH</th></tr><tr><td>90+00 - 119+00</td><td>112</td></tr><tr><td>119+00 - 133+76</td><td>-</td></tr><tr><td>133+76 - 147+00</td><td>344</td></tr><tr><td>147+00 - 204+25</td><td>344</td></tr><tr><td>204+25 - 249+46</td><td>80</td></tr><tr><td>UNDISTRIBUTED</td><td>13,828</td></tr><tr><td>TOTALS</td><td>14,708</td></tr></table>				STATION TO STATION	EACH	90+00 - 119+00	112	119+00 - 133+76	-	133+76 - 147+00	344	147+00 - 204+25	344	204+25 - 249+46	80	UNDISTRIBUTED	13,828	TOTALS	14,708																																																																																																														
STATION TO STATION	SY																																																																																																																																																																						
90+00 - 119+00	-																																																																																																																																																																						
119+00 - 133+76	238																																																																																																																																																																						
133+76 - 147+00	-																																																																																																																																																																						
147+00 - 204+25	-																																																																																																																																																																						
204+25 - 249+46	-																																																																																																																																																																						
TOTALS	238																																																																																																																																																																						
STATION TO STATION	EACH																																																																																																																																																																						
90+00 - 119+00	315																																																																																																																																																																						
119+00 - 133+76	30																																																																																																																																																																						
133+76 - 147+00	531																																																																																																																																																																						
147+00 - 204+25	827																																																																																																																																																																						
204+25 - 249+46	203																																																																																																																																																																						
UNDISTRIBUTED	2,786																																																																																																																																																																						
TOTALS	4,692																																																																																																																																																																						
STATION TO STATION	EACH																																																																																																																																																																						
90+00 - 119+00	112																																																																																																																																																																						
119+00 - 133+76	-																																																																																																																																																																						
133+76 - 147+00	344																																																																																																																																																																						
147+00 - 204+25	344																																																																																																																																																																						
204+25 - 249+46	80																																																																																																																																																																						
UNDISTRIBUTED	13,828																																																																																																																																																																						
TOTALS	14,708																																																																																																																																																																						
CONCRETE DRIVEWAY 602.0810 6-INCH SY <table><tr><th>STATION TO STATION</th><th>SY</th></tr><tr><td>90+00 - 119+00</td><td>-</td></tr><tr><td>119+00 - 133+76</td><td>62</td></tr><tr><td>133+76 - 147+00</td><td>-</td></tr><tr><td>147+00 - 204+25</td><td>-</td></tr><tr><td>204+25 - 249+46</td><td>-</td></tr><tr><td>TOTALS</td><td>62</td></tr></table>				STATION TO STATION	SY	90+00 - 119+00	-	119+00 - 133+76	62	133+76 - 147+00	-	147+00 - 204+25	-	204+25 - 249+46	-	TOTALS	62	CONCRETE DRIVEWAY 602.0815 7-INCH SY <table><tr><th>STATION TO STATION</th><th>SY</th></tr><tr><td>90+00 - 119+00</td><td>-</td></tr><tr><td>119+00 - 133+76</td><td>66</td></tr><tr><td>133+76 - 147+00</td><td>27</td></tr><tr><td>147+00 - 204+25</td><td>-</td></tr><tr><td>204+25 - 249+46</td><td>-</td></tr><tr><td>TOTALS</td><td>93</td></tr></table>				STATION TO STATION	SY	90+00 - 119+00	-	119+00 - 133+76	66	133+76 - 147+00	27	147+00 - 204+25	-	204+25 - 249+46	-	TOTALS	93	HMA PAVEMENT CATEGORY 1020 460.6223 3 MT 58-28 S TON <table><tr><th>STATION TO STATION</th><th>TON</th></tr><tr><td>90+00 - 119+00</td><td>2,880</td></tr><tr><td>119+00 - 133+76</td><td>227</td></tr><tr><td>133+76 - 147+00</td><td>1,750</td></tr><tr><td>147+00 - 204+25</td><td>6,308</td></tr><tr><td>204+25 - 249+46</td><td>4,634</td></tr><tr><td>UNDISTRIBUTED</td><td>-</td></tr><tr><td>CATEGORY TOTAL</td><td>15,799</td></tr><tr><td>PROJECT TOTAL</td><td>15,799</td></tr></table>				STATION TO STATION	TON	90+00 - 119+00	2,880	119+00 - 133+76	227	133+76 - 147+00	1,750	147+00 - 204+25	6,308	204+25 - 249+46	4,634	UNDISTRIBUTED	-	CATEGORY TOTAL	15,799	PROJECT TOTAL	15,799	HMA PAVEMENT CATEGORY 1020 460.6224 4 MT 58-28 S TON <table><tr><th>STATION TO STATION</th><th>TON</th></tr><tr><td>90+00 - 119+00</td><td>2,240</td></tr><tr><td>119+00 - 133+76</td><td>114</td></tr><tr><td>133+76 - 147+00</td><td>1,361</td></tr><tr><td>147+00 - 204+25</td><td>4,906</td></tr><tr><td>204+25 - 249+46</td><td>3,604</td></tr><tr><td>UNDISTRIBUTED</td><td>-</td></tr><tr><td>CATEGORY TOTAL</td><td>12,225</td></tr><tr><td>PROJECT TOTAL</td><td>12,225</td></tr></table>				STATION TO STATION	TON	90+00 - 119+00	2,240	119+00 - 133+76	114	133+76 - 147+00	1,361	147+00 - 204+25	4,906	204+25 - 249+46	3,604	UNDISTRIBUTED	-	CATEGORY TOTAL	12,225	PROJECT TOTAL	12,225	CATEGORY 8020 465.0120 DRIVEWAYS AND FIELD ENTRANCES TON <table><tr><th>STATION TO STATION</th><th>TON</th></tr><tr><td>90+00 - 119+00</td><td>18</td></tr><tr><td>119+00 - 133+76</td><td>42</td></tr><tr><td>133+76 - 147+00</td><td>8</td></tr><tr><td>147+00 - 204+25</td><td>-</td></tr><tr><td>204+25 - 249+46</td><td>-</td></tr><tr><td>UNDISTRIBUTED</td><td>-</td></tr><tr><td>CATEGORY TOTAL</td><td>68</td></tr><tr><td>PROJECT TOTAL</td><td>68</td></tr></table>				STATION TO STATION	TON	90+00 - 119+00	18	119+00 - 133+76	42	133+76 - 147+00	8	147+00 - 204+25	-	204+25 - 249+46	-	UNDISTRIBUTED	-	CATEGORY TOTAL	68	PROJECT TOTAL	68	CATEGORY 8020 465.0110 ASPHALTIC SURFACE PATCHING TON <table><tr><th>STATION TO STATION</th><th>TON</th></tr><tr><td>90+00 - 119+00</td><td>-</td></tr><tr><td>119+00 - 133+76</td><td>-</td></tr><tr><td>133+76 - 147+00</td><td>-</td></tr><tr><td>147+00 - 204+25</td><td>-</td></tr><tr><td>204+25 - 249+46</td><td>-</td></tr><tr><td>UNDISTRIBUTED</td><td>36</td></tr><tr><td>CATEGORY TOTAL</td><td>36</td></tr><tr><td>PROJECT TOTAL</td><td>36</td></tr></table>				STATION TO STATION	TON	90+00 - 119+00	-	119+00 - 133+76	-	133+76 - 147+00	-	147+00 - 204+25	-	204+25 - 249+46	-	UNDISTRIBUTED	36	CATEGORY TOTAL	36	PROJECT TOTAL	36	CATEGORY 1020 455.0605 TACK COAT GAL <table><tr><th>STATION TO STATION</th><th>GAL</th></tr><tr><td>90+00 - 119+00</td><td>-</td></tr><tr><td>119+00 - 133+76</td><td>2,763</td></tr><tr><td>133+76 - 147+00</td><td>130</td></tr><tr><td>147+00 - 204+25</td><td>1,625</td></tr><tr><td>204+25 - 249+46</td><td>5,851</td></tr><tr><td>UNDISTRIBUTED</td><td>-</td></tr><tr><td>CATEGORY TOTAL</td><td>9,369</td></tr><tr><td>PROJECT TOTAL</td><td>9,369</td></tr></table>				STATION TO STATION	GAL	90+00 - 119+00	-	119+00 - 133+76	2,763	133+76 - 147+00	130	147+00 - 204+25	1,625	204+25 - 249+46	5,851	UNDISTRIBUTED	-	CATEGORY TOTAL	9,369	PROJECT TOTAL	9,369	CATEGORY 8020 455.0605 TACK COAT GAL <table><tr><th>STATION TO STATION</th><th>GAL</th></tr><tr><td>90+00 - 119+00</td><td>-</td></tr><tr><td>119+00 - 133+76</td><td>-</td></tr><tr><td>133+76 - 147+00</td><td>-</td></tr><tr><td>147+00 - 204+25</td><td>-</td></tr><tr><td>204+25 - 249+46</td><td>-</td></tr><tr><td>UNDISTRIBUTED</td><td>-</td></tr><tr><td>CATEGORY TOTAL</td><td>-</td></tr><tr><td>PROJECT TOTAL</td><td>-</td></tr></table>				STATION TO STATION	GAL	90+00 - 119+00	-	119+00 - 133+76	-	133+76 - 147+00	-	147+00 - 204+25	-	204+25 - 249+46	-	UNDISTRIBUTED	-	CATEGORY TOTAL	-	PROJECT TOTAL	-
STATION TO STATION	SY																																																																																																																																																																						
90+00 - 119+00	-																																																																																																																																																																						
119+00 - 133+76	62																																																																																																																																																																						
133+76 - 147+00	-																																																																																																																																																																						
147+00 - 204+25	-																																																																																																																																																																						
204+25 - 249+46	-																																																																																																																																																																						
TOTALS	62																																																																																																																																																																						
STATION TO STATION	SY																																																																																																																																																																						
90+00 - 119+00	-																																																																																																																																																																						
119+00 - 133+76	66																																																																																																																																																																						
133+76 - 147+00	27																																																																																																																																																																						
147+00 - 204+25	-																																																																																																																																																																						
204+25 - 249+46	-																																																																																																																																																																						
TOTALS	93																																																																																																																																																																						
STATION TO STATION	TON																																																																																																																																																																						
90+00 - 119+00	2,880																																																																																																																																																																						
119+00 - 133+76	227																																																																																																																																																																						
133+76 - 147+00	1,750																																																																																																																																																																						
147+00 - 204+25	6,308																																																																																																																																																																						
204+25 - 249+46	4,634																																																																																																																																																																						
UNDISTRIBUTED	-																																																																																																																																																																						
CATEGORY TOTAL	15,799																																																																																																																																																																						
PROJECT TOTAL	15,799																																																																																																																																																																						
STATION TO STATION	TON																																																																																																																																																																						
90+00 - 119+00	2,240																																																																																																																																																																						
119+00 - 133+76	114																																																																																																																																																																						
133+76 - 147+00	1,361																																																																																																																																																																						
147+00 - 204+25	4,906																																																																																																																																																																						
204+25 - 249+46	3,604																																																																																																																																																																						
UNDISTRIBUTED	-																																																																																																																																																																						
CATEGORY TOTAL	12,225																																																																																																																																																																						
PROJECT TOTAL	12,225																																																																																																																																																																						
STATION TO STATION	TON																																																																																																																																																																						
90+00 - 119+00	18																																																																																																																																																																						
119+00 - 133+76	42																																																																																																																																																																						
133+76 - 147+00	8																																																																																																																																																																						
147+00 - 204+25	-																																																																																																																																																																						
204+25 - 249+46	-																																																																																																																																																																						
UNDISTRIBUTED	-																																																																																																																																																																						
CATEGORY TOTAL	68																																																																																																																																																																						
PROJECT TOTAL	68																																																																																																																																																																						
STATION TO STATION	TON																																																																																																																																																																						
90+00 - 119+00	-																																																																																																																																																																						
119+00 - 133+76	-																																																																																																																																																																						
133+76 - 147+00	-																																																																																																																																																																						
147+00 - 204+25	-																																																																																																																																																																						
204+25 - 249+46	-																																																																																																																																																																						
UNDISTRIBUTED	36																																																																																																																																																																						
CATEGORY TOTAL	36																																																																																																																																																																						
PROJECT TOTAL	36																																																																																																																																																																						
STATION TO STATION	GAL																																																																																																																																																																						
90+00 - 119+00	-																																																																																																																																																																						
119+00 - 133+76	2,763																																																																																																																																																																						
133+76 - 147+00	130																																																																																																																																																																						
147+00 - 204+25	1,625																																																																																																																																																																						
204+25 - 249+46	5,851																																																																																																																																																																						
UNDISTRIBUTED	-																																																																																																																																																																						
CATEGORY TOTAL	9,369																																																																																																																																																																						
PROJECT TOTAL	9,369																																																																																																																																																																						
STATION TO STATION	GAL																																																																																																																																																																						
90+00 - 119+00	-																																																																																																																																																																						
119+00 - 133+76	-																																																																																																																																																																						
133+76 - 147+00	-																																																																																																																																																																						
147+00 - 204+25	-																																																																																																																																																																						
204+25 - 249+46	-																																																																																																																																																																						
UNDISTRIBUTED	-																																																																																																																																																																						
CATEGORY TOTAL	-																																																																																																																																																																						
PROJECT TOTAL	-																																																																																																																																																																						
PROJECT NO: 2030-10-71				COUNTY: MILWAUKEE				ALL ITEMS CATEGORY 1000 UNLESS NOTED																																																																																																																																																															
HWY: STH 100				PLOT NAME: _____				PLOT SCALE: 1:1																																																																																																																																																															
FILE NAME: _____				PLOT BY: _____				SHEET: 510																																																																																																																																																															
E				E				E																																																																																																																																																															

Addendum No. 01
ID 2030-10-71
Revised Sheet 524
July 2, 2026

DESIGN DATA

STATE PROJECT NUMBER
2030-10-71

LIVE LOAD:
HL-93
DESIGN LOADING: RF = 1.28
INVENTORY RATING: RF = 1.74
WISCONSIN STANDARD PERMIT VEHICLE (WIS-SPV): 250 (KIPS)
STRUCTURE IS DESIGNED FOR A FUTURE WEARING SURFACE OF 20 POUNDS PER SQUARE FOOT.

MATERIAL PROPERTIES:
CONCRETE MASONRY: $f'_c = 4,000$ PSI
SUPERSTRUCTURE & STRUCTURAL APPROACH SLAB: $f'_c = 3,500$ PSI
ALL OTHER: $f'_c = 3,500$ PSI
BAR STEEL REINFORCEMENT: $f_y = 60,000$ PSI
GRADE 60: $f_y = 60,000$ PSI
STAINLESS, GRADE 60: $f_y = 60,000$ PSI
36W" PRESTRESSED GIRDERS: $f'_c = 8,000$ PSI
CONCRETE MASONRY: $f'_c = 8,000$ PSI
STRANDS: 0.6" DIA. WITH ULTIMATE TENSILE STRENGTH OF 270,000 P.S.I.

FOUNDATION DATA

SOUTH ABUTMENT TO BE SUPPORTED ON HP10X42 PILING SEALED IN PRE-BORED HOLES. PRE-BORED HOLES SHALL EXTEND A MINIMUM OF 10 FEET BELOW THE BOTTOM OF THE ABUTMENT AND BE EMBEDDED A MINIMUM OF 3'-0" INTO COMPETENT ROCK. PILES PLACED IN PRE-BORED HOLES BORED INTO ROCK DO NOT REQUIRE DRILLING RECORDS. PILES IN COMPRESSION USED FOR DESIGN IS 180 TONS MULTIPLIED BY A RESISTANCE FACTOR OF 0.5.

NORTH ABUTMENT WITH SPREAD FOOTINGS TO BE SUPPORTED BY SOUND ROCK WITH A REQUIRED FACTORED BEARING RESISTANCE OF 40,000 PSF***. A GEOTECHNICAL ENGINEER WILL DETERMINE THE FACTORED BEARING RESISTANCE BY VISUAL INSPECTION PRIOR TO CONSTRUCTION OF THE ABUTMENT FOOTING.

PIERS WITH SPREAD FOOTINGS TO BE SUPPORTED BY SOUND ROCK WITH A REQUIRED FACTORED BEARING RESISTANCE OF 40,000 PSF***. A GEOTECHNICAL ENGINEER WILL DETERMINE THE FACTORED BEARING RESISTANCE BY VISUAL INSPECTION PRIOR TO CONSTRUCTION OF THE PIER FOOTING.

***THE FACTORED BEARING RESISTANCE IS THE VALUE USED FOR DESIGN.

TRAFFIC DATA

5TH 100
ADT = 24,500 (2045)
R.D.S. = 45 MPH

HYDRAULIC DATA
100-YEAR FREQUENCY:
 $Q_{100} = 5,550$ C.F.S.
 $V_{100} = 1.0$ F.P.S.
 $HW_{100} = EL. 695.52$
WATERWAY AREA = 1,724 SQ. FT.
CHANNEL VELOCITY = 1.0 F.P.S.
ROADWAY OVERTOPPING = N/A
SCOUR CRITICAL CODE = 5





STRUCTURE DESIGN CONTACTS:
OWNER: CITY OF MILWAUKEE
DESIGNER: KEVIN G. WOOD
BOS CONTACT: AARON BOMK (608) 261-0261

NO.	DATE	REVISION	BY
6/29/2026	UPDATED UTILITY INFORMATION	WAR	



STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION
ACCEPTED: CHIEF STRUCTURES DESIGN ENGINEER DATE

STRUCTURE B-40-1029	
COUNTY	WALWATOSA
CITY	MILWAUKEE
DESIGN SPEC.	ASHD LTD BRIDGE DESIGN SPECIFICATION
DESIGNED BY	WAR GCS
DRAWN BY	WAR GCS
PLANS	WAR 1029
DATE	6/29/2026
GENERAL PLAN	
SHEET 1 OF 32	
778	



LIST OF DRAWINGS:

ELEVATION

LOOKING WEST

- 1 GENERAL PLAN
- 2 GENERAL NOTES
- 3 QUANTITIES
- 4 SUBSURFACE EXPLORATION 1
- 5 SUBSURFACE EXPLORATION 2
- 6 SOUTH ABUTMENT
- 7 SUPERSTRUCTURE CROSS SECTION
- 8 SUPERSTRUCTURE DETAILS 1
- 9 SUPERSTRUCTURE DETAILS 2
- 10 TOP OF DECK ELEVATIONS
- 11 NORTH ABUTMENT DETAILS
- 12 ALTERNATE CONSTRUCTION JOINT
- 13 ELASTOMERIC BEARING DETAILS
- 14 36W" PRESTRESSED GIRDER DETAILS
- 15 36W" PRESTRESSED GIRDER DESIGN DATA
- 16 INTERM. STEEL DIAPHRAGMS
- 17 SUPERSTRUCTURE PLAN
- 18 SUPERSTRUCTURE CROSS SECTION
- 19 SUPERSTRUCTURE DETAILS 1
- 20 SUPERSTRUCTURE DETAILS 2
- 21 TOP OF DECK ELEVATIONS
- 22 CONDUIT DETAILS
- 23 RAILING TYPE C4
- 24 PARAPET 'A' ELECTRICAL WORK
- 25 SOUTH STR. APPROACH SLAB PLAN
- 26 SOUTH STR. APPROACH SLAB DETAILS
- 27 NORTH STR. APPROACH SLAB PLAN
- 28 NORTH STR. APPROACH SLAB DETAILS
- 29 NORTH STR. APPROACH SLAB DETAILS 1
- 30 NORTH STR. APPROACH SLAB DETAILS 2
- 31 AESTHETIC DETAILS 1
- 32 AESTHETIC DETAILS 2

Addendum No. 01
ID 2030-10-71
Revised Sheet 778
July 2, 2026

DESIGN DATA

THE CONTRACTOR SHALL PROVIDE COMPLETE DESIGN, PLANS, DETAILS, SPECIFICATIONS, AND SHOP DRAWINGS FOR THE RETAINING WALLS IN THIS PROJECT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM THE APPROPRIATE AGENCIES. THE CONTRACTOR SHALL PROVIDE TECHNICAL ASSISTANCE TO THE CONTRACTOR DURING CONSTRUCTION. THE COST OF FURNISHING THESE ITEMS SHALL BE INCLUDED IN THE BID ITEM "WALL CONCRETE PANEL MECHANICALLY STABILIZED EARTH R-40-730".

PLANS, ELEVATIONS, AND DETAILS SHOWN ON THESE DRAWINGS ARE INTENDED TO INDICATE WALL LOCATIONS AND TO PROVIDE A GENERAL IDEA OF THE WALL SYSTEM. THE CONTRACTOR SHALL VERIFY THAT THE WALL SYSTEM SELECTED WILL CONFORM TO THE REQUIRED ALIGNMENT AND DETAILS. THE RETAINING WALL IS TO BE DESIGNED USING THE ELEVATIONS GIVEN ON THIS SHEET.

DESIGN RETAINING WALL FOR A LIVE LOAD SURCHARGE OF 240 PSF. THE MAXIMUM VALUE OF THE ANGLE OF INTERNAL FRICTION OF THE WALL BACKFILL MATERIAL IN THE REINFORCED ZONE SHALL BE ASSUMED TO BE 30° WITHOUT CERTIFIED TEST VALUES.

LIVE LOAD:

LIVE LOAD SURCHARGE: 240 PSF

MATERIAL PROPERTIES:

CONCRETE MASONRY $f_c = 3,500$ P.S.I.PRECAST CONCRETE WALL PANELS $f_c = 4,000$ P.S.I.BAR STEEL REINFORCEMENT, GRADE 60 $f_y = 60,000$ P.S.I.

ALLOWABLE WALL SYSTEMS

WALL CONCRETE PANEL MECHANICALLY STABILIZED EARTH

TRAFFIC DATA

STH 100 SB

ADT = 1,200 (2045)


R.D.S. = 45 MPH

LIST OF DRAWINGS

1. GENERAL PLAN
2. QUANTITIES AND WALL DATA
3. TYPICAL WALL SECTION
4. WALL DETAILS
5. PARAPET AND ANCHOR SLAB REINFORCING
6. VERTICAL FACE PARAPET R/W
7. SUBSURFACE EXPLORATION
8. SUBSURFACE EXPLORATION
9. AESTHETIC DETAILS


LEGEND

- (E) EXPANSION JOINT IN CONCRETE ANCHOR
SLO AND PARAPET



PLAN

MSE RETAINING WALL



ELEVATION

LOOKING EAST DIMENSIONS AND STATIONS
GIVEN ALONG FRONT FACE OF WALL

STRUCTURE DESIGN CONTACTS:
CONSULTANT CONTACT: KEVIN WOOD
BOS CONTACT: AARON BONK

NO.	DATE	REVISION	WAR	BY
1	6/29/2026	UPDATED UTILITY INFORMATION		

GR&EF

278 W. Wisconsin Avenue
Milwaukee, WI 53201
414.259.1500 Fax
info@grandef.com

8


8

Addendum No. 01
ID 2030-10-71
Revised Sheet 819
July 2, 2026

GENERAL PLAN
SHEET 1 OF 9
819

SCALE =

Addendum No. 01
ID 2030-10-71
Revised Sheet 836
July 2, 2026



LOCATION MAP

NOTE

POINT OF MIN. VERTICAL CLEARANCE
STA. 129+27.41, 28.50' (LEFT)
EL. 701.82


LEGEND

- ☆ ELEVATIONS GIVEN ALONG C/L MONOTUBE CHORD
- Ⓜ SIGN NUMBERS (PERMANENT SIGNING PLAN)
- STANDOFF DIMENSION IS ASSUMED TO BE 24";
- Ⓢ DIMENSION OF 2" X ANCHOR ROD
- DIAMETER SEE FOUNDATION DETAILS SHEET
- AND SHOP DRAWINGS FOR MORE INFORMATION.




NO.	DATE	REVISION	BY
①	6/29/26	UPDATED UTILITY INFORMATION	WAR

STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
STRUCTURE	S-40-3107
DESIGNED BY	WAR
CHECKED BY	WAR
APPROVED BY	WAR
GENERAL LAYOUT S-40-3107	
SHEET 3 OF 8	
836	



PLAN

STATION 129+27.41 STH 100 SB
1/4 MILE S. STH 190 (CAPITOL DR.)



ELEVATION

(LOOKING DOWNSTATION AT E.F. OF SIGN)



Proposal Schedule of Items

Page 5 of 24

Proposal ID: 20260714004 Project(s): 2030-10-71

Federal ID(s): WISC 2026378

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0110	390.0405 Base Patching Concrete SHES	43.000 CY	_____.	_____.
0112	405.0100 Coloring Concrete WisDOT Red	17.000 CY	_____.	_____.
0114	415.0080 Concrete Pavement 8-Inch	9,658.000 SY	_____.	_____.
0116	415.0410 Concrete Pavement Approach Slab	238.000 SY	_____.	_____.
0118	415.1080 Concrete Pavement HES 8-Inch	1,160.000 SY	_____.	_____.
0120	416.0610 Drilled Tie Bars	4,692.000 EACH	_____.	_____.
0122	416.0620 Drilled Dowel Bars	14,708.000 EACH	_____.	_____.
0124	416.1720 Concrete Pavement Replacement	534.000 SY	_____.	_____.
0126	455.0605 Tack Coat	14,706.000 GAL	_____.	_____.
0128	460.0105.S HMA Percent Within Limits (PWL) Test Strip Volumetrics	2.000 EACH	_____.	_____.
0130	460.6223 HMA Pavement 3 MT 58-28 S	15,799.000 TON	_____.	_____.
0132	460.6224 HMA Pavement 4 MT 58-28 S	12,225.000 TON	_____.	_____.
0134	465.0110 Asphaltic Surface Patching	36.000 TON	_____.	_____.
0136	465.0120 Asphaltic Surface Driveways and Field Entrances	218.000 TON	_____.	_____.
0138	465.0125 Asphaltic Surface Temporary	260.000 TON	_____.	_____.



Proposal Schedule of Items

Page 20 of 24

Proposal ID: 20260714004 Project(s): 2030-10-71

Federal ID(s): WISC 2026378

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0554	673.0105 Communication Vault Type 1	2.000 EACH	_____.	_____.
0556	674.0300 Remove Cable	15,915.000 LF	_____.	_____.
0558	678.0072 Install Fiber Optic Cable Outdoor Plant 72-CT	7,060.000 LF	_____.	_____.
0560	678.0200 Fiber Optic Splice Enclosure	2.000 EACH	_____.	_____.
0562	678.0300 Fiber Optic Splice	148.000 EACH	_____.	_____.
0564	678.0501 Communication System Testing	1.000 EACH	_____.	_____.
0566	690.0150 Sawing Asphalt	2,030.000 LF	_____.	_____.
0568	690.0250 Sawing Concrete	32,596.000 LF	_____.	_____.
0570	715.0502 Incentive Strength Concrete Structures	13,920.000 DOL	1.00000	13,920.00
0572	715.0720 Incentive Compressive Strength Concrete Pavement	2,969.000 DOL	1.00000	2,969.00
0574	740.0440 Incentive IRI Ride	35,400.000 DOL	1.00000	35,400.00
0576	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	9,100.000 HRS	5.00000	45,500.00
0578	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	18,000.000 HRS	5.00000	90,000.00
0580	SPV.0045 Special 01. Portable Speed Trailer	670.000 DAY	_____.	_____.
0582	SPV.0055 Special 01. Incentive Density PWL HMA Pavement Core Only	16,975.000 DOL	1.00000	16,975.00