



Wisconsin Department of Transportation

July 9, 2026

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #05: 1130-65-71, WISC 2026379
Appleton – De Pere
I-41 Mainline, Meade St-Ballard Rd
IH 41
Outagamie County

1130-65-72, WISC 2026380
Appleton – De Pere
I-41 Mainline, Ballard Rd-French Rd
IH 41
Outagamie County

1130-65-73, WISC 2026381
Appleton – De Pere
I-41 Mainline, French Rd-Holland Rd
IH 41
Outagamie County

1130-65-74, WISC 2026382
Appleton – De Pere
STH 441 Mainline, Northland-I-41
STH 441
Outagamie County

1130-65-78, WISC 2026383
Appleton – De Pere
STH 441 Intchg Fill & Structures
STH 441
Outagamie County

Letting of July 14, 2026

This is Addendum No. 02, which provides for the following:

Special Provisions:

Revised Special Provisions	
Article No.	Description
3.1	Prosecution and Progress
7.12	Excavation, Hauling, and Reuse of Low-Level Contaminated Material
11.8	Concrete Masonry Bridges Special...
11.15	Precast Concrete Box...
11.19	Wall Concrete Panel Mechanically Stabilized Earth LFCF...

Added Special Provisions	
Article No.	Description
16.14	Roadway Debris Removal
1.5	Railroad Insurance and Coordination - Fox Valley and Lake Superior Rail System, LLC
1.6	Railroad Insurance and Coordination - Wisconsin Central Ltd (CN)
7.13	Clay Cover

Deleted Special Provisions	
Article No.	Description
1.4	Railroad Insurance and Coordination - Wisconsin Central Ltd (CN).

Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Proposal Quantity Change (-)	Proposal Total After Addendum
205.0100	Excavation Common	CY	760,171	3,235	763,406
312.0110	Select Crushed Material	CY	757,057	5,580	762,637
511.1100	Temporary Shoring	SF	2,530	-1,050	1,480
625.0500	Salvaged Topsoil	SY	1,705,561	-1,140,730	564,831
SPV.0035.0100	Roadway Embankment	CY	4,893	2,010	6,903
SPV.0060.0105	Baseline CPM Progress Schedule	Each	5	-4	1
SPV.0060.0110	Baseline CPM Progress Schedule and Accepted Revisions	Each	180	-144	36

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Quantity Added	Proposal Total After Addendum
511.1200.0327	Temporary Shoring B-44-327	SF	0	4,500	4,500
640.1305.S	Clay Cover	CY	0	650	650
SPV.0075.2000	Roadway Debris Removal	HR	0	20	20
SPV.0090.0910	Precast Concrete Box Culvert, 9FT x 5FT	LF	0	200	200

Deleted Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Proposal Quantity Change (-)	Proposal Total After Addendum
210.1100	Backfill Structure Type A	CY	860	-860	0

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
3	Added note regarding using a splice during the stem pours of B-44-326/327
1390	Miscellaneous Quantities – Earthwork
1397	Replaces duplicate sheet and provides quantity table for underdrain
1442	Miscellaneous Quantities – Earthwork
1512	Miscellaneous Quantities – Earthwork
1515	Miscellaneous Quantities - Updated Select Crushed Material
1608	Miscellaneous Quantities – Updated Temporary Shoring
1609	Miscellaneous Quantities – Added Clay Cover

Added Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of why sheet was added)
2460A	Miscellaneous Quantities – Earthwork
2493A	Miscellaneous Quantities – Earthwork
2526A	Miscellaneous Quantities – Earthwork

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 02
1130-65-71/72/73/74/78
July 14, 2026

Special Provisions

1.4 DELETED

1.5 Railroad Insurance and Coordination – Fox Valley and Lake Superior Rail System, LLC.

A. Description

Comply with standard spec 107.17 for all work affecting Fox Valley and Lake Superior Rail System, LLC property and any existing tracks.

A.1 Railroad Insurance Requirements

In addition to standard spec 107.26, provide railroad protective liability insurance coverage as specified in standard spec 107.17.3 Insurance is filed in the name of Watco Companies, L.L.C., and its affiliates, subsidiaries, and assigns.

Notify evidence of the required coverage, and duration to Justin Mahr, Senior Manager Real Estate - Contracts; 315 W. 3rd Street, Pittsburg, KS 66762; Telephone (402) 651-8238; E-mail: justin.mahr@watco.com

Also send a copy to the following: NE Region Railroad Coordinator; 944 Vanderperren Way, Green Bay, WI 54304; Telephone (920) 492-5661; E-mail: DOTDTSNERRailroadCoordination@dot.wi.gov.

Include the following information on the insurance document:

- Project ID: 1130-65-74/78
- Project Location: Appleton, WI
- Route Name: STH 441, Outagamie County
- Crossing ID: 693816V
- Railroad Subdivision: Fox River
- Railroad Milepost: 117.45
- Work Performed on or within 50' of RR ROW: Sign structure work, traffic control

A.2 Train Operation

Approximately 2 through freight trains operate daily at up to 10 mph. There are no switch trains.

A.3 Names and Addresses of Railroad Representatives for Consultation and Coordination

Construction Contact

Roger Schaalma, Divisional Engineer, Fox Valley and Lake Superior Rail System, LLC.; 1890 East Johnson Street, Madison, WI 53704; Telephone (608) 620-2044; E-mail rschaalma@watco.com for consultation on railroad requirements during construction.

Amend standard spec 108.4 to include the railroad in the distribution of the initial bar chart, and monthly schedule updates. The bar chart shall specifically show work involving coordination with the railroad.

Flagging Contact

Send flagging request to flaggingapplication@watco.com Reference the Crossing ID, Wisconsin Milepost and Subdivision found in A.1. Contractor must officially request a railroad flagger a minimum of 15 day prior to scheduled work. If the contractor fails to do so and is required to pay an Expedited Fee, the project will not reimburse the contractor for said fee.

Cable Locate Contact

In addition to contacting Diggers Hotline, contact the Flagging Contact above at least five working days before the locate is needed. Reference the Crossing ID, Wisconsin Milepost and Subdivision found in A.1.

Fox Valley and Lake Superior Rail System, LLC will only locate railroad owned facilities located in the railroad right-of-way. The railroad does not locate any other utilities.

cc: WisDOT Region Railroad Coordinator referenced in A.1 on all written correspondence with the railroads.

A.4 Work by Railroad

The railroad will perform the work described in this section, except for work described in other special provisions, and will be accomplished without cost to the contractor. None.

A.5 Temporary Grade Crossing

If a temporary grade crossing is desired, submit a written request to the railroad representative named in A.3 at least 40 days prior to the time needed. Approval is subject to the discretion of the railroad. The department has made no arrangements for a temporary grade crossing.

stp-107-026 (20250701)

1.6 Railroad Insurance and Coordination - Wisconsin Central Ltd (CN)

A. Description

Comply with standard spec 107.17 for all work affecting Wisconsin Central Ltd (CN) property and any existing tracks.

A.1 Railroad Insurance Requirements

In addition to standard spec 107.26, provide railroad protective liability insurance coverage as specified in standard spec 107.17.3 Insurance is filed in the name of Wisconsin Central Ltd and Its Parents (CN).

Notify evidence of the required coverage, and duration to Suzanne Crueger, Senior Officer, Public Works, 1625 Depot Street, Stevens Point, WI 55481; Telephone (715) 572-7803; E-mail: suzanne.crueger@cn.ca

Also send a copy to the following: NE Region Railroad Coordinator; 944 Vanderperren Way, Green Bay, WI 54304; Telephone (920) 492-5661; E-mail: DOTDTSNERRailroadCoordination@dot.wi.gov.

Include the following information on the insurance document:

- Project ID: 1130-65-74/78
- Project Location: Appleton, WI
- Route Name: STH 441, Outagamie County
- Crossing ID: 693817C
- Railroad Subdivision: Fox River
- Railroad Milepost: 217.20
- Work Performed on or within 50' of RR ROW: Traffic control.

A.2 Train Operation

Approximately 2 through freight trains operate daily at up to 49 mph. There are no switch trains.

A.3 Names and Addresses of Railroad Representatives for Consultation and Coordination

Construction Contact

Suzanne Crueger, Senior Officer, Public Works, 1625 Depot Street, Stevens Point, WI 55481; Telephone (715) 572-7803; E-mail: suzanne.crueger@cn.ca for consultation on railroad requirements during construction.

Amend standard spec 108.4 to include the railroad in the distribution of the initial bar chart, and monthly schedule updates. The bar chart shall specifically show work involving coordination with the railroad.

Flagging Contact

Submit by US Mail a "Request for Flagging Services and Cable Location" form with prepayment to: Flagging-US, 17641 South Ashland Avenue, Homewood, IL 60430; Flagging_US@CN.CA.

The form can be obtained at: <https://www.cn.ca/en/safety/utility-installations/>

Requests for flagging and cable locates can take up to five business days after the railroad receives the paperwork. Reference the Wisconsin Milepost and Subdivision located in A.1. Advise Wisconsin Central Ltd (CN) that the flagging services are to be billed at the rate for a public highway project.

Cable Locate Contact

In addition to contacting Diggers Hotline, follow the procedure listed under Flagging Contact.

Wisconsin Central Ltd (CN) will only locate railroad owned facilities buried in the railroad right-of-way. The railroad does not locate any other utilities.

cc: WisDOT Region Railroad Coordinator referenced in A.1 on all written correspondence with the railroads.

A.4 Work by Railroad

The railroad will perform the work described in this section, except for work described in other special provisions, and will be accomplished without cost to the contractor. None.

A.5 Temporary Grade Crossing

If a temporary grade crossing is desired, submit a written request to the railroad representative named in A.3 at least 40 days prior to the time needed. Approval is subject to the discretion of the railroad. The department has made no arrangements for a temporary grade crossing.

stp-107-026 (20250701)

3.1 Prosecution and Progress.

*Replace paragraph one under section titled **07 Interim Completion and Liquidated Damages – SB 41 to SB 441 Ramp 120 Calendar days** with the following:*

The SB 41 to SB 441 Ramp may be closed for 120 consecutive calendar days during Stages 4A and 4B. Complete the work necessary to reopen the SB 41 to SB 441 Ramp to traffic within 120 calendar days after closure. Do not reopen to traffic until all work shown in Stages 4A and 4B is completed.

7.12 Excavation, Hauling, and Reuse of Low-Level Contaminated Material, Item SPV.0035.2000.

*Replace last paragraph under section titled **A.3 Reuse of Fly Ash** with the following:*

Low-level contaminated material from the locations specified in A.2 that cannot be reused in the specified reuse locations must be hauled off-site and disposed of according to Section C below. Hauling costs to and from the off-site location will be paid as Extra Work. Submit hauling invoices for payment.

*Replace last paragraph under section titled **C Construction** with the following*

If dewatering of groundwater is required in the contaminated locations, water shall be either containerized for disposal, treated, and discharged to surface, or upon approval of the municipality, discharged to the sanitary sewer. Pump contaminated water that exceeds surface water discharge limits, as determined by the environmental consultant, into either temporary holding tanks, a treatment system provided by the contractor, or upon approval of the municipality, discharged to the sanitary sewer, as necessary to complete

construction. The contractor will coordinate holding tank mobilizations, waste characterization sampling of accumulated water, and transportation/disposal of contaminated water. The cost for holding tank mobilization, transportation, and contaminated water disposal shall be paid as Extra Work. Management of contaminated groundwater and dewatering shall be incidental to this item.

7.13 Clay Cover, Item 640.1305.S.

A Description

This special provision describes furnishing and installing clay in areas the plans show. Construction of the clay cover shall be performed in accordance with NR 504 and NR 506.

B Materials

For each source, prior to excavating and hauling the clay to the project, submit the results of the laboratory source screening tests described in Table 1. Laboratory test results of the clay must meet or exceed the requirements before placing material.

Submit source screening test results to the engineer for review, two weeks before clay placement.

C Construction

C.1 Clay Cover

C.1.1 Subgrade

Compact the subgrade to the minimum density using standard spec 207.3.6.2, Standard Compaction, or as otherwise specified in the contract requirements.

C.1.2 Erosion Protection

Do not place the clay cover until after all adjacent site grading has been completed and only after silt fence has been installed completely around the area of clay placement.

C.1.3 Clay Placement

After the fine grading is complete, place and compact clay in compacted 6-inch lifts. Place each lift of clay in one continuous lift. See plans for clay construction limits. Measure the thickness of the clay, the plans show, perpendicular to the surface.

Notify the engineer at least three days before starting construction of clay cover.

Table 1

Reference	Number	Test Title	Requirements	Testing Frequency		
				Source Screening	Project Testing	
					Top Cover	Sideslopes

ASTM	D698	Test Method for Laboratory Compaction Characteristics of Soil Using Standard Effort	NA	1/source	1/source	1/source
ASTM	D1140	Standard Test Methods for Amount of Material in Soils Finer Than the No. 200 (75-um) Sieve	Per NR 504 ¹	2/source	1/2,220 cy per lift ²	1/3,330 cy per lift ²
ASTM	D422	Standard Test Method for Particle-Size Analysis of Soils	Per NR 504 ¹	2/source	1/2,220 cy per lift ²	1/3,330 cy per lift ²
ASTM	D4318	Test Method for Liquid Limit, Plastic Limit, and Plasticity Index of Soils.	Per NR 504 ¹	2/source	1/2,220 cy per lift ²	1/3,330 cy per lift ²
ASTM	D2487	Practice for Classification of Soils for Engineering Purposes (Unified Soil Classification System)	Per NR 504 ¹	2/source	1/2,220 cy per lift ²	1/3,330 cy per lift ²
ASTM	D2922	Standard Test Methods for Density of Soil and Soil-Aggregate in Place by Nuclear Methods (Shallow Depth)	Per NR 504 ¹	NA	200'x200' Grid/lift ²	240'x240' Grid/lift ²
ASTM	D5084	Standard Test Methods for Measurement of Hydraulic Conductivity of Saturated Porous Materials Using a Flexible Wall Permeameter	See Note 3	1/source	1/6,660 cy per lift ^{2, 4}	1/10,000 cy per lift ^{2, 4}

Notes:

1. NR 504 = Wisconsin Department of Natural Resources Regulations Chapter NR 504 Landfill Location, Performance, Design and Construction Criteria.
2. A lift shall not exceed 6-inches.
3. The sample for the test shall be remolded at a minimum dry density of 95% of the maximum dry density as determined by the Standard Proctor test and at a moisture content required to achieve the required hydraulic conductivity of 1×10^{-5} cm/sec as stated in NR 506.08(3)(a), but with a minimum moisture content at or above the optimum moisture content as determined in the Standard Proctor test.
4. An undisturbed sample from a thinned walled sampler (Shelby tube).

Compact the clay cover to a minimum of 95% Standard Proctor ASTM D698 Maximum Dry Density with footed compaction equipment having feet at least as long as the loose lift height. As needed, clay shall be disked or otherwise mechanically processed before compaction to break up clods and allow moisture content adjustment. Clod size shall be no greater than 4 inches. All compaction equipment utilized shall have a minimum static weight of 30,000 pounds.

Provide all equipment necessary to adjust clay to the proper moisture content for compaction.

Make sufficient number of passes of the compaction equipment over each lift of clay to ensure complete remolding of the clay.

Do not proceed with placement of additional lifts until all required clay testing and documentation has been completed for the previous lift.

During placement of the clay cover, the minimum moisture content shall be as defined by the testing performed in the source screening evaluation and with the following limits:

- No drier than the optimum moisture content as determined by the Standard Proctor test ASTM D698.

If the in-place clay fails to meet the requirements of Table 1, then remove and replace or rework any portion of the clay cover not meeting the project requirements until project specifications are met. There shall be no compensation for removing, replacing and reworking clay not meeting the requirements in Table 1.

C.1.4 Project Testing and Acceptance

Perform all project testing at the frequency shown in Table 1 except for project testing for ASTM D5084 Standard Test Methods for Measurement of Hydraulic Conductivity of Saturated Porous Materials Using a Flexible Wall Permeameter, which will be done by the department. Record clay cover thickness on a 200 foot x 200 foot grid pattern for the top cover and sideslopes.

Provide the following:

- Access for on-site testing, inspection, and documentation.
- Machinery required to grade/blade density test locations.
- Machinery required to collect undisturbed clay samples (i.e., with Shelby tubes).
- Replace and recompact clay material removed for testing purposes.

Perform sampling, testing, and documentation for project testing in Table 1, required under this provision using HTCP certified technicians. Have a HTCP Grading Technician I (GRADINGTEC-I); or Assistant Certified Technician, Grading (ACT-GRADING); or Aggregate Technician I (AGGTEC-I); or Assistant Certified Technician, Aggregate (ACT-AGG) present at each grading site during all clay cover placement, compaction, and sampling/testing activities. Have a HTCP Nuclear Density Technician I (NUCDENSITYTEC-I) or Assistant Certified Technician, Nuclear Density Gauge Operator (ACT-NUC) perform field density and field moisture content testing.

If an Assistant Certified Technician (ACT) is performing sampling or testing, a certified technician must coordinate and take responsibility for the work an ACT performs. Have a certified technician ensure that all sampling and testing is performed correctly, analyze test results, and post resulting data. No more than one ACT can work under a single certified technician.

Perform all project testing with a department approved laboratory.

C.1.5 Department Testing

The department will perform the project testing for ASTM 5084 Standard Test Methods for Measurement of Hydraulic Conductivity of Saturated Porous Materials Using a Flexible Wall Permeameter.

D Measurement

The department will measure Clay Cover in volume by the cubic yards, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
640.1305.S	Clay Cover	CY

Payment is full compensation for furnishing, placing and compacting the clay cover; and for performing all tests.

stp-640-017 (20210113)

11.8 Concrete Masonry Bridges Special, Item SPV.0035.1010.

Replace entire section titled B Materials with the following:

B Materials

501.2.4 Cementitious Material

Furnish only Type IP(HS), Type IS(HS), Type IT(HS), or Type IL(HS) cement to provide high sulfate resistance. The department will accept the cement in accordance with standard specification

501.2.4.1(2).

16.14 Roadway Debris Removal, Item SPV.0075.2000.

A Description

This special provision describes removal and disposal of roadway debris encountered within the work zone.

B Vacant

C Construction

Provide appropriate personal protective equipment for the removal of roadway debris from the roadway. Roadway debris will consist of trash on the roadway that requires removal.

Removal of animal carcasses will be handled under a separate item.

Collect roadway debris from live lanes of traffic and shoulders as directed by the engineer. Complete debris removal utilizing lane closures or mobile operations per SDD 15D43, during off peak hours as shown in the Freeway Lane Requirements. Complete roadway debris removal within three (3) calendar days of notification by the engineer.

Provide adequate equipment to load roadway debris and keep roadway debris secure. Properly dispose of roadway debris in dumpsters, landfills, or other approved disposal receptacle.

Notify the engineer prior to start and upon completion of the roadway debris removal operations.

D Measurement

The department will measure Roadway Debris Removal by the HOUR that the contractor is actively picking up from the roadway, relocating, and disposing of debris.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0075.2000	Roadway Debris Removal	HOURS

Payment is full compensation for mobilization of traffic control, cleanup crews, and any other crews necessary to complete the work; traffic control, materials, equipment, loading, unloading, and delivery of roadway debris to an approved disposal receptacle, and for any tipping fees required for disposal; and submitting hourly invoices. The cost for lane closures and mobile operations, SDD 15D43, including vehicles and traffic control shall be incidental to the Roadway Debris Removal bid item. The department shall make no payment for time to set up and removal of traffic control and is considered incidental to the Roadway Debris Removal bid item. ner41-643 (06242026)

11.15 Precast Concrete Box Culvert, 9 FT x 5 FT, Item SPV.0900.0910.

Revise title of article to the following:

11.15 Precast Concrete Box Culvert, 8 FT x 4 FT, Item SPV.0900.0900; Precast Concrete Box Culvert, 9 FT x 5 FT, Item SPV.0090.0910

Replace paragraph one under section titled D Measurement with the following:

The department will measure Precast Concrete Box Culvert, (8) FT x (4) FT, and (9) FT x (5) FT completed according to the contract and accepted, in length by the linear foot in place. The box culvert will be measured on the centerline of the box along the flow line.

Replace the ITEM NUMBER paragraph under section titled **E Payment** with the following:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0090.0900	Precast Concrete Box Culvert, (8) FT x (4) FT	LF
SPV.0090.0910	Precast Concrete Box Culvert, (9) FT x (5) FT	LF

**11.19 Wall Concrete Panel Mechanically Stabilized Earth LFCF R-44-42, Item SPV.0165.0142;
Wall Concrete Panel Mechanically Stabilized Earth LFCF R-44-45, Item
SPV.0165.0145; Wall Concrete Panel Mechanically Stabilized Earth LFCF R-44-
47, Item SPV.0165.0147.**

Replace paragraph five under section titled **C.6 LFCF Placement** with the following:

- Submit a written cold weather protection plan along with the quality control plan for engineers approval.
- Surfaces to receive LFCF shall be free of frost, snow, ice, and standing water prior to LFCF placement. Insulating blankets or heated enclosures/mats must be used to heat the area in which LFCF will be placed.
 - Provide each exposed excavation with complete and uniform cold weather protection.
- The fresh LFCF must maintain a temperature of 50 degrees Fahrenheit or greater during placement.
 - Take temperature measurements of the fresh LFCF from every truck and report those results to the region once the ambient temperature is tracking to descend below 35 degrees. The LFCF temperature at discharge should be above 50 F for every single truck otherwise it should be turned away.
- The LFCF must be protected with insulated blanket immediately after placement and until it has reached minimum required strength.
 - Store and test cylinders under conditions similar to the placed material during the initial curing period.
- Inspect the LFCF surface for freeze/thaw or scaling damage after removing insulated blanked and prior to placing additional lifts.
- Do not place LFCF at a temperature of less than 32 degrees Fahrenheit, nor when freezing conditions are expected in less than 24 hours, unless precautions are taken to maintain temperatures above freezing.
- Additionally, consult the manufacturer as to what precautions are necessary to assure installation of an acceptable LFCF in addition to requirements listed above.

Schedule of Items

Attached, dated July 9, 2026, are the revised Schedule of Items Pages 1 – 39.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 3, 1390, 1397, 1442, 1512, 1515, 1608, 1609

Added: 2460A, 2493A, 2526A

END OF ADDENDUM

PROJECT NO:	1130-65-71	HWY: IH 41	COUNTRY: OUTAGAMIE	MISCELLANEOUS QUANTITIES	SHEET 1390
FILE NAME: C:\USER\AVATH\HATCH\CDOS\WISDOT\11306571\PROJECT FILES\DWG\11306571\SHEETS\11306571-CR0201-RD-WY.DWG					
			PLOT DATE: 7/7/2016 4:58 PM	PLOT BY: MUTHI, CAMERON	PLOT SCALE: 1"=1'
WOODWARD/CADDS SHEET 421					

CATEGORY 1000	DIVISION	FROM/TO STATION	LOCATION	EXCAVATION COMMON (1)		ROADWAY EMBANKMENT (CY) (4) SPV.0035.0100	MASS ORDNATE +/- (5)
				CUT (2)	EBS EXCAVATION (3)		
STAGE 1							
NB		814+96.74/815+59.74	TEMP DITCH - PROPOSED 60" CULVERT	5	-	21	-16
SB		815+01.76/816+23.26	TEMP DITCH - PROPOSED 60" CULVERT	30	-	16	1.4
STAGE 1 SUBTOTAL				35	0	37	-2
STAGE 2							
NB		806+68.08/852+00.00	NB MEDIAN WIDENING STAGE 2A	6,323	-	824	5,499
NB		802+59.11/840+00.00	NB OUTSIDE WIDENING STAGE 2B	4,517	-	194	4,323
NB		843+77.50/852+00.00	NB OUTSIDE WIDENING STAGE 2B	774	-	53	721
STAGE 2 SUBTOTAL				11,614	-	1,071	10,543
STAGE 3							
SB		845+71.07/852+00.00	SB IH 41	4,368	-	117	4,251
SB		846+50.00/851+50.00	IH 41 RELIEF TRENCHES	96	-	117	96
STAGE 3 SUBTOTAL				4,464	-	117	4,347
STAGE 4							
SB		792+00.27/845+71.23	SB IH 41	67,077	-	502	66,575
SB		814+50.00/824+00.00	IH 41 RELIEF TRENCHES	257	-	0	257
NB		792+00.57/815+65.95	SB IH 41	207	-	104	103
NB		819+65.51/845+71.08	MEDIAN DITCH STAGE 4A	1,236	-	221	1,015
EC		837+93.50/843+00.00	MEDIAN DITCH STAGE 4B	1,570	-	387	1,183
STAGE 4 SUBTOTAL			RAMP EC	70,541	-	1,214	69,327
STAGE 5							
SB		792+00.26/852+00.28	SB IH 41	4,876	-	104	4,772
NB		806+68.61/852+00.00	MEDIAN DITCH STAGE 5A	380	-	289	91
STAGE 5 SUBTOTAL				5,256	-	393	4,863
STAGE 6							
NB		792+00.00/852+00.00	NB IH 41	68,363	-	4,409	63,954
NB		792+50.00/849+00.00	IH 41 RELIEF TRENCHES	703	-	0	703
EB		843+18.57/851+06.57	RAMP EB	1,606	-	855	751
STAGE 6 SUBTOTAL				70,712	-	5,264	65,448
GRAND TOTAL			TOTAL COMMON EXC	167,628	-	8,096	154,532
				161,650	-	8,096	154,532

NOTES:

- (1) SALVAGED/UNSUALE PAVEMENT MATERIAL IS INCLUDED IN CUT.
- (2) SALVAGED/UNSUALE PAVEMENT MATERIAL IS INCLUDED IN CUT.
- (3) EBS EXCAVATION TO BE BACKFILLED WITH SELECT CRUSHED MATERIAL, SEE BASE AGGREGATE MQ TABLE
- (4) ROADWAY EMBANKMENT = FILL
- (5) THE MASS ORDNATE + OR - QTY CALCULATED FOR THE DIVISION. PLUS QUANTITY INDICATES AN EXCESS OF MATERIAL WITHIN THE DIVISION. MINUS INDICATES A SHORTAGE OF MATERIAL WITHIN THE DIVISION.

PROJECT NO:	1130-65-71	HWY:	IH 41	COUNTRY:	OUTAGAMIE	MISCELLANEOUS QUANTITIES	E
FILE NAME:	CAMBERMATH\DOTS\CAD\DWG\11306571\11306571\PROJECT FILES\GENERAL\11306571\11306571\SHEET1.DWG						
DATE DRAWN:	11/08/2006	BY:	WJW	PLOT DATE:	11/20/06 12:17 PM	PLOT BY:	MUTH CAMERON
CAD FILE NAME:	11306571.dwg	SCALE:	AS SHOWN	PLOT SCALE:	1"=3'	PLOT NAME:	
SHEET NUMBER:	1 OF 1	TOTAL SHEETS:	1	WSPC/CADD SHEET #:	1	WSPC/CADD SHEET #:	1

FENCING									
CATEGORY	ROADWAY	STATION	TO	STATION	OFFSET	LOCATION	LINK 6-FT LF	GATES CHAIN LINK 12-FT LF	616.0700.S FENCE SAFETY LF
1000									
STAGE 4									
SB		799+31	-	799+97	VARIES	LT	228	1	--
SB		800+68	-	840+05	VARIES	LT	4,140	--	--
STAGE 4 SUBTOTAL									
1									
STAGE 6									
NB		799+12	-	799+97	VARIES	RT	242	--	--
NB		800+68	-	801+50	VARIES	RT	220	--	--
NB		812+48	-	816+39	VARIES	RT	392	--	--
NB		827+45	-	839+67	VARIES	RT	1,250	--	--
EC		850+65	-	852+15	VARIES	RT	367	--	--
STAGE 6 SUBTOTAL									
2,471									
CATEGORY 1000 SUBTOTAL									
6,839									
UNDISTRIBUTED									
1									
PROJECT 1130-65-71 TOTAL									
6,839									
1,000									
PIPE UNDERDRAIN ITEMS									
CATEGORY	ROADWAY	STATION	TO	STATION	OFFSET	LOCATION	SPV.0090.2000 PIPE UNDERDRAIN 6-INCH SPECIAL LF		
1000									
STAGE 4									
SB		798+95	-	801+40	51	LT	245		
SB		828+50	-	836+15	VARIES	LT	765		
SB		840+25	-	843+30	36.5	LT	305		
STAGE 4 SUBTOTAL									
1,315									
STAGE 5									
SB		792+00	-	852+00	23	RT	6,000		
STAGE 5 SUBTOTAL									
6,000									
STAGE 6									
NB		792+00	-	852+00	23	LT	6,000		
NB		798+40	-	801+20	50.3	RT	180		
NB		812+97	-	821+43	47.5	RT	846		
NB		821+43	-	827+76	VARIES	RT	633		
NB		827+76	-	839+67	57.2	RT	1,190		
NB		845+44	-	848+51	51	RT	307		
NB		851+51	-	852+00	51	RT	49		
STAGE 6 SUBTOTAL									
9,205									
PROJECT 1130-65-71 TOTAL									
16,520									

ID 1130-65-72

Revised Sheet 1442

July 9, 2026

CATEGORY 1000	DIVISION	FROM/TO STATION	LOCATION	205.0100		ROADWAY EMBANKMENT (CY) (4)	MASS ORDINATE +/- (5)
				CUT (2)	EXCAVATION COMMON (1)		
STAGE 1	NB	855+20.40/870+00.00	NB MEDIAN WIDENING STAGE 1	2,052	-	740	1,312
	NB	870+00.00/895+30.20	NB MEDIAN WIDENING STAGE 1	4,287	-	555	3,732
	NB	916+51.41/920+00.00	NB MEDIAN WIDENING STAGE 1	-	-	92	350
	SB	907+36.30/911+72.50	SB CROSSOVER STAGE 1	531	-	0	531
	NB	870+85.00/877+22.00	TEMP DITCH 36" TWIN PIPES	52	-	77	-25
	SB	871+60.00/884+50.00	TEMP DITCH 36" TWIN PIPES	2,976	-	427	2,549
	STAGE 1 SUBTOTAL			10,340	-	1,891	8,449
	STAGE 2						
	CD	1861+01.59/1892+86.70	NB IH 41 CD ROAD	9,704	-	4,136	5,568
	CD	1863+50.00/1891+00.00	IH 41 RELIEF TRENCHES	306	-	0	306
STAGE 2	EA	862+43.57/865+743.80	RAMP EA	1,087	-	207	880
	NB	852+00.00/855+20.40	NB MEDIAN WIDENING STAGE 2A	907	-	4	903
	NB	895+30.21/916+51.41	NB MEDIAN WIDENING STAGE 2A	3,942	-	82	3,860
	CD	1861+01.59/1870+00.00	CD ROAD INSIDE WIDENING STAGE 2A	743	-	0	743
	CD	1870+00.00/1887+48.35	CD ROAD INSIDE WIDENING STAGE 2A	2,062	-	0	2,062
	CD	852+00.00/861+00.00	CD ROAD OUTSIDE WIDENING STAGE 2B	1,006	-	187	819
	CD	887+50.00/913+37.25	CD ROAD OUTSIDE WIDENING STAGE 2B	5,940	-	390	5,550
	STAGE 2 SUBTOTAL			25,697	-	5,006	20,691
	STAGE 3						
	SB	852+00.00/897+22.05	SB IH 41	26,849	-	2,067	24,782
STAGE 3	SB	871+00.00/914+50.00	IH 41 RELIEF TRENCHES	372	-	0	372
	SB	911+60.27/920+00.00	SB IH 41	1,867	-	1,921	-54
	ED	298+25.00/327+00.00	RAMP ED	7,370	-	6,362	1,008
	ED	297+00.00/307+84.86	TEMP CONSTRUCTION ACCESS	141	-	1,443	1,302
	EDE	521+18.44/540+00.00	RAMP EDE	11,316	-	622	10,694
	NB	858+70.04/870+00.00	NB MEDIAN CROSS OVER STAGE 3A	77,548	-	520	-38
	STAGE 3 SUBTOTAL			115,905	-	13,757	102,148
	STAGE 4						
	NB	870+63.36/900+11.20	NB IH 41	14,232	-	31	14,201
	SB	870+63.05/920+00.00	SB IH 41	16,815	-	1,534	15,281
STAGE 4	SB	897+21.85/919+34.33	SB MEDIAN DITCH STAGE 4A	379	-	1,178	-799
	SB	900+11.13/940+00.00	SB MEDIAN DITCH STAGE 4B	1,404	-	3,602	-2,198
	SB	940+00.00/945+33.72	SB MEDIAN DITCH STAGE 4B	433	-	188	245
	EDE	540+00/54608.45	RAMP EDE	2,106	-	1,806	300
	STAGE 4 SUBTOTAL			35,369	-	8,339	27,030
	STAGE 5						
	NB	855+75.46/870+63.36	NB IH 41	5,778	-	9	5,769
	NB	869+50.00/881+50.00	IH 41 RELIEF TRENCHES	265	-	0	265
	NB	852+00.00/855+00.00	MEDIAN DITCH STAGE 5A	0	-	18	-18
	NB	855+20.19/861+00.00	NB TEMP PAVEMENT TRANSITION STAGE 5A	804	-	227	577
STAGE 5	NB	887+50.00/897+45.25	NB TEMP PAVEMENT TRANSITION STAGE 5A	2,209	-	73	2,136
	NB	900+11.13/920+00.00	MEDIAN DITCH STAGE 5A	1,946	-	563	1,383
	SB	852+00.28/870+63.05	SB IH 41	894	-	553	341
	STAGE 5 SUBTOTAL			11,896	-	1,443	10,453
	STAGE 6						
	NB	852+00.00/861+01.63	NB IH 41	3,452	-	4	3,448
	NB	852+31.00/919+50.00	IH 41 RELIEF TRENCHES	687	-	0	687
	NB	887+50.00/919+59.99	SB IH 41	12,967	-	3,051	9,916
	CD	1855+06.23/1861+00.97	NB IH 41 CD ROAD	1,742	-	665	1,077
	CD	1887+50.00/1900+33.84	NB IH 41 CD ROAD	1,835	-	570	1,265
STAGE 6	SE	223+75.00/228+03.66	RAMP SE	1,201	-	180	1,021
	STAGE 6 SUBTOTAL			21,884	-	4,450	17,434
	GRAND TOTAL			231,131	47,830	34,886	196,245
	TOTAL COMMON EXC			230,661	-	-	-
	NOTES:						
	(1) COMMON EXCAVATION IS THE SUM OF THE CUT AND EBS EXCAVATION COLUMNS. ITEM NUMBER 205.0100						
	(2) SALVAGED/UNSUIABLE PAVEMENT MATERIAL IS INCLUDED IN CUT.						
	(3) EBS TO BE BACKFILLED WITH SELECT CRUSHED MATERIAL. SEE BASE AGGREGATE MQ TABLE						
	(4) ROADWAY EMBANKMENT = FILL						
	(5) THE MASS ORDINATE + OR - QTY CALCULATED FOR THE DIVISION. PLUS QUANTITY INDICATES AN EXCESS OF MATERIAL WITHIN THE DIVISION. MINUS INDICATES A SHORTAGE OF MATERIAL WITHIN THE DIVISION.						

Addendum No. 02
ID 1130-65-72
Revised Sheet 1442
July 9, 2026

WISDOT/CADDS SHEET 42

NOTES:

- (1) SALVAGED/UNSUALE PAVEMENT MATERIAL IS INCLUDED IN CUT;
(2) SALVAGED/UNSUALE PAVEMENT MATERIAL IS INCLUDED IN CUT;
(3) EBS EXCAVATION TO BE BACKFILLED WITH SELECT CRUSHED MATERIAL, SEE BASE AGGREGATE MQ TABLE
(4) ROADWAY EMBANKMENT = FILL
(5) THE MASS ORDINATE + OR - QTY CALCULATED FOR THE DIVISION. PLUS QUANTITY INDICATES AN EXCESS OF MATERIAL WITHIN THE DIVISION. MINUS INDICATES A SHORTAGE OF MATERIAL WITHIN THE DIVISION.

[illegible]

ASPHALT PAVEMENT ITEMS

TEMPORARY PAVEMENT ITEMS

*ADDITIONAL QUANTITIES SHOWN ELSEWHERE

PROJECT NO:	1130-65-73	HWY: IH 41	COUNTY: OUTAGAMIE	MISCELLANEOUS QUANTITIES	E
FILE NAME: C:\USER\MI\THOMAS\CD\GCS\WISDOT\11306573\PROJECTS\11306573\11306573\SHEETS\11306573-0320D-IHQ-BDW.DWG					
PLOT DATE: 6/30/2016 12:39 PM					
PLOT BY: MUTHI, CAMERON					
PLOT SCALE: 1" = 1'					
					SHEET 1515
LAYOUT NAME: 11306573-0320D-IHQ-BDW_08					

MOBILIZATION

619,1000 MOBILIZATION EACH	LOCATION CAT 1000
0.2	PROJECT NO: 1130-65-78
0.2	PROJECT 1130-65-78 TOTAL

CATEGORY	ROADWAY	SPV.0060.0105 BASELINE CPM PROGRESS SCHEDULE	SPV.0060.0110 CPM PROGRESS SCHEDULE AND ACCEPTED REVISIONS EACH EACH
<u>CPM SCHEDULES</u>			

CATEGORY	ROADWAY	EACH	EACH
1000	STH 441	1	36
PROJECT 1130-65-78 TOTAL		1	36

FINISH ROADWAY	LOCATION	EACH
	CAT 1000	
213.0100.0005		
FINISH ROADWAY		
1130-65-78		

213.0100.0005 FINISH ROADWAY 1130-65-78 EACH	LOCATION	
	CAT 1000	
	PROJECT NO: 1130-65-78	1
	PROJECT 1130-65-78 TOTAL	1

TEMPORARY SHORING	511.1200	
	TEMPORARY SHORING	
	B-44-327	SF
LOCATION	B-44-327 PIER CONSTRUCTION	4,500
TOTAL		4,500

FILE NAME:	C:\USERS\AUMTHICH\CDCCDCS\WISDOT\1130650\PROJECT FILES\SDSN\11306578\SHEETS\11306578-MQ-HRWY.DWG
LAYOUT NAME:	-11
PLOT DATE:	5/14/2016 1:07 PM
PLOT BY:	MULTH, CAMERON
PLOT NAME:	
PLOT SCALE:	1" = 1'
WISDOT/CADD SHEET #:	42

RIPRAP & GEOTEXTILE

CATEGORY	ROADWAY	STATION	TO	STATION	OFFSET	LOCATION	RIP RAP MEDIUM CY	645.0120 GEOTEXTILE TYPE HR SY
1000								
STAGE 2								
WS	WS	144+89	-	135+06	73	RT	25	50
	WS	146+45	-	146+55	56	LT	9	17
	WS	147+70	-	147+80	52	LT	9	17
	WS	148+70	-	148+80	51	LT	9	17
NTD	NTD	809+69	-	809+86	36	LT	9	17
	NTD	810+82	-	810+91	39	LT	9	17
	NTD	812+44	-	812+54	44	LT	12	24
	NTD	814+70	-	814+80	48	LT	9	17
NTD	NTD	816+95	-	817+05	53	LT	9	17
	NTD	818+95	-	819+05	52	LT	16	32
	NTD	820+95	-	821+05	52	LT	17	33
	NTD	825+92	-	826+02	60	LT	19	37
STAGE 2 SUBTOTAL							161	312
STAGE 3								
41 NB	41 NB	898+13	-	898+38	101	RT	14	27
	41 NB	906+95	-	907+05	89	RT	12	24
STAGE 3 SUBTOTAL							26	51
PROJECT 1130-65-78 TOTAL							187	363

ROADWAY DEBRIS REMOVAL	
SPV.0075.2000	
LOCATION	HOURS
IH 41 & STH 441	80
TOTAL	80

CLAY COVER	
640.1305.S	
LOCATION	CLAY COVER CY
IH 41/STH 441 INFIELD	650
TOTAL	650

Addendum No. 02
ID 1130-65-78
revised Sheet 1609
July 9, 2026

41 NB - TEMP DITCH - PROPOSED 60" CULVERT - STAGE 1

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)		CUMULATIVE VOL (CY)		MASS ORDNATE
			CUT	FILL	CUT	FILL	CUT	EXPANDED FILL	
814+96.74	81453.22	0.00	0.04	7.18	0	0	0	0	0
815+00.00	81456.48	3.26	0.23	6.03	0	1	0	1	-1
815+32.87	81489.35	32.87	3.59	14.38	2	12	2	13	-11
815+50.00	81506.48	17.13	3.35	4.80	2	6	4	19	-15
815+59.74	81516.22	9.74	0.53	8.36	1	2	5	21	-16
					5	21			

41 SB - TEMP DITCH - PROPOSED 60" CULVERT - STAGE 1

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)		CUMULATIVE VOL (CY)		MASS ORDNATE
			CUT	FILL	CUT	FILL	CUT	EXPANDED FILL	
815+01.76	81546.36	0.00	0.89	7.53	0	0	0	0	0
815+33.94	81578.55	32.19	9.21	2.64	6	6	6	6	0
815+50.00	81594.60	16.05	14.53	0.30	7	1	13	7	6
816+00.00	81644.60	50.00	2.46	4.16	16	4	29	11	18
816+23.26	81667.86	23.26	0.00	7.89	1	5	30	16	14
					30	16			

Addendum No. 02
ID 1130-65-71
Added Sheet 2460A
July 9, 2026

Addendum No. 02
ID 1130-65-72
Added Sheet 2493A
July 9, 2026

RAMP ED - 72 - CONSTRUCTION ACCESS - STAGE 3A-1									
STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY)		CUMULATIVE VOL (CY)		MASS ORDNATE
			CUT	FILL	CUT	FILL	CUT	EXPANDED FILL	
297+00.00	29700.00	0.00	3.50	0.00	0	0	0	0	0
297+50.00	29750.00	50.00	5.92	0.01	9	0	9	0	9
298+00.00	29800.00	50.00	6.06	3.91	11	4	20	4	16
298+50.00	29850.00	50.00	4.10	31.08	9	32	29	36	-7
299+00.00	29900.00	50.00	3.04	47.85	7	73	36	109	-73
299+50.00	29950.00	50.00	3.04	47.85	6	89	42	198	-156
300+00.00	30000.00	50.00	3.04	48.12	6	89	48	287	-239
300+50.00	30050.00	50.00	3.10	45.28	6	86	54	373	-319
301+00.00	30100.00	50.00	3.00	44.94	6	84	60	457	-397
301+50.00	30150.00	50.00	3.08	45.15	6	83	66	540	-474
302+00.00	30200.00	50.00	3.03	43.38	6	82	72	622	-550
302+50.00	30250.00	50.00	3.02	42.52	6	80	78	702	-624
303+00.00	30300.00	50.00	3.13	42.42	6	79	84	781	-697
303+50.00	30350.00	50.00	3.13	43.08	6	79	90	860	-770
304+00.00	30400.00	50.00	3.13	43.48	6	80	96	940	-844
304+50.00	30450.00	50.00	3.13	43.75	6	81	102	1021	-919
305+00.00	30500.00	50.00	3.13	43.98	6	81	108	1102	-994
305+50.00	30550.00	50.00	3.13	43.85	6	81	114	1183	-1069
306+00.00	30600.00	50.00	3.13	43.72	6	81	120	1264	-1144
306+50.00	30650.00	50.00	3.13	43.57	6	81	126	1345	-1219
307+00.00	30700.00	50.00	3.13	29.85	6	68	132	1413	-1281
307+50.00	30750.00	50.00	3.13	1.57	6	29	138	1442	-1304
307+84.86	30784.86	34.86	1.74	0.00	3	3	141	1443	-1302
					141	1443			

411 NB - TEMP DITCH - C44-147 - STAGE 1

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)		CUMULATIVE VOL (CY)	
			CUT	FILL	CUT	FILL	CUT	EXPANDED FILL MASS ORDINATE
928+54.00	92810.48	0.00	0.08	5.38	0	0	1.00	0
928+82.47	92838.95	28.47	20.17	0.05	11	3	0	8
929+00.00	92856.48	17.53	11.25	3.46	10	1	4	17
929+50.00	92906.48	50.00	0.06	17.10	10	19	23	8
					31	23		

Addendum No. 02
ID 1130-65-73
Added Sheet 2526A
July 9, 2026



Proposal Schedule of Items

Page 1 of 39

Proposal ID: 20260714005 **Project(s):** 1130-65-71, 1130-65-72, 1130-65-73, 1130-65-74, 1130-65-78**Federal ID(s):** WISC 2026379, WISC 2026380, WISC 2026381, WISC 2026382, WISC 2026383**SECTION:** 0001

Contract Items

Alt Set ID:**Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	201.0105 Clearing	92.000 STA	_____.	_____.
0004	201.0205 Grubbing	106.000 STA	_____.	_____.
0006	203.0100 Removing Small Pipe Culverts	2.000 EACH	_____.	_____.
0008	203.0220 Removing Structure (structure) 0001. B-44-129	1.000 EACH	_____.	_____.
0010	203.0220 Removing Structure (structure) 0002. B-44-130	1.000 EACH	_____.	_____.
0012	203.0220 Removing Structure (structure) 0030. C-44-30	1.000 EACH	_____.	_____.
0014	203.0220 Removing Structure (structure) 0128. B-44-0128	1.000 EACH	_____.	_____.
0016	203.0220 Removing Structure (structure) 0180. C-44-018	1.000 EACH	_____.	_____.
0018	204.0100 Removing Concrete Pavement	141,933.000 SY	_____.	_____.
0020	204.0110 Removing Asphaltic Surface	8,700.000 SY	_____.	_____.
0022	204.0120 Removing Asphaltic Surface Milling	1,098.000 SY	_____.	_____.
0024	204.0150 Removing Curb & Gutter	1,840.000 LF	_____.	_____.
0026	204.0155 Removing Concrete Sidewalk	240.000 SY	_____.	_____.
0028	204.0157 Removing Concrete Barrier	3,592.000 LF	_____.	_____.



Proposal Schedule of Items

Page 2 of 39

Proposal ID: 20260714005 **Project(s):** 1130-65-71, 1130-65-72, 1130-65-73, 1130-65-74, 1130-65-78**Federal ID(s):** WISC 2026379, WISC 2026380, WISC 2026381, WISC 2026382, WISC 2026383**SECTION:** 0001

Contract Items

Alt Set ID:**Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0030	204.0165 Removing Guardrail	7,012.000 LF	_____.	_____.
0032	204.0167 Removing Cable Barrier	9,590.000 LF	_____.	_____.
0034	204.0170 Removing Fence	28,415.000 LF	_____.	_____.
0036	204.0180 Removing Delineators and Markers	148.000 EACH	_____.	_____.
0038	204.0195 Removing Concrete Bases	20.000 EACH	_____.	_____.
0040	204.0210 Removing Manholes	6.000 EACH	_____.	_____.
0042	204.0220 Removing Inlets	31.000 EACH	_____.	_____.
0044	204.0245 Removing Storm Sewer (size) 0001. 12-Inch	55.000 LF	_____.	_____.
0046	204.0245 Removing Storm Sewer (size) 0002. 15-Inch	816.000 LF	_____.	_____.
0048	204.0245 Removing Storm Sewer (size) 0003. 18-Inch	2,940.000 LF	_____.	_____.
0050	204.0245 Removing Storm Sewer (size) 0004. 24-Inch	683.000 LF	_____.	_____.
0052	204.0245 Removing Storm Sewer (size) 0005. 30-Inch	901.000 LF	_____.	_____.
0054	204.0245 Removing Storm Sewer (size) 0006. 36-Inch	515.000 LF	_____.	_____.



Proposal Schedule of Items

Page 3 of 39

Proposal ID: 20260714005 **Project(s):** 1130-65-71, 1130-65-72, 1130-65-73, 1130-65-74, 1130-65-78**Federal ID(s):** WISC 2026379, WISC 2026380, WISC 2026381, WISC 2026382, WISC 2026383**SECTION:** 0001

Contract Items

Alt Set ID:**Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0056	204.0245 Removing Storm Sewer (size) 0007. 48-Inch	525.000 LF	_____.	_____.
0058	204.0270 Abandoning Culvert Pipes	1.000 EACH	_____.	_____.
0060	204.9060.S Removing (item description) 0001. Removing Anchor Bolt Cover Shroud	4.000 EACH	_____.	_____.
0062	204.9060.S Removing (item description) 0002. Removing Street Light Assembly	19.000 EACH	_____.	_____.
0064	204.9060.S Removing (item description) 0003. Removing Lighting Control	1.000 EACH	_____.	_____.
0066	204.9060.S Removing (item description) 0004. Removing Sign	6.000 EACH	_____.	_____.
0068	204.9060.S Removing (item description) 0103. Removing Apron Endwalls	3.000 EACH	_____.	_____.
0070	204.9060.S Removing (item description) 0701. Communication Vault	16.000 EACH	_____.	_____.
0072	204.9090.S Removing (item description) 0001. Removing Electrical Conductors From Existing Conduit	3,405.000 LF	_____.	_____.
0074	204.9090.S Removing (item description) 0002. Removing Or Abandoning Existing Conduit	3,405.000 LF	_____.	_____.
0076	205.0100 Excavation Common	763,406.000 CY	_____.	_____.
0078	206.1001 Excavation for Structures Bridges (structure) 0001. B-44-326	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 4 of 39

Proposal ID: 20260714005 **Project(s):** 1130-65-71, 1130-65-72, 1130-65-73, 1130-65-74, 1130-65-78**Federal ID(s):** WISC 2026379, WISC 2026380, WISC 2026381, WISC 2026382, WISC 2026383**SECTION:** 0001 Contract Items**Alt Set ID:** **Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0080	206.1001 Excavation for Structures Bridges (structure) 0002. B-44-327	1.000 EACH	_____.	_____.
0082	206.1001 Excavation for Structures Bridges (structure) 0128. B-44-128	1.000 EACH	_____.	_____.
0084	206.2001 Excavation for Structures Culverts (structure) 0146. C-44-0146	1.000 EACH	_____.	_____.
0086	206.2001 Excavation for Structures Culverts (structure) 0147. C-44-0147	1.000 EACH	_____.	_____.
0088	206.3001 Excavation for Structures Retaining Walls (structure) 0070. R-44-0070	1.000 EACH	_____.	_____.
0090	206.3001 Excavation for Structures Retaining Walls (structure) 0071. R-44-0071	1.000 EACH	_____.	_____.
0092	209.0200.S Backfill Controlled Low Strength	73.000 CY	_____.	_____.
0096	210.1500 Backfill Structure Type A	1,555.000 TON	_____.	_____.
0098	210.2500 Backfill Structure Type B	3,350.000 TON	_____.	_____.
0100	213.0100 Finishing Roadway (project) 0001. 1130-65-71	1.000 EACH	_____.	_____.
0102	213.0100 Finishing Roadway (project) 0002. 1130-65-72	1.000 EACH	_____.	_____.
0104	213.0100 Finishing Roadway (project) 0003. 1130-65-73	1.000 EACH	_____.	_____.
0106	213.0100 Finishing Roadway (project) 0004. 1130-65-74	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 5 of 39

Proposal ID: 20260714005 **Project(s):** 1130-65-71, 1130-65-72, 1130-65-73, 1130-65-74, 1130-65-78**Federal ID(s):** WISC 2026379, WISC 2026380, WISC 2026381, WISC 2026382, WISC 2026383**SECTION:** 0001

Contract Items

Alt Set ID:**Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0108	213.0100 Finishing Roadway (project) 0005. 1130-65-78	1.000 EACH	_____.	_____.
0110	305.0110 Base Aggregate Dense 3/4-Inch	1,770.000 TON	_____.	_____.
0112	305.0120 Base Aggregate Dense 1 1/4-Inch	236,524.000 TON	_____.	_____.
0114	311.0110 Breaker Run	260.000 TON	_____.	_____.
0116	312.0110 Select Crushed Material	762,637.000 TON	_____.	_____.
0118	320.0105 Concrete Base 4-Inch	11,186.000 SY	_____.	_____.
0120	320.0140 Concrete Base 7 1/2-Inch	674.000 SY	_____.	_____.
0122	390.0100 Removing Pavement for Base Patching	300.000 CY	_____.	_____.
0124	390.0201 Base Patching Asphaltic	500.000 TON	_____.	_____.
0126	415.0090 Concrete Pavement 9-Inch	84,591.000 SY	_____.	_____.
0128	415.0410 Concrete Pavement Approach Slab	473.000 SY	_____.	_____.
0130	416.0610 Drilled Tie Bars	10,892.000 EACH	_____.	_____.
0132	416.0620 Drilled Dowel Bars	885.000 EACH	_____.	_____.
0134	455.0605 Tack Coat	6,406.000 GAL	_____.	_____.
0136	460.2000 Incentive Density HMA Pavement	3,320.000 DOL	1.00000	3,320.00



Proposal Schedule of Items

Page 6 of 39

Proposal ID: 20260714005 **Project(s):** 1130-65-71, 1130-65-72, 1130-65-73, 1130-65-74, 1130-65-78**Federal ID(s):** WISC 2026379, WISC 2026380, WISC 2026381, WISC 2026382, WISC 2026383**SECTION:** 0001

Contract Items

Alt Set ID:**Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0138	460.5223 HMA Pavement 3 LT 58-28 S	2,258.000 TON	_____.	_____.
0140	460.5224 HMA Pavement 4 LT 58-28 S	2,791.000 TON	_____.	_____.
0142	460.6224 HMA Pavement 4 MT 58-28 S	76.000 TON	_____.	_____.
0144	465.0105 Asphaltic Surface	37,573.000 TON	_____.	_____.
0146	465.0125 Asphaltic Surface Temporary	95.000 TON	_____.	_____.
0148	495.1000.S Cold Patch	500.000 TON	_____.	_____.
0150	501.1000.S Ice Hot Weather Concreting	45,000.000 LB	_____.	_____.
0152	502.0100 Concrete Masonry Bridges	4,429.100 CY	_____.	_____.
0154	502.3101 Expansion Device	115.000 LF	_____.	_____.
0156	502.3111.S Expansion Device Modular	208.000 LF	_____.	_____.
0158	502.3200 Protective Surface Treatment	16,065.000 SY	_____.	_____.
0160	502.3210 Pigmented Surface Sealer	5,388.000 SY	_____.	_____.
0162	502.4206 Adhesive Anchors No. 6 Bar	34.000 EACH	_____.	_____.
0164	502.4209 Adhesive Anchors No. 9 Bar	9.000 EACH	_____.	_____.
0166	503.0155 Prestressed Girder Type I 54W-Inch	8,674.000 LF	_____.	_____.



Proposal Schedule of Items

Page 7 of 39

Proposal ID: 20260714005 **Project(s):** 1130-65-71, 1130-65-72, 1130-65-73, 1130-65-74, 1130-65-78**Federal ID(s):** WISC 2026379, WISC 2026380, WISC 2026381, WISC 2026382, WISC 2026383**SECTION:** 0001

Contract Items

Alt Set ID:**Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0168	504.0100 Concrete Masonry Culverts	22.000 CY	_____.	_____.
0170	504.0500 Concrete Masonry Retaining Walls	1,170.000 CY	_____.	_____.
0172	505.0400 Bar Steel Reinforcement HS Structures	194,790.000 LB	_____.	_____.
0174	505.0600 Bar Steel Reinforcement HS Coated Structures	2,159,010.000 LB	_____.	_____.
0176	505.0800.S Bar Steel Reinforcement HS Stainless Structures	16,400.000 LB	_____.	_____.
0178	506.0605 Structural Steel HS	4,253,000.000 LB	_____.	_____.
0180	506.2605 Bearing Pads Elastomeric Non-Laminated	52.000 EACH	_____.	_____.
0182	506.2610 Bearing Pads Elastomeric Laminated	16.000 EACH	_____.	_____.
0184	506.3020 Welded Stud Shear Connectors 7/8x7-Inch	33,243.000 EACH	_____.	_____.
0186	506.4000 Steel Diaphragms (structure) 0001. B-44-326	30.000 EACH	_____.	_____.
0188	506.4000 Steel Diaphragms (structure) 0002. B-44-327	80.000 EACH	_____.	_____.
0190	506.4000 Steel Diaphragms (structure) 0128. B-44-128	4.000 EACH	_____.	_____.
0192	506.5000 Bearing Assemblies Fixed (structure) 0001. B-44-327	12.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 8 of 39

Proposal ID: 20260714005 **Project(s):** 1130-65-71, 1130-65-72, 1130-65-73, 1130-65-74, 1130-65-78**Federal ID(s):** WISC 2026379, WISC 2026380, WISC 2026381, WISC 2026382, WISC 2026383**SECTION:** 0001

Contract Items

Alt Set ID:**Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0194	506.6000 Bearing Assemblies Expansion (structure) 0001. B-44-326	20.000 EACH	_____.	_____.
0196	506.6000 Bearing Assemblies Expansion (structure) 0002. B-44-327	120.000 EACH	_____.	_____.
0198	509.1500 Concrete Surface Repair	5.000 SF	_____.	_____.
0200	509.5100.S Polymer Overlay	14,398.000 SY	_____.	_____.
0202	511.1100 Temporary Shoring	1,480.000 SF	_____.	_____.
0204	511.1200 Temporary Shoring (structure) 0128. B-44-128	930.000 SF	_____.	_____.
0206	511.1200 Temporary Shoring (structure) 0147. C-44-147	1,000.000 SF	_____.	_____.
0208	513.2001 Railing Pipe	43.000 LF	_____.	_____.
0210	514.0445 Floor Drains Type GC	4.000 EACH	_____.	_____.
0212	514.0450 Floor Drains Type WF	7.000 EACH	_____.	_____.
0214	514.0460 Floor Drains Type H	11.000 EACH	_____.	_____.
0216	514.2608 Downspout 8-Inch	883.000 LF	_____.	_____.
0218	516.0100 Dampproofing	1,534.000 SY	_____.	_____.
0220	516.0500 Rubberized Membrane Waterproofing	150.000 SY	_____.	_____.



Proposal Schedule of Items

Page 9 of 39

Proposal ID: 20260714005 **Project(s):** 1130-65-71, 1130-65-72, 1130-65-73, 1130-65-74, 1130-65-78**Federal ID(s):** WISC 2026379, WISC 2026380, WISC 2026381, WISC 2026382, WISC 2026383**SECTION:** 0001

Contract Items

Alt Set ID:**Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0222	517.0601 Painting Epoxy System (structure) 0001. B-44-326	1.000 EACH	_____.	_____.
0224	517.0601 Painting Epoxy System (structure) 0002. B-44-327	1.000 EACH	_____.	_____.
0226	517.1010.S Concrete Staining (structure) 0001. B-44-326	39,102.000 SF	_____.	_____.
0228	517.1010.S Concrete Staining (structure) 0002. B-44-327	101,315.000 SF	_____.	_____.
0230	517.1010.S Concrete Staining (structure) 0003. R-44-0042	17,130.000 SF	_____.	_____.
0232	517.1010.S Concrete Staining (structure) 0004. R-44-0045	7,810.000 SF	_____.	_____.
0234	517.1010.S Concrete Staining (structure) 0005. R-44-0047	960.000 SF	_____.	_____.
0236	517.1010.S Concrete Staining (structure) 0070. R-44-0070	762.000 SF	_____.	_____.
0238	517.1010.S Concrete Staining (structure) 0071. R-44-0071	808.000 SF	_____.	_____.
0240	517.1010.S Concrete Staining (structure) 0127. B-44-0127	5,425.000 SF	_____.	_____.
0242	517.1010.S Concrete Staining (structure) 0128. B-44-0128	5,830.000 SF	_____.	_____.
0244	520.8000 Concrete Collars for Pipe	14.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 10 of 39

Proposal ID: 20260714005 **Project(s):** 1130-65-71, 1130-65-72, 1130-65-73, 1130-65-74, 1130-65-78**Federal ID(s):** WISC 2026379, WISC 2026380, WISC 2026381, WISC 2026382, WISC 2026383**SECTION:** 0001

Contract Items

Alt Set ID:**Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0246	522.0130 Culvert Pipe Reinforced Concrete Class III 30-Inch	250.000 LF	_____.	_____.
0248	522.0136 Culvert Pipe Reinforced Concrete Class III 36-Inch	1,001.000 LF	_____.	_____.
0250	522.0418 Culvert Pipe Reinforced Concrete Class IV 18-Inch	51.000 LF	_____.	_____.
0252	522.0424 Culvert Pipe Reinforced Concrete Class IV 24-Inch	119.000 LF	_____.	_____.
0254	522.0436 Culvert Pipe Reinforced Concrete Class IV 36-Inch	236.000 LF	_____.	_____.
0256	522.0518 Culvert Pipe Reinforced Concrete Class V 18-Inch	25.000 LF	_____.	_____.
0258	522.0524 Culvert Pipe Reinforced Concrete Class V 24-Inch	24.000 LF	_____.	_____.
0260	522.0542 Culvert Pipe Reinforced Concrete Class V 42-Inch	34.000 LF	_____.	_____.
0262	522.1015 Apron Endwalls for Culvert Pipe Reinforced Concrete 15-Inch	5.000 EACH	_____.	_____.
0264	522.1018 Apron Endwalls for Culvert Pipe Reinforced Concrete 18-Inch	57.000 EACH	_____.	_____.
0266	522.1024 Apron Endwalls for Culvert Pipe Reinforced Concrete 24-Inch	22.000 EACH	_____.	_____.
0268	522.1030 Apron Endwalls for Culvert Pipe Reinforced Concrete 30-Inch	7.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 11 of 39

Proposal ID: 20260714005 **Project(s):** 1130-65-71, 1130-65-72, 1130-65-73, 1130-65-74, 1130-65-78**Federal ID(s):** WISC 2026379, WISC 2026380, WISC 2026381, WISC 2026382, WISC 2026383**SECTION:** 0001

Contract Items

Alt Set ID:**Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0270	522.1036 Apron Endwalls for Culvert Pipe Reinforced Concrete 36-Inch	13.000 EACH	_____.	_____.
0272	522.1042 Apron Endwalls for Culvert Pipe Reinforced Concrete 42-Inch	2.000 EACH	_____.	_____.
0274	522.1048 Apron Endwalls for Culvert Pipe Reinforced Concrete 48-Inch	5.000 EACH	_____.	_____.
0276	522.2338 Culvert Pipe Reinforced Concrete Horizontal Elliptical Class HE-III 38x60-Inch	80.000 LF	_____.	_____.
0278	522.2419 Culvert Pipe Reinforced Concrete Horizontal Elliptical Class HE-IV 19x30-Inch	113.000 LF	_____.	_____.
0280	522.2424 Culvert Pipe Reinforced Concrete Horizontal Elliptical Class HE-IV 24x38-Inch	250.000 LF	_____.	_____.
0282	522.2434 Culvert Pipe Reinforced Concrete Horizontal Elliptical Class HE-IV 34x53-Inch	17.000 LF	_____.	_____.
0284	522.2619 Apron Endwalls for Culvert Pipe Reinforced Concrete Horizontal Elliptical 19x30-Inch	6.000 EACH	_____.	_____.
0286	522.2624 Apron Endwalls for Culvert Pipe Reinforced Concrete Horizontal Elliptical 24x38-Inch	3.000 EACH	_____.	_____.
0288	522.2634 Apron Endwalls for Culvert Pipe Reinforced Concrete Horizontal Elliptical 34x53-Inch	2.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 12 of 39

Proposal ID: 20260714005 **Project(s):** 1130-65-71, 1130-65-72, 1130-65-73, 1130-65-74, 1130-65-78**Federal ID(s):** WISC 2026379, WISC 2026380, WISC 2026381, WISC 2026382, WISC 2026383**SECTION:** 0001

Contract Items

Alt Set ID:**Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0290	522.2638 Apron Endwalls for Culvert Pipe Reinforced Concrete Horizontal Elliptical 38x60-Inch	2.000 EACH	_____.	_____.
0292	531.1100 Concrete Masonry Ancillary Structures Type NS	212.200 CY	_____.	_____.
0294	531.1140 Steel Reinforcement HS Ancillary Structures Type NS	18,943.000 LB	_____.	_____.
0296	531.1160 Steel Reinforcement HS Coated Ancillary Structures Type NS	11,900.000 LB	_____.	_____.
0298	531.2024 Drilling Shaft 24-Inch	201.000 LF	_____.	_____.
0300	531.2036 Drilling Shaft 36-Inch	646.000 LF	_____.	_____.
0302	531.2042 Drilling Shaft 42-Inch	322.000 LF	_____.	_____.
0304	531.2048 Drilling Shaft 48-Inch	138.000 LF	_____.	_____.
0306	531.2054 Drilling Shaft 54-Inch	14.000 LF	_____.	_____.
0308	531.4050 Foundation Camera Pole 50-FT	1.000 EACH	_____.	_____.
0310	531.4080 Foundation Camera Pole 80-FT	1.000 EACH	_____.	_____.
0312	531.5030 Foundation Two-Shaft Butterfly Type B-1 (structure) 0380. S-44-0380	1.000 EACH	_____.	_____.
0314	531.5330 Foundation Single-Shaft Type TC-III (structure) 0372. S-44-0372	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 13 of 39

Proposal ID: 20260714005 **Project(s):** 1130-65-71, 1130-65-72, 1130-65-73, 1130-65-74, 1130-65-78**Federal ID(s):** WISC 2026379, WISC 2026380, WISC 2026381, WISC 2026382, WISC 2026383**SECTION:** 0001

Contract Items

Alt Set ID:**Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0316	531.5330 Foundation Single-Shaft Type TC-III (structure) 0375. S-44-0375	1.000 EACH	_____.	_____.
0318	531.6010 Foundation Two-Shaft Type FC-I (structure) 0378. S-44-0378	1.000 EACH	_____.	_____.
0320	531.6010 Foundation Two-Shaft Type FC-I (structure) 0409. S-44-0409	1.000 EACH	_____.	_____.
0322	531.6110 Foundation Two-Shaft Type FF-I (structure) 0374. S-44-0374	1.000 EACH	_____.	_____.
0324	531.6110 Foundation Two-Shaft Type FF-I (structure) 0376. S-44-0376	1.000 EACH	_____.	_____.
0326	531.6110 Foundation Two-Shaft Type FF-I (structure) 0407. S-44-0407	1.000 EACH	_____.	_____.
0328	531.6110 Foundation Two-Shaft Type FF-I (structure) 0408. S-44-0408	2.000 EACH	_____.	_____.
0330	531.6120 Foundation Two-Shaft Type FF-II (structure) 0368. S-44-0368	2.000 EACH	_____.	_____.
0332	531.6120 Foundation Two-Shaft Type FF-II (structure) 0405. S-44-0405	2.000 EACH	_____.	_____.
0334	531.6120 Foundation Two-Shaft Type FF-II (structure) 0406. S-44-0406	2.000 EACH	_____.	_____.
0336	531.6130 Foundation Two-Shaft Type FF-III (structure) 0365. S-44-0365	2.000 EACH	_____.	_____.
0338	531.6130 Foundation Two-Shaft Type FF-III (structure) 0366. S-44-0366	2.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 14 of 39

Proposal ID: 20260714005 **Project(s):** 1130-65-71, 1130-65-72, 1130-65-73, 1130-65-74, 1130-65-78**Federal ID(s):** WISC 2026379, WISC 2026380, WISC 2026381, WISC 2026382, WISC 2026383**SECTION:** 0001

Contract Items

Alt Set ID:**Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0340	531.6130 Foundation Two-Shaft Type FF-III (structure) 0379. S-44-0379	2.000 EACH	_____.	_____.
0342	531.8990 Anchor Assemblies Poles on Structures	24.000 EACH	_____.	_____.
0344	532.5030 Butterfly 2-Chord Type 1 (structure) 0380. S-44-0380	1.000 EACH	_____.	_____.
0346	532.5330 Truss Cantilever 2-Chord Type III (structure) 0372. S-44-0372	1.000 EACH	_____.	_____.
0348	532.5330 Truss Cantilever 2-Chord Type III (structure) 0375. S-44-0375	1.000 EACH	_____.	_____.
0350	532.6010 Truss Cantilever 4-Chord Type I (structure) 0378. S-44-0378	1.000 EACH	_____.	_____.
0352	532.6010 Truss Cantilever 4-Chord Type I (structure) 0409. S-44-0409	1.000 EACH	_____.	_____.
0354	532.6110 Truss Full Span 4-Chord Type I (structure) 0374. S-44-0374	1.000 EACH	_____.	_____.
0356	532.6110 Truss Full Span 4-Chord Type I (structure) 0376. S-44-0376	1.000 EACH	_____.	_____.
0358	532.6110 Truss Full Span 4-Chord Type I (structure) 0407. S-44-0407	1.000 EACH	_____.	_____.
0360	532.6110 Truss Full Span 4-Chord Type I (structure) 0408. S-44-0408	1.000 EACH	_____.	_____.
0362	532.6120 Truss Full Span 4-Chord Type II (structure) 0368. S-44-0368	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 15 of 39

Proposal ID: 20260714005 **Project(s):** 1130-65-71, 1130-65-72, 1130-65-73, 1130-65-74, 1130-65-78**Federal ID(s):** WISC 2026379, WISC 2026380, WISC 2026381, WISC 2026382, WISC 2026383**SECTION:** 0001

Contract Items

Alt Set ID:**Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0364	532.6120 Truss Full Span 4-Chord Type II (structure) 0379. S-44-0379	1.000 EACH	_____.	_____.
0366	532.6120 Truss Full Span 4-Chord Type II (structure) 0405. S-44-0405	1.000 EACH	_____.	_____.
0368	532.6120 Truss Full Span 4-Chord Type II (structure) 0406. S-44-0406	1.000 EACH	_____.	_____.
0370	532.6130 Truss Full Span 4-Chord Type III (structure) 0365. S-44-0365	1.000 EACH	_____.	_____.
0372	532.6130 Truss Full Span 4-Chord Type III (structure) 0366. S-44-0366	1.000 EACH	_____.	_____.
0374	532.6130 Truss Full Span 4-Chord Type III (structure) 0377. S-44-0377	1.000 EACH	_____.	_____.
0376	541.0300.S Noise Barriers Double-Sided Sound Absorptive (structure) 0017. N-44-0017	88,420.000 SF	_____.	_____.
0378	550.0500 Pile Points	16.000 EACH	_____.	_____.
0380	550.1120 Piling Steel HP 12-Inch X 53 Lb	1,040.000 LF	_____.	_____.
0382	550.2148 Piling CIP Concrete 14 X 0.50-Inch	35,655.000 LF	_____.	_____.
0384	601.0405 Concrete Curb & Gutter 18-Inch Type A	480.000 LF	_____.	_____.
0386	601.0409 Concrete Curb & Gutter 30-Inch Type A	257.000 LF	_____.	_____.
0388	602.0405 Concrete Sidewalk 4-Inch	2,485.000 SF	_____.	_____.



Proposal Schedule of Items

Page 16 of 39

Proposal ID: 20260714005 **Project(s):** 1130-65-71, 1130-65-72, 1130-65-73, 1130-65-74, 1130-65-78**Federal ID(s):** WISC 2026379, WISC 2026380, WISC 2026381, WISC 2026382, WISC 2026383**SECTION:** 0001

Contract Items

Alt Set ID:**Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0390	602.3010 Concrete Surface Drains	2.000 CY	_____.	_____.
0392	602.3210 Concrete Rumble Strips, Shoulder Divided Roadway	84,010.000 LF	_____.	_____.
0394	603.0105 Concrete Barrier Single-Faced 32-Inch	765.000 LF	_____.	_____.
0396	603.1242 Concrete Barrier Type S42A	293.000 LF	_____.	_____.
0398	603.1442 Concrete Barrier Type S42C	84.000 LF	_____.	_____.
0400	603.3113 Concrete Barrier Transition Type NJ32SF to S36	6.000 EACH	_____.	_____.
0402	603.3513 Concrete Barrier Transition Type S32 to S36	16.000 EACH	_____.	_____.
0404	603.3535 Concrete Barrier Transition Type S36 to S42	20.000 EACH	_____.	_____.
0406	603.3559 Concrete Barrier Transition Type S42 to S56	20.000 EACH	_____.	_____.
0408	603.8000 Concrete Barrier Temporary Precast Delivered	245,421.000 LF	_____.	_____.
0410	603.8125 Concrete Barrier Temporary Precast Installed	246,141.000 LF	_____.	_____.
0412	603.8500 Anchoring Concrete Barrier Temporary Precast	69,448.000 LF	_____.	_____.
0414	603.8505 Anchoring Concrete Barrier Temporary Precast on Bridge Decks	237.000 LF	_____.	_____.



Proposal Schedule of Items

Page 17 of 39

Proposal ID: 20260714005 **Project(s):** 1130-65-71, 1130-65-72, 1130-65-73, 1130-65-74, 1130-65-78**Federal ID(s):** WISC 2026379, WISC 2026380, WISC 2026381, WISC 2026382, WISC 2026383**SECTION:** 0001

Contract Items

Alt Set ID:**Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0416	604.0400 Slope Paving Concrete	14.000 SY	_____.	_____.
0418	604.0600 Slope Paving Select Crushed Material	891.000 SY	_____.	_____.
0420	606.0100 Riprap Light	5,684.000 CY	_____.	_____.
0422	606.0200 Riprap Medium	1,290.000 CY	_____.	_____.
0424	606.0300 Riprap Heavy	56.000 CY	_____.	_____.
0426	608.0315 Storm Sewer Pipe Reinforced Concrete Class III 15-Inch	613.000 LF	_____.	_____.
0428	608.0318 Storm Sewer Pipe Reinforced Concrete Class III 18-Inch	2,510.000 LF	_____.	_____.
0430	608.0324 Storm Sewer Pipe Reinforced Concrete Class III 24-Inch	7,080.000 LF	_____.	_____.
0432	608.0330 Storm Sewer Pipe Reinforced Concrete Class III 30-Inch	850.000 LF	_____.	_____.
0434	608.0336 Storm Sewer Pipe Reinforced Concrete Class III 36-Inch	910.000 LF	_____.	_____.
0436	608.0415 Storm Sewer Pipe Reinforced Concrete Class IV 15-Inch	56.000 LF	_____.	_____.
0438	608.0418 Storm Sewer Pipe Reinforced Concrete Class IV 18-Inch	5,687.000 LF	_____.	_____.
0440	608.0424 Storm Sewer Pipe Reinforced Concrete Class IV 24-Inch	11,666.000 LF	_____.	_____.



Proposal Schedule of Items

Page 18 of 39

Proposal ID: 20260714005 **Project(s):** 1130-65-71, 1130-65-72, 1130-65-73, 1130-65-74, 1130-65-78**Federal ID(s):** WISC 2026379, WISC 2026380, WISC 2026381, WISC 2026382, WISC 2026383**SECTION:** 0001

Contract Items

Alt Set ID:**Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0442	608.0430 Storm Sewer Pipe Reinforced Concrete Class IV 30-Inch	1,657.000 LF	_____.	_____.
0444	608.0436 Storm Sewer Pipe Reinforced Concrete Class IV 36-Inch	1,151.000 LF	_____.	_____.
0446	608.0442 Storm Sewer Pipe Reinforced Concrete Class IV 42-Inch	500.000 LF	_____.	_____.
0448	608.0448 Storm Sewer Pipe Reinforced Concrete Class IV 48-Inch	516.000 LF	_____.	_____.
0450	608.0524 Storm Sewer Pipe Reinforced Concrete Class V 24-Inch	8.000 LF	_____.	_____.
0452	608.2419 Storm Sewer Pipe Reinforced Concrete Horizontal Elliptical Class HE-IV 19x30-Inch	1,026.000 LF	_____.	_____.
0454	608.2424 Storm Sewer Pipe Reinforced Concrete Horizontal Elliptical Class HE-IV 24x38-Inch	1,208.000 LF	_____.	_____.
0456	611.0430 Reconstructing Inlets	2.000 EACH	_____.	_____.
0458	611.0530 Manhole Covers Type J	4.000 EACH	_____.	_____.
0460	611.0535 Manhole Covers Type J-Special	38.000 EACH	_____.	_____.
0462	611.0606 Inlet Covers Type B	1.000 EACH	_____.	_____.
0464	611.0624 Inlet Covers Type H	2.000 EACH	_____.	_____.
0466	611.0642 Inlet Covers Type MS	22.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 19 of 39

Proposal ID: 20260714005 **Project(s):** 1130-65-71, 1130-65-72, 1130-65-73, 1130-65-74, 1130-65-78**Federal ID(s):** WISC 2026379, WISC 2026380, WISC 2026381, WISC 2026382, WISC 2026383**SECTION:** 0001

Contract Items

Alt Set ID:**Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0468	611.0654 Inlet Covers Type V	8.000 EACH	_____.	_____.
0470	611.0656 Inlet Covers Type VV-B	394.000 EACH	_____.	_____.
0472	611.2004 Manholes 4-FT Diameter	22.000 EACH	_____.	_____.
0474	611.2005 Manholes 5-FT Diameter	332.000 EACH	_____.	_____.
0476	611.2006 Manholes 6-FT Diameter	24.000 EACH	_____.	_____.
0478	611.2007 Manholes 7-FT Diameter	3.000 EACH	_____.	_____.
0480	611.2008 Manholes 8-FT Diameter	4.000 EACH	_____.	_____.
0482	611.2009 Manholes 9-FT Diameter	1.000 EACH	_____.	_____.
0484	611.2044 Manholes 4x4-FT	10.000 EACH	_____.	_____.
0486	611.2055 Manholes 5x5-FT	3.000 EACH	_____.	_____.
0488	611.3003 Inlets 3-FT Diameter	5.000 EACH	_____.	_____.
0490	611.3004 Inlets 4-FT Diameter	1.000 EACH	_____.	_____.
0492	611.3225 Inlets 2x2.5-FT	8.000 EACH	_____.	_____.
0494	611.3260 Inlets 2x3.5-FT	36.000 EACH	_____.	_____.
0496	611.3901 Inlets Median 1 Grate	8.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 20 of 39

Proposal ID: 20260714005 **Project(s):** 1130-65-71, 1130-65-72, 1130-65-73, 1130-65-74, 1130-65-78**Federal ID(s):** WISC 2026379, WISC 2026380, WISC 2026381, WISC 2026382, WISC 2026383**SECTION:** 0001

Contract Items

Alt Set ID:**Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0498	611.3902 Inlets Median 2 Grate	7.000 EACH	_____.	_____.
0500	611.8115 Adjusting Inlet Covers	3.000 EACH	_____.	_____.
0502	611.8120.S Cover Plates Temporary	59.000 EACH	_____.	_____.
0504	612.0206 Pipe Underdrain Unperforated 6-Inch	190.000 LF	_____.	_____.
0506	612.0406 Pipe Underdrain Wrapped 6-Inch	527.000 LF	_____.	_____.
0508	612.0806 Apron Endwalls for Underdrain Reinforced Concrete 6-Inch	1.000 EACH	_____.	_____.
0510	614.0150 Anchor Assemblies for Steel Plate Beam Guard	1.000 EACH	_____.	_____.
0512	614.0397 Guardrail Mow Strip Emulsified Asphalt	649.000 SY	_____.	_____.
0514	614.0800 Crash Cushions Permanent	9.000 EACH	_____.	_____.
0516	614.0905 Crash Cushions Temporary	79.000 EACH	_____.	_____.
0518	614.2300 MGS Guardrail 3	462.500 LF	_____.	_____.
0520	614.2500 MGS Thrie Beam Transition	394.000 LF	_____.	_____.
0522	614.2610 MGS Guardrail Terminal EAT	10.000 EACH	_____.	_____.
0524	616.0206 Fence Chain Link 6-FT	25,431.000 LF	_____.	_____.
0526	616.0329 Gates Chain Link (width) 0001. 12-FT	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 21 of 39

Proposal ID: 20260714005 **Project(s):** 1130-65-71, 1130-65-72, 1130-65-73, 1130-65-74, 1130-65-78**Federal ID(s):** WISC 2026379, WISC 2026380, WISC 2026381, WISC 2026382, WISC 2026383**SECTION:** 0001

Contract Items

Alt Set ID:**Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0528	616.0700.S Fence Safety	5,000.000 LF	_____.	_____.
0530	618.0100 Maintenance and Repair of Haul Roads (project) 0001. 1130-65-71	1.000 EACH	_____.	_____.
0532	618.0100 Maintenance and Repair of Haul Roads (project) 0002. 1130-65-72	1.000 EACH	_____.	_____.
0534	618.0100 Maintenance and Repair of Haul Roads (project) 0003. 1130-65-73	1.000 EACH	_____.	_____.
0536	618.0100 Maintenance and Repair of Haul Roads (project) 0004. 1130-65-74	1.000 EACH	_____.	_____.
0538	618.0100 Maintenance and Repair of Haul Roads (project) 0005. 1130-65-78	1.000 EACH	_____.	_____.
0540	619.1000 Mobilization	1.000 EACH	_____.	_____.
0542	620.0300 Concrete Median Sloped Nose	27.000 SF	_____.	_____.
0544	623.0200 Dust Control Surface Treatment	612,952.000 SY	_____.	_____.
0546	624.0100 Water	3,374.000 MGAL	_____.	_____.
0548	625.0500 Salvaged Topsoil	564,831.000 SY	_____.	_____.
0550	627.0200 Mulching	7,388.000 SY	_____.	_____.
0552	628.1504 Silt Fence	18,299.000 LF	_____.	_____.
0554	628.1520 Silt Fence Maintenance	83,109.000 LF	_____.	_____.



Proposal Schedule of Items

Page 22 of 39

Proposal ID: 20260714005 **Project(s):** 1130-65-71, 1130-65-72, 1130-65-73, 1130-65-74, 1130-65-78**Federal ID(s):** WISC 2026379, WISC 2026380, WISC 2026381, WISC 2026382, WISC 2026383**SECTION:** 0001

Contract Items

Alt Set ID:**Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0556	628.1905 Mobilizations Erosion Control	132.000 EACH	_____.	_____.
0558	628.1910 Mobilizations Emergency Erosion Control	130.000 EACH	_____.	_____.
0560	628.2004 Erosion Mat Class I Type B	447,888.000 SY	_____.	_____.
0562	628.2008 Erosion Mat Urban Class I Type B	43,960.000 SY	_____.	_____.
0564	628.2027 Erosion Mat Class II Type C	5,570.000 SY	_____.	_____.
0566	628.2037 Erosion Mat Class III Type C	15.000 SY	_____.	_____.
0568	628.7005 Inlet Protection Type A	570.000 EACH	_____.	_____.
0570	628.7010 Inlet Protection Type B	634.000 EACH	_____.	_____.
0572	628.7015 Inlet Protection Type C	5.000 EACH	_____.	_____.
0574	628.7504 Temporary Ditch Checks	5,582.000 LF	_____.	_____.
0576	628.7555 Culvert Pipe Checks	311.000 EACH	_____.	_____.
0578	628.7560 Tracking Pads	26.000 EACH	_____.	_____.
0580	628.7570 Rock Bags	608.000 EACH	_____.	_____.
0582	629.0210 Fertilizer Type B	2,852.000 CWT	_____.	_____.
0584	630.0120 Seeding Mixture No. 20	200.000 LB	_____.	_____.



Proposal Schedule of Items

Page 23 of 39

Proposal ID: 20260714005 **Project(s):** 1130-65-71, 1130-65-72, 1130-65-73, 1130-65-74, 1130-65-78**Federal ID(s):** WISC 2026379, WISC 2026380, WISC 2026381, WISC 2026382, WISC 2026383**SECTION:** 0001

Contract Items

Alt Set ID:**Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0586	630.0130 Seeding Mixture No. 30	28,004.000 LB	_____.	_____.
0588	630.0500 Seed Water	11,364.000 MGAL	_____.	_____.
0590	633.1000 Delineators Barrier Wall	843.000 EACH	_____.	_____.
0592	634.0614 Posts Wood 4x6-Inch X 14-FT	1.000 EACH	_____.	_____.
0594	634.0616 Posts Wood 4x6-Inch X 16-FT	48.000 EACH	_____.	_____.
0596	634.0618 Posts Wood 4x6-Inch X 18-FT	16.000 EACH	_____.	_____.
0598	635.0200 Sign Supports Structural Steel HS	13,700.000 LB	_____.	_____.
0600	637.1220 Signs Type I Reflective SH	6,640.000 SF	_____.	_____.
0602	637.2210 Signs Type II Reflective H	661.500 SF	_____.	_____.
0604	637.2230 Signs Type II Reflective F	162.000 SF	_____.	_____.
0606	638.2102 Moving Signs Type II	19.000 EACH	_____.	_____.
0608	638.2601 Removing Signs Type I	18.000 EACH	_____.	_____.
0610	638.2602 Removing Signs Type II	140.000 EACH	_____.	_____.
0612	638.3000 Removing Small Sign Supports	176.000 EACH	_____.	_____.
0614	638.3100 Removing Structural Steel Sign Supports	18.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 24 of 39

Proposal ID: 20260714005 **Project(s):** 1130-65-71, 1130-65-72, 1130-65-73, 1130-65-74, 1130-65-78**Federal ID(s):** WISC 2026379, WISC 2026380, WISC 2026381, WISC 2026382, WISC 2026383**SECTION:** 0001

Contract Items

Alt Set ID:**Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0616	638.4000 Moving Small Sign Supports	15.000 EACH	_____.	_____.
0618	640.1303.S Pond Liner Clay	31,375.000 CY	_____.	_____.
0620	643.0300 Traffic Control Drums	600,925.000 DAY	_____.	_____.
0622	643.0320.S Temporary Tape Rumble Strip Orange	1,296.000 LF	_____.	_____.
0624	643.0420 Traffic Control Barricades Type III	53,187.000 DAY	_____.	_____.
0626	643.0705 Traffic Control Warning Lights Type A	106,375.000 DAY	_____.	_____.
0628	643.0715 Traffic Control Warning Lights Type C	103,997.000 DAY	_____.	_____.
0630	643.0810 Traffic Control Connected Arrow Boards	2,700.000 DAY	_____.	_____.
0632	643.0900 Traffic Control Signs	171,644.000 DAY	_____.	_____.
0634	643.0910 Traffic Control Covering Signs Type I	35.000 EACH	_____.	_____.
0636	643.0920 Traffic Control Covering Signs Type II	18.000 EACH	_____.	_____.
0638	643.1000 Traffic Control Signs Fixed Message	1,547.000 SF	_____.	_____.
0640	643.1050 Traffic Control Signs PCMS	3,601.000 DAY	_____.	_____.
0642	643.1220 Traffic Control Connected Work Zone Start and End Location Markers	9,040.000 DAY	_____.	_____.
0644	643.3165 Temporary Marking Line Paint 6-Inch	342,056.000 LF	_____.	_____.



Proposal Schedule of Items

Page 25 of 39

Proposal ID: 20260714005 **Project(s):** 1130-65-71, 1130-65-72, 1130-65-73, 1130-65-74, 1130-65-78**Federal ID(s):** WISC 2026379, WISC 2026380, WISC 2026381, WISC 2026382, WISC 2026383**SECTION:** 0001

Contract Items

Alt Set ID:**Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0646	643.3170 Temporary Marking Line Epoxy 6-Inch	219,698.000 LF	_____.	_____.
0648	643.3180 Temporary Marking Line Removable Tape 6-Inch	56,053.000 LF	_____.	_____.
0650	643.3265 Temporary Marking Line Paint 10-Inch	25,520.000 LF	_____.	_____.
0652	643.3270 Temporary Marking Line Epoxy 10-Inch	22,018.000 LF	_____.	_____.
0654	643.3280 Temporary Marking Line Removable Tape 10-Inch	9,257.000 LF	_____.	_____.
0656	643.3760 Temporary Marking Raised Pavement Marker Type I	963.000 EACH	_____.	_____.
0658	643.5000 Traffic Control	1.000 EACH	_____.	_____.
0660	645.0105 Geotextile Type C	450.000 SY	_____.	_____.
0662	645.0111 Geotextile Type DF Schedule A	267.000 SY	_____.	_____.
0664	645.0120 Geotextile Type HR	2,486.000 SY	_____.	_____.
0666	645.0130 Geotextile Type R	11,089.000 SY	_____.	_____.
0668	645.0140 Geotextile Type SAS	68,690.000 SY	_____.	_____.
0670	646.2020 Marking Line Epoxy 6-Inch	709.000 LF	_____.	_____.
0672	646.2040 Marking Line Grooved Wet Ref Epoxy 6-Inch	163,075.000 LF	_____.	_____.



Proposal Schedule of Items

Page 26 of 39

Proposal ID: 20260714005 **Project(s):** 1130-65-71, 1130-65-72, 1130-65-73, 1130-65-74, 1130-65-78**Federal ID(s):** WISC 2026379, WISC 2026380, WISC 2026381, WISC 2026382, WISC 2026383**SECTION:** 0001

Contract Items

Alt Set ID:**Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0674	646.4020 Marking Line Epoxy 10-Inch	708.000 LF	_____.	_____.
0676	646.4040 Marking Line Grooved Wet Ref Epoxy 10-Inch	24,529.000 LF	_____.	_____.
0678	646.5020 Marking Arrow Epoxy	15.000 EACH	_____.	_____.
0680	646.5120 Marking Word Epoxy	4.000 EACH	_____.	_____.
0682	646.6120 Marking Stop Line Epoxy 18-Inch	115.000 LF	_____.	_____.
0684	646.6220 Marking Yield Line Epoxy 18-Inch	6.000 EACH	_____.	_____.
0686	646.7220 Marking Chevron Epoxy 24-Inch	1,407.000 LF	_____.	_____.
0688	646.8105 Marking Curb Paint	10.000 LF	_____.	_____.
0690	646.8205 Marking Island Nose Paint	1.000 EACH	_____.	_____.
0692	646.9000 Marking Removal Line 4-Inch	3,934.000 LF	_____.	_____.
0694	646.9002 Marking Removal Line 6-Inch	67,208.000 LF	_____.	_____.
0696	646.9102 Marking Removal Line 10-Inch	424.000 LF	_____.	_____.
0698	646.9300 Marking Removal Special Marking	2.000 EACH	_____.	_____.
0700	652.0125 Conduit Rigid Metallic 2-Inch	226.000 LF	_____.	_____.
0702	652.0225 Conduit Rigid Nonmetallic Schedule 40 2-Inch	52,656.000 LF	_____.	_____.



Proposal Schedule of Items

Page 27 of 39

Proposal ID: 20260714005 **Project(s):** 1130-65-71, 1130-65-72, 1130-65-73, 1130-65-74, 1130-65-78**Federal ID(s):** WISC 2026379, WISC 2026380, WISC 2026381, WISC 2026382, WISC 2026383**SECTION:** 0001

Contract Items

Alt Set ID:**Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0704	652.0235 Conduit Rigid Nonmetallic Schedule 40 3-Inch	8,308.000 LF	_____.	_____.
0706	652.0325 Conduit Rigid Nonmetallic Schedule 80 2-Inch	5.000 LF	_____.	_____.
0708	652.0335 Conduit Rigid Nonmetallic Schedule 80 3-Inch	990.000 LF	_____.	_____.
0710	652.0615 Conduit Special 3-Inch	128.000 LF	_____.	_____.
0712	652.0700.S Install Conduit into Existing Item	15.000 EACH	_____.	_____.
0714	652.0800 Conduit Loop Detector	204.000 LF	_____.	_____.
0716	653.0154 Pull Boxes Non-Conductive 24x36-Inch	9.000 EACH	_____.	_____.
0718	653.0164 Pull Boxes Non-Conductive 24x42-Inch	57.000 EACH	_____.	_____.
0720	653.0222 Junction Boxes 18x12x6-Inch	33.000 EACH	_____.	_____.
0722	653.0905 Removing Pull Boxes	8.000 EACH	_____.	_____.
0724	654.0102 Concrete Bases Type 2	1.000 EACH	_____.	_____.
0726	654.0105 Concrete Bases Type 5	11.000 EACH	_____.	_____.
0728	654.0107 Concrete Bases Type 7	63.000 EACH	_____.	_____.
0730	654.0230 Concrete Control Cabinet Bases Type L30	2.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 28 of 39

Proposal ID: 20260714005 **Project(s):** 1130-65-71, 1130-65-72, 1130-65-73, 1130-65-74, 1130-65-78**Federal ID(s):** WISC 2026379, WISC 2026380, WISC 2026381, WISC 2026382, WISC 2026383**SECTION:** 0001

Contract Items

Alt Set ID:**Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0732	655.0230 Cable Traffic Signal 5-14 AWG	138.000 LF	_____	_____
0734	655.0260 Cable Traffic Signal 12-14 AWG	263.000 LF	_____	_____
0736	655.0305 Cable Type UF 2-12 AWG Grounded	263.000 LF	_____	_____
0738	655.0515 Electrical Wire Traffic Signals 10 AWG	319.000 LF	_____	_____
0740	655.0610 Electrical Wire Lighting 12 AWG	68,443.000 LF	_____	_____
0742	655.0625 Electrical Wire Lighting 6 AWG	48,698.000 LF	_____	_____
0744	655.0630 Electrical Wire Lighting 4 AWG	190,037.000 LF	_____	_____
0746	655.0700 Loop Detector Lead In Cable	1,032.000 LF	_____	_____
0748	655.0800 Loop Detector Wire	424.000 LF	_____	_____
0750	656.0201 Electrical Service Meter Breaker Pedestal (location) 0001. MB3-3	1.000 EACH	_____	_____
0752	656.0201 Electrical Service Meter Breaker Pedestal (location) 0002. MB5-1	1.000 EACH	_____	_____
0754	656.0401 Electrical Service Main Lugs Only Meter Pedestal (location) 0001. CB800	1.000 EACH	_____	_____
0756	656.0401 Electrical Service Main Lugs Only Meter Pedestal (location) 0002. CB900	1.000 EACH	_____	_____
0758	656.0501 Electrical Service Breaker Disconnect Box (location) 0001. CB3-3	1.000 EACH	_____	_____



Proposal Schedule of Items

Page 29 of 39

Proposal ID: 20260714005 **Project(s):** 1130-65-71, 1130-65-72, 1130-65-73, 1130-65-74, 1130-65-78**Federal ID(s):** WISC 2026379, WISC 2026380, WISC 2026381, WISC 2026382, WISC 2026383**SECTION:** 0001

Contract Items

Alt Set ID:**Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0760	656.0501 Electrical Service Breaker Disconnect Box (location) 0003. CB6-1	1.000 EACH	_____.	_____.
0762	657.0210 Transformer Bases Breakaway 15-17 Inch Bolt Circle	127.000 EACH	_____.	_____.
0764	657.0255 Transformer Bases Breakaway 11 1/2-Inch Bolt Circle	9.000 EACH	_____.	_____.
0766	657.0310 Poles Type 3	1.000 EACH	_____.	_____.
0768	657.0322 Poles Type 5-Aluminum	34.000 EACH	_____.	_____.
0770	657.0337 Poles Type 17-Aluminum	128.000 EACH	_____.	_____.
0772	657.0605 Luminaire Arms Single Member 4 1/2-Inch Clamp 4-FT	23.000 EACH	_____.	_____.
0774	657.0620 Luminaire Arms Single Member 6-Inch Clamp 4-FT	181.000 EACH	_____.	_____.
0776	659.1120 Luminaires Utility LED B	23.000 EACH	_____.	_____.
0778	659.1125 Luminaires Utility LED C	181.000 EACH	_____.	_____.
0780	659.2230 Lighting Control Cabinets 240/480 30-Inch	2.000 EACH	_____.	_____.
0782	659.5000.S Lamp, Ballast, LED, Switch Disposal by Contractor	19.000 EACH	_____.	_____.
0784	670.0101 Field System Integrator	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 30 of 39

Proposal ID: 20260714005 **Project(s):** 1130-65-71, 1130-65-72, 1130-65-73, 1130-65-74, 1130-65-78**Federal ID(s):** WISC 2026379, WISC 2026380, WISC 2026381, WISC 2026382, WISC 2026383**SECTION:** 0001

Contract Items

Alt Set ID:**Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0786	670.0201 ITS Documentation	1.000 EACH	_____.	_____.
0788	671.0132 Conduit HDPE 3-Duct 2-Inch	12,615.000 LF	_____.	_____.
0790	671.0142 Conduit HDPE 4-Duct 2-Inch	4,731.000 LF	_____.	_____.
0792	671.0232 Conduit HDPE Directional Bore 3-Duct 2-Inch	1,480.000 LF	_____.	_____.
0794	671.0242 Conduit HDPE Directional Bore 4-Duct 2-Inch	368.000 LF	_____.	_____.
0796	671.0300 Fiber Optic Cable Marker	39.000 EACH	_____.	_____.
0798	673.0105 Communication Vault Type 1	17.000 EACH	_____.	_____.
0800	673.0200 Tracer Wire Marker Posts	34.000 EACH	_____.	_____.
0802	673.1225.S Install Pole Mounted Cabinet	14.000 EACH	_____.	_____.
0804	674.0200 Cable Microwave Detector	16,960.000 LF	_____.	_____.
0806	674.0300 Remove Cable	20,734.000 LF	_____.	_____.
0808	675.0300 Install Mounted Controller Microwave Detector Assembly	13.000 EACH	_____.	_____.
0810	677.0150 Install Camera Pole 50-FT	1.000 EACH	_____.	_____.
0812	677.0180 Install Camera Pole 80-FT	1.000 EACH	_____.	_____.
0814	677.0200 Install Camera Assembly	3.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 31 of 39

Proposal ID: 20260714005 **Project(s):** 1130-65-71, 1130-65-72, 1130-65-73, 1130-65-74, 1130-65-78**Federal ID(s):** WISC 2026379, WISC 2026380, WISC 2026381, WISC 2026382, WISC 2026383**SECTION:** 0001

Contract Items

Alt Set ID:**Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0816	677.9051.S Removing 50-FT Camera Pole	1.000 EACH	_____.	_____.
0818	678.0012 Install Fiber Optic Cable Outdoor Plant 12-CT	1,768.000 LF	_____.	_____.
0820	678.0024 Install Fiber Optic Cable Outdoor Plant 24-CT	1,488.000 LF	_____.	_____.
0822	678.0072 Install Fiber Optic Cable Outdoor Plant 72-CT	28,752.000 LF	_____.	_____.
0824	678.0200 Fiber Optic Splice Enclosure	5.000 EACH	_____.	_____.
0826	678.0300 Fiber Optic Splice	406.000 EACH	_____.	_____.
0828	678.0400 Fiber Optic Termination	28.000 EACH	_____.	_____.
0830	678.0501 Communication System Testing	4.000 EACH	_____.	_____.
0832	678.0600 Install Ethernet Switches	4.000 EACH	_____.	_____.
0834	678.0700 Install Wireless Antennas	6.000 EACH	_____.	_____.
0836	690.0150 Sawing Asphalt	46,340.000 LF	_____.	_____.
0838	690.0250 Sawing Concrete	4,923.000 LF	_____.	_____.
0840	715.0502 Incentive Strength Concrete Structures	70,798.000 DOL	1.00000	70,798.00
0842	715.0603 Incentive Strength Concrete Barrier	41,438.000 DOL	1.00000	41,438.00



Proposal Schedule of Items

Page 32 of 39

Proposal ID: 20260714005 **Project(s):** 1130-65-71, 1130-65-72, 1130-65-73, 1130-65-74, 1130-65-78**Federal ID(s):** WISC 2026379, WISC 2026380, WISC 2026381, WISC 2026382, WISC 2026383**SECTION:** 0001

Contract Items

Alt Set ID:**Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0844	715.0715 Incentive Flexural Strength Concrete Pavement	108,480.000 DOL	1.00000	108,480.00
0846	801.0117 Railroad Flagging Reimbursement	50,000.000 DOL	1.00000	50,000.00
0848	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	2,100.000 HRS	5.00000	10,500.00
0850	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	5,760.000 HRS	5.00000	28,800.00
0852	SPV.0035 Special 0100. Roadway Embankment	123,188.000 CY	_____.	_____.
0854	SPV.0035 Special 1000. HPC Masonry Structures	6,006.000 CY	_____.	_____.
0856	SPV.0035 Special 1010. Concrete Masonry Bridges Special	503.000 CY	_____.	_____.
0858	SPV.0035 Special 2000. Excavation, Hauling, and Reuse of Low-Level Contaminated Material	31,500.000 CY	_____.	_____.
0860	SPV.0035 Special 4020. Lightweight Foamed Concrete Fill Grade 1	11,103.000 CY	_____.	_____.
0862	SPV.0035 Special 4030. Lightweight Foamed Concrete Fill Grade 2	4,893.000 CY	_____.	_____.
0864	SPV.0055 Special 0100. Incentive IRI Ride PCC Surfaces	176,400.000 DOL	_____.	_____.
0866	SPV.0060 Special 0003. Concrete Barrier Transition Type M1	3.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 33 of 39

Proposal ID: 20260714005 **Project(s):** 1130-65-71, 1130-65-72, 1130-65-73, 1130-65-74, 1130-65-78**Federal ID(s):** WISC 2026379, WISC 2026380, WISC 2026381, WISC 2026382, WISC 2026383**SECTION:** 0001

Contract Items

Alt Set ID:**Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0868	SPV.0060 Special 0004. Concrete Barrier Transition Type M2	2.000 EACH	_____.	_____.
0870	SPV.0060 Special 0090. Fire Hydrant Sign Mounting	2.000 EACH	_____.	_____.
0872	SPV.0060 Special 0100. Construction Staking Survey Project 1130-65-71	1.000 EACH	_____.	_____.
0874	SPV.0060 Special 0105. Baseline CPM Progress Schedule	1.000 EACH	_____.	_____.
0876	SPV.0060 Special 0110. CPM Progress Schedule and Accepted Revisions	36.000 EACH	_____.	_____.
0878	SPV.0060 Special 0127. Sawing Concrete Barrier Single Faced	4.000 EACH	_____.	_____.
0880	SPV.0060 Special 0140. Concrete Barrier Transition	8.000 EACH	_____.	_____.
0882	SPV.0060 Special 0150. Adjusting Sanitary Manhole Covers	2.000 EACH	_____.	_____.
0884	SPV.0060 Special 0165. Emergency Response to Traffic Involving Concrete Barrier Temporary	53.000 EACH	_____.	_____.
0886	SPV.0060 Special 0170. Emergency Response to Traffic Involving Crash Cushion Temporary	35.000 EACH	_____.	_____.
0888	SPV.0060 Special 0200. Construction Staking Survey Project 1130-65-72	1.000 EACH	_____.	_____.
0890	SPV.0060 Special 0210. Storm Sewer Plug	3.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 34 of 39

Proposal ID: 20260714005 **Project(s):** 1130-65-71, 1130-65-72, 1130-65-73, 1130-65-74, 1130-65-78**Federal ID(s):** WISC 2026379, WISC 2026380, WISC 2026381, WISC 2026382, WISC 2026383**SECTION:** 0001

Contract Items

Alt Set ID:**Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0892	SPV.0060 Special 0215. Reconnect Storm Sewer	2.000 EACH	_____.	_____.
0894	SPV.0060 Special 0220. Pond A Outlet Storm Sewer Structure	1.000 EACH	_____.	_____.
0896	SPV.0060 Special 0225. Pond BC Outlet Storm Sewer Structure	1.000 EACH	_____.	_____.
0898	SPV.0060 Special 0230. Inlet Covers Type Y	5.000 EACH	_____.	_____.
0900	SPV.0060 Special 0235. Fastening Sewer Access Covers	65.000 EACH	_____.	_____.
0902	SPV.0060 Special 0240. Sealing Storm Sewer Structure	1.000 EACH	_____.	_____.
0904	SPV.0060 Special 0300. Construction Staking Survey Project 1130-65-73	1.000 EACH	_____.	_____.
0906	SPV.0060 Special 0400. Construction Staking Survey Project 1130-65-74	1.000 EACH	_____.	_____.
0908	SPV.0060 Special 0440. Fixed Message Sign Portable Support	20.000 EACH	_____.	_____.
0910	SPV.0060 Special 0500. Anchor Bolt Cover Shroud	17.000 EACH	_____.	_____.
0912	SPV.0060 Special 0501. Concrete Bases Type 7 Tall	77.000 EACH	_____.	_____.
0914	SPV.0060 Special 0502. Temporary Overhead Sign Structure (S-04-0001-Temp)	1.000 EACH	_____.	_____.
0916	SPV.0060 Special 0504. Temporary Overhead Sign Structure (S-04-0002-Temp)	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 35 of 39

Proposal ID: 20260714005 **Project(s):** 1130-65-71, 1130-65-72, 1130-65-73, 1130-65-74, 1130-65-78**Federal ID(s):** WISC 2026379, WISC 2026380, WISC 2026381, WISC 2026382, WISC 2026383**SECTION:** 0001 Contract Items**Alt Set ID:****Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0918	SPV.0060 Special 0510. Remove Traffic Signal S-44-0510 (STH SB & OO)	1.000 EACH	_____.	_____.
0920	SPV.0060 Special 0520. Temporary Overhead Sign Structure (S-04-0003-Temp)	1.000 EACH	_____.	_____.
0922	SPV.0060 Special 0530. Temporary Overhead Sign Structure (S-01-0004-Temp)	1.000 EACH	_____.	_____.
0924	SPV.0060 Special 0540. Relocating Temporary Overhead Sign Structure (S-01-0003-Temp)	3.000 EACH	_____.	_____.
0926	SPV.0060 Special 0550. Relocating Temporary Overhead Sign Structure (S-01-0004-Temp)	3.000 EACH	_____.	_____.
0928	SPV.0060 Special 0560. Transporting S-01-0001-Temp to Project	1.000 EACH	_____.	_____.
0930	SPV.0060 Special 0570. Transporting S-01-0002-Temp to Project	1.000 EACH	_____.	_____.
0932	SPV.0060 Special 0580. Transporting S-01-0003-Temp to Project	1.000 EACH	_____.	_____.
0934	SPV.0060 Special 0590. Transporting S-01-0004-Temp To Project	1.000 EACH	_____.	_____.
0936	SPV.0060 Special 0600. ANR Pipeline protection	1.000 EACH	_____.	_____.
0938	SPV.0060 Special 0601. Transporting S-01-0001-Temp to Department	1.000 EACH	_____.	_____.
0940	SPV.0060 Special 0610. Transporting S-01-0002-Temp to Department	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 36 of 39

Proposal ID: 20260714005 **Project(s):** 1130-65-71, 1130-65-72, 1130-65-73, 1130-65-74, 1130-65-78**Federal ID(s):** WISC 2026379, WISC 2026380, WISC 2026381, WISC 2026382, WISC 2026383**SECTION:** 0001 Contract Items**Alt Set ID:****Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0942	SPV.0060 Special 0620. Transporting S-01-0003-Temp to Department	1.000 EACH	_____.	_____.
0944	SPV.0060 Special 0630. Transporting S-01-0004-Temp to Department	1.000 EACH	_____.	_____.
0946	SPV.0060 Special 0701. Install Ethernet Extender	22.000 EACH	_____.	_____.
0948	SPV.0060 Special 0702. Salvaging Microwave Detector Equipment	1.000 EACH	_____.	_____.
0950	SPV.0060 Special 0703. Salvaging Wireless Antennas	3.000 EACH	_____.	_____.
0952	SPV.0060 Special 0704. Remove and Reinstall ITS Equipment	1.000 EACH	_____.	_____.
0954	SPV.0060 Special 0705. Wood Pole 60-ft	1.000 EACH	_____.	_____.
0956	SPV.0060 Special 0706. Remove Poles Wood	1.000 EACH	_____.	_____.
0958	SPV.0060 Special 0800. Construction Staking Survey Project 1130-65-78	1.000 EACH	_____.	_____.
0960	SPV.0060 Special 0900. Precast Concrete Wingwalls (C-44-0146)	4.000 EACH	_____.	_____.
0962	SPV.0060 Special 0901. Precast Concrete Wingwalls (C-44-0147)	1.000 EACH	_____.	_____.
0964	SPV.0060 Special 1000. Pile Dynamic Analyzer (PDA) Testing	64.000 EACH	_____.	_____.
0966	SPV.0060 Special 1010. Pile Dynamic Analyzer (PDA) Restrikes	64.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 37 of 39

Proposal ID: 20260714005 **Project(s):** 1130-65-71, 1130-65-72, 1130-65-73, 1130-65-74, 1130-65-78**Federal ID(s):** WISC 2026379, WISC 2026380, WISC 2026381, WISC 2026382, WISC 2026383**SECTION:** 0001

Contract Items

Alt Set ID:**Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0968	SPV.0060 Special 1020. Case Pile Wave Analysis Program (CAPWAP) Evaluation	32.000 EACH	_____.	_____.
0970	SPV.0060 Special 2000. Inlet Markers	409.000 EACH	_____.	_____.
0972	SPV.0075 Special 0100. Street Sweeping	1,000.000 HRS	_____.	_____.
0974	SPV.0075 Special 5000. Animal Carcass Removal	184.000 HRS	_____.	_____.
0976	SPV.0085 Special 1000. Post-Tensioning integral Pier Cap	2,460.000 LB	_____.	_____.
0978	SPV.0090 Special 0100. HMA Longitudinal Joint Repair	7,100.000 LF	_____.	_____.
0980	SPV.0090 Special 0115. Concrete Barrier Type S42 Special	44,407.000 LF	_____.	_____.
0982	SPV.0090 Special 0120. Concrete Barrier Type S56 Special	36,443.000 LF	_____.	_____.
0984	SPV.0090 Special 0125. Single Slope Concrete Barrier Retaining Wall	2,005.000 LF	_____.	_____.
0986	SPV.0090 Special 0154. Concrete Gutter 48-Inch	1,008.000 LF	_____.	_____.
0988	SPV.0090 Special 0200. Slotted Vane Drain Permanent	1,294.000 LF	_____.	_____.
0990	SPV.0090 Special 0205. Slotted Vane Drain Temporary	1,080.000 LF	_____.	_____.
0992	SPV.0090 Special 0210. Cure In Place Liner For 36-Inch Pipe	359.000 LF	_____.	_____.



Proposal Schedule of Items

Page 38 of 39

Proposal ID: 20260714005 **Project(s):** 1130-65-71, 1130-65-72, 1130-65-73, 1130-65-74, 1130-65-78**Federal ID(s):** WISC 2026379, WISC 2026380, WISC 2026381, WISC 2026382, WISC 2026383**SECTION:** 0001

Contract Items

Alt Set ID:**Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0994	SPV.0090 Special 0215. Jack and Bore Storm Sewer Pipe Reinforced Concrete Pipe Class V 36-Inch	270.000 LF	_____.	_____.
0996	SPV.0090 Special 0220. Jack and Bore Storm Sewer Pipe Reinforced Concrete Pipe Class V 48-Inch	418.000 LF	_____.	_____.
0998	SPV.0090 Special 0305. Glare Screen Temporary	4,300.000 LF	_____.	_____.
1000	SPV.0090 Special 0800. Abutment Anchorage	43.000 LF	_____.	_____.
1004	SPV.0090 Special 1010. Pile Wrapping	325.000 LF	_____.	_____.
1006	SPV.0090 Special 1020. Piling CIP Concrete 14 x 0.50-Inch Special	22,310.000 LF	_____.	_____.
1008	SPV.0090 Special 2000. Pipe Underdrain 6-Inch Special	49,732.000 LF	_____.	_____.
1010	SPV.0165 Special 0042. Wall Concrete Panel Mechanically Stabilized Earth (R-44-0042)	2,945.000 SF	_____.	_____.
1012	SPV.0165 Special 0142. Wall Concrete Panel Mechanically Stabilized Earth, LFCF (R-44-0042)	12,610.000 SF	_____.	_____.
1014	SPV.0165 Special 0145. Wall Concrete Panel Mechanically Stabilized Earth, LFCF (R-44-0045)	6,555.000 SF	_____.	_____.
1016	SPV.0165 Special 0147. Wall Concrete Panel Mechanically Stabilized Earth, LFCF (R-44-0047)	940.000 SF	_____.	_____.



Proposal Schedule of Items

Page 39 of 39

Proposal ID: 20260714005 **Project(s):** 1130-65-71, 1130-65-72, 1130-65-73, 1130-65-74, 1130-65-78**Federal ID(s):** WISC 2026379, WISC 2026380, WISC 2026381, WISC 2026382, WISC 2026383**SECTION:** 0001

Contract Items

Alt Set ID:**Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
1018	SPV.0165 Special 1000. Longitudinal Grooving Bridge Deck	132,290.000 SF	_____.	_____.
1020	SPV.0180 Special 0100. Concrete Pavement 10 1/2-Inch Special	276,488.000 SY	_____.	_____.
1022	SPV.0180 Special 0127. Methacrylate Flood Seal	1,911.000 SY	_____.	_____.
1024	646.2025 Marking Line Grooved Black Epoxy 6-Inch	24,699.000 LF	_____.	_____.
1026	646.4025 Marking Line Grooved Black Epoxy 10-Inch	6,000.000 LF	_____.	_____.
1028	SPV.0090 Special 0900. Precast Concrete Box Culvert 8 FT x 4 FT	198.000 LF	_____.	_____.
1030	511.1200 Temporary Shoring (structure) 0327. B-44-327	4,500.000 SF	_____.	_____.
1032	640.1305.S Clay Cover	650.000 CY	_____.	_____.
1034	SPV.0075 Special 2000. Roadway Debris Removal	80.000 HRS	_____.	_____.
1036	SPV.0090 Special 0910. Precast Concrete Box Culvert, 9FT x 5FT	200.000 LF	_____.	_____.
Section: 0001			Total:	_____.
			Total Bid:	_____.

