



Wisconsin Department of Transportation

July 30, 2026

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #14: 1053-07-85, WISC2026441
Abbotsford-Wausau
CTH E South to STH 97, WB
STH 29
Marathon County

Letting of August 11, 2026

This is Addendum No. 01, which provides for the following:

Special Provisions:

Revised Special Provisions	
Article No.	Description
19	Grading and Shaping Ditch

Added Special Provisions	
Article No.	Description
21	Notice to Contractor, Contamination Beyond Construction Limits

Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Proposal Quantity Change (-)	Proposal Total After Addendum
205.0100	Excavation Common	CY	72,521	-236	72,285
312.0110	Select Crushed Material	TON	56,839	-21	56,818
624.0100	Water	MGAL	1,116	-1	1,115

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
56	Miscellaneous Quantities (Update to Excavation Common, Select Crushed Material and Water)
61	Miscellaneous Quantities (Added CY of Excavation Common for information only)
68	Plan and Profile (Added approximate limits of residual soil contamination)
155	Earthwork (Removed cut associated with Grading and Shaping Ditch)
156	Earthwork (Removed cut associated with Grading and Shaping Ditch)
157	Earthwork (Updated Totals)

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01

1053-07-85

July 30, 2026

Special Provisions

19. Grading and Shaping Ditch

*Replace the last two paragraphs under section titled **E Payment** with the following:*

Payment is full compensation for all excavation, grading, shaping, and compacting; furnishing and placing fill if necessary; and disposal of surplus material.

Any required riprap, geotextile fabric, topsoil, erosion control, and finishing items will be measured and paid for separately under the pertinent items provided in the contract.

21. Notice to Contractor, Contamination Beyond Construction Limits.

The department completed case file review for locations within the project where excavation is required. Review findings indicated that petroleum contaminated soil is suspected to be present at the following locations:

Oleinik Property (BRRS #03-37-557053) 1556 STH 29 Village of Edgar, WI 54426	Residual soil contamination is suspected beyond construction limits from Station 9665+50 WB to 9666+25 WB, approximately 60 feet left of centerline. Contaminated soil is suspected at a depth of approximately 4 to 16 feet below ground surface. Depth to groundwater is anticipated to be greater than 16 ft below ground surface and is not anticipated to be encountered with construction.
---	---

The contaminated soils at the above sites are expected to be beyond the excavation limits necessary to complete the work under this project. Control construction operations at these locations to ensure that they do not extend beyond the excavation limits indicated in the plans. If contaminated soils are encountered at these sites or elsewhere on the project during excavation, terminate excavation in the area and notify the engineer.

Schedule of Items

Attached, dated July 30, 2026, are the revised Schedule of Items Pages 1 and 3.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 56, 61, 68, 155, 156, and 157.

END OF ADDENDUM

DIVISION	STATION - STATION	LOCATION	205.0100 EXCAVATION COMMON (1)		SALVAGED/UNUSABLE PAVEMENT MATERIAL	AVAILABLE MATERIAL (4)	UNEXPANDED FILL	EXPANDED FILL		MASS ORDINATE +/- (6)	WASTE	312.0110* SELECT CRUSHED MATERIAL (TON)	624.0100* WATER (FOR DUST CONTROL) (MGAL)
			CUT (2)	EBS EXCAVATION (3)				FACTOR 1.25 (5)					
5TH 29 MAINLINE	9576+08 WB - 9713+68 WB	LT/RT	58,374	2,919	12,531	45,843	245	306	48,455	48,455	48,455	5,546	64
CROSSOVER REMOVAL	9692+00 WB - 9713+68 WB	RT	2,455	0	0	2,455	0	0	2,455	2,455	2,455	0	2
SIDEROADS		LT/RT	1,602	80	361	1,241	37	46	1,275	1,275	1,275	152	2
BURIED CONCRETE REMOVAL (7)		LT	6,855	0	2,354	4,501	0	0	4,501	4,501	4,501	0	7
GRAND TOTAL			69,286	2,999	15,246	54,040	282	353	56,686	56,686	56,686	5,698	75
TOTAL COMMON ETC			72,285										

*ADDITIONAL QUANTITIES LISTED ELSEWHERE

NOTES:

- (1) EXCAVATION COMMON IS THE SUM OF THE CUT AND EBS EXCAVATION COLUMNS. ITEM NUMBER 205.0100.
(2) SALVAGED/UNUSABLE PAVEMENT MATERIAL IS INCLUDED IN CUT.
(3) EBS EXCAVATION TO BE BACKFILLED WITH SELECT CRUSHED MATERIAL OR SUITABLE CUT MATERIAL AS DIRECTED BY THE PROJECT ENGINEER.
(4) AVAILABLE MATERIAL = CUT - SALVAGED/UNUSABLE PAVEMENT MATERIAL.
(5) EXPANDED FILL = UNEXPANDED FILL * EXPANDED FILL FACTOR. EXPANDED FILL FACTOR = 1.25.
(6) MASS ORDINATE = CUT + EBS EXCAVATION - SALVAGED/UNUSABLE PAVEMENT MATERIAL - EXPANDED FILL. PLUS QUANTITY INDICATES AN EXCESS OF MATERIAL WITHIN THE DIVISION. MINUS INDICATES A SHORTAGE OF MATERIAL WITHIN THE DIVISION.
(7) BURIED CONCRETE PAVEMENT REMOVED IS INCLUDED IN SALVAGED/UNUSABLE PAVEMENT MATERIAL. REMAINING EBS MATERIAL IS INCLUDED IN AVAILABLE MATERIAL AND TO BE USED TO BACKFILL EBS AS DIRECTED BY THE PROJECT ENGINEER.

Addendum No. 01
ID 1053-07-85
Revised Sheet 56
July 30, 2026

Addendum No. 01
ID 1053-07-85
Revised Sheet 61
July 30, 2026

PERMANENT MARKING SUMMARY

CATEGORY	STATION - STATION	646.2025		646.2040		646.2050		646.4050		646.6466	
		MARKING LINE GROOVED BLACK EPOXY 6-INCH (BLACK SKIP) (12.5' SEG) LF	MARKING LINE GROOVED W/ET REF EPOXY 6-INCH (WHITE) (YELLOW) (12.5' SEG) LF	MARKING LINE GROOVED PERMANENT TAPE 6-INCH (WHITESKIP) LF	MARKING LINE GROOVED PERMANENT TAPE 10-INCH (WHITE) LF	MARKING LINE GROOVED PERMANENT TAPE 10-INCH (WHITE) LF	MARKING LINE GROOVED PERMANENT TAPE 10-INCH (WHITE) LF	MARKING LINE GROOVED PERMANENT TAPE 10-INCH (WHITE) LF	MARKING LINE GROOVED PERMANENT TAPE 10-INCH (WHITE) LF	MARKING LINE GROOVED PERMANENT TAPE 10-INCH (WHITE) LF	MARKING LINE GROOVED PERMANENT TAPE 10-INCH (WHITE) LF
0010	MAINLINE 9543+42 WB - 9600+00 WB 9600+00 WB - 9650+00 WB 9650+00 WB - 9700+00 WB 9700+00 WB - 9770+89 WB	1,170	4,440	5,880	1,170	390	1,110	1,470	2,435	2,443	2,500
		2,500	9,740	9,770	2,500	410	2,435	2,500	2,500	2,500	2,500
		3,540	10,000	10,000	2,500	--	2,500	433	433	433	433
		1,730	1,730	1,730	3,540	3,620	433	433	433	433	433
SUBTOTALS		9,710	25,910	27,380	9,710	4,420	6,478	6,846			
ITEM TOTALS		9,710	53,290	9,710	4,420	13,324	13,324	13,324			

TRAFFIC CONTROL SIGNS FIXED MESSAGE

CATEGORY	LOCATION	SIGN MESSAGE	SIZE		NOTES
			IN X IN	SF	
0010	EB STH 29 AT CTH E	HWY 29	96 X 48	32	INSTALL 7 DAYS BEFORE CONSTRUCTION START
		ROAD WORK BEGINS XXX-XX			
	WB STH 29 WEST OF STH 97	HWY 28	96 X 48	32	INSTALL 7 DAYS BEFORE CONSTRUCTION START
		ROAD WORK BEGINS XXX-XX			
	WB STH 29 AT STH 97 EXIT RAMP	WIDE LOADS EXCEEDING 14FT	114 X 42	33	INSTALL WITH ADVANCED WARNING SIGNING
TOTAL					97

CONSTRUCTION STAKING SUMMARY

CATEGORY	STATION - STATION	LOCATION	650.4500		650.5000		650.5500		650.6000		650.7000		650.9920	
			CONSTRUCTION STAKING SUBGRADE	LF	CONSTRUCTION STAKING BASE	LF	CONSTRUCTION STAKING CURB/GUTTER AND	LF	CONSTRUCTION STAKING PIPE/CULVERTS	LF	CONSTRUCTION STAKING CONCRETE PAVEMENT	LF	CONSTRUCTION SLOPE/STAKES	LF
0010	MAINLINE	9576+08 WB - 9600+00 WB	2,392	935	151	151	---	2,392	2,392	5,000	5,000	5,000	700	700
		9600+00 WB - 9650+00 WB	LT/RT	740	151	---	1	---	---	---	---	---	---	---
		9650+00 WB - 9700+00 WB	LT/RT	5,000	---	---	---	---	---	---	---	---	---	---
		9700+00 WB - 9707+00 WB	LT/RT	700	---	---	---	---	---	---	---	---	---	---
TOTALS			13,092	1,675	302	1	13,092	13,092	13,092	13,092	13,092	13,092	13,092	

PROJECT NO: 1053-07-85

HWY: STH 29

COUNTY: MARATHON

MISCELLANEOUS QUANTITIES

FILE NAME :

PLOT DATE :

PLOT BY :

PLOT NAME :

1" = 1'

WISDOT/CADD'S SHEET 42

SHEET: 61

*FOR INFORMATION ONLY

NOTE: SEE CROSS SECTIONS AND EARTHWORK DATA SHEETS FOR ADDITIONAL INFORMATION ON GRADING AND SHAPING LOCATIONS.

GRADING AND SHAPING DITCH

CATEGORY	STATION - STATION	LOCATION	SPV.0090.01		REMARKS* (CY EXCAVATION)
			LF		
0010	9583+00 WB - 9586+60 WB	RT	360		88
	9595+00 WB - 9595+70 WB	RT	70		9
	9607+30 WB - 9607+46 WB	RT	66		22
	9608+46 WB - 9610+00 WB	RT	154		33
	9654+47 WB - 9658+62 WB	RT	415		84
TOTAL			1,065		

SAWING

CATEGORY	STAGE	STATION - STATION	LOCATION	690.0150		690.0250	
				ASPHALT	CONCRETE	LF	LF
0010	STAGE 1	9565+39 WB - 9600+00 WB	LT/RT	150	1,069		
		9600+00 WB - 9650+00 WB	RT	264	—		
		9650+00 WB - 9700+00 WB	RT	726	—		
		9700+00 WB - 9713+68 WB	LT/RT	2,202	26		
		TOTALS		3,342	1,095		

5

Addendum No. 01
ID 1053-07-85
Revised Sheet 155
July 30, 2026

DIVISION - STH 29 MAINLINE

STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL. (CY) (UNADJUSTED)		CUMULATIVE VOL. (CY)	
		CUT	FILL	CUT	FILL	CUT	FILL
9576+08.01	0.00	120.13	0.00	0	0	0	0
9577+00.00	91.99	144.75	1.10	451	2	451	3
9578+00.00	100.00	128.20	0.00	505	2	956	5
9579+00.00	100.00	139.46	6.06	496	11	1,452	19
9580+00.00	100.00	146.33	5.92	529	22	1,981	46
9581+00.00	100.00	137.32	0.27	525	11	2,506	60
9582+00.00	100.00	128.55	0.00	492	1	2,998	61
9583+02.45	2.45	119.89	0.00	11	0	3,470	61
9584+00.00	97.55	121.15	0.00	435	5	3,925	68
9585+00.00	100.00	123.48	0.00	453	4	4,401	73
9586+00.00	100.00	129.36	0.00	468	1	4,897	74
9586+59.85	59.85	126.85	0.00	284	1	5,195	75
9587+00.00	40.15	129.88	0.00	195	0	5,390	76
9588+00.00	100.00	129.66	0.00	481	0	5,871	76
9589+00.00	100.00	124.65	0.00	471	0	6,342	76
9590+00.00	100.00	118.63	0.00	451	0	6,793	76
9591+00.00	100.00	114.85	0.21	432	0	7,225	76
9592+00.00	100.00	115.02	0.92	426	2	7,651	79
9593+00.00	100.00	118.74	0.00	433	2	8,084	81
9594+00.00	100.00	117.12	0.00	437	0	8,521	81
9595+00.00	100.00	110.18	0.37	421	1	8,947	86
9595+70.97	70.97	106.14	0.13	284	1	9,235	115
9596+00.00	28.35	106.33	0.00	115	0	9,350	125
9597+00.00	100.00	110.46	0.38	405	1	9,755	126
9598+00.00	100.00	114.80	1.10	417	3	10,172	130
9599+00.00	100.00	115.92	0.43	427	3	10,599	134
9600+00.00	100.00	116.25	0.16	430	1	11,029	135
9601+00.00	100.00	119.04	0.00	436	0	11,465	135
9602+00.00	100.00	115.77	0.20	435	0	11,900	135
9603+00.00	100.00	114.41	0.00	426	0	12,326	135
9604+00.00	100.00	118.54	0.00	431	0	12,757	135
9605+00.00	100.00	113.15	0.00	429	0	13,186	135
9606+00.00	100.00	111.85	0.00	417	0	13,603	135
9607+00.00	100.00	106.52	0.73	406	0	14,009	135
9607+30.27	30.27	108.45	0.13	122	0	14,136	135
9607+86.17	55.90	110.69	0.11	228	0	14,381	136
9608+00.00	18.83	107.43	0.00	57	0	14,438	136
9608+23.29	23.29	104.35	0.00	97	0	14,535	136
9608+60.13	36.80	112.19	0.00	146	0	14,678	136
9609+00.00	39.81	110.90	0.00	164	3	14,852	140
9609+96.78	96.78	107.53	0.10	391	8	15,256	150
9610+00.00	3.22	106.48	0.08	13	0	15,269	150
9611+00.00	100.00	110.80	0.06	406	0	15,675	150
9612+00.00	100.00	116.28	0.00	421	0	16,096	150
9613+00.00	100.00	115.81	0.08	430	0	16,526	150
9614+00.00	100.00	120.19	0.22	437	1	16,963	151
9615+00.00	100.00	122.61	0.00	450	0	17,413	151
9616+00.00	100.00	119.43	0.00	448	0	17,861	151
9617+00.00	100.00	123.51	0.00	450	0	18,311	151
9618+00.00	100.00	125.98	0.00	462	0	18,773	151
9619+00.00	100.00	127.73	0.00	470	0	19,243	151
9620+00.00	100.00	128.04	0.00	474	0	19,717	151
9621+00.00	100.00	126.21	0.00	471	0	20,188	151
9622+00.00	100.00	126.06	0.00	467	0	20,655	151

NOTES:
1- CUT INCLUDES SALVAGED/UNUSABLE PAVEMENT MATERIAL
2- FILL DOES NOT INCLUDE UNUSABLE PAVEMENT EXC VOLUME

PROJECT NO: 1053-07-85

COUNTY: MARATHON

EARTHWORK

SHEET: 155

FILE NAME:

PLOT DATE:

PLOT BY:

PLOT SCALE: 1" = 1'

WISDOT/CADD SHEET 42

DIVISION - STH 29 MAINLINE

STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)		CUMULATIVE VOL (CY)	
		CUT	FILL	CUT	FILL	CUT	EXPANDED FILL
		NOTE 1	NOTE 2	NOTE 1	NOTE 2	1.00	1.25
9623+00.00	100.00	128.11	0.00	471	0	21,126	151
9624+00.00	100.00	124.67	0.00	468	0	21,594	151
9625+00.00	100.00	119.70	0.00	453	0	22,047	151
9626+00.00	100.00	120.81	0.00	445	0	22,492	151
9627+00.00	100.00	121.17	0.01	448	0	22,940	151
9628+00.00	100.00	120.37	0.11	447	0	23,387	151
9629+00.00	100.00	124.17	0.01	453	0	23,840	151
9630+00.00	100.00	132.34	0.00	475	0	24,315	151
9631+00.00	100.00	142.97	0.00	510	0	24,825	151
9632+00.00	100.00	138.66	2.65	522	5	25,347	158
9633+00.00	100.00	112.10	0.38	465	6	25,812	165
9634+00.00	100.00	121.34	0.00	432	1	26,244	166
9635+00.00	100.00	117.08	1.32	442	2	26,686	169
9635+62.27	62.27	116.36	0.00	269	2	26,955	171
9636+00.00	37.73	120.21	0.00	165	0	27,120	171
9637+00.00	100.00	123.61	0.00	452	0	27,572	171
9638+00.00	100.00	119.48	0.00	450	0	28,022	171
9639+00.00	100.00	118.24	0.00	440	0	28,462	171
9640+00.00	100.00	116.59	0.01	435	0	28,897	171
9641+00.00	100.00	114.07	0.04	427	0	29,324	171
9642+00.00	100.00	113.92	0.07	422	0	29,746	171
9643+00.00	100.00	117.63	0.05	429	0	30,175	171
9644+00.00	100.00	117.48	0.24	435	1	30,610	173
9644+60.20	60.20	109.07	0.00	253	0	30,863	173
9645+00.00	39.80	114.61	0.00	165	0	31,028	173
9646+00.00	100.00	122.25	0.00	439	0	31,467	173
9647+00.00	100.00	118.37	0.01	446	0	31,913	173
9648+00.00	100.00	117.51	0.12	437	0	32,350	173
9649+00.00	100.00	118.79	0.00	438	0	32,788	173
9650+00.00	100.00	119.71	0.02	442	0	33,230	173
9651+00.00	100.00	115.61	0.21	436	0	33,666	173
9652+00.00	100.00	117.89	0.25	432	1	34,098	174
9653+00.00	100.00	115.38	1.10	432	2	34,530	176
9654+00.00	100.00	115.75	1.40	428	3	34,958	180
9654+47.24	47.24	116.59	0.49	203	2	35,166	190
9655+00.00	52.76	117.15	0.47	228	1	35,407	199
9656+00.00	100.00	120.50	1.14	440	3	35,879	208
9657+00.00	100.00	121.55	0.10	448	2	36,346	213
9658+00.00	100.00	125.67	0.52	458	1	36,810	228
9658+62.24	62.24	123.02	0.25	287	1	37,103	241
9659+00.00	37.76	119.15	0.64	171	3	37,274	245
9660+00.00	100.00	111.22	0.54	427	2	37,701	248
9661+00.00	100.00	112.96	0.17	415	1	38,116	249
9662+00.00	100.00	115.73	0.00	424	0	38,540	249
9663+00.00	100.00	123.98	0.00	444	0	38,984	249
9664+00.00	100.00	130.64	0.00	472	0	39,456	249
9665+00.00	100.00	125.79	0.03	475	0	39,931	249
9666+00.00	100.00	125.91	0.00	466	0	40,397	249
9667+00.00	100.00	124.22	0.00	463	0	40,860	249
9667+81.56	81.56	118.83	0.00	367	0	41,227	249
9668+00.00	18.44	118.21	0.00	81	0	41,308	249
9669+00.00	100.00	120.01	0.00	441	0	41,749	249
9670+00.00	100.00	121.36	0.00	447	0	42,196	249
9671+00.00	100.00	119.79	0.00	447	0	42,643	249
9672+00.00	100.00	117.07	0.00	439	0	43,082	249

NOTES:
1- CUT INCLUDES SALVAGED/UNUSABLE PAVEMENT MATERIAL
2- FILL DOES NOT INCLUDE UNUSABLE PAVEMENT EXC VOLUME

PROJECT NO: 1053-07-85

HWY: STH 29

COUNTY: MARATHON

EARTHWORK

PLOT NAME: _____
PLOT SCALE: 1" = 1'

SHEET: 156

E
WISDOT/CADD'S SHEET 42

Addendum No. 01
ID 1053-07-85
Revised Sheet 156
July 30, 2026

Addendum No. 01
ID 1053-07-85
Revised Sheet 157
July 30, 2026

DIVISION - STH 29 MAINLINE

STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL. (CY) (UNADJUSTED)		CUMULATIVE VOL. (CY)	
		CUT	FILL	CUT	FILL	CUT	EXPANDED FILL
		NOTE 1	NOTE 2	NOTE 1	NOTE 2	NOTE 1	NOTE 1
9673+00.00	100.00	115.87	0.00	431	0	43,513	249
9674+00.00	100.00	114.95	0.12	427	0	43,940	249
9675+00.00	100.00	115.72	0.76	426	2	44,366	251
9675+37.50	37.50	105.17	0.00	153	1	44,519	253
9675+55.19	17.69	104.90	0.00	69	0	44,588	253
9676+00.00	44.81	113.60	0.27	181	0	44,769	253
9677+00.00	100.00	115.87	0.22	425	1	45,194	254
9678+00.00	100.00	110.17	1.67	419	4	45,613	259
9679+00.00	100.00	107.58	1.41	403	6	46,016	266
9680+00.00	100.00	107.39	2.81	398	8	46,414	276
9681+00.00	100.00	109.66	1.11	402	7	46,816	285
9682+00.00	100.00	106.34	0.40	400	3	47,216	289
9683+00.00	100.00	115.69	0.00	411	1	47,627	290
9684+00.00	100.00	122.56	0.00	441	0	48,068	290
9685+00.00	100.00	125.32	0.00	459	0	48,527	290
9686+00.00	100.00	127.33	0.00	468	0	48,995	290
9687+00.00	100.00	127.05	0.00	471	0	49,466	290
9688+00.00	100.00	126.97	0.00	470	0	49,936	290
9689+00.00	100.00	123.34	0.00	464	0	50,400	290
9690+00.00	100.00	123.90	0.00	458	0	50,858	290
9691+00.00	100.00	121.48	0.01	454	0	51,312	290
9692+00.00	100.00	132.30	2.93	470	5	51,782	296
9693+00.00	100.00	123.72	1.01	474	7	52,256	305
9694+00.00	100.00	118.16	8.79	448	18	52,704	328
9695+00.00	100.00	121.57	4.99	444	26	53,148	360
9696+00.00	100.00	126.13	0.69	459	11	53,607	374
9697+00.00	100.00	130.34	0.61	475	2	54,082	376
9698+00.00	100.00	135.57	0.72	492	2	54,574	379
9699+00.00	100.00	133.88	0.39	499	2	55,073	381
9700+00.00	100.00	133.00	0.19	494	1	55,567	383
9701+00.00	100.00	147.21	0.47	519	1	56,086	384
9702+00.00	100.00	108.69	0.00	474	1	56,560	385
9703+00.00	100.00	176.71	0.10	529	0	57,089	385
9704+00.00	100.00	181.70	0.01	664	0	57,753	385
9705+00.00	100.00	185.67	0.00	680	0	58,433	385
9706+00.00	100.00	188.96	0.00	694	0	59,127	385
9707+00.00	100.00	187.82	0.00	698	0	59,825	385
9708+00.00	100.00	65.82	0.00	470	0	60,295	385
9709+00.00	100.00	60.43	0.00	234	0	60,529	385
9710+00.00	100.00	47.36	0.00	200	0	60,729	385
9711+00.00	100.00	26.65	0.00	137	0	60,866	385
9712+00.00	100.00	20.69	0.00	88.00	0.00	60,954	385
9713+00.00	100.00	17.15	0.00	70	0	61,024	385
9713+67.96	67.96	67.43	0.66	30	1	61,054	386
		COLUMN TOTALS		60,829	245		

NOTES:
1- CUT INCLUDES SALVAGED/UNUSABLE PAVEMENT MATERIAL
2- FILL DOES NOT INCLUDE UNUSABLE PAVEMENT EXC VOLUME

PROJECT NO: 1053-07-85

HWY: STH 29

COUNTY: MARATHON

EARTHWORK

PLOT NAME: _____
PLOT SCALE: 1" = 1'

SHEET: 157

E
WISDOT/CADD/SHEET 42



Proposal Schedule of Items

Page 1 of 7

Proposal ID: 20260811014 Project(s): 1053-07-85

Federal ID(s): WISC 2026441

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	203.0100 Removing Small Pipe Culverts	1.000 EACH	_____.	_____.
0004	204.0100 Removing Concrete Pavement	37,730.000 SY	_____.	_____.
0006	204.0110 Removing Asphaltic Surface	360.000 SY	_____.	_____.
0008	204.0150 Removing Curb & Gutter	300.000 LF	_____.	_____.
0010	204.0180 Removing Delineators and Markers	34.000 EACH	_____.	_____.
0012	204.0220 Removing Inlets	1.000 EACH	_____.	_____.
0014	204.0245 Removing Storm Sewer (size) 01. 18-Inch	8.000 LF	_____.	_____.
0016	204.9180.S Removing (item description) 01. Buried Concrete Pavement	9,390.000 SY	_____.	_____.
0018	205.0100 Excavation Common	72,285.000 CY	_____.	_____.
0020	211.0400 Prepare Foundation for Asphaltic Shoulders	11.000 STA	_____.	_____.
0022	213.0100 Finishing Roadway (project) 01. 1053-07-85	1.000 EACH	_____.	_____.
0024	305.0110 Base Aggregate Dense 3/4-Inch	7,210.000 TON	_____.	_____.
0026	305.0120 Base Aggregate Dense 1 1/4-Inch	34,700.000 TON	_____.	_____.
0028	312.0110 Select Crushed Material	56,818.000 TON	_____.	_____.
0030	415.0210 Concrete Pavement Gaps	2.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 3 of 7

Proposal ID: 20260811014 Project(s): 1053-07-85

Federal ID(s): WISC 2026441

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0062	612.0406 Pipe Underdrain Wrapped 6-Inch	720.000 LF	_____.	_____.
0064	618.0100 Maintenance and Repair of Haul Roads (project) 01. 1053-07-85	1.000 EACH	_____.	_____.
0066	619.1000 Mobilization	1.000 EACH	_____.	_____.
0068	624.0100 Water	1,115.000 MGAL	_____.	_____.
0070	625.0100 Topsoil	13,480.000 SY	_____.	_____.
0072	628.1905 Mobilizations Erosion Control	8.000 EACH	_____.	_____.
0074	628.1910 Mobilizations Emergency Erosion Control	4.000 EACH	_____.	_____.
0076	628.2008 Erosion Mat Urban Class I Type B	13,480.000 SY	_____.	_____.
0078	628.7005 Inlet Protection Type A	8.000 EACH	_____.	_____.
0080	628.7504 Temporary Ditch Checks	154.000 LF	_____.	_____.
0082	628.7555 Culvert Pipe Checks	92.000 EACH	_____.	_____.
0084	628.7560 Tracking Pads	3.000 EACH	_____.	_____.
0086	628.7570 Rock Bags	20.000 EACH	_____.	_____.
0088	629.0210 Fertilizer Type B	64.100 CWT	_____.	_____.
0090	630.0130 Seeding Mixture No. 30	2,112.000 LB	_____.	_____.
0092	630.0300 Seeding Borrow Pit	345.000 LB	_____.	_____.

