



Wisconsin Department of Transportation

July 30, 2026

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631

Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #18: 1510-02-60 / WISC 2026435
Waupaca - Appleton
Appletree Lane to Old STH 49, EB
USH 10
Waupaca County

Letting of August 11, 2026

This is Addendum No. 01, which provides for the following:

Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Proposal Quantity Change (-)	Proposal Total After Addendum
205.0100	Excavation Common	CY	12,290	-250	12,040
208.0100	Borrow	CY	990	-550	440

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
108	Updates to the Earthwork Table
303	Revised Salvaged/Unusable Pavement Material
304	Revised Salvaged/Unusable Pavement Material

Schedule of Items

Attached, dated July 30, 2026, are the revised Schedule of Items Pages 1 and 2.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 108, 303, and 304.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

END OF ADDENDUM

REMOVALS

CATEGORY	LOCATION	203.0100	204.0100	204.0110	204.0115	204.0120	204.0150	204.0165	204.0180	204.0190	204.0220	204.0245	REMARKS
0010	CTH X/MAIN STREET BTW RAMPS	-	-	-	61	2,877	-	-	-	-	-	-	-
0010	CROSSOVERS, MEDIAN TURNBAYS, SIDEROADS	-	-	-	2,789	20,425	-	-	-	-	-	-	-
0010	CROSSOVER PAVEMENT SEGMENT 1	-	6657	-	-	-	-	-	-	-	-	-	NO SEPARATE PAYMENT FOR COMMON EXCAVATION INCLUDED FOR PAVEMENT REMOVAL
0010	CROSSOVER PAVEMENT SEGMENT 2	-	17903	-	-	-	-	-	-	-	-	-	NO SEPARATE PAYMENT FOR COMMON EXCAVATION INCLUDED FOR PAVEMENT REMOVAL
0010	5TH Z2	-	-	16	-	-	99	85	-	1	-	71	-
0010	B-68-83 LT	-	-	-	-	-	-	392	-	-	1	108	-
0010	B-68-83 RT	-	-	-	-	-	15	329	-	-	-	-	-
0010	B-68-104 LT	-	-	-	-	-	-	391	-	-	-	-	-
0010	B-68-104 RT	-	-	-	-	-	-	333	-	-	-	-	-
0010	B-68-121 & 5' CONC	-	61	-	-	-	-	-	-	-	-	-	-
0010	APPROACH SLABS	-	514	-	-	-	-	-	-	-	-	-	-
0010	CTH X/MAIN STREET ON-RAMP	-	-	-	-	-	-	-	-	-	-	-	-
0010	PROJECTWIDE	-	-	-	-	-	-	-	-	-	-	-	-
0010	TOTAL 0010	2	25,375	16	2,850	23,310	114	1,530	35	1	1	179	-

	205.0100 COMMON EXCAVATION			SALVAGED/UNUSABLE PAVEMENT MATERIAL (4)	AVAILABLE MATERIAL (5)	REDUCED EBS IN FILL (9)		EXPANDED EBS BACKFILL (11)		UNEXPANDED FILL	EXPANDED FILL (13)		MASS ORDINATE +/- (14)	
	CUT (2)	EBS EXCAVATION (3)				FACTOR 0.80	FACTOR 1.30		FACTOR 1.25					
LOCATION	1786	70		90	1696	-	-	-	-	469	586	1110	1110	-
SOUTH CROSSOVER INSTALL	-	-	-	-	-	-	-	-	-	-	-	-	-	-
SOUTH CROSSOVER REMOVAL	641	65	21	620	-	-	-	-	847	1059	-	-	-439	-
NORTH CROSSOVER INSTALL	-	-	3458	-	-	-	-	-	-	-	-	-	-	440
NORTH CROSSOVER REMOVAL	265	65	-	265	-	-	-	-	-	-	-	-	265	-
WIDENING INSTALL	205	-	205	-	-	-	-	-	-	-	-	-	265	-
WIDENING REMOVAL	1456	-	1456	-	-	-	-	-	-	-	-	-	-	-
LEFT SHOULDER	3519	-	3519	-	-	-	-	-	-	-	-	-	-	-
RIGHT SHOULDER	431	-	431	-	-	-	-	-	-	-	-	-	-	-
RAMP SHOULDERS	-	-	-	-	-	-	-	-	-	-	-	-	-	-
MEDIAN CROSSOVERS & SIDEROADS	-	-	-	-	-	-	-	-	-	-	-	-	-	-
GORES	71	-	71	-	-	-	-	-	-	-	-	-	-	-
GRAND TOTAL	11,840	200	9,251	2,581	0	0	0	0	1,316	1,645	936	1,375	440	440
TOTAL COMMON EXC	12,040													

Addendum No. 01
ID 1510-02-60
Revised Sheet 108
July 30, 2026

NOTES:

- (1) COMMON EXCAVATION IS THE SUM OF THE CUT AND EBS EXCAVATION COLUMNS. ITEM NUMBER 205-0100
- (2) SALVAGED/UNUSABLE PAVEMENT MATERIAL IS INCLUDED IN CUT.
- (3) EBS EXCAVATION TO BE BACKFILLED WITH SELECT BORROW MATERIAL. NOTE: THIS IS DESIGNER'S CHOICE. CAN BE BACKFILLED WITH BORROW, OR CUT AS WELL.
- (4) SALVAGED/UNUSABLE PAVEMENT MATERIAL
- 5) AVAILABLE MATERIAL = CUT - SALVAGED/UNUSABLE PAVEMENT MATERIAL
- (9) REDUCED EBS IN FILL - EXCAVATED EBS MATERIAL IS USABLE IN FILLS OUTSIDE THE 1:1 SLOPE. EBS IN FILL REDUCTION FACTOR = 0.80
- (11) EXPANDED EBS BACKFILL - THIS IS TO BE FILLED WITH SELECT BORROW MATERIAL. EBS BACKFILL FACTOR = 1.30. ITEM NUMBER 208.1100
- (13) EXPANDED FILL FACTOR = 1.25
- DEPENDENT ON SELECTIONS:
- OR EXPANDED FILL = (UNEXPANDED FILL - EXPANDED ROCK - REDUCED MARSH - REDUCED EBS) * FILL FACTOR
- OR EXPANDED FILL = (UNEXPANDED FILL - EXPANDED ROCK - REDUCED MARSH) * FILL FACTOR
- OR EXPANDED FILL = (UNEXPANDED FILL - EXPANDED ROCK) * FILL FACTOR
- (14) THE MASS ORDINATE + OR - QTY CALCULATED FOR THE DIVISION. PLUS QUANTITY INDICATES AN EXCESS OF MATERIAL WITHIN THE DIVISION. MINUS INDICATES A SHORTAGE OF MATERIAL WITHIN THE DIVISION.

PROJECT NO: 1510-02-60

HWY: USH 10

COUNTY: WAUPACA

MISCELLANEOUS QUANTITIES

SHEET: REV 108

E

FILE NAME : N:\PDS\1_1030200_mtl.pxd

PLOT DATE : JULY 27, 2026

PLOT BY :

PLOT NAME :

PLOT SCALE : 1:1

Addendum No. 01
ID 1510-02-60
Revised Sheet 303
July 30, 2026

STATION	DISTANCE	AREA (SF)		EARTHWORK NORTH CROSSOVER					CUMULATIVE VOL. (CY)						
		CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	EBS	INCREMENTAL VOL. (CY) (UNADJUSTED)			CUT	EXPANDED FILL		EXPANDED EBS BACKFILL 1.30	REDUCED EBS IN FILL 0.80	MASS ORDNATE	
						CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL		EBS	NOTE 1				1.25
6+00.00	0.00	20.88	0.75	0.08	0.00	NOTE 1	NOTE 2	NOTE 3		NOTE 1					
6+50.00	50.00	23.71	0.75	0.15	0.00	41	1	0	0	0	0	0	0	0	0
7+00.00	50.00	21.63	0.75	0.46	0.00	42	1	1	0	83	1	0	0	0	40
7+50.00	50.00	21.50	0.75	0.05	0.00	40	1	0	0	123	1	0	0	0	80
8+00.00	50.00	17.55	0.75	0.17	0.00	36	1	0	0	159	0	0	0	0	119
8+50.00	50.00	14.61	0.75	1.29	0.00	30	1	1	0	189	3	0	0	0	154
9+00.00	50.00	14.40	0.75	3.66	0.00	27	1	5	0	216	9	0	0	0	182
9+50.00	50.00	17.76	0.75	3.03	0.00	30	1	3.03	0	246	16	0	0	0	201
10+00.00	50.00	29.05	0.75	0.06	0.00	43	1	6	0	289	20	0	0	0	223
10+50.00	50.00	37.19	0.75	0.00	0.00	61	1	0	0	350	20	0	0	0	261
11+00.00	50.00	15.37	0.75	2.93	0.00	49	1	3	0	399	24	0	0	0	321
11+50.00	50.00	2.93	0.00	16.71	0.00	17	1	18	0	416	46	0	0	0	365
12+00.00	50.00	3.94	0.00	25.91	0.00	6	0	39	0	422	95	0	0	0	359
12+50.00	50.00	2.26	0.00	28.90	0.00	6	0	51	0	428	159	0	0	0	316
13+00.00	50.00	1.47	0.00	36.42	0.00	3	0	60	0	431	234	0	0	0	258
13+50.00	50.00	2.56	0.00	44.52	0.00	4	0	75	0	435	338	0	0	0	186
14+00.00	50.00	4.20	0.00	48.31	0.00	6	0	86	0	441	435	0	0	0	97
14+50.00	50.00	6.64	0.00	50.07	0.00	10	0	91	0	451	549	0	0	0	-5
15+00.00	50.00	1.99	0.00	49.03	0.00	8	0	92	0	459	664	0	0	0	-109
15+50.00	50.00	3.59	0.00	44.89	0.00	5	0	87	0	464	773	0	0	0	-216
16+00.00	50.00	5.72	0.00	34.30	0.00	9	0	73	0	473	864	0	0	0	-320
16+50.00	50.00	4.18	0.00	27.02	0.00	9	0	57	0	482	935	0	0	0	-402
17+00.00	50.00	3.84	0.75	21.17	0.00	7	1	45	0	489	991	0	0	0	-464
17+50.00	50.00	4.59	0.75	13.43	0.00	8	1	32	0	497	1031	0	0	0	-514
18+00.00	50.00	12.54	0.75	2.87	0.00	16	1	15	0	513	1050	0	0	0	-547
18+50.00	50.00	11.18	0.75	0.90	0.00	22	1	3	0	535	1054	0	0	0	-551
19+00.00	50.00	13.00	0.75	0.43	0.00	22	1	1	0	557	1055	0	0	0	-534
19+50.00	50.00	14.29	0.75	0.16	0.00	25	1	1	0	582	1056	0	0	0	-514
20+00.00	50.00	5.72	0.75	1.25	0.00	19	1	1	0	601	1058	0	0	0	-491
20+50.00	50.00	5.47	0.75	0.03	0.00	10	1	1	0	611	1059	0	0	0	-475
21+00.00	50.00	7.65	0.75	0.00	0.00	12	1	0	0	623	1059	0	0	0	-467
21+50.00	50.00	11.65	0.75	0.00	0.00	18	1	0	0	641	1059	0	0	0	-456

NOTES:	
1 - CUT	CUT INCLUDES SALVAGED/UNUSABLE PAVEMENT MATERIAL
2 - SALVAGED/UNUSABLE PAVEMENT MATERIAL	THIS DOES NOT SHOW UP IN CROSS SECTIONS
3 - FILL	DOES NOT INCLUDE UNUSABLE PAVEMENT EXC VOLUME
4 - EXPANDED MARSH BACKFILL	WILL BE BACKFILLED WITH GRANULAR BACKFILL (OR CUT, OR BORROW)
5 - EXPANDED EBS	WILL BE BACKFILLED WITH GRANULAR BACKFILL (OR CUT, OR BORROW)
6 - REDUCED MARSH IN FILL	REDUCED MARSH EXCAVATION THAT CAN BE USED IN FILL
7 - REDUCED EBS IN FILL	REDUCED EBS EXCAVATION THAT CAN BE USED IN FILL
8 - MASS ORDNATE	IF MARSH OR EBS TO BE BACKFILLED WITH COMMON OR BORROW: [(CUT - SALVAGED PAVT - EXPANDED MARSH EXC - EXPANDED EBS) - ((FILL - REDUCED MARSH IN FILL - REDUCED EBS IN FILL - EXPANDED ROCK) * FILL FACTOR)]
8 - MASS ORDNATE	IF MARSH AND EBS TO BE BACKFILLED WITH GRANULAR: [(CUT - SALVAGED PAVT - ((FILL - REDUCED MARSH IN FILL - REDUCED EBS IN FILL - EXPANDED ROCK) * FILL FACTOR)]
8 - MASS ORDNATE	IF MARSH AND EBS TO BE BACKFILLED WITH COMMON OR BORROW: [(CUT - SALVAGED PAVT - EXPANDED MARSH EXC - EXPANDED EBS) - ((FILL - EXPANDED ROCK) * FILL FACTOR)]
8 - MASS ORDNATE	IF MARSH AND EBS TO BE BACKFILLED WITH GRANULAR: [(CUT - SALVAGED PAVT - ((FILL - EXPANDED ROCK) * FILL FACTOR)]

Addendum No. 01
ID 1510-02-60
Revised Sheet 304
July 30, 2026

EARTHWORK SOUTH CROSSOVER

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)				CUMULATIVE VOL (CY)						
			CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	EBS	CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	EBS	CUT	EXPANDED FILL 1.25	EXPANDED EBS BACKFILL 1.00	REDUCED EBS IN FILL 1.00	MASS ORDNATE
766+00.00	76600.00	0.00	0.00	0.00	0.00	0.00	0	0	0	0	0	0	0	0	0
766+50.00	76650.00	50	0.00	0.00	0.00	0.00	0	0	0	0	0	0	0	0	0
767+00.00	76700.00	50	16.14	0.75	0.00	0.00	15	1	0	0	15	0	0	14	14
767+50.00	76750.00	50	14.04	0.75	0.18	0.00	28	0.75	0	0	41	0	0	41	43
768+00.00	76800.00	50	14.02	0.75	0.12	0.00	26	1	0	0	69	0	0	66	66
768+50.00	76850.00	50	35.85	1.50	0.00	0.00	46	2	0	0	115	0	0	110	110
769+00.00	76900.00	50	42.87	1.50	0.00	0.00	73	3	0	0	188	0	0	180	180
769+50.00	76950.00	50	39.88	1.50	0.00	0.00	77	3	0	0	265	0	0	254	254
770+00.00	77000.00	50	38.09	1.50	0.11	0.00	72	3	0	0	337	0	0	323	323
770+50.00	77050.00	50	34.96	1.50	1.67	0.00	68	3	2	0	405	3	0	386	386
771+00.00	77100.00	50	35.29	1.50	2.84	0.00	65	3	4	0	470	8	0	443	443
771+50.00	77150.00	50	27.90	1.50	4.95	0.00	59	3	7	0	529	16	0	490	490
772+00.00	77200.00	50	26.01	1.50	20.82	0.00	50	3	24	0	579	46	0	507	507
772+50.00	77250.00	50	28.03	1.50	17.10	0.00	50	3	35	0	629	90	0	510	510
773+00.00	77300.00	50	33.48	1.50	19.55	0.00	57	3	34	0	686	133	0	522	522
773+50.00	77350.00	50	32.36	1.50	18.60	0.00	61	3	35	0	747	176	0	536	536
774+00.00	77400.00	50	33.19	1.50	13.34	0.00	61	3	30	0	808	214	0	556	556
774+50.00	77450.00	50	29.63	1.50	17.62	0.00	58	3	29	0	866	250	0	575	575
775+00.00	77500.00	50	28.91	1.50	15.19	0.00	54	3	30	0	920	288	0	589	589
775+50.00	77550.00	50	28.24	1.50	15.40	0.00	53	3	28	0	973	323	0	604	604
776+00.00	77600.00	50	29.66	1.50	12.49	0.00	54	3	26	0	1027	355	0	622	622
776+50.00	77650.00	50	31.31	1.50	9.19	0.00	56	3	20	0	1083	380	0	650	650
777+00.00	77700.00	50	32.34	1.50	6.02	0.00	59	3	14	0	1142	398	0	689	689
777+50.00	77750.00	50	31.54	1.50	11.10	0.00	59	3	16	0	1201	418	0	725	725
778+00.00	77800.00	50	33.81	1.50	12.73	0.00	61	3	22	0	1262	445	0	755	755
778+50.00	77850.00	50	31.57	1.50	14.55	0.00	61	3	25	0	1323	476	0	782	782
779+00.00	77900.00	50	30.81	1.50	10.14	0.00	58	3	23	0	1381	505	0	808	808
779+50.00	77950.00	50	27.82	1.50	9.31	0.00	54	3	18	0	1435	528	0	837	837
780+00.00	78000.00	50	26.18	1.50	8.92	0.00	50	3	17	0	1485	549	0	862	862
780+50.00	78050.00	50	27.67	1.50	5.33	0.00	50	3	13	0	1535	565	0	893	893
781+00.00	78100.00	50	29.57	1.50	2.30	0.00	53	3	7	0	1588	574	0	934	934
781+50.00	78150.00	50	28.80	1.50	2.17	0.00	54	3	4	0	1642	579	0	980	980
782+00.00	78200.00	50	28.90	1.50	1.77	0.00	53	3	4	0	1695	584	0	1025	1025
782+50.00	78250.00	50	34.51	1.50	0.17	0.00	59	3	2	0	1754	586	0	1079	1079
783+00.00	78300.00	50	0.00	0.00	0.00	0.00	32	1	0	0	1786	586	0	1110	1110

NOTES:

- 1 - CUT
- 2 - SALVAGED/UNUSABLE PAVEMENT MATERIAL
THIS DOES NOT SHOW UP IN CROSS SECTIONS
DOES NOT INCLUDE UNUSABLE PAVEMENT EXC VOLUME
- 3 - FILL
- 4 - EXPANDED MARSH BACKFILL
WILL BE BACKFILLED WITH GRANULAR BACKFILL (OR CUT, OR BORROW)
- 5 - EXPANDED EBS
WILL BE BACKFILLED WITH GRANULAR BACKFILL (OR CUT, OR BORROW)
- 6 - REDUCED MARSH IN FILL
REDUCED MARSH EXCAVATION THAT CAN BE USED IN FILL
- 7 - REDUCED EBS IN FILL
IF MARSH OR EBS TO BE BACKFILLED WITH COMMON OR BORROW: [(CUT - SALVAGED PAYT - EXPANDED MARSH EXC - EXPANDED EBS) - ((FILL - REDUCED MARSH IN FILL - REDUCED EBS IN FILL - EXPANDED ROCK) * FILL FACTOR)]
- 8 - MASS ORDNATE
- 8 - MASS ORDNATE
IF MARSH AND EBS TO BE BACKFILLED WITH COMMON OR BORROW: [(CUT - SALVAGED PAYT - EXPANDED MARSH EXC - EXPANDED EBS) - ((FILL - EXPANDED ROCK) * FILL FACTOR)]
- 8 - MASS ORDNATE
- 8 - MASS ORDNATE
IF MARSH AND EBS TO BE BACKFILLED WITH GRANULAR: [(CUT - SALVAGED PAYT - ((FILL - EXPANDED ROCK) * FILL FACTOR)]

PROJECT NO: 1510-02-60

HWY: USH 10

COUNTY: WAUPACA

EARTHWORK TABLES

SHEET REV 304

E

FILE NAME :

PLOT DATE :

PLOT BY :

PLOT NAME :

ORG DATE :

ORIGINATOR - DIST _

PLOT SCALE : 1:1



Proposal Schedule of Items

Page 1 of 12

Proposal ID: 20260811018 Project(s): 1510-02-60

Federal ID(s): WISC 2026435

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	203.0100 Removing Small Pipe Culverts	2.000 EACH	_____.	_____.
0004	203.0220 Removing Structure (structure) 01. B-68-104	1.000 EACH	_____.	_____.
0006	204.0100 Removing Concrete Pavement	25,375.000 SY	_____.	_____.
0008	204.0110 Removing Asphaltic Surface	16.000 SY	_____.	_____.
0010	204.0115 Removing Asphaltic Surface Butt Joints	2,850.000 SY	_____.	_____.
0012	204.0120 Removing Asphaltic Surface Milling	23,310.000 SY	_____.	_____.
0014	204.0150 Removing Curb & Gutter	114.000 LF	_____.	_____.
0016	204.0165 Removing Guardrail	1,530.000 LF	_____.	_____.
0018	204.0180 Removing Delineators and Markers	35.000 EACH	_____.	_____.
0020	204.0190 Removing Surface Drains	1.000 EACH	_____.	_____.
0022	204.0220 Removing Inlets	1.000 EACH	_____.	_____.
0024	204.0245 Removing Storm Sewer (size) 01. 12-Inch	179.000 LF	_____.	_____.
0026	204.9090.S Removing (item description) 01. Pipe Handrail	16.000 LF	_____.	_____.
0028	205.0100 Excavation Common	12,040.000 CY	_____.	_____.
0030	206.1001 Excavation for Structures Bridges (structure) 01. B-68-104	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Page 2 of 12

Proposal ID: 20260811018 Project(s): 1510-02-60

Federal ID(s): WISC 2026435

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0032	208.0100 Borrow	440.000 CY	_____.	_____.
0034	210.1500 Backfill Structure Type A	212.000 TON	_____.	_____.
0036	211.0400 Prepare Foundation for Asphaltic Shoulders	4,140.000 STA	_____.	_____.
0038	213.0100 Finishing Roadway (project) 01. 1510-02-60	1.000 EACH	_____.	_____.
0040	305.0110 Base Aggregate Dense 3/4-Inch	10,710.000 TON	_____.	_____.
0042	305.0120 Base Aggregate Dense 1 1/4-Inch	8,530.000 TON	_____.	_____.
0044	415.0070 Concrete Pavement 7-Inch	61.000 SY	_____.	_____.
0046	415.0120 Concrete Pavement 12-Inch	40.000 SY	_____.	_____.
0048	415.0210 Concrete Pavement Gaps	5.000 EACH	_____.	_____.
0050	415.0410 Concrete Pavement Approach Slab	514.000 SY	_____.	_____.
0052	416.0610 Drilled Tie Bars	9,740.000 EACH	_____.	_____.
0054	416.0620 Drilled Dowel Bars	7,640.000 EACH	_____.	_____.
0056	416.1710 Concrete Pavement Repair	2,700.000 SY	_____.	_____.
0058	416.1720 Concrete Pavement Replacement	7,042.000 SY	_____.	_____.
0060	420.1000 Continuous Diamond Grinding Concrete Pavement	14,830.000 SY	_____.	_____.

