

SEPTEMBER 2026

ORDER OF SHEETS

Section No.	1	Title
Section No.	2	Typical Sections and Details
Section No.	3	Estimate of Quantities
Section No.	3	Miscellaneous Quantities
Section No.	4	Right of Way Plat
Section No.	5	Plan and Profile
Section No.	6	Standard Detail Drawings
Section No.	7	Sign Plates
Section No.	8	Structure Plans
Section No.	9	Computer Earthwork Data
Section No.	9	Cross Sections

TOTAL SHEETS = 50



DESIGN DESIGNATION


A.A.D.T.	2026	=	<100
A.A.D.T.	2046	=	<100
D.H.V.		=	28
D.D.		=	60/40
T.		=	4%
DESIGN SPEED		=	30 MPH
ESALS		=	7,300

CONVENTIONAL SYMBOLS

PLAN	
CORPORATE LIMITS	
PROPERTY LINE	
LOT LINE	
LIMITED HIGHWAY EASEMENT	
EXISTING RIGHT OF WAY	
PROPOSED OR NEW R/W LINE	
SLOPE INTERCEPT	
REFERENCE LINE	
EXISTING CULVERT	
PROPOSED CULVERT (Box or Pipe)	
COMBUSTIBLE FLUIDS	
MARSH AREA	
WOODED OR SHRUB AREA	

PROFILE	
GRADE LINE	
ORIGINAL GROUND	
MARSH OR ROCK PROFILE (To be noted as such)	
SPECIAL DITCH	
GRADE ELEVATION	
CULVERT (Profile View)	
UTILITIES	
ELECTRIC	
FIBER OPTIC	
GAS	
SANITARY SEWER	
STORM SEWER	
TELEPHONE	
WATER	
UTILITY PEDESTAL	
POWER POLE	
TELEPHONE POLE	

BEGIN PROJECT
STA 0+55.28
X: 517,455.491
Y: 289,337.130



LAYOUT
SCALE 0 0.5 MI

TOTAL NET LENGTH OF CENTERLINE = 0.026 MI

HORIZONTAL POSITIONS SHOWN ON THIS PLAN ARE WISCONSIN COORDINATE REFERENCE SYSTEM (WISCRS), SAUK COUNTY, NAD83 (2011), IN U.S. SURVEY FEET. POSITIONS SHOWN ARE GRID COORDINATES, GRID BEARINGS, AND GRID DISTANCES. GRID DISTANCES ARE THE SAME AS GROUND DISTANCES.

ELEVATIONS ARE REFERENCED TO NAVD 88 (2012). GPS DERIVED ELEVATIONS ARE BASED ON GEOID 12A.

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

PLAN OF PROPOSED IMPROVEMENT

T WOODLAND, DAVID DRIVE

BR PLUM CREEK, BRIDGE B-56-0256

LOC STR
SAUK COUNTY

STATE PROJECT NUMBER

5738-00-74

STATE PROJECT

5738-00-74

FEDERAL PROJECT

PROJECT

WISC 2026414

CONTRACT

1

ACCEPTED FOR

TOWN OF WOODLAND

Date: 3-12-26
Elmer J. Wolske
Chairman
(Signature and Title of Official)

ORIGINAL PLANS PREPARED BY

TEAM
ENGINEERING

WISCONSIN
PROFESSIONAL ENGINEER
JEREMY F. KRACHEY
E-37258
WAUZEKA
WIS

DATE: _____
(Professional Engineer Signature)

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

PREPARED BY

Surveyor	TEAM ENGINEERING INC.
Designer	TEAM ENGINEERING INC.
Project Manager	DELLA KOENIG, P.E.
Regional Examiner	SW REGION
Regional Supervisor	KYLE HEMP, P.E.

APPROVED FOR THE DEPARTMENT

DATE: _____
Della Koenig, P.E.
Date: 2026.04.23
16:45:23-05'00'

E

LIST OF STANDARD ABBREVIATIONS

ABUT.	Abutment	JT	Joint	SEC	Section
AC	Acce	JCT	Junction	SHLDR	Shoulder
AGG.	Aggregate	LHF	Left-Hand Forward	SHR	Shrinkage
AH	Ahead	L	Length of Curve	SW	Sidewalk
<	Angle	LIN FT OR LF	Linear Foot	S	South
ASPH	Asphaltic	LC	Long Chord of Curve	SQ	Square
AVG.	Average	MH	Manhole	SF OR SQ FT	Square Feet
A.D.T.	Average Daily Traffic	MB	Mailbox	SY OR SQ YD	Square Yard
BAD	Base Aggregate Dense	ML OR M/L	Match Line	STD	Standard
BK.	Back	N	North	SDD	Standard Detail Drawings
BF	Back Fence	Y	North Grid Coordinate	STH	State Trunk Highways
B.M	Bench Mark	OAL	Overall Length	STA	Station
BR.	Bridge	OD	Outside Diameter	SS	Storm Sewer
C/L	Center Line	PLE	Permanent Limited Easement	SG	Subgrade
CC	Center to Center	PT	Point	SE	Superelevation
CTH	County Truck Highway	PC	Point of Curvature	SL OR S/L	Survey Line
CR.	Creek	PI	Point of Intersection	SV	Septic Vent
CY OR CU YD	Cubic Yard	PRC	Point of Reverse Curvature	T	Tangent
CP	Culvert Pipe	PT	Point of Tangency	TEL	Telephone
C & G	Curb and Gutter	POC	Point on Curve	TEMP	Temporary
D	Degree of Curve	POT	Point on Tangent	TI	Temporary Interest
DHV	Design Hour Volume	PVC	Polyvinyl Chloride	TLE	Temporary Limited Easement
DIA	Diameter	PCC	Portland Cement Concrete	t	Ton
E	East	LB	Pound	T OR TN	Town
X	East Grid Coordinate	PSI	Pounds Per Square Inch	TRANS	Transition
ELEC	Electric	PE	Private Entrance	TL OR T/L	Transit Line
EL OR ELEV	Elevation	R	Radius	T	Trucks (percent of)
ESALS	Equivalent Single Axle Loads	RR	Railroad	TYP	Typical
EBS	Excavation Below Subgrade	RL OR R/L	Reference Line	UNCL	Unclassified
FF	Face to Face	RP	Reference Point	UG	Underground Cable
FE	Field Entrance	RCCP	Reinforced Concrete Culvert Pipe	USH	United States Highway
F	Fill	REQD	Required	VAR	Variable
FG	Finished Grade	RES	Residence or Residential	V	Velocity or Design Speed
FL OR F/L	Flow Line	RW	Retaining Wall	VERT	Vertical
FT	Foot	RT	Right	VC	Vertical Curve
FTG	Footing	RHF	Right-Hand Forward	VOL	Volume
GN	Grid North	R/W	Right-of-Way	WM	Water Main
HT	Height	R	River	WV	Water Valve
CWT	Hundredweight	RD	Road	W	West
HYD	Hydrant	RDWY	Roadway	WB	Westbound
INL	Inlet	SALV	Salvaged	YD	Yard
ID	Inside Diameter	SAN S	Sanitary Sewer		
INV	Invert				
IP	Iron Pipe or Pin				
IRS	Iron Rod Set				

GENERAL NOTES

THE LOCATIONS OF EXISTING AND PROPOSED UTILITY INSTALLATIONS AS SHOWN ON THE PLAN ARE APPROXIMATE. THERE MAY BE OTHER UTILITY INSTALLATIONS WITHIN THE PROJECT AREA THAT ARE NOT SHOWN.

4-INCH ASPHALTIC SURFACE SHALL BE PLACED WITH A 2 1/4-INCH LOWER LAYER AND A 1 3/4-INCH UPPER LAYER.

UTILITIES

LAVALLE TELEPHONE COOPERATIVE

COMLN
JOSH LIEN
S1421 STATE HWY 33, P.O. BOX 28
LAVALLE, WI 53941
PHONE: 608-434-2796
EMAIL: joshl@rgtc.coop
EMAIL: johnb@rgtc.coop

BRIGHTSPEED OF WESTERN WISCONSIN, LLC

COMLN
THOMAS DINEEN
1905 WARD AVENUE
LA CROSSE, WI 54601
PHONE: 319-423-5242
EMAIL: thomas.dineen@brightspeed.com
EMAIL: relocations@brightspeed.com
EMAIL: dshea@congruex.com

VERNON ELECTRIC COOPERATIVE

ELCTY
COLE CARY
110 SAUGSTAD RD.
WESTBY, WI 54667
PHONE: 608-634-7472
EMAIL: ccary@vernonelectric.org

DESIGNER

TEAM ENGINEERING, INC.
210 GUARD STREET
WAUZEKA, WI 53826
ATTN: JEREMY KRACHEY, P.E.
PH: (608) 875-5075
jkrachey@teamenginc.com

DNR CONTACT

DEPARTMENT OF NATURAL RESOURCES
101 S. WEBSTER STREET
MADISON, WI 53703
ATTN: ANDY BARTA
ENVIRONMENTAL ANALYSIS & REVIEW SPECIALIST
PH: (608) 235-2955
EMAIL: andrew.barta@wisconsin.gov

WISDOT CONTACT

ATTENTION: DELLA KOENIG, P.E.
LOCAL PROGRAM PROJECT MANAGER
WISDOT - SW REGION
2101 WRIGHT STREET
MADISON, WI 53704
WORK: (608) 246-7963
EMAIL: della.koenig@dot.wi.gov


RUNOFF COEFFICIENT TABLE

LAND USE:	HYDROLOGIC SOIL GROUP											
	A			B			C			D		
	SLOPE RANGE (PERCENT)			SLOPE RANGE (PERCENT)			SLOPE RANGE (PERCENT)			SLOPE RANGE (PERCENT)		
ROW CROPS:	0-2	2-6	6 & OVER	0-2	2-6	6 & OVER	0-2	2-6	6 & OVER	0-2	2-6	6 & OVER
	.08	.16	.22	.12	.20	.27	.15	.24	.33	.19	.28	.38
	.22	.30	.38	.26	.34	.44	.30	.37	.50	.34	.41	.56
MEDIAN STRIPTURF:	.19	.20	.24	.19	.22	.26	.20	.23	.30	.20	.25	.30
	.24	.26	.30	.25	.28	.33	.26	.30	.37	.27	.32	.40
SIDE SLOPETURF:			.25			.27			.28			.30
			.32			.34			.36			.38
PAVEMENT:												
ASPHALT:	.70 - .95											
CONCRETE:	.80 - .95											
BRICK:	.70 - .80											
DRIVES, WALKS:	.75 - .85											
ROOFS:	.75 - .95											
GRAVEL ROADS, SHOULDERS:	.40 - .60											


TOTAL PROJECT AREA = 0.76 ACRES
TOTAL AREA EXPECTED TO BE DISTURBED BY CONSTRUCTION ACTIVITIES = 0.48 ACRES




Dial  or (800)242-8511
www.DiggersHotline.com

**EXISTING TYPICAL SECTION - DAVID DRIVE**


STA 0+55.28 - 1+05.28
STA 1+45.28 - 1+95.28

**FINISHED TYPICAL SECTION - DAVID DRIVE**

STA 0+55.28 - 0+95.28
STA 1+45.28 - 1+95.28

**FINISHED TYPICAL SECTION - TEMP ROAD**

STA 10+00 - 12+97.07



STATION & OFFSET TABLE						
POINT	POINT DESCRIPTION	STATION	OFFSET	Y COORDS	X COORDS	ELEVATION
1	CP 1	2+34.15	17.09 LT	289363.040	517633.298	954.28
2	CP 2	-0+12.66	25.92 RT	289307.884	517388.896	955.06
3	CP 3	0+85.39	6.12 RT	289332.503	517485.865	955.28



Estimate Of Quantities By Plan Sets

5738-00-74					
Line	Item	Item Description	Unit	Total	Qty
0002	201.0105	Clearing	STA	3.000	3.000
0004	201.0205	Grubbing	STA	3.000	3.000
0006	203.0260	Removing Structure Over Waterway Minimal Debris (structure) 01. P-56-0933	EACH	1.000	1.000
0010	205.0100	Excavation Common	CY	414.000	414.000
0012	206.1001	Excavation for Structures Bridges (structure) 01. B-56-0256	EACH	1.000	1.000
0016	208.0100	Borrow	CY	118.000	118.000
0018	210.1500	Backfill Structure Type A	TON	446.000	446.000
0020	213.0100	Finishing Roadway (project) 01. 5738-00-74	EACH	1.000	1.000
0024	305.0110	Base Aggregate Dense 3/4-Inch	TON	30.000	30.000
0026	305.0120	Base Aggregate Dense 1 1/4-Inch	TON	520.000	520.000
0028	312.0110	Select Crushed Material	TON	150.000	150.000
0030	455.0605	Tack Coat	GAL	20.000	20.000
0032	465.0105	Asphaltic Surface	TON	70.000	70.000
0034	502.0100	Concrete Masonry Bridges	CY	148.000	148.000
0036	502.3200	Protective Surface Treatment	SY	188.000	188.000
0038	505.0400	Bar Steel Reinforcement HS Structures	LB	4,220.000	4,220.000
0040	505.0600	Bar Steel Reinforcement HS Coated Structures	LB	19,310.000	19,310.000
0042	513.4061	Railing Tubular Type M	LF	90.000	90.000
0044	516.0500	Rubberized Membrane Waterproofing	SY	10.000	10.000
0046	526.0101	Temporary Structure (station) 01. STA 11+48	EACH	1.000	1.000
0048	550.0020	Pre-Boring Rock or Consolidated Materials	LF	175.000	175.000
0050	550.1100	Piling Steel HP 10-Inch x 42 Lb	LF	245.000	245.000
0052	606.0300	Riprap Heavy	CY	70.000	70.000
0054	612.0406	Pipe Underdrain Wrapped 6-Inch	LF	140.000	140.000
0056	618.0100	Maintenance and Repair of Haul Roads (project) 01. 5738-00-74	EACH	1.000	1.000
0060	619.1000	Mobilization	EACH	0.500	0.500
0062	624.0100	Water	MGAL	10.000	10.000
0064	625.0500	Salvaged Topsoil	SY	400.000	400.000
0066	627.0200	Mulching	SY	1,250.000	1,250.000
0068	628.1504	Silt Fence	LF	700.000	700.000
0070	628.1520	Silt Fence Maintenance	LF	1,400.000	1,400.000
0072	628.1905	Mobilizations Erosion Control	EACH	4.000	4.000
0074	628.1910	Mobilizations Emergency Erosion Control	EACH	4.000	4.000
0076	628.2008	Erosion Mat Urban Class I Type B	SY	420.000	420.000
0078	628.6005	Turbidity Barriers	SY	280.000	280.000
0080	628.7504	Temporary Ditch Checks	LF	60.000	60.000
0082	629.0210	Fertilizer Type B	CWT	2.000	2.000
0084	630.0120	Seeding Mixture No. 20	LB	60.000	60.000
0086	630.0200	Seeding Temporary	LB	50.000	50.000
0088	630.0300	Seeding Borrow Pit	LB	20.000	20.000
0090	630.0500	Seed Water	MGAL	30.000	30.000
0092	633.1100	Delineators Temporary	EACH	22.000	22.000
0094	634.0614	Posts Wood 4x6-Inch x 14-FT	EACH	4.000	4.000
0096	637.2230	Signs Type II Reflective F	SF	12.000	12.000
0098	638.2602	Removing Signs Type II	EACH	4.000	4.000
0100	638.3000	Removing Small Sign Supports	EACH	4.000	4.000
0102	642.5001	Field Office Type B	EACH	0.500	0.500
0104	643.0300	Traffic Control Drums	DAY	1,690.000	1,690.000
0106	643.0420	Traffic Control Barricades Type III	DAY	845.000	845.000

Estimate Of Quantities By Plan Sets

5738-00-74					
Line	Item	Item Description	Unit	Total	Qty
0108	643.0705	Traffic Control Warning Lights Type A	DAY	1,690.000	1,690.000
0110	643.0715	Traffic Control Warning Lights Type C	DAY	780.000	780.000
0112	643.0900	Traffic Control Signs	DAY	1,820.000	1,820.000
0114	643.5000	Traffic Control	EACH	0.500	0.500
0116	645.0111	Geotextile Type DF Schedule A	SY	100.000	100.000
0118	645.0120	Geotextile Type HR	SY	170.000	170.000
0120	645.0140	Geotextile Type SAS	SY	740.000	740.000
0122	645.0220	Geogrid Type SR	SY	300.000	300.000
0124	650.4500	Construction Staking Subgrade	LF	395.000	395.000
0126	650.5000	Construction Staking Base	LF	395.000	395.000
0128	650.6501	Construction Staking Structure Layout (structure) 01. B-56-0256	EACH	1.000	1.000
0132	650.9911	Construction Staking Supplemental Control (project) 01. 5738-00-74	EACH	1.000	1.000
0136	650.9920	Construction Staking Slope Stakes	LF	395.000	395.000
0138	690.0150	Sawing Asphalt	LF	50.000	50.000
0140	715.0502	Incentive Strength Concrete Structures	DOL	888.000	888.000
0144	ASP.1T0A	On-the-Job Training Apprentice at \$5.00/HR	HRS	1,200.000	1,200.000
0146	ASP.1T0G	On-the-Job Training Graduate at \$5.00/HR	HRS	600.000	600.000

DIVISION	FROM/TO STATION	LOCATION	205.0100 EXCAVATION COMMON (1)	AVAILABLE MATERIAL (5)	UNEXPANDED FILL	EXPANDED FILL (13)	MASS ORDINATE +/- (14)	WASTE	208.0100 BORROW	COMMENT
			CUT (2)			FACTOR 1.25				
DIVISION 1										
TEMP ROAD WEST	10+75.00/11+25.00		0	0	48	60	-60			
TEMP ROAD EAST	11+75.00/12+25.00		0	0	46	58	-58			
DIVISION 1 SUBTOTAL			0	0	94	118	-118	0	118	
DIVISION 2										
DAVID DRIVE WEST	0+55.28/1+04.03		69	69	48	60	9			
DAVID DRIVE EAST	1+47.26/1+95.28		52	52	21	26	26			
DIVISION 2 SUBTOTAL			121	121	69	86	35	35	0	
DIVISION 3										
REMOVAL OF TEMP ROAD	10+75.00/12+25.00		293	0	0	0	293			
GRAND TOTAL			414	121	163	204	210	35	118	

NOTES:

(1) COMMON EXCAVATION IS THE SUM OF THE CUT AND EBS EXCAVATION COLUMNS. ITEM NUMBER 205.0100

(2) SALVAGED/UNSUABLE PAVEMENT MATERIAL IS INCLUDED IN CUT.

(5) AVAILABLE MATERIAL = CUT - SALVAGED/UNUSUABLE PAVEMENT MATERIAL

(13) EXPANDED FILL FACTOR = 1.25

DEPENDING ON SELECTIONS:

EXPANDED FILL = UNEXPANDED FILL * FILL FACTOR

(14) THE MASS ORDINATE + OR - QTY CALCULATED FOR THE DIVISION. PLUS QUANTITY INDICATES AN EXCESS OF MATERIAL WITHIN THE DIVISION. MINUS INDICATES A SHORTAGE OF MATERIAL WITHIN THE DIVISION.

CLEARING ITEMS							
CATEGORY	STATION	TO	STATION	LOCATION	201.0105 CLEARING STA	201.0205 GRUBBING STA	REMARKS
0010	10+00	-	12+97	TEMP ROAD, LT & RT	3	3	INCLUDES TREES ALONG DAVID ROAD
TOTAL 0010					3	3	

SAWING ITEMS			
CATEGORY	STATION	LOCATION	690.0150 SAWING ASPHALT LF
0010	0+55	CL	25
0010	1+95	CL	25
TOTAL 0010			50



BASE AGGREGATE ITEMS														
					305.0110	305.0120	312.0110	624.0100	645.0220	645.0140	645.0220	650.4500	650.5000	650.9920
CATEGORY	STATION	TO	STATION	LOCATION	BASE AGGREGATE DENSE 3/4-INCH TON	BASE AGGREGATE DENSE 1 1/4-INCH TON	SELECT CRUSHED MATERIAL TON	WATER MGAL	GEOGRID TYPE SR SY	GEOTEXTILE TYPE SAS SY	GEOGRID TYPE SR SY	CONSTRUCTION STAKING SUBGRADE LF	CONSTRUCTION STAKING BASE LF	CONSTRUCTION STAKING SLOPE STAKES LF
0010	0+55.28	-	1+04.05	DAVID DRIVE	10	75	65	5	150	-	150	49	49	49
0010	1+46.55	-	1+95.28	DAVID DRIVE	10	75	65	5	150	-	150	49	49	49
0010	10+00	-	12+97.07	TEMP BYPASS ROAD	-	350	-	-	-	740	-	297	297	297
0010				UNDISTRIBUTED	10	20	20	-	-	-	-	-	-	-
TOTAL 0010					30	520	150	10	300	740	300	395	395	395

ASPHALT ITEMS							SIGN ITEMS									
CATEGORY	STATION	TO	STATION	LOCATION	455.0605	465.0105	CATEGORY	STATION	LOCATION	SIGN CODE	SIZE	SIGN NO	634.0614	637.2230	638.2602	638.3000
					TACK COAT	ASPHALTIC							POSTS WOOD	SIGNS TYPE II	REMOVING	REMOVING
					GAL	SURFACE							4X6-INCH X 14- FT	REFLECTIVE F	SIGNS TYPE II	SUPPORTS
						TON							EACH	SF	EACH	EACH
0010	0+55.28	-	1+04.05	DAVID DRIVE	8	25	0010	1+01	LT	W5-52L	12" x 36"	1/1R	1	3	1	1
0010	1+46.55	-	1+95.28	DAVID DRIVE	8	25	0010	1+01	RT	W5-52R	12" x 36"	2/2R	1	3	1	1
0010				UNDISTRIBUTED	4	20	0010	1+50	LT	W5-52L	12" x 36"	3/3R	1	3	1	1
							0010	1+50	RT	W5-52R	12" x 36"	4/4R	1	3	1	1
TOTAL 0010					20	70	TOTAL 0010						4	12	4	4

					628.1504	628.1520	628.1905	628.1910	628.6005	628.7504		
							MOBILIZATIONS	MOBILIZATIONS				
							EROSION	EROSION				
					SILT FENCE	SILT FENCE	CONTROL	CONTROL	TURBIDITY	TEMPORARY		
CATEGORY	STATION	TO	STATION	LOCATION	LF	LF	EACH	EACH	SY	LF	REMARKS	
0010	0+55.28	-	1+04.05	DAVID DRIVE	320	640	-	-	140	20	INCLUDES AROUND THE TEMP ROAD	
0010	1+46.55	-	1+95.28	DAVID DRIVE	320	640	-	-	140	20	INCLUDES AROUND THE TEMP ROAD	
0010				UNDISTRIBUTED	60	120	4	4	-	20		
TOTAL 0010					700	1,400	4	4	280	60		


CATEGORY	STATION	TO	STATION	LOCATION	625.0500	627.0200	628.2008	629.0210	630.0120	630.0200	630.0300	630.0500	REMARKS
					SALVAGED TOPSOIL SY	MULCHING SY	EROSION MAT URBAN CLASS I TYPE B SY	FERTILIZER TYPE B CWT	SEEDING MIXTURE NO. 20 LB	SEEDING TEMPORARY LB	SEEDING BORROW PIT LB	SEED WATER MGAL	
0010	10+00	-	11+35	TEMPORARY BYPASS	-	200	-	-	-	5	-	-	INSTALLATION OF BYPASS
0010	11+60	-	12+97	TEMPORARY BYPASS	-	200	-	-	-	5	-	-	INSTALLATION OF BYPASS
0010	0+55	-	1+04	DAVID DRIVE	200	-	200	0.2	9	6	-	5	
0010	1+47	-	1+95	DAVID DRIVE	180	-	200	0.2	9	6	-	5	
0010	10+00	-	11+35	TEMPORARY BYPASS	-	400	-	0.4	18	10	-	10	REMOVAL OF BYPASS
0010	11+60	-	12+97	TEMPORARY BYPASS	-	400	-	0.4	18	10	-	10	REMOVAL OF BYPASS
0010				BORROW / WASTE PIT	-	-	-	-	-	-	17	-	
0010				UNDISTRIBUTED	20	50	20	0.8	6	8	3	-	
				TOTAL 0010	400	1,250	420	2.0	60	50	20	30	

				643.0300		633.1100		643.0420		643.0705		643.0715		643.0900	
				TRAFFIC CONTROL DRUMS		DELINEATORS TEMPORARY		TRAFFIC CONTROL BARRICADES TYPE III		TRAFFIC CONTROL WARNING LIGHTS TYPE A		TRAFFIC CONTROL WARNING LIGHTS TYPE C		TRAFFIC CONTROL SIGNS	
CATEGORY	STATION - STATION	LOCATION	DAYS	DAY	NO REQD	EACH		DAY	NO REQD	DAY	NO REQD	DAY	NO REQD	DAY	NO REQD
0010	0+55 - 1+96	MAINLINE	65	-	-	-		845	13	1,690	26	-	-	390	6
0010	0+55 - 1+96	BYPASS	65	1,690	26	22		-	-	-	-	780	12	1,430	22
TOTAL 0010				1,690		22		845		1,690		780		1,820	



Standard Detail Drawing List



08E08-03	TYPICAL INSTALLATIONS OF EROSION BALES / TEMPORARY DITCH CHECKS
08E09-06	SILT FENCE
08E11-02	TURBIDITY BARRIER
12A03-10	NAME PLATE (STRUCTURES)
13C19-03	HMA LONGITUDINAL JOINTS
15C02-10A	BARRICADES AND SIGNS FOR MAINLINE CLOSURES
15C02-10B	BARRICADES AND SIGNS FOR VARIOUS CLOSURES
15C06-12	SIGNING & MARKING FOR TWO LANE BRIDGES
15C11-11B	CHANNELIZING DEVICES DRUMS, CONES, BARRICADES AND VERTICAL PANELS
15D31-05	TRAFFIC CONTROL, TEMPORARY BYPASS ROADWAY



GENERAL NOTES

DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.

- ① TEMPORARY DITCH CHECKS EITHER EROSION BALES OR MANUFACTURED SHALL BE PAID FOR UNDER THE BID ITEM OF TEMPORARY DITCH CHECK. THE DEPARTMENT WILL NOT PAY FOR TEMPORARY DITCH CHECKS CONSTRUCTED OF A SINGLE ROW OF EROSION BALES.

TYPICAL INSTALLATIONS OF
EROSION BALES / TEMPORARY
DITCH CHECKS


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED


6/04/02
DATE

/S/ Beth Canestra
CHIEF ROADWAY DEVELOPMENT ENGINEER


FHWA




TYPICAL APPLICATION OF SILT FENCE



SILT FENCE




SILT FENCE AT MEDIAN SURFACE DRAINS




GENERAL NOTES

DETAILS OF CONSTRUCTION NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND APPLICABLE SPECIAL PROVISIONS.

- ① HORIZONTAL BRACE REQUIRED WITH 2" X 4" WOODEN FRAME OR EQUIVALENT AT TOP OF POSTS.
- ② FOR MANUAL INSTALLATIONS THE TRENCH SHALL BE A MINIMUM OF 4" WIDE & 6" DEEP TO BURY AND ANCHOR THE GEOTEXTILE FABRIC. FOLD MATERIAL TO FIT TRENCH AND BACKFILL & COMPACT TRENCH WITH EXCAVATED SOIL.
- ③ WOOD POSTS SHALL BE A MINIMUM SIZE OF 1 1/8" X 1 1/8" OF OAK OR HICKORY.
- ④ SILT FENCE TO EXTEND ACROSS THE TOP OF THE PIPE.
- ⑤ CONSTRUCT SILT FENCE FROM A CONTINUOUS ROLL IF POSSIBLE BY CUTTING LENGTHS TO AVOID JOINTS. IF A JOINT IS NECESSARY USE ONE OF THE FOLLOWING TWO METHODS; A) OVERLAP THE END POSTS AND TWIST, OR ROTATE, AT LEAST 180 DEGREES, B) HOOK THE END OF EACH SILT FENCE LENGTH.



TRENCH DETAIL



SILT FENCE TIE BACK (WHEN REQUIRED BY THE ENGINEER)

SILT FENCE


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED

4-29-05
DATE


FHWA

/S/ Beth Cannestra
CHIEF ROADWAY DEVELOPMENT ENGINEER



SECTION B - B


TURBIDITY BARRIER - FLOAT ALTERNATIVE
CAUTION - SEE NOTE 6




SECTION A - A

TURBIDITY BARRIER - STANDARD POST INSTALLATION

TURBIDITY BARRIER PLACEMENT DETAILS



PLAN VIEW




PLAN VIEW

GENERAL NOTES


DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.

TURBIDITY BARRIER MAY BE REMOVED AT THE ENGINEERS DISCRETION, WHEN PERMANENT EROSION CONTROL MEASURES HAVE BEEN ESTABLISHED.

- 1 DRIVEN STEEL POSTS, PIPES, OR CHANNELS. LENGTH SHALL BE SUFFICIENT TO SECURELY SUPPORT BARRIER AT HIGH WATER ELEVATIONS.
- 2 SAND BAGS TO BE USED AS ADDITIONAL BALLAST WHEN ORDERED BY THE ENGINEER TO MEET ADVERSE FIELD CONDITIONS. SPACE AS APPROPRIATE FOR SITE CONDITIONS.
- 3 WHEN BARRIER HEIGHT "H" EXCEEDS 8 FEET, POST SPACING MAY NEED TO BE DECREASED.
- 4 IN WATERWAYS SUBJECT TO FLUCTUATING WATER ELEVATIONS, PROVISIONS SHOULD BE MADE TO ALLOW THE WATER TO EQUALIZE ON EACH SIDE OF THE BARRIER. THIS MAY BE ACCOMPLISHED BY LEAVING A PORTION OF THE BARRIER OPEN ON THE UPSTREAM END.
- 5 ESTIMATED HIGH WATER ELEVATION DURING CONSTRUCTION PERIOD. MINIMUM BARRIER HEIGHT SHALL BE 2' GREATER THAN EITHER THE Q2 ELEVATION OR THE ESTIMATED HIGH WATER ELEVATION DURING CONSTRUCTION, WHICHEVER IS GREATER.
- 6 FLOAT ALTERNATIVE WILL ONLY BE ALLOWED WITH WRITTEN APPROVAL OF THE ENGINEER, AND IS MEANT FOR LOCATIONS WHERE BEDROCK PREVENTS THE INSTALLATION OF POSTS.
- 7 ALLOW SUFFICIENT SLACK VERTICALLY AND HORIZONTALLY SO THAT SEDIMENT BUILD UP WILL NOT SEPARATE OR LOWER THE TURBIDITY BARRIER.
- 8 USE AS DIRECTED BY COAST GUARD OR DNR PERMIT WHEN WORKING IN NAVIGABLE WATERWAYS.



PLAN VIEW




SECTION C - C

TURBIDITY BARRIER DETAIL SHOWING
TYPICAL PLACEMENT AT STRUCTURES


TURBIDITY BARRIER

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
6/4/02 DATE /S/ Beth Canestra
DATE CHIEF ROADWAY DEVELOPMENT
ENGINEER
FHWA



TYPICAL NAME PLATE
(BRIDGES, CULVERTS, AND RETAINING WALLS)




**NUMBERING DESIGNATION
MULTI-UNIT STRUCTURES**

GENERAL NOTES


NAME PLATES TO BE INSTALLED ON BRIDGES, CULVERTS, AND RETAINING WALLS SHALL CONFORM TO THE REQUIREMENTS OF SECTION 502.3.11 OF THE STANDARD SPECIFICATIONS.

THE BRIDGE NUMBER AND YEAR BUILT SHOWN ON THIS DRAWING ARE EXAMPLES ONLY. SEE CONSTRUCTION PLANS FOR INDIVIDUAL NUMBERING AND YEAR BUILT.

- ① EPOXY RESIN SHALL BE FROM AN APPROVED MANUFACTURER AND USED IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.
- ② REHABILITATION OF AN EXISTING STRUCTURE SHOULD USE THE DATE OF ORIGINAL STRUCTURE CONSTRUCTION.




SECTION A-A



ALTERNATE LUG

- ① ADHERE ANCHOR LUG TO PRECAST RETAINING WALL WITH EPOXY RESIN.



ALTERNATE LUG
(FOR ATTACHMENT TO PRECAST STRUCTURES)

**NAME PLATE
(STRUCTURES)**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED


3/26/10
DATE

FHWA


/S/ Scot Becker
CHIEF STRUCTURAL DEVELOPMENT ENGINEER



TYPICAL PAVEMENT CROSS SECTION
NOTCHED WEDGE JOINT



TYPICAL PAVEMENT CROSS SECTION
VERTICAL JOINT



TYPICAL PAVEMENT CROSS SECTION
VERTICAL JOINT (MILLED)

GENERAL NOTES


IN ADDITION TO THE DETAILS PROVIDED IN THIS DRAWING, CONFORM TO STANDARD SPECIFICATION 450.3.2.8 FOR WHEN A NOTCHED WEDGE JOINT IS REQUIRED AND FOR GENERAL JOINT CONSTRUCTION REQUIREMENTS.

FOR ALL LONGITUDINAL JOINTS, ENSURE THE PAVER SCREED OVERLAPS THE PREVIOUSLY PLACED PAVEMENT BY 1" ± 0.5" AND THE HOT SIDE OF THE JOINT REMAINS HIGHER THAN THE COLD SIDE BY APPROXIMATELY 0.1" AFTER FINAL COMPACTION. (IT WILL BE FLUSH WHEN PAVING IN ECHELON.)

ONLY REMOVE THE LONGITUDINAL NOTCHED WEDGE JOINT FOR SMA PAVEMENT OR AS DIRECTED BY THE ENGINEER TO ADDRESS SPECIFIC LENGTHS OF JOINT DAMAGED BY TRAFFIC.

WHEN MILLING BACK OR REMOVING ANY LONGITUDINAL JOINT, LIMIT THE MATERIAL REMOVED TO 2" FROM THE TOP NOTCH OR FROM THE VERTICAL JOINT EDGE ON THE COLD SIDE OF THE JOINT.

USE LONGITUDINAL MILLED JOINT AS PLANS SHOW OR THE AS THE ENGINEER DIRECTS.





OVERLAP DETAIL (TYPICAL)

HMA LONGITUDINAL JOINTS

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
November 2020 /S/ Steven Hefel
DATE HMA PAVEMENT ENGINEER
FHWA




SPEED LIMIT (MPH)	"STOP AHEAD" ADVANCE WARNING DISTANCE (FT)
25	200
30	200
35	350
40	350
45	500
50	550
55	750


SEE SDD 15C2-SHEET "b"
FOR GENERAL NOTES
AND FOOTNOTES ① THROUGH ⑦

	SIGN ON PERMANENT SUPPORT
	TYPE III BARRICADE
	TYPE III BARRICADE WITH ATTACHED SIGN
	TYPE "A" WARNING LIGHT (FLASHING)
	WORK AREA
	FLAGS, 16" X 16" MIN. (ORANGE)


 M4 - 8
 M3 - X
 OR  OR 
M1 - 4 M1 - 6 M1 - 5A
 OR 
M05 - 1 M06 - 1



APPROVED
November 2025 /S/ Andrew Heidtke
DATE WORK ZONE ENGINEER



DETAIL D
ROAD CLOSURE BARRICADE DETAIL
APPROACH VIEW



DETAIL E
LANE CLOSURE BARRICADE DETAIL
APPROACH VIEW

SEE SDD 15C2 - SHEET "a" FOR LEGEND

GENERAL NOTES

THE EXACT NUMBER, LOCATION, AND SPACING OF ALL SIGNS AND BARRICADES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.

ANY SIGNS TEMPORARY OR EXISTING, WHICH CONFLICT WITH TRAFFIC CONTROL "IN USE", SHALL BE REMOVED OR COVERED AS NEEDED AND AS APPROVED BY THE ENGINEER.

THE SPACING BETWEEN TRAFFIC CONTROL SIGNS SHOULD BE ADJUSTED TO NOT CONFLICT WITH AND SHOULD PROVIDE A DESIRABLE MINIMUM OF 200 FEET CLEARANCE TO EXISTING SIGNS THAT WILL REMAIN IN PLACE.

BARRICADES THAT MUST BE MOVED FOR A WORK OPERATION SHALL BE IMMEDIATELY RE-ESTABLISHED UPON COMPLETION OF THE OPERATION, OR FOR CONTINUING OPERATIONS, AT THE END OF EACH WORKING DAY.

SIGNS THAT WILL BE IN PLACE LESS THAN 7 CONTINUOUS DAYS AND NIGHTS MAY BE MOUNTED ON PORTABLE SUPPORTS.

ALL TYPE III BARRICADES SHALL HAVE RAILS REFLECTORIZED ON BOTH FACES. STRIPES SHALL BE PROPERLY SLOPED DOWN TOWARD THE TRAFFIC SIDE OR AS SHOWN IN THE ROAD CLOSURE BARRICADE DETAIL "D" FOR FULL ROAD CLOSURES.

TYPE "A" LOW - INTENSITY FLASHING WARNING LIGHTS SHALL BE VISIBLE ON BOTH SIDES OF THE BARRICADE.

PARTIAL NUMBERS ON SIGNS SHALL BE DISPLAYED AS A WHOLE NUMBER(AS NEEDED) FOLLOWED BY A FRACTION. SIGNS SHALL NOT DISPLAY NUMBERS IN DECIMAL FORM.


"WO" AND "MO" SIGNS ARE THE SAME AS "W" AND "M" SIGNS EXCEPT THE BACKGROUND IS ORANGE.

ALL SIGNS SHALL BE 48" X 48" UNLESS OTHERWISE NOTED BELOW:
R11 - 2 SHALL BE 48" X 30"
R11 - 3 SHALL, R11 - 4 AND R10 - 61 SHALL BE 60 " X 30"
M4 - 9 SHALL BE 30" X 24"
M3 - X SHALL BE 24" X 12" (36" X 18" IF NEEDED TO MATCH EXISTING SIGNS)
M4 - 8 SHALL BE 24" X 12" (36" X 18" IF NEEDED TO MATCH EXISTING SIGNS)
M1 - 4, M1 - 5A AND M1 - 6 SHALL BE 24" X 24" (36" X 36" IF NEEDED TO MATCH EXISTING SIGNS)
MO5 - 1 AND MO6 - 1 SHALL BE 21" X 21" (30" X 30" IF NEEDED TO MATCH EXISTING SIGNS)
D1 - X SHALL BE AS SHOWN ON SPECIFIC PROJECT SIGNING DETAIL SHEETS.
R1 - 1 SHALL BE 36" X 36"


SIGNS PLACED ON TYPE III BARRICADES THAT ARE SIZES OTHER THAN 48"X30" SHALL HAVE A CORRUGATED POLYPROPYLENE OR POLYETHYLENE PLASTIC SIGN BASE.

- ① TWO WARNING LIGHTS SHALL BE PROVIDED ON THE CENTER BARRICADE AND A MINIMUM OF ONE WARNING LIGHT SHALL BE PROVIDED ON EACH OF THE OTHER BARRICADES WITHIN THE ROADWAY LIMITS. SPACING OF THE WARNING LIGHTS SHALL BE UNIFORM TO THE EDGE OF ROADWAY AS SHOWN (APPROX. 8 FOOT LIGHT SPACING).
- ② THESE SIGNS AND BARRICADES ARE NOT REQUIRED IF ROAD CLOSURE BEGINS AT AN INTERSECTION.
- ③ FOR ROAD CLOSURE WITHOUT LOCAL ACCESS TO PROJECT, SEE ROAD CLOSURE BARRICADE DETAIL "D".
- ④ FOR ROAD CLOSURE WITH LOCAL ACCESS TO PROJECT, SEE ROAD CLOSURE BARRICADE DETAIL "E".
- ⑤ FOR BRIDGE OR CULVERT REPLACEMENTS, SUBSTITUTE "BRIDGE OUT" INSTEAD OF "ROAD CLOSED" ON R11 - 2 AND R11 - 3 SIGNS.
- ⑥ INSTALL DETOUR AND COMMUNITY GUIDE SIGNS AND ARROWS ONLY IF SPECIFIED IN THE CONTRACT. IF THERE ARE EXISTING ROUTE MARKER ASSEMBLIES THAT WILL REMAIN IN PLACE, ADJUST THE LOCATION OF THE DETOUR ROUTE SIGNS TO CORRESPOND WITH THE EXISTING ASSEMBLIES. MODIFY EXISTING SIGNS WHERE POSSIBLE. SEE SPECIFIC PROJECT DETOUR SIGNING DETAIL SHEETS. IF DETOUR SIGNS ARE BEING INSTALLED BY OTHERS, PLACE THE CONTRACTED TRAFFIC CONTROL SIGNS TO ALLOW FOR PLACEMENT OF ALL WARNING, DETOUR AND GUIDE SIGNS AS SHOWN.
- ⑦ "EAST" CARDINAL DIRECTION MARKERS AND RIGHT TURN ARROWS ARE SHOWN. USE OTHER CARDINAL DIRECTIONS AND ARROWS AS APPROPRIATE.

BARRICADES AND SIGNS FOR VARIOUS CLOSURES	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED November 2025 DATE	/S/ Andrew Heidtke WORK ZONE ENGINEER
FHWA	



SITUATION 1
WARRANTING CRITERIA:
BRIDGE WIDTH IS AT LEAST 16 FEET BUT LESS THAN 24 FEET.



SITUATION 2
WARRANTING CRITERIA:
1. BRIDGE WIDTH IS AT LEAST 24 FEET AND
2. BRIDGE SHOULDER WIDTH IS LESS THAN 6 FEET

GENERAL NOTES

DETAILS OF TRAFFIC CONTROL DEVICES AND INSTALLATION NOT SHOWN ON THE DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS, THE SPECIAL PROVISIONS, AND THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.

LOCATE W5-52 SIGN POST(S) BEHIND GUARDRAIL WHEN PRESENT.

PLACE THE EDGE OF THE W5-52 SIGN IN LINE WITH FACE OF CURB OR PARAPET.

ON BRIDGE ONLY PROJECTS, PLACE 300 FEET OF EDGELINE.

OMIT EDGELINES ON ROADWAYS WITHOUT EXISTING EDGELINES.

① OMIT ON ONE-WAY TRAVELED WAYS.

LEGEND

⊙ SIGN ON PERMANENT SUPPORT

➡ DIRECTION OF TRAFFIC

DISTANCE TABLE

POSTED OR 85TH PERCENTILE SPEED	DISTANCE "A"
25	150'
30	200'
35	250'
40	300'
45	400'
50	550'
55	700'


**SIGNING AND MARKING
FOR TWO LANE BRIDGES**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


APPROVED
May 2023
DATE

/S/ Jeannie Silver
Statewide Pavement Marking Engineer


FHWA




DRUM
BALLAST WIDTHS
RANGE FROM 24"-36"



42" CONE
DO NOT USE IN TAPERS
½ SPACING OF DRUMS
BALLAST WIDTHS
RANGE FROM 14"-20"



VERTICAL PANEL
THE STRIPES SHALL SLOPE DOWNWARD TO
THE TRAFFIC SIDE FOR CHANNELIZATION.



TYPE III BARRICADE
IF SIGN MOUNTED, DO NOT COVER MORE THAN 50% OF THE TOP
TWO RAILS OR 33% OF THE TOTAL AREA OF THE THREE RAILS.
★ IF USED FOR A PERMANENT APPLICATION USE RED SHEETING.

GENERAL NOTES

- ① REFLECTIVE SHEETING SHALL FOLLOW THE REQUIREMENTS IN THE APPROVED PRODUCTS LISTING FOR SIGN SHEETING.
- ② LOCATION OF WARNING LIGHTS WHEN SHOWN ON THE PLAN.

**CHANNELIZING DEVICES
DRUMS, CONES, BARRICADES
AND VERTICAL PANELS**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
February 2026 /S/ Andrew Heidtke
DATE WORK ZONE ENGINEER

FHWA

LEGEND

GENERAL NOTES

ALL SIGNS ARE 48"X48" UNLESS OTHERWISE NOTED.

"WO" IS THE SAME AS "W" EXCEPT THE BACKGROUND IS ORANGE.

ANY SIGNS TEMPORARY OR EXISTING, WHICH CONFLICT WITH THE TRAFFIC CONTROL "IN USE" SHALL BE REMOVED OR COVERED AS NEEDED AND AS APPROVED BY THE ENGINEER.

THE EXACT NUMBER, LOCATION, AND SPACING OF ALL SIGNS AND DEVICES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.

THE SPACING BETWEEN SIGNS SHOULD BE ADJUSTED TO NOT CONFLICT WITH AND TO PROVIDE A MINIMUM OF 200 FEET (500' DESIRABLE) DISTANCE TO EXISTING SIGNS.


SIGN LAYOUTS SHALL BE IN ACCORDANCE WITH THE FHWA'S MANUAL ON STANDARD HIGHWAY SIGNS OR THE WISCONSIN STANDARD SIGN PLATES.

EQUIPMENT, VEHICLES, OR MATERIAL SHOULD NOT BE STORED IN BUFFER SPACE.

- ① IF ADVISORY SPEED IS GREATER THAN 30 MPH, USE THE WO1-4 SIGN. IF ADVISORY SPEED IS 30 MPH OR LESS, USE THE WO1-3 SIGN.
- ② WHEN THE DISTANCE TO / FROM THE NEXT CLOSEST NO-PASSING ZONE IS LESS THAN THE MINIMUM DISTANCE BETWEEN ZONES AS INDICATED IN THE SPECIFICATIONS, THE TWO ZONES SHALL BE CONNECTED.
- ③ OMIT THESE WO1-6 SIGNS IF THE ADVISORY SPEED OF THE CURVE IS GREATER THAN 30 MPH.
- ④ TEMPORARY STEEL PLATE BEAM GUARD AND END TREATMENT WHEN INCLUDED IN THE CONTRACT. FOR LAYOUT, SEE DETAILS ELSEWHERE IN THE PLAN.



S (MPH)	BUFFER SPACE (DESIRABLE)
25	55'
30	85'
35	120'
40	170'
45	220'
50	280'
55	335'

S = NON-CONSTRUCTION SPEED LIMIT (MPH)





TRAFFIC CONTROL, TEMPORARY BYPASS ROADWAY	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED May 2023 DATE	/S/ Andrew Heidtke WORK ZONE ENGINEER
FHWA	

URBAN AREA



* * The existence of curb and gutter does not in itself mandate the vertical clearance illustrated. That height is typically measured where there is sidewalk adjacent to the roadway or parking is permitted. In the absence of sidewalk vertical clearance is measured from the top of the curb. Offset of signs is measured from the flow line.

RURAL AREA (See Note 2)



* 6 feet from edge of a paved shoulder or 12 feet from the edge of pavement (edge line location) or 2 feet from outside edge of gravel, whichever is greater unless directed by project engineer.

GENERAL NOTES

- Signs wider than 4 feet or 20 sq.ft or larger, shall be mounted on multiple posts. Refer to plate A4-4.
- If signs are mounted on or behind barrier wall, see A4-10 sign plate.
The Double Arrow sign (W12-1D) shall be mounted at a height of 2'-3" (±) 3". The Chevron sign (W1-8), Roundabout Chevron panel (R6-4B), Enhanced Reference Markers, Clearance Markers (W5-52), Mile Markers (D10 series), In Road Object Markers (W5-54) & End of Road Markers (W5-56) shall be mounted at a height of 4'-3" (±) 3".
- For expressways and freeways, mounting height is 7'-3" (±) 3" or 6'-3" (±) 3" depending upon existence of a sub-sign.
- Minimum mounting height for signs mounted on traffic signal poles is 5'-3" (±) 3".
- Offset distance shall be consistent with existing signs or consistent throughout length of project.
- Folding signs shall be mounted at a height of 5'-3" (±) 3" or as directed by the Engineer.

POST EMBEDMENT DEPTH


Area of Sign Installation (Sq. Ft.)	D (Min)
20 or Less	4'
Greater than 20	5'

TYPICAL INSTALLATION
OF PERMANENT TYPE II
SIGNS ON SINGLE POSTS

WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Rauch*
for State Traffic Engineer


DATE 12/6/23 PLATE NO. A4-3.23



ELEVATION VIEW


DETAIL OF WOOD 4 X 6 SIGN POST IN BOX-OUT

- NOTES: 1. ALL MATERIAL TO BE APPROVED BY ENGINEER PRIOR TO INSTALLATION
2. SEE SIGN PLATE A4-8 FOR SIGN HARDWARE REQUIREMENTS
3. 18 INCH X 18 INCH SQUARE BOX-OUTS MAY BE USED FOR INSTALLATIONS IN EXISTING CONCRETE OR ASPHALT LOCATIONS.



ELEVATION VIEW

DETAIL OF STEEL 2 X 2 SIGN POST IN BOX-OUT



PLAN VIEW

FOR NEW CONCRETE/ASPHALT INSTALLATIONS

SIGN POST
BOX-OUTS
A4-3B

WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Rauch*
for State Traffic Engineer

DATE 1/27/14 PLATE NO. A4-3B.1

PROJECT NO:


HWY:

COUNTY:



SHEET NO:

E


URBAN AREA




RURAL AREA (See Note 3)



2' Min - 4' Max (See Note 6)



48" DIAMOND WARNING SIGN



48" DIAMOND WARNING SIGN

GENERAL NOTES

1. For 3 or 4 post installations, individual post spacing shall be greater than 3'-6".
2. See tables below for required number of posts.
3. For expressways and freeways, mounting height is 7'-3" (±) 3" or 6'-3" (±) 3" depending upon existence of sub-sign.
4. The (±) tolerance for mounting height is 3 inches.
5. J-Assemblies are considered to be one sign for mounting height.
6. Offset distance shall be consistent with existing signs or consistent throughout length of project.
7. Folding signs shall be mounted at a height of 5'-3" (±) 3" or as directed by the engineer.
8. The Double Arrow sign (W12-1) shall be mounted at a height of 2'-3" (±) 3". The Chevron sign (W1-8), Roundabout Chevron panel (R6-4B), Clearance Markers (W5-52), Mile Markers (D10 series), In Road Object Markers (W5-54) & End of Road Markers (W5-56) shall be mounted at a height of 4'-3" (±) 3".

* 6 feet from edge of a paved shoulder or 12 feet from the edge of pavement (edge line location) or 2 feet from outside edge of gravel, whichever is greater unless directed by project engineer.

** The existence of curb and gutter does not in itself mandate the vertical clearance illustrated. That height is typically measured where there is sidewalk adjacent to the roadway or parking is permitted. In the absence of sidewalk vertical clearance is measured from the top of the curb. Offset of signs is measured from the flow line.

*** See A4-3 sign plate for signs 4' or less in width and less than 20 S.F. in area.

SIGN SHAPE OTHER THAN DIAMOND (TWO POSTS REQUIRED)	
L	E
Greater than 48" Less than 60"	12"
60" to 108"	L/5

SIGN SHAPE OTHER THAN DIAMOND (THREE POSTS REQUIRED)	
L	E
Greater than 108" to 144"	12"

POST EMBEDMENT DEPTH

Area of Sign Installation (Sq.Ft.)	D (Min)
20 or Less	4'
Greater than 20	5'

TYPICAL INSTALLATION
OF TYPE II SIGNS
ON MULTIPLE POSTS

WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Rauch*
for State Traffic Engineer

DATE 12/6/23 PLATE NO. A4-4.16



PROJECT NO:

HWY:

COUNTY:

SHEET NO:

E



Nuts, bolts and lags used for mounting signs shall have hexagonal heads and shall be either :

- a. Hot dip galvanized in accordance with ASTM Designation: A 153, Class D, or SC 3
- b. Electro-galvanized in accordance with ASTM Designation : B 633, TYPE III, SC 3.


Threads on bolts and nuts shall be manufactured with sufficient allowance for the cadmium plate or galvanized coating to permit the nuts to run freely on the bolts.

- STRINGER BOLTING TO ALUMINUM SIGNS (SEE SIGN PLATE A4-18)
- MACHINE BOLTS - $\frac{5}{16}$ " X 1-3/4" Length w/ lock nuts
- WOOD POSTS (4" x 6")
- LAG SCREWS - $\frac{3}{8}$ " X 3" (NO STRINGERS ON BACK OF SIGN)
 $\frac{3}{8}$ " X 4" (STRINGERS ON BACK OF SIGN)
- SQUARE STEEL POSTS (2" x 2")
- MACHINE BOLTS - $\frac{3}{8}$ " X 3-1/4" Length w/ nuts (NO STRINGER ON BACK OF SIGN)
 $\frac{3}{8}$ " X 5" Length w/ nuts (STRINGERS ON BACK OF SIGN)
- RIVETS - $\frac{9}{32}$ " (6605-9-6) BULB-TITE, TRI-FOLD, ALUMINUM BODY/MANDREL
O.D. FLANGE .720-.765 INCH, GRIP RANGE .042-.375 INCH
- WASHERS (ALL POSTS) -
- 1-1/4" O.D. X $\frac{3}{8}$ " I.D. X $\frac{1}{16}$ " STEEL
 - 1-1/4" O.D. X $\frac{3}{8}$ " I.D. X .080 NYLON


* Two different fastening systems are shown for illustration purposes. On any individual sign, either one or the other system shall be used. Actual number of fasteners per sign varies with the sign area, but normally there are two. For a single post installation, all signs greater than 9 sq. ft. require the use of 3 fasteners.

ATTACHMENT OF SIGNS TO POSTS	
WISCONSIN DEPT OF TRANSPORTATION	
APPROVED	<i>Matthew R. Rauch</i> For State Traffic Engineer
DATE 4/1/2020	PLATE NO. A4-8.9

**2 1/4" SQUARE
12 GAUGE
PERFORATED
GALVANIZED FINISH**



**2 1/2" SQUARE
12 GAUGE
OMNI-DIRECTIONAL
PERFORATED
SOIL STABILIZING SLEEVE
GALVANIZED FINISH**

[illegible]

TECHNICAL DRAWING OF A SIGNPOST ASSEMBLY.

Side View Dimensions:


- Overall height: LENGTH SHOWN ON MISC. Q'TYS
- Section 1: 2" STEEL TUBULAR SQUARE UPPER SECTION
- Section 2: 2 1/2" SQUARE X 18" (SOIL STABILIZING SLEEVE)
- Section 3: 2 1/4" SQUARE X 36"
- Section 4: 36" (Total length of the lower square section)
- Section 5: 18"
- Section 6: 12"

Top View Details:

- TELESCOPE PIECES FLUSH AT TOP
- ALL HOLES 7/16" SPACED 1" C-C
- ALL FOUR SIDES
- 3/8" ZINC PLATED CORNER ANCHOR BOLT AND NUT
- 1" (Distance from corner to bolt)
- 3/8" ZINC PLATED ANCHOR BOLT AND NUT

Sign Assembly Details:

- SIGN
- SEE SIGN PLATE A4-8 FOR BOLT WASHER, & NUT MATERIAL



Area of Sign Installation (Sq. Ft.)	Number of Required Posts
9 or less	1
Greater than 9 less than or equal to 18	2
Greater than 18 less than or equal to 27	3

Signs wider than 3 feet or larger than 9 sq. ft shall be mounted on multiple posts (see above table).

TUBULAR STEEL
SIGN POST
A4-9

WISCONSIN DEPT OF TRANSPORTATION

APPROVED Matthew R. Rauch

for State Traffic Engineer

DATE 2/05/15 PLATE NO. A4-9.9



PROJECT NO:

HWY:

COUNTY:

SHEET NO:

T



SIDE VIEW

GENERAL NOTES

1. All 4 x 6 Wood Posts shall be modified by having two 1 1/2" diameter holes drilled perpendicular to the roadway centerline.

4 X 6 WOOD POST MODIFICATIONS

WISCONSIN DEPT OF TRANSPORTATION

APPROVED

Chester J. Spang
for State Traffic Engineer

DATE 3/27/97

PLATE NO. A4-11.2

PROJECT NO:

HWY:




COUNTY:

SHEET NO:


E

BANDING

SINGLE SIGN



WASHER PLACEMENT




WASHERS (ALL POSTS) -
1-1/4" O.D. X 3/8" I.D. X 1/16" STEEL
1-1/4" O.D. X 3/8" I.D. X .080 NYLON
FOR ALL TYPE H SIGNS


GENERAL NOTES

1. Any sign over 3 feet in width shall use the V-Block banding method. See A5-10 standard plate.
2. Signs 3 feet or greater in height shall have three bracket bands installed. Signs less than 3 feet in height shall have two bracket bands installed.
3. Banding and assembly bracket shall be stainless steel. All bands shall be 3/4" in width and 0.025" thickness.
4. ALL SIGN MOUNTING BOLTS AND WASHERS SHALL BE EITHER:
 - a. Hot dip or mechanically galvanized in accordance with ASTM Designation: A 153, Class D
 - b. Electro-galvanized in accordance with ASTM designation: B 633, Type III, SC 3

"J" ASSEMBLY



CHANNEL
SEE TYPICAL PANEL
INSTALLATION SHEET



STANDARD SIGN
SIGN BANDING DETAILS

WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Rauch*
for State Traffic Engineer
DATE 6/10/19 PLATE NO. A5-9.4


VIEW FROM
BACK

7


PROJECT NO:

SHEET NO:

E



VIEW FROM SIDE



VIEW FROM TOP

GENERAL NOTES

1. WOOD 4"X6" POST MATERIAL SHALL CONFORM TO 507.2.2 OF THE WISDOT STANDARD SPECIFICATIONS
2. BLOCK BANDING AND CLIPS SHALL BE STAINLESS STEEL, $\frac{3}{4}$ " WIDTH AND 0.025" THICKNESS
3. SIGNS 3' OR GREATER IN HEIGHT SHALL UTILIZE 3 BLOCK BANDS. SIGNS UNDER 3' IN HEIGHT SHALL UTILIZE 2 BLOCK BANDS
4. ACTUAL NUMBER OF FASTENERS PER SIGN VARIES WITH THE SIGN AREA, BUT NORMALLY THERE ARE TWO. FOR SIGNS GREATER THAN 9 S.F. 3 FASTENERS SHALL BE USED.
5. ALL SIGN MOUNTING BOLTS AND WASHERS SHALL BE EITHER:
 - a. Hot dip or mechanically galvanized in accordance with ASTM Designation: A 153, Class D
 - b. Electro-galvanized in accordance with ASTM Designation : B 633, TYPE III, SC 3
6. ALL BOLTS SHALL HAVE HEXAGONAL HEADS.
7. STEEL WASHERS SHALL BE $\frac{1}{4}$ " O.D. X $\frac{3}{8}$ " I.D. X $\frac{1}{16}$ "
8. NYLON WASHERS SHALL BE $\frac{1}{4}$ " O.D. X $\frac{3}{8}$ " I.D. X .080 FOR TYPE H OR TYPE F FACE SIGN



✱ LAG BOLTS SHALL BE $\frac{3}{8}$ " X $2\frac{1}{2}$ "

BLOCK BANDING DETAIL
(V-BLOCK OPTION)

WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Rauch*
for State Traffic Engineer

DATE 4/19/2022 PLATE NO. A5-10.3



NOTES

1. Sign is Type II - Type F Reflective
2. Color:
Background - Yellow
Message - Black
3. Alternate colors of stripes as shown.



SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1																											
2S	12	36	1 1/2			4 3/8	3 1/2	5 5/8	45°	4	4																3.0
2M	12	36	1 1/2			4 3/8	3 1/2	5 5/8	45°	4	4																3.0
3	18	54	1 1/2			6	5 1/2	8 1/2	45°	6	6 9/16																6.75
4																											
5																											

STANDARD SIGN
W5-52L & W5-52R

WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Rauch*
For State Traffic Engineer

DATE 3/4/2024 PLATE NO. W5-52.10



THIS SHEET WAS CREATED BY THE WISDOT BUREAU OF STRUCTURES STANDARD BRIDGE DESIGN TOOL VERSION 1.1.0.0

DESIGN DATA

LIVE LOAD:

DESIGN LOADING: HL-93
INVENTORY RATING FACTOR: RF = 1.10
OPERATING RATING FACTOR: RF = 1.42
WISCONSIN STANDARD PERMIT VEHICLE (WIS.-SPV): 250 (KIPS)

STRUCTURE IS DESIGNED FOR A FUTURE WEARING SURFACE OF 20 POUNDS PER SQUARE FOOT.

MATERIAL PROPERTIES:

CONCRETE MASONRY: _____ f'c = 4,000 P.S.I.
SUPERSTRUCTURE _____ f'c = 3,500 P.S.I.
ALL OTHER _____

BAR STEEL REINFORCEMENT: _____ fy = 60,000 P.S.I.
GRADE 60 _____

FOUNDATION DATA

ABUTMENTS TO BE SUPPORTED ON HP 10 x 42 PILING SEATED IN PRE-BORED HOLES CORED 6 FEET MINIMUM INTO ROCK FOR THE WEST ABUTMENT AND 4 FEET MINIMUM INTO ROCK FOR THE EAST ABUTMENT. PILE DRIVING IS NOT REQUIRED. THE FACTORED AXIAL RESISTANCE OF THE PILES IN COMPRESSION USED FOR DESIGN IS 180 TONS MULTIPLIED BY A RESISTANCE FACTOR OF 0.5. ESTIMATED 17 FEET LONG FOR WEST ABUTMENT AND 18 FEET LONG FOR EAST ABUTMENT.

TRAFFIC VOLUME

DAVID DRIVE
ADT = 135 (2046)
R.D.S. = 30 M.P.H.

HYDRAULIC DATA

100 YEAR FREQUENCY

Q₁₀₀ = 1370 C.F.S.
VEL. = 7.3 F.P.S.
HW₁₀₀ = EL. 953.66
WATERWAY AREA = 188 SQ. FT.
DRAINAGE AREA = 2.18 SQ. MI.
ROADWAY OVERTOPPING = NA
SCOUR CRITICAL CODE = 5

2 YEAR FREQUENCY

Q₂ = 138 C.F.S.
VEL. = 2.6 F.P.S.
HW₂ = EL. 948.93

TEMPORARY STRUCTURE:

Q₅ = 322 C.F.S.
HW₅ = EL. 950.23
WATERWAY AREA 74 SQ. FT.

LIST OF DRAWINGS

- GENERAL PLAN
- CROSS SECTION & QUANTITIES
- SUBSURFACE EXPLORATION
- WEST ABUTMENT
- WEST ABUTMENT DETAILS
- EAST ABUTMENT
- EAST ABUTMENT DETAILS
- SUPERSTRUCTURE
- SUPERSTRUCTURE DETAILS
- TUBULAR STEEL RAILING TYPE 'M'

STRUCTURE DESIGN CONTACTS:

JEREMY KRACHEY 608-988-7059
AARON BONK 608-261-0261

THESE PLANS ARE BASED UPON STANDARD BRIDGE PLANS DEVELOPED AND MAINTAINED BY THE WISCONSIN DEPARTMENT OF TRANSPORTATION THROUGH THE USE OF THE WISDOT STANDARD BRIDGE DESIGN TOOL. THE UNDERSIGNED DESIGNER CERTIFIES THE ACCURACY OF THE BRIDGE TYPE, SIZE AND LOCATION, HYDRAULICS AND FOUNDATION SUPPORT, AND INFORMATION IN THE PLANS THAT IS NOT PART OF THE STANDARD PLANS SUPPLIED BY THE DEPARTMENT. THE DESIGNER FURTHER CERTIFIES THAT USE OF THE STANDARD BRIDGE DESIGN TOOL FOR DEVELOPMENT OF THIS PLAN IS CONSISTENT WITH THE GUIDANCE PROVIDED IN THE WISDOT BRIDGE MANUAL.



NO.	DATE	REVISION	BY
-----	------	----------	----

ORIGINAL PLANS
PREPARED BY:



STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

ACCEPTED  JLR 05/11/26
CHIEF STRUCTURES DESIGN ENGINEER DATE

STRUCTURE B-56-256

DAVID DRIVE OVER BRANCH OF PLUM CREEK

COUNTY SAUK TOWN WOODLAND

DESIGN SPEC.
AASHTO LRFD BRIDGE DESIGN SPECIFICATION

DESIGNED BY	JFK	DESIGNED CK'D	JLB	DRAWN BY	BAS	PLANS CK'D	RDG
-------------	-----	---------------	-----	----------	-----	------------	-----

GENERAL PLAN

SHEET 1 OF 10

I.D.

DATE:

SCALE = 10

GENERAL NOTES

DRAWINGS SHALL NOT BE SCALED.

BAR STEEL REINFORCEMENT SHALL BE EMBEDDED 2" CLEAR UNLESS OTHERWISE SHOWN OR NOTED.

THE FIRST OR FIRST TWO DIGITS OF THE BAR MARK SIGNIFIES THE BAR SIZE.

BEVEL EXPOSED EDGES OF CONCRETE ¾" UNLESS OTHERWISE NOTED.

THE UPPER LIMITS OF "EXCAVATION FOR STRUCTURES B-56-256 " SHALL BE THE EXISTING GROUNDLINE.

AT THE BACK FACE OF ABUTMENT ALL VOLUME WHICH CANNOT BE PLACED BEFORE ABUTMENT CONSTRUCTION AND IS NOT OCCUPIED BY THE NEW STRUCTURE SHALL BE BACKFILLED WITH STRUCTURE BACKFILL TYPE A.

EXCAVATION BELOW THE ABUTMENT AND ABUTMENT BEDDING MATERIALS REQUIRES ENGINEER APPROVAL. GEOTEXTILE SHALL BE SET AT THE BOTTOM OF EXCAVATION AND EXTEND 2'-0" ABOVE BOTTOM OF ABUTMENT.


THE QUANTITY FOR BACKFILL STRUCTURE IS CALCULATED BASED ON THE DETAIL SHOWN IN THE PLANS.

THE SLOPE OF THE FILL IN FRONT OF THE ABUTMENTS SHALL BE COVERED WITH HEAVY RIPRAP AND GEOTEXTILE TYPE HR TO THE EXTENT SHOWN ON SHEET 1 AND THE ABUTMENT DETAILS.

AT ABUTMENTS, CONCRETE POURED UNDER WATER WILL BE ALLOWED AND SHALL BE DONE IN ACCORDANCE WITH SECTION 502.3.5.3 OF THE STANDARD SPECIFICATIONS.


SLAB FALSEWORK SHALL BE SUPPORTED ON PILES OR THE SUBSTRUCTURE UNLESS AN ALTERNATE METHOD IS APPROVED BY THE ENGINEER.

PROTECTIVE SURFACE TREATMENT TO BE APPLIED TO ENTIRE EXPOSED TOP OF SLAB, INCLUDING THE SLAB EDGE AND 1'-0" UNDER THE SLAB, THE TOP AND EXTERIOR EXPOSED FACE OF WINGS AND FRONT FACE OF ABUTMENT TO 1'-0" PAST THE EDGE OF SLAB.



CROSS SECTION THRU ROADWAY

LOOKING UPSTATION
(PILING NOT SHOWN FOR CLARITY)




ABUTMENT BACKFILL DIAGRAM


- L = ABUTMENT BODY LENGTH AT BACKFACE (FT)
- H = AVERAGE ABUTMENT FILL HEIGHT (FT)
- H1 = WING 1 HEIGHT AT TIP (FT)
- H2 = WING 2 HEIGHT AT TIP (FT)
- W = WING LENGTH (FT)
- EF = EXPANSION FACTOR (1.20 FOR CY BID ITEMS AND 1.00 FOR TON BID ITEMS)
- $V_{CF} = (L)(3.0')(H) + (L)(0.5)(1.5H)(H) + (3')(0.5)(H1+H2+H+H)(W)$
- $V_{CY} = V_{CF}(EF)/27$
- $V_{TON} = V_{CY}(2.0)$

TOTAL ESTIMATED QUANTITIES

BID ITEM NUMBER	BID ITEMS	UNIT	SUPER	WEST ABUT.	EAST ABUT.	TOTALS
203.0260	REMOVING STRUCTURE OVER WATERWAY WITH MINIMAL DEBRIS P-56-933	EACH	---	---	---	1
206.1001	EXCAVATION FOR STRUCTURES BRIDGES (B-56-256)	EACH	---	---	---	1
210.1500	BACKFILL STRUCTURE TYPE A	TON	---	267	179	446
502.0100	CONCRETE MASONRY BRIDGES	CY	77	41	30	148
502.3200	PROTECTIVE SURFACE TREATMENT	SY	148	23	17	188
505.0400	BAR STEEL REINFORCEMENT HS STRUCTURES	LB	---	2180	2,040	4220
505.0600	BAR STEEL REINFORCEMENT HS COATED STRUCTURES	LB	15,920	1860	1,530	19310
513.4061	RAILING TUBULAR TYPE M	LF	90	---	---	90
516.0500	RUBBERIZED MEMBRANE WATERPROOFING	SY	---	5	5	10
526.0101	TEMPORARY STRUCTURE (11+48)	EACH	---	---	---	1
550.0020	PRE-BORING ROCK OR CONSOLIDATED MATERIALS	LF	---	77	98	175
550.1100	PILING STEEL HP 10-INCH X 42 LB	LF	---	119	126	245
606.0300	RIPRAP HEAVY	CY	---	35	35	70
612.0406	PIPE UNDERDRAIN WRAPPED 6-INCH	LF	---	70	70	140
645.0111	GEOTEXTILE TYPE DF SCHEDULE A	SY	---	50	50	100
645.0120	GEOTEXTILE TYPE HR	SY	---	85	85	170
NON-BID ITEMS						
	FILLER	SIZE	---	---	---	½", ¾"




PROTECTIVE SURFACE TREATMENT DETAILS



TYPICAL SECTION THRU ABUTMENT

- ▲ BACKFILL PAY LIMITS. BACKFILL BEYOND PAY LIMITS SHALL BE INCIDENTAL TO EXCAVATION FOR STRUCTURES. LIMITS OF EXCAVATION SHALL BE DETERMINED BY THE CONTRACTOR.
- PIPE UNDERDRAIN WRAPPED (6-INCH). SLOPE 0.5% MIN. TO SUITABLE DRAINAGE. ATTACH RODENT SHIELD AT ENDS OF PIPE UNDERDRAIN.





RODENT SHIELD DETAIL

- * DIMENSIONS ARE APPROXIMATE. THE GRATE IS SIZED TO FIT INTO A PIPE COUPLING. ORIENT SO SLOTS ARE VERTICAL.
- THE RODENT SHIELD, PIPE COUPLING AND SCREWS SHALL BE CONSIDERED INCIDENTAL TO THE BID ITEM "PIPE UNDERDRAIN WRAPPED 6-INCH".
- THE RODENT SHIELD SHALL BE A PVC GRATE SIMILAR TO THIS DETAIL. THE GRATE IS COMMERCIALY AVAILABLE AS A FLOOR STRAINER. A PIPE COUPLING IS REQUIRED FOR THE ATTACHMENT OF THIS SHIELD TO THE EXPOSED END OF THE PIPE UNDERDRAIN. THE SHIELD SHALL BE FASTENED TO THE PIPE COUPLING WITH TWO OR MORE NO. 10 X 1-INCH STAINLESS STEEL SHEET METAL SCREWS.

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-56-256			
DRAWN BY		BAS	PLANS CK'D JFK
CROSS SECTION & QUANTITIES		SHEET 2 OF 10	

BORING #	DATE COMPLETED	NORTHING (Y)	EASTING (X)
1	9/24/2025	289334.41	517498.21
2	9/24/2025	289345.45	517551.89
BORINGS COMPLETED BY: GEOTEST, INC.			
REPORT COMPLETED BY: GEOTEST, INC.			
ALL COORDINATES REFERENCED TO WCCS NAD 83(91)		SAUK COUNTY	




STATE PROJECT NUMBER

5738-00-74

MATERIAL SYMBOLS

ASPHALT	TOPSOIL	PEAT
CONCRETE	FILL	GRAVEL
SAND	CLAY	SILT
BOULDERS OR COBBLES	LIMESTONE	BEDROCK (UNKNOWN)
SHALE	SANDSTONE	IGNEOUS/META

LEGEND OF BORING



(1) UNCONFINED STRENGTH, AS DETERMINED BY A POCKET PENETROMETER (TSF)

(2) UNLESS OTHERWISE, SPECIFIED THE SPT 'N' VALUE IS BASED ON AASHTO T-206, STANDARD PENETRATION TEST. THE SPT 'N' VALUE PRESENTED HAS NOT BEEN CORRECTED FOR OVERBURDEN PRESSURE OR HAMMER EFFICIENCY.

GROUND WATER ELEVATION

- ▽ AT TIME OF DRILLING
- ▼ END OF DRILLING
- ▼ AFTER DRILLING

ABBREVIATIONS

F-FINE M-MEDIUM C-COARSE ST-SHELBY TUBE

SUBSURFACE EXPLORATION FOR FOUNDATION DESIGN AND BIDDERS INFORMATION

BORINGS WERE COMPLETED AT POINTS APPROXIMATELY AS INDICATED ON THIS DRAWING TO OBTAIN INFORMATION CONCERNING THE CHARACTER OF SUBSURFACE MATERIALS FOUND AT THE SITE. BECAUSE THE INVESTIGATED DEPTHS ARE LIMITED AND THE AREA OF THE BORINGS IS VERY SMALL IN RELATION TO THE ENTIRE SITE, THE WISCONSIN DEPARTMENT OF TRANSPORTATION DOES NOT WARRANT SIMILAR SUBSURFACE CONDITIONS BELOW, BETWEEN, OR BEYOND THESE BORINGS. VARIATIONS IN SOIL CONDITIONS SHOULD BE EXPECTED AND FLUCTUATIONS IN GROUNDWATER LEVELS MAY OCCUR.

NO.	DATE	REVISION	BY
-----	------	----------	----

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION
STRUCTURES DESIGN SECTION

STRUCTURE B-56-256

DRAWN BY	BAS	PLANS CK'D
----------	-----	------------

SUBSURFACE
EXPLORATION

SHEET 3 OF 10




- | | | | |
|--|------|-----------------|-------------------|
| | | | |
| NO. | DATE | REVISION | BY |
| STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION | | | |
| STRUCTURE | | B-56-256 | |
| DRAWN
BY | | BAS | PLANS
CK'D JFR |
| WEST
ABUTMENT | | SHEET 4 | |
| | | | |


NOTE: THE FIRST OR FIRST TWO DIGITS OF THE BAR MARK SIGNIFIES THE BAR SIZE.

Diagram showing the layout of three horizontal pipes (A502, A407, A508) with vertical dimensions (7'-6", 2'-7", 5'-11", 4'-4") and horizontal dimensions (2'-2", 1'-8", 2'-2").

A502, A407, A508




A414





A416


SHOWING F.F. WING




SHOWING F.F. WING



SHOWING UPPER WING REINFORCEMENT




SHOWING LOWER WING REINFORCEMENT
WING 2 SIMILAR



'HP' PILE DETAILS

THIS SHEET WAS CREATED BY THE WISDOT BUREAU OF STRUCTURES STANDARD BRIDGE DESIGN TOOL VERSION 1.1.0.0

TYPICAL BOTH WINGS



- A01** OPTIONAL CONST. JOINT: KEYWAY FORMED BY A BEVELED 2X6. PROVIDE $\frac{3}{4}$ " "V" GROOVE ON F.F. OF WINGWALL IF JOINT IS USED.
- A06** SUPPORT ABUTMENT ON HP 10 x 42 PILING, ESTIMATED 17 FT LONG WITH A REQUIRED DRIVING RESISTANCE OF 180TONS PER PILE.
- A15** PIPE UNDERDRAIN WRAPPED (6-INCH). SLOPE 0.5% MIN. TO SUITABLE DRAINAGE. RODENT SHIELD REQUIRED. DISCHARGE 1 FT ABOVE NORMAL WATER ELEVATION
- A19** 18" RUBBERIZED MEMBRANE WATERPROOF ONLY IF OPTIONAL CONSTRUCTION JOINT IS USED. COST INCIDENTAL TO BID ITEM "CONCRETE MASONRY STRUCTURES"

NO.	DATE	REVISION
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION		
STRUCTURE B-56-256		
DRAWN BY		PLANS CK'D
BAS		JFK
WEST ABUTMENT DETAILS		SHEET 5 OF 10

SCALE -




- | | | | |
|--|------|-----------------|-------------------|
| | | | |
| NO. | DATE | REVISION | BY |
| STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION | | | |
| STRUCTURE | | B-56-256 | |
| DRAWN
BY | | BAS | PLANS
CK'D JFR |
| EAST
ABUTMENT | | SHEET 6 OF 10 | |
| | | | |

BILL OF BARS


NOTE: THE FIRST OR FIRST TWO DIGITS OF THE BAR MARK SIGNIFIES THE BAR SIZE.

BAR MARK	COAT	NO. REQ'D.	LENGTH	BENT	BAR SERIES	LOCATION
B501		64	7'-0"	X		ABUT BODY STIRRUPS
B502		26	7'-1"	X		ABUT BODY STIRRUPS - TOP U-BAR
B503		9	31'-3"			ABUT BODY HORIZ. - F.F.
B804		18	21'-7"	X		ABUT BODY HORIZ. - B.F.
B405		27	3'-0"	X		ABUT BODY TIE BARS
B506	X	25	2'-0"			ABUT BODY DOWEL BARS
B407	X	56	11'-4"	X		WING STIRRUPS
B508	X	6	10'-7"	X		WING CORNER STIRRUPS
B509	X	18	11'-9"	X		WING LOWER HORIZ. - F.F.
B810	X	18	13'-3"	X		WING LOWER HORIZ. - B.F.
B411	X	4	10'-1"			WING UPPER HORIZ.
B412	X	4	7'-7"			WING UPPER HORIZ.
B413	X	4	5'-0"			WING UPPER HORIZ.
B414	X	4	9'-8"	X		WING TOP HORIZ.
B415	X	4	8'-3"	X		WING 3 UPPER HORIZ. CORNER
B416	X	4	8'-4"	X		WING 4 UPPER HORIZ. CORNER




WING 3 ELEVATION

SHOWING F.F. WING




WING 3 PLAN

SHOWING UPPER WING REINFORCEMENT




WING 3 PLAN

SHOWING LOWER WING REINFORCEMENT
WING 4 SIMILAR




'HP' PILE DETAILS

THIS SHEET WAS CREATED BY THE WISDOT BUREAU OF STRUCTURES STANDARD BRIDGE DESIGN TOOL VERSION 1.1.0.0




WING 4 ELEVATION

SHOWING F.F. WING



WING 4 PLAN


SHOWING UPPER WING REINFORCEMENT



SECTION THRU WING 3

TYPICAL BOTH WINGS


SECTION A-A




- A01 OPTIONAL CONST. JOINT: KEYWAY FORMED BY A BEVELED 2X6. PROVIDE 3/4" "V" GROOVE ON F.F. OF WINGWALL IF JOINT IS USED.
- A06 SUPPORT ABUTMENT ON HP 10 x 42 PILING, ESTIMATED .18 FT LONG WITH A REQUIRED DRIVING RESISTANCE OF 180TONS PER PILE.
- A15 PIPE UNDERDRAIN WRAPPED (6-INCH). SLOPE 0.5% MIN. TO SUITABLE DRAINAGE. RODENT SHIELD REQUIRED. DISCHARGE 1 FT ABOVE NORMAL WATER ELEVATION
- A19 18" RUBBERIZED MEMBRANE WATERPROOFING, ONLY IF OPTIONAL CONSTRUCTION JOINT IS USED. COST INCIDENTAL TO BID ITEM "CONCRETE MASONRY STRUCTURES"

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-56-256			
DRAWN BY		BAS	PLANS CK'D JFK
EAST ABUTMENT DETAILS		SHEET 7 OF 10	


SCALE =



CROSS SECTION THRU ROADWAY



PLAN




LONGITUDINAL SECTION

DIMENSIONS ARE GIVEN PARALLEL TO ϵ ROADWAY UNLESS OTHERWISE NOTED.


MEASURED NORMAL TO THE ϵ OF ABUTMENT. DIMENSIONS ARE TYPICAL FOR BOTH ABUTMENTS.

(A22) A506, B506 BARS SPACED @ 1'-0" CNTRS. MAY BE PLACED AFTER CONCRETE IS POURED BUT BEFORE INITIAL SET HAS TAKEN PLACE. (EMBED 1'-0" INTO CONC.)



END POST DETAILS

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-56-256			
DRAWN BY		BAS	PLANS CK'D JFK
SUPERSTRUCTURE		SHEET 8 OF 10	



CAMBER AND SLAB THICKNESS DIAGRAM


CAMBER SHOWN IS BASED ON 3 TIMES DEAD LOAD DEFLECTIONS. CAMBER SPANS AS SHOWN TO PROVIDE FOR DEAD LOAD DEFLECTION AND FUTURE CREEP. CAMBER DOES NOT INCLUDE ALLOWANCE FOR FORM SETTLEMENT. PARAPETS PLACED ON TOP OF THE SLAB SHALL BE POURED AFTER FALSEWORK HAS BEEN RELEASED, EXCEPT FOR STAGED CONSTRUCTION.

TO DETERMINE FALSEWORK ELEVATION AT EDGE OF SLAB, CROWN OR REFERENCE LINE FOLLOW THIS PROCEDURE:


LESS	TOP OF SLAB ELEVATION AT FINAL GRADE
PLUS	SLAB THICKNESS
PLUS	CAMBER
PLUS	FORM SETTLEMENT/DEFLECTION DUE TO PLACEMENT OF SLAB CONCRETE (TO BE COMPUTED BY THE CONTRACTOR)
EQUALS	TOP OF SLAB FALSEWORK ELEVATION

TOP OF SLAB ELEVATIONS

LOCATION	C/L BRG. W. ABUT.	1/10 PT.	2/10 PT.	3/10 PT.	4/10 PT.	5/10 PT.	6/10 PT.	7/10 PT.	8/10 PT.	9/10 PT.	C/L BRG. E. ABUT.
N. EDGE OF DECK	955.15	955.13	955.12	955.10	955.09	955.07	955.05	955.04	955.02	955.01	954.99
CROWN OF R/L	955.42	955.40	955.39	955.37	955.36	955.34	955.32	955.31	955.29	955.28	955.26
S. EDGE OF DECK	955.15	955.13	955.12	955.10	955.09	955.07	955.05	955.04	955.02	955.01	954.99



S505



S608

S609

BILL OF BARS

NOTE: THE FIRST OR FIRST TWO DIGITS OF THE BAR MARK SIGNIFIES THE BAR SIZE.

BAR MARK	COAT	NO. REQ'D.	LENGTH	BENT	BAR SERIES	LOCATION
S1001	X	58	42'-2"			SLAB BOTTOM LONGITUDINAL
S602	X	43	26'-2"			SLAB BOTTOM TRANSVERSE
S503	X	43	26'-2"			SLAB TOP TRANSVERSE
S504	X	21	42'-2"			SLAB TOP LONGITUDINAL
S505	X	54	7'-4"	X		ABUTMENT DIAPHRAGM STIRRUPS
S506	X	4	26'-2"			ABUTMENT DIAPHRAGM LONGITUDINAL
S607	X	48	6'-0"			SLAB TOP LONGIT. UNDER RAIL POSTS
S608	X	16	4'-8"	X		SLAB TOP LONGIT. UNDER RAIL END POSTS
S609	X	32	11'-3"	X		SLAB TOP HOOKS UNDER RAIL POSTS

SURVEY TOP OF SLAB ELEVATIONS

LOCATION	ABUTMENT	5/10 PT.	ABUTMENT
N. EDGE OF DECK			
CROWN OR R/L			
S. EDGE OF DECK			

PRIOR TO RELEASING SLAB FALSEWORK, TAKE TOP OF SLAB ELEVATIONS AT THE C/L OF ABUTMENTS, THE C/L OF PIERS AND AT 5/10 PTS. TO VERIFY CAMBER. TAKE ELEVATIONS ALONG GUTTER LINES AND CROWN OR R/L. RECORD THE ELEVATIONS IN THE ABOVE TABLE FOR THE "AS BUILT" PLANS.

NOTES

FILL IN THE TABLE OF "SURVEY TOP OF SLAB ELEVATIONS" FOR EACH SPAN ON AS BUILT PLANS.

TOP TRANSVERSE BARS IN SLAB SHALL BE SUPPORTED BY INDIVIDUAL BAR CHAIRS AT APPROXIMATELY 3'-0" CENTERS EACH WAY. BOTTOM LONGITUDINAL BARS SHALL BE SUPPORTED BY CONTINUOUS BAR CHAIRS AT APPROXIMATELY 4'-0" CENTERS.

ALL SLAB THICKNESS DIMENSIONS ARE MINIMUM. ANY TOLERANCES NECESSARY TO CORRECT CONSTRUCTION DISCREPANCIES ARE TO BE PLUS (+).



LOCATION MUST BE
SHOWN ON SHOP DRAWINGS



* ANCHOR BOLT ASSEMBLY MAY BE TACK WELDED, EITHER IN THE SHOP, OR IN THE FIELD AFTER THE ANCHOR PLATE IS PLACED.



NOTE: CONNECTIONS AT LOWER RAILS SHOWN.
CONNECTIONS AT TOP RAIL SIMILAR.

TYPICAL RAIL TO POST CONNECTIONS

- ## LEGEND
- (1) W6 x 25 WITH $1\frac{1}{8}$ " X $1\frac{1}{2}$ " HORIZ. SLOTS ON EACH SIDE OF POST FOR BOLT NO. 6. CUT BOTTOM OF POST TO MATCH CROSS SLOPE OF ROADWAY. PLACE POST VERTICAL. PLACE POSTS NORMAL TO GRADE LINE.
 - (2) PLATE $1\frac{1}{4}$ " x $11\frac{3}{4}$ " x $1'-8"$ WITH $1\frac{1}{16}$ " OVERSIZED HOLES FOR ANCHOR BOLTS NO. 3. WELD TO NO. 1 AS SHOWN.
 - (3) ASTM A449 - $1\frac{1}{8}$ " DIA. ANCHOR BOLTS WITH NUT AND HARDENED WASHER (ALL GALVANIZED). 5 REQ'D. PER POST. THREAD 3" AND PLACE NORMAL TO PLATE NO. 2. CHAMFER TOP OF BOLTS BEFORE THREADING. USE $1'-9"$ LONG IN ABUTMENT WINGS. AT POSTS ON CONCRETE SLAB SUPERSTRUCTURES WHERE THE SLAB THICKNESS IS $> 16"$ USE $1'-3"$ LONG. USE $10\frac{3}{4}$ " LONG AT ALL OTHER LOCATIONS. (AN EQUIVALENT THREADED ROD WITH NUTS AND HARDENED WASHERS MAY BE SUBSTITUTED FOR ANCHOR BOLTS IN WINGS IF REQ'D. FOR CONSTRUCTIBILITY.)
 - (4) $\frac{5}{8}$ " x $11"$ x $1'-8"$ ANCHOR PLATE (GALVANIZED) WITH $1\frac{1}{16}$ " DIA. HOLES FOR ANCHOR BOLTS NO. 3.
 - (4) TS 5 x 4 x 0.25 STRUCTURAL TUBING. ATTACH TO NO. 1 WITH NO. 6.
 - (5A) TS 5 x 5 x 0.25 STRUCTURAL TUBING. ATTACH TO NO. 1 WITH NO. 6.
 - (6) $\frac{7}{8}$ " DIA. A325 SLOTTED ROUND HEAD BOLT WITH NUT, $\frac{3}{16}$ " X $1\frac{5}{8}$ " X $1\frac{1}{8}$ " MIN. WASHER, AND LOCK WASHER (2 REQ'D. AT EACH RAIL TO POST LOCATION).
 - (7) SPLICE SLEEVE FABRICATED FROM $\frac{1}{4}$ " PLATE. PROVIDE "SLIDING FIT".
 - (8) $\frac{3}{8}$ " X $2\frac{5}{8}$ " X $2'-4"$ PLATE. 2 PER RAIL. USED IN NO. 5 & 5A.
 - (8A) $\frac{3}{8}$ " X $2\frac{5}{8}$ " X $2'-4"$ PLATE USED IN NO. 5, $\frac{3}{8}$ " X $3\frac{5}{8}$ " X $2'-4"$ PLATE USED IN NO. 5A. 2 PER RAIL.
 - (9) $\frac{7}{8}$ " DIA. A325 ROUND HEAD BOLT WITH NUT, WASHER, AND LOCK WASHER. USE $1\frac{1}{16}$ " x $1\frac{1}{4}$ " LONGIT. SLOTTED HOLES IN PLATE NO. 10A AT FIELD JOINTS AND $1\frac{5}{16}$ " x $2\frac{1}{4}$ " MIN. LONGIT. SLOTTED HOLES AT EXP. JOINTS IN PLATE NO. 8A. PROVIDE $1\frac{1}{16}$ " DIA. ROUND HOLES IN TUBES NO. 5 AND NO. 5A.


1. BID ITEM SHALL BE "RAILING TUBULAR TYPE M" WHICH INCLUDES ALL ITEMS SHOWN.
2. RAIL POST AND BASE PLATES SHALL CONFORM TO THE REQUIREMENTS OF ASTM A709 GRADE 50. HOLLOW RAILING STRUCTURAL TUBING SHALL CONFORM TO THE REQUIREMENTS OF ASTM A500 GRADE B OR C WITH A CERTIFIED FY = 50 KSI. ANCHOR PLATES, AND SPLICE TUBE PLATES SHALL CONFORM TO THE REQUIREMENTS OF ASTM A709 GRADE 36.
3. THE NUT SECURING THE POST BASE PLATE TO THE CONCRETE SHALL BE TIGHTENED TO A SNUG FIT AND GIVEN AN ADDITIONAL 1/2 TURN.
4. RAILS SHALL BE CONTINUOUS OVER A MINIMUM OF THREE (3) POSTS WITHOUT SPLICES WHERE POSSIBLE.
5. ENDS OF TUBE SECTIONS SHALL BE SAWED. GRIND SMOOTH EXPOSED EDGES. ALL CUT ENDS SHALL BE TRUE AND SMOOTH.
6. WELD IS THE SAME ON BOTH FLANGES. FLANGE WELD DOES NOT REQUIRE MAGNETIC PARTICLE TESTING.
7. FILL BOLT SLOT OPENINGS IN POST SHIMS AND PLATE NO. 2 AND CAULK AROUND PERIMETER OF PLATE NO. 2 WITH NON-STAINING GRAY NON-BITUMINOUS JOINT SEALER. STEEL POST SHIMS MAY BE USED UNDER POSTS WHERE REQ'D. FOR ALIGNMENT.
8. POST BASE PLATES SHALL BE FLAT WITH ALL SURFACES SMOOTH AND FREE FROM WARP AND ALL EDGES SMOOTH, STRAIGHT AND VERTICAL. ALL PLATE CUTS SHALL BE MACHINE OR MACHINE FLAME CUT.
9. ALL MATERIAL SHALL BE GALVANIZED AFTER FABRICATION. PRIOR TO GALVANIZING, ALL STEEL RAILING POSTS & STEEL TUBING SHALL BE GIVEN A NO. 6 BLAST CLEANING BY SSPC SPECIFICATIONS.



AT RAIL TO DECK CONNECTION



DETAIL



DIVISION 1 - DAVID DRIVE

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)		CUMULATIVE VOL (CY)		
			CUT	FILL	CUT	FILL	CUT 1.00	EXPANDED FILL 1.25	MASS ORDINATE
0+55.28	55.28	0.00	47.20	4.74	0	0	0	0	0
0+70.00	70.00	14.72	51.54	25.58	27	8	27	10	17
1+00.00	100.00	30.00	18.90	35.16	39	34	66	53	14
1+04.03	104.03	4.03	17.33	45.11	3	6	69	60	9

DIVISION 1 - DAVID DRIVE

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)		CUMULATIVE VOL (CY)		
			CUT	FILL	CUT	FILL	CUT 1.00	EXPANDED FILL 1.25	MASS ORDINATE
1+47.26	147.26	0.00	17.80	36.92	0	0	0	0	0
1+50.00	150.00	2.74	19.69	29.36	2	3	2	4	-2
1+70.00	170.00	20.00	29.86	7.32	18	14	20	21	-1
1+95.28	195.28	25.28	38.09	1.32	32	4	52	26	26

DIVISION 1 - TEMP ROAD


STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)		CUMULATIVE VOL (CY)		
			CUT	FILL	CUT	FILL	CUT 1.00	EXPANDED FILL 1.25	MASS ORDINATE
10+75.00	1075.00	0.00	0.00	23.01	0	0	0	0	0
11+00.00	1100.00	25.00	0.00	28.19	0	24	0	30	-30
11+25.00	1125.00	25.00	0.00	24.57	0	24	0	60	-60

DIVISION 1 - TEMP ROAD

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)		CUMULATIVE VOL (CY)		
			CUT	FILL	CUT	FILL	CUT 1.00	EXPANDED FILL 1.25	MASS ORDINATE
11+75.00	1175.00	0.00	0.00	50.02	0	0	0	0	0
12+00.00	1200.00	25.00	0.00	12.76	0	29	0	36	-36
12+25.00	1225.00	25.00	0.00	23.30	0	17	0	58	-58

NOTES:	
1 - CUT	CUT INCLUDES SALVAGED/UNUSABLE PAVEMENT MATERIAL
3 - FILL	DOES NOT INCLUDE UNUSABLE PAVEMENT EXC VOLUME
8 - MASS ORDINATE	IF MARSH AND EBS TO BE BACKFILLED WITH GRANULAR: [CUT - SALVAGED PAVT - ((FILL - EXPANDED ROCK) * FILL FACTOR)]

TEMPORARY STRUCTURE (STA 11+48)



PROJECT NO: 5738-00-74


HWY: DAVID DRIVE

COUNTY: SAUK


CROSS SECTIONS: TEMP ROAD


SHEET


E




PROJECT NO: 5738-00-74	HWY: DAVID DRIVE	COUNTY: SAUK	CROSS SECTIONS: TEMP ROAD	SHEET	E
------------------------	------------------	--------------	---------------------------	-------	---









Wisconsin Department of Transportation

Dedicated people creating transportation solutions
through innovation and exceptional service.

<http://www.dot.wisconsin.gov>

MAD
PROJECT ID:
WITH: 5738-00-74

5738-00-75

COUNTY:
SAUK

SEPTEMBER 2026

ORDER OF SHEETS

Section No.	1	Title
Section No.	2	Typical Sections and Details
Section No.	3	Estimate of Quantities
Section No.	3	Miscellaneous Quantities
Section No.	4	Right of Way Plat
Section No.	5	Plan and Profile
Section No.	6	Standard Detail Drawings
Section No.	7	Sign Plates
Section No.	8	Structure Plans
Section No.	9	Computer Earthwork Data
Section No.	9	Cross Sections

TOTAL SHEETS = 44




DESIGN DESIGNATION

A.A.D.T.	2026	=	<100
A.A.D.T.	2046	=	<100
D.H.V.		=	28
D.D.		=	60/40
T.		=	4%
DESIGN SPEED		=	25 MPH
ESALS		=	7,300

CONVENTIONAL SYMBOLS

PLAN	
CORPORATE LIMITS	
PROPERTY LINE	
LOT LINE	
LIMITED HIGHWAY EASEMENT	
EXISTING RIGHT OF WAY	
PROPOSED OR NEW R/W LINE	
SLOPE INTERCEPT	
REFERENCE LINE	
EXISTING CULVERT	
PROPOSED CULVERT (Box or Pipe)	
COMBUSTIBLE FLUIDS	
MARSH AREA	
WOODED OR SHRUB AREA	

PROFILE	
GRADE LINE	
ORIGINAL GROUND	
MARSH OR ROCK PROFILE (To be noted as such)	
SPECIAL DITCH	
GRADE ELEVATION	
CULVERT (Profile View)	
UTILITIES	
ELECTRIC	
FIBER OPTIC	
GAS	
SANITARY SEWER	
STORM SEWER	
TELEPHONE	
WATER	
UTILITY PEDESTAL	
POWER POLE	
TELEPHONE POLE	



STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

PLAN OF PROPOSED IMPROVEMENT

T WOODLAND, ROTT ROAD

LITTLE BARABOO RIVER, BRIDGE B-56-0257

LOC STR
SAUK COUNTY

STATE PROJECT NUMBER
5738-00-75



R-2-W R-3-W

END PROJECT
STA 4+00.00

STRUCTURE B-56-0257
STA 2+62.45 - STA 3+10.45

BEGIN PROJECT
STA 1+54
X= 517,065.203
Y= 276,418.149

LAYOUT
SCALE 0 1.0 MI

TOTAL NET LENGTH OF CENTERLINE = 0.046 MI

HORIZONTAL POSITIONS SHOWN ON THIS PLAN ARE WISCONSIN COORDINATE REFERENCE SYSTEM (WISCRS), SAUK COUNTY, NAD83 (2011), IN U.S. SURVEY FEET. POSITIONS SHOWN ARE GRID COORDINATES, GRID BEARINGS, AND GRID DISTANCES. GRID DISTANCES ARE THE SAME AS GROUND DISTANCES.

ELEVATIONS ARE REFERENCED TO NAVD 88 (2012). GPS DERIVED ELEVATIONS ARE BASED ON GEOID 12A.

STATE PROJECT	FEDERAL PROJECT	
	PROJECT	CONTRACT
5738-00-75	WISC 2026415	1

ACCEPTED FOR
TOWN OF WOODLAND
Edwin J. Woodner
Chairman
Date: 3-12-26
(Signature and Title of Official)

ORIGINAL PLANS PREPARED BY
TEAM ENGINEERING
WISCONSIN PROFESSIONAL ENGINEER
JEREMY F. KRACHEY
E-37258
WAUZEKA WIS.
Digitally signed by JEREMY F. KRACHEY, DN: c=US, E=J.KRACHEY@TEAMENGINEERING.COM, O=TEAM ENGINEERING, INC., CN=JEREMY F. KRACHEY, PE, Date: 2026.03.12 10:21:03-0500
DATE: _____
(Professional Engineer Signature)

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION
PREPARED BY
Surveyor: TEAM ENGINEERING INC.
Designer: TEAM ENGINEERING INC.
Project Manager: DELLA KOENIG, P.E.
Regional Examiner: SW REGION
Regional Supervisor: KYLE HEMP, P.E.

APPROVED FOR THE DEPARTMENT
DATE: _____
Digitally signed by Della Koenig P.E., Date: 2026.04.23 16:46:11-0500
E

LIST OF STANDARD ABBREVIATIONS

ABUT.	Abutment	JT	Joint	SEC	Section
AC	Acre	JCT	Junction	SHLDR	Shoulder
AGG.	Aggregate	LHF	Left-Hand Forward	SHR	Shrinkage
AH	Ahead	L	Length of Curve	SW	Sidewalk
<	Angle	LIN FT OR LF	Linear Foot	S	South
ASPH	Asphaltic	LC	Long Chord of Curve	SQ	Square
AVG.	Average	MH	Manhole	SF OR SQ FT	Square Feet
A.D.T.	Average Daily Traffic	MB	Mailbox	SY OR SQ YD	Square Yard
BAD	Base Aggregate Dense	ML OR M/L	Match Line	STD	Standard
BK.	Back	N	North	SDD	Standard Detail Drawings
BF	Back Fence	Y	North Grid Coordinate	STH	State Trunk Highways
B.M	Bench Mark	OAL	Overall Length	STA	Station
BR.	Bridge	OD	Outside Diameter	SS	Storm Sewer
C/L	Center Line	PLE	Permanent Limited Easement	SG	Subgrade
CC	Center to Center	PT	Point	SE	Superelevation
CTH	County Truck Highway	PC	Point of Curvature	SL OR S/L	Survey Line
CR.	Creek	PI	Point of Intersection	SV	Septic Vent
CY OR CU YD	Cubic Yard	PRC	Point of Reverse Curvature	T	Tangent
CP	Culvert Pipe	PT	Point of Tangency	TEL	Telephone
C & G	Curb and Gutter	POC	Point on Curve	TEMP	Temporary
D	Degree of Curve	POT	Point on Tangent	TI	Temporary Interest
DHV	Design Hour Volume	PVC	Polyvinyl Chloride	TLE	Temporary Limited Easement
DIA	Diameter	PCC	Portland Cement Concrete	t	Ton
E	East	LB	Pound	T OR TN	Town
X	East Grid Coordinate	PSI	Pounds Per Square Inch	TRANS	Transition
ELEC	Electric	PE	Private Entrance	TL OR T/L	Transit Line
EL OR ELEV	Elevation	R	Radius	T	Trucks (percent of)
ESALS	Equivalent Single Axle Loads	RR	Railroad	TYP	Typical
EBS	Excavation Below Subgrade	RL OR R/L	Reference Line	UNCL	Unclassified
FF	Face to Face	RP	Reference Point	UG	Underground Cable
FE	Field Entrance	RCCP	Reinforced Concrete Culvert Pipe	USH	United States Highway
F	Fill	REQD	Required	VAR	Variable
FG	Finished Grade	RES	Residence or Residential	V	Velocity or Design Speed
FL OR F/L	Flow Line	RW	Retaining Wall	VERT	Vertical
FT	Foot	RT	Right	VC	Vertical Curve
FTG	Footing	RHF	Right-Hand Forward	VOL	Volume
GN	Grid North	R/W	Right-of-Way	WM	Water Main
HT	Height	R	River	WV	Water Valve
CWT	Hundredweight	RD	Road	W	West
HYD	Hydrant	RDWY	Roadway	WB	Westbound
INL	Inlet	SALV	Salvaged	YD	Yard
ID	Inside Diameter	SAN S	Sanitary Sewer		
INV	Invert				
IP	Iron Pipe or Pin				
IRS	Iron Rod Set				

GENERAL NOTES

THE LOCATIONS OF EXISTING AND PROPOSED UTILITY INSTALLATIONS AS SHOWN ON THE PLAN ARE APPROXIMATE. THERE MAY BE OTHER UTILITY INSTALLATIONS WITHIN THE PROJECT AREA THAT ARE NOT SHOWN.

4-INCH ASPHALTIC SURFACE SHALL BE PLACED WITH A 2 1/4-INCH LOWER LAYER AND A 1 3/4-INCH UPPER LAYER.

UTILITIES

LAVALLE TELEPHONE COOPERATIVE
COMLN
JOSH LIEN
S1421 STATE HWY 33, P.O. BOX 28
LAVALLE, WI 53941
PHONE: 608-434-2796
EMAIL: joshl@rgtc.coop
EMAIL: johnb@rgtc.coop

VERNON ELECTRIC COOPERATIVE
ELCTY
COLE CARY
110 SAUGSTAD RD.
WESTBY, WI 54667
PHONE: 608-634-7472
EMAIL: ccary@vernonelectric.org

DESIGNER

TEAM ENGINEERING, INC.
210 GUARD STREET
WAUZEKA, WI 53826
ATTN: JEREMY KRACHEY, P.E.
PH: (608) 875-5075
jkrachey@teamenginc.com

DNR CONTACT

DEPARTMENT OF NATURAL RESOURCES
101 S. WEBSTER STREET
MADISON, WI 53703-7921
ATTN: ANDY BARTA
ENVIRONMENTAL ANALYSIS & REVIEW SPECIALIST
PH: (608) 235-2955
andrew.barta@wisconsin.gov

WISDOT CONTACT

ATTENTION: DELLA KOENIG, P.E.
LOCAL PROGRAM PROJECT MANAGER
WISDOT - SW REGION
2101 WRIGHT ST.
MADISON, WI 53704
WORK: (608) 246-7963
EMAIL: della.koenig@dot.wi.gov


RUNOFF COEFFICIENT TABLE


LAND USE:	HYDROLOGIC SOIL GROUP											
	A			B			C			D		
	SLOPE RANGE (PERCENT)			SLOPE RANGE (PERCENT)			SLOPE RANGE (PERCENT)			SLOPE RANGE (PERCENT)		
ROW CROPS:	0-2	2-6	6 & OVER	0-2	2-6	6 & OVER	0-2	2-6	6 & OVER	0-2	2-6	6 & OVER
	.08	.16	.22	.12	.20	.27	.15	.24	.33	.19	.28	.38
	.22	.30	.38	.26	.34	.44	.30	.37	.50	.34	.41	.56
MEDIAN STRIPTURF:	.19	.20	.24	.19	.22	.26	.20	.23	.30	.20	.25	.30
	.24	.26	.30	.25	.28	.33	.26	.30	.37	.27	.32	.40
SIDE SLOPETURF:			.25			.27			.28			.30
			.32			.34			.36			.38
PAVEMENT:												
ASPHALT:	.70 - .95											
CONCRETE:	.80 - .95											
BRICK:	.70 - .80											
DRIVES, WALKS:	.75 - .85											
ROOFS:	.75 - .95											
GRAVEL ROADS, SHOULDERS:	.40 - .60											


TOTAL PROJECT AREA = 1.0 ACRES
TOTAL AREA EXPECTED TO BE DISTURBED BY CONSTRUCTION ACTIVITIES = 1.0 ACRES



Dial  or (800)242-8511
www.DiggersHotline.com







PROJECT NO: 5738-00-75	HWY: ROTT ROAD	COUNTY: SAUK	PLAN DETAILS - EROSION CONTROL	SHEET	E
------------------------	----------------	--------------	--------------------------------	-------	---

Estimate Of Quantities By Plan Sets

5738-00-75					
Line	Item	Item Description	Unit	Total	Qty
0002	201.0105	Clearing	STA	2.000	2.000
0004	201.0205	Grubbing	STA	2.000	2.000
0008	203.0260	Removing Structure Over Waterway Minimal Debris (structure) 02. P-56-0948	EACH	1.000	1.000
0010	205.0100	Excavation Common	CY	56.000	56.000
0014	206.1001	Excavation for Structures Bridges (structure) 02. B-56-0257	EACH	1.000	1.000
0018	210.1500	Backfill Structure Type A	TON	290.000	290.000
0022	213.0100	Finishing Roadway (project) 02. 5738-00-75	EACH	1.000	1.000
0024	305.0110	Base Aggregate Dense 3/4-Inch	TON	50.000	50.000
0026	305.0120	Base Aggregate Dense 1 1/4-Inch	TON	160.000	160.000
0028	312.0110	Select Crushed Material	TON	140.000	140.000
0030	455.0605	Tack Coat	GAL	20.000	20.000
0032	465.0105	Asphaltic Surface	TON	60.000	60.000
0034	502.0100	Concrete Masonry Bridges	CY	155.000	155.000
0036	502.3200	Protective Surface Treatment	SY	209.000	209.000
0038	505.0400	Bar Steel Reinforcement HS Structures	LB	4,020.000	4,020.000
0040	505.0600	Bar Steel Reinforcement HS Coated Structures	LB	25,530.000	25,530.000
0042	513.4061	Railing Tubular Type M	LF	106.000	106.000
0044	516.0500	Rubberized Membrane Waterproofing	SY	10.000	10.000
0050	550.1100	Piling Steel HP 10-Inch x 42 Lb	LF	231.000	231.000
0052	606.0300	Riprap Heavy	CY	110.000	110.000
0054	612.0406	Pipe Underdrain Wrapped 6-Inch	LF	140.000	140.000
0058	618.0100	Maintenance and Repair of Haul Roads (project) 02. 5738-00-75	EACH	1.000	1.000
0060	619.1000	Mobilization	EACH	0.500	0.500
0062	624.0100	Water	MGAL	4.000	4.000
0064	625.0500	Salvaged Topsoil	SY	320.000	320.000
0066	627.0200	Mulching	SY	100.000	100.000
0072	628.1905	Mobilizations Erosion Control	EACH	3.000	3.000
0074	628.1910	Mobilizations Emergency Erosion Control	EACH	3.000	3.000
0076	628.2008	Erosion Mat Urban Class I Type B	SY	320.000	320.000
0078	628.6005	Turbidity Barriers	SY	250.000	250.000
0080	628.7504	Temporary Ditch Checks	LF	100.000	100.000
0082	629.0210	Fertilizer Type B	CWT	0.500	0.500
0084	630.0120	Seeding Mixture No. 20	LB	25.000	25.000
0086	630.0200	Seeding Temporary	LB	15.000	15.000
0090	630.0500	Seed Water	MGAL	10.000	10.000
0094	634.0614	Posts Wood 4x6-Inch x 14-FT	EACH	4.000	4.000
0096	637.2230	Signs Type II Reflective F	SF	12.000	12.000
0098	638.2602	Removing Signs Type II	EACH	6.000	6.000
0100	638.3000	Removing Small Sign Supports	EACH	6.000	6.000
0102	642.5001	Field Office Type B	EACH	0.500	0.500
0104	643.0300	Traffic Control Drums	DAY	600.000	600.000
0106	643.0420	Traffic Control Barricades Type III	DAY	480.000	480.000
0108	643.0705	Traffic Control Warning Lights Type A	DAY	600.000	600.000
0112	643.0900	Traffic Control Signs	DAY	600.000	600.000
0114	643.5000	Traffic Control	EACH	0.500	0.500
0116	645.0111	Geotextile Type DF Schedule A	SY	94.000	94.000
0118	645.0120	Geotextile Type HR	SY	224.000	224.000
0122	645.0220	Geogrid Type SR	SY	310.000	310.000
0124	650.4500	Construction Staking Subgrade	LF	98.000	98.000

Estimate Of Quantities By Plan Sets

5738-00-75					
Line	Item	Item Description	Unit	Total	Qty
0126	650.5000	Construction Staking Base	LF	98.000	98.000
0130	650.6501	Construction Staking Structure Layout (structure) 02. B-56-0257	EACH	1.000	1.000
0134	650.9911	Construction Staking Supplemental Control (project) 02. 5738-00-75	EACH	1.000	1.000
0136	650.9920	Construction Staking Slope Stakes	LF	98.000	98.000
0140	715.0502	Incentive Strength Concrete Structures	DOL	930.000	930.000
0142	999.2100.S	Installing and Maintaining Climbing Turtle Exclusion Fence	LF	350.000	350.000
0144	ASP.1T0A	On-the-Job Training Apprentice at \$5.00/HR	HRS	1,200.000	1,200.000
0146	ASP.1T0G	On-the-Job Training Graduate at \$5.00/HR	HRS	600.000	600.000

DIVISION	FROM/TO STATION	LOCATION	205.0100 COMMON EXCAVATION (1)	AVAILABLE MATERIAL (5)	UNEXPANDED FILL	EXPANDED FILL (13)	MASS ORDINATE +/- (14)	WASTE	208.0100 BORROW	COMMENT
			CUT (2)			FACTOR 1.25				
DIVISION 1										
ROTT ROAD SOUTH	2+12.45/2+50.00		28	28	22	28	1			
ROTT ROAD NORTH	3+25.00/3+60.00		28	28	18	23	6			
DIVISION 1 SUBTOTAL			56	56	40	50	6	6	0	
GRAND TOTAL			56	56	40	50	6	6	0	

NOTES:

- (1) COMMON EXCAVATION IS THE SUM OF THE CUT AND EBS EXCAVATION COLUMNS. ITEM NUMBER 205.0100
- (2) SALVAGED/UNSUALE PAVEMENT MATERIAL IS INCLUDED IN CUT.
- (5) AVAILABLE MATERIAL = CUT - SALVAGED/UNUSUALE PAVEMENT MATERIAL
- (13) EXPANDED FILL FACTOR = 1.25
- DEPENDING ON SELECTIONS:
- (14) THE MASS ORDINATE + OR - QTY CALCULATED FOR THE DIVISION . PLUS QUANTITY INDICATES AN EXCESS OF MATERIAL WITHIN THE DIVISION. MINUS INDICATES A SHORTAGE OF MATERIAL WITHIN THE DIVISION.
- (15) FACTORS USED TO COMPUTE ANTICIPATED WASTE AND THE COMPUTED WASTE VOLUME IDENTIFIED ARE FOR GENERAL INFORMATION ONLY.

CLEARING ITEMS

CATEGORY	STATION	TO	STATION	LOCATION	201.0105 CLEARING STA	201.0205 GRUBBING STA
0010	2+12.45	-	3+60.45	ROTT ROAD, LT & RT	2	2
0010				TOTAL 0010	2	2

BASE AGGREGATE ITEMS

CATEGORY	STATION	TO	STATION	LOCATION	305.0110 BASE AGGREGATE DENSE 3/4-INCH TON	305.0120 BASE AGGREGATE DENSE 1 1/4-INCH TON	312.0110 SELECT CRUSHED MATERIAL TON	624.0100 WATER MGAL	645.0220 GEOGRID TYPE SR SY	650.4500 CONSTRUCTION STAKING SUBGRADE LF	650.5000 CONSTRUCTION STAKING BASE LF	650.9920 CONSTRUCTION STAKING SLOPE STAKES LF
0010	2+12.45	-	2+61.17	ROTT ROAD	20	75	65	2	155	49	49	49
0010	3+11.71	-	3+60.45	ROTT ROAD	20	75	65	2	155	49	49	49
0010		-		UNDISTRIBUTED	10	10	10	-	-	-	-	-
				TOTAL 0010	50	160	140	4	310	98	98	98

ASPHALT ITEMS

CATEGORY	STATION	TO	STATION	LOCATION	455.0605 TACK COAT GAL	465.0105 ASPHALTIC SURFACE TON
0010	2+12.45	-	2+61.17	ROTT ROAD	8	25
0010	3+11.71	-	3+60.45	ROTT ROAD	8	25
0010		-		UNDISTRIBUTED	4	10
				TOTAL 0010	20	60

EROSION CONTROL ITEMS

						999.2100.S	628.1905	628.1910	628.6005	628.7504
						INSTALLING AND MAINTAINING CLIMBING TURTLE EXCLUSION FENCE	MOBILIZATIONS	MOBILIZATIONS EROSION CONTROL	EROSION CONTROL	TEMPORARY DITCH CHECKS
CATEGORY	STATION	TO	STATION	LOCATION	LF		EACH	EACH	TURBIDITY BARRIERS SY	LF
0010	2+12.45	-	2+61.17	ROTT ROAD	155		-	-	125	40
0010	3+11.71	-	3+60.45	ROTT ROAD	170		-	-	115	40
0010		-		UNDISTRIBUTED	25		3	3	10	20
TOTAL 0010					350		3	3	250	100

LANDSCAPING ITEMS

					625.0500	627.0200	628.2008	629.0210	630.0120	630.0200	630.0500
					SALVAGED TOPSOIL	MULCHING	EROSION MAT URBAN CLASS I TYPE B	FERTILIZER TYPE B	SEEDING MIXTURE NO. 20	SEEDING TEMPORARY	SEED WATER
CATEGORY	STATION	TO	STATION	LOCATION	SY	SY	SY	CWT	LB	LB	MGAL
0010	2+12.45	-	2+61.17	ROTT ROAD	155	-	155	0.2	10	6	5
0010	3+11.71	-	3+60.45	ROTT ROAD	139	-	139	0.2	10	6	5
0010				UNDISTRIBUTED	26	100	26	0.1	5	3	-
TOTAL 0010					320	100	320	0.5	25	15	10



SIGN ITEMS

						634.0614	637.2230	638.2602	638.3000	
						POSTS WOOD			REMOVING	
						4X6-INCH X 14-	SIGNS TYPE II	REMOVING	SMALL SIGN	
						FT	REFLECTIVE F	SIGNS TYPE II	SUPPORTS	
CATEGORY	STATION	LOCATION	SIGN CODE	SIZE	SIGN NO	EACH	SF	EACH	EACH	REMARKS
0010	2+50	RT	-	-	5R	-	-	1	1	WEIGHT LIMIT SIGN
0010	2+55	LT	W5-52L	12" x 36"	1/1R	1	3	1	1	
0010	2+58	RT	W5-52R	12" x 36"	2/2R	1	3	1	1	
0010	3+12	LT	W5-52L	12" x 36"	3/3R	1	3	1	1	
0010	3+17	RT	W5-52R	12" x 36"	4/4R	1	3	1	1	
0010	3+80	LT	-	-	6R	-	-	1	1	WEIGHT LIMIT SIGN
TOTAL 0010						4	12	6	6	

TRAFFIC CONTROL

			643.0300		643.0420		643.0705		643.0900	
			TRAFFIC CONTROL DRUMS		TRAFFIC CONTROL BARRICADES TYPE III		TRAFFIC CONTROL WARNING LIGHTS TYPE A		TRAFFIC CONTROL SIGNS	
CATEGORY	DESCRIPTION	NO. OF DAYS	NO.	DAY	NO.	DAY	NO.	DAY	NO.	DAY
0010	CLOSURE OF ROTT ROAD	60	10	600	8	480	10	600	10	600
0010										
		TOTAL 0010		600		480		600		600


BENCH MARKS			
NO.	STATION	ELEV.	DESCRIPTION
BM 1	2+96.78	973.58	CHISELED X ON STRUCTURE
BM 2	1+73.12	971.13	3/4" REBAR
BM 3	4+30.95	970.57	3/4" REBAR



PROJECT NO: 5738-00-75	HWY: ROTT ROAD	COUNTY: SAUK	PLAN AND PROFILE: ROTT ROAD	SHEET	E
------------------------	----------------	--------------	-----------------------------	-------	---

Standard Detail Drawing List



08E08-03	TYPICAL INSTALLATIONS OF EROSION BALES / TEMPORARY DITCH CHECKS
08E09-06	SILT FENCE
08E11-02	TURBIDITY BARRIER
12A03-10	NAME PLATE (STRUCTURES)
13C19-03	HMA LONGITUDINAL JOINTS
14D01-01	TURTLE EXCLUSION FENCE CLIMBING TURTLE
15C02-10A	BARRICADES AND SIGNS FOR MAINLINE CLOSURES
15C02-10B	BARRICADES AND SIGNS FOR VARIOUS CLOSURES
15C06-12	SIGNING & MARKING FOR TWO LANE BRIDGES
15C11-11B	CHANNELIZING DEVICES DRUMS, CONES, BARRICADES AND VERTICAL PANELS



GENERAL NOTES

DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.

- ① TEMPORARY DITCH CHECKS EITHER EROSION BALES OR MANUFACTURED SHALL BE PAID FOR UNDER THE BID ITEM OF TEMPORARY DITCH CHECK. THE DEPARTMENT WILL NOT PAY FOR TEMPORARY DITCH CHECKS CONSTRUCTED OF A SINGLE ROW OF EROSION BALES.

TYPICAL INSTALLATIONS OF
EROSION BALES / TEMPORARY
DITCH CHECKS

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED


6/04/02
DATE

FHWA


/S/ Beth Canestra
CHIEF ROADWAY DEVELOPMENT ENGINEER



- ① HORIZONTAL BRACE REQUIRED WITH 2" X 4" WOODEN FRAME OR EQUIVALENT AT TOP OF POSTS.
- ② FOR MANUAL INSTALLATIONS THE TRENCH SHALL BE A MINIMUM OF 4" WIDE & 6" DEEP TO BURY AND ANCHOR THE GEOTEXTILE FABRIC. FOLD MATERIAL TO FIT TRENCH AND BACKFILL & COMPACT TRENCH WITH EXCAVATED SOIL.
- ③ WOOD POSTS SHALL BE A MINIMUM SIZE OF 1 1/8" X 1 1/8" OF OAK OR HICKORY.
- ④ SILT FENCE TO EXTEND ACROSS THE TOP OF THE PIPE.
- ⑤ CONSTRUCT SILT FENCE FROM A CONTINUOUS ROLL IF POSSIBLE BY CUTTING LENGTHS TO AVOID JOINTS. IF A JOINT IS NECESSARY USE ONE OF THE FOLLOWING TWO METHODS; A) OVERLAP THE END POSTS AND TWIST, OR ROTATE, AT LEAST 180 DEGREES, B) HOOK THE END OF EACH SILT FENCE LENGTH.




SILT FENCE	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED <u>4-29-05</u> <u>DATE</u>	<u>/S/ Beth Canestra</u> CHIEF ROADWAY DEVELOPMENT ENGINEER



SECTION B - B


TURBIDITY BARRIER - FLOAT ALTERNATIVE
CAUTION - SEE NOTE 6




SECTION A - A

TURBIDITY BARRIER - STANDARD POST INSTALLATION

TURBIDITY BARRIER PLACEMENT DETAILS



PLAN VIEW




PLAN VIEW

GENERAL NOTES


DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.

TURBIDITY BARRIER MAY BE REMOVED AT THE ENGINEERS DISCRETION, WHEN PERMANENT EROSION CONTROL MEASURES HAVE BEEN ESTABLISHED.

- 1 DRIVEN STEEL POSTS, PIPES, OR CHANNELS. LENGTH SHALL BE SUFFICIENT TO SECURELY SUPPORT BARRIER AT HIGH WATER ELEVATIONS.
- 2 SAND BAGS TO BE USED AS ADDITIONAL BALLAST WHEN ORDERED BY THE ENGINEER TO MEET ADVERSE FIELD CONDITIONS. SPACE AS APPROPRIATE FOR SITE CONDITIONS.
- 3 WHEN BARRIER HEIGHT "H" EXCEEDS 8 FEET, POST SPACING MAY NEED TO BE DECREASED.
- 4 IN WATERWAYS SUBJECT TO FLUCTUATING WATER ELEVATIONS, PROVISIONS SHOULD BE MADE TO ALLOW THE WATER TO EQUALIZE ON EACH SIDE OF THE BARRIER. THIS MAY BE ACCOMPLISHED BY LEAVING A PORTION OF THE BARRIER OPEN ON THE UPSTREAM END.
- 5 ESTIMATED HIGH WATER ELEVATION DURING CONSTRUCTION PERIOD. MINIMUM BARRIER HEIGHT SHALL BE 2' GREATER THAN EITHER THE Q2 ELEVATION OR THE ESTIMATED HIGH WATER ELEVATION DURING CONSTRUCTION, WHICHEVER IS GREATER.
- 6 FLOAT ALTERNATIVE WILL ONLY BE ALLOWED WITH WRITTEN APPROVAL OF THE ENGINEER, AND IS MEANT FOR LOCATIONS WHERE BEDROCK PREVENTS THE INSTALLATION OF POSTS.
- 7 ALLOW SUFFICIENT SLACK VERTICALLY AND HORIZONTALLY SO THAT SEDIMENT BUILD UP WILL NOT SEPARATE OR LOWER THE TURBIDITY BARRIER.
- 8 USE AS DIRECTED BY COAST GUARD OR DNR PERMIT WHEN WORKING IN NAVIGABLE WATERWAYS.



PLAN VIEW




SECTION C - C

TURBIDITY BARRIER DETAIL SHOWING
TYPICAL PLACEMENT AT STRUCTURES


TURBIDITY BARRIER

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
6/4/02 DATE /S/ Beth Cannestra
DATE CHIEF ROADWAY DEVELOPMENT
ENGINEER
FHWA



TYPICAL NAME PLATE
(BRIDGES, CULVERTS, AND RETAINING WALLS)




**NUMBERING DESIGNATION
MULTI-UNIT STRUCTURES**

GENERAL NOTES


NAME PLATES TO BE INSTALLED ON BRIDGES, CULVERTS, AND RETAINING WALLS SHALL CONFORM TO THE REQUIREMENTS OF SECTION 502.3.11 OF THE STANDARD SPECIFICATIONS.

THE BRIDGE NUMBER AND YEAR BUILT SHOWN ON THIS DRAWING ARE EXAMPLES ONLY. SEE CONSTRUCTION PLANS FOR INDIVIDUAL NUMBERING AND YEAR BUILT.

- ① EPOXY RESIN SHALL BE FROM AN APPROVED MANUFACTURER AND USED IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.
- ② REHABILITATION OF AN EXISTING STRUCTURE SHOULD USE THE DATE OF ORIGINAL STRUCTURE CONSTRUCTION.




SECTION A-A



ALTERNATE LUG

- ① ADHERE ANCHOR LUG TO PRECAST RETAINING WALL WITH EPOXY RESIN.



ALTERNATE LUG
(FOR ATTACHMENT TO PRECAST STRUCTURES)

**NAME PLATE
(STRUCTURES)**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED


3/26/10
DATE

FHWA


/S/ Scot Becker
CHIEF STRUCTURAL DEVELOPMENT ENGINEER



TYPICAL PAVEMENT CROSS SECTION
NOTCHED WEDGE JOINT



TYPICAL PAVEMENT CROSS SECTION
VERTICAL JOINT



TYPICAL PAVEMENT CROSS SECTION
VERTICAL JOINT (MILLED)

GENERAL NOTES


IN ADDITION TO THE DETAILS PROVIDED IN THIS DRAWING, CONFORM TO STANDARD SPECIFICATION 450.3.2.8 FOR WHEN A NOTCHED WEDGE JOINT IS REQUIRED AND FOR GENERAL JOINT CONSTRUCTION REQUIREMENTS.

FOR ALL LONGITUDINAL JOINTS, ENSURE THE PAVER SCREED OVERLAPS THE PREVIOUSLY PLACED PAVEMENT BY 1" ± 0.5" AND THE HOT SIDE OF THE JOINT REMAINS HIGHER THAN THE COLD SIDE BY APPROXIMATELY 0.1" AFTER FINAL COMPACTION. (IT WILL BE FLUSH WHEN PAVING IN ECHELON.)

ONLY REMOVE THE LONGITUDINAL NOTCHED WEDGE JOINT FOR SMA PAVEMENT OR AS DIRECTED BY THE ENGINEER TO ADDRESS SPECIFIC LENGTHS OF JOINT DAMAGED BY TRAFFIC.

WHEN MILLING BACK OR REMOVING ANY LONGITUDINAL JOINT, LIMIT THE MATERIAL REMOVED TO 2" FROM THE TOP NOTCH OR FROM THE VERTICAL JOINT EDGE ON THE COLD SIDE OF THE JOINT.

USE LONGITUDINAL MILLED JOINT AS PLANS SHOW OR THE AS THE ENGINEER DIRECTS.



OVERLAP DETAIL (TYPICAL)


HMA LONGITUDINAL JOINTS

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
November 2020 /S/ Steven Hefel
DATE HMA PAVEMENT ENGINEER
FHWA


GENERAL NOTES:

- 1. WHERE SILT FENCE IS REQUIRED, IT SHALL BE PLACED ON THE CONSTRUCTION SIDE OF THE EXCLUSION FENCING, OR COMBINED WITH THE EXCLUSION FENCING AS ALLOWED IN THE SPECIFICATIONS. STAKES ON THIS DETAIL ARE OPPOSITE OF STANDARD SILT FENCE FOR SEDIMENT CONTROL.
 - 2. PLACE TURNAROUNDS AT ALL TERMINI ENDS OF THE EXCLUSION FENCING.
 - 3. IF TEMPORARY ACCESS POINTS ARE NEEDED DURING CONSTRUCTION THAT REQUIRE OPENINGS IN THE EXCLUSION FENCING, ACCESS OPENINGS SHOULD BE TIGHTLY SECURED WITH BALES OF HAY OR STRAW WHENEVER CONSTRUCTION RELATED ACTIVITIES ARE NOT OCCURRING. REINSTALL EXCLUSION FENCING WHEN THE WORK REQUIRING THE TEMPORARY ACCESS OPENING IS COMPLETED.
 - 4. THE FENCE CAP MAY BE A 6" UNDER DRAIN PIPE, SLIT DOWN THE CENTER AND PLACED OVER THE FENCE. COMMERCIALY AVAILABLE SAFETY CAPS WITH A LIP MAY BE USED. OTHER DNR APPROVED METHODS TO PREVENT TURTLES FROM PASSING OVER THE TOP OF THE FENCE MAY BE USED.
- SECURELY FASTEN THE CAP TO PREVENT IT FROM BEING DISLODGED.




PLAN VIEW

CLIMBING TURTLE EXCLUSION FENCE DETAIL



PLAN VIEW




FRONT VIEW

CLIMBING TURTLE FENCE RELIEF DETAIL

TURTLE EXCLUSION FENCE
CLIMBING TURTLE

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
AUGUST 2025 /S/ ALYSSA BARRETTE
DATE CHIEF STATEWIDE ENVIRONMENTAL SERVICES
FHWA BUREAU OF TECHNICAL SERVICES



SPEED LIMIT (MPH)	"STOP AHEAD" ADVANCE WARNING DISTANCE (FT)
25	200
30	200
35	350
40	350
45	500
50	550
55	750


SEE SDD 15C2-SHEET "b"
FOR GENERAL NOTES
AND FOOTNOTES ① THROUGH ⑦

	SIGN ON PERMANENT SUPPORT
	TYPE III BARRICADE
	TYPE III BARRICADE WITH ATTACHED SIGN
	TYPE "A" WARNING LIGHT (FLASHING)
	WORK AREA
	FLAGS, 16" X 16" MIN. (ORANGE)


-  M4 - 8
 M3 - X
 OR  OR 
M1 - 4 M1 - 6 M1 - 5A
 OR 
M05 - 1 M06 - 1



APPROVED
November 2025 /S/ Andrew Heidtke
DATE WORK ZONE ENGINEER



DETAIL D
ROAD CLOSURE BARRICADE DETAIL
APPROACH VIEW



DETAIL E
LANE CLOSURE BARRICADE DETAIL
APPROACH VIEW

SEE SDD 15C2 - SHEET "a" FOR LEGEND

GENERAL NOTES

THE EXACT NUMBER, LOCATION, AND SPACING OF ALL SIGNS AND BARRICADES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.

ANY SIGNS TEMPORARY OR EXISTING, WHICH CONFLICT WITH TRAFFIC CONTROL "IN USE", SHALL BE REMOVED OR COVERED AS NEEDED AND AS APPROVED BY THE ENGINEER.

THE SPACING BETWEEN TRAFFIC CONTROL SIGNS SHOULD BE ADJUSTED TO NOT CONFLICT WITH AND SHOULD PROVIDE A DESIRABLE MINIMUM OF 200 FEET CLEARANCE TO EXISTING SIGNS THAT WILL REMAIN IN PLACE.

BARRICADES THAT MUST BE MOVED FOR A WORK OPERATION SHALL BE IMMEDIATELY RE-ESTABLISHED UPON COMPLETION OF THE OPERATION, OR FOR CONTINUING OPERATIONS, AT THE END OF EACH WORKING DAY.

SIGNS THAT WILL BE IN PLACE LESS THAN 7 CONTINUOUS DAYS AND NIGHTS MAY BE MOUNTED ON PORTABLE SUPPORTS.

ALL TYPE III BARRICADES SHALL HAVE RAILS REFLECTORIZED ON BOTH FACES. STRIPES SHALL BE PROPERLY SLOPED DOWN TOWARD THE TRAFFIC SIDE OR AS SHOWN IN THE ROAD CLOSURE BARRICADE DETAIL "D" FOR FULL ROAD CLOSURES.

TYPE "A" LOW - INTENSITY FLASHING WARNING LIGHTS SHALL BE VISIBLE ON BOTH SIDES OF THE BARRICADE.

PARTIAL NUMBERS ON SIGNS SHALL BE DISPLAYED AS A WHOLE NUMBER(AS NEEDED) FOLLOWED BY A FRACTION. SIGNS SHALL NOT DISPLAY NUMBERS IN DECIMAL FORM.


"WO" AND "MO" SIGNS ARE THE SAME AS "W" AND "M" SIGNS EXCEPT THE BACKGROUND IS ORANGE.

ALL SIGNS SHALL BE 48" X 48" UNLESS OTHERWISE NOTED BELOW:
R11 - 2 SHALL BE 48" X 30"
R11 - 3 SHALL, R11 - 4 AND R10 - 61 SHALL BE 60 " X 30"
M4 - 9 SHALL BE 30" X 24"
M3 - X SHALL BE 24" X 12" (36" X 18" IF NEEDED TO MATCH EXISTING SIGNS)
M4 - 8 SHALL BE 24" X 12" (36" X 18" IF NEEDED TO MATCH EXISTING SIGNS)
M1 - 4, M1 - 5A AND M1 - 6 SHALL BE 24" X 24" (36" X 36" IF NEEDED TO MATCH EXISTING SIGNS)
MO5 - 1 AND MO6 - 1 SHALL BE 21" X 21" (30" X 30" IF NEEDED TO MATCH EXISTING SIGNS)
D1 - X SHALL BE AS SHOWN ON SPECIFIC PROJECT SIGNING DETAIL SHEETS.
R1 - 1 SHALL BE 36" X 36"


SIGNS PLACED ON TYPE III BARRICADES THAT ARE SIZES OTHER THAN 48"X30" SHALL HAVE A CORRUGATED POLYPROPYLENE OR POLYETHYLENE PLASTIC SIGN BASE.

- ① TWO WARNING LIGHTS SHALL BE PROVIDED ON THE CENTER BARRICADE AND A MINIMUM OF ONE WARNING LIGHT SHALL BE PROVIDED ON EACH OF THE OTHER BARRICADES WITHIN THE ROADWAY LIMITS. SPACING OF THE WARNING LIGHTS SHALL BE UNIFORM TO THE EDGE OF ROADWAY AS SHOWN (APPROX. 8 FOOT LIGHT SPACING).
- ② THESE SIGNS AND BARRICADES ARE NOT REQUIRED IF ROAD CLOSURE BEGINS AT AN INTERSECTION.
- ③ FOR ROAD CLOSURE WITHOUT LOCAL ACCESS TO PROJECT, SEE ROAD CLOSURE BARRICADE DETAIL "D".
- ④ FOR ROAD CLOSURE WITH LOCAL ACCESS TO PROJECT, SEE ROAD CLOSURE BARRICADE DETAIL "E".
- ⑤ FOR BRIDGE OR CULVERT REPLACEMENTS, SUBSTITUTE "BRIDGE OUT" INSTEAD OF "ROAD CLOSED" ON R11 - 2 AND R11 - 3 SIGNS.
- ⑥ INSTALL DETOUR AND COMMUNITY GUIDE SIGNS AND ARROWS ONLY IF SPECIFIED IN THE CONTRACT. IF THERE ARE EXISTING ROUTE MARKER ASSEMBLIES THAT WILL REMAIN IN PLACE, ADJUST THE LOCATION OF THE DETOUR ROUTE SIGNS TO CORRESPOND WITH THE EXISTING ASSEMBLIES. MODIFY EXISTING SIGNS WHERE POSSIBLE. SEE SPECIFIC PROJECT DETOUR SIGNING DETAIL SHEETS. IF DETOUR SIGNS ARE BEING INSTALLED BY OTHERS, PLACE THE CONTRACTED TRAFFIC CONTROL SIGNS TO ALLOW FOR PLACEMENT OF ALL WARNING, DETOUR AND GUIDE SIGNS AS SHOWN.
- ⑦ "EAST" CARDINAL DIRECTION MARKERS AND RIGHT TURN ARROWS ARE SHOWN. USE OTHER CARDINAL DIRECTIONS AND ARROWS AS APPROPRIATE.

BARRICADES AND SIGNS FOR VARIOUS CLOSURES	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED November 2025 DATE	/S/ Andrew Heidtke WORK ZONE ENGINEER
FHWA	



SITUATION 1
WARRANTING CRITERIA:
BRIDGE WIDTH IS AT LEAST 16 FEET BUT LESS THAN 24 FEET.



SITUATION 2
WARRANTING CRITERIA:
1. BRIDGE WIDTH IS AT LEAST 24 FEET AND
2. BRIDGE SHOULDER WIDTH IS LESS THAN 6 FEET

GENERAL NOTES

DETAILS OF TRAFFIC CONTROL DEVICES AND INSTALLATION NOT SHOWN ON THE DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS, THE SPECIAL PROVISIONS, AND THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.

LOCATE W5-52 SIGN POST(S) BEHIND GUARDRAIL WHEN PRESENT.

PLACE THE EDGE OF THE W5-52 SIGN IN LINE WITH FACE OF CURB OR PARAPET.

ON BRIDGE ONLY PROJECTS, PLACE 300 FEET OF EDGELINE.

OMIT EDGELINES ON ROADWAYS WITHOUT EXISTING EDGELINES.

① OMIT ON ONE-WAY TRAVELED WAYS.

LEGEND

⊙ SIGN ON PERMANENT SUPPORT

➡ DIRECTION OF TRAFFIC

DISTANCE TABLE

POSTED OR 85TH PERCENTILE SPEED	DISTANCE "A"
25	150'
30	200'
35	250'
40	300'
45	400'
50	550'
55	700'


**SIGNING AND MARKING
FOR TWO LANE BRIDGES**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


APPROVED
May 2023
DATE

/S/ Jeannie Silver
Statewide Pavement Marking Engineer


FHWA




DRUM
BALLAST WIDTHS
RANGE FROM 24"-36"



42" CONE
DO NOT USE IN TAPERS
½ SPACING OF DRUMS
BALLAST WIDTHS
RANGE FROM 14"-20"



VERTICAL PANEL
THE STRIPES SHALL SLOPE DOWNWARD TO
THE TRAFFIC SIDE FOR CHANNELIZATION.



TYPE III BARRICADE
IF SIGN MOUNTED, DO NOT COVER MORE THAN 50% OF THE TOP
TWO RAILS OR 33% OF THE TOTAL AREA OF THE THREE RAILS.
* IF USED FOR A PERMANENT APPLICATION USE RED SHEETING.

GENERAL NOTES


- ① REFLECTIVE SHEETING SHALL FOLLOW THE REQUIREMENTS IN THE APPROVED PRODUCTS LISTING FOR SIGN SHEETING.
- ② LOCATION OF WARNING LIGHTS WHEN SHOWN ON THE PLAN.

**CHANNELIZING DEVICES
DRUMS, CONES, BARRICADES
AND VERTICAL PANELS**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
February 2026 /S/ Andrew Heidtke
DATE WORK ZONE ENGINEER


FHWA



ELEVATION VIEW


DETAIL OF WOOD 4 X 6 SIGN POST IN BOX-OUT

- NOTES: 1. ALL MATERIAL TO BE APPROVED BY ENGINEER PRIOR TO INSTALLATION
2. SEE SIGN PLATE A4-8 FOR SIGN HARDWARE REQUIREMENTS
3. 18 INCH X 18 INCH SQUARE BOX-OUTS MAY BE USED FOR INSTALLATIONS IN EXISTING CONCRETE OR ASPHALT LOCATIONS.



ELEVATION VIEW

DETAIL OF STEEL 2 X 2 SIGN POST IN BOX-OUT



PLAN VIEW

FOR NEW CONCRETE/ASPHALT INSTALLATIONS

SIGN POST
BOX-OUTS
A4-3B

WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Rauch*
for State Traffic Engineer

DATE 1/27/14 PLATE NO. A4-3B.1

PROJECT NO:

HWY:

COUNTY:

SHEET NO:

E

GENERAL NOTES


- For 3 or 4 post installations, individual post spacing shall be greater than 3'-6".
- See tables below for required number of posts.
- For expressways and freeways, mounting height is 7'-3" (±) 3" or 6'-3" (±) 3" depending upon existence of sub-sign.
- The (±) tolerance for mounting height is 3 inches.
- J-Assemblies are considered to be one sign for mounting height.
- Offset distance shall be consistent with existing signs or consistent throughout length of project.
- Folding signs shall be mounted at a height of 5'-3" (±) 3" or as directed by the engineer.
- The Double Arrow sign (W12-1) shall be mounted at a height of 2'-3" (±) 3". The Chevron sign (W1-8), Roundabout Chevron panel (R6-4B), Clearance Markers (W5-52), Mile Markers (D10 series), In Road Object Markers (W5-54) & End of Road Markers (W5-56) shall be mounted at a height of 4'-3" (±) 3".

* 6 feet from edge of a paved shoulder or 12 feet from the edge of pavement (edge line location) or 2 feet from outside edge of gravel, whichever is greater unless directed by project engineer.



** The existence of curb and gutter does not in itself mandate the vertical clearance illustrated. That height is typically measured where there is sidewalk adjacent to the roadway or parking is permitted. In the absence of sidewalk vertical clearance is measured from the top of the curb. Offset of signs is measured from the flow line.

*** See A4-3 sign plate for signs 4' or less in width and less than 20 S.F. in area.


URBAN AREA




RURAL AREA (See Note 3)



2' Min - 4' Max (See Note 6)



48" DIAMOND WARNING SIGN



48" DIAMOND WARNING SIGN

SIGN SHAPE OTHER THAN DIAMOND (TWO POSTS REQUIRED)	
L	E
Greater than 48" Less than 60"	12"
60" to 108"	L/5

SIGN SHAPE OTHER THAN DIAMOND (THREE POSTS REQUIRED)	
L	E
Greater than 108" to 144"	12"

POST EMBEDMENT DEPTH



Area of Sign Installation (Sq.Ft.)	D (Min)
20 or Less	4'
Greater than 20	5'

TYPICAL INSTALLATION
OF TYPE II SIGNS
ON MULTIPLE POSTS

WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Rauch*
for State Traffic Engineer

DATE 12/6/23 PLATE NO. A4-4.16



Nuts, bolts and lags used for mounting signs shall have hexagonal heads and shall be either :

- a. Hot dip galvanized in accordance with ASTM Designation: A 153, Class D, or SC 3
- b. Electro-galvanized in accordance with ASTM Designation : B 633, TYPE III, SC 3.


Threads on bolts and nuts shall be manufactured with sufficient allowance for the cadmium plate or galvanized coating to permit the nuts to run freely on the bolts.

- STRINGER BOLTING TO ALUMINUM SIGNS (SEE SIGN PLATE A4-18)
- MACHINE BOLTS - $\frac{5}{16}$ " X 1-3/4" Length w/ lock nuts
- WOOD POSTS (4" x 6")
- LAG SCREWS - $\frac{3}{8}$ " X 3" (NO STRINGERS ON BACK OF SIGN)
 $\frac{3}{8}$ " X 4" (STRINGERS ON BACK OF SIGN)
- SQUARE STEEL POSTS (2" x 2")
- MACHINE BOLTS - $\frac{3}{8}$ " X 3-1/4" Length w/ nuts (NO STRINGER ON BACK OF SIGN)
 $\frac{3}{8}$ " X 5" Length w/ nuts (STRINGERS ON BACK OF SIGN)
- RIVETS - $\frac{9}{32}$ " (6605-9-6) BULB-TITE, TRI-FOLD, ALUMINUM BODY/MANDREL
O.D. FLANGE .720-.765 INCH, GRIP RANGE .042-.375 INCH
- WASHERS (ALL POSTS) -
- 1-1/4" O.D. X $\frac{3}{8}$ " I.D. X $\frac{1}{16}$ " STEEL
 - 1-1/4" O.D. X $\frac{3}{8}$ " I.D. X .080 NYLON


* Two different fastening systems are shown for illustration purposes. On any individual sign, either one or the other system shall be used. Actual number of fasteners per sign varies with the sign area, but normally there are two. For a single post installation, all signs greater than 9 sq. ft. require the use of 3 fasteners.

ATTACHMENT OF SIGNS TO POSTS	
WISCONSIN DEPT OF TRANSPORTATION	
APPROVED	<i>Matthew R. Rauch</i> For State Traffic Engineer
DATE 4/1/2020	PLATE NO. A4-8.9



TELESCOPIC TUBING ANCHORS
TWO PIECE SYSTEM



DETAIL OF TUBULAR STEEL SIGN POST
(IN POURED CONCRETE OR ASPHALT)



DETAIL OF TUBULAR STEEL SIGN POST
(IN LOCATIONS OTHER THAN POURED CONCRETE OR ASPHALT)



Area of Sign Installation (Sq. Ft.)	Number of Required Posts
9 or less	1
Greater than 9 less than or equal to 18	2
Greater than 18 less than or equal to 27	3



Signs wider than 3 feet or larger than 9 sq. ft shall be mounted on multiple posts (see above table).

TUBULAR STEEL
SIGN POST
A4-9

WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Rauch*
for State Traffic Engineer

DATE 2/05/15 PLATE NO. A4-9.9



SIDE VIEW

GENERAL NOTES

1. All 4 x 6 Wood Posts shall be modified by having two 1 1/2" diameter holes drilled perpendicular to the roadway centerline.

4 X 6 WOOD POST MODIFICATIONS

WISCONSIN DEPT OF TRANSPORTATION

APPROVED

Chester J. Spang
for State Traffic Engineer

DATE 3/27/97

PLATE NO. A4-11.2

PROJECT NO:

HWY:




COUNTY:

SHEET NO:


E

BANDING

SINGLE SIGN



WASHER PLACEMENT




WASHERS (ALL POSTS) -
1-1/4" O.D. X 3/8" I.D. X 1/16" STEEL
1-1/4" O.D. X 3/8" I.D. X .080 NYLON
FOR ALL TYPE H SIGNS


GENERAL NOTES

1. Any sign over 3 feet in width shall use the V-Block banding method. See A5-10 standard plate.
2. Signs 3 feet or greater in height shall have three bracket bands installed. Signs less than 3 feet in height shall have two bracket bands installed.
3. Banding and assembly bracket shall be stainless steel. All bands shall be 3/4" in width and 0.025" thickness.
4. ALL SIGN MOUNTING BOLTS AND WASHERS SHALL BE EITHER:
 - a. Hot dip or mechanically galvanized in accordance with ASTM Designation: A 153, Class D
 - b. Electro-galvanized in accordance with ASTM designation: B 633, Type III, SC 3

"J" ASSEMBLY



CHANNEL
SEE TYPICAL PANEL
INSTALLATION SHEET





STANDARD SIGN
SIGN BANDING DETAILS

WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Rauch*
for State Traffic Engineer

DATE 6/10/19 PLATE NO. A5-9.4



GENERAL NOTES

1. WOOD 4"X6" POST MATERIAL SHALL CONFORM TO 507.2.2 OF THE WISDOT STANDARD SPECIFICATIONS
2. BLOCK BANDING AND CLIPS SHALL BE STAINLESS STEEL, $\frac{3}{4}$ " WIDTH AND 0.025" THICKNESS
3. SIGNS 3' OR GREATER IN HEIGHT SHALL UTILIZE 3 BLOCK BANDS. SIGNS UNDER 3' IN HEIGHT SHALL UTILIZE 2 BLOCK BANDS
4. ACTUAL NUMBER OF FASTENERS PER SIGN VARIES WITH THE SIGN AREA, BUT NORMALLY THERE ARE TWO. FOR SIGNS GREATER THAN 9 S.F. 3 FASTENERS SHALL BE USED.
5. ALL SIGN MOUNTING BOLTS AND WASHERS SHALL BE EITHER:
 - a. Hot dip or mechanically galvanized in accordance with ASTM Designation: A 153, Class D
 - b. Electro-galvanized in accordance with ASTM Designation : B 633, TYPE III, SC 3
6. ALL BOLTS SHALL HAVE HEXAGONAL HEADS.
7. STEEL WASHERS SHALL BE $\frac{1}{4}$ " O.D. X $\frac{3}{8}$ " I.D. X $\frac{1}{16}$ "
8. NYLON WASHERS SHALL BE $\frac{1}{4}$ " O.D. X $\frac{3}{8}$ " I.D. X .080 FOR TYPE H OR TYPE F FACE SIGN

✱ LAG BOLTS SHALL BE $\frac{3}{8}$ " X $2\frac{1}{2}$ "

BLOCK BANDING DETAIL
(V-BLOCK OPTION)

WISCONSIN DEPT OF TRANSPORTATION



APPROVED *Matthew R. Rauch*
for State Traffic Engineer

DATE 4/19/2022 PLATE NO. A5-10.3

PROJECT NO:

SHEET NO:

E



NOTES

1. Sign is Type II - Type F Reflective
2. Color:
Background - Yellow
Message - Black
3. Alternate colors of stripes as shown.

SIZE	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z	Area sq. ft.
1																											
2S	12	36	1 1/2			4 3/8	3 1/2	5 5/8	45°	4	4																3.0
2M	12	36	1 1/2			4 3/8	3 1/2	5 5/8	45°	4	4																3.0
3	18	54	1 1/2			6	5 1/2	8 1/2	45°	6	6 9/16																6.75
4																											
5																											

STANDARD SIGN
W5-52L & W5-52R

WISCONSIN DEPT OF TRANSPORTATION

APPROVED *Matthew R. Rauch*
For State Traffic Engineer

DATE 3/4/2024 PLATE NO. W5-52.10

DESIGN DATA

LIVE LOAD:

DESIGN LOADING: HL-93
INVENTORY RATING FACTOR: RF = 1.10
OPERATING RATING FACTOR: RF = 1.42
WISCONSIN STANDARD PERMIT VEHICLE (WIS.-SPV): 250 (KIPS)

STRUCTURE IS DESIGNED FOR A FUTURE WEARING SURFACE OF 20 POUNDS PER SQUARE FOOT.

MATERIAL PROPERTIES:

CONCRETE MASONRY: _____ f'c = 4,000 P.S.I.
SUPERSTRUCTURE _____ f'c = 3,500 P.S.I.
ALL OTHER _____

BAR STEEL REINFORCEMENT: _____ fy = 60,000 P.S.I.
GRADE 60 _____

FOUNDATION DATA

ABUTMENTS TO BE SUPPORTED ON HP 10 X 42 PILING DRIVEN TO A REQUIRED DRIVING RESISTANCE OF 180 TONS ** PER PILE AS DETERMINED BY THE MODIFIED GATES DYNAMIC FORMULA.
ESTIMATED 16 FEET LONG FOR SOUTH ABUTMENT AND 17 FEET LONG FOR NORTH ABUTMENT.

**THE FACTORED AXIAL RESISTANCE OF PILES IN COMPRESSION USED FOR DESIGN IS THE REQUIRED DRIVING RESISTANCE MULTIPLIED BY A RESISTANCE FACTOR OF 0.5 USING MODIFIED GATES TO DETERMINE PILE CAPACITY.

TRAFFIC VOLUME

ROTT ROAD
ADT = <100 (2046)
R.D.S = 25 M.P.H.

HYDRAULIC DATA

100-YEAR FREQUENCY:

Q₁₀₀ = 3540 C.F.S.
Q_{BRIDGE} = 2526 C.F.S.
Q_{ROADWAY} = 1014 C.F.S.

V₁₀₀ = 7.5 F.P.S.
HW₁₀₀ = EL. 973.17
WATERWAY AREA = 338 SQ. FT.
DRAINAGE AREA = 13.1 SQ. MI.
SCOUR CRITICAL CODE = 5

ROADWAY OVERTOPPING

FREQUENCY = 20 YEARS
Q = 1885 C.F.S.
HW = EL. 971.65

2-YEAR FREQUENCY:

Q₂ = 425 C.F.S.
V₂ = 2.1 F.P.S.
HW₂ = EL. 968.58


LIST OF DRAWINGS

1. GENERAL PLAN
2. CROSS SECTION & QUANTITIES
3. SUBSURFACE EXPLORATION
4. SOUTH ABUTMENT
5. SOUTH ABUTMENT DETAILS
6. NORTH ABUTMENT
7. NORTH ABUTMENT DETAILS
8. SUPERSTRUCTURE
9. SUPERSTRUCTURE DETAILS
10. TUBULAR STEEL RAILING TYPE 'M'

STRUCTURE DESIGN CONTACTS:

JEREMY KRACHEY 608-988-7059
AARON BONK 608-261-0261

THESE PLANS ARE BASED UPON STANDARD BRIDGE PLANS DEVELOPED AND MAINTAINED BY THE WISCONSIN DEPARTMENT OF TRANSPORTATION THROUGH THE USE OF THE WISDOT STANDARD BRIDGE DESIGN TOOL. THE UNDERSIGNED DESIGNER CERTIFIES THE ACCURACY OF THE BRIDGE TYPE, SIZE AND LOCATION, HYDRAULICS AND FOUNDATION SUPPORT, AND INFORMATION IN THE PLANS THAT IS NOT PART OF THE STANDARD PLANS SUPPLIED BY THE DEPARTMENT. THE DESIGNER FURTHER CERTIFIES THAT USE OF THE STANDARD BRIDGE DESIGN TOOL FOR DEVELOPMENT OF THIS PLAN IS CONSISTENT WITH THE GUIDANCE PROVIDED IN THE WISDOT BRIDGE MANUAL.



NO.	DATE	REVISION	BY
-----	------	----------	----

ORIGINAL PLANS
PREPARED BY:



STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

ACCEPTED  JLR 05/11/26
CHIEF STRUCTURES DESIGN ENGINEER DATE

STRUCTURE B-56-257

ROTT ROAD OVER LITTLE BARABOO RIVER

COUNTY SAUK TOWN WOODLAND

DESIGN SPEC.
AASHTO LRFD BRIDGE DESIGN SPECIFICATION


DESIGNED BY	DESIGNED	DRAWN	PLANS
JFK	CK'D	JLB	BAS
			CK'D

GENERAL PLAN

SHEET 1 OF 10


I.D.

DATE:



PLAN

SINGLE SPAN FLAT SLAB



ELEVATION

NORMAL TO WATERWAY

⊙ INDICATES WING NUMBER



THIS SHEET WAS CREATED BY THE WISDOT BUREAU OF STRUCTURES STANDARD BRIDGE DESIGN TOOL VERSION 1.1.0.0

EXCAVATION AS INDICATED IN THE HATCH AREAS, TO BE INCLUDED IN THE BID ITEM "EXCAVATION FOR STRUCTURES BRIDGES B-56-256".

SCALE = SCALE

GENERAL NOTES

DRAWINGS SHALL NOT BE SCALED.

BAR STEEL REINFORCEMENT SHALL BE EMBEDDED 2" CLEAR UNLESS OTHERWISE SHOWN OR NOTED.

THE FIRST OR FIRST TWO DIGITS OF THE BAR MARK SIGNIFIES THE BAR SIZE.

BEVEL EXPOSED EDGES OF CONCRETE ¾" UNLESS OTHERWISE NOTED.

THE UPPER LIMITS OF "EXCAVATION FOR STRUCTURES B-56-257 " SHALL BE THE EXISTING GROUNDLINE.

AT THE BACK FACE OF ABUTMENT ALL VOLUME WHICH CANNOT BE PLACED BEFORE ABUTMENT CONSTRUCTION AND IS NOT OCCUPIED BY THE NEW STRUCTURE SHALL BE BACKFILLED WITH STRUCTURE BACKFILL TYPE A.

EXCAVATION BELOW THE ABUTMENT AND ABUTMENT BEDDING MATERIALS REQUIRES ENGINEER APPROVAL. GEOTEXTILE SHALL BE SET AT THE BOTTOM OF EXCAVATION AND EXTEND 2'-0" ABOVE BOTTOM OF ABUTMENT.


THE QUANTITY FOR BACKFILL STRUCTURE IS CALCULATED BASED ON THE DETAIL SHOWN IN THE PLANS.

THE SLOPE OF THE FILL IN FRONT OF THE ABUTMENTS SHALL BE COVERED WITH HEAVY RIPRAP AND GEOTEXTILE TYPE HR TO THE EXTENT SHOWN ON SHEET 1 AND THE ABUTMENT DETAILS.

AT ABUTMENTS, CONCRETE POURED UNDER WATER WILL BE ALLOWED AND SHALL BE DONE IN ACCORDANCE WITH SECTION 502.3.5.3 OF THE STANDARD SPECIFICATIONS.


SLAB FALSEWORK SHALL BE SUPPORTED ON PILES OR THE SUBSTRUCTURE UNLESS AN ALTERNATE METHOD IS APPROVED BY THE ENGINEER.

PROTECTIVE SURFACE TREATMENT TO BE APPLIED TO ENTIRE EXPOSED TOP OF SLAB, INCLUDING THE SLAB EDGE AND 1'-0" UNDER THE SLAB, THE TOP AND EXTERIOR EXPOSED FACE OF WINGS AND FRONT FACE OF ABUTMENT TO 1'-0" PAST THE EDGE OF SLAB.




CROSS SECTION THRU ROADWAY

LOOKING UPSTATION
(PILING NOT SHOWN FOR CLARITY)



PROFILE GRADE LINE




ABUTMENT BACKFILL DIAGRAM


- L = ABUTMENT BODY LENGTH AT BACKFACE (FT)
H = AVERAGE ABUTMENT FILL HEIGHT (FT)
H1 = WING 1 HEIGHT AT TIP (FT)
H2 = WING 2 HEIGHT AT TIP (FT)
W = WING LENGTH (FT)
EF = EXPANSION FACTOR (1.20 FOR CY BID ITEMS AND 1.00 FOR TON BID ITEMS)
 $V_{CF} = (L)(3.0')(H) + (L)(0.5)(1.5H)(H) + (3')(0.5)(H1+H2+H+H)(W)$
 $V_{CY} = V_{CF}(EF)/27$
 $V_{TON} = V_{CY}(2.0)$

TOTAL ESTIMATED QUANTITIES

BID ITEM NUMBER	BID ITEMS	UNIT	SUPER	SOUTH ABUT.	NORTH ABUT.	TOTALS
203.0260	REMOVING STRUCTURE OVER WATERWAY WITH MINIMAL DEBRIS P-56-948	EACH	---	---	---	1
206.1001	EXCAVATION FOR STRUCTURES BRIDGES (B-56-257)	EACH	---	---	---	1
210.1500	BACKFILL STRUCTURE TYPE A	TON	---	145	145	290
502.0100	CONCRETE MASONRY BRIDGES	CY	103	26	26	155
502.3200	PROTECTIVE SURFACE TREATMENT	SY	179	15	15	209
505.0400	BAR STEEL REINFORCEMENT HS STRUCTURES	LB	---	2,010	2,010	4,020
505.0600	BAR STEEL REINFORCEMENT HS COATED STRUCTURES	LB	22,510	1,510	1,510	25,530
513.4061	RAILING TUBULAR TYPE M	LF	106	---	---	106
516.0500	RUBBERIZED MEMBRANE WATERPROOFING	SY	---	5	5	10
550.1100	PILING STEEL HP 10-INCH X 42 LB	LF	---	112	119	231
606.0300	RIPRAP HEAVY	CY	---	55	55	110
612.0406	PIPE UNDERDRAIN WRAPPED 6-INCH	LF	---	70	70	140
645.0111	GEOTEXTILE TYPE DF SCHEDULE A	SY	---	47	47	94
645.0120	GEOTEXTILE TYPE HR	SY	---	112	112	224
	NON-BID ITEMS					
	FILLER	SIZE	---	---	---	½", ¾"




PROTECTIVE SURFACE
TREATMENT DETAILS



TYPICAL SECTION THRU ABUTMENT

▲ BACKFILL PAY LIMITS. BACKFILL BEYOND PAY LIMITS SHALL BE INCIDENTAL TO EXCAVATION FOR STRUCTURES. LIMITS OF EXCAVATION SHALL BE DETERMINED BY THE CONTRACTOR.

■ PIPE UNDERDRAIN WRAPPED (6-INCH). SLOPE 0.5% MIN. TO SUITABLE DRAINAGE. ATTACH RODENT SHIELD AT ENDS OF PIPE UNDERDRAIN.



RODENT SHIELD DETAIL



* DIMENSIONS ARE APPROXIMATE. THE GRATE IS SIZED TO FIT INTO A PIPE COUPLING. ORIENT SO SLOTS ARE VERTICAL.

THE RODENT SHIELD, PIPE COUPLING AND SCREWS SHALL BE CONSIDERED INCIDENTAL TO THE BID ITEM "PIPE UNDERDRAIN WRAPPED 6-INCH".

THE RODENT SHIELD SHALL BE A PVC GRATE SIMILAR TO THIS DETAIL. THE GRATE IS COMMERCIALY AVAILABLE AS A FLOOR STRAINER. A PIPE COUPLING IS REQUIRED FOR THE ATTACHMENT OF THIS SHIELD TO THE EXPOSED END OF THE PIPE UNDERDRAIN. THE SHIELD SHALL BE FASTENED TO THE PIPE COUPLING WITH TWO OR MORE NO. 10 X 1-INCH STAINLESS STEEL SHEET METAL SCREWS.

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-56-257			
DRAWN BY		BAS	PLANS CK'D JFK
CROSS SECTION & QUANTITIES		SHEET 2 OF 10	

BORING #	DATE COMPLETED	NORTHING (Y)	EASTING (X)
1	9/27/2024	276527.97	517066.20
2	9/27/2024	276576.04	517066.37
BORINGS COMPLETED BY: GEOTEST, INC.			
REPORT COMPLETED BY: GEOTEST, INC.			
ALL COORDINATES REFERENCED TO WCCS NAD 83(91)		SAUK COUNTY	




STATE PROJECT NUMBER

5738-00-75

MATERIAL SYMBOLS

ASPHALT	TOPSOIL	PEAT
CONCRETE	FILL	GRAVEL
SAND	CLAY	SILT
BOULDERS OR COBBLES	LIMESTONE	BEDROCK (UNKNOWN)
SHALE	SANDSTONE	IGNEOUS/META

LEGEND OF BORING



(1) UNCONFINED STRENGTH, AS DETERMINED BY A POCKET PENETROMETER (TSF)

(2) UNLESS OTHERWISE, SPECIFIED THE SPT 'N' VALUE IS BASED ON AASHTO T-206, STANDARD PENETRATION TEST. THE SPT 'N' VALUE PRESENTED HAS NOT BEEN CORRECTED FOR OVERBURDEN PRESSURE OR HAMMER EFFICIENCY.

GROUND WATER ELEVATION

▽	AT TIME OF DRILLING
▼	END OF DRILLING
▽	AFTER DRILLING

ABBREVIATIONS

F-FINE M-MEDIUM C-COARSE ST-SHELBY TUBE

SUBSURFACE EXPLORATION FOR FOUNDATION DESIGN AND BIDDERS INFORMATION

BORINGS WERE COMPLETED AT POINTS APPROXIMATELY AS INDICATED ON THIS DRAWING TO OBTAIN INFORMATION CONCERNING THE CHARACTER OF SUBSURFACE MATERIALS FOUND AT THE SITE. BECAUSE THE INVESTIGATED DEPTHS ARE LIMITED AND THE AREA OF THE BORINGS IS VERY SMALL IN RELATION TO THE ENTIRE SITE, THE WISCONSIN DEPARTMENT OF TRANSPORTATION DOES NOT WARRANT SIMILAR SUBSURFACE CONDITIONS BELOW, BETWEEN, OR BEYOND THESE BORINGS. VARIATIONS IN SOIL CONDITIONS SHOULD BE EXPECTED AND FLUCTUATIONS IN GROUNDWATER LEVELS MAY OCCUR.

NO.	DATE	REVISION	BY
-----	------	----------	----

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION
STRUCTURES DESIGN SECTION

STRUCTURE B-56-257

DRAWN BY	BAS	PLANS CK'D
----------	-----	------------

SUBSURFACE
EXPLORATION

SHEET 3 OF 10




- | | | | |
|--|------|-----------------|--------------|
| | | | |
| NO. | DATE | REVISION | B |
| STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION | | | |
| STRUCTURE | | B-56-257 | |
| | | DRAWN
BY | BAS CK'D JFL |
| SOUTH
ABUTMENT | | SHEET 4 OF 10 | |
| | | | |

BILL OF BARS


NOTE: THE FIRST OR FIRST TWO DIGITS OF THE BAR MARK SIGNIFIES THE BAR SIZE.

BAR MARK	COAT	NO. REQ'D.	LENGTH	BENT	BAR SERIES	LOCATION
A501		64	6'-0"	X		ABUT BODY STIRRUPS
A502		27	7'-5"	X		ABUT BODY STIRRUPS - TOP U-BAR
A503		9	31'-8"			ABUT BODY HORIZ. - F.F.
A804		18	21'-9"	X		ABUT BODY HORIZ. - B.F.
A405		27	3'-0"	X		ABUT BODY TIE BARS
A506	X	25	2'-0"			ABUT BODY DOWEL BARS
A407	X	56	10'-10"	X		WING STIRRUPS
A508	X	5	11'-7"	X		WING CORNER STIRRUPS
A509	X	18	11'-9"	X		WING LOWER HORIZ. - F.F.
A810	X	18	13'-3"	X		WING LOWER HORIZ. - B.F.
A411	X	4	10'-2"			WING UPPER HORIZ.
A412	X	4	7'-7"			WING UPPER HORIZ.
A413	X	4	5'-0"			WING UPPER HORIZ.
A414	X	4	9'-9"	X		WING TOP HORIZ.
A415	X	4	7'-11"	X		WING 1 UPPER HORIZ. CORNER
A416	X	4	8'-11"	X		WING 2 UPPER HORIZ. CORNER




WING 1 ELEVATION

SHOWING F.F. WING




WING 1 PLAN

SHOWING UPPER WING REINFORCEMENT




WING 1 PLAN

SHOWING LOWER WING REINFORCEMENT
WING 2 SIMILAR




'HP' PILE DETAILS

THIS SHEET WAS CREATED BY THE WISDOT BUREAU OF STRUCTURES STANDARD BRIDGE DESIGN TOOL VERSION 1.1.0.0




WING 2 ELEVATION

SHOWING F.F. WING



WING 2 PLAN


SHOWING UPPER WING REINFORCEMENT



SECTION THRU WING 1

TYPICAL BOTH WINGS


SECTION A-A




- A01 OPTIONAL CONST. JOINT: KEYWAY FORMED BY A BEVELED 2X6. PROVIDE 3/4" "V" GROOVE ON F.F. OF WINGWALL IF JOINT IS USED.
- A06 SUPPORT ABUTMENT ON HP 10 x 42 PILING, ESTIMATED 16 FT LONG WITH A REQUIRED DRIVING RESISTANCE OF 180TONS PER PILE.
- A15 PIPE UNDERDRAIN WRAPPED (6-INCH). SLOPE 0.5% MIN. TO SUITABLE DRAINAGE. RODENT SHIELD REQUIRED.
- A19 18" RUBBERIZED MEMBRANE WATERPROOFING, ONLY IF OPTIONAL CONSTRUCTION JOINT IS USED. COST INCIDENTAL TO BID ITEM "CONCRETE MASONRY STRUCTURES".

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-56-257			
DRAWN BY		BAS	PLANS CK'D JFK
SOUTH ABUTMENT DETAILS		SHEET 5	


SCALE =




ELEVATION
LOOKING UPSTATION




SECTION THRU BODY



PLAN



DETAIL A



PILE PLAN


- A01 CONST. JOINT: KEYWAY FORMED BY A BEVELED 2X6.
- A06 SUPPORT ABUTMENT ON HP 10 x 42 PILING, ESTIMATED 17 FT LONG WITH A REQUIRED DRIVING RESISTANCE OF 180TONS PER PILE.
- A15 PIPE UNDERDRAIN WRAPPED (6-INCH). SLOPE 0.5% MIN. TO SUITABLE DRAINAGE. RODENT SHIELD REQUIRED.
- A17 1/2" FILLER: SEAL ALL EXPOSED HORIZ. & VERT. SURFACES OF 1/2" FILLER WITH NON-STAINING GRAY NON-BITUMINOUS JOINT SEALER. (1" DEEP AND HOLD 3/8" BELOW SURFACE OF CONCRETE). EXTEND SEALER 3" BELOW GUTTER LINE AT INSIDE FACE.
- A19 18" RUBBERIZED MEMBRANE WATERPROOFING. SEAL ALL HORIZ. & VERT. JOINTS AT BACKFACE.
- A22 B506 BARS SPACED @ 1'-0" CNTRS. MAY BE PLACED AFTER CONCRETE IS POURED BUT BEFORE INITIAL SET HAS TAKEN PLACE. (EMBED 1'-0" INTO CONC.)
- ALTERNATE THE POSITION OF THE 90° AND 180° HOOKS AT EACH VERTICAL LAYER OF TIES.

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-56-257			
DRAWN BY		BAS	PLANS CK'D JFK
NORTH ABUTMENT		SHEET 6	

BILL OF BARS


NOTE: THE FIRST OR FIRST TWO DIGITS OF THE BAR MARK SIGNIFIES THE BAR SIZE.

BAR MARK	COAT	NO. REQ'D.	LENGTH	BENT	BAR SERIES	LOCATION
B501		64	6'-0"	X		ABUT BODY STIRRUPS
B502		27	7'-5"	X		ABUT BODY STIRRUPS - TOP U-BAR
B503		9	31'-8"			ABUT BODY HORIZ. - F.F.
B804		18	21'-9"	X		ABUT BODY HORIZ. - B.F.
B405		27	3'-0"	X		ABUT BODY TIE BARS
B506	X	25	2'-0"			ABUT BODY DOWEL BARS
B407	X	56	10'-10"	X		WING STIRRUPS
B508	X	5	11'-7"	X		WING CORNER STIRRUPS
B509	X	18	11'-9"	X		WING LOWER HORIZ. - F.F.
B810	X	18	13'-3"	X		WING LOWER HORIZ. - B.F.
B411	X	4	10'-2"			WING UPPER HORIZ.
B412	X	4	7'-7"			WING UPPER HORIZ.
B413	X	4	5'-0"			WING UPPER HORIZ.
B414	X	4	9'-9"	X		WING TOP HORIZ.
B415	X	4	7'-11"	X		WING 3 UPPER HORIZ. CORNER
B416	X	4	8'-11"	X		WING 4 UPPER HORIZ. CORNER




WING 3 ELEVATION

SHOWING F.F. WING




WING 3 PLAN

SHOWING UPPER WING REINFORCEMENT




WING 3 PLAN

SHOWING LOWER WING REINFORCEMENT
WING 4 SIMILAR




'HP' PILE DETAILS

THIS SHEET WAS CREATED BY THE WISDOT BUREAU OF STRUCTURES STANDARD BRIDGE DESIGN TOOL VERSION 1.1.0.0




WING 4 ELEVATION

SHOWING F.F. WING



WING 4 PLAN

SHOWING UPPER WING REINFORCEMENT




SECTION THRU WING 3

TYPICAL BOTH WINGS


SECTION A-A

- A01 OPTIONAL CONST. JOINT: KEYWAY FORMED BY A BEVELED 2X6. PROVIDE 3/4" "V" GROOVE ON F.F. OF WINGWALL IF JOINT IS USED.
- A06 SUPPORT ABUTMENT ON HP 10 x 42 PILING, ESTIMATED .17 FT LONG WITH A REQUIRED DRIVING RESISTANCE OF 180TONS PER PILE.
- A15 PIPE UNDERDRAIN WRAPPED (6-INCH). SLOPE 0.5% MIN. TO SUITABLE DRAINAGE. RODENT SHIELD REQUIRED.
- A19 18" RUBBERIZED MEMBRANE WATERPROOFING, ONLY IF OPTIONAL CONSTRUCTION JOINT IS USED. COST INCIDENTAL TO BID ITEM "CONCRETE MASONRY STRUCTURES".




NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-56-257			
DRAWN BY		BAS	PLANS CK'D JFK
NORTH ABUTMENT DETAILS		SHEET 7	


SCALE =



CROSS SECTION THRU ROADWAY



PLAN




LONGITUDINAL SECTION

DIMENSIONS ARE GIVEN PARALLEL TO ε ROADWAY UNLESS OTHERWISE NOTED.


MEASURED NORMAL TO THE ε OF ABUTMENT. DIMENSIONS ARE TYPICAL FOR BOTH ABUTMENTS.

A506, B506 BARS SPACED @ 1'-0" CNTRS. MAY BE PLACED AFTER CONCRETE IS POURED BUT BEFORE INITIAL SET HAS TAKEN PLACE. (EMBED 1'-0" INTO CONC.)



END POST DETAILS

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-56-257			
DRAWN BY		BAS	PLANS CK'D JFK
SUPERSTRUCTURE		SHEET 8 OF 10	



CAMBER AND SLAB THICKNESS DIAGRAM


CAMBER SHOWN IS BASED ON 3 TIMES DEAD LOAD DEFLECTIONS. CAMBER SPANS AS SHOWN TO PROVIDE FOR DEAD LOAD DEFLECTION AND FUTURE CREEP. CAMBER DOES NOT INCLUDE ALLOWANCE FOR FORM SETTLEMENT. PARAPETS PLACED ON TOP OF THE SLAB SHALL BE POURED AFTER FALSEWORK HAS BEEN RELEASED, EXCEPT FOR STAGED CONSTRUCTION.

TO DETERMINE FALSEWORK ELEVATION AT EDGE OF SLAB, CROWN OR REFERENCE LINE FOLLOW THIS PROCEDURE:


LESS	TOP OF SLAB ELEVATION AT FINAL GRADE
PLUS	SLAB THICKNESS
PLUS	CAMBER
PLUS	FORM SETTLEMENT/DEFLECTION DUE TO PLACEMENT OF SLAB CONCRETE (TO BE COMPUTED BY THE CONTRACTOR)
EQUALS	TOP OF SLAB FALSEWORK ELEVATION

TOP OF SLAB ELEVATIONS

LOCATION	C/L BRG. S. ABUT.	1/10 PT.	2/10 PT.	3/10 PT.	4/10 PT.	5/10 PT.	6/10 PT.	7/10 PT.	8/10 PT.	9/10 PT.	C/L BRG. N. ABUT.
W. EDGE OF DECK	973.57	973.65	973.71	973.76	973.79	973.81	973.81	973.79	973.76	973.71	973.64
CROWN OR R/L	973.88	973.95	974.01	974.05	974.07	974.08	974.07	974.05	974.01	973.95	973.88
E. EDGE OF DECK	973.65	973.71	973.76	973.79	973.81	973.81	973.79	973.76	973.71	973.65	973.57



S505



S608

S609

BILL OF BARS

NOTE: THE FIRST OR FIRST TWO DIGITS OF THE BAR MARK SIGNIFIES THE BAR SIZE.

BAR MARK	COAT	NO. REQ'D.	LENGTH	BENT	BAR SERIES	LOCATION
S1101	X	58	50'-2"			SLAB BOTTOM LONGITUDINAL
S702	X	51	26'-7"			SLAB BOTTOM TRANSVERSE
S503	X	51	26'-7"			SLAB TOP TRANSVERSE
S504	X	21	50'-2"			SLAB TOP LONGITUDINAL
S505	X	54	7'-7"	X		ABUTMENT DIAPHRAGM STIRRUPS
S506	X	4	26'-7"			ABUTMENT DIAPHRAGM LONGITUDINAL
S607	X	56	6'-0"			SLAB TOP LONGIT. UNDER RAIL POSTS
S608	X	16	4'-8"	X		SLAB TOP LONGIT. UNDER RAIL END POSTS
S609	X	36	11'-3"	X		SLAB TOP HOOKS UNDER RAIL POSTS

SURVEY TOP OF SLAB ELEVATIONS

LOCATION	ABUTMENT	5/10 PT.	ABUTMENT
W. GUTTER			
CROWN OR R/L			
E. GUTTER			


PRIOR TO RELEASING SLAB FALSEWORK, TAKE TOP OF SLAB ELEVATIONS AT THE C/L OF ABUTMENTS, THE C/L OF PIERS AND AT 5/10 PTS. TO VERIFY CAMBER. TAKE ELEVATIONS ALONG GUTTER LINES AND CROWN OR R/L. RECORD THE ELEVATIONS IN THE ABOVE TABLE FOR THE "AS BUILT" PLANS.

NOTES


FILL IN THE TABLE OF "SURVEY TOP OF SLAB ELEVATIONS" FOR EACH SPAN ON AS BUILT PLANS.

TOP TRANSVERSE BARS IN SLAB SHALL BE SUPPORTED BY INDIVIDUAL BAR CHAIRS AT APPROXIMATELY 3'-0" CENTERS EACH WAY. BOTTOM LONGITUDINAL BARS SHALL BE SUPPORTED BY CONTINUOUS BAR CHAIRS AT APPROXIMATELY 4'-0" CENTERS.


ALL SLAB THICKNESS DIMENSIONS ARE MINIMUM. ANY TOLERANCES NECESSARY TO CORRECT CONSTRUCTION DISCREPANCIES ARE TO BE PLUS (+).




SECTION THRU RAILING ON DECK



FIELD ERECTION JOINT DETAIL




SHOP RAIL SPLICE DETAIL
LOCATION MUST BE SHOWN ON SHOP DRAWINGS




ANCHOR BOLTS


* ANCHOR BOLT ASSEMBLY MAY BE TACK WELDED, EITHER IN THE SHOP, OR IN THE FIELD AFTER THE ANCHOR PLATE IS PLACED.



SECTION B-B



SECTION THRU POST WEB



SECTION THRU RAIL

NOTE: CONNECTIONS AT LOWER RAILS SHOWN. CONNECTIONS AT TOP RAIL SIMILAR.


TYPICAL RAIL TO POST CONNECTIONS

LEGEND


- 1 W6 x 25 WITH 1 1/8" x 1 1/2" HORIZ. SLOTS ON EACH SIDE OF POST FOR BOLT NO. 6. CUT BOTTOM OF POST TO MATCH CROSS SLOPE OF ROADWAY. PLACE POST VERTICAL. PLACE POSTS NORMAL TO GRADE LINE.
- 2 PLATE 1 1/4" x 11 3/4" x 1'-8" WITH 1 1/16" OVERSIZED HOLES FOR ANCHOR BOLTS NO. 3. WELD TO NO. 1 AS SHOWN.
- 3 ASTM A449 - 1 1/8" DIA. ANCHOR BOLTS WITH NUT AND HARDENED WASHER (ALL GALVANIZED). 5 REQ'D. PER POST. THREAD 3" AND PLACE NORMAL TO PLATE NO. 2. CHAMFER TOP OF BOLTS BEFORE THREADING. USE 1'-9" LONG IN ABUTMENT WINGS. AT POSTS ON CONCRETE SLAB SUPERSTRUCTURES WHERE THE SLAB THICKNESS IS > 16" USE 1'-3" LONG. USE 10 3/4" LONG AT ALL OTHER LOCATIONS. (AN EQUIVALENT THREADED ROD WITH NUTS AND HARDENED WASHERS MAY BE SUBSTITUTED FOR ANCHOR BOLTS IN WINGS IF REQ'D. FOR CONSTRUCTIBILITY.)
- 4 5/8" x 11" x 1'-8" ANCHOR PLATE (GALVANIZED) WITH 1 3/16" DIA. HOLES FOR ANCHOR BOLTS NO. 3.
- 5 TS 5 x 4 x 0.25 STRUCTURAL TUBING. ATTACH TO NO. 1 WITH NO. 6.
- 5A TS 5 x 5 x 0.25 STRUCTURAL TUBING. ATTACH TO NO. 1 WITH NO. 6.
- 6 7/8" DIA. A325 SLOTTED ROUND HEAD BOLT WITH NUT, 3/16" x 1 5/8" x 1 5/8" MIN. WASHER, AND LOCK WASHER (2 REQ'D. AT EACH RAIL TO POST LOCATION).
- 7 SPLICE SLEEVE FABRICATED FROM 1/4" PLATE. PROVIDE "SLIDING FIT".
- 8 3/8" x 3 5/8" x 2'-4" PLATE. 2 PER RAIL. USED IN NO. 5 & 5A.
- 8A 3/8" x 2 5/8" x 2'-4" PLATE USED IN NO. 5, 3/8" x 3 5/8" x 2'-4" PLATE USED IN NO. 5A. 2 PER RAIL.
- 9 7/8" DIA. A325 ROUND HEAD BOLT WITH NUT, WASHER, AND LOCK WASHER. USE 1 5/16" x 1 1/4" LONGIT. SLOTTED HOLES IN PLATE NO. 10A AT FIELD JOINTS AND 1 5/16" x 2 1/4" MIN. LONGIT. SLOTTED HOLES AT EXP. JOINTS IN PLATE NO. 8A. PROVIDE 1 5/16" DIA. ROUND HOLES IN TUBES NO. 5 AND NO. 5A.

GENERAL NOTES

1. BID ITEM SHALL BE "RAILING TUBULAR TYPE M" WHICH INCLUDES ALL ITEMS SHOWN.
2. RAIL POST AND BASE PLATES SHALL CONFORM TO THE REQUIREMENTS OF ASTM A709 GRADE 50. HOLLOW RAILING STRUCTURAL TUBING SHALL CONFORM TO THE REQUIREMENTS OF ASTM A500 GRADE B OR C WITH A CERTIFIED FY = 50 KSI. ANCHOR PLATES, AND SPLICE TUBE PLATES SHALL CONFORM TO THE REQUIREMENTS OF ASTM A709 GRADE 36.
3. THE NUT SECURING THE POST BASE PLATE TO THE CONCRETE SHALL BE TIGHTENED TO A SNUG FIT AND GIVEN AN ADDITIONAL 1/2 TURN.
4. RAILS SHALL BE CONTINUOUS OVER A MINIMUM OF THREE (3) POSTS WITHOUT SPLICES WHERE POSSIBLE.
5. ENDS OF TUBE SECTIONS SHALL BE SAWED. GRIND SMOOTH EXPOSED EDGES. ALL CUT ENDS SHALL BE TRUE AND SMOOTH.
6. WELD IS THE SAME ON BOTH FLANGES. FLANGE WELD DOES NOT REQUIRE MAGNETIC PARTICLE TESTING.
7. FILL BOLT SLOT OPENINGS IN POST SHIMS AND PLATE NO. 2 AND CAULK AROUND PERIMETER OF PLATE NO. 2 WITH NON-STAINING GRAY NON-BITUMINOUS JOINT SEALER. STEEL POST SHIMS MAY BE USED UNDER POSTS WHERE REQ'D. FOR ALIGNMENT.
8. POST BASE PLATES SHALL BE FLAT WITH ALL SURFACES SMOOTH AND FREE FROM WARP AND ALL EDGES SMOOTH, STRAIGHT AND VERTICAL. ALL PLATE CUTS SHALL BE MACHINE OR MACHINE FLAME CUT.
9. ALL MATERIAL SHALL BE GALVANIZED AFTER FABRICATION. PRIOR TO GALVANIZING, ALL STEEL RAILING POSTS & STEEL TUBING SHALL BE GIVEN A NO. 6 BLAST CLEANING BY SSPC SPECIFICATIONS.



SECTION A-A




ANCHOR PLATE

AT RAIL TO DECK CONNECTION

POST SHIM

DETAIL



PART ELEVATION OF RAILING

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-56-257			
DRAWN BY		BAS	PLANS CK'D JFK
TUBULAR STEEL RAILING TYPE 'M'		SHEET 10	


DIVISION 1 - ROTT ROAD

STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)		CUMULATIVE VOL (CY)		
			CUT	FILL	CUT	FILL	CUT	EXPANDED FILL	MASS ORDINATE
					NOTE 1	NOTE 3	NOTE 1	1.25	NOTE 8
2+12.45	212.45	0.00	21.67	3.82	0	0	0	0	0
2+25.00	225.00	12.55	20.55	10.09	10	3	10	4	6
2+50.00	250.00	25.00	17.47	31.36	18	19	28	28	1


DIVISION 1 - ROTT ROAD


STATION	REAL STATION	DISTANCE	AREA (SF)		INCREMENTAL VOL (CY) (UNADJUSTED)		CUMULATIVE VOL (CY)		
			CUT	FILL	CUT	FILL	CUT	EXPANDED FILL	MASS ORDINATE
					NOTE 1	NOTE 3	NOTE 1	1.25	NOTE 8
3+25.00	325.00	0.00	20.95	24.72	0	0	0	0	0
3+50.00	350.00	25.00	20.15	9.15	19	16	19	20	-1
3+60.00	360.00	10.00	28.30	0.91	9	2	28	23	6

NOTES:	
1 - CUT	CUT INCLUDES SALVAGED/UNUSABLE PAVEMENT MATERIAL
2 - SALVAGED/UNUSABLE PAVEMENT MATERIAL	THIS DOES NOT SHOW UP IN CROSS SECTIONS
3 - FILL	DOES NOT INCLUDE UNUSABLE PAVEMENT EXC VOLUME
8 - MASS ORDINATE	IF MARSH AND EBS TO BE BACKFILLED WITH GRANULAR: [CUT - SALVAGED PAVT - ((FILL - EXPANDED ROCK) * FILL FACTOR)]



PROJECT NO: 5738-00-75	HWY: ROTT ROAD	COUNTY: SAUK	CROSS SECTIONS: ROTT ROAD	SHEET E
------------------------	----------------	--------------	---------------------------	---------





Wisconsin Department of Transportation

Dedicated people creating transportation solutions
through innovation and exceptional service.

<http://www.dot.wisconsin.gov>