

WKE

PROJECT ID: 3742-03-71


COUNTY: VARIOUS

WITH:

SEPTEMBER 2026  
ORDER OF SHEETS

|                        |              |                                    |
|------------------------|--------------|------------------------------------|
| Section No.            | 1            | Title                              |
| Section No.            | 2            | Typical Sections and Details       |
| Section No.            | 3            | Estimate of Quantities             |
| Section No.            | 3            | Miscellaneous Quantities           |
| <del>Section No.</del> | <del>4</del> | <del>Right of Way Plat</del>       |
| Section No.            | 5            | Plan and Profile                   |
| Section No.            | 6            | Standard Detail Drawings           |
| <del>Section No.</del> | <del>7</del> | <del>Sign Plates</del>             |
| <del>Section No.</del> | <del>8</del> | <del>Structure Plans</del>         |
| <del>Section No.</del> | <del>9</del> | <del>Computer Earthwork Data</del> |
| <del>Section No.</del> | <del>9</del> | <del>Cross Sections</del>          |

TOTAL SHEETS = 48




DESIGN DESIGNATION

|              |   |
|--------------|---|
| A.A.D.T.     | = |
| A.A.D.T.     | = |
| D.H.V.       | = |
| D.D.         | = |
| T.           | = |
| DESIGN SPEED | = |
| ESALS        | = |

CONVENTIONAL SYMBOLS


|                                   |  |
|-----------------------------------|--|
| <u>PLAN</u>                       |  |
| CORPORATE LIMITS                  |  |
| PROPERTY LINE                     |  |
| LOT LINE                          |  |
| LIMITED HIGHWAY EASEMENT          |  |
| EXISTING RIGHT OF WAY             |  |
| PROPOSED OR NEW R/W LINE          |  |
| SLOPE INTERCEPT                   |  |
| REFERENCE LINE                    |  |
| EXISTING CULVERT                  |  |
| PROPOSED CULVERT<br>(Box or Pipe) |  |
| COMBUSTIBLE FLUIDS                |  |
| MARSH AREA                        |  |
| WOODED OR SHRUB AREA              |  |

|                                                |
|------------------------------------------------|
| <u>PROFILE</u>                                 |
| GRADE LINE                                     |
| ORIGINAL GROUND                                |
| MARSH OR ROCK PROFILE<br>(To be noted as such) |
| SPECIAL DITCH                                  |
| GRADE ELEVATION                                |
| CULVERT (Profile View)                         |
| <u>UTILITIES</u>                               |
| ELECTRIC                                       |
| FIBER OPTIC                                    |
| GAS                                            |
| SANITARY SEWER                                 |
| STORM SEWER                                    |
| TELEPHONE                                      |
| WATER                                          |
| UTILITY PEDESTAL                               |
| POWER POLE                                     |
| TELEPHONE POLE                                 |



STATE OF WISCONSIN  
DEPARTMENT OF TRANSPORTATION  
PLAN OF PROPOSED IMPROVEMENT  
FY27 SER TREE CLEARING PROJECT  
VARIOUS SER COUNTIES  
VARIOUS HIGHWAYS  
SOUTHEAST REGION WIDE

|                      |
|----------------------|
| STATE PROJECT NUMBER |
| 3742-03-71           |



LAYOUT  
SCALE 0 1 MI  
TOTAL NET LENGTH OF CENTERLINE =

HORIZONTAL POSITIONS SHOWN ON THIS PLAN ARE WISCONSIN  
COORDINATE REFERENCE SYSTEM (WISCRS), {NAME} COUNTY,  
NAD83 HYEAR, IN U.S. SURVEY FEET. POSITIONS SHOWN ARE GRID  
COORDINATES, GRID BEARINGS, AND GRID DISTANCES. GRID DISTANCES  
ARE THE SAME AS GROUND DISTANCES.

ELEVATIONS ARE REFERENCED TO NAVD 88 {YEAR}. GPS DERIVED  
ELEVATIONS ARE BASED ON GEOID XX.

| STATE PROJECT | FEDERAL PROJECT |          |
|---------------|-----------------|----------|
|               | PROJECT         | CONTRACT |
| 3742-03-71    |                 |          |
|               |                 |          |
|               |                 |          |
|               |                 |          |

STATE OF WISCONSIN  
DEPARTMENT OF TRANSPORTATION

|                     |                   |
|---------------------|-------------------|
| PREPARED BY         |                   |
| Surveyor            | VARIOUS           |
| Designer            | WISDOT            |
| Project Manager     | JON GILL          |
| Regional Examiner   | REGIONAL EXAMINER |
| Regional Supervisor | JANET CANNON      |

APPROVED FOR THE DEPARTMENT  
DATE: 7/22/2026

E

ORDER OF SECTION 2 DETAIL SHEETS

GENERAL NOTES  
PROJECT OVERVIEW  
CONSTRUCTION DETAILS

WISCONSIN DNR LIAISON

CRAIG WEBSTER  
SOUTHERN REGION - WALWORTH AND WAUKESHA COUNTIES  
141 NW BARSTOW ST  
WAUKESHA, WI 53188  
PHONE: 414-303-3011  
EMAIL: CRAIG.WEBSTER@WISCONSIN.GOV

WISCONSIN DNR LIAISON

RYAN PAPPAS  
SOUTHERN REGION - MILWAUKEE, OZAUKEE, AND WASHINGTON COUNTIES  
1027 W ST. PAUL AVE  
MILWAUKEE, WI 53233  
PHONE: 414-750-7495  
EMAIL: RYAN.PAPPAS@WISCONSIN.GOV

WISCONSIN DNR LIAISON

JESSIAH BENNETT  
SOUTHERN REGION - RACINE AND KENOSHA COUNTIES  
1027 W ST. PAUL AVE  
MILWAUKEE, WI 53233  
PHONE: 414-750-7495  
EMAIL: JESSIAH.BENNETT@WISCONSIN.GOV

DESIGN PROJECT MANAGER

JON GILL, P.E.  
SOUTHEAST REGION  
141 NW BARSTOW ST  
WAUKESHA, WI 53188  
PHONE: 262-548-8812  
EMAIL: JONATHAN.GILL@DOT.WI.GOV

DESIGN PROJECT LEADER

ZORRIS BASS  
SOUTHEAST REGION  
141 NW BARSTOW ST  
WAUKESHA, WI 53188  
PHONE: 414-750-7161  
EMAIL: ZORRIS.BASS@DOT.WI.GOV

REGION SURVEY COORDINATOR

TOM LIPSKY, PLS  
SOUTHEAST REGION  
141 NW BARSTOW ST  
WAUKESHA, WI 53188  
PHONE: 262-548-6737  
EMAIL: THOMAS.LIPSKY@DOT.WI.GOV

STANDARD ABBREVIATIONS

|            |                                                        |           |                                                            |
|------------|--------------------------------------------------------|-----------|------------------------------------------------------------|
| ABUT       | ABUTMENT                                               | LT        | LEFT                                                       |
| AC         | ACRE                                                   | LHF       | LEFT HAND FORWARD                                          |
| AGG        | AGGREGATE                                              | L         | LENGTH OF CURVE                                            |
| AH         | AHEAD                                                  | LF        | LINEAR FOOT                                                |
| ∠          | ANGLE                                                  | LC        | LONG CHORD OF CURVE                                        |
| AADT       | ANNUAL AVERAGE DAILY TRAFFIC                           | LS        | LUMP SUM                                                   |
| AEW        | APRON ENDWALL                                          | MGAL      | ONE THOUSAND GALLONS                                       |
| ASPH       | ASPHALTIC                                              | MH        | MANHOLE                                                    |
| BK         | BACK                                                   | ML OR M/L | MATCH LINE                                                 |
| BC         | BACK OF CURB                                           | NOM       | NOMINAL                                                    |
| BAD        | BASE AGGREGATE DENSE                                   | NC        | NORMAL CROWN                                               |
| BL OR B/L  | BASE LINE                                              | NB        | NORTHBOUND                                                 |
| BM         | BENCH MARK                                             | NO        | NUMBER                                                     |
| CB         | CATCH BASIN                                            | OD        | OUTSIDE DIAMETER                                           |
| CL OR C/L  | CENTER LINE                                            | PAVT      | PAVEMENT                                                   |
| Δ          | CENTRAL ANGLE OR DELTA                                 | PLE       | PERMANENT LIMITED EASEMENT                                 |
| CE         | COMMERCIAL ENTRANCE                                    | PC        | POINT OF CURVATURE                                         |
| CONC       | CONCRETE                                               | PI        | POINT OF INTERSECTION                                      |
| CSW        | CONCRETE SIDEWALK                                      | PT        | POINT OF TANGENCY                                          |
| CONST      | CONSTRUCTION                                           | PCC       | PORTLAND CEMENT CONCRETE                                   |
| CP         | CONTROL POINT                                          | LB        | POUND                                                      |
| CO         | COUNTY                                                 | PSI       | POUNDS PER SQUARE INCH                                     |
| CTH        | COUNTY TRUCK HIGHWAY                                   | PE        | PRIVATE ENTRANCE                                           |
| CY         | CUBIC YARD                                             | PROJ      | PROJECT                                                    |
| CP         | CULVERT PIPE                                           | PL        | PROPERTY LINE                                              |
| CPCA       | CULVERT PIPE CORRUGATED ALUMINUM                       | PRW       | PROPOSED RIGHT OF WAY                                      |
| CPCPE      | CULVERT PIPE CORRUGATED POLYETHYLENE                   | R         | RADIUS                                                     |
| CPCPP      | CULVERT PIPE CORRUGATED POLYPROPYLENE                  | RL OR R/L | REFERENCE LINE                                             |
| PCPS       | CULVERT PIPE CORRUGATED STEEL                          | REQD      | REQUIRED                                                   |
| CPCSAC     | CULVERT PIPE CORRUGATED STEEL ALUMINUM COATED          | RT        | RIGHT                                                      |
| CPCSPC     | CULVERT PIPE CORRUGATED STEEL POLYMER COATED           | RHF       | RIGHT HAND FORWARD                                         |
| CPRC       | CULVERT PIPE REINFORCED CONCRETE                       | R/W       | RIGHT OF WAY                                               |
| CPRCHE     | CULVERT PIPE REINFORCED CONCRETE HORIZONTAL ELLIPTICAL | RD        | ROAD                                                       |
| CPS        | CULVERT PIPE SALVAGED                                  | RDWY      | ROADWAY                                                    |
| CPT        | CULVERT PIPE TEMPORARY                                 | SHLDR     | SHOULDER                                                   |
| C & G      | CURB AND GUTTER                                        | SW        | SIDEWALK                                                   |
| D          | DEGREE OF CURVE                                        | SB        | SOUTHBOUND                                                 |
| DHV        | DESIGN HOUR VOLUME                                     | SPECS     | SPECIFICATIONS                                             |
| DIA        | DIAMETER                                               | SF        | SQUARE FEET                                                |
| DD         | DIRECTIONAL DISTRIBUTION                               | SY        | SQUARE YARD                                                |
| DE         | DRAINAGE EASEMENT                                      | SDD       | STANDARD DETAIL DRAWINGS                                   |
| DWY        | DRIVEWAY                                               | STH       | STATE TRUNK HIGHWAY                                        |
| EA         | EACH                                                   | STA       | STATION                                                    |
| EB         | EASTBOUND                                              | SSPC      | STORM SEWER PIPE COMPOSITE                                 |
| EL OR ELEV | ELEVATION                                              | SSCPE     | STORM SEWER PIPE CORRUGATED POLYETHYLENE                   |
| EMB        | EMBANKMENT                                             | SSCPP     | STORM SEWER PIPE CORRUGATED POLYPROPYLENE                  |
| EW         | ENDWALL                                                | SSPNRC    | STORM SEWER PIPE NON-REINFORCED CONCRETE                   |
| EAT        | ENERGY ABSORBING TERMINAL                              | SSPRC     | STORM SEWER PIPE REINFORCED CONCRETE                       |
| ESALS      | EQUIVALENT SINGLE AXLE LOADS                           | SSPRC     | STORM SEWER PIPE REINFORCED CONCRETE                       |
| EXC        | EXCAVATION                                             | SSPRCHE   | STORM SEWER PIPE REINFORCED CONCRETE HORIZONTAL ELLIPTICAL |
| EBS        | EXCAVATION BELOW SUBGRADE                              | SE        | SUPERELEVATION                                             |
| EXIST      | EXISTING                                               | SL OR S/L | SURVEY LINE                                                |
| FERT       | FERTILIZER                                             | TEMP      | TEMPORARY                                                  |
| FE         | FIELD ENTRANCE                                         | TI        | TEMPORARY INTEREST                                         |
| FL OR F/L  | FLOW LINE                                              | TLE       | TEMPORARY LIMITED EASEMENT                                 |
| FT         | FOOT                                                   | TC        | TOP OF CURB                                                |
| FTMS       | FREE TRAFFIC MANAGEMENT SYSTEM                         | TL OR T/L | TRANSIT LINE                                               |
| HES        | HIGH EARLY STRENGTH                                    | T         | TRUCKS (PERCENT OF)                                        |
| HE         | HIGHWAY EASEMENT                                       | TYP       | TYPICAL                                                    |
| CWT        | HUNDRED WEIGHT                                         | USH       | UNITED STATES HIGHWAY                                      |
| IN DIA     | INCH DIAMETER                                          | VAR       | VARIABLE                                                   |
| INL        | INLET                                                  | VC        | VERTICAL CURVE                                             |
| ID         | INSIDE DIAMETER                                        | VPC       | VERTICAL POINT OF CURVATURE                                |
| INTERS     | INTERSECTION                                           | VPI       | VERTICAL POINT OF INTERSECTION                             |
| IH         | INTERSTATE HIGHWAY                                     | VPT       | VERTICAL POINT OF TANGENCY                                 |
| INV        | INVERT                                                 | W         | WEST                                                       |
| JT         | JOINT                                                  | WB        | WESTBOUND                                                  |

GENERAL NOTES

THE LOCATIONS OF EXISTING AND PROPOSED UTILITY INSTALLATIONS AS SHOWN ON THE PLANS ARE APPROXIMATE. THERE MAY BE OTHER UTILITY INSTALLATIONS WITHIN THE PROJECT AREA THAT ARE NOT SHOWN.

CONTRACTOR WILL BE RESPONSIBLE FOR RESHAPING AND SEEDING ANY PREVIOUSLY GRASSED AREAS WHICH ARE DISTURBED BY OPERATIONS, OUTSIDE OF THE NORMAL CONSTRUCTION LIMITS.

NO TREES OR SHRUBS ARE TO BE REMOVED WITHOUT THE APPROVAL OF THE ENGINEER.

RIGHT OF WAY INFORMATION SHOWN ON THE PLANS IS APPROXIMATE.

THE CONTRACTOR IS TO WORK WITH UTMOST CARE AND PROTECT ALL SURVEY MARKERS. REMOVAL OF ANY SURVEY MARKER IS TO BE WITH THE APPROVAL OF THE ENGINEER.

EROSION CONTROL FEATURES AS SHOWN IN THE PLANS ARE AT APPROXIMATE LOCATIONS. EXACT LOCATIONS WILL BE DETERMINED BY THE CONTRACTOR’S EROSION CONTROL IMPLEMENTATION PLAN (ECIP) AND APPROVED BY THE ENGINEER. MAINTAIN EROSION CONTROL MEASURES UNTIL SUCH A TIME AS THE ENGINEER DETERMINES THE MEASURE IS NO LONGER NECESSARY.

TRAFFIC CONTROL DEVICES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS DIRECTED BY THE ENGINEER.

DO NOT DRIVE OR STORE EQUIPMENT, OR STORE CONSTRUCTION MATERIALS IN ENVIRONMENTALLY SENSITIVE AREAS, WETLANDS OR WATERWAYS.



UTILITIES CONTACTS

CITY OF MILWAUKEE - COMMUNICATIONS  
JOE MACIEJEWSKI  
PHONE: 414-286-3547  
EMAIL: JOE.MACIEJEWSKI@MILWAUKEE.GOV

CITY OF MILWAUKEE - UNDERGROUND CONDUIT  
ENG-KIE LEE  
PHONE: 414-286-2174  
EMAIL: ELEE@MILWAUKEE.GOV

CITY OF MILWAUKEE - SEWERS  
ZAFAR YOUSUF  
PHONE: 414-286-2467  
EMAIL: ZYOUSU@MILWAUKEE.GOV

CITY OF MILWAUKEE - WATER WORKS  
JOSHUA IWEN  
PHONE: 414-286-3640  
EMAIL: JIWEN@MILWAUKEE.GOV

WE ENERGIES  
ELECTRIC AND GAS  
SYDNEY BATCHELOR  
EMAIL: SYDNEY.BATCHELOR@WE-ENERGIES.COM

OTHER CONTACTS

MILWAUKEE COUNTY PARKS

MUSTAFA GHAZAI  
PARKS ENGINEER  
9480 W. WATERTOWN PLANK ROAD  
WAUWATOSA, WI 53226  
PHONE: 414-257-6242  
EMAIL: MUSTAFA.GHAZAI@MILWAUKEECOUNTYWI.GOV

MILWAUKEE COUNTY TRANSIT SYSTEM

DAVID LOCHER  
MANAGER OF ENHANCED TRANSIT  
1942 N 17TH STREET  
MILWAUKEE, WI 53205  
PHONE: 414-343-1727  
EMAIL: DLOCHER@MCTS.ORG

MILWAUKEE METROPOLITAN SEWERAGE DISTRICT

MICHAEL LEE  
UTILITY COORDINATOR  
260 W SEEBOTH STREET  
MILWAUKEE, WI 53204  
PHONE: 414-225-2241  
EMAIL: MLEE@MMSD.COM

CITY OF MILWAUKEE - TRAFFIC SIGNALS

SCOTT REINBACHER  
PHONE: 414-286-3232  
EMAIL: SREINB@MILWAUKEE.GOV

CITY OF MILWAUKEE - STREET LIGHTING

ENG-KIE LEE  
STREET LIGHTING AND CUC  
841 N BROADWAY  
MILWAUKEE, WI 53202  
PHONE: 414-286-2174  
EMAIL: ELEE@MILWAUKEE.GOV

DIGGERSHOTLINE

Dial 811 or (800)242-8511

www.DiggersHotline.com

UTILITY CONTACTS

AT&T LEGACY - COMMUNICATION LINE

JEREMY DENNY  
211 GRAVOIS RD  
FENTON, MO 63026  
PHONE: (314) 343-7228  
JD075B@ATT.COM

AT&T WISCONSIN - COMMUNICATION LINE

DAVID BRUZAS  
411 7TH ST  
RACINE, WI 53403  
PHONE: (262) 636-0571  
DB4154@ATT.COM

AT&T MOBILITY - COMMUNICATION LINE

MARC BROWN  
301 E MILWAUKEE ST  
JANESVILLE, WI 53545  
PHONE: (608) 755-5535  
MB2682@ATT.COM

ATC MANAGEMENT, INC. - ELECTRICITY-TRANSMISSION

TRANS 220 MAILBOX  
801 O'KEEFE RD  
DE PERE, WI 54115  
PHONE: (920) 338-6582  
DL-ATCDOTNOTIFICATIONS@ATCLLC.COM

CITY OF GREENFIELD - COMMUNICATION LINE / SEWER

JEFF KATZ  
7325 W FOREST HOME AVE  
GREENFIELD, WI 53220  
CELL: (414) 329-5325  
JEFFK@GREENFIELDWI.US

CITY OF WEST ALLIS - COMMUNICATION LINE / SEWER / WATER

MELINDA DEJEWSKI  
7525 W GREENFIELD AVE  
WEST ALLIS, WI 53214  
CELL: (414) 302-8374  
MDEJEWSKI@WESTALLISWI.GOV

EVERSTREAM - COMMUNICATION LINE

EVERSTREAM UTILITY COORDINATION  
324 E WISCONSIN AVE. SUITE 730  
MILWAUKEE, WI 53202  
PHONE: (414) 409-1709  
WI-RELOCATIONS@EVERSTREAM.NET

LEVEL 3 COMMUNICATIONS LLC - COMMUNICATION LINE

NETWORK RELOCATIONS  
1025 ELDORADO BLVD  
BROOMFIELD, CO 80021  
RELOCATIONS@LUMEN.COM

MIDWEST FIBER NETWORKS LLC - COMMUNICATION LINE

MWFN UTILITY COORDINATOR  
6070 NORTH FLINT RD  
GLENDALE, WI 53209  
PHONE: (414) 672-5612  
RELOCATIONREQUESTS@MIDWESTFIBERNETWORKS.COM

MILWAUKEE METROPOLITAN SEWERAGE DISTRICT-SEWER

MICHAEL LEE  
260 W SEEBOTH ST  
MILWAUKEE, WI 53204  
PHONE: (414) 225-2241  
MLEE@MMSD.COM

SPECTRUM - COMMUNICATION LINE

GENERAL MAILBOX SPECTRUM  
12405 POWERCOURT DRIVE  
ST LOUIS, MO 63131  
CHTR\_WI\_CONST@CHARTER.COM

TDS METROCOM LLC - COMMUNICATION LINE

TDS TELECOM OSP  
525 JUNCTION ROAD  
MADISON, WI 53717  
PHONE: (608) 664-0132  
TDSTELECOMOSP@TDSTELECOM.COM

VERIZON BUSINESS - COMMUNICATION LINE

RJ CICALTELLO  
15725 WEST RYERSON ROAD  
NEW BERLIN, WI 53151  
PHONE: (262) 782-9836  
RANDY.CICALTELLO@VERIZON.COM

WE ENERGIES - ELECTRICITY

WE ENERGIES UTILITY COORDINATOR  
500 S 116TH STREET  
WEST ALLIS, WI 53214  
PHONE: (414) 944-5738  
WE-UTILITY-RELOCATIONS@WE-ENERGIES.COM

WE ENERGIES - GAS/PETROLEUM

WE ENERGIES UTILITY COORDINATOR  
500 S 116TH STREET  
WEST ALLIS, WI 53214  
PHONE: (414) 944-5738  
WE-UTILITY-RELOCATIONS@WE-ENERGIES.COM

STATE AGENCIES

WISCONSIN DEPARTMENT OF TRANSPORTATION RWIS PROGRAM - COMMUNICATION TOWER

MIKE ADAMS  
PO BOX 7986  
MADISON, WI 53707-7986  
PHONE: (608) 266-5004  
MICHAEL\_ADAMS@DOT.WI.GOV

WISCONSIN DEPARTMENT OF TRANSPORTATION

RABI BISTA - UTILITY COORDINATOR  
141 NW BARSTOW STREET  
WAUKESHA, WI 53187-0798  
PHONE: (262) 548-5690  
RABI BASTA@DOT.WI.GOV

WISCONSIN DEPARTMENT OF TRANSPORTATION - STREET LIGHTING

ERIC PEREA  
141 NW BARSTOW ST  
WAUKESHA, WI 53188  
PHONE: (262) 574-5422  
ERIC.PEREA@DOT.WI.GOV

WISCONSIN DEPARTMENT OF TRANSPORTATION - COMMUNICATION LINE

JEFF MADSON  
STE. 300  
433 W. ST. PAUL AVE.  
MILWAUKEE, WI 53203-3007  
PHONE: (414) 225-3723  
JEFFREY.MADSON@DOT.WI.GOV

WISCONSIN DEPARTMENT OF TRANSPORTATION - WISCONSIN SIGNAL

JARRETT GATES  
141 NW BARSTOW STREET  
PO BOX 798  
WAUKESHA, WI 53188-0798  
PHONE: (262) 548-5894  
JARRETT.GATES@DOT.WI.GOV

WISCONSIN DEPARTMENT OF TRANSPORTATION RWIS PROGRAM- COMMUNICATION TOWER

MIKE ADAMS  
PO BOX 7986  
MADISON, WI 53707-7986  
PHONE: (608) 266-5004  
MICHAEL\_ADAMS@DOT.WI.GOV

OTHER AGENCIES

MILWAUKEE COUNTY DEPARTMENT OF PUBLIC WORKS - ROAD FACILITY

DANIEL MURPHY  
10930 WEST LAPHAM STREET  
WEST ALLIS, WI 53214  
PHONE: (414) 257-6580  
PHONE: (414) 257-5942  
DANIEL.MURPHY@MILWAUKEECOUNTYWI.GOV

MILWAUKEE COUNTY PARKS DEPARTMENT - ELECTRICITY

BLAKE PRUSAK  
1150 N 68TH STREET  
MILWAUKEE, WI 53213  
BLAKE.PRUSAK@MILWAUKEECOUNTYWI.GOV

WAUKESHA WATER UTILITY - COMMUNICATION LINE / WATER

MAT KADRICH  
115 DELAFIELD STREET  
WAUKESHA, WI 53188  
PHONE: (262) 521-5272  
MKADRICH@WAUKESHA-WATER.COM

CITY OF MILWAUKEE - ROAD FACILITY

KEVIN MUHS  
841 N BROADWAY, ROOM 701  
MILWAUKEE, WI 53202  
CELL: (414) 286-2400  
KMUHS@MILWAUKEE.GOV

CITY OF WEST ALLIS - STREET LIGHTING

MELINDA DEJEWSKI  
7525 W GREENFIELD AVE  
WEST ALLIS, WI 53214  
CELL: (414) 302-8374  
MDEJEWSKI@WESTALLISWI.GOV

TO OBTAIN LOCATION OF PARTICIPANTS' UNDERGROUND FACILITIES  
BEFORE YOU DIG IN WISCONSIN





OTHER CONTACTS

- \* VILLAGE OF GERMANTOWN  
ROADWAY  
SCOTT ANDERSON  
N112 W17001 MEQUON ROAD  
P.O.BOX 337  
GERMANTOWN, WI 53022  
PHONE: 262-253-8253  
EMAIL: SANDERSON@GERMANTOWNWI.GOV
- \* VILLAGE OF MENOMONEE FALLS  
STREET LIGHTING  
ARLYN JOHNSON  
W156 N8480 PILGRIM ROAD  
MENOMONEE FALLS, WI 53051-3140  
PHONE: 262-253-4700  
EMAIL: PW@MENOMONEE-FALLS.ORG
- \* WISDOT  
STREET LIGHTING  
ERIC PEREA  
141 NW BARSTOW STREET  
WAUKESHA, WI 53188  
PHONE: 262-574-5422  
EMAIL: ERIC.PEREA@DOT.WI.GOV
- \* WISDOT  
TRAFFIC SIGNALS  
JOYCE MURPHY  
141 NW BARSTOW STREET  
WAUKESHA, WI 53188  
PHONE: 262-548-5933  
EMAIL: JOYCE.MURPHY@DOT.WI.GOV

UTILITY CONTACTS

- \* AT&T - LOCAL NETWORK  
COMMUNICATION LINE  
DALE DEFEVER  
39869 LINN STREET  
CANTON, MI 48147  
PHONE: 586-242-2671  
EMAIL: DD2579@ATT.COM
- \* AT&T - WISCONSIN  
COMMUNICATION LINE  
STEVE BURTC  
220 WISCONSIN AVENUE  
WAUKESHA, WI 53186  
PHONE: 262-506-2849  
EMAIL: SB7561@ATT.COM
- \* BLUEBIRD FIBER  
COMMUNICATION LINE  
324 E WISCONSIN AVENUE, SUITE 730  
MILWAUKEE, WI 53202  
PHONE: 414-409-1709  
EMAIL: WI-RELOCATIONS@EVERSTREAM.NET
- \* VILLAGE OF GERMANTOWN  
SEWER  
TIM ZIMMERMAN  
N122 W17177 FOND FU LAC AVENUE  
GERMANTOWN, WI 53022  
PHONE: 262-253-7765  
EMAIL: TZIMMERMAN@VILLAGE.GERMANTOWN.WI.US
- \* PAETEC COMMUNICATIONS  
COMMUNICATION LINE  
LORI KETTER  
314 N DANZ AVENUE  
GREEN BAY, WI 54302-3526  
PHONE: 920-410-6902  
EMAIL: LORI.KETTER@WINDSTREAM.COM
- \* SPECTRUM  
COMMUNICATION LINE  
DAVE YOPPS  
1320 N DR. MARTIN LUTHER KING JR DRIVE  
MILWAUKEE, WI 53212  
PHONE: 414-277-4281  
EMAIL: CHTR\_WI\_CONST@CHARTER.COM
- \* VERIZON BUSINESS  
COMMUNICATION LINE  
RJ CICATELLO JR.  
15725 W RYERSON ROAD  
NEW BERLIN, WI 53151  
PHONE: 262-782-9836  
EMAIL: RANDY.CICATELLO@VERIZON.COM
- \* VILLAGE OF MENOMONEE FALLS  
SEWER AND WATER  
MATTHEW JANECKE  
W156 N8480 PILGRIM ROAD  
MENOMONEE FALLS, WI 53051  
PHONE: 262-532-4704  
EMAIL: MJANECKE@MENOMONEE-FALLS.ORG
- \* VILLAGE OF GERMANTOWN  
WATER  
PAUL HAUGEN  
N122 W17001 MEQUON ROAD  
GERMANTOWN, WI 53022-0337  
PHONE: 262-253-8254  
EMAIL: PHAUGEN@VILLAGE.GERMANTOWN.WI.US
- \* WE ENERGIES  
GAS  
500 S 116TH STREET  
WEST ALLIS, WI 53214  
PHONE: 414-221-2738  
EMAIL: WE-UTILITY-RELOCATIONS@WE-ENERGIES.COM
- \* WE ENERGIES  
ELECTRICITY  
500 S 116TH STREET  
WEST ALLIS, WI 53214  
PHONE: 414-221-2738  
EMAIL: WE-UTILITY-RELOCATIONS@WE-ENERGIES.COM

DIGGERSHOTLINE

811

Dial 811 or (800)242-8511

www.DiggersHotline.com

\* DENOTES DIGGERS HOTLINE MEMBERS

UTILITY CONTACTS

Tyler Fleck  
AT&T Wisconsin - Communication Line  
220 Wisconsin Avenue  
Waukesha, WI 53186  
(414) 248-6803  
[TF8394@ATT.com](mailto:TF8394@ATT.com)

RJ Cicatello Jr.  
Verizon Business - Communication Line  
15725 West Ryerson Road  
New Berlin, WI 53151  
(262) 232-1323  
[randy.cicatello@verizon.com](mailto:randy.cicatello@verizon.com)

Rob Kincaid  
City of Pewaukee Department of Public Works - Water  
W240 N3065 Pewaukee Road  
Pewaukee, WI 53072  
(262) 691-6005  
[kincaid@pewaukee.wi.us](mailto:kincaid@pewaukee.wi.us)

Lori Ketter  
PaeTec Communications, LLC - Communication Line  
969 Waube Lane  
Green Bay, WI 54304  
(920) 410-6902  
[Lori.Ketter@windstream.com](mailto:Lori.Ketter@windstream.com)

Shawn Tremaine  
Village of Pewaukee Water/Sewer Utility - Water  
235 Hickory St  
Pewaukee, WI 53072  
(262) 613-5835  
[stremaine@villageofpewaukeewi.gov](mailto:stremaine@villageofpewaukeewi.gov)

Shawn Tremaine  
Village of Pewaukee Water/Sewer Utility - Sewer  
235 Hickory St  
Pewaukee, WI 53072  
(262) 613-5835  
[stremaine@villageofpewaukeewi.gov](mailto:stremaine@villageofpewaukeewi.gov)

Jon Baumann  
Village of Sussex - Water  
N64W23760 Main St.  
Sussex, WI 53089  
(262) 246-5200  
[jbaumann@sussexwi.gov](mailto:jbaumann@sussexwi.gov)

Jon Baumann  
Village of Sussex - Sewer  
N64W23760 Main St.  
Sussex, WI 53089  
(262) 246-5200  
[jbaumann@sussexwi.gov](mailto:jbaumann@sussexwi.gov)

Steve King  
We Energies - Electricity  
S13 W33800 HWY 18  
Delafield, WI 53018  
(414) 940-0570  
Dispatch: (800) 662-4797  
[Steve.king@we-energies.com](mailto:Steve.king@we-energies.com)

Jacob Hulbert  
We Energies - Gas  
500 S 116th Street  
West Allis, WI 53214  
(414) 651-1577  
Dispatch: (800) 261-5325  
[Jacob.Hulbert@we-energies.com](mailto:Jacob.Hulbert@we-energies.com)

Beau Abuya  
Spectrum - Communication Line  
1320 N. Dr. Martin Luther King Jr Drive  
Milwaukee, WI 53212  
(414) 758-9241  
[Beau.abuya@charter.net](mailto:Beau.abuya@charter.net)

Ryan Heikkila  
Level 3 Communications LLC - Communication Line  
715 2nd St. N  
Minneapolis, MN 55401  
[ryan.heikkila@lumen.com](mailto:ryan.heikkila@lumen.com)

DNR CONTACT  
Craig Webster  
Wisconsin Department of Natural Resources  
141 NW Barstow ST, Room 180  
Waukesha, WI 53188  
Phone: (262) 574-2141  
Cell: (414) 303-3011  
[Craig.Webster@Wi.Gov](mailto:Craig.Webster@Wi.Gov)



Dial **811** or (800) 242-8511  
[www.DiggersHotline.com](http://www.DiggersHotline.com)

UTILITY CONTACTS

\*FOR INFORMATION ONLY

AT&T - WISCONSIN (COMMUNICATION LINE)  
WILL SCHROEDER  
435 S 95TH STREET  
MILWAUKEE, WI 53214  
PHONE: 414-379-7522  
EMAIL: WS3060@ATT.COM

CITY OF GLENDALE (SEWER)  
CHARLIE IMIG  
5909 N MILWAUKEE RIVER PARKWAY  
GLENDALE, WI 53209  
PHONE: 414-228-1746  
EMAIL: C.IMIG@GLENDALE-WI.GOV

CITY OF GLENDALE (WATER)  
CHARLIE IMIG  
5909 N MILWAUKEE RIVER PARKWAY  
GLENDALE, WI 53209  
PHONE: 414-228-1746  
EMAIL: C.IMIG@GLENDALE-WI.GOV

EVERSTREAM (COMMUNICATION LINE)  
ABBY STEIN  
324 E WISCONSIN AVENUE, SUITE 730  
MILWAUKEE, WI 53202  
PHONE: 414-442-9427  
EMAIL: ASTEIN@EVERSTREAM.NET

MILWAUKEE METROPOLITAN SEWERAGE DISTRICT (SEWER)  
JEREMY METZ  
260 W SEEBOTH STREET  
MILWAUKEE, WI 53204  
PHONE: 414-225-2241  
EMAIL: JMETZ@MMSD.COM

SPECTRUM (COMMUNICATION LINE)  
BRYAN JANKOWSKI  
1320 N DR. MARTIN LUTHER KING JR DRIVE  
MILWAUKEE, WI 53203  
PHONE: 414-239-5880  
EMAIL: BRYAN.JANKOWSKI@CHARTER.COM

VILLAGE OF BROWN DEER (SEWER)  
MATTHEW MAEDERER  
8717 N 43RD STREET  
BROWN DEER, WI 53209  
PHONE: 414-357-0120  
EMAIL: MMAEDERER@BROWNDDEERWI.ORG

VILLAGE OF BROWN DEER (WATER)  
MIRANDA DURBIN  
4800 W GREEN BROOK DRIVE  
BROWN DEER, WI 53223  
PHONE: 414-374-1903  
MIRANDA.DURBIN@CITYWATERUSA.COM

VILLAGE OF RIVER HILLS (SEWER)  
CRAIG SCHROEDER  
7650 N PHEASANT LANE  
RIVER HILLS, WI 53217  
PHONE: 414-352-0080  
EMAIL: CSCHROEDER@RIVERHILLSWI.GOV

WE ENERGIES (ELECTRICITY)  
LAUREL RICE  
500 S 116TH STREET  
WEST ALLIS, WI 53214  
PHONE: 414-410-5218  
EMAIL: LAUREL.RICE1@WE-ENERGIES.COM

WE ENERGIES (GAS)  
JEANNETTE SCHULTZ  
500 S 116TH STREET  
WEST ALLIS, WI 53214  
PHONE: 414-365-6421  
EMAIL: JEANNETTE.SCHULTZ@WE-ENERGIES.COM

NON-UTILITY CONTACTS

MILWAUKEE COUNTY DOT  
SIGNALS  
DANIEL MURPHY  
10930 W LAPHAM STREET  
WEST ALLIS, WI 53214  
PHONE: 414-257-5934  
EMAIL: DANIEL.MURPHY@MILWAUKEECOUNTYWI.GOV

MILWAUKEE COUNTY DOT  
KEVIN KENT  
HIGHWAY SUPERINTENDENT  
10320 W WATERTOWN PLANK ROAD, 1ST FLOOR  
WAUWATOSA, WI 53226  
PHONE: 262-257-6580  
EMAIL: KEVIN.KENT@MILWAUKEE COUNTYWI.GOV

MILWAUKEE COUNTY DOT  
ANDREA WEDDLE-HENNING  
DIRECTOR OF TRANSPORTATION ENGINEERING  
10930 W LAPHAM STREET  
WEST ALLIS, WI 53214  
PHONE: 414-257-5934  
EMAIL: ANDREA.WEDDLE-HENNING@MILWAUKEE COUNTYWI.GOV

WISDOT  
SINGALS  
JOYCE MURPHY  
PHONE: 262-548-5933  
EMAIL: JOYCE.MURPHY@DOT.WI.GOV



Dial 811 or (800)242-8511  
www.DiggersHotline.com


SEWRPC CONTACT

ANDY TRAEGER (CONSTRUCTION COORDINATOR)  
SOUTHEASTERN WISCONSIN REGIONAL PLANNING COMMISSION  
W239 N1812 ROCKWOOD DRIVE  
P.O. BOX 1607  
WAUKESHA, WI 53187-1607  
(262) 953-4296  
ATRAEGER@SEWRPC.ORG


WISCONSIN DNR LIAISON

RYAN PAPPAS  
SE REGION HEADQUARTERS  
1027 W ST. PAUL AVENUE  
MILWAUKEE, WI 53233  
(414) 750-7495  
RYAN.PAPPAS@WISCONSIN.GOV


| Site | CONSTRUCTION ID | ROUTE   | COUNTY     |
|------|-----------------|---------|------------|
| 2    | 2080-05-71      | LOC STR | MILWAUKEE  |
| 3    | 1090-10-71      | IH 041  | MILWAUKEE  |
| 15   | 2475-08-71      | STH 145 | WASHINGTON |
| 16   | 2370-00-76      | STH 164 | WAUKESHA   |
| 17   | 2565-03-73      | STH 57  | MILWAUKEE  |




SITE 2  
MILWAUKEE COUNTY  
LINCOLN CREEK BRIDGE




SITE 3  
MILWAUKEE COUNTY  
IH 41




SITE 15  
WASHINGTON COUNTY  
STH 145



SITE 16  
WAUKESHA COUNTY  
STH 164



SITE 17  
MILWAUKEE COUNTY  
STH 57





Estimate Of Quantities

3742-03-71

| Line | Item       | Item Description                                              | Unit | Total   | Qty     |
|------|------------|---------------------------------------------------------------|------|---------|---------|
| 0002 | 201.0105   | Clearing                                                      | STA  | 131.000 | 131.000 |
| 0004 | 201.0120   | Clearing                                                      | ID   | 68.000  | 68.000  |
| 0006 | 204.0170   | Removing Fence                                                | LF   | 170.000 | 170.000 |
| 0008 | 213.0100   | Finishing Roadway (project) 01. 3742-03-71                    | EACH | 1.000   | 1.000   |
| 0010 | 616.0600.S | Fence Temporary                                               | LF   | 150.000 | 150.000 |
| 0012 | 618.0100   | Maintenance and Repair of Haul Roads (project) 01. 3742-03-71 | EACH | 1.000   | 1.000   |
| 0014 | 628.1504   | Silt Fence                                                    | LF   | 100.000 | 100.000 |
| 0016 | 628.1520   | Silt Fence Maintenance                                        | LF   | 100.000 | 100.000 |
| 0018 | 628.1905   | Mobilizations Erosion Control                                 | EACH | 5.000   | 5.000   |
| 0020 | 628.1910   | Mobilizations Emergency Erosion Control                       | EACH | 5.000   | 5.000   |
| 0022 | 628.7555   | Culvert Pipe Checks                                           | EACH | 4.000   | 4.000   |
| 0024 | 628.7570   | Rock Bags                                                     | EACH | 5.000   | 5.000   |
| 0026 | 643.1050   | Traffic Control Signs PCMS                                    | DAY  | 100.000 | 100.000 |
| 0028 | SPV.0045   | Special 01. Traffic Control - Lane Closure                    | DAY  | 5.000   | 5.000   |
| 0030 | SPV.0045   | Special 02. Traffic Control - Shoulder Closure                | DAY  | 7.000   | 7.000   |
| 0032 | SPV.0045   | Special 03. Traffic Control - Ramp Closure                    | DAY  | 2.000   | 2.000   |
| 0034 | SPV.0045   | Special 04. Traffic Control - Pedestrian Accommodation        | DAY  | 2.000   | 2.000   |
| 0036 | SPV.0060   | Special 01. Frozen Ground Erosion Control                     | EACH | 1.000   | 1.000   |
| 0038 | SPV.0060   | Special 02. Semi-Frozen Ground Erosion Control                | EACH | 1.000   | 1.000   |
| 0040 | SPV.0060   | Special 03. Thawed Ground Erosion Control                     | EACH | 1.000   | 1.000   |
| 0042 | SPV.0060   | Special 04. Site Mobilization                                 | EACH | 5.000   | 5.000   |
| 0044 | SPV.0060   | Special 05. Semi-Permanent Restoration                        | EACH | 1.000   | 1.000   |

3

3

| TREE REMOVAL |                      |              |        |             |                             |                              |                            |         |
|--------------|----------------------|--------------|--------|-------------|-----------------------------|------------------------------|----------------------------|---------|
| SITE         | LOCATION             | STATION      | TO     | STATION     | OFFSET                      | 201.0105<br>CLEARING<br>STA  | 201.0120<br>CLEARING<br>ID | REMARKS |
| 2            | N TEUTONIA AVE       | 9+10         | -      | 10+90       | LT/RT                       | 2                            | -                          |         |
|              |                      | 11+00        | -      | 11+85       | LT/RT                       | 1                            | -                          |         |
|              |                      | SUBTOTAL     |        | 3           | 0                           | SITE 2 FOR INFORMATION ONLY  |                            |         |
| 3            | IH4 1NB/43 SB/849 WB | 150EW'+05    | -      | 174'EW'+70  | LT/RT                       | 26                           | -                          |         |
|              | IH41 SB/43 NB/894 EB | 230'EWE' +85 | -      | 256'EWE'+72 | LT/RT                       | 28                           | -                          |         |
|              | SUBTOTAL             |              | 54     | 0           | SITE 3 FOR INFORMATION ONLY |                              |                            |         |
| 15           | STH 145              |              | 25+51  |             | LT                          | -                            | 8                          |         |
|              |                      |              | 25+52  |             | LT                          | -                            | 8                          |         |
|              |                      | 45+25        | -      | 46+60       | LT/RT                       | 2                            | -                          |         |
|              |                      |              | 45+53  |             | LT                          | -                            | 12                         |         |
|              |                      | 108+00       | -      | 108+75      | LT/RT                       | 1                            | -                          |         |
|              |                      | 180+25       | -      | 180+50      | LT/RT                       | 1                            | -                          |         |
|              |                      | SUBTOTAL     |        | 4           | 28                          | SITE 15 FOR INFORMATION ONLY |                            |         |
| 16           | STH 164              | 465+50       | -      | 466+25      | LT                          | 2                            | -                          |         |
|              |                      | 486+05       | -      | 489+40      | RT                          | 4                            | -                          |         |
|              |                      | 512+45       | -      | 514+00      | LT/RT                       | 2                            | -                          |         |
|              |                      |              | 514+30 |             | LT                          | -                            | 20                         |         |
|              |                      | 515+00       | -      | 515+50      | RT                          | 2                            | -                          |         |
|              |                      |              | 518+90 |             | LT                          | -                            | 20                         |         |
|              |                      | 520+45       |        | 521+50      | LT                          | 2                            | -                          |         |
|              | PLAINVIEW ROAD       | 598+25       |        | 598+65      | RT                          | 2                            | -                          |         |
|              |                      | 2+00         | -      | 3+00        | LT                          | 1                            | -                          |         |
|              |                      | 3+60         | -      | 4+05        | LT                          | 2                            | -                          |         |
|              |                      | SUBTOTAL     |        | 17          | 40                          | SITE 16 FOR INFORMATION ONLY |                            |         |
| 17           | STH 57               | 31+70        | -      | 32+05       | RT                          | 2                            | -                          |         |
|              |                      | 34+15        | -      | 34+30       | RT                          | 1                            | -                          |         |
|              |                      | 35+95        | -      | 36+60       | RT                          | 2                            | -                          |         |
|              |                      | 37+20        | -      | 37+75       | RT                          | 1                            | -                          |         |
|              |                      | 39+00        | -      | 44+75       | RT                          | 6                            | -                          |         |
|              |                      | 45+10        | -      | 54+05       | RT                          | 10                           | -                          |         |
|              |                      | 55+80        | -      | 64+95       | RT                          | 10                           | -                          |         |
|              |                      | 65+60        | -      | 72+95       | RT                          | 8                            | -                          |         |
|              |                      | 73+85        | -      | 75+25       | LT                          | 3                            | -                          |         |
|              |                      | 94+30        | -      | 96+45       | LT                          | 3                            | -                          |         |
|              |                      | 97+60        | -      | 98+10       | LT                          | 2                            | -                          |         |
|              |                      | 133+50       | -      | 136+85      | LT                          | 4                            | -                          |         |
|              |                      | 138+80       | -      | 138+99      | LT                          | 1                            | -                          |         |
|              |                      | SUBTOTAL     |        | 53          | 0                           | SITE 17 FOR INFORMATION ONLY |                            |         |
|              |                      | TOTAL        |        | 131         | 68                          | TOTAL FOR INFORMATION ONLY   |                            |         |



3

| TRAFFIC CONTROL |                                           |                                                  |                                                      |                                                  |                                           |
|-----------------|-------------------------------------------|--------------------------------------------------|------------------------------------------------------|--------------------------------------------------|-------------------------------------------|
|                 | 643.1050<br>TRAFFIC CONTROL<br>SIGNS PCMS | SPV.0045.01<br>TRAFFIC CONTROL -<br>LANE CLOSURE | SPV.0045.02<br>TRAFFIC CONTROL -<br>SHOULDER CLOSURE | SPV.0045.03<br>TRAFFIC CONTROL -<br>RAMP CLOSURE | SPV.0045.04<br>PEDESTRIAN<br>ACCOMODATION |
| SITE            | DAY                                       | DAY                                              | DAY                                                  | DAY                                              | DAY                                       |
| 2               | -                                         | 2                                                | -                                                    | -                                                | 2                                         |
| 3               | -                                         | 2                                                | 2                                                    | 2                                                | -                                         |
| 15              | -                                         | 1                                                | 1                                                    | -                                                | -                                         |
| 16              | -                                         | -                                                | 2                                                    | -                                                | -                                         |
| 17              | -                                         | -                                                | 2                                                    | -                                                | -                                         |
| UNDISTRIBUTED   | 100                                       | -                                                | -                                                    | -                                                | -                                         |
| TOTAL           | 100                                       | 5                                                | 7                                                    | 2                                                | 2                                         |

\*FOR INFORMATION ONLY

| MISCELLANEOUS |                            |                                                       |                                  |                                 |
|---------------|----------------------------|-------------------------------------------------------|----------------------------------|---------------------------------|
|               | 204.0170<br>REMOVING FENCE | 213.0100.01<br>FINISHING ROADWAY (01. 3742-03-<br>70) | 616.0600.S<br>FENCE<br>TEMPORARY | SPV.0060.04<br>SITE MOBLIZATION |
| SITE          | LF                         | EACH                                                  | LF                               | EACH                            |
| 2             | -                          | -                                                     | -                                | 1                               |
| 3             | 150                        | -                                                     | 150                              | 1                               |
| 15            | -                          | -                                                     | -                                | 1                               |
| 16            | -                          | -                                                     | -                                | 1                               |
| 17            | 20                         | -                                                     | -                                | 1                               |
| UNDISTRIBUTED | -                          | 1                                                     | -                                | -                               |
| TOTAL         | 170                        | 1                                                     | 150                              | 5                               |

\*FOR INFORMATION ONLY

3


| EROSION CONROL |                        |                                       |                                                |                                                             |                                    |                       |                                                 |                                                         |                                                    |                                              |
|----------------|------------------------|---------------------------------------|------------------------------------------------|-------------------------------------------------------------|------------------------------------|-----------------------|-------------------------------------------------|---------------------------------------------------------|----------------------------------------------------|----------------------------------------------|
|                | 628.1504<br>SILT FENCE | 628.1520<br>SILT FENCE<br>MAINTENANCE | 628.1905<br>MOBLIZATIONS<br>EROSION<br>CONTROL | 628.1910<br>MOBLIZATIONS<br>EMERGENCY<br>EROSION<br>CONTROL | 628.7555<br>CULVERT PIPE<br>CHECKS | 628.7570<br>ROCK BAGS | SPV.0060.01<br>FROZEN GROUND<br>EROSION CONTROL | SPV.0060.02<br>SEMI-FROZEN<br>GROUND EROSION<br>CONTROL | SPV.0060.03<br>THAWED<br>GROUND EROSION<br>CONTROL | SPV.0060.05<br>SEMI-PERMANENT<br>RESTORATION |
| SITE           | LF                     | LF                                    | EACH                                           | EACH                                                        | EACH                               | EACH                  | EACH                                            | EACH                                                    | EACH                                               | EACH                                         |
| 2              | -                      | -                                     | 1                                              | -                                                           | -                                  | -                     | -                                               | -                                                       | -                                                  | -                                            |
| 3              | -                      | -                                     | 1                                              | -                                                           | -                                  | -                     | -                                               | -                                                       | -                                                  | -                                            |
| 15             | -                      | -                                     | 1                                              | -                                                           | 4                                  | -                     | -                                               | -                                                       | -                                                  | 1                                            |
| 16             | -                      | -                                     | 1                                              | -                                                           | -                                  | -                     | -                                               | -                                                       | -                                                  | -                                            |
| 17             | -                      | -                                     | 1                                              | -                                                           | -                                  | -                     | -                                               | -                                                       | -                                                  | -                                            |
| UNDISTRIBUTED  | 100                    | 100                                   | -                                              | 5                                                           | -                                  | 5                     | 1*                                              | 1*                                                      | 1*                                                 | -                                            |
| TOTAL 0010     | 100                    | 100                                   | 5                                              | 5                                                           | 4                                  | 5                     | 1*                                              | 1*                                                      | 1*                                                 | 1                                            |


\*DEPENDENT ON FIELD CONDITIONS; ONE EROSION CONTROL ITEM PAID PER SITE

\*FOR INFORMATION ONLY


| MAXIMUM, EXPECTED, AND MINIMUM QUANTITIES |          |          |                |                 |            |                        |                               |                                         |                     |           |                            |                                |                                    |
|-------------------------------------------|----------|----------|----------------|-----------------|------------|------------------------|-------------------------------|-----------------------------------------|---------------------|-----------|----------------------------|--------------------------------|------------------------------------|
|                                           | 201.0105 | 201.0120 | 204.0170       | 616.0600.S      | 628.1504   | 628.1520               | 628.1905                      | 628.1910                                | 628.7555            | 628.7570  | 643.1050                   | SPV.0045.01                    | SPV.0045.02                        |
|                                           | CLEARING | CLEARING | REMOVING FENCE | FENCE TEMPORARY | SILT FENCE | SILT FENCE MAINTENANCE | MOBILIZATIONS EROSION CONTROL | MOBILIZATIONS EMERGENCY EROSION CONTROL | CULVERT PIPE CHECKS | ROCK BAGS | TRAFFIC CONTROL SIGNS PCMS | TRAFFIC CONTROL - LANE CLOSURE | TRAFFIC CONTROL - SHOULDER CLOSURE |
|                                           | STA      | ID       | LF             | LF              | LF         | LF                     | EACH                          | EACH                                    | EACH                | EACH      | DAY                        | DAY                            | DAY                                |
| MINIMUM                                   | 20       | 10       | 75             | 75              | 0          | 0                      | 2                             | 0                                       | 0                   | 0         | 0                          | 4                              | 2                                  |
| EXPECTED                                  | 131      | 68       | 170            | 150             | 100        | 100                    | 5                             | 5                                       | 4                   | 5         | 100                        | 5                              | 7                                  |
| MAXIMUM                                   | 250      | 200      | 500            | 500             | 200        | 200                    | 6                             | 6                                       | 6                   | 6         | 200                        | 12                             | 10                                 |

| MAXIMUM, EXPECTED, AND MINIMUM QUANTITIES |                                |                                            |                               |                                    |                               |                   |                            |
|-------------------------------------------|--------------------------------|--------------------------------------------|-------------------------------|------------------------------------|-------------------------------|-------------------|----------------------------|
|                                           | SPV.0045.03                    | SPV.0045.04                                | SPV.0060.01                   | SPV.0060.02                        | SPV.0060.03                   | SPV.0060.04       | SPV.0060.05                |
|                                           | TRAFFIC CONTROL - RAMP CLOSURE | TRAFFIC CONTROL - PEDESTRIAN ACCOMMODATION | FROZEN GROUND EROSION CONTROL | SEMI-FROZEN GROUND EROSION CONTROL | THAWED GROUND EROSION CONTROL | SITE MOBILIZATION | SEMI-PERMANENT RESTORATION |
| LOCATION                                  | DAY                            | DAY                                        | EACH                          | EACH                               | EACH                          | EACH              | EACH                       |
| MINIMUM                                   | 1                              | 1                                          | 0                             | 0                                  | 0                             | 1                 | 0                          |
| EXPECTED                                  | 2                              | 2                                          | 1                             | 1                                  | 1                             | 5                 | 1                          |
| MAXIMUM                                   | 5                              | 5                                          | 10                            | 10                                 | 10                            | 10                | 10                         |









\*FOR INFORMATION ONLY


5



5

|                        |            |                   |                         |          |   |
|------------------------|------------|-------------------|-------------------------|----------|---|
| PROJECT NO: 3742-03-71 | HWY: IH 41 | COUNTY: MILWAUKEE | CLEARING PLANS - SITE 3 | SHEET 18 | E |
|------------------------|------------|-------------------|-------------------------|----------|---|






5





















- LEGEND
- INDIVIDUAL TREES TO BE REMOVED
  - CLUSTER OF TREES TO BE REMOVED

\*FOR INFORMATION ONLY






\*FOR INFORMATION ONLY



5

5





\*FOR INFORMATION ONLY

\*FOR INFORMATION ONLY

LEGEND



INDIVIDUAL TREES TO BE REMOVED



CLUSTER OF TREES TO BE REMOVED



WELL

PROPOSED R/W

EXISTING R/W

EXISTING R/W

BERM

NGIS.®

EXISTING R/W

EXISTING R/W

WELL

SEP V

|             |            |
|-------------|------------|
| PROJECT NO: | 3742-03-71 |
|-------------|------------|

HWY: STH 164

COUNTY: WAUKESHA

CLEARING PLANS - SITE 16

SHEET

28

E

FILE NAME : N:\PDS\C3D\23700005\SHEETSOTHER\23700076\_TREECLEARING.DWG  
LAYOUT NAME - 06

PLOT DATE : 6/11/2026 10:51 AM

PLOT BY : MARSHALL, DAWN L

PLOT NAME :

PLOT SCALE : 1 IN:40 FT


WISDOT/CADDS SHEET 44



\*FOR INFORMATION ONLY

LEGEND

- INDIVIDUAL TREES TO BE REMOVED
- CLUSTER OF TREES TO BE REMOVED



PROJECT NO: 3742-03-71

HWY: STH 164



COUNTY: WAUKESHA



CLEARING PLANS - SITE 16

SHEET



29

E





|             |            |             |                   |                          |       |    |   |
|-------------|------------|-------------|-------------------|--------------------------|-------|----|---|
| PROJECT NO: | 3742-03-71 | HWY: STH 57 | COUNTY: MILWAUKEE | CLEARING PLANS - SITE 17 | SHEET | 31 | E |
|-------------|------------|-------------|-------------------|--------------------------|-------|----|---|






Standard Detail Drawing List

|           |                                                                                  |
|-----------|----------------------------------------------------------------------------------|
| 08E09-06  | SILT FENCE                                                                       |
| 08E15-01  | CULVERT PIPE CHECK                                                               |
| 15C02-10D | ON RAMP LANE CLOSURE                                                             |
| 15C02-10E | OFF RAMP LANE CLOSURE                                                            |
| 15C02-10G | TRAFFIC CONTROL FOR ENTRANCE RAMP CLOSURE                                        |
| 15C12-09A | TRAFFIC CONTROL FOR LANE CLOSURE WITH FLAGGING OPERATION                         |
| 15D12-16A | TRAFFIC CONTROL, LANE CLOSURE                                                    |
| 15D16-07  | TRAFFIC CONTROL, EXIT RAMP CLOSURE                                               |
| 15D27-05  | TRAFFIC CONTROL, SHOULDER CLOSURE ON DIVIDED ROADWAY, SPEEDS GREATER THAN 40 MPH |
| 15D28-05  | TRAFFIC CONTROL, WORK ON SHOULDER OR PARKING LANE, UNDIVIDED ROADWAY             |
| 15D30-12C | TRAFFIC CONTROL, PEDESTRIAN ACCOMMODATION                                        |
| 15D30-12K | TRAFFIC CONTROL, PEDESTRIAN ACCOMMODATION                                        |
| 15D49-05  | TRAFFIC CONTROL, SYSTEM RAMP CLOSURE                                             |





- ① HORIZONTAL BRACE REQUIRED WITH 2" X 4" WOODEN FRAME OR EQUIVALENT AT TOP OF POSTS.
- ② FOR MANUAL INSTALLATIONS THE TRENCH SHALL BE A MINIMUM OF 4" WIDE & 6" DEEP TO BURY AND ANCHOR THE GEOTEXTILE FABRIC. FOLD MATERIAL TO FIT TRENCH AND BACKFILL & COMPACT TRENCH WITH EXCAVATED SOIL.
- ③ WOOD POSTS SHALL BE A MINIMUM SIZE OF 1½" X 1½" OF OAK OR HICKORY.
- ④ SILT FENCE TO EXTEND ACROSS THE TOP OF THE PIPE.
- ⑤ CONSTRUCT SILT FENCE FROM A CONTINUOUS ROLL IF POSSIBLE BY CUTTING LENGTHS TO AVOID JOINTS. IF A JOINT IS NECESSARY USE ONE OF THE FOLLOWING TWO METHODS; A) OVERLAP THE END POSTS AND TWIST, OR ROTATE, AT LEAST 180 DEGREES, B) HOOK THE END OF EACH SILT FENCE LENGTH.




**SILT FENCE**


STATE OF WISCONSIN  
DEPARTMENT OF TRANSPORTATION

APPROVED  
4-29-05 /S/ Beth Connolly  
DATE CHIEF ROADWAY DEVELOP 35 INEER

FHWA



END VIEW



SIDE VIEW

**CULVERT PIPE CHECK**  
(INSTALL ON INLET END ONLY)

| CULVERT PIPE CHECK                                 |                                           |    |
|----------------------------------------------------|-------------------------------------------|----|
| STATE OF WISCONSIN<br>DEPARTMENT OF TRANSPORTATION |                                           |    |
| APPROVED<br>May 2019<br>DATE                       | /S/ Daniel Schave<br>EROSION CONTROL ENGI | 36 |





THIS DRAWING PROVIDES GENERAL GUIDANCE ON TYPICAL "TO" MO-4 SIGN LAYOUT AND SPACING. SEE PROJECT TO SIGNING SHEETS FOR SPECIFIC DETAILS FOR EACH PROJECT.

## LEGEND



## SIGN ON PERMANENT SUPPORT

PCMS

## PORTABLE CHANGEABLE MESSAGE SIGN

**TO** MO4 - 5



M1 - 4

C



M1 - 6

OF



M1 - 5A



M05 - 1

PK



105 - 2

1



MO6 -



MO6 -



MO6 -

## GENERAL NOTES

SEE SDD 15D16 "TRAFFIC CONTROL, EXIT RAMP CLOSURE" DETAIL FOR  
TRAFFIC CONTROL AT EXIT RAMP CLOSURE.

THE EXACT NUMBER, LOCATION AND SPACING OF ALL SIGNS SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER

IF THERE ARE ANY ROUTE MARKER ASSEMBLIES THAT WILL REMAIN IN PLACE, ADJUST THE LOCATION OF THE "TO" MO-4 ROUTE SIGNS TO CORRESPOND WITH THE EXISTING ASSEMBLIES. SEE SPECIFIC PROJECT TO SIGNING DETAIL SHEETS. MODIFY EXISTING SIGNS WHERE POSSIBLE.

THE SPACING BETWEEN TRAFFIC CONTROL AND "TO" MO-4 SIGNS SHOULD BE ADJUSTED TO NOT CONFLICT WITH AND TO PROVIDE A DESIRABLE MINIMUM OF 200 FEET CLEARANCE TO EXISTING SIGNS THAT WILL REMAIN IN PLACE.

ANY SIGNS TEMPORARY OR EXISTING, WHICH CONFLICT WITH TRAFFIC CONTROL "IN USE" SHALL BE REMOVED OR COVERED AS NEEDED AND AS APPROVED BY THE ENGINEER.

SIGNS THAT SHALL BE IN PLACE LESS THAN 7 CONTINUOUS DAYS AND NIGHTS MAY BE MOUNTED ON PORTABLE SUPPORTS.

"MO" SIGNS ARE THE SAME AS "M" SIGNS EXCEPT THE BACKGROUND IS ORANGE.

SIGN SIZES SHALL BE AS FOLLOW:

MO4 - 5 SHALL BE 24" X 12". (36" X 18" IF NEEDED TO MATCH EXISTING SIGNS).

M1 - 4, M1 - 5A, AND M1 - 6 SHALL BE 24" X 24" (36" X 36" IF NEEDED TO MATCH EXISTING SIGNS).

MO5 - 1, MO5 - 2, AND MO6 - 1, SHALL BE 21" X 21". (30" X 30" IF NEEDED TO MATCH EXISTING SIGNS).

① ONLY ADD IF THERE ARE NO EXISTING ROUTE MARKERS FOR THE INTERSECTING ROADWAY.

6

**SDD 15C02-10e**

6

**SDD 15C02-10e**

## OFF RAMP LANE CLOSURE

STATE OF WISCONSIN  
DEPARTMENT OF TRANSPORTATION

APPROVED  
November 2025  
DATE


/S/ Andrew Heidtke  
WORK ZONE ENGINEER

FHWA

38

LEGEND

- TRAFFIC CONTROL DRUM
- ☼ TRAFFIC CONTROL DRUM WITH TYPE "C" STEADY BURN LIGHT
- ↑ TYPE III BARRICADE
- ↑↓ TYPE III BARRICADE WITH ATTACHED SIGN
- ▮ SIGN ON PERMANENT SUPPORT
- ┌ SIGN ON TEMPORARY SUPPORT
- DIRECTION OF TRAFFIC



TRAFFIC CONTROL FOR ENTRANCE RAMP CLOSURE

TRAFFIC CONTROL NOTES

THE EXACT NUMBER, LOCATION AND SPACING OF ALL SIGNS AND DEVICES SHALL BE ADJUSTED TO FIT THE FIELD CONDITIONS AS APPROVED BY THE ENGINEER.

THE SPACING BETWEEN TRAFFIC CONTROL AND TO SIGNS SHOULD BE ADJUSTED TO NOT CONFLICT WITH AND TO PROVIDE A DESIRABLE MINIMUM OF 200 FEET CLEARANCE TO EXISTING SIGNS THAT WILL REMAIN IN PLACE.

ANY SIGNS TEMPORARY OR EXISTING, WHICH CONFLICT WITH THE TRAFFIC CONTROL "IN USE" SHALL BE REMOVED OR COVERED AS NEEDED AND AS APPROVED BY THE ENGINEER.

SIGNS THAT SHALL BE IN PLACE LESS THAN 7 CONTINUOUS DAYS AND NIGHTS MAY BE MOUNTED ON PORTABLE SUPPORTS.

SIGN SIZES SHALL BE AS FOLLOWS:

- M3-X SHALL BE 24"x24" (36" x18" IF NEEDED TO MATCH EXISTING SIGNS)
- M1-1, M1-4, AND M1-6 SHALL BE 24"x24" (36"x36" IF NEEDED TO MATCH EXISTING SIGNS)
- W20-53A SHALL BE 48"x48"

\* PLACE "RAMP CLOSED BEGINNING" SIGN 7 CALENDAR DAYS PRIOR TO CLOSURE OR AS DIRECTED BY THE ENGINEER. SEE WISCONSIN STANDARD SIGN PLATES FOR LAYOUT.

TRAFFIC CONTROL FOR ENTRANCE RAMP CLOSURE

STATE OF WISCONSIN  
DEPARTMENT OF TRANSPORTATION

APPROVED  
November 2025 /S/ Andrew Heidtke  
DATE WORK ZONE ENGINEER

FHWA

|                                                                                   |                                                                   |
|-----------------------------------------------------------------------------------|-------------------------------------------------------------------|
|  | SIGN ON PORTABLE OR PERMANENT SUPPORT                             |
|  | TEMPORARY PORTABLE RUMBLE STRIP ARRAY                             |
|  | DIRECTION OF TRAFFIC                                              |
|  | WORK AREA                                                         |
|  | FLAGGER, EQUIPPED WITH STOP/SLOW PADDLE FASTENED ON SUPPORT STAFF |

DETAILS OF TRAFFIC CONTROL DEVICES AND INSTALLATION NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS, THE SPECIAL PROVISIONS, AND THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.

ALL SIGNS ARE 48" X 48" UNLESS OTHERWISE NOTED.

"WO" SIGNS ARE THE SAME AS "W" SIGNS EXCEPT THE BACKGROUND IS ORANGE.

THE EXACT NUMBER, LOCATION AND SPACING OF ALL SIGNS, DEVICES, AND LOCATION OF ALL FLAGGERS SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.

THE FIRST ADVANCE WARNING SIGN SHOULD TYPICALLY BE LOCATED IN ADVANCE OF THE ANTICIPATED TRAFFIC BACKUP OR QUEUE.

WHEN A SIDE ROAD OR RAMP INTERSECTS THE FACILITY ON WHICH THE WORK IS BEING PERFORMED, ADDITIONAL TRAFFIC CONTROLS SHALL BE PROVIDED AS SPECIFIED IN THE PLANS AND/OR THE SPECIAL PROVISIONS OR AS APPROVED BY THE ENGINEER.

FLAGGERS SHALL BE IN SIGHT OF EACH OTHER OR IN DIRECT COMMUNICATION AT ALL TIMES. THEY SHALL BE EQUIPPED WITH STOP/SLOW PADDLES FASTENED ON SUPPORT STAFFS. WHEN THE FLAGGING OPERATION IS NOT IN EFFECT REMOVE TEMPORARY PORTABLE RUMBLE STRIPS PRIOR TO COVERING OR REMOVING ALL ADVANCE SIGNING.

- ① FOR MOVING WORK OPERATIONS, POST ADDITIONAL W20-7A FLAGGER SIGNS AT APPROXIMATELY 3,500' INTERVALS IN THE MOVING WORK OPERATION OR AS APPROVED BY THE ENGINEER.
- ② SIGN NOT REQUIRED IF FLAGGING OPERATION OCCURS WITHIN A SIGNED ROAD WORK ZONE AREA.

WHEN THE DISTANCE BETWEEN FLAGGERS EXCEEDS 2 MILES, A PILOT CAR IS REQUIRED. WHEN CURVES REDUCE SIGHT DISTANCE BELOW 400', A PILOT CAR IS REQUIRED.

UTILIZE TEMPORARY PORTABLE RUMBLE STRIPS ON ALL FLAGGING OPERATIONS.


③ EACH TEMPORARY PORTABLE RUMBLE STRIP ARRAY CONSISTS OF THREE RUMBLE STRIPS PLACED TRANSVERSE ACROSS THE LANE AT THE LOCATIONS SHOWN. WITHIN EACH ARRAY, SPACING BETWEEN RUMBLE STRIPS SHALL BE 15 FEET ON CENTER

ONLY USE TEMPORARY PORTABLE RUMBLE STRIPS FROM THE APPROVED PRODUCTS LIST.

INSTALL TEMPORARY RUMBLE STRIPS PER MANUFACTURER'S RECOMMENDATIONS.

PLACE ADVANCE SIGNING PRIOR TO INSTALLING TEMPORARY RUMBLE STRIPS.

DO NOT INSTALL TEMPORARY PORTABLE RUMBLE STRIPS ON GRAVEL, MILLED SURFACES, OR ASPHALT THAT HAS BEEN PAVED LESS THAN 12 HOURS.



APPROVED  
May 2022  
DATE

/S/ Andrew Heidtke  
WORK ZONE ENGINEER

40

FHWA

GENERAL NOTES

THE EXACT NUMBER, LOCATION, AND SPACING OF ALL SIGNS AND DEVICES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.

THE SPACING BETWEEN SIGNS SHOULD BE ADJUSTED TO NOT CONFLICT WITH AND TO PROVIDE A MINIMUM OF 200 FEET (500 FEET DESIRABLE) CLEARANCE TO EXISTING SIGNS.

THIS LANE CLOSURE IS TYPICAL FOR CLOSING RIGHT LANE - REVERSE FOR CLOSING LEFT LANE.

ALL SIGNS ARE 48" x 48" UNLESS OTHERWISE NOTED.

"WO" IS THE SAME AS "W" EXCEPT THE BACKGROUND IS ORANGE.

ANY SIGNS TEMPORARY OR EXISTING, WHICH CONFLICT WITH TRAFFIC CONTROL "IN USE" SHALL BE REMOVED OR COVERED AS NEEDED OR AS APPROVED BY THE ENGINEER.

FOR A LANE CLOSURE THAT IS IN PLACE LESS THAN 7 CONTINUOUS DAYS AND NIGHTS, THE ADVANCED WARNING SIGNS MAY BE MOUNTED ON PORTABLE SUPPORTS.

REMOVE PAVEMENT MARKINGS AND PLACE TEMPORARY PAVEMENT MARKING LINE IF LANE CLOSURE IS TO BE IN PLACE 4 OR MORE CONTINUOUS DAYS AND NIGHTS.

IF THE HORIZONTAL ALIGNMENT IS SUCH THAT A CURVE MAY REQUIRE ADDITIONAL DELINEATION, THE DEVICE SPACING MAY BE DECREASED TO 50 FEET.

WARNING LIGHTS ARE NOT REQUIRED IF THE LANE CLOSURE IS A DAYTIME ONLY OPERATION.


ADJUSTMENTS IN BUFFER SPACE NEED TO BE INCORPORATED WHEN THE LANE CLOSURE OCCURS NEAR AN INTERCHANGE EXIT OR ENTRANCE RAMP OR INTERSECTION. THE LANE CLOSURE MUST TAKE PLACE FAR ENOUGH IN ADVANCE OF AN EXIT OR ENTRANCE RAMP TO STILL ALLOW FOR ADEQUATE BUFFER SPACE. THE MINIMUM LENGTH OF THE BUFFER SPACE BEFORE AN EXIT RAMP SHOULD BE ONE HALF THE LENGTH OF THE TRANSITION AREA. THE ENTRANCE RAMP SHOULD BE FOLLOWED BY THE ORIGINAL BUFFER SPACE LENGTH OF 800 FEET DESIRABLE PRIOR TO ANOTHER TRAFFIC CONTROL CHANGE SUCH AS A CROSSOVER MANEUVER.

CONSIDER ROADWAY GEOMETRICS WHEN LOCATING SIGNS AND ARROW BOARD SO THE DRIVER HAS A CLEAR VIEW OF THE ARROW BOARD AND LANE CLOSURE DRUMS.

① DRUMS IN A CLOSED LANE THAT MUST BE MOVED FOR A WORK OPERATION SHALL BE IMMEDIATELY REESTABLISHED UPON COMPLETION OF THE OPERATION, OR FOR CONTINUING OPERATIONS, AT THE END OF EACH WORKING DAY.

LEGEND

- SIGN ON PERMANENT SUPPORT
- TRAFFIC CONTROL DRUM
- TRAFFIC CONTROL DRUM WITH TYPE "C" STEADY BURN LIGHT
- TYPE III BARRICADE WITH ATTACHED SIGN
- TYPE "A" WARNING LIGHT (FLASHING)
- REMOVING PAVEMENT MARKINGS
- DIRECTION OF TRAFFIC
- WORK AREA
- CONNECTED ARROW BOARD
- WZ START LOCATION MARKER
- WZ END LOCATION MARKER




TRAFFIC CONTROL  
LANE CLOSURE

STATE OF WISCONSIN  
DEPARTMENT OF TRANSPORTATION

APPROVED  
November 2025 /S/ Andrew Heidtke  
DATE ROADWAY STANDARDS DEVELOPMENT UNIT SUPERVISOR

FHWA



- LEGEND**
- TYPE III BARRICADE
  - TYPE III BARRICADE WITH ATTACHED SIGN
  - TRAFFIC CONTROL DRUM
  - SIGN ON PERMANENT SUPPORT
  - TYPE "A" WARNING LIGHT (FLASHING)
  - DIRECTION OF TRAFFIC

**GENERAL NOTES**

THIS RAMP CLOSURE DETAIL IS TYPICAL FOR CLOSING A RIGHT SIDE EXIT RAMP. FOR A LEFT SIDE EXIT RAMP, REVERSE THE TRAFFIC CONTROL.

THE EXACT NUMBER, LOCATION, AND SPACING OF ALL SIGNS AND DEVICES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.

THE SPACING BETWEEN TRAFFIC CONTROL SIGNS SHOULD BE ADJUSTED TO NOT CONFLICT WITH AND SHOULD PROVIDE A MINIMUM OF 200 FEET (500 FEET DESIRABLE) CLEARANCE TO EXISTING SIGNS THAT WILL REMAIN IN PLACE.

ALL SIGNS ARE 48" X 48" UNLESS OTHERWISE NOTED.

SIGNS THAT WILL BE IN PLACE LESS THAN 7 CONTINUOUS DAYS AND NIGHTS MAY BE MOUNTED ON PORTABLE SUPPORTS.

ANY SIGNS, TEMPORARY OR EXISTING, WHICH CONFLICT WITH TRAFFIC CONTROL "IN USE" SHALL BE REMOVED OR COVERED AS NEEDED AND AS APPROVED BY THE ENGINEER.

PLACE TEMPORARY PAVEMENT MARKING LINE IF RAMP CLOSURE IS TO BE IN PLACE 4 OR MORE CONTINUOUS DAYS AND NIGHTS.

WORK AREAS WITH A DROP OFF ALONG THE EDGE OF AN OPEN TRAVEL LANE SHALL BE LEVELED WITH TEMPORARY FILL WHEN THE CONTRACTOR IS NOT WORKING ADJACENT TO THE TRAVEL LANE. DRUMS SHALL BE PLACED ENTIRELY OUTSIDE THE TRAVEL LANE, ALLOWING THE FULL UNOBSTRUCTED LANE WIDTH, WHEN WORK IS NOT IN PROGRESS.

WHERE MEDIAN BARRIER IS IN PLACE, SIGNS SHOWN ON LEFT SIDE OF ROADWAY MAY BE OMITTED FOR RIGHT SIDE RAMP CLOSURES OF LESS THAN 12 - HOUR DURATION.

① W20 - 1A AND G20 - 2A SIGNS ARE NOT REQUIRED IF THE RAMP CLOSURE IS WITHIN A LARGER WORK ZONE WHERE THESE SIGNS ARE ALREADY PRESENT.

② PLACE "RAMP CLOSED BEGINNING" SIGN OR PCMS 7 CALENDAR DAYS PRIOR TO CLOSURE OR AS DIRECTED BY THE ENGINEER. SEE WISCONSIN STANDARD SIGN PLATES FOR SIGN LAYOUT.

| RAMP CLOSED BEGINNING<br>XXX - XX |                    |
|-----------------------------------|--------------------|
| G20 - 58<br>OR<br>PCMS MESSAGING  |                    |
| FRAME 1                           | FRAME 2            |
| RAMP<br>TO<br>CLOSE               | XXXDAY<br>XX XX XX |

| TRAFFIC CONTROL,<br>EXIT RAMP CLOSURE              |                                  |
|----------------------------------------------------|----------------------------------|
| STATE OF WISCONSIN<br>DEPARTMENT OF TRANSPORTATION |                                  |
| APPROVED<br>November 2025<br>DATE                  | /S/ Andrew Heidtke<br><position> |
| FHWA                                               |                                  |



LEGEND

-  SIGN ON PERMANENT SUPPORT
-  TRAFFIC CONTROL DRUM
-  DIRECTION OF TRAFFIC
-  CONNECTED ARROW BOARD
-  WORK AREA
-  WZ START LOCATION MARKER
-  WZ END LOCATION MARKER

GENERAL NOTES

THIS DETAIL IS TYPICAL FOR CLOSING THE RIGHT SHOULDER. FOR CLOSING THE LEFT SHOULDER, REVERSE THE TRAFFIC CONTROL.

THIS DETAIL MAY BE USED FOR DIVIDED ROADWAYS WITH ANY NUMBER OF TRAVEL LANES.

ALL SIGNS ARE 48"X48" UNLESS OTHERWISE NOTED.

ANY SIGNS TEMPORARY OR EXISTING, WHICH CONFLICT WITH THE TRAFFIC CONTROL "IN USE" SHALL BE REMOVED OR COVERED AS NEEDED AND AS APPROVED BY THE ENGINEER.

THE EXACT NUMBER, LOCATION, AND SPACING OF ALL SIGNS AND DEVICES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.

WHEN A RAMP OR SIDE ROAD INTERSECTS THE FACILITY ON WHICH THE WORK IS BEING PERFORMED, ADDITIONAL TRAFFIC CONTROLS SHALL BE PROVIDED AS SPECIFIED IN THE PLANS AND/OR SPECIAL PROVISIONS OR AS APPROVED BY THE ENGINEER.


CHANNELIZING DEVICES PLACED ADJACENT TO WORK AREA SHALL BE PULLED BACK FROM THE TRAVEL LANE WHEN WORK IS NOT IN PROGRESS.

SIGNS THAT WILL BE IN PLACE LESS THAN 7 CONTINUOUS DAYS AND NIGHTS MAY BE MOUNTED ON PORTABLE SUPPORTS.

SIGN LAYOUTS SHALL BE IN ACCORDANCE WITH THE FHWA'S MANUAL OF STANDARD HIGHWAY SIGNS OR THE WISCONSIN STANDARD SIGN PLATES.

① FOR SHORT DURATION SHOULDER WORK OF LESS THAN ONE HOUR THE W21-5A SIGN MAY BE OMITTED.

② IF ALREADY PRESENT WITHIN PROJECT , DO NOT INCLUDE ADDITIONAL DEVICE.



**TRAFFIC CONTROL,  
SHOULDER CLOSURE ON  
DIVIDED ROADWAY, SPEEDS  
GREATER THAN 40 MPH**

STATE OF WISCONSIN  
DEPARTMENT OF TRANSPORTATION

APPROVED  
Noveber 2025  
DATE

/S/ Andrew Heidtke  
STATEWIDE WORK ZONE TRAFFIC  
SAFETY ENGINEER

FHWA

-  SIGN ON PERMANENT SUPPORT
-  TRAFFIC CONTROL DRUM
-  DIRECTION OF TRAFFIC
-  WORK ZONE

ALL SIGNS ARE 48"X48" UNLESS OTHERWISE NOTED. IF NECESSARY DUE TO SPACE CONSTRAINTS IN URBAN AREAS, 36" X 36" SIGNS MAY BE USED IF APPROVED BY THE REGIONAL TRAFFIC UNIT.

"WO" SIGN IS THE SAME AS "W" SIGN EXCEPT THE BACKGROUND IS ORANGE.


ANY SIGNS TEMPORARY OR EXISTING, WHICH CONFLICT WITH THE TRAFFIC CONTROL "IN USE" SHALL BE REMOVED OR COVERED AS NEEDED AND AS APPROVED BY THE ENGINEER.

THE EXACT NUMBER, LOCATION, AND SPACING OF ALL SIGNS AND DEVICES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.

CHANNELIZING DEVICES PLACED ADJACENT TO WORK AREA SHALL BE PULLED BACK FROM THE TRAVEL LANE WHEN WORK IS NOT IN PROGRESS.

SIGNS THAT WILL BE IN PLACE LESS THAN 7 CONTINUOUS DAYS AND NIGHTS MAY BE MOUNTED ON PORTABLE SUPPORTS.



W20-1A AND G20-2A SIGNS ARE NOT REQUIRED IF THE WORK AREA IS WITHIN A LARGER WORK ZONE WHERE THESE SIGNS ARE ALREADY PRESENT. G20-2A SIGNS MAY ALSO BE OMITTED IF DURATION OF WORK IS LESS THAN 7 CONTINUOUS DAYS AND NIGHTS.



APPROVED  
November 2025  
DATE

/S/ ANDREW HEIDTKE  
STATEWIDE WORK ZONE TRAFFIC  
SAFETY ENGINEER





**TEMPORARY CURB RAMP PERPENDICULAR TO CURB**

## GENERAL NOTES

CURB RAMPS SHALL BE 48" MINIMUM WIDTH WITH A FIRM, STABLE AND SLIP RESISTANT SURFACE.

ALTERNATE SIDEWALK WORK BETWEEN LEFT AND RIGHT SIDE OF ROADWAY TO MAINTAIN PEDESTRIAN ACCESS.

CURB RAMPS AND LANDINGS SHALL HAVE A 1:48 (2.1%) MAX. CROSS-SLOPE.

CLEAR SPACE OF 48" X 48" SHALL BE PROVIDED ABOVE AND BELOW THE CURB RAMP.


LATERAL JOINTS OR GAPS BETWEEN SURFACES SHALL BE LESS THAN ½" WIDTH.

CHANGES BETWEEN SURFACE HEIGHTS SHALL NOT EXCEED ½". LATERAL EDGES MAY BE VERTICAL UP TO ¼" HIGH AND SHALL BE BEVELED AT 1:2 BETWEEN ¼" AND ½".

- ① INSTALL CONTRASTING TEMPORARY DETECTABLE WARNING FIELD AT PEDESTRIAN STREET CROSSINGS, AS SHOWN IN THE PLANS
- ② PROTECTIVE EDGING WITH A 2" MIN. HEIGHT SHALL BE INSTALLED WHEN A CURB RAMP OR LANDING PLATFORM HAS A VERTICAL DROP OF 6" OR GREATER OR HAS A SIDE APRON SLOPE STEEPER THAN 1:3 (33%). PROTECTIVE EDGING SHOULD BE CONSIDERED WHEN CURB RAMPS OR LANDING PLATFORMS HAVE A VERTICAL DROP OF 3" OR MORE.
- ③ DETECTABLE EDGING WITH 6" MIN. HEIGHT AND CONTRASTING COLOR SHALL BE INSTALLED ON ALL CURB RAMP LANDINGS WHERE THE WALKWAY CHANGES DIRECTION (TURNS).
- ④ DO NOT RESTRICT WATER FLOW IN THE GUTTER SYSTEM.
- ⑤ CAN ONLY BE USED FOR RAMPS WITH 6" OR LESS OF VERTICAL CHANGE.

LEGEND

- SIGN ON PERMANENT SUPPORT
- SIGN ON TEMPORARY SUPPORT
- UNDER PEDESTRIAN TRAFFIC
- WORK AREA
- TEMPORARY PEDESTRIAN BARRICADE
- DIRECTION OF TRAFFIC
- TEMPORARY AUDIBLE MESSAGE DEVICE (EXACT PLACEMENT BASED UPON FIELD CONDITIONS)




SIDEWALK DETOUR, SIDEWALK ON BOTH SIDES

GENERAL NOTES

- WHERE TEMPORARY BARRICADE RUNS PARALLEL ALONG SIDEWALK, PLACE THE FACE OF THE BARRICADE AT THE EDGE OF THE SIDEWALK.
- SIGNS THAT REMAIN IN PLACE LESS THAN SEVEN CONTINUOUS DAYS AND NIGHTS MAY BE MOUNTED ON PORTABLE SUPPORTS.
- PLACE TEMPORARY PEDESTRIAN BARRICADE TO FIT FIELD CONDITIONS, AVOIDING CONFLICT WITH DRIVEWAYS AND OTHER EXISTING FEATURES.
- IF TERRACE IS LESS THAN 6 FEET WIDE, OMIT TEMPORARY PEDESTRIAN BARRICADE FROM THE SIDEWALK TO THE CURB.
  - PLACE BARRICADE CLOSURE SO THAT THE TEMPORARY PEDESTRIAN BARRICADE END IS AT THE LAST OPEN SIDEWALK ACCESS TO RESIDENCES OR BUSINESSES BEFORE THE SIDEWALK CLOSURE.
  - IF TEMPORARY PEDESTRIAN BARRICADE PANEL IS WIDER THAN THE SIDEWALK WIDTH, THE PORTION OF EXCESS PANEL SHOULD EXTEND INTO THE TERRACE.
  - MOUNTING HEIGHT OF 5 FEET FROM THE SURFACE TO THE BOTTOM OF SIGN.

|                                                                                   |                                                      |
|-----------------------------------------------------------------------------------|------------------------------------------------------|
|  | SIGN ON TEMPORARY SUPPORT                            |
|  | TRAFFIC CONTROL DRUM                                 |
|  | TRAFFIC CONTROL DRUM WITH TYPE "C" STEADY BURN LIGHT |
|  | TYPE III BARRICADE                                   |
|  | TYPE III BARRICADE WITH ATTACHED SIGN                |
|  | TYPE "A" WARNING LIGHT (FLASHING)                    |
|  | REMOVING PAVEMENT MARKINGS                           |
|  | DIRECTION OF TRAFFIC                                 |
|  | WORK AREA                                            |
|  | CONNECTED ARROW BOARD                                |
|  | WZ START LOCATION MARKER                             |
|  | WZ END LOCATION MARKER                               |

- ① 5 DRUMS SPACED AT 10 FOOT INTERVALS.
- ② DURING THE PRE-WARNING PERIOD, PLACE THE PCMS AT THE SYSTEM RAMP THAT IS TO BE CLOSED.
- ③ DURING CLOSURE PERIOD, PLACE PCMS OR FMS AT LAST AVAILABLE EXIT IN ADVANCE OF SYSTEM RAMP CLOSURE. IF DYNAMIC MESSAGE SIGNS (DMS) ARE AVAILABLE, COORDINATE POTENTIAL SIGN MESSAGES WITH THE TRAFFIC MANAGEMENT CENTER (TMC).




SEE SDD 15C2 (SHEET "b"), DETAIL "D"  
"BARRICADES AND SIGNS FOR MAINLINE  
CLOSURES" PLACE BARRICADES TO FULLY  
SEAL OFF ROAD

RAMP CLOSED  
BEGINNING  
XXX-XX

| PCMS MESSAGING                     |                   |                          |                     |
|------------------------------------|-------------------|--------------------------|---------------------|
| ONE WEEK IN ADVANCE<br>OF CLOSURE: |                   | DURING CLOSURE:          |                     |
| <b>FRAME 1</b>                     | <b>FRAME 2</b>    | <b>FRAME 1</b>           | <b>FRAME 2</b>      |
| RAMP<br>TO<br>CLOSE                | XXDAY<br>XX XX XX | HWY XX<br>RAMP<br>CLOSED | USE<br>ALT<br>ROUTE |

|                                                    |                                                 |
|----------------------------------------------------|-------------------------------------------------|
| <b>TRAFFIC CONTROL,<br/>SYSTEM RAMP CLOSURE</b>    |                                                 |
| STATE OF WISCONSIN<br>DEPARTMENT OF TRANSPORTATION |                                                 |
| APPROVED<br><u>February 2025</u><br>DATE           | <u>/S/ Andrew Heidtke</u><br>WORK ZONE ENGINEER |



## ***Wisconsin Department of Transportation***

Dedicated people creating transportation solutions through innovation and exceptional service.

<http://www.dot.wisconsin.gov>