Wisconsin Department of Transportation

Division of Transportation Systems Development
Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

October 8, 2026

NOTICE TO ALL CONTRACTORS:

Proposal #08: 2695-03-72, WISC 2027018
T Cedarburg, Cedar Creek Rd
Cedar Creek Bridge P45-0038
Local Street
Ozaukee County

Letting of October 13, 2026

This is Addendum No. 01, which provides for the following:

Special Provisions:

Revised Special Provisions	
Article No.	Description
3	Prosecution and Progress
6	Utilities

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01

2695-03-72

October 8, 2026

Special Provisions

3. Prosecution & Progress.

Replace paragraph nine under section titled **State Threatened Snake** *with the following:*

The DNR maintains a list of individuals in Wisconsin with current Endangered/Threatened (E/T) Species Permits for herp removals that are willing to have their names distributed. The list is not an endorsement of an individual or organization. The list can be found at the following location:

https://widnr.widen.net/view/pdf/8x0eoj8l8z/NH_Review_ExternalHerpContacts.pdf?t.download=true&u=kkadwx

6. Utilities.

Replace entire section titled **AT&T Wisconsin (communications)** *with the following:*

AT&T Wisconsin (communications) has existing underground facilities inside the project limits.

The following work is planned prior to construction:

Approximate Location	Planned Work
Cedar Creek Rd Station 13+52.27, 22.40' RT – 16+69.37, 18.40' RT – 17+67.20, 20.00' LT	Aerial copper cable discontinued and removed from poles
Cedar Creek Rd Station 15+40.20, 20.55' RT	Remove pole
Cedar Creek Rd Station 16+69.76, 18.10' RT	Remove pole
Cedar Creek Rd Station 16+74.10, 18.51' RT	Remove pedestal
Cedar Creek Rd Station 16+74.10, 18.51' RT – 16+72.95, 69.24' RT	Remove underground buried copper cable

Work prior to construction is anticipated to take 4 working days to complete.

The following work is planned during construction:

Approximate Location	Planned Work
Cedar Creek Rd Station 13+64.78, 24.03' LT – 15+28.12, 24.71' LT	The AT&T aerial fiber optic cable running on the north side of Cedar Creek Rd will remain active during construction. Prior to bridge construction, AT&T will temporarily lower or raise the fiber cable as requested. AT&T will return their cable to its existing elevation after the work is complete. Multiple lowering and raising operations are anticipated during construction. AT&T will provide a watchdog for work near their cable. Provide advance notice to AT&T to schedule a watchdog and to make temporary adjustments when needed.

Replace entire section titled **Spectrum (communications)** *with the following:*

Spectrum (communications) has existing underground and overhead facilities inside the project limits.

The following work is planned prior to construction:

Approximate Location	Planned Work
Cedar Creek Rd Station 13+52	Relocate existing pedestal towards edge of right of way outside of grading limits

Work prior to construction is anticipated to take 3 working days to complete.

The following work is planned during construction:

Cedar Creek Rd Station 13+64.78, 24.03' LT – 15+28.12, 24.71' LT	The Spectrum aerial coax cable running on the north side of Cedar Creek Rd will remain active during construction. Prior to bridge construction, Spectrum will temporarily lower or raise the fiber cable as requested. Spectrum will return their cable to its existing elevation after the work is complete. Multiple lowering and raising operations are anticipated during construction. Provide advance notice to Spectrum to schedule temporary adjustments when needed.

x

END OF ADDENDUM