Wisconsin Department of Transportation

Division of Transportation Systems Development
Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

October 6, 2026

NOTICE TO ALL CONTRACTORS:

Proposal #23: 1021-01-79
Baldwin - Menomonie
Hall Estate Rd/160th St B-17-0216
IH 94
Dunn County

Letting of October 13, 2026

This is Addendum No. 02, which provides for the following:

Special Provisions:

Revised Special Provisions	
Article No.	Description
5	Traffic

Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Proposal Quantity Change (-)	Proposal Total After Addendum
643.0300	Traffic Control Drums	DAY	2,984	1,410	4,394
643.0420	Traffic Control Barricades Type III	DAY	1,760	868	2,628
643.0705	Traffic Control Warning Lights Type A	DAY	3,952	1,952	5,904
643.0715	Traffic Control Warning Lights Type C	DAY	1,401	661	2,062
643.0180	Connected Arrow Boards	DAY	136	64	200
643.0900	Traffic Control Signs	DAY	7,915	3,883	11,798
643.1220	Traffic Control Connected Work Zone Start and End Location Markers	DAY	214	106	320
643.1050	Traffic Control Signs PCMS	DAY	321	159	480
643.1051	Traffic Control Signs PCMS with Cellular Communications	DAY	321	159	480
643.1205.S	Basic Traffic Queue Warning System	DAY	214	106	320
643.4100.S	Traffic Control Interim Lane Closure	DAY	32	16	48

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
33	MQ (Traffic control quantities updated to reflect additional contract time)
34	MQ (Traffic control quantities updated to reflect additional contract time)

Other

Revise Contract Completion Time from 60 Working Days to 90 Working Days (an additional 30 Working Days).

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 02

1021-01-79

October 6, 2026

Special Provisions

5. Traffic.

Replace paragraph one under section titled **Girder Placement and Removal** *with the following:*

Girder Placement and Removal
The contractor will be allowed to close two lanes in a single direction for a maximum of six nights to facilitate bridge girder removal (B-17-0020) and girder delivery and placement for Structure B-17-0216. The allowance includes two nights for existing deck and girder removal, two nights for girder placement and two nights for stripping the superstructure. The closures must take place between 10pm to 5am.

Schedule of Items
Attached, dated October 6, 2026, are the revised Schedule of Items Pages 6 and 7.

Plan Sheets
The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:
Revised: 33 and 34.

END OF ADDENDUM

PERMANENT SIGNING

CATEGORY	STATION	LOCATION	634.0612 POSTS WOOD 4X6-INCH X 12-FT EACH	637.2230 SIGNS TYPE II REFLECTIVE F SF	REMARKS
0010	8+75	160 TH ST, LT & RT	2	6	W5-52L & W5-52R
0010	11+25	161 TH ST, LT & RT	2	6	W5-52L & W5-52R
		TOTAL 0010	4	12	

SIGNING REMOVALS

CATEGORY	STATION	LOCATION	638.2602 REMOVING SIGNS TYPE II EACH	638.3000 REMOVING SMALL SIGN SUPPORTS EACH	REMARKS
0010	576+00	IH 94 EB, RT	1	1	W5-52L
0010	576+70	IH 94 WB, LT	1	1	W5-52L
		TOTAL 0010	2	2	

CATEGORY	LOCATION	642.5001 FIELD OFFICE TYPE B EACH
0010	PROJECT	1
	TOTAL 0010	1

TRAFFIC CONTROL ITEMS

CATEGORY	LOCATION	643.0300 TRAFFIC CONTROL DRUMS DAY	643.0420 TRAFFIC CONTROL BARRICADES TYPE III DAY	643.0705 TRAFFIC CONTROL WARNING LIGHTS TYPE A DAY	643.0715 TRAFFIC CONTROL WARNING LIGHTS TYPE C DAY	643.0180 CONNECTED ARROW BOARDS DAY	643.0900 TRAFFIC CONTROL SIGNS DAY	643.1220 TRAFFIC CONTROL CONNECTED WORK ZONE START AND END LOCATION MARKERS DAY	643.1050 TRAFFIC CONTROL SIGNS PCMS DAY	643.1051 TRAFFIC CONTROL SIGNS PCMS WITH CELLULAR COMMUNICATIONS DAY	643.4100.S TRAFFIC CONTROL INTERIM LANE CLOSURE EACH	REMARKS
0010	IH 94 EB AT 160 TH ST	902	66	132	484	44	242					LEFT LANE CLOSURE
0010	IH 94 EB AT 160 TH ST	902	66	132	594	44	220					RIGHT LANE CLOSURE
0010	IH 94 WB AT 160 TH ST	902	44	88	330	44	176					LEFT LANE CLOSURE
0010	IH 94 WB AT 160 TH ST	902	44	88	330	44	176					RIGHT LANE CLOSURE
0010	IH 94 EB	498	96	504	162	12	1020					FULL CLOSURE, COVER X SIGN FOR X CYCLES
0010	IH 94 WB	288	72	480	162	12	204					FULL CLOSURE, COVER X SIGN FOR X CYCLES
0010	IH 94 EB ALT ROUTE						2560		320	320		ALTERNATE ROUTE
0010	IH 94 WB ALT ROUTE						1760		160	160		ALTERNATE ROUTE
0010	IH 94 SHOULDERS						640					PROJECT DURATION (SPEED LIMIT 70 MPH)
0010	IH 94 SHOULDERS						640					PROJECT DURATION (END ROAD WORK)
0010	IH 94 SHOULDERS						640					PROJECT DURATION (ROAD WORK 1 MILE)
0010	IH 94 SHOULDERS						1280					SHOULDER CLOSURES
0010	160TH ST		2240	4480			2240					BRIDGE AND ROADWAY CLOSURE
0010	IH 94							320			48	PROJECT DURATION
	TOTAL 0010	4,394	2,628	5,904	2,062	200	11,798	320	480	480	48	

TRAFFIC CONTROL

CATEGORY	STATION	LOCATION	643.5000 EACH
0010	PROJECT	IH 94 & 160 TH ST	1
		TOTAL 0010	1

TRAFFIC CONTROL COVERING SIGN

CATEGORY	STAGE	LOCATION	643.0920 EACH	# CYCLES	# SIGNS
0010	ALL	IH 94	2	1	2
		TOTAL 0010	2		

Addendum No. 02
ID 1021-01-79
Revised Sheet 33
October 6, 2026

CATEGORY	STATION	LOCATION	FLASHING BEACON SIGNS (FBS)	PORTABLE TRAFFIC SENSORS (PTS	643.1205.S BASIC TRAFFIC QUEUE WARNING SYSTEM DAY
0010	PROJECT	IH 94 EB	3	3	160
0010	PROJECT	IH 94 WB	3	3	160
		TOTAL 0010			320

CATEGORY	STATION	LOCATION	999.2000.S INSTALLING AND MAINTAINING BIRD DETERRENT SYSTEM (STATION) 10+00 EACH	REMARKS
0010	10+00	160TH	1	EXISTING STRUCTURE
		TOTAL 0010	1	

CONSTRUCTION STAKING ITEMS

CATEGORY	STATION	TO	STATION	LOCATION	650.4500 CONSTRUCTION STAKING SUBGRADE LF	650.5000 CONSTRUCTION STAKING BASE LF	650.6000 CONSTRUCTION STAKING PIPE CULVERTS EACH	650.9920 CONSTRUCTION STAKING SLOPE STAKES LF
0010	6+60	-	7+25	160TH ST	65	65	1	65
0010	7+25	-	9+03	160TH ST	178	178		178
0010	11+03	-	13+50	160TH ST	247	247	1	247
0010	13+50	-	16+00	160TH ST	250	250		250
0010	573+80	-	577+95	IH 94 EB RT	415	415	1	415
0010	574+92	-	578+52	IH 94 WB LT	360	360	1	360
0010	3+98	-	5+88		190	190		190
				TOTAL 0010	1,705	1,705	4	1,705

CATEGORY	STATION	TO	STATION	LOCATION	SPV.0090.01 SPECIAL 01. REMOVE AND REINSTALL GUARDRAIL LF
0010	573'EB'+17	-	576'EB'+12	94 EB RT	295
				TOTAL 0010	295

CATEGORY	STATION	TO	STATION	LOCATION	SPV.0090.02 SPECIAL 02. SALVAGE AND REINSTALL HIGH TENSION CABLE BARRIER LF
0010	573'EB'+00	-	579'EB'+93	94 EB	693
				TOTAL 0010	693

SAWING ASPHALT

CATEGORY	STATION	TO	STATION	LOCATION	690.0150 SAWING ASPHALT LF
0010	6+60	-		160 TH ST	35
0010	16+00	-		161 TH ST	25
0010	575+17	-		IH 94 EB	10
0010	577+02	-		IH 94 EB	10
0010	575+71	-		IH 94 WB	10
0010	578+52	-		IH 94 WB	10
				TOTAL 0010	100

CATEGORY	STATION	LOCATION	SPV.0180.01 SPECIAL 01. REMOVE EXISTING FIELD ENTRANCE SY
0010	12+00	160TH ST, LT	60
		TOTAL 0010	60

Addendum No. 02
ID 1021-01-79
Revised Sheet 34
October 6, 2026

Proposal ID: 20261013023 **Project(s):** 1021-01-79

Federal ID(s): N/A

SECTION: 0001 Contract Items

Alt Set ID: **Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0154	634.0612 Posts Wood 4x6-Inch x 12-FT	4.000 EACH	_____.____	_____.____
0156	637.2230 Signs Type II Reflective F	12.000 SF	_____.____	_____.____
0158	638.2602 Removing Signs Type II	2.000 EACH	_____.____	_____.____
0160	638.3000 Removing Small Sign Supports	2.000 EACH	_____.____	_____.____
0162	642.5001 Field Office Type B	1.000 EACH	_____.____	_____.____
0164	643.0300 Traffic Control Drums	4,394.000 DAY	_____.____	_____.____
0166	643.0420 Traffic Control Barricades Type III	2,628.000 DAY	_____.____	_____.____
0168	643.0705 Traffic Control Warning Lights Type A	5,904.000 DAY	_____.____	_____.____
0170	643.0715 Traffic Control Warning Lights Type C	2,062.000 DAY	_____.____	_____.____
0172	643.0810 Traffic Control Connected Arrow Boards	200.000 DAY	_____.____	_____.____
0174	643.0900 Traffic Control Signs	11,798.000 DAY	_____.____	_____.____
0176	643.0920 Traffic Control Covering Signs Type II	2.000 EACH	_____.____	_____.____
0178	643.1050 Traffic Control Signs PCMS	480.000 DAY	_____.____	_____.____
0180	643.1051 Traffic Control Signs PCMS with TMC Communications	480.000 DAY	_____.____	_____.____
0182	643.1205.S Basic Traffic Queue Warning System	320.000 DAY	_____.____	_____.____

Proposal ID: 20261013023 **Project(s):** 1021-01-79

Federal ID(s): N/A

SECTION: 0001 Contract Items

Alt Set ID: **Alt Mbr ID:**

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0184	643.1220 Traffic Control Connected Work Zone Start and End Location Markers	320.000 DAY	_____.____	_____.____
0186	643.4100 Traffic Control Interim Lane Closure	48.000 EACH	_____.____	_____.____
0188	643.5000 Traffic Control	1.000 EACH	_____.____	_____.____
0190	645.0111 Geotextile Type DF Schedule A	52.000 SY	_____.____	_____.____
0192	645.0120 Geotextile Type HR	60.000 SY	_____.____	_____.____
0194	650.4500 Construction Staking Subgrade	1,705.000 LF	_____.____	_____.____
0196	650.5000 Construction Staking Base	1,705.000 LF	_____.____	_____.____
0198	650.6000 Construction Staking Pipe Culverts	4.000 EACH	_____.____	_____.____
0200	650.6501 Construction Staking Structure Layout (structure) 01. B-17-0216	1.000 EACH	_____.____	_____.____
0202	650.9911 Construction Staking Supplemental Control (project) 01. 1021-01-79	1.000 EACH	_____.____	_____.____
0204	650.9920 Construction Staking Slope Stakes	1,705.000 LF	_____.____	_____.____
0206	652.0225 Conduit Rigid Nonmetallic Schedule 40 2-Inch	180.000 LF	_____.____	_____.____
0208	652.0700.S Install Conduit into Existing Item	2.000 EACH	_____.____	_____.____
0210	653.0900 Adjusting Pull Boxes	1.000 EACH	_____.____	_____.____
0212	674.0300 Remove Cable	130.000 LF	_____.____	_____.____